# PHILOSOPHICAL

# TRANSACTIONS

OF THE

# ROYAL SOCIETY

OF

# LONDON.

FOR THE YEAR MDCCCL.

PART II.

LONDON:

PRINTED BY RICHARD AND JOHN E. TAYLOR, RED LION COURT, FLEET STREET.

MDCCCL.

FRANKLIN INSTITUTE LIBRARY

## Adjudication of the Medals of the Royal Society for the year 1850 by the President and Council.

FRANKLIN INSTITUTE LIBRARY

---

The Copley Medal to Professor Hansen, for his researches in Physical Astronomy.

The Royal Medal in the department of Chemistry, to B. C. Brodie, Esq., F.R.S., for his "Investigations on the Chemical Nature of Wax," published in the Philosophical Transactions for 1848 and 1849.

There being no paper in the department of Mathematics coming within the terms of the award of the Royal Medal, it was awarded to Thomas Graham, Esq., F.R.S., for his paper "On the Motion of Gases," published in the Philosophical Transactions for 1849.

The Rumford Medal to M. F. J. D. Arago, for his "Experimental Investigations on Polarized Light," the concluding memoirs on which were communicated to the Academy of Sciences of Paris during the last two years.

---

The Bakerian Lecture for 1850 was delivered by Michael Faraday, Esq., F.R.S., and entitled "Experimental Researches in Electricity.—Twenty-fourth, Twenty-fifth, Twenty-sixth and Twenty-seventh Series. On the magnetic condition of oxygen," &c.

17724

# CONTENTS.

XV. *Discussion of Meteorological Observations taken in India, at various heights, embracing those at Dodabetta on the Neelgherry Mountains, at 8640 feet above the level of the sea. By Lieutenant-Colonel* W. H. SYKES, *F.R.S.* . page 297

XVI. *On the* PELOROSAURUS; *an undescribed gigantic terrestrial reptile whose remains are associated with those of the Iguanodon and other Saurians in the Strata of Tilgate Forest, in Sussex. By* GIDEON ALGERNON MANTELL, *Esq., LL.D., F.R.S., F.L.S., Vice-President of the Geological Society, &c.* . . . . 379

XVII. *On a Dorsal dermal Spine of the Hylæosaurus, recently discovered in the Strata of Tilgate Forest. By* GIDEON ALGERNON MANTELL, *Esq., LL.D., F.R.S., F.L.S., Vice-President of the Geological Society, &c.* . . . . . 391

XVIII. *Supplementary Observations on the Structure of the* BELEMNITE *and* BELEMNOTEUTHIS. *By* GIDEON ALGERNON MANTELL, *Esq., LL.D., F.R.S., F.L.S., Vice-President of the Geological Society, &c.* . . . . . 393

XIX. *On the Algebraic Expression of the number of Partitions of which a given number is susceptible. By Sir* J. F. W. HERSCHEL, *Bart., K.H., F.R.S.* . . . 399

XX. *Experiments on the Section of the Glossopharyngeal and Hypoglossal Nerves of the Frog, and observations of the alterations produced thereby in the Structure of their Primitive Fibres. By* AUGUSTUS WALLER, *M.D. Communicated by Professor* OWEN, *F.R.S.* . . . . . 423

XXI. *Influence of Physical Agents on the development of the Tadpole of the Triton and the Frog. By* JOHN HIGGINBOTTOM, *Hon. Fellow of the Royal College of Surgeons of England. Communicated by* THOMAS BELL, *Esq., Sec. R.S.* . 431

XXII. *On the Temperature of Man within the Tropics. By* JOHN DAVY, *M.D., F.R.S., L. & E., Inspector-General of Army Hospitals* . . . . . 437

XXIII. *On the Oils produced by the Action of Sulphuric Acid upon various Classes of Vegetables. By* JOHN STENHOUSE, *Esq., Ph.D., F.R.S.* . . . . . 467

XXIV. *On the Development and Homologies of the Molar Teeth of the Wart-Hogs* (Phacochœrus), *with Illustrations of a System of Notation for the Teeth in the Class* MAMMALIA. *By Professor* OWEN, *F.R.S. &c.* . . . . . 481

XXV. *Observations on the Nebulæ. By The Earl of* ROSSE, *Pres. R.S. &c. &c.* 499

XXVI. *On the Structure and Use of the Ligamentum Rotundum Uteri, with some observations upon the change which takes place in the Structure of the Uterus during Utero-gestation. By* G. RAINEY, *M.R.C.S., Demonstrator of Anatomy at St. Thomas's Hospital. Communicated by* JOSEPH HENRY GREEN, *Esq., F.R.S.* . . . . . 515

XXVII. *On the Communications between the Cavity of the Tympanum and the Palate in the* Crocodilia (*Gavials, Alligators and Crocodiles*). *By Professor* OWEN, *F.R.S. &c.* . . . . . 521

XXVIII. *On the Structure of the Dental Tissues of the Order Rodentia. By* JOHN TOMES, *Surgeon-Dentist to the Middlesex Hospital. Communicated by* WILLIAM BOWMAN, *Esq., F.R.S.* . . . . . 529

XXIX. *Sequel to a paper on the Reduction of the Thermometrical Observations made at the Apartments of the Royal Society. By* JAMES GLAISHER, *Esq., F.R.S., of the Royal Observatory, Greenwich* . . . . . 569

XXX. *On the Dynamical Stability and on the Oscillations of Floating Bodies. By the Rev.* HENRY MOSELEY, *M.A., F.R.S., Corresponding Member of the Institute of France* . . . . . 609

XXXI. *Electro-Physiological Researches. On Induced Contraction.—Ninth Series. By Signor* CARLO MATTEUCCI, *Professor in the University of Pisa, &c. &c. Communicated by* W. R. GROVE, *Esq., F.R.S.* . . . . . 645

XXXII. *Contributions to the Chemistry of the Urine.*—Paper IV. *On the so-called Chylous Urine. By* HENRY BENCE JONES, *M.D., M.A. Cantab., F.R.S., Physician to St. George's Hospital* . . . . . 651

XXXIII. *Contributions to the Chemistry of the Urine.*—Paper III. PART IV. *On the Variations of the Sulphates and Phosphates in Disease. By* HENRY BENCE JONES, *M.D., M.A. Cantab., F.R.S., Physician to St. George's Hospital.* 661

XXXIV. *Second Appendix to a paper on the Variations of the Acidity of the Urine in*

*the state of Health.* *By* HENRY BENCE JONES, *M.D., M.A. Cantab., F.R.S., Physician to St. George's Hospital* . . . . . 669

XXXV. *An Experimental Inquiry into the Strength of Wrought-Iron Plates and their Riveted Joints as applied to Ship-building and Vessels exposed to severe strains. By* WILLIAM FAIRBAIRN, *Esq. Communicated by the Rev.* HENRY MOSELEY, *F.R.S.* . . . . . 677

XXXVI. *On the Mutual Relations of the Vital and Physical Forces. By* WILLIAM B. CARPENTER, *M.D., F.R.S., F.G.S., Examiner in Physiology and Comparative Anatomy in the University of London* . . . . . 727

XXXVII. *On the Condition of certain Elements at the moment of Chemical Change. By* BENJAMIN COLLINS BRODIE, *Esq., F.R.S.* . . . . . 759

XXXVIII. *Supplementary Observations on the Diffusion of Liquids. By* THOMAS GRAHAM, *F.R.S., F.C.S.* . . . . . 805

*Index* . . . . . 837

APPENDIX.

*Presents* . . . . . [ 1 ]

PHILOSOPHICAL TRANSACTIONS, PART I. 1850.

ERRATA.

Page 245, line 13, *after* placed *insert* parallel to it.
—— 246, line 1, *for* VI. *read* XV.
—— 246, line 1, *for* one, A, *read* one, B.
—— 246, line 2, *for* B *read* A.
—— 246, line 17, *after* result *insert* in.
—— 246, line 19, *for* fringe *read* force.
—— 252, line 13, *erase* $b$=DE, *and for* $\frac{1}{\sqrt{a^2+(x-b)^2}-\sqrt{c^2+x^2}}$ *read* $\frac{1}{\sqrt{a^2+x^2}-\sqrt{b^2+x^2}}$.
—— 253, line 16, *for* being *read* between.
—— 254, line 19, *for* XI. *read* XII.
—— 254, line 21, *for* $e$, $c$ *read* $c$, $e$.
—— 257, line 13, *for* 19 *read* 21.
—— 257, line 25, *for* light *read* night.
—— 257, line 29, *for* polarity *read* polarization.
—— 258, line 4, for $ss$ read $s$.
—— 258, line 6, *for* $\sqrt{v^2+Zdx}$ *read* $\sqrt{v^2+2\int Zdx}$.
In figs. 6 and 7, R R′ should be a straight line.
In fig. 9, P should be opposite to $q$.

# PHILOSOPHICAL TRANSACTIONS.

FRANKLIN INSTITUTE LIBRARY

## XV. *Discussion of Meteorological Observations taken in India, at various heights, embracing those at Dodabetta on the Neelgherry Mountains, at 8640 feet above the level of the sea.* By Lieutenant-Colonel W. H. Sykes, *F.R.S.*

Received January 12,—Read March 21, 1850.

In the year 1835 the Royal Society did me the honour to publish the results of six years' meteorological observations, taken by me on the elevated plateau of the Dukhun (Deccan) from 1825 to 1830, both years inclusive; my chief object being to illustrate the diurnal oscillations of the barometer as indicative of the periodic tides (if they may be so called) of the atmosphere. I showed that in many thousand observations, taken personally, there was not a solitary instance in which the barometer was not higher at 9—10 A.M. than at sunrise; and lower at 4—5 P.M. than at 9—10 A.M., *whatever the state of the weather or the indications of the thermometer or hygrometer might be*; nor was there a solitary instance in 1830, during which year only I took systematic night observations, and observed at the turning-points every five minutes, in which the maximum nocturnal tide was not higher at 9—10 P.M. than at 4—5 P.M. The 4—5 A.M. minimum tide was less regularly noticed than the other three tides; but nevertheless sufficiently often to render it perfectly clear, that in the twenty-four hours there were two minima as well as two maxima of pressure in twenty-four hours. I had the advantage at times of carrying on my observations in the six years, at a mean elevation of 1800 feet, simultaneously with observations made in Bombay at the level of the sea, and at Mahabuleshwur at 4500 feet above the sea. These simultaneous observations for limited periods led me to remark, that the amount or range of the diurnal oscillation between the maximum and minimum hours did not correspond at the different elevations. At the level of the sea in Bombay the range between 9—10 A.M. and 4—5 P.M., appeared generally to be less than the range between the same hours in Dukhun (Deccan) at 1800 feet above the sea; but at Mahabuleshwur, at 4500 feet, the range was *constantly* less than in Bombay or on the plateau of the Deccan. Not having had further means of prosecuting inquiry into the fact, it was with much interest I remarked that the orders of the Court of Directors of the East India Company had been carried out by the astronomer at Madras, and meteorological observations taken for a whole year at a

greater elevation above the sea-level, than had ever been attempted before in India. Observations so made were peculiarly acceptable to me, as they would subject the accuracy of my own observations to an additional test, and would supply the means of investigating the supposed diminished diurnal oscillation of the barometer in relation to elevation above the sea. At the present time I have the further advantage of being enabled to subject my Deccan observations to the test of comparison with recent observations at the Bombay and Madras Observatories, taken chiefly with a view to determine the amount of the hourly and diurnal changes of the barometer. Those for Madras are from the years 1841 to 1845, both inclusive*: for Bombay, I am sorry to say, the records which have reached my hands are for more limited periods. Dr. Buist, LL.D., while in temporary charge of the observatory, made observations for 1842, 1843 and 1844, but those for 1843 and 1844 only are available to me, and Professor Orlebar has published observations from April to December 1845. In addition to the above, a meteorological register is kept in the office of the Deputy Surveyor-General in Calcutta, the instruments since 1844 being new, and of Newman's construction; but hourly observations do not appear to have been taken, and three out of the five periods of observation, namely, sunrise, noon and sunset, are useless for determining the diurnal oscillation of the barometer; and the barometrical observations taken before the receipt of the new instruments, which came to hand respectively in 1844 and 1847, were recorded from defective instruments.

| | |
|---|---|
| Troughton's barometer reduced to 32° stood at . . . | 29·493 |
| Colonel Everest's reduced to 32° stood at . . . . . | 29·637 |
| While Newman's barometer of Sept. 1844 stood at . . . | 29·654 |
| And that of April 1847 at . . . . . | 29·667 |

The height of the cistern above the level of the sea being 18·21 feet. Observations are also taken at the Royal Observatory at Oude, and at the Rajah of Travancore's Observatory at Trevandrum; but the records have not reached my hands, nor are those of the magnetic observatory at Simla available to me.

Independently of the diurnal atmospheric tides, the Dodabetta observations afford the means of further investigating the debatable question of the influence of elevation upon the quantity of rain precipitated; for these observations, contrasted with the records from Mahabuleshwur, Mercara in Coorg, and from the numerous stations in Travancore furnished by General Cullen (all the localities being under nearly the same meridian, although differing greatly in latitude), will supply data, which, if they do not set the question at rest, will assist to guide the judgement to deductions approximating to the truth.

*Diurnal Tides.*—I shall first notice the observations taken at the greatest elevation. The Dodabetta observations commenced in February 1847. The locality of the observatory, which is in latitude 11° 23′ 22″ N., and longitude approximatively 76°·47 E. of Greenwich, is understood to be the highest point in the range of Ghauts in Western

* At Madras, from the years 1822 to 1837, the barometric records are useless for determining the daily atmospheric tides, the hours of observation being sunrise,—10 A.M., noon,—2 P.M., and sunset,—10 P.M. was added in some of the latter years. Hourly observations only commenced in 1841.

India, that run parallel to the sea-coast from latitude 24°—25° to Cape Comorin. This range of mountains rise abruptly above the western coast of India, and the watershed from them is almost entirely to the Coromandel or eastern coast of the Peninsula of India. The aqueous vapours from the ocean are condensed on these mountains, and as Dodabetta is within the influence of both the south-west and north-east monsoons, it would appear to be favoured with rain in every month in the year. The observations were taken by an assistant of the Madras Observatory, John De Cruz; and as the instruments had been selected by the astronomer, Mr. Taylor, and every precaution taken to ensure accuracy in the observations, there is every reason to suppose they are worthy of confidence. To determine the pressure of the atmosphere, observations were taken only twice in the day at the supposed hours of maxima and minima; namely, $9^h\ 40^m$ A.M. and $3^h\ 40^m$ P.M., excepting on the 21st and 22nd of each month, when the observations were taken hourly for twenty-four consecutive hours.

With respect to the daily oscillation of the barometer the following Tables are given, and the records show, that, as in my observations in the Deccan, there is not at this great elevation *a single day throughout the whole year* in which the pressure at $3^h\ 40^s$ P.M. is higher than at $9^h\ 40^s$ A.M., and there is but a solitary instance in which the pressure at the two hours is identical. On the 15th of August the barometer is recorded as standing at 21°·952 at $9^h\ 40^m$ A.M., and at 21°·952 at $3^h\ 40^m$ P.M.; but as there is not an approximation to anything similar in the preceding or following days, it may be questioned whether this supposed suspension of the atmospheric tide may not be a typographical error, that might well be excused in a multitude of figures. As these observations taken at such a height are the first of the kind recorded in India, I have thought it right to append them *in extenso*; at least for pressure and temperature, and wet bulb depression*.

* While this paper is passing through the press, Lieut. R. Strachey of the Bengal Engineers is arrived in England from his travels in the Himalayas and Thibet. He made some hourly observations of the barometer at an elevation of 18,400, at 16,000, and at 11,500 feet, and found that the horary oscillations or atmospheric tides were as regular as on the plains of Hindoostan, and the hours of maxima and minima were the same.

Meteorological observations made by Lieut. R. Strachey on Lunjar Mountain in Thibet (lat. 31° 2′ north) at an elevation of 18,400 feet above the sea, August 22nd and 23rd, 1849.

| Date. | Hour. | Bar. at 32°. | Air. | Wet bulb. | | Date. | Hour. | Bar. at 32°. | Air. | Wet. bulb. | |
|---|---|---|---|---|---|---|---|---|---|---|---|
| | P.M. h m | in. | | | | | P.M. h m | in. | | | |
| Aug. 22. | 2 0 | 15·374 | 45·0 | 37·7 | Moderate wind and a few light clouds. | Aug. 23. | 4 0 | 15·381 | 29·0 | 24·3 | Calm, clear. |
| | 4 30 | ·355 | 48·7 | 37·8 | Moderate wind and a few light clouds. | | 5 0 | ·389 | 29·0 | 24·5 | Calm, clear. |
| | 5 0 | ·355 | 42·7 | 36·2 | Moderate wind and a few light clouds. | | 6 0 | ·393 | 28·0 | 26·5 | Sunrise. |
| | 6 0 | ·362 | 37·7 | 35·5 | Moderate wind and a few light clouds. | | 7 0 | ·397 | 33·0 | 32·8 | Calm and clear. |
| | 7 0 | ·369 | 31·5 | 29·9 | Wind light. | | 8 0 | ·405 | 36·0 | 35·8 | Calm and clear. |
| | 8 0 | ·396 | 34·0 | 29·5 | Wind light. | | 9 0 | ·420 | 39·8 | 31·75 | Calm and clear. |
| | 9 0 | ·410 | 33·6 | 28·9 | Calm, clear. | | 10 0 | ·424 | 44·9 | 35·5 | Light winds, S.E., few clouds. |
| | 10 0 | ·412 | 33·0 | 28·5 | Calm, clear. | | 11 0 | ·421 | 56·2 | 46·5 | Wind increasing, also clouds. |
| | 11 0 | ·414 | 32·0 | 26·7 | Calm, clear. | | noon. | ·415 | 56·0 | 40·2 | |
| | midnight. | ·394 | 31·7 | 27·7 | Calm, clear. | | 1 0 | ·407 | 56·9 | 40·9 | |
| Aug. 23. | 1 15 | ·399 | 31·0 | 25·25 | Calm, clear. | | 1 30 | ·404 | | | |
| | 2 0 | ·395 | 30·7 | 27·4 | Calm, clear. | | 2 0 | ·397 | 49·1 | 37·15 | |
| | 3 0 | ·383 | 29·7 | 27·6 | Calm, clear. | | 3 0 | ·387 | 46·5 | 36·5 | Strong wind and more cloudy. |

## Daily Oscillations of the Barometer at Dodabetta, at 8640 feet above the level of the sea, &c.

### FEBRUARY.

| Date. | h m 9 40 A.M. | | | h m 3 40 P.M. | | | |
|---|---|---|---|---|---|---|---|
| 1847. | Barometer. | Att. | Det. | Barometer. | Att. | Det. | Rain. |
| | in. | ° | ° | in. | ° | ° | in. |
| 1 | 22·105 | 52·5 | 54·0 | 22·046 | 51·0 | 52·0 | — |
| 2 | ·115 | 53·0 | 54·0 | ·062 | 50·0 | 52·0 | — |
| 3 | ·114 | 53·0 | 53·8 | ·068 | 53·0 | 52·9 | 0·02 |
| 4 | ·124 | 51·8 | 52·5 | ·060 | 53·0 | 52·8 | 0·31 |
| 5 | ·128 | 50·0 | 51·0 | ·072 | 52·9 | 52·5 | 0·03 |
| 6 | ·140 | 48·8 | 50·0 | ·086 | 52·2 | 50·0 | 0·02 |
| 7 | ·136 | 47·8 | 48·0 | ·065 | 51·0 | 51·0 | — |
| 8 | ·138 | 51·4 | 53·0 | ·082 | 52·0 | 52·5 | — |
| 9 | ·144 | 51·5 | 52·5 | ·064 | 52·5 | 52·5 | 0·38 |
| 10 | ·082 | 51·4 | 48·0 | ·022 | 50·0 | 50·5 | 0·03 |
| 11 | ·082 | 50·0 | 51·0 | ·014 | 51·0 | 51·4 | 0·05 |
| 12 | ·120 | 52·2 | 53·0 | ·056 | 50·5 | 52·2 | 0·05 |
| 13 | ·154 | 52·4 | 53·0 | ·081 | 52·4 | 53·0 | 1·39 |
| 14 | ·134 | 51·8 | 52·0 | ·068 | 52·0 | 53·0 | 0·39 |
| 15 | ·142 | 52·6 | 54·0 | ·073 | 53·0 | 53·4 | 0·69 |
| 16 | ·138 | 54·4 | 55·0 | ·072 | 54·5 | 54·5 | 3·24 |
| 17 | ·140 | 53·5 | 55·0 | ·089 | 54·5 | 54·5 | — |
| 18 | ·165 | 52·0 | 54·0 | ·099 | 53·0 | 53·5 | — |
| 19 | ·158 | 52·0 | 52·5 | ·066 | 52·5 | 53·0 | — |
| 20 | ·132 | 50·5 | 51·0 | ·046 | 53·0 | 53·0 | 0·03 |
| 21 | ·123 | 51·8 | 51·8 | ·068 | 53·8 | 53·0 | 0·03 |
| 22 | ·139 | 49·8 | 50·5 | ·079 | 51·8 | 52·0 | 0·77 |
| 23 | ·132 | 50·5 | 51·0 | ·080 | 51·3 | 52·0 | — |
| 24 | ·128 | 51·0 | 52·0 | ·066 | 52·5 | 53·0 | — |
| 25 | ·134 | 51·8 | 54·0 | ·076 | 52·0 | 53·0 | — |
| 26 | ·116 | 51·0 | 52·0 | ·080 | 52·0 | 52·0 | — |
| 27 | ·110 | 50·0 | 51·0 | ·062 | 51·0 | 52·4 | — |
| 28 | ·128 | 48·5 | 49·5 | ·084 | 50·0 | 51·0 | — |
| Mean | 22·129 | 51·3 | 52·1 | 22·068 | 52·1 | 52·5 | 7·43 |

### MARCH.

| Date. | h m 9 40 A.M. | | | h m 3 40 P.M. | | | |
|---|---|---|---|---|---|---|---|
| 1847. | Barometer. | Att. | Det. | Barometer. | Att. | Det. | Rain. |
| | in. | ° | ° | in. | ° | ° | in. |
| 1 | 22·166 | 52·0 | 53·0 | 22·072 | 51·0 | 52·0 | — |
| 2 | ·182 | 54·0 | 54·0 | ·130 | 52·0 | 53·0 | — |
| 3 | ·186 | 53·0 | 53·4 | ·122 | 52·8 | 53·0 | 2·29 |
| 4 | ·168 | 50·0 | 50·5 | ·116 | 50·0 | 51·0 | 0·03 |
| 5 | ·180 | 50·4 | 50·8 | ·124 | 50·5 | 51·5 | — |
| 6 | ·174 | 50·0 | 53·0 | ·126 | 50·8 | 51·8 | — |
| 7 | ·166 | 50·0 | 52·0 | ·130 | 50·0 | 51·0 | — |
| 8 | ·182 | 52·2 | 53·0 | ·130 | 54·0 | 54·0 | — |
| 9 | ·159 | 50·0 | 51·8 | ·098 | 53·0 | 53·0 | — |
| 10 | ·172 | 54·0 | 55·0 | ·100 | 56·8 | 57·0 | — |
| 11 | ·153 | 55·0 | 56·0 | ·078 | 53·0 | 54·0 | — |
| 12 | ·148 | 55·0 | 56·0 | ·106 | 53·0 | 55·0 | — |
| 13 | ·158 | 55·0 | 56·0 | ·105 | 55·0 | 55·0 | — |
| 14 | ·152 | 52·0 | 53·0 | ·118 | 58·8 | 59·0 | — |
| 15 | ·150 | 51·8 | 53·0 | ·088 | 53·0 | 53·5 | 0·77 |
| 16 | ·176 | 51·0 | 52·0 | ·147 | 53·0 | 53·0 | 0·16 |
| 17 | ·218 | 21·0 | 51·5 | ·128 | 52·0 | 52·0 | 0·21 |
| 18 | ·186 | 54·2 | 55·2 | ·084 | 53·0 | 53·0 | 0·25 |
| 19 | ·136 | 52·0 | 53·0 | ·066 | 54·0 | 54·0 | — |
| 20 | ·160 | 53·0 | 54·0 | ·123 | 55·0 | 55·0 | — |
| 21 | ·186 | 53·0 | 54·8 | ·150 | 55·0 | 56·0 | — |
| 22 | ·168 | 51·0 | 50·0 | ·104 | 55·0 | 56·0 | — |
| 23 | ·140 | 56·0 | 57·0 | ·116 | 56·0 | 56·5 | — |
| 24 | ·131 | 58·0 | 58·0 | ·076 | 55·0 | 56·8 | — |
| 25 | ·146 | 57·0 | 55·0 | ·086 | 58·5 | 58·0 | — |
| 26 | ·132 | 57·0 | 58·0 | ·089 | 57·0 | 57·5 | — |
| 27 | ·138 | 56·0 | 57·0 | ·061 | 56·0 | 57·5 | — |
| 28 | ·140 | 56·0 | 57·0 | ·072 | 56·0 | 57·0 | — |
| 29 | ·136 | 56·0 | 57·0 | ·080 | 56·0 | 57·0 | — |
| 30 | ·184 | 57·0 | 58·0 | ·120 | 57·5 | 58·8 | — |
| 31 | ·190 | 57·0 | 59·0 | ·117 | 57·5 | 58·0 | — |
| Mean | 22·160 | 53·5 | 54·4 | 22·105 | 54·2 | 54·6 | 3·61 |

### APRIL.

| Date. | h m 9 40 A.M. | | | h m 3 40 P.M. | | | |
|---|---|---|---|---|---|---|---|
| 1847. | Barometer. | Att. | Det. | Barometer. | Att. | Det. | Rain. |
| | in. | ° | ° | in. | ° | ° | in. |
| 1 | 22·180 | 58·0 | 59·0 | 22·106 | 58·0 | 58·5 | — |
| 2 | ·177 | 59·5 | 61·5 | ·080 | 58·5 | 60·0 | — |
| 3 | ·172 | 59·0 | 60·5 | ·115 | 58·0 | 59·0 | — |
| 4 | ·186 | 58·0 | 59·0 | — | — | — | — |
| 5 | ·199 | 57·5 | 58·5 | ·164 | 58·0 | 58·0 | — |
| 6 | ·188 | 56·0 | 57·0 | ·150 | 60·0 | 59·0 | — |
| 7 | ·172 | 56·0 | 57·5 | ·119 | 57·0 | 57·4 | — |
| 8 | ·160 | 57·0 | 58·5 | ·110 | 58·5 | 58·5 | 0·05 |
| 9 | ·162 | 54·8 | 56·0 | ·106 | 57·0 | 58·0 | 0·06 |
| 10 | ·176 | 56·0 | 57·0 | ·110 | 56·5 | 57·5 | — |
| 11 | ·136 | 56·5 | 57·0 | ·114 | 56·0 | 57·0 | — |
| 12 | ·122 | 56·5 | 57·5 | ·058 | 57·0 | 58·0 | — |
| 13 | ·098 | 55·0 | 56·0 | ·038 | 56·0 | 56·0 | 1·77 |
| 14 | ·100 | 53·8 | 54·0 | ·026 | 55·0 | 55·0 | 0·02 |
| 15 | ·036 | 52·5 | 53·5 | 21·983 | 51·8 | 51·5 | 0·10 |
| 16 | 21·998 | 51·0 | 51·8 | ·912 | 51·0 | 51·5 | 1·14 |
| 17 | ·946 | 53·5 | 54·0 | ·886 | 53·0 | 53·0 | 4·75 |
| 18 | 22·016 | 53·0 | 53·0 | ·952 | 53·5 | 53·5 | 10·00 |
| 19 | ·056 | 53·0 | 53·0 | 22·012 | 53·0 | 53·5 | 1·72 |
| 20 | ·088 | 52·0 | 53·0 | ·056 | 54·0 | 54·0 | 0·09 |
| 21 | ·126 | 52·0 | 52·0 | ·078 | 57·0 | 57·0 | — |
| 22 | ·128 | 52·8 | 53·0 | ·072 | 54·0 | 55·0 | — |
| 23 | ·128 | 54·5 | 54·0 | ·060 | 57·0 | 58·0 | — |
| 24 | ·128 | 54·8 | 55·5 | ·070 | 55·0 | 56·5 | — |
| 25 | ·142 | 58·0 | 58·0 | ·074 | 55·0 | 56·0 | — |
| 26 | ·170 | 56·5 | 57·0 | ·100 | 57·0 | 58·0 | — |
| 27 | ·164 | 57·0 | 58·0 | ·090 | 58·0 | 59·0 | — |
| 28 | ·172 | 58·0 | 59·0 | ·093 | 57·0 | 56·5 | — |
| 29 | ·160 | 55·8 | 56·5 | ·078 | 56·5 | 57·0 | 0·05 |
| 30 | ·160 | 58·0 | 58·0 | ·088 | 58·0 | 58·5 | 0·05 |
| Mean | 22·128 | 55·5 | 56·3 | 22·066 | 56·1 | 56·6 | 19·80 |

### Depression of the wet bulb.

| February. | | March. | | April. | |
|---|---|---|---|---|---|
| h m 9 40 A.M. | h m 3 40 P.M. | h m 9 40 A.M. | h m 3 40 P.M. | h m 9 40 A.M. | h m 3 40 P.M. |
| ° | ° | ° | ° | ° | ° |
| 10·5 | 1·5 | 6·0 | 0·0 | 5·0 | 2·0 |
| 2·0 | 5·0 | 3·0 | 1·0 | 7·5 | 2·5 |
| 1·8 | 1·5 | 0·9 | 1·0 | 4·5 | 1·2 |
| 0·5 | 0·8 | 4·5 | 2·0 | 7·0 | — |
| 2·0 | 1·1 | 4·3 | 2·1 | 5·0 | 4·0 |
| 3·5 | 2·2 | 6·0 | 3·3 | 7·0 | 7·0 |
| 6·5 | 2·5 | 4·0 | 2·0 | 6·5 | 2·9 |
| 1·8 | 1·5 | 6·0 | 3·5 | 4·5 | 5·2 |
| 0·5 | 1·5 | 3·8 | 1·0 | 6·5 | 5·2 |
| 1·5 | 0·5 | 7·0 | 5·0 | 5·5 | 2·5 |
| 0·2 | 0·4 | 9·0 | 2·0 | 6·2 | 6·0 |
| 0·5 | 0·2 | 8·8 | 2·0 | 2·5 | 3·0 |
| 0·0 | 0·4 | 7·2 | 6·0 | 1·0 | 1·0 |
| 0·0 | 0·5 | 4·5 | 4·5 | 0·5 | 0·5 |
| 0·4 | 0·4 | 1·0 | 1·5 | 1·0 | 0·5 |
| 0·5 | 0·5 | 0·8 | 0·5 | 0·5 | 0·5 |
| 2·0 | 1·5 | 0·5 | 1·0 | 1·5 | 0·0 |
| 4·0 | 0·9 | 2·2 | 4·2 | 0·0 | 0·5 |
| 0·6 | 0·5 | 6·2 | 4·0 | 0·5 | 0·0 |
| 1·3 | 0·8 | 6·0 | 7·0 | 1·0 | 4·5 |
| 0·5 | 0·5 | 10·0 | 10·0 | 7·0 | 3·0 |
| 0·0 | 0·0 | 8·0 | 9·5 | 5·0 | 3·2 |
| 0·5 | 0·6 | 7·0 | 4·8 | 1·5 | 1·0 |
| 4·0 | 1·0 | 5·0 | 6·0 | 5·0 | 2·0 |
| 3·0 | 1·5 | 6·0 | 5·0 | 3·0 | 3·5 |
| 2·0 | 2·4 | 7·2 | 7·7 | 3·0 | 2·5 |
| 2·0 | 1·2 | 4·0 | 2·0 | 4·0 | 1·5 |
| | | 6·0 | 2·5 | 1·5 | 3·0 |
| | | 3·2 | 1·8 | 5·0 | 2·5 |
| | | 4·8 | 2·0 | | |
| 1·9 | 1·1 | 5·0 | 3·5 | 3·6 | 2·5 |

## TABLE (Continued).

| MAY. | | | | | | | | JUNE. | | | | | | | | JULY. | | | | | | | | Depression of the wet bulb. | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Date. | h m 9 40 A.M. | | | h m 3 40 P.M. | | | | Date. | h m 9 40 A.M. | | | h m 3 40 P.M. | | | | Date. | h m 9 40 A.M. | | | h m 3 40 P.M. | | | | May. | | June. | | July. | | | |
| 1847. | Barometer. | Att. | Det. | Barometer. | Att. | Det. | Rain. | 1847. | Barometer. | Att. | Det. | Barometer. | Att. | Det. | Rain. | 1847. | Barometer. | Att. | Det. | Barometer. | Att. | Det. | Rain. | h m 9 40 A.M. | h m 3 40 P.M. | h m 9 40 A.M. | h m 3 40 P.M. | h m 9 40 A.M. | h m 3 40 P.M. | | |
| | in. | ° | ° | in. | ° | ° | in. | | in. | ° | ° | in. | ° | ° | in. | | in. | ° | ° | in. | ° | ° | in. | ° | ° | ° | ° | ° | ° | | |
| 1 | 22·150 | 58·5 | 59·0 | 22·072 | 57·0 | 56·5 | — | 1 | 22·016 | 52·8 | 53·0 | 21·964 | 53·5 | 52·8 | — | 1 | 22·026 | 51·2 | 51·2 | 21·942 | 53·0 | 52·0 | 0·45 | 3·0 | 2·1 | 0·2 | 0·3 | 0·0 | 0·2 | | |
| 2 | ·124 | 56·5 | 57·0 | ·062 | 57·4 | 58·0 | — | 2 | ·038 | 51·2 | 51·5 | 22·002 | 52·8 | 52·0 | 0·10 | 2 | ·005 | 51·2 | 51·6 | ·946 | 52·8 | 53·1 | 0·13 | 3·0 | 2·0 | 2·0 | 0·6 | 0·1 | 0·6 | | |
| 3 | ·140 | 58·0 | 59·0 | ·084 | 59·0 | 59·0 | — | 3 | ·042 | 51·4 | 52·0 | ·016 | 52·5 | 52·0 | — | 3 | 21·976 | 51·6 | 51·9 | ·930 | 52·6 | 53·0 | 0·15 | 3·0 | 3·0 | 1·0 | 1·0 | 0·1 | 0·6 | | |
| 4 | ·135 | 57·5 | 58·8 | ·080 | 57·5 | 58·0 | 0·01 | 4 | ·069 | 52·8 | 53·0 | ·009 | 53·8 | 54·0 | 0·02 | 4 | 22·010 | 51·9 | 52·2 | ·965 | 53·0 | 53·2 | 0·35 | 5·4 | 4·0 | 1·6 | 0·2 | 0·2 | 0·2 | | |
| 5 | ·138 | 57·2 | 58·0 | ·052 | 56·0 | 55·4 | — | 5 | ·062 | 54·8 | 55·0 | 21·978 | 52·0 | 52·2 | 0·40 | 5 | ·016 | 51·8 | 51·9 | ·946 | 51·0 | 51·0 | 0·29 | 3·0 | 4·5 | 0·5 | 0·4 | 0·3 | 0·5 | | |
| 6 | ·154 | 57·0 | 58·0 | ·078 | 57·0 | 57·0 | 1·26 | 6 | ·026 | 52·5 | 52·5 | ·999 | 55·5 | 55·5 | 0·19 | 6 | ·029 | 51·8 | 52·2 | ·984 | 52·9 | 52·9 | 0·21 | 2·5 | 1·0 | 0·0 | 0·7 | 0·2 | 0·3 | | |
| 7 | ·154 | 57·5 | 58·0 | ·093 | 57·2 | 58·0 | — | 7 | ·068 | 52·4 | 52·6 | 22·008 | 53·2 | 53·8 | — | 7 | ·024 | 52·4 | 52·6 | ·990 | 51·0 | 50·8 | 0·12 | 2·0 | 1·8 | 0·8 | 0·4 | 0·8 | 0·4 | | |
| 8 | ·169 | 56·5 | 57·5 | ·096 | 58·5 | 59·0 | 0·06 | 8 | ·067 | 52·0 | 52·2 | ·008 | 53·6 | 53·9 | 0·04 | 8 | ·030 | 52·8 | 52·9 | ·968 | 53·0 | 53·0 | 0·16 | 2·5 | 3·0 | 0·4 | 0·7 | 0·1 | 0·0 | | |
| 9 | ·140 | 57·5 | 58·5 | ·082 | 58·2 | 58·0 | — | 9 | ·056 | 53·2 | 53·6 | 21·974 | 52·4 | 52·8 | 0·03 | 9 | ·022 | 51·0 | 51·2 | ·960 | 52·0 | 52·4 | 0·02 | 4·5 | 1·5 | 1·4 | 0·4 | 1·4 | 0·4 | | |
| 10 | ·142 | 58·0 | 58·0 | ·048 | 58·0 | 58·0 | — | 10 | 21·984 | 50·5 | 50·8 | ·968 | 52·5 | 53·0 | — | 10 | 21·990 | 51·0 | 51·4 | ·932 | 51·6 | 51·5 | 0·08 | 2·0 | 3·0 | 3·6 | 1·0 | 1·2 | 0·5 | | |
| 11 | ·118 | 58·5 | 59·4 | ·074 | 57·4 | 58·0 | — | 11 | ·982 | 51·6 | 51·9 | ·918 | 51·5 | 51·8 | 0·13 | 11 | ·972 | 48·8 | 49·0 | ·946 | 53·2 | 53·5 | 0·02 | 4·9 | 3·0 | 0·4 | 0·6 | 3·0 | 0·7 | | |
| 12 | ·114 | 58·0 | 59·0 | ·052 | 58·4 | 59·0 | — | 12 | ·940 | 49·8 | 50·0 | ·884 | 50·2 | 50·3 | 0·08 | 12 | 22·020 | 51·5 | 51·8 | ·980 | 54·2 | 54·5 | 0·04 | 3·0 | 2·9 | 0·5 | 0·3 | 0·9 | 1·0 | | |
| 13 | ·138 | 57·4 | 58·4 | ·082 | 57·0 | 58·4 | 0·64 | 13 | ·963 | 50·8 | 51·4 | ·930 | 53·8 | 54·2 | 0·56 | 13 | ·032 | 52·0 | 52·2 | ·958 | 52·8 | 53·2 | 0·24 | 3·0 | 2·9 | 0·6 | 1·2 | 0·2 | 0·2 | | |
| 14 | ·112 | 57·5 | 58·0 | ·062 | 57·0 | 57·4 | — | 14 | 22·004 | 51·8 | 52·2 | ·956 | 53·4 | 53·8 | — | 14 | 21·992 | 51·8 | 52·0 | ·942 | 52·4 | 52·5 | 0·32 | 3·0 | 2·2 | 4·0 | 0·3 | 0·0 | 0·1 | | |
| 15 | ·126 | 57·8 | 58·2 | ·052 | 57·5 | 57·9 | — | 15 | ·063 | 52·6 | 52·2 | ·961 | 51·2 | 51·6 | 0·05 | 15 | ·990 | 52·0 | 52·2 | ·934 | 53·6 | 53·8 | 0·17 | 3·2 | 1·4 | 1·0 | 0·2 | 0·2 | 0·6 | | |
| 16 | ·102 | 58·0 | 58·4 | ·030 | 58·8 | 59·2 | 0·05 | 16 | ·068 | 50·5 | 50·9 | ·924 | 51·3 | 51·5 | 0·04 | 16 | ·992 | 52·2 | 52·5 | ·957 | 52·5 | 53·0 | — | 5·4 | 3·2 | 3·5 | 0·3 | 0·3 | 0·6 | | |
| 17 | ·090 | 58·0 | 58·5 | ·040 | 57·2 | 58·0 | 0·30 | 17 | 21·964 | 49·5 | 50·0 | ·924 | 51·8 | 51·8 | — | 17 | 22·010 | 51·8 | 52·0 | ·970 | 53·2 | 53·4 | 0·08 | 3·3 | 3·5 | 2·1 | 0·3 | 0·2 | 0·4 | | |
| 18 | ·096 | 57·0 | 57·0 | ·044 | 57·5 | 58·0 | 0·02 | 18 | ·986 | 55·0 | 55·5 | ·940 | 55·6 | 56·0 | — | 18 | ·016 | 51·0 | 51·0 | ·972 | 53·4 | 53·9 | 0·03 | 5·2 | 3·0 | 1·7 | 0·5 | 0·0 | 0·7 | | |
| 19 | ·102 | 59·4 | 60·0 | ·024 | 58·8 | 58·5 | 0·12 | 19 | ·996 | 52·2 | 52·8 | ·940 | 52·3 | 52·8 | 0·43 | 19 | ·012 | 52·0 | 52·8 | ·956 | 52·0 | 52·4 | 0·05 | 5·0 | 3·3 | 0·8 | 0·6 | 1·0 | 0·4 | | |
| 20 | ·046 | 55·0 | 55·0 | 21·972 | 56·2 | 56·8 | 1·05 | 20 | ·996 | 52·4 | 52·9 | ·958 | 52·8 | 53·0 | 0·03 | 20 | ·004 | 53·8 | 53·9 | ·955 | 52·4 | 52·8 | 0·02 | 1·1 | 0·8 | 0·9 | 0·2 | 0·7 | 0·6 | | |
| 21 | ·012 | 57·8 | 58·0 | ·948 | 58·0 | 57·5 | 0·03 | 21 | ·960 | 52·8 | 52·9 | — | — | — | 0·25 | 21 | ·024 | 53·9 | 53·9 | ·962 | 54·4 | 54·5 | 0·21 | 1·5 | 1·0 | 0·1 | — | 0·1 | 0·6 | | |
| 22 | ·018 | 58·9 | 58·5 | ·982 | 58·0 | 57·6 | 0·02 | 22 | ·916 | 52·2 | 52·4 | ·858 | 52·4 | 52·6 | — | 22 | 21·998 | 54·0 | 54·0 | ·931 | 55·5 | 55·5 | 0·16 | 1·5 | 1·1 | 0·5 | 0·6 | 0·1 | 0·3 | | |
| 23 | ·040 | 56·5 | 56·9 | ·942 | 58·2 | 57·8 | 0·07 | 23 | ·848 | 52·0 | 52·0 | ·800 | 50·0 | 50·0 | 0·09 | 23 | ·992 | 53·2 | 53·5 | ·924 | 54·3 | 54·6 | 0·03 | 0·9 | 1·0 | 0·2 | 0·5 | 0·3 | 0·4 | | |
| 24 | ·020 | 55·2 | 55·8 | ·930 | 57·0 | 56·8 | 0·08 | 24 | ·924 | 51·4 | 51·5 | ·880 | 51·8 | 51·8 | 1·00 | 24 | ·984 | 53·0 | 53·8 | ·925 | 53·0 | 53·2 | 1·15 | 0·3 | 0·8 | 0·1 | 0·4 | 0·8 | 0·3 | | |
| 25 | ·006 | 54·0 | 54·5 | ·952 | 56·2 | 56·0 | 0·31 | 25 | ·956 | 51·7 | 51·7 | ·912 | 52·0 | 52·2 | 0·07 | 25 | ·956 | 51·0 | 51·2 | ·948 | 52·5 | 52·8 | 0·18 | 0·5 | 0·5 | 0·1 | 0·2 | 0·2 | 0·4 | | |
| 26 | ·026 | 54·5 | 55·0 | ·974 | 55·8 | 56·2 | 0·09 | 26 | 22·006 | 51·6 | 51·8 | ·954 | 52·5 | 52·2 | 0·21 | 26 | ·958 | 51·9 | 52·2 | ·889 | 52·0 | 52·2 | 0·55 | 0·5 | 0·2 | 0·3 | 0·2 | 0·2 | 0·2 | | |
| 27 | ·036 | 55·4 | 55·6 | ·962 | 57·4 | 57·0 | 0·12 | 27 | 21·952 | 49·2 | 49·2 | ·926 | 50·8 | 51·0 | 0·07 | 27 | ·939 | 51·5 | 51·8 | ·915 | 53·2 | 52·5 | 0·70 | 0·4 | 1·1 | 0·4 | 0·2 | 0·4 | 0·4 | | |
| 28 | 21·986 | 53·8 | 54·0 | ·943 | 53·5 | 53·8 | 0·04 | 28 | ·946 | 51·0 | 51·0 | ·880 | 51·8 | 52·0 | 0·33 | 28 | ·950 | 52·8 | 53·0 | ·913 | 53·2 | 52·5 | 0·63 | 0·2 | 0·4 | 0·0 | 0·4 | 0·2 | 0·3 | | |
| 29 | ·990 | 52·0 | 52·5 | ·946 | 53·6 | 53·8 | 0·25 | 29 | ·912 | 51·0 | 51·2 | ·879 | 50·0 | 50·4 | 0·08 | 29 | ·974 | 52·8 | 53·1 | ·961 | 52·0 | 52·1 | 0·38 | 0·5 | 0·5 | 0·3 | 0·2 | 0·1 | 0·1 | | |
| 30 | 22·030 | 52·5 | 52·0 | — | — | — | 0·16 | 30 | ·964 | 51·0 | 51·0 | ·920 | 52·0 | 52·4 | 0·35 | 30 | 22·032 | 52·5 | 52·8 | ·962 | 53·2 | 53·6 | 0·24 | 0·0 | — | 0·0 | 0·2 | 0·6 | 0·6 | | |
| 31 | ·054 | 54·5 | 54·8 | ·960 | 53·5 | 53·2 | 0·18 | | | | | | | | | 31 | ·030 | 53·1 | 53·4 | ·964 | 53·0 | 53·1 | 0·05 | 0·0 | 0·2 | ..... | ..... | 0·3 | 0·3 | | |
| Mean | 22·087 | 56·6 | 57·1 | 22·024 | 57·1 | 57·3 | 4·86 | Mean | 21·992 | 51·8 | 52·1 | 21·940 | 52·4 | 52·9 | 4·55 | Mean | 22·000 | 52·0 | 52·3 | ·949 | 52·8 | 53·0 | 7·41 | 2·5 | 2·0 | 1·0 | 0·4 | 0·5 | 0·4 | | |

TABLE (Continued).

| AUGUST. | | | | | | | | SEPTEMBER. | | | | | | | | OCTOBER. | | | | | | | | Depression of the wet bulb. | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Date. | h m 9 40 A.M. | | | h m 3 40 A.M. | | | | Date. | h m 9 40 A.M. | | | h m 3 40 P.M. | | | | Date. | h m 9 40 A.M. | | | h m 3 40 P.M. | | | | August. | | September. | | October. | | | |
| 1847. | Barometer. | Att. | Det. | Barometer. | Att. | Det. | Rain. | 1847. | Barometer. | Att. | Det. | Barometer. | Att. | Det. | Rain. | 1847. | Barometer. | Att. | Det. | Barometer. | Att. | Det. | Rain. | h m 9 40 A.M. | a m 3 40 P.M. | h m 9 40 A.M. | h m 3 40 P.M. | h m 9 40 A.M. | h m 3 40 P.M. | | |
| | in. | ° | ° | in. | ° | ° | in. | | in. | ° | ° | in. | ° | ° | in. | | in. | ° | ° | in. | ° | ° | in. | | | | | | | | |
| 1 | 22·012 | 52·1 | 52·2 | 21·934 | 52·4 | 52·9 | 0·46 | 1 | 22·032 | 53·5 | 53·8 | 21·976 | 53·0 | 53·0 | 0·36 | 1 | 22·000 | 51·0 | 51·5 | 21·960 | 52·1 | 52·5 | | 0·1 | 0·5 | 0·3 | 0·1 | 0·0 | 2·5 | | |
| 2 | 21·972 | 52·8 | 53·0 | ·912 | 52·2 | 52·2 | 0·25 | 2 | ·050 | 53·1 | 53·2 | 22·010 | 53·5 | 53·5 | 0·55 | 2 | ·046 | 52·5 | 53·0 | 22·013 | 52·1 | 52·2 | 0·02 | 0·1 | 0·1 | 0·0 | 0·1 | 0·7 | 0·2 | | |
| 3 | ·979 | 52·0 | 52·2 | ·937 | 52·0 | 52·1 | 0·21 | 3 | ·052 | 53·5 | 53·4 | 21·990 | 53·0 | 53·0 | 0·17 | 3 | ·086 | 52·8 | 53·1 | ·032 | 52·5 | 53·0 | | 0·3 | 0·2 | 0·0 | 0·0 | 0·1 | 1·0 | | |
| 4 | ·971 | 51·0 | 51·2 | ·920 | 52·5 | 52·8 | 0·12 | 4 | ·030 | 51·8 | 52·0 | ·980 | 53·0 | 53·0 | 0·35 | 4 | ·122 | 53·5 | 53·8 | ·058 | 55·0 | 55·2 | 0·02 | 0·2 | 0·8 | 0·2 | 0·1 | 0·3 | 0·2 | | |
| 5 | ·979 | 51·9 | 52·0 | ·920 | 52·1 | 52·2 | 0·59 | 5 | ·030 | 50·1 | 50·2 | ·967 | 51·8 | 51·8 | 0·36 | 5 | ·100 | 53·4 | 54·0 | ·028 | 53·4 | 53·6 | 0·36 | 0·0 | 0·1 | 0·1 | 1·2 | 1·0 | 0·3 | | |
| 6 | ·978 | 51·8 | 51·9 | ·910 | 52·4 | 52·5 | 0·79 | 6 | 21·928 | 48·5 | 48·6 | ·913 | 50·1 | 50·2 | 0·15 | 6 | ·084 | 51·6 | 52·0 | ·012 | 52·3 | 52·5 | 0·44 | 0·1 | 0·5 | 1·6 | 0·1 | 0·8 | 0·5 | | |
| 7 | ·974 | 52·4 | 52·5 | ·892 | 51·4 | 51·5 | 0·74 | 7 | ·948 | 51·5 | 51·8 | ·900 | 50·2 | 50·4 | 0·48 | 7 | ·104 | 52·0 | 52·5 | ·026 | 53·0 | 53·0 | 0·02 | 0·1 | 0·0 | 0·3 | 0·2 | 0·4 | 0·5 | | |
| 8 | ·972 | 52·0 | 52·2 | ·932 | 53·0 | 53·2 | 0·03 | 8 | ·932 | 50·4 | 50·5 | ·876 | 51·5 | 51·6 | 0·50 | 8 | ·124 | 52·5 | 53·1 | ·040 | 53·2 | 53·5 | 0·14 | 0·2 | 0·2 | 0·1 | 0·3 | 0·7 | 0·3 | | |
| 9 | 22·034 | 53·4 | 53·5 | ·974 | 53·1 | 53·1 | 0·50 | 9 | ·880 | 50·8 | 50·8 | ·879 | 51·9 | 52·0 | 0·32 | 9 | ·116 | 52·6 | 53·0 | ·038 | 52·8 | 53·1 | 0·05 | 0·5 | 0·1 | 0·3 | 0·2 | 0·5 | 0·2 | | |
| 10 | ·072 | 53·2 | 53·4 | 22·026 | 54·0 | 54·2 | 0·37 | 10 | ·976 | 51·8 | 51·9 | ·934 | 52·2 | 52·5 | 0·34 | 10 | ·090 | 53·9 | 54·3 | ·042 | 53·2 | 53·4 | 0·45 | 0·4 | 0·2 | 0·4 | 0·4 | 0·4 | 0·2 | | |
| 11 | ·090 | 53·2 | 53·5 | ·032 | 53·0 | 53·0 | 0·18 | 11 | ·967 | 51·7 | 51·5 | ·900 | 52·0 | 52·2 | 0·40 | 11 | ·072 | 53·4 | 53·5 | 21·994 | 55·1 | 55·2 | 1·21 | 0·3 | 0·0 | 0·3 | 0·2 | 0·1 | 0·1 | | |
| 12 | ·070 | 52·0 | 52·2 | ·009 | 53·0 | 53·2 | 0·73 | 12 | ·984 | 51·3 | 51·5 | — | — | — | 0·28 | 12 | ·098 | 53·8 | 54·1 | 22·030 | 54·2 | 54·4 | 0·67 | 0·9 | 0·2 | 0·2 | — | 0·1 | 0·3 | | |
| 13 | ·052 | 52·2 | 52·5 | 21·988 | 52·1 | 52·1 | 0·08 | 13 | 22·006 | 51·6 | 52·2 | ·978 | 51·9 | 52·0 | 0·20 | 13 | ·076 | 53·0 | 53·2 | 21·989 | 53·0 | 53·0 | 0·11 | 0·2 | 0·3 | 0·4 | 0·5 | 0·1 | 0·0 | | |
| 14 | 21·973 | 50·2 | 50·3 | ·932 | 50·6 | 50·9 | 0·18 | 14 | ·024 | 52·2 | 52·4 | 22·010 | 51·9 | 52·1 | 0·15 | 14 | 21·999 | 51·9 | 52·1 | ·900 | 51·4 | 51·6 | 1·82 | 0·2 | 0·3 | 0·2 | 0·2 | 0·1 | 0·2 | | |
| 15 | ·952 | 52·0 | 52·2 | ·952 | 51·1 | 51·2 | — | 15 | ·050 | 53·1 | 53·3 | 21·990 | 52·0 | 52·2 | 0·12 | 15 | 22·016 | 53·1 | 53·4 | ·958 | 53·8 | 54·0 | 0·92 | 0·2 | 0·8 | 0·2 | 0·2 | 0·2 | 0·1 | | |
| 16 | 22·022 | 51·4 | 51·8 | ·984 | 51·5 | 51·8 | 0·25 | 16 | ·066 | 52·3 | 53·5 | 22·012 | 54·4 | 54·5 | 0·07 | 16 | ·052 | 53·5 | 53·8 | ·990 | 53·9 | 54·1 | 0·17 | 0·4 | 2·6 | 0·3 | 0·2 | 0·2 | 0·1 | | |
| 17 | ·046 | 53·3 | 53·4 | ·993 | 54·5 | 54·9 | 0·25 | 17 | ·070 | 52·6 | 53·0 | ·002 | 53·8 | 54·1 | 0·08 | 17 | ·088 | 53·4 | 53·5 | 22·022 | 54·4 | 54·8 | 0·09 | 0·1 | 0·5 | 0·6 | 0·3 | 0·0 | 0·4 | | |
| 18 | ·057 | 53·9 | 53·2 | 22·017 | 55·1 | 55·5 | 0·20 | 18 | ·078 | 49·5 | 49·8 | ·019 | 53·8 | 54·1 | — | 18 | ·110 | 53·5 | 53·5 | ·032 | 55·1 | 55·3 | 0·11 | 0·2 | 0·3 | 2·6 | 0·6 | 0·1 | 0·2 | | |
| 19 | ·066 | 52·5 | 52·8 | ·018 | 54·0 | 54·2 | — | 19 | ·074 | 52·6 | 53·1 | ·012 | 52·8 | 53·2 | — | 19 | ·089 | 54·2 | 54·4 | ·010 | 54·3 | 54·5 | 0·30 | 3·0 | 0·4 | 0·6 | 0·5 | 0·2 | 0·3 | | |
| 20 | ·071 | 55·4 | 56·0 | ·022 | 53·8 | 54·2 | 0·02 | 20 | ·088 | 52·0 | 52·4 | ·020 | 53·2 | 53·5 | 0·37 | 20 | ·122 | 53·4 | 54·0 | ·031 | 53·5 | 53·8 | 1·24 | 9·6 | 0·5 | 0·4 | 0·6 | 0·5 | 0·2 | | |
| 21 | ·090 | 53·5 | 54·0 | ·022 | 55·0 | 55·2 | — | 21 | ·066 | 53·6 | 54·0 | 21·988 | 54·3 | 54·7 | 0·78 | 21 | ·129 | 54·4 | 54·9 | ·035 | 53·0 | 53·3 | 0·54 | 0·5 | 0·2 | 0·5 | 0·2 | 0·4 | 0·3 | | |
| 22 | ·084 | 54·9 | 55·0 | ·022 | 55·1 | 55·3 | 0·18 | 22 | ·071 | 53·2 | 53·5 | 22·006 | 54·0 | 54·3 | 0·66 | 22 | ·116 | 54·0 | 54·5 | ·034 | 54·8 | 55·2 | 0·29 | 0·4 | 0·3 | 1·0 | 0·4 | 0·5 | 0·8 | | |
| 23 | ·055 | 53·2 | 53·3 | ·006 | 54·3 | 54·5 | 1·63 | 23 | ·100 | 53·4 | 54·0 | ·034 | 53·8 | 54·0 | — | 23 | ·104 | 52·2 | 52·5 | ·048 | 53·8 | 53·8 | 2·39 | 0·8 | 0·4 | 0·9 | 0·2 | 0·2 | 0·3 | | |
| 24 | ·048 | 54·5 | 54·8 | ·014 | 53·0 | 53·5 | — | 24 | ·088 | 47·2 | 48·0 | ·022 | 52·5 | 54·0 | — | 24 | ·111 | 52·2 | 52·5 | ·047 | 52·4 | 52·5 | 0·07 | 1·8 | 0·5 | 3·5 | 7·0 | 0·2 | 0·1 | | |
| 25 | ·078 | 53·1 | 53·4 | ·010 | 53·6 | 54·0 | 0·50 | 25 | ·079 | 49·8 | 51·0 | ·020 | 52·5 | 53·0 | — | 25 | ·092 | 52·4 | 52·8 | ·026 | 53·2 | 53·5 | 0·19 | 0·9 | 0·4 | 5·8 | 1·1 | 0·3 | 0·1 | | |
| 26 | ·060 | 52·2 | 52·5 | 21·986 | 55·0 | 55·2 | 0·30 | 26 | ·082 | 51·5 | 52·2 | ·020 | 53·5 | 54·4 | — | 26 | ·116 | 53·9 | 54·2 | ·034 | 53·9 | 54·0 | 0·01 | 2·0 | 0·6 | 0·8 | 0·6 | 0·3 | 0·1 | | |
| 27 | ·032 | 52·0 | 52·0 | ·998 | 53·5 | 53·5 | 0·23 | 27 | ·064 | 52·5 | 53·1 | 21·984 | 52·9 | 53·1 | 0·03 | 27 | ·092 | 55·2 | 55·3 | ·036 | 54·2 | 54·5 | 0·04 | 0·0 | 0·3 | 0·7 | 0·1 | 0·1 | 0·3 | | |
| 28 | ·059 | 54·8 | 55·1 | ·990 | 53·1 | 53·1 | 0·06 | 28 | ·047 | 52·3 | 52·5 | ·986 | 52·5 | 53·0 | 0·55 | 28 | ·102 | 51·6 | 52·2 | ·020 | 51·5 | 51·5 | | 2·1 | 0·6 | 0·6 | 0·6 | 1·4 | 0·6 | | |
| 29 | ·040 | 52·2 | 52·5 | ·980 | 51·9 | 52·0 | 0·29 | 29 | ·029 | 49·6 | 50·1 | ·963 | 52·6 | 53·1 | 0·18 | 29 | ·077 | 49·4 | 50·2 | ·014 | 50·5 | 50·5 | 0·06 | 0·3 | 0·1 | 0·6 | 0·8 | 1·4 | 1·3 | | |
| 30 | ·019 | 53·0 | 53·1 | ·960 | 53·5 | 53·8 | 0·03 | 30 | ·028 | 51·4 | 52·0 | ·946 | 52·5 | 52·6 | 0·07 | 30 | ·056 | 51·4 | 51·6 | 21·991 | 52·0 | 52·0 | 0·10 | 0·1 | 1·4 | 1·0 | 1·1 | 0·2 | 0·0 | | |
| 31 | ·028 | 53·0 | 53·0 | ·955 | 53·0 | 53·0 | 0·15 | | | | | | | | | 31 | ·064 | 52·2 | 52·5 | ·998 | 53·0 | 53·2 | 0·66 | 0·0 | 0·0 | ... | ... | 0·3 | 0·4 | | |
| Mean. | 22·030 | 52·8 | 52·9 | 21·976 | 53·1 | 53·3 | 9·32 | Mean. | 22·031 | 51·6 | 52·0 | 21·977 | 52·7 | 52·9 | 7·52 | Mean. | 22·086 | 52·8 | 53·2 | 22·014 | 53·2 | 53·4 | 12·49 | 0·8 | 0·4 | 0·8 | 0·6 | 0·6 | 0·4 | | |

## TABLE (Continued).

| NOVEMBER. | | | | | | | | DECEMBER. | | | | | | | | JANUARY. | | | | | | | | Depression of the wet bulb. | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Date. | h m 9 40 A.M. | | | h m 3 40 A.M. | | | | Date. | h m 9 40 A.M. | | | h m 3 40 P.M. | | | | Date. | h m 9 40 A.M. | | | h m 3 40 P.M. | | | | November. | | December. | | January, 1848. | | | |
| 1847. | Barometer. | Att. | Det. | Barometer. | Att. | Det. | Rain. | 1847. | Barometer. | Att. | Det. | Barometer. | Att. | Det. | Rain. | 1848. | Barometer. | Att. | Det. | Barometer. | Att. | Det. | Rain. | h m 9 40 A.M. | h m 3 40 P.M. | h m 9 40 A.M. | h m 3 40 P.M. | h m 9 40 A.M. | h m 3 40 P.M. | | |
| | in. | ° | ° | in. | ° | ° | in. | | in. | ° | ° | in. | ° | ° | in. | | in. | ° | ° | in. | ° | ° | in. | ° | ° | ° | ° | ° | ° | | |
| 1 | 22·093 | 53·2 | 53·3 | 22·030 | 52·6 | 52·8 | 1·03 | 1 | 22·040 | 53·0 | 54·2 | 21·990 | 47·8 | 47·8 | 0·24 | 1 | 22·128 | 49·5 | 53·5 | 22·080 | 51·9 | 52·0 | — | 0·1 | 0·3 | 9·0 | 5·9 | 2·5 | 1·2 | | |
| 2 | ·083 | 51·8 | 52·1 | ·022 | 52·2 | 52·4 | 1·64 | 2 | ·036 | 51·5 | 52·1 | ·962 | 50·0 | 50·1 | — | 2 | ·138 | 47·0 | 49·4 | ·064 | 50·1 | 50·8 | — | 0·2 | 0·2 | 0·5 | 0·1 | 6·2 | 4·8 | | |
| 3 | ·014 | 52·2 | 52·5 | 21·982 | 52·6 | 52·9 | 1·10 | 3 | ·032 | 51·5 | 51·8 | ·972 | 51·3 | 51·5 | 0·52 | 3 | ·125 | 49·0 | 49·4 | ·066 | 51·2 | 53·0 | — | 0·1 | 0·1 | 0·2 | 0·3 | 1·4 | 2·0 | | |
| 4 | ·114 | 52·6 | 52·9 | 22·046 | 53·5 | 53·5 | 2·32 | 4 | ·056 | 53·2 | 54·0 | 22·006 | 51·0 | 52·0 | 0·53 | 4 | ·132 | 51·6 | 52·5 | ·070 | 54·2 | 54·4 | 0·03 | 0·0 | 0·0 | 0·2 | 0·0 | 0·5 | 1·0 | | |
| 5 | ·140 | 53·0 | 53·3 | ·060 | 52·6 | 52·8 | 0·75 | 5 | ·108 | 53·2 | 52·8 | ·056 | 52·3 | 52·5 | 5·15 | 5 | ·128 | 51·4 | 52·5 | ·050 | 52·9 | 53·9 | — | 0·2 | 0·1 | 0·0 | 0·0 | 1·1 | 0·5 | | |
| 6 | ·113 | 52·0 | 52·8 | ·050 | 53·0 | 53·4 | 1·35 | 6 | ·099 | 52·2 | 52·6 | ·038 | 52·8 | 52·8 | 0·40 | 6 | ·112 | 52·0 | 53·2 | ·035 | 52·4 | 52·9 | 0·02 | 0·8 | 0·4 | 0·1 | 0·0 | 1·3 | 0·7 | | |
| 7 | ·060 | 52·2 | 52·6 | 21·966 | 51·0 | 51·2 | 0·24 | 7 | ·100 | 48·6 | 50·2 | ·026 | 50·5 | 51·2 | 0·15 | 7 | ·092 | 51·1 | 52·4 | ·021 | 53·0 | 53·2 | 0·04 | 0·4 | 0·4 | 3·3 | 1·4 | 0·8 | 1·1 | | |
| 8 | ·064 | 52·6 | 53·0 | 22·010 | 52·2 | 52·6 | 0·12 | 8 | ·114 | 49·4 | 50·2 | ·048 | 50·2 | 50·4 | 0·02 | 8 | ·080 | 49·6 | 50·4 | ·026 | 52·0 | 52·0 | 0·03 | 0·4 | 0·8 | 0·3 | 0·0 | 7·2 | 1·2 | | |
| 9 | ·080 | 49·0 | 49·5 | ·064 | 50·0 | 50·2 | | 9 | ·081 | 48·8 | 51·0 | ·010 | 49·2 | 49·5 | — | 9 | ·102 | 47·3 | 50·0 | ·040 | 52·3 | 52·3 | — | 0·5 | 0·4 | 7·4 | 4·3 | 5·5 | 6·7 | | |
| 10 | ·074 | 48·0 | 49·0 | ·035 | 50·2 | 50·5 | 0·03 | 10 | ·016 | 46·2 | 49·4 | 21·960 | 46·5 | 47·8 | — | 10 | ·092 | 49·2 | 50·6 | ·037 | 52·0 | 52·8 | — | 0·9 | 0·2 | 6·9 | 9·8 | 9·6 | 2·4 | | |
| 11 | ·120 | 48·8 | 50·0 | ·056 | 51·5 | 51·5 | 0·06 | 11 | ·004 | 46·8 | 48·5 | ·942 | 49·0 | 49·4 | — | 11 | ·120 | 52·5 | 54·2 | ·072 | 52·8 | 52·5 | — | 1·5 | 0·4 | 3·3 | 1·1 | 10·4 | 4·3 | | |
| 12 | ·150 | 51·5 | 51·5 | ·080 | 51·8 | 52·2 | | 12 | 21·990 | 49·0 | 50·9 | ·926 | 50·0 | 50·2 | — | 12 | ·130 | 52·8 | 55·3 | ·066 | 55·0 | 54·2 | — | 0·3 | 0·2 | 1·7 | 0·2 | 6·3 | 4·5 | | |
| 13 | ·152 | 51·2 | 51·5 | — | — | — | 0·04 | 13 | ·979 | 50·0 | 50·5 | ·921 | 50·0 | 50·4 | 0·89 | 13 | ·099 | 51·5 | 57·0 | ·028 | 52·8 | 53·5 | — | 0·1 | — | 0·0 | 0·1 | 14·4 | 6·5 | | |
| 14 | ·136 | 51·4 | 51·8 | ·064 | 51·5 | 52·0 | 0·17 | 14 | ·973 | 50·1 | 50·3 | ·928 | 50·2 | 50·3 | 0·96 | 14 | ·090 | 52·0 | 54·5 | ·021 | 56·4 | 56·4 | — | 0·2 | 0·5 | 0·2 | 0·0 | 3·6 | 5·4 | | |
| 15 | ·108 | 46·8 | 50·4 | ·052 | 48·9 | 49·2 | 0·04 | 15 | 22·020 | 46·2 | 47·5 | ·970 | 49·0 | 49·8 | 0·54 | 15 | ·074 | 48·6 | 50·0 | ·016 | 52·3 | 52·0 | — | 6·4 | 1·7 | 2·2 | 0·3 | 5·0 | 2·5 | | |
| 16 | ·068 | 45·2 | 48·5 | ·006 | 47·0 | 47·2 | | 16 | ·056 | 47·2 | 47·8 | 22·004 | 51·2 | 51·8 | — | 16 | ·101 | 51·8 | 52·9 | ·047 | 53·8 | 53·5 | — | 9·5 | 3·4 | 0·8 | 0·4 | 8·5 | 5·9 | | |
| 17 | ·058 | 47·5 | 49·5 | ·002 | 48·0 | 48·6 | | 17 | ·065 | 49·2 | 50·0 | ·014 | 50·4 | 51·0 | 0·07 | 17 | ·122 | 53·5 | 56·5 | ·056 | 56·0 | 55·2 | — | 8·1 | 1·1 | 0·1 | 0·2 | 2·9 | 7·9 | | |
| 18 | ·104 | 53·0 | 55·8 | ·034 | 51·8 | 52·5 | | 18 | ·089 | 51·8 | 52·0 | ·022 | 52·0 | 52·4 | 0·30 | 18 | ·119 | 50·8 | 51·0 | ·040 | 52·0 | 52·4 | — | 3·8 | 0·7 | 0·0 | 0·1 | 10·0 | 3·5 | | |
| 19 | ·130 | 52·2 | 53·1 | ·052 | 51·4 | 51·8 | | 19 | ·112 | 53·0 | 53·5 | ·033 | 51·9 | 52·4 | 1·29 | 19 | ·100 | 50·3 | 51·1 | ·026 | 52·0 | 52·0 | — | 0·3 | 0·2 | 0·1 | 0·1 | 6·6 | 2·8 | | |
| 20 | ·117 | 51·9 | 52·5 | ·046 | 51·5 | 51·5 | 0·24 | 20 | ·120 | 51·5 | 52·0 | ·050 | 52·4 | 52·5 | 0·60 | 20 | ·108 | 49·0 | 49·6 | ·052 | 51·8 | 51·6 | — | 0·9 | 0·1 | 0·1 | 0·5 | 8·2 | 4·2 | | |
| 21 | ·108 | 49·0 | 51·4 | ·059 | 51·6 | 51·5 | 0·18 | 21 | ·120 | 51·8 | 52·5 | ·036 | 52·0 | 52·1 | — | 21 | ·101 | 49·2 | 50·0 | ·038 | 51·5 | 51·1 | — | 6·6 | 2·6 | 0·3 | 0·0 | 10·7 | 5·5 | | |
| 22 | ·136 | 54·0 | 56·1 | ·064 | 53·0 | 53·9 | | 22 | ·110 | 51·6 | 52·1 | ·044 | 52·5 | 52·5 | 0·05 | 22 | ·120 | 52·8 | 54·0 | ·056 | 51·8 | 51·8 | — | 9·1 | 1·7 | 1·6 | 1·3 | 12·0 | 8·9 | | |
| 23 | ·116 | 52·2 | 53·0 | ·048 | 53·0 | 53·3 | | 23 | ·099 | 48·0 | 51·9 | ·040 | 49·4 | 49·0 | — | 23 | ·112 | 49·2 | 51·0 | ·049 | 52·5 | 52·5 | — | 0·6 | 0·3 | 9·1 | 0·5 | 11·0 | 6·1 | | |
| 24 | ·106 | 52·0 | 52·9 | ·035 | 53·1 | 53·5 | 0·19 | 24 | ·081 | 50·0 | 51·2 | ·046 | 48·5 | 48·2 | — | 24 | ·090 | 49·0 | 52·1 | ·032 | 51·0 | 51·3 | — | 0·6 | 0·1 | 8·2 | 7·0 | 9·6 | 7·8 | | |
| 25 | ·102 | 53·8 | 54·0 | ·030 | 53·4 | 53·5 | 0·85 | 25 | ·090 | 47·4 | 51·5 | ·032 | 51·0 | 50·2 | — | 25 | ·102 | 49·0 | 51·8 | ·037 | 53·3 | 52·3 | — | 0·5 | 0·3 | 5·9 | 5·3 | 7·6 | 10·1 | | |
| 26 | ·109 | 52·2 | 52·5 | ·032 | 53·9 | 54·0 | 0·11 | 26 | ·096 | 48·9 | 51·6 | ·044 | 51·1 | 51·0 | — | 26 | ·100 | 48·8 | 51·0 | ·039 | 52·0 | 51·2 | — | 0·1 | 0·0 | 4·6 | 4·5 | 10·8 | 9·9 | | |
| 27 | ·098 | 53·4 | 54·0 | ·034 | 53·1 | 53·4 | 0·20 | 27 | ·100 | 49·8 | 50·4 | ·042 | 50·0 | 50·5 | — | 27 | ·120 | 49·0 | 50·8 | ·040 | 50·0 | 51·0 | — | 0·5 | 0·3 | 0·9 | 0·0 | 8·3 | 8·1 | | |
| 28 | ·094 | 53·5 | 54·0 | ·048 | 52·8 | 52·0 | 0·73 | 28 | ·100 | 50·8 | 51·0 | ·050 | 49·1 | 49·4 | 0·36 | 28 | ·134 | 49·8 | 51·5 | ·088 | 53·2 | 52·7 | — | 0·2 | 0·0 | 0·0 | 0·5 | 9·0 | 8·7 | | |
| 29 | ·100 | 52·0 | 52·5 | ·052 | 52·5 | 52·5 | 0·34 | 29 | ·150 | 48·4 | 50·0 | ·081 | 49·0 | 49·0 | 0·21 | 29 | ·163 | 47·5 | 50·0 | ·100 | 52·5 | 52·2 | — | 0·1 | 0·5 | 1·5 | 0·4 | 8·6 | 6·7 | | |
| 30 | ·106 | 52·0 | 52·4 | ·034 | 52·2 | 52·4 | 0·12 | 30 | ·105 | 48·0 | 49·4 | ·039 | 49·0 | 49·1 | — | 30 | ·132 | 49·5 | 50·2 | ·072 | 49·2 | 50·0 | — | 0·3 | 0·3 | 1·8 | 3·2 | 9·4 | 4·8 | | |
| | | | | | | | | 31 | ·112 | 47·0 | 49·5 | ·064 | 48·8 | 49·0 | — | 31 | ·124 | 49·5 | 51·2 | ·085 | 51·2 | 50·5 | — | | | 5·1 | 4·5 | 8·2 | 7·3 | | |
| Mean. | 22·117 | 51·3 | 52·3 | 22·038 | 51·8 | 52·0 | 11·85 | Mean. | 22·073 | 49·8 | 51·1 | 22·013 | 50·3 | 50·5 | 12·28 | Mean. | 22·113 | 50·1 | 51·9 | 22·050 | 52·4 | 52·5 | 0·12 | 1·8 | 0·6 | 2·4 | 1·7 | 7·0 | 4·9 | | |

On the 15th, 16th and 17th of November ice was found around the office at sunrise.

*Range of Barometer at Dodabetta.*

An inspection of the above Tables shows that the range of the daily pressure, on the whole, had been very regular. The minimum oscillation was 0·08 on the 25th of July, although on the preceding and following days it was respectively 0·059 and 0·069; on the 25th of July 0·18 of rain fell, but the oscillation was only 0·16 on the 10th of June, on which day no rain fell, and the wet bulb was depressed 3°·6 in the morning and 1° in the afternoon. There are two other instances in which the diurnal oscillation was less than three hundredths,—on the 11th of April ·022, and on the 3rd of June ·026. The maximum oscillation occurred on the 16th of June, and was ·144. The preceding day it was ·102, but the following day it was only ·040. On the 18th of March it was ·102, on the 1st of March ·094, and on the 19th of February ·092; with these few exceptions of maxima and minima in diurnal oscillation, the daily range of the barometer was from ·040 to ·060, showing no violent atmospheric changes. The maximum pressure was on the 17th of March, and was 22·218 in., and the minimum on the 23rd of June, when the barometer stood at 21·800, although only ·09 of an inch of rain fell on that day, and little for several days before. The extreme annual range of the barometer, therefore, was only ·418, or less than half an inch. I have shown, in my former paper in the Philosophical Transactions, that the annual range in the Deccan, at 1800 feet above the sea, was only ·672 in 1830, from 28·242 in. in January to 27·570 in July, the difference of the thermometer at the extreme periods being only 1°·4; and in no instance, on comparing the maximum pressure of one year with the minimum pressure of any other year, did the difference amount to eight-tenths of an inch. In Goldingham's tables at Madras, for twenty-one years, the greatest range in any year (with the single exception of a terrific storm in May 1820) appears to have been ·960 in 1818. In the more careful observations recorded by Capt. Ludlow at the Madras Magnetic Observatory, from 1841 to 1845 both inclusive, *taken hourly*, the maximum range in 1842 (the observations for 1841 being imperfect) was from 30·156 at forty-one minutes past 9 A.M. on the 5th of December, to 29·454 on the 1st of June at $3^h\ 41^m$ P.M., and 29·455 on the 3rd of June at $4^h\ 41^m$ P.M., the range being 0·702 of an inch, the standard thermometer at the maximum pressure being 80°·6, and at the minimum 97°·3. In 1843 the maximum pressure was 30·208 on the 24th of January at $9^h\ 41^m$ A.M., and the minimum on the 21st of May being 29·256 at $3^h\ 41^m$ A.M., the range therefore 0·952; the thermometer at the maximum 81°·2, and at the minimum period 77° $8^m$. In 1844 the maximum pressure was on the 16th of January, *i. e.* 30°·170 at $9^h\ 41^m$ A.M., and the minimum on the 1st of June, at $4^h\ 41^m$ P.M., *i. e.* 29·537, the range therefore 0·633, the thermometer at the first period being 79°·5, and at the second 89°·8. In 1845 the maximum pressure was on the 10th of January, 30°·196 at $9^h\ 41^m$ A.M., and the minimum on the 31st of May, 29°·531 at $4^h\ 41^m$ P.M., the range therefore 0·665: the thermometer at the maximum period was 79°·9, and at the minimum it was 101°·5. The following Table shows the extreme range of pressure at Madras, Bombay, Calcutta, &c.

Dates and Hours of the Maximum and Minimum Pressure at Madras, and extreme range of Barometer at Madras, Bombay, Calcutta, &c.

| Years. | Max. Pres. | Date. | Hour. | Min. Pres. | Date. | Hour. | Annual range at Madras. | Annual range at Bombay. | Annual range at Calcutta. | Annual range at Poona. | Annual range at Mahabuleshwur. | Annual range at Dodabetta. |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | h m | | | h m | | | | | | |
| 1842. | 30·156 | Dec. 5. | 9 41 A.M. | 29·454 | June 1. | 3 41 P.M. | 0·702 | ..... | ..... | *0·672 | | |
| 1843. | 30·208 | Jan. 24. | 9 41 A.M. | 29·256 | May 21. | 3 41 P.M. | 0·952 | 0·705 | | | | |
| 1844. | 30·170 | Jan. 16. | 9 41 A.M. | 29·537 | June 1. | 4 41 P.M. | 0·633 | 0·661 | 0·957 | | | |
| 1845. | 30·196 | Jan. 10. | 9 41 A.M. | 29·531 | May 31. | 4 41 P.M. | 0·665 | ..... | ..... | | | |
| 1846. | ..... | ..... | ..... | ..... | ..... | ..... | 0·723 | ..... | 0·869 | | | |
| 1847. | ..... | ..... | ..... | ..... | ..... | ..... | ..... | ..... | 0·859 | ..... | | 0·418 |
| 1848. | ..... | ..... | ..... | ..... | ..... | ..... | ..... | ..... | 0·961 | ..... | 0·443† | |

The maximum pressure, therefore, at Madras occurred at the *same hour* annually and within a range from the 5th of December to the 24th of January; and the minimum pressure occurred between $3^h\ 41^m$ and $4^h\ 41^m$ P.M., and within the range of ten days between the 21st of May and 1st of June. The maximum pressure at Dodabetta, in 1847, was on the 17th of March, instead of December or January, as at Madras, but the minimum occurred in June, as at Madras. The Poona maximum was in January and the minimum in July; at Bombay, in 1843, the maximum pressure occurred on the same day and the same hour as at Madras, and the minimum pressure occurred equally in May, but on the 16th instead of the 21st of May. These facts Dr. Buist recorded in a series of meteorological observations, taken hourly in Bombay for the year 1843, on the opposite side of the peninsula from Madras; and in his tables it is stated that the maximum pressure of the atmosphere, 30·136, occurred on the 24th of January at 10 A.M., and the minimum pressure, 29·431, on the 16th of May, before the monsoon set in, at 4 P.M.; the extreme range therefore being 0·705, while the extreme range at Madras in that year was 0·952, but the mean of the five years at Madras was 0·735. In Bombay, in 1844, the range was ·661 from 30·119 on the 13th of January to 29·458 on the 4th of June. At Calcutta unfortunately the observations were not taken hourly, and exact data are not attainable; but the record in 1846 states that the maximum pressure occurred on the 12th of January at $9^h\ 50^m$ A.M., viz. 30·225, and the minimum on the 25th of July at 4 P.M. 29·356, the annual range therefore 0·869. In 1847 the barometer stood highest on the 5th of February at $9^h\ 50^m$, being 30·169, and the least pressure was on the 25th of May, at *sunset*, 29·310, the annual range therefore 0·859, singularly approximating to that of the preceding year, but in both years being greater than at Madras or Bombay. In 1848, at Calcutta, the maximum pressure was on the 24th of December 30·231 (9th of February 30·200, and 16th of February 30·191), and the minimum pressure on the 20th of July 29·270 (on 18th of June 29·353, and on 20th of May 29·459), the extreme range in the year

* For 1830.

† For ten months of 1828–29.

therefore was 0·961. At no one of the places in the Table does there appear to have been a range of an inch; not only within the year, but taking the maximum pressure of one year with the minimum pressure of another year, the range of the barometer never amounted to 1 inch; and but for a record left by the late Mr. GOLDINGHAM, astronomer at Madras, it might be supposed the peninsula of India was not subject to any great changes of pressure. In a furious hurricane however which occurred at Madras on the 30th of October 1836, at 6 A.M., the barometer stood at 29·940, and at 7 P.M. it stood at 28·285, and stood at that during an awful lull until $7^h\ 45^m$ P.M., when the hurricane *recommenced* and the barometer *rose* to 28·725; the removal of pressure in thirteen hours amounting to 1·665 inch. But the area of any such removal of pressure would appear to be comparatively limited, and we are indebted to the elaborate researches of Mr. PIDDINGTON of Calcutta, and Colonel REID of the Royal Engineers, in their investigation of the Rotatory Storms or Cyclones within the tropics, for enabling us to give an approximative area to the great depressions of the barometer at sea, of which the observations on shore scarcely record a trace. For instance, in a storm at Madras on the 16th of May 1841, the hourly observations at the observatory gave the barometer 29·650 at $10\frac{1}{2}$ A.M., and the lowest depression was 29·513 at $4^h\ 41^m$ P.M., while the barque Tenasserim, which had been compelled to slip her cable and run to sea at 1 P.M., at 8 P.M., when not many miles distant from Madras, had the barometer at 28·60, the mercury at Madras at the same hour standing at 29·641, there being a difference of pressure of more than an inch of mercury *within a few miles*. The only effects of this storm upon the diurnal tide at Madras were, that the maximum nocturnal tide turned at $10^h\ 41^m$ P.M. instead of $9^h\ 41^m$ P.M., and the minimum ebb tide stopped at $2^h\ 41^m$ A.M. instead of $3^h\ 41^m$ A.M., but the minimum day-tide turned at the usual hour, $3^h\ 41$ P.M.

Again, in a storm at Madras which took place on the 21st of May 1843, the simultaneous record of the barometer at the observatory and on board the General Kyd, which had been compelled to slip her cables and put to sea from Madras roads, was as follows:—

| | Hours. | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | h m 12 41 | h m 3 41 | h m 5 41 | h m 7 41 | h m 9 41 | h m 11 41 | h m 12 41 | h m 2 41 A.M. | h m 12 41 | h m 2 41 P.M. | h m 5 41 | 23rd noon. |
| Madras ..... | 29·332 | 29·256 | 29·284 | 29·381 | 29·490 | 29·419 | 29·391 | 29·333 | 29·409 | 29·382 | 29·411 | 29·522 |
| General Kyd | 29·45 | 29·38 | 29·28 | 29·26 | 29·19 | 28·17 | 29·11 | 29·11 | 29·18 | 29·19 | 29·27 | 29·42 |

From this Table it is seen that at $11^h\ 41^m$ on the night of the 21st of May, the barometer stood respectively at Madras and on board the General Kyd at 29·412 and 28·17, a difference of 1·242; and as the General Kyd was only sixty-eight miles east of Madras at noon on the 22nd, this prodigious difference of pressure occurred within fifty or sixty miles. The daily atmospheric tides continued at Madras despite the storm. The barometer reached its maximum at $9^h\ 41^m$ A.M., 29·421; and at $3^h\ 41^m$ P.M. it had fallen to its minimum, 29·360; then as usual it rose to 29·498 at $9^h\ 41^m$ P.M., and

as usual fell gradually to 29·373 at $3^h\ 41^m$ A.M. Although therefore the general pressure of the atmosphere had been lowered three or four-tenths of an inch from the 20th and 21st of May, the daily tides had not been interrupted, the maxima and minima occurring at their usual hours. In a storm at Madras on the 24th of October 1842, the P.M. tide reached its maximum at $10^h\ 41^m$ P.M., but the ebb stopped at $1^h\ 41^m$ A.M. instead of $3^h\ 41^m$ A.M., and then rose until $9^h\ 41^m$ A.M., the duration of the ebb being three hours only, and the flow from $1^h\ 41^m$ A.M. to $9^h\ 41^m$ A.M., no less than eight hours; the next ebb six hours, and the subsequent flow seven hours. One other illustration will show how little the pressure of the atmosphere is affected at a great height by a proximate storm. On the 17th and 18th of April 1847 a great storm occurred on the Malabar coast. The following is the record of the barometer on the 17th, at different distances from the *centre of the storm*, as recorded by Colonel REID; the Dodabetta observations being interpolated by myself.

| | in. |
|---|---|
| Madras, 300 miles distant from centre, barometer . . . | 29·97 |
| Dodabetta, 166 miles distant from centre, barometer . . | 21·917 |
| Cannanore, 100 miles distant from centre, barometer . . | 29·64 |
| Ship Mermaid, 60 miles distant from centre, barometer . | 29·35 |

On the 18th of April.

| | in. |
|---|---|
| Madras, 400 miles distant from centre of storm, barometer . . . . . | 29·94 |
| Bombay, 240 miles distant from centre of storm, barometer. . . . . | 29·70 |
| Dodabetta, 196 miles distant from centre of storm, barometer . . . . | 21·984 |
| Cannanore, 130 miles distant from centre of storm, barometer . . . . | 29·78 |
| Ship Buckinghamshire, 20 miles distant from centre of storm, barometer | 28·35 |
| Ship in centre of the storm, barometer . . . . . | 28·00 |

At the centre of the storm, distant from Cannanore 130 miles, the difference of pressure therefore was 1·78; at Dodabetta, at 8642 feet above the sea, and 196 miles from the Buckinghamshire, the greatest difference on the 17th, 18th, or 19th of April from the mean pressure of the month, was less than two-tenths of an inch, as the following records at Dodabetta show:—

| 1847. April 17. | | April 18. | | April 19. | | Mean pressure of month of April. | |
|---|---|---|---|---|---|---|---|
| Barometer. | Oscillation. | Barometer. | Oscillation. | Barometer. | Oscillation. | Barometer. | Oscillation. |
| 21·917 | ·058 | 21·984 | ·064 | 22·034 | ·044 | 22·097 | ·062 |

*And although the wind at Dodabetta on the* 17*th and* 18*th blew from the east round to the west with a maximum pressure of* 35 *and* 22 *lbs., and with a mean pressure for the two days of* 21 *and* 14 *lbs.; and though ten inches of rain fell on the* 18*th, the daily atmospheric tides were neither suppressed, inverted, nor interrupted, and scarcely differed from the daily mean oscillation of the month.* Sufficient instances have thus been

adduced of the comparatively narrow area of very great barometrical depressions, and the annual ranges given in the preceding Table may for the present be considered normal conditions, at least at Madras.

The following Table gives the monthly means of the diurnal oscillation of the barometer at Dodabetta, together with the monthly and annual range of the barometer, and the monthly fall of rain:—

Barometer at Dodabetta, at 8640 feet above the level of the sea.

| | Barometer. Monthly means. | | Difference. | Maximum. | Minimum. | Extreme monthly range. | Rain. |
|---|---|---|---|---|---|---|---|
| | 9h 40′ A.M. | 3h 40′ P.M. | | | | | |
| 1847. | in. | in. | | in. | in. | | |
| February | 22·129 | 22·068 | ·061 | 22·165 | 22·014 | ·151 | 7·43 |
| March | 22·160 | 22·105 | ·055 | 22·218 | 22·064 | ·154 | 3·61 |
| April | 22·128 | 22·066 | ·062 | 22·199 | 21·888 | ·311 | 19·80 |
| May | 22·087 | 22·024 | ·063 | 22·169 | 21·930 | ·239 | 4·86 |
| June | 21·992 | 21·940 | ·052 | 22·069 | 21·800 | ·269 | 4·55 |
| July | 22·000 | 21·949 | ·051 | 22·032 | 21·889 | ·143 | 7·41 |
| August | 22·030 | 21·976 | ·054 | 22·090 | 21·898 | ·198 | 9·32 |
| September | 22·031 | 21·977 | ·054 | 22·100 | 21·876 | ·224 | 7·52 |
| October | 22·086 | 22·014 | ·072 | 22·129 | 21·958 | ·171 | 12·49 |
| November | 22·117 | 22·038 | ·079 | 22·152 | 21·966 | ·186 | 11·85 |
| December | 22·073 | 22·013 | ·060 | 22·150 | 21·921 | ·229 | 12·28 |
| 1848. | | | | | | | |
| January | 22·113 | 22·050 | ·063 | 22·163 | 22·016 | ·147 | 0·12 |
| Year | 22·079 | 22·019 | ·060 | 22·218 | 21·800 | ·418 | 101·24 |

*Horary Oscillations.*

It is thus shown that the mean daily range for the year is 0·060, and in no month of the year did it exceed 0·079 in. This is different from Mahabuleshwur, Poona, Madras and Bombay. At Mahabuleshwur, at 4500 feet, the mean diurnal oscillation for ten months, by simultaneous observations, was 0·0694, and in no month did the monthly mean exceed 0·0835. At Poona, at 1823 feet, for 1827, it was 0·1009, for 1828 it was 0·1075, and for 1829 it was 0·0991; but this last diminished oscillation is partly to be attributed to three months' observations having been taken at an elevation of 4000 feet above the sea; but in 1830 the barometers were stationed for the whole year at Poona, at 1823 feet, and the mean diurnal fall of the barometer from 9—10 A.M. to 4—5 P.M. was 0·1166; the mean of the four years was 0·1060. The greatest *mean* diurnal range for any month in those four years was 0·1616 in the month of December 1827. At Madras hourly observations were recorded from the years 1842 to 1845, both inclusive, and for ten months in 1841, of which I shall not take any account, as the year is incomplete. The mean monthly fall of the barometer from 9h 41m A.M. to 3h 41m P.M. daily, was respectively 0·124, 0·120, 0·122 and 0·121, exhibiting a singular uniformity, the differences being only in the thousandths of an inch of pressure. This uniformity is equally marked in the successive months of the several years, and I have gone through the labour of working out the details to show it, the Madras printed observations being a record of facts only without deductions or comment.

## Mean Diurnal Horary Oscillations.

| | Madras. | | | | Bombay, 35 feet. | | Calcutta, 18 feet. | | Deccan, about 1800 feet. | | | Poona, 1823 feet. | Mahabuleshwur, 4500 feet. | | Dodabetta, 8640 feet. |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | 1842. | 1843. | 1844. | 1845. | 1843. | 1844. | Means. 1829–31. | 1848. | 1827. | 1828. | 1829. | 1830. | 1828–29. | Means, 15 years. | 1847–48. |
| January ..... | 0·120 | 0·105 | 0·114 | 0·111 | 0·112 | 0·120 | 0·123 | 0·142 | 0·113 | 0·148 | 0·125 | 0·136 | 0·073 | 0·158 | 0·063 |
| February ... | 0·119 | 0·121 | 0·119 | 0·120 | 0·114 | 0·112 | 0·117 | 0·147 | 0·125 | 0·150 | 0·108 | 0·140 | 0·066 | 0·087 | 0·061 |
| March ..... | 0·126 | 0·127 | 0·128 | 0·125 | 0·113 | 0·123 | 0·125 | 0·121 | 0·124 | 0·112 | 0·102 | 0·133 | 0·082 | 0·094 | 0·055 |
| April ..... | 0·134 | 0·133 | 0·134 | 0·138 | 0·119 | 0·118 | 0·124 | 0·131 | 0·083 | 0·133 | 0·098 | 0·143 | 0·083 | 0·092 | 0·062 |
| May ..... | 0·126 | 0·111 | 0·121 | 0·120 | 0·110 | 0·098 | 0·115 | 0·131 | 0·062 | 0·083 | 0·093 | 0·132 | 0·075 | 0·085 | 0·063 |
| June ..... | 0·126 | 0·119 | 0·118 | 0·120 | 0·074 | 0·071 | 0·095 | 0·094 | 0·090 | 0·100 | 0·073 | 0·106 | 0·052 | 0·062 | 0·052 |
| July ..... | 0·135 | 0·129 | 0·126 | 0·118 | 0·034 | 0·063 | 0·090 | 0·094 | 0·048 | 0·047 | 0·065 | 0·075 | 0·055 | 0·017 | 0·051 |
| August ..... | 0·131 | 0·127 | 0·129 | 0·139 | 0·087 | 0·070 | 0·099 | 0·103 | 0·060 | 0·070 | 0·086 | 0·085 | 0·053 | 0·043 | 0·054 |
| September ... | 0·124 | 0·134 | 0·131 | 0·128 | 0·086 | 0·097 | 0·101 | 0·105 | 0·081 | 0·091 | 0·077 | 0·090 | ..... | 0·073 | 0·054 |
| October ..... | 0·123 | 0·115 | 0·123 | 0·122 | 0·108 | 0·122 | 0·110 | 0·113 | 0·114 | 0·110 | 0·111 | 0·125 | ..... | 0·130 | 0·072 |
| November ... | 0·108 | 0·110 | 0·111 | 0·103 | 0·119 | 0·127 | 0·107 | 0·125 | 0·144 | 0·127 | 0·106 | 0·125 | 0·080 | 0·152 | 0·079 |
| December ... | 0·116 | 0·110 | 0·108 | 0·107 | 0·116 | 0·122 | 0·114 | 0·129 | 0·161 | 0·114 | 0·133 | 0·110 | 0·073 | 0·082 | 0·060 |
| Year ..... | 0·124 | 0·120 | 0·122 | 0·121 | 0·099 | 0·095 | 0·110 | 0·097 | 0·102 | 0·109 | 0·099 | 0·116 | 0·069 | 0·089 | 0·060 |

*Note.*—The above means are the daily fall of the barometer from 9 to 10 A.M. to 4 to 5 P.M.

At Madras the mean daily oscillation would appear to have been least when the barometer was highest in November, December, or January; and the reverse of this was the case when the barometer was lowest in May, June and July. The *mean* of the four years, at Madras, in the months of highest pressure, December and January, is 0·111, and the mean of the four years in the months of least pressure 0·122. The mean daily oscillation therefore was greatest when the pressure of the atmosphere was least. The same was not observed to be the case in the observations made in the Dukhun in the years 1827, 1828, 1829 and 1830; the means for the two periods being 0·131 and 0·081; nor in Calcutta in the years 1829, 1830 and 1831, the oscillations being respectively 0·118 and 0·100; and in 1848 the difference was more marked, the means of the daily oscillation for the periods of greatest and least annual pressure being 0·135 and 0·106: the same was the case at Bombay and at Dodabetta. This peculiar feature exhibited at Madras is not satisfactorily explained by its not being subjected, like Calcutta and Bombay, to the south-west monsoon, because the general curve of pressure at Madras follows the order of pressure at Calcutta and Bombay, with the exception of the month of November in the years 1844 and 1845, when the mean monthly pressure was greater in that month than in December. The hourly observations at Madras were too systematically and apparently accurately taken to suppose there could have been inaccuracy in the records, and they are quite as trustworthy, if not more so, than any other meteorological records in India. There appears a great discrepancy in the mean daily range at Madras and Bombay in the months from March to November, particularly in the month of April, which does not belong to the monsoon of either place. In the other months, the small range at Bombay may be accounted for by the prevalence of the monsoon at Bombay and the absence of the monsoon at Madras, but the means of the daily range for the year indicate a greater oscillation at Madras than might have been expected.

*Times of ebb and flow of the Atmospheric Tides, or Turning-points.*

I have given separately the chief of the four daily tides, namely, the fall between 9—10 A.M. to 4—5 P.M., to facilitate comparison of the movements of the same tide at different places by simple inspection. The following Table gives the movements of the three other daily tides; but I have confined it to the Madras records, as three daily movements for various places could not have been put conveniently into juxtaposition.

Monthly means of the Daily Atmospheric Tides between the hours $3^h\ 41^m$—$4^h\ 41^m$ P.M. to $9^h\ 41^m$—$10^h\ 41^m$ A.M.

| | Madras, 1842. | | | Madras, 1843. | | | Madras, 1844. | | | Madras, 1845. | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | $3^h\ 41^m$–$4^h\ 41^m$ P.M. to $9^h\ 41^m$–$10^h\ 41^m$ P.M. | $9^h\ 41^m$–$10^h\ 41^m$ P.M. to $3^h\ 41^m$–$4^h\ 41^m$ A.M. | $3^h\ 41^m$–$4^h\ 41^m$ A.M. to $9^h\ 41^m$–$10^h\ 41^m$ A.M. | $3^h\ 41^m$–$4^h\ 41^m$ P.M. to $9^h\ 41^m$–$10^h\ 41^m$ P.M. | $9^h\ 41^m$–$10^h\ 41^m$ P.M. to $3^h\ 41^m$–$4^h\ 41^m$ A.M. | $3^h\ 41^m$–$4^h\ 41^m$ A.M. to $9^h\ 41^m$–$10^h\ 41^m$ A.M. | $3^h\ 41^m$–$4^h\ 41^m$ P.M. to $9^h\ 41^m$–$10^h\ 41^m$ P.M. | $9^h\ 41^m$–$10^h\ 41^m$ P.M. to $3^h\ 41^m$–$4^h\ 41^m$ A.M. | $3^h\ 41^m$–$4^h\ 41^m$ A.M. to $9^h\ 41^m$–$10^h\ 41^m$ A.M. | $3^h\ 41^m$–$4^h\ 41^m$ P.M. to $9^h\ 41^m$–$10^h\ 41^m$ P.M. | $9^h\ 41^m$–$10^h\ 41^m$ P.M. to $3^h\ 41^m$–$4^h\ 41^m$ A.M. | $3^h\ 41^m$–$4^h\ 41^m$ A.M. to $9^h\ 41^m$–$10^h\ 41^m$ A.M. |
| Jan. | +0·078 | −0·063 | +0·105 | +0·080 | −0·069 | +0·094 | +0·078 | −0·060 | +0·096 | +0·079 | −0·062 | +0·094 |
| Feb. | +0·091 | −0·068 | +0·096 | +0·084 | −0·058 | +0·095 | +0·072 | −0·049 | +0·095 | +0·083 | −0·063 | +0·100 |
| March | +0·100 | −0·064 | +0·090 | +0·094 | −0·058 | +0·091 | +0·092 | −0·055 | +0·091 | +0·097 | −0·071 | +0·099 |
| April | +0·113 | −0·056 | +0·077 | +0·103 | −9·059 | +0·089 | +0·103 | −0·048 | +0·072 | +0·116 | −0·046 | +0·075 |
| May | +0·114 | −0·064 | +0·076 | +0·096 | −0·065 | +0·080 | +0·110 | −0·059 | +0·070 | +0·100 | −0·053 | +0·073 |
| June | +0·106 | −0·046 | +0·064 | +0·098 | −0·052 | +0·073 | +0·090 | −0·038 | +0·066 | +0·105 | −0·043 | +0·058 |
| July | +0·113 | −0·046 | +0·068 | +0·103 | −0·043 | +0·076 | +0·106 | −0·052 | +0·072 | +0·102 | −0·039 | +0·057 |
| Aug. | +0·110 | −0·054 | +0·075 | +0·095 | −0·046 | +0·078 | +0·107 | −0·048 | +0·070 | +0·106 | −0·036 | +0·069 |
| Sept. | +0·108 | −0·059 | +0·075 | +0·101 | −0·039 | +0·072 | +0·104 | −0·048 | +0·075 | +0·105 | −0·044 | +0·067 |
| Oct. | +0·101 | −0·058 | +0·080 | +0·087 | −0·058 | +0·087 | +0·097 | −0·058 | +0 084 | +0·093 | −0·050 | +0·079 |
| Nov. | +0·085 | −0·063 | +0·086 | +0·091 | −0·070 | +0·089 | +0·086 | −0·059 | +0·087 | +0·096 | −0·075 | +0·083 |
| Dec. | +0·087 | −0·063 | +0·092 | +0·086 | −0·067 | +0·091 | +0·091 | −0·070 | +0·087 | +0·086 | −0·048 | +0·089 |
| Means | +0·1005 | −0·0587 | +0·082 | +0·0932 | −0·0577 | +0·0846 | +0·0947 | −0·0537 | +0·0804 | +0·0973 | −0·0525 | +0·0786 |

A close inspection of the hourly observations upon which the above Table of means is founded, shows that the tides turn occasionally on consecutive days at different hours, and the intervals between the maxima and minima in the several diurnal tides frequently vary from five hours to seven hours in the duration of each tide; and not less frequently it is found that at the turning-point or turn of the tide, there is no movement of the atmosphere at all

for an hour to an hour and a half; nevertheless the *monthly means* of the same tide for successive years are almost identical; take for instance the *rising* afternoon tide from 3—4 P.M. to 10 or 11 P.M. in the month of January, and it is seen that the means in the successive four years were ·078, ·080, ·078 and ·079, so that the daily irregularities were merged in the monthly means. Similarly, the rising tide from $3^h\ 41^m$—$4^h\ 41^m$ A.M. to $9^h\ 41^m$—$10^h\ 41^m$ A.M. in the month of February was ·096, ·095, ·095 and ·100 in successive years. The falling night-tide between P.M. and A.M. does not exhibit quite the same regular features; for instance, in the month of March we have ·064, ·058, ·055 and ·071. November also has ·063, ·070, ·059 and ·075; but the annual means of each tide, as in the great diurnal tide, remarkably approximate to each other in successive years, as is shown by the Table, which is worked out from the Madras hourly observations. Another feature exhibited by the Table is the alteration in the range of the monthly means of the diurnal movement of the same tide in different months of the year, the increment and decrement alternating at different seasons of the year with the increment and decrement of another of the tides; for instance, in the month of January throughout the four years the rising tide from $3^h\ 41^m$—$4^h\ 41^m$ P.M. to $9^h\ 41^m$—$10^h\ 41^m$ P.M. is LESS than the rising tide from $3^h\ 41^m$—$4^h\ 41^m$ A.M. to $9^h\ 41^m$—$10^h\ 41^m$ A.M.; but the reverse of this takes place as the year advances, and in April the P.M. *rising* tide is considerably greater than the A.M. rising tide, and this continues until November, when the previous relations return. The same remarks do not apply to the two *falling* tides, as the falling tide by day is invariably greater (more than double) than that of the falling tide by night.

In my paper on the Atmospheric Tides of the Deccan, I gave a Table (No. 3) of the anomalies in the period of the ebb and flow of the different tides in 1830, and to enable me to do this I had observed the barometer every five minutes about the period of the expected turn of the tide. The anomalies were numerous. In the Madras hourly observations the same anomalies are observable, as the intervals of maxima and minima vary from five hours to eight hours, although the absolute time of the turn of the tide within the hour is not shown. Dr. BUIST's observations in Bombay for 1843 and 1844 are also hourly, and exhibit the same occasional irregularities in the time of the tides turning as at Poona and Madras. The recent observations at Calcutta do not afford the means of detecting this no doubt existing fact; for observations at Calcutta are not recorded by night at all, and only every two hours during the day. A bare inspection of and reliance upon the Calcutta monthly tables therefore would justify the assertion that the daily maxima and minima in the oscillations of the barometer occurred at fixed hours, which, although generally true, is not absolutely so. The observations at Dodabetta were unfortunately not made hourly, with the exception of those for twenty-four hours between the twenty-first and twenty-second days of each month; the means of comparison therefore of the diurnal hourly oscillations with those of Madras and Bombay, are limited to those twenty-four hours in each month; but although so limited, features of interest are exhibited. It has hitherto I believe been supposed that the two ascending and two descending diurnal

tides of the atmosphere within the tropics, *although turning after a longer or shorter interval in each tide, were never interrupted or retrograde in the onward or backward movement of each tide.* The Dodabetta hourly observations indicate that such is not the case, and I have thrown the facts into a table for a comprehensive view of them.

Movements of the Atmosphere in twenty-four hours in each month (21st to 22nd) of the year 1847–48 at Dodabetta, at 8640 feet above the sea.

| | Hours. | | | | | | | | | | | | | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | A.M. | | | P.M. | | | | | | | | | | | | A.M. | | | | | | | | | |
| | 10 | 11 | Noon. | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | Midnight. | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 |
| Feb. | ..... | ... | ... | ... | ... | −·060 | −·052 | −·052 | −·050 | ..... | ... | +·086 | +·086 | ..... | ..... | −·050 | −·030 | ±·032 | ±·032 | ..... | ..... | ... | ... | +·129 |
| March | +·310 | ... | ... | ... | ... | −·250 | ±·269 | −·260 | ..... | ..... | ... | ..... | ..... | +·320 | ..... | ..... | −·238 | ±·244 | −·228 | | | | | | |
| April | +·130 | ... | ... | ... | ... | ..... | −·078 | ..... | ..... | ..... | ... | +·118 | +·118 | ..... | ..... | ..... | ..... | ..... | −·048 | | | | | | |
| May | ..... | ... | ... | ... | ... | ..... | −·953 | ±·970 | −·964 | +·974 | ... | ..... | +·018 | ..... | ..... | ..... | ..... | −·960 | ..... | ..... | ..... | ... | ... | +·012 |
| June | +·962 | ... | ... | ... | ... | ..... | ..... | −·882 | ..... | ..... | ... | ..... | +·944 | ..... | ..... | ..... | ..... | ..... | −·880 | ±·804 | −·880 | | | |
| July | +·026 | ... | ... | ... | ... | ..... | −·960 | ..... | ..... | ..... | ... | ..... | +·015 | ..... | ..... | −·968 | ±·970 | ..... | −·950 | | | | | | |
| Aug. | ..... | ... | ... | ... | ... | ..... | −·022 | ..... | ..... | ..... | ... | ..... | +·073 | ..... | ..... | ..... | −·030 | −·030 | −·030 | ..... | ..... | ... | ... | +·084 |
| Sept. | ..... | ... | ... | ... | ... | ..... | −·988 | ..... | ..... | ..... | ... | ..... | ..... | +·042 | ..... | ..... | ..... | −·998 | ..... | ..... | ..... | ... | ... | +·072 |
| Oct. | +·128 | ... | ... | ... | ... | −·028 | ..... | ..... | ..... | ..... | ... | +·040 | ..... | ..... | ..... | ..... | ..... | −·040 | | | | | | |
| Nov. | ..... | ... | ... | ... | ... | ..... | ..... | −·056 | ..... | ..... | ... | ..... | +·100 | ..... | ..... | ..... | ..... | −·058 | ..... | ..... | ..... | ... | ... | +·133 |
| Dec. | +·120 | ... | ... | ... | ... | ..... | −·036 | ..... | ..... | ..... | ... | +·090 | ..... | ..... | ..... | ..... | ..... | −·034 | −·034 | | | | | |
| Jan. | ..... | ... | ... | ... | ... | ..... | ..... | −·035 | ..... | ..... | ... | +·078 | +·078 | ..... | −·058 | ±·062 | −·042 | −·036 | −·036 | −·028 | ..... | ... | ... | +·114 |

\+ Indicates the maximum tide. — Indicates the minimum tide. ± Indicates an interruption to usual rise or fall.

The barometer ranged between 21·800 and 22·218 inches.

*Observations on Horary Oscillations.*

It is hence seen that in the month of March the diurnal tide, which usually falls from 10 A.M. until 4 P.M., turned at 3 P.M., and should then have gradually risen until 9—10 P.M., instead of which it rose only until 4 P.M. and then fell until 5 P.M., when it turned again and ran its usual course. In the same month the A.M. tide, which usually falls from 10 P.M. until 4 A.M., had its fall interrupted at 2 A.M. and rose until 3 A.M., when it turned and fell to its ordinary minimum, and then gradually rose until 10 A.M. In the month of May the daily minimum occurred at the proper hour, 4 P.M., and its ordinary regular rise continued until 5 P.M.; but at this hour it changed and fell until 6 P.M., but at that hour resumed its usual course. The other tides were free from these aberrations, but two of them turned at 3 and 9 A.M. instead of 4 and 10 A.M. In the month of June the flow is irregular in the 4 A.M. tide. Its minimum occurs properly at 4 A.M., and it rises until 5 A.M., but at this hour it has turned, instead of continuing to rise, and falls until 6 A.M., when the barometer is as low as at 4 A.M.,—a solitary instance within the year. In the month of January 1848, the falling tide from 10 P.M. goes on regularly until midnight, when it turns and rises until 1 A.M.; it then turns again in the proper direction, but instead of stopping at 4 A.M., the minimum hour, it continues until 5 A.M. and then turns. An inspection of the Table shows that the barometer never appeared to remain stationary at the turning hour of the maximum A.M. (9—10) tide, but that in the months of January, February and April, no movement of the tide took place for a full hour at the 9—10 P.M. maximum tide. In August, although the other tides flowed as usual, that of the A.M. period remained stationary from 2—4 A.M., both inclusive. The maximum A.M. tide occurred six times in six months of the year at 9 A.M., and six times in the other six months at 10 A.M. The maximum nocturnal tide took place only twice at 11 P.M., thrice at 9 P.M., five times at 10 P.M., and thrice was stationary between 9 and 10 P.M. The minimum diurnal tide turned once only at 6 P.M. The chief irregularities appear to have been in the A.M. minimum nocturnal tide, embracing the hours from 1—6 A.M. On looking over the Madras hourly observations for four years for the twenty-four hours between the 21st and 22nd of each month in the year 1842, there are *only two instances of similar irregularities*. On the 22nd of March in the falling A.M. tide at $2^h\ 41^m$ A.M., the barometer stood at 29·859, and at $3^h\ 41^m$ A.M., instead of continuing to fall, it had risen to 29·869, but at $4^h\ 41^m$ it resumed its regular course and fell to 29·865. On the 22nd of November an irregularity occurred in the nocturnal P.M. tide. At $10^h\ 41^m$ the barometer stood at 30·004; at $11^h\ 41^m$ it had fallen in due course to 29·991, but at $12^h\ 41^m$ it had risen to 29·992, and only at $1^h\ 41^m$ resumed its usual ebb, and fell to 29·981. In the year 1843 there are also *only two instances* of irregularity in the specified days; namely, on the 21st of August in the A.M. falling tide. At $1^h\ 41^m$ A.M. the barometer stood at 29·722; at $2^h\ 41^m$, instead of falling, it rose to 29·725, then fell, at $3^h\ 41^m$, to 29·724; then rose, at $4^h\ 41^m$, to 29·726, and continued regular to the maximum period at 9 A.M. On the 21st of December, at $11^h\ 41^m$

P.M., the barometer was 30·121; at $12^h\ 41^m$, instead of continuing to fall, it had risen to 30·125, but then changed; and at $2^h\ 41^m$ it was 30·104, and fell regularly till $3^h\ 41^m$ A.M., when it was at its minimum, 30·089. On the 21st of September, in 1843, the minimum A.M. nocturnal tide occurred at $1^h\ 41^m$ A.M. instead of $3^h\ 41^m$, at which hour it took place on the morning of the 22nd; the interval, therefore, between the minimum of this A.M. nocturnal tide and the maximum of the 9—10 morning tide, was seven hours, the maximum occurring at $8^h\ 41^m$, a very rare instance of the continued flow of this A.M. tide, which usually runs its course within four or five hours, and on rare occasions in three hours; the change of pressure, however, was only equal to 0·114, from 29·763 to 29·877. In 1844 there is *but one instance* of irregularity within the prescribed hours. On the 22nd of September, at $12^h\ 41^m$ A.M., the barometer stood at 29·820; at $1^h\ 41^m$ it had fallen as usual to 29·808, but at $2^h\ 41^m$ it had risen to 29·819; at $3^h\ 41^m$ to 29·833; but at $4^h\ 41^m$ it had fallen to 29·832, and then continued regular. In 1845 there is also *only a solitary instance* on the 21st of March. At $7^h\ 41^m$ A.M. the barometer stood at 29·933; at $8^h\ 41^m$ it had fallen, instead of rising, to 29·932, but at $9^h\ 41^m$ resumed its usual course. It will be remarked that at Madras there is *not a single instance* of irregularity in four years in the fall of the great diurnal tide from 9—10 A.M. to 4—5 P.M., and the instances of irregularities in the other tides only serve to prove that the laws are not without exceptions. From the above comparisons it is seen that the irregular movements in the tides were not common to Dodabetta and Madras at simultaneous periods of time, nor at proximate periods of time. The irregularities in the intervals of the different tides are numerous, as are also the instances of stationary periods in which the atmosphere appears to be quiescent from one to two hours. It now remains to notice the deviations from the usual laws at Bombay, as recorded by Dr. Buist in his Bombay hourly observations for 1843 and 1844. On the 21st of January, at 3 A.M., the barometer stood at 29·864, at 4 A.M. at 29·865; but at 5 A.M., instead of continuing to rise, it had fallen to 29·863, and continued to fall until 6 A.M., when it stood at 29·856; at 7 A.M. it resumed its usual course, and continued to rise until the maximum hour. At Madras, on the same day, making allowance for the difference of longitude, *nothing of the kind occurred.* At Bombay, on the 21st of March, at 11 P.M., the barometer stood at 29·688; but at midnight, instead of continuing to fall, it had risen to 29·699, and it was only at 1 A.M. it resumed its ebb. *There was nothing of the kind at Madras*, where the maximum, 29·861, was attained at $10^h\ 41^m$ with the ordinary regularity. On the 22nd of May, at Bombay, there were irregularities in all the tides, a thing so unusual, and not occurring at all on the 20th or 23rd of May, as to render the table apocryphal, either from error in the record or in the lithography; the A.M. falling tide stops at 2 A.M., then rises to 8 A.M., falls to 9 A.M., and then rises to 10 A.M., its maximum, however, being at 8 A.M. From 4 P.M. the tide as usual rises to 6 P.M., then falls to 8 P.M., and afterwards proceeds to attain its maximum at 11 P.M. Something similar occurs between 1 and 5 A.M. on the 21st of June, but not on the 22nd. *Nothing of the kind occurs at Madras, either on the*

*20th, 21st, 22nd or 23rd of May.* The last irregularity to be noticed at Bombay, within the limit hours, was on the 21st of October. At midnight the barometer stood at 29·803; at 1 A.M. it had risen in the usual course to 29·887, but at 2 o'clock it had fallen to 29·881, and only resumed its ordinary rise at 3 A.M.; as far as the record goes, there does not appear to have been any irregularity at Madras*. Similar instances occur within the limit hours in 1844,—on 21st of January at 3 A.M., 21st of May at 1 A.M., when the tide remained stationary at $3^h\ 41^m$, and 5 A.M., and at 1 A.M. on the 22nd of December. In September the maximum horary pressure occurred at $11^h\ 30^m$ A.M., and in other months several times at 11 A.M.

If we extend our comparisons to Aden, on the coast of Arabia, nearly in the latitude of Madras, but 35° 6′ of longitude to the west of Madras, we find the very same exceptions to normal conditions. Dr. BUIST has been kind enough to transmit to me proof sheets, now going through the press, of part of a meteorological journal kept at Aden for 1847 and 1848. Hourly observations were taken on certain term-days monthly; instead of taking up the whole of these term-days, it will suffice to select those of January and June of each year, these being months in which the maximum and minimum pressure of the atmosphere usually occur in India. Barometer 187 feet above the sea at Aden. All corrections made.

| | Hours. | | | | | | | | | | | | | | | | | | | | | | | Means. |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | P.M. | | | | | | | | | | | | A.M. | | | | | | | | | | | |
| January, 1847. | Noon. | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | |
| 15 | 29·760 | ... | ... | ·743 | ... | ... | ... | ... | ... | ·821 | ... | ... | ·778 | ·780 | ... | ·770 | ... | ... | ... | ... | ... | ·853 | ... | ... | ... | 29·790 |
| 25 | 29·684 | ... | ... | ·661 | ... | ... | ... | ·717 | ... | ... | ... | ... | ... | ... | ... | ·646 | ... | ... | ... | ... | ... | ·743 | ... | ... | ... | 29·691 |
| 30 | 29·763 | ... | ... | ·716 | ... | ... | ... | ... | ... | ... | ·786 | ... | ... | ... | ... | ·722 | ... | ... | ... | ... | ·808 | ... | ... | ... | ... | 29·760 |
| June, 1847. | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 8 | 29·648 | ... | ... | ·557 | ... | ... | ... | ... | ... | ... | ·637 | ... | ... | ... | ... | ·583 | ... | ... | ... | ... | ... | ·698 | ... | ... | ... | 29·614 |
| 16 | 29·582 | ... | ... | ·488 | ·488 | ... | ... | ... | ·542 | ... | ... | ... | ... | ... | ... | ·507 | ... | ... | ... | ... | ... | ·613 | ... | ... | ... | 29·533 |
| 20 | 29·631 | ... | ... | ·502 | ... | ... | ... | ·574 | ... | ... | ... | ... | ... | ... | ... | ·506 | ... | ... | ... | ... | ... | ·620 | ... | ... | ... | 29·552 |
| 29 | 29·490 | ... | ... | ... | ·385 | ... | ... | ... | ... | ·484 | ... | ... | ... | ... | ... | ·431 | ... | ... | ... | ... | ... | ·548 | ... | ... | ... | 29·468 |
| January, 1848. | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 7 | 29·856 | ... | ·810 | ... | ... | ... | ... | ... | ... | ·921 | ... | ... | ·858 | ·864 | ... | ·844 | ... | ... | ... | ... | ·914 | ... | ... | ... | ... | 29·876 |
| 14 | 29·868 | ... | ... | ·835 | ... | ... | ... | ... | ... | ... | ·902 | ... | ... | ... | ... | ·860 | ... | ... | ... | ... | ·915 | ... | ... | ... | ... | 29·874 |
| 24 | 29·791 | ... | ... | ·732 | ... | ... | ... | ... | ... | ... | ·807 | ... | ... | ... | ... | ·733 | ... | ... | ... | ... | ·853 | ... | ... | ... | ... | 29·781 |
| 28 | 29·774 | ... | ·730 | ·730 | ... | ... | ... | ... | ... | ... | ·814 | ... | ... | ... | ... | ·761 | ... | ... | ... | ... | ... | ·853 | ... | ... | ... | 29·781 |
| June, 1848. | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 8 | 29·497 | ... | ... | ·416 | ... | ... | ... | ... | ... | ... | ·507 | ... | ... | ... | ·395 | ... | ... | ... | ... | ... | ·532 | ... | ... | ... | ... | 29·460 |
| 15 | 29·546 | ... | ... | ·481 | ... | ... | ... | ... | ·549 | ... | ... | ... | ... | ... | ... | ·479 | ... | ·572 | ·563 | ... | ... | ... | ·609 | ... | ... | 29·533 |
| 21 | 29·522 | ... | ... | ·382 | ·382 | ... | ... | ... | ·469 | ·446 | ·466 | ·462 | ... | ... | ... | ·377 | ... | ... | ... | ... | ... | ·567 | ... | ... | ... | 29·456 |
| 29 | 29·651 | ... | ... | ·542 | ... | ... | ... | ... | ... | ·599 | ... | ... | ... | ... | ... | ·544 | ... | ... | ... | ... | ·673 | ... | ... | ... | ... | 29·589 |

A glance of the eye over the above Table shows the turning-points of the several tides and their irregularities. The first marked feature is the almost constant turning of the descending P.M. tide and ascending A.M. tide at 3 P.M. and 3 A.M., instead of at 4 or 5 P.M. and A.M., as on the continent of India; to this there are only five

* In a diagram of the comparative readings of seven barometers at Bombay, between the 20th and 21st of June 1843, these anomalies appear to have occurred between 2 and 3 P.M., 7 and 8 P.M., 10 and 11 P.M. and 1 to 4 A.M., but the barometers did not exactly harmonize in their movements.

exceptions to the former and only one to the latter; but two of the exceptions are remarkable, the tide having turned on the 7th and 28th of January 1848, at 2 P.M. I do not recollect a single case of the kind in the records in India. In the first of these cases the tide flowed from 2 until 9 P.M., seven hours; and in the second it remained stationary from 2 until 3 P.M., and then flowed until 10 P.M.; this portion of the diurnal movement of the atmosphere occupying eight hours instead of six. As a contrast to these lengthened periods, we find that the 3 P.M. ascending tide, on the 25th of January and 20th of June 1847, flowed only from 3 P.M. until 8 P.M., five hours instead of eight. On the 15th of January 1848, the ascending A.M. tide did not attain its maximum until 11 A.M., but this retardation was probably owing to an inversion in the flow at 7 A.M.; the pressure, instead of increasing at this hour, having diminished from 29·572 at 6 A.M. to 29·563, but after this interruption the usual increase took place up to 11 A.M. It will be seen that there are two instances of a stationary state of the barometer on the 28th of January 1848, from 2 to 3 P.M., and on the 21st of June 1848, from 3 to 4 P.M. Meteorologists know that this circumstance, which would excite no attention without the tropics, is of rare occurrence within the tropics. The next great feature in this Table is the absence of any retrograde movement in the P.M. descending and ascending tides; but this is not the case with the other two tides; as at Dodabetta, several interruptions in the flow or ebb are recorded. In the descending nocturnal A.M. tide there are three instances. On the 15th of January 1847, at 1 A.M., the tide has risen from midnight instead of continuing to fall. Precisely the same thing occurs on the 7th of January 1848, at the same hours. On the 21st of June the interruption occurs at an earlier hour. The pressure is at its maximum at 9 P.M.; it then diminishes until 10 P.M., but instead of continuing to diminish it increases until 11 P.M., but at midnight has resumed its usual course. In the A.M. ascending tide there is only one instance of inversion; on the 15th of June 1848, the usual rise stops at 6 A.M. and retrogrades until 7 A.M., it then resumes its usual flow and continues until 11 A.M., a very unusual hour for the period of the maximum of the A.M. tide. Had the term-days of the other months been noticed, numerous instances of deviations from normal conditions could have been given. *It would be desirable to ascertain whether these aberrations have any relation with changes in the electrical tension in the atmosphere.*

If these anomalies be tested by a comparison with hourly readings of the barometer, at Aden CORRECTED FOR THE TENSION OF VAPOUR*, for four days in each month of the year 1847, not only is their occurrence rendered unquestionable, but new phases in abnormal conditions appear. Annexed is a Table of the "Means" of hourly readings of the barometer in four days in each month at Aden in 1847, CORRECTED FOR MOISTURE.

* Corrected by the observer.

## Means of the Hourly Readings of the Barometer at Aden for 1847, corrected for Moisture.

| | Noon. | P.M. 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | A.M. 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | Means. |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Jan. | 28·969 | ... | ·954 | ..... | ... | ... | ... | ... | ... | 29·018 | ..... | ..... | ..... | 28·973 | ... | ..... | ..... | ... | ..... | ... | ... | ... | 29·063 | ... | ... | 28·996 |
| Feb. | 29·118 | ·121 | ... | ..... | ... | ... | ... | ... | ... | ..... | 29·171 | ..... | ..... | ..... | ... | 29·110 | ..... | ... | ..... | ... | ... | ... | 29·188 | ... | ... | 29·132 |
| March | 29·051 | ... | ... | ·005 | ... | ... | ... | ... | ... | ..... | ·081 | ..... | ..... | ..... | ... | ..... | 30·020 | ... | ..... | ... | ... | ·103 | ..... | ... | ... | 29·052 |
| April | 28·914 | ... | ... | ..... | ·867 | ... | ... | ·896 | ·878 | ..... | ·904 | ..... | ..... | ..... | ... | ·870 | ..... | ... | ..... | ... | ... | ... | ·931 | ... | ... | 28·893 |
| May | 28·729 | ... | ... | ·643 | ... | ... | ... | ·691 | ·686 | ..... | ·717 | ..... | ..... | ..... | ... | ..... | ·667 | ... | ·739 | ·722 | ... | ... | ·738 | ... | ... | 28·702 |
| June | 28·679 | ... | ... | ..... | ·550 | ... | ·634 | ·684 | ... | ·654 | ·634 | ·664 | ..... | ..... | ... | ..... | ..... | ·554 | ..... | ... | ... | ... | ·667 | ... | ... | 28·624 |
| July | 28·655 | ... | ... | ..... | ... | ·715 | ... | ... | ... | ..... | ..... | ..... | ..... | ·590 | ·599 | ·591 | ..... | ... | ·667 | ·613 | ... | ... | ·656 | ... | ... | 28·639 |
| Aug. | 28·709 | ·707 | ... | ..... | ... | ... | ... | ·777 | ·747 | ·758 | ..... | ·695 | ·744 | ·727 | ·714 | ·717 | ·704 | ·676 | ..... | ... | ... | ... | ·836 | ... | ... | 28·735 |
| Sept. | 28·739 | ·784 | ... | ·733 | ... | ·762 | ·746 | ... | ... | ·765 | ..... | ..... | ..... | ·715 | ... | ..... | ..... | ... | ·775 | ·751 | ... | ·760 | ..... | ... | ... | 28·748 |
| Oct. | 29·011 | ... | ... | 28·933 | ... | ... | ... | ... | ... | ..... | 29·051 | 29·032 | 29·068 | ..... | ... | 29·031 | ..... | ... | 29·166 | ... | ... | ... | ..... | ... | ... | 29·032 |
| Nov. | 29·195 | ... | ... | ·135 | ... | ... | ... | ... | ... | ..... | ·309 | ..... | ..... | ·252 | ·252 | ..... | ..... | ... | ·311 | ... | ... | ·262 | ·269 | ... | ... | 29·239 |
| Dec. | 29·259 | ... | ... | ·174 | ... | ... | ... | ... | ... | ..... | ·292 | ..... | ..... | ..... | ... | ·240 | ..... | ... | ..... | ·280 | ·275 | ... | ·307 | ... | ... | 29·253 |

It has been asserted that when the barometer is corrected for moisture its diurnal movements in the tropics are resolvable into a simple ascending and descending curve in the twenty-four hours, nevertheless the first feature of the Table is the existence of two ascending and two descending tides, although the correction for moisture had reduced the air in which the mercurial column had moved to a supposed dry state. The usual hours of the ebb and flow are generally sufficiently manifest, particularly in the hours of greatest pressure, yet there is the unusual circumstance of the ascending A.M. tide turning in five months at 6 A.M. instead of 9—10 A.M., and in this tide also there are three instances of a check to its usual movements. The ascending P.M. tide has also its anomalies. In eight months it attained its maximum at the usual time between 9 and 10 P.M., but in July there is the rare circumstance of its turning at 5 P.M. instead of 9—10 P.M., and in June and August the equally rare circumstance of its turning at 7 P.M.; the next anomaly in this tide is in October, when it did not turn until midnight. The chief anomalies, as at Madras, Bombay and Dodabetta, occur in the A.M. and P.M. ebb or descending tide. The Table shows that the turning-points of the P.M. diurnal ebb, ranged from noon in February, and July, to 4 P.M. in April and June. In February, when the minimum occurred at noon, the maximum took place at the usual hour, 10 P.M.; there was therefore the almost unprecedented circumstance *of a tide continuing to flow for nine hours*. In the A.M. descending or ebb tide, the anomalies are even more marked than in the corresponding P.M. tide, for the turning-points range from 1 A.M. to 5 A.M. In January it turned at 1 A.M., and then the ascending tide continued to flow uninterruptedly until 10 A.M., a second instance of a *nine hours' flow*. In July, September and November, it also turned at 1 A.M., but the maximum occurred at 6 A.M. instead of 10 A.M., the flow in each of these months being five hours! a glance of the eye over the Table will show; although the different tides ultimately attained their respective maxima and minima, yet in many instances they were subject to checks or interruptions, which appeared to give way after a short resistance to the periodic movements of the atmosphere. In the month of August, however, the atmosphere appeared in so vacillating and disturbed a state, that the only tide which turned at the normal hour was the 10 A.M. maximum tide. The means of the hourly readings on four days in each month, corrected for moisture, give a mean curve of pressure in each month which nearly corresponds with the curve of pressure of the daily readings of the barometer corrected for temperature only. The maximum pressure with both corrections occurs in December, but the minimum occurs in June corrected for temperature and in July with both corrections. The whole of the facts connected with the meteorology of Aden of which I have made use, are from observations taken by Sergeant Moyes, with excellent instruments, and Dr. Buist is now passing the observations through the press.

These facts, which could be very greatly multiplied, have been somewhat dwelt upon, with a view to a right understanding of Humboldt's observations in his Cosmos*,

* Bohn's Edition, vol. i. p. 320.

where, speaking of the horary oscillations of the barometer, he says, "their regularity is so great, that in the day-time especially, the hour may be ascertained from the height of the mercurial column without error, on the average of fifteen or seventeen minutes. In the torrid zones of the new continent, on the coasts, as well as at elevations of nearly 13,000 feet above the level of the sea, where the mean temperature falls to 44°·6, I have found the regularity of the ebb and flow of the aërial ocean undisturbed by storms, hurricanes, rain and earthquakes." It is now shown that the horary oscillations have a different range in different months of the year; their range is influenced by height above the sea, and the tides do not always flow and ebb in equal periods of time; but the existence of two ascending and two descending but unequal tides within twenty-four hours within the tropics, is established beyond all question; and if not altogether *undisturbed*, as HUMBOLDT says, by storms, hurricanes or rain, yet the meteorological records in India prove that the periodic daily movements of the aërial ocean are never suppressed*.

*Pressure of the Atmosphere.*

With respect to the mean pressure of the atmosphere in India near the sea-level, I shall limit myself to the insertion of a comparative *table* showing the means of four years' hourly observations at Madras, the means of two years' hourly observations at Bombay, and the observations taken every two hours (but during the day only) at Calcutta, for 1843–44 and 1848. I append however curves of pressure at these places projected for longer periods, and for which I am indebted to Dr. BUIST, LL.D. The barometers at these respective localities, being each only a few feet above the sea-level, should have differed from each other in their mean annual results only in the third place of decimals, or at most only slightly in the second place of decimals, nevertheless the pressure at Bombay differs from that at Madras a twentieth of an inch; and at Calcutta, where the barometer is 17 feet nearer the mean sea-level than at Bombay, the mean annual pressure is even less than at Bombay, while on the other hand the pressure at Aden reduced to the sea-level is greater than anywhere else. These discrepancies originate probably in the neglect of using previously compared instruments. At Madras, the annual means in successive years differ from each other only in hundredths of an inch. For the mean pressure at different elevations tables are annexed.

* The observations of Lieut. R. STRACHEY in Thibet, at 18,400 feet above the sea, show that on the 22nd and 23rd of August 1849, the following were the oscillations of the four tides:—

| | B. uncorrected for temperature. | B. corrected for temperature. |
|---|---|---|
| 5 P.M. to 11 P.M. | +·059 | +·075 |
| 11 P.M. to 4 A.M. | −·033 | −·029 |
| 4 A.M. to 10 A.M. | +·043 | +·016 |
| 10 A.M. to 3 P.M. | −·037 | −·032 |

Monthly Mean Pressure of the Atmosphere, reduced to 32°.

| | Madras. | | | | Bombay, 35 feet. | | Calcutta, 16 feet. | | Aden, 127 feet. | | Poona, 1823 feet. | Mahabuleshwur, 4500 feet. | | Dodabetta, 8640 feet. | Royal Observatory, Greenwich, 159 feet. |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Years .... | 1842. | 1843. | 1844. | 1845. | 1843. | 1844. | 1848. | 1843, 1844. | 1847. | 1848. | 1830. | 1828, 1829. | Means of 1 year. | 1847, 1848. | Means of 6 years, 1841 to 1846. |
| January. | 29·995 | 29·985 | 29·998 | 30·015 | 29·923 | 29·947 | 30·000 | 29·937 | 29·774 | 29·872 | 28·087 | 25·465 | 25·737 | 22·081‡ | 29·766 |
| February | 29·972 | 29·966 | 29·980 | 29·965 | 29·889 | 29·928 | 29·980 | 29·915 | 29·832 | 29·853 | 28·002 | 25·452 | 25·765 | 22·098 | 29·737 |
| March... | 29·860 | 29·886 | 29·907 | 29·924 | 29·839 | 29·869 | 29·838 | 29·793 | 29·770 | 29·783 | 27·952 | 25·576 | 25·688 | 22·132 | 29·750 |
| April ... | 29·805 | 29·864 | 29·809 | 29·818 | 29·813 | 29·804 | 29·716 | 29·656 | 29·690 | 29·711 | 27·907 | 25·538 | 25·667 | 22·097 | 29·708 |
| May ... | 29·713 | 29·692 | 29·700 | 29·712 | 29·662 | 29·750 | 29·636 | 29·563 | 29·635 | 29·584 | 27·846 | 25·467 | 25·643 | 22·055 | 29·785 |
| June ... | 29·664 | 29·709 | 29·668 | 29·705 | 29·654 | 29·628 | 29·516 | 29·184 | 29·545 | 29·511 | 27·768 | 25·377 | 25·664 | 21·966 | 29·797 |
| July ... | 29·697 | 29·709 | 29·723 | 29·726 | 29·661 | 29·648 | 29·526 | 29·517 | 29·491 | 29·475 | 27·766 | 25·319 | 25·600 | 21·974 | 29·799 |
| August.. | 29·729 | 29·759 | 29·731 | 29·742 | 29·730 | 29·701 | 29·571 | 29·516 | 29·540 | 29·483 | 27·840 | 25·387 | 25·647 | 22·003 | 29·787 |
| Sept. ... | 29·768 | 29·788 | 29·793 | 29·830 | 29·779 | 29·795 | 29·713 | 29·662 | 29·639 | 29·626 | 27·925 | ..... | 25·524 | 22·004 | 29·809 |
| October | 29·873 | 29·863 | 29·868 | 29·850 | 29·845 | 29·835 | *29·881 | 29·633 | 29·811 | 29·745 | 27·923 | ..... | 25·810 | 22·050 | 29·858 |
| Nov. ... | 29·941 | 29·926 | 29·963 | 29·984 | 29·887 | 29·934 | 30·005 | 29·867 | 29·897 | 29·855 | 28·018 | †25·500 | 25·733 | 22·077 | 29·714 |
| Dec. ... | 30·001 | 30·001 | 29·926 | 29·965 | 29·961 | 29·893 | 30·021 | 29·951 | 29·902 | 29·876 | 28·068 | †25·498 | 25·739 | 22·043 | 29·857 |
| Means of year | 29·8515 | 29·8457 | 29·839 | 29·853 | 29·805 | 29·809 | 29·783 | 29·707 | 29·711 | 29·698 | 27·925 | ..... | 25·684 | 22·046 | 29·781 |

The mean monthly pressure at Calcutta for 1843–44 is from reductions of Dr. M'Clelland, and the record commences in November 1843 and ends in October 1844. An inspection of the above Table shows that the maximum mean monthly pressure does not occur in the same month in successive years. At Madras, in 1842 and 1843, the maximum pressure was in the month of December, in the two following years it was in the month of January. At Bombay, in 1843, the maximum was in December, in 1844 in January, at Calcutta, in 1843, in December, and in 1848 it was in December. At Madras the minimum monthly mean pressure, in three years out of the four, occurred in the month of June. In 1843 it was in the month of May, but at Bombay in the same year in June: at Bombay and Calcutta in 1844, and in 1848, at Calcutta, it took place also in June. At Poona, at 1823 feet, the maximum was in January and the minimum in July. At Dodabetta, at 8640 feet, unlike any of the stations at the sea-level, the maximum mean monthly pressure took place in March: the same thing occurred at Mahabuleshwur § in 1828–29, at 4500 feet above the sea; but like the other stations the minimum pressure at Dodabetta occurred in June, but at Mahabuleshwur in July. Dr. Buist of Bombay mentions that for three years at Aden (1846–48) the minimum occurred in July, and the maximum in February, but by the preceding Table the maximum in 1847 and 1848 occurred in December, and the minimum in both years in July. At Greenwich the means of thirty years' observations, recorded in Belville's Manual, give results inverse to those in India, as the maximum pressure is in June and the minimum in November; but there is a second maximum in January and a second minimum in March; but the greatest *daily* mean pressure occurs about the 9th of January, and

* Thirteen days' observations wanting.

† For 1828, remaining months for 1829.

‡ For 1848, remaining months for 1847.

§ The means of one year's pressure at Mahabuleshwur is inserted from the Bombay Medical Journal, but the observations do not appear to have been corrected for temperature, and as the maximum pressure is represented to occur in October and the minimum in September, there evidently must be some mistake, and I therefore only notice my own simultaneous observations with Dr. Walker for 1828–29.

the minimum daily mean depression at the end of November. From the means of eight years' observations, obligingly furnished to me by Mr. Glaisher, from the Royal Observatory, Greenwich, the maximum was in October; with a second maximum in December, the minimum was in April; corrected however for the tension of vapour, the maximum was in December and the minimum in August; but consecutive years differ greatly when the vapour correction is applied.

I attempt no explanation of these anomalies, as much more lengthened observations are required than those at my disposal afford for philosophical deductions. From the month of the maximum pressure, there is a gradual mean monthly decline of pressure until the minimum pressure; then there is a gradual monthly increase of pressure, even when the monsoon sets in at Madras in October until the maximum is attained again; but there is no rule without an exception, and the curve was interrupted in the month of December in the years 1844 and 1845 at Madras, and in 1844 at Bombay; but in Calcutta, in October 1844, and at Mahabuleshwur, and at Dodabetta in December 1828 and 1847 respectively. At Aden, in 1847, it was interrupted in February. In 1848 the curve was regular.

Appended to this paper are annual pressure curves at Madras, Bombay and Calcutta, protracted from the records of the barometer at the several places. The three localities are under very different conditions of temperature and moisture in the same months, and they differ considerably in latitude and longitude; Madras and Bombay, situated upon opposite sides of the peninsula of India, are subject to different monsoons; Madras to the N.E. monsoon, which commences in October and ends in February, and Bombay is subject to the S.W. monsoon, which commences in June and ends in October. Calcutta is under the full influence of the S.W. monsoon, but has occasional showers from the Madras rains. When Bombay is deluged with rain Madras is comparatively dry, and the hot weather prevails; and when Madras is under the influence of the Coromandel rains, Bombay is cold and dry. Very different atmospheric conditions therefore exist at the two places in the same months. Nevertheless the annual curves of pressure protracted from monthly means, may be said to be identical, not only for Madras and Bombay, but also for Calcutta. The few exceptional cases are lost or disappear in the means, and may originate in local causes. It would thus appear that the periodic movements of the *mass* of the atmosphere within the northern tropic are independent of, or only very slightly affected by, the hygrometric and thermometric conditions of the *lower strata of the atmosphere*. It occurs to me that this phenomenon may be owing to the sun's place in the ecliptic. When the sun is at the southern tropic, the air above the northern tropic is comparatively cold and therefore dense, and at its greatest pressure; this would be from December to January inclusive. As the sun returns to the north the air gets gradually warmer and dilates, and the pressure being inversely as the volume, the barometer gradually sinks, until the sun is returning from the northern tropic again, when the mass of the atmosphere gradually cools, gets denser, and the pressure gradually increases again. Supposing this explanation to have any foundation in truth, the curve of pressure within the tropic south of the equator would be the reverse of that in the tropic north of the equator. The maximum pressure would be from June to July inclusive,

and the minimum pressure from December to January inclusive. On referring to the St. Helena observations for 1843 this is very nearly the case, the maximum pressure and minimum temperature being in August instead of July, and the minimum pressure and maximum temperature in February to March instead of January.

Meteorological Observations at St. Helena, 1843.

| | Barom. in. | Therm. ° |
|---|---|---|
| January . . . | 28·238 | 64·76 |
| February . . . | 28·214 | 66·25 |
| March . . . . | 28·214 | 65·35 |
| April . . . . | 28·251 | 64·93 |
| May . . . . . | 28·292 | 61·53 |
| June . . . . | 28·335 | 58·88 |
| July . . . . . | 28·341 | 57·43 |
| August . . . . | 28·358 | 56·71 |
| September . . . | 28·328 | 56·92 |
| October . . . | 28·279 | 57·23 |
| November . . . | 28·250 | 59·54 |
| December . . . | 28·251 | 62·44* |

From the occurrence of the maxima and minima of the horary oscillations of the barometer at the same *local hours* in different meridians, these phenomena also would seem to be connected with the sun's action upon the atmosphere.

In the fitful movements of the atmosphere beyond the northern tropic the sun's influence would not appear to be similarly felt, as the maximum pressure at Greenwich is in October, with a second maximum in December, and the minimum pressure, instead of being when the sun is at the northern tropic, is in November.

*Temperature.*

The hourly observations at Madras for four years afford the most complete and trustworthy data for determining at that place the fluctuations of temperature, the exact diurnal and annual range, and the exact periods of the fluctuations in the occurrence of the maxima and minima, which cannot be satisfactorily shown by any observations short of hourly record. For Bombay I have only such records made by Dr. Buist for the years 1843 and 1844. Those at Calcutta were two-hourly only during the daytime, and those at Dodabetta were made but twice a day, with the exception of twenty-four hours once a month between the 21st and 22nd, when the observations were taken hourly. For exact determinations I am constrained to abandon many proposed comparisons, and in many instances to use less frequently recorded observations to express general features. The following Table shows the monthly means and annual temperatures at Madras and Bombay from hourly observations. For the other localities the means are derived from less frequent observations, and are therefore only approximations to the truth.

* The above table is confirmed by the Mauritius and Cape observations; the minimum pressure being from January to February inclusive, and the maximum July to September inclusive.

## Monthly Mean Temperatures at Madras and Bombay from Hourly Observations, and at Calcutta and elsewhere from less frequent periods of record.

| | Madras. | | | | Bombay, 35 feet. | | Calcutta, 18 feet. | | | | Aden, 187 feet. | Phultoon, about 1700 feet. | Bijapoor, about 1700 feet. | Poona, 1823 feet. | Sattarah, 2320 feet. | Mahabuleshwur, 4500 feet. | | | Mercara, Coorg, 4500 feet. | Uttra Mullay, 4500 feet. | | Dodabetta, 8640 feet. |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | 1842. | 1843. | 1844. | 1845. | 1843. | 1844. | 1845. | 1846. | 1847. | 1848. | 1848. | 1847. | 1848. | 1830. | Means of 1844–47. | 1828–29. | 1834. | 1829 to 1843. | Means of 1838–40. | 1845. | 1846. | 1847–48. |
| Jan. | 76°·98 | 77°·59 | 75°·71 | 76°·81 | 76°·4 | 74°·9 | 76°·52 | 75°·72 | 75°·95 | 73°·70 | 72°·6 | 74°·8 | 78°·7 | 75°·4 | 70°·0 | 65°·38 | 65°·70 | 64°·0 | 66°·6 | 62°·08 | 63°·42 | 52°·20 |
| Feb. | 77·92 | 77·90 | 77·74 | 79·41 | 78·1 | 76·0 | 78·55 | 76·78 | 76·08 | 80·20 | 73·4 | 76·9 | 75·3 | 78·85 | 72·6 | 68·30 | 67·50 | 66·3 | 70·80 | 64·25 | 65·75 | 52·30 |
| March | 82·36 | 81·52 | 82·20 | 83·13 | 79·9 | 79·3 | 89·05 | 87·85 | 87·90 | 88·08 | 76·8 | 83·9 | 84·8 | 85·9 | 77·8 | 74·68 | 74·00 | 71·5 | 73·7 | 69·58 | 65·58 | 54·55 |
| April | 85·67 | 85·19 | 86·34 | 86·58 | 84·3 | 83·9 | 87·97 | 91·85 | 88·60 | 88·08 | 80·6 | 83·9 | 88·4 | 87·95 | 80·6 | 75·71 | 74·40 | 74·5 | 73·1 | 68·42 | 67·83 | 56·20 |
| May | 88·09 | 85·02 | 86·98 | 88·63 | 85·9 | 85·7 | 90·67 | 88·67 | 89·93 | 91·80 | 84·8 | 86·1 | 88·5 | 86·70 | 80·1 | 74·79 | 73·90 | 72·4 | 71·9 | 67·83 | 65·33 | 57·20 |
| June | 88·05 | 85·52 | 88·58 | 86·64 | 85·4 | 85·0 | 88·12 | 87·00 | 87·50 | 89·85 | 85·5 | 81·2 | 85·0 | 83·65 | 77·0 | 68·08 | 66·30 | 66·3 | 69·1 | 65·08 | 62·33 | 52·50 |
| July | 86·68 | 85·79 | 85·76 | 86·12 | 83·1 | 81·8 | 86·25 | 86·88 | 85·88 | 86·03* | 83·4 | 80·2 | 81·2 | 76·95 | 73·8 | 65·43 | 64·90 | 63·2 | 67·1 | 66·00 | 63·83 | 52·65 |
| Aug. | 84·45 | 84·51 | 85·25 | 85·88 | 81·1 | 81·4 | 85·20 | 86·28 | 85·82 | 85·18* | 81·5 | 79·3 | 78·7 | 76·85 | 73·0 | 64·60 | 65·30 | 63·2 | 66·0 | 66·66 | 64·42 | 53·10 |
| Sept. | 82·36 | 84·26 | 82·97 | 83·91 | 81·2 | 80·5 | 87·70 | 85·35 | 85·66 | 86·10* | 84·9 | 78·9 | 78·2 | 78·35 | 74·0 | 64·34 | 65·00 | 63·9 | 65·6 | 67·50 | 64·92 | 52·45 |
| Oct | 81·86 | 80·72 | 80·53 | 82·95 | 82·3 | 83·4 | 85·30 | 83·70 | 84·58 | 83·55* | 83·4 | 80·0 | 76·6 | 80·65 | 76·1 | 65·68 | 65·50 | 66·6 | 66·8 | 65·58 | 63·42 | 53·30 |
| Nov. | 78·27 | 77·83 | 79·17 | 79·11 | 80·2 | 80·4 | 80·42 | 80·65 | 77·88 | 78·50* | 78·5 | 73·5 | 76·7 | 77·15 | 72·0 | 64·76 | 63·50 | 64·4 | 66·5 | 65·58 | 63·92 | 52·15 |
| Dec. | 76·57 | 75·89 | 76·94 | 77·70 | 76·6 | 79·3 | 73·55 | 73·08 | 73·28 | 75·30* | 77·2 | 72·9 | 79·2 | 75·05 | 71·8 | 63·56 | 62·30 | 63·2 | 64·4 | 63·50 | 63·17 | 50·80 |
| Year | 82·44 | 81·81 | 82·35 | 83·07 | 81·2 | 80·9 | 84·11 | 83·65 | 83·26 | 83·86 | 80·2 | 79·2 | 81·7 | 80·28 | 75·0 | 67·52 | 67·30 | 66·60 | 68·6 | 66·00 | 64·49 | 53·20 |

* Means of two-hourly observations. The mean temperature at Madras, in 1848, was 83°·15, and the curve the same as that of the preceding years. Sattarah is in Lat. 17° 40′. Long. 74° 2′. Mercara is sixty-five miles E. of Cannanore. Uttray Mullay, twenty-two miles N.E. by E. from Trevandrum. The mean temperature at Mahabuleshwur, from 1829 to 1843, was deduced from the *mean* of a daily maximum and minimum thermometer in the shade.

The first feature is the close approximation of the annual means at Madras for the four years; the difference between the greatest and least being only 1°·26 FAHR., although the difference between the means of the same month in successive years may have exceeded three degrees. Nevertheless the means of most of the months in successive years show a great amount of uniformity. The coldest months are December or January, and the hottest May or June. In 1842 and 1843 December was the coldest month. In 1844 and 1845 January was the coldest. In 1842 and 1845 May was the hottest month. In 1843 the maximum mean heat was not reached until July, and in 1844 it occurred in June. Although these discrepancies occur, the monthly increment or decrement to or from the maximum period is gradual, and rarely checked or inverted. In Bombay the annual mean temperature for 1843 is almost identical with that of Madras for 1843, although the two places differ 5° 41′ in latitude. The monthly means of the two places correspond tolerably well from January until July; for instance, February corresponds within a tenth of a degree, and June within two-tenths. But in July there is a difference of 3°·79, August 3°·31, September 3°·16, Madras being plus: then the sign changes and Bombay becomes plus for the remaining months of the year, and also in January. The coldest month in Bombay was January, and the hottest May. In Bombay, in 1843 and 1844, unlike Madras, there is an inversion in the decrement of heat on the sun's going south; for October is represented as hotter than September in both years: a very remarkable fact is exhibited by these hourly means, *namely, that neither the south-west monsoon at Bombay, nor the north-east monsoon at Madras, at all affect the monthly mean regular increment or decrement of heat*, with the exception of October in Bombay. It will be observed that the maximum heat, both at Madras and Bombay, was not when the sun was vertical at either place passing to the northern tropic; but when the sun was near to the northern tropic in June, the mean temperature in 1843 at Madras, in lat. 13° 4′, was at its maximum in July, while at Bombay, in lat. 18° 55′, the greatest heat was in May of that year; and though the sun passes over both places again to the south the mean temperature gradually declines in each year, with the exceptions noticed. I was desirous of inserting in the Table of Mean Temperatures those for 1843 and 1844 at Calcutta, for comparison with the Madras and Bombay observations for the same year; but on referring to the volumes of the Bengal Asiatic Researches for 1843 and 1844, I found that the tables had not been inserted. They were met with however in the Journal of the Horticultural Society of Calcutta, but proved to be records of the temperature during the day only at 9½ A.M., noon, 4 P.M. and sunset*. A mean temperature from such data would neces-

* In the fifth volume of the Calcutta Journal of Natural History, Dr. M'CLELLAND states that the mean temperature of 1844, from daily observations, was 82°·35, the coldest period at sunrise, and the hottest at 2h 40m P.M. daily; the maximum heat 104° on the 10th of April, the minimum 51°·7 on the 19th of January, and the annual range 52°·3. He speaks also of the minimum daily pressure of the barometer occurring twice at 6 P.M. in January, February and May.

sarily be unsatisfactory. In 1847 meteorological tables appear in the Journal of the Asiatic Society of Bengal from the same source as those used by the Horticultural Society in the preceding years, namely, from the office of the Deputy Surveyor-General in Calcutta, but they were even of less use than the preceding tables, for they had but two daily records, namely, at 9½ A.M. and 4 P.M., and the records were otherwise useless for determining the absolute range of the thermometer, as there was only a record of the maximum temperature and no minimum. In 1848 more elaborate tables make their appearance, containing two-hourly records from sunrise to sunset, at sunrise, 9½ A.M., noon, $2^h\ 40^m$ P.M., 4 P.M., and sunset, together with the indications of a maximum and minimum thermometer, but without any observations after sunset. This is an improvement upon the former records, but falls short of the requisites for scientific purposes. The maximum and minimum thermometer certainly gives the range of temperature, but does not give the hours of the occurrence of the maxima and minima. Mean temperatures deduced from a maximum and minimum thermometer may possibly be true; but an arithmetical mean from two extreme observations daily would be incorrect, unless the increment and decrement of heat from a mean point were regular, which is known to be rarely the case. Annual mean temperatures deduced from formulæ, of which the latitude is the element, are often fallacious; for independently of the great discrepancies in mean temperatures between America and Europe on the same parallels of latitude, and as indicated also by isothermal lines in Europe, there are places differing little in longitude where the annual mean temperature is higher than at places nearer to the equator, both within and without the tropics: taking an instance from Dove's temperature tables, we have the following:—

| | | | |
|---|---|---|---|
| 1 | Aberdeen . | Latitude 57° 9′ | Mean temperature 49°·18 |
| 2 | Dundee . . | Latitude 56 27 | Mean temperature 51·94 |
| 3 | Edinburgh . | Latitude 55 58 | Mean temperature 47·13 |
| 4 | Liverpool . | Latitude 53 25 | Mean temperature 50·80 |
| 5 | London . . | Latitude 51 30 | Mean temperature 50·83, or 49·7 by Glaisher. |

Aberdeen, therefore, nearly six degrees north of London, has almost the same mean temperature as London: and Edinburgh, intermediate between both, has a lower mean temperature than either. Dundee, five degrees north of London, has absolutely a higher mean temperature; and Liverpool, two degrees north of London, has the same mean temperature. In the tropics similar instances are found.

| | | | |
|---|---|---|---|
| Calcutta . . . . . | Latitude | 22° 34′ 40″ | Mean temperature 83°·72 |
| Bombay . . . . . | Latitude | 18 55 42 | Mean temperature 81·1 |
| Madras . . . . . | Latitude | 13 4 10 | Mean temperature 82·42 |
| Aden . . . . . | Latitude | 12 46 26 | Mean temperature 80·2 |

In this case Calcutta, 9 degrees north of Madras and 3⅓ of Bombay, has a higher mean temperature than either; and Aden, in a lower latitude than any of the places,

instead of a higher has a lower mean temperature than Calcutta, Bombay or Madras. This mean temperature at Madras and Bombay is deduced from hourly observations; and had Dove's previously noticed mean temperature been derived from similar records, the anomalies might have been modified or have disappeared altogether. With the reservations contingent upon the explanations given, I shall comprise my observations upon the temperature tables of places other than those for Madras and Bombay, within very narrow limits. And first, with respect to Calcutta, the means are derived from observations taken at the Surveyor-General's office, with excellent instruments, but the observations are day observations, and it is only for the last six months of 1848 that records were made every two hours. The means, however, of those six months correspond sufficiently near with those of the same six months in the three preceding years to show that the conversion of three-hourly observations into two-hourly observations, had very little effect upon the mean results. What was wanting were observations at night, and of these there are not any. The mean temperature of the years, from 1845 to 1848, both inclusive, never falls below 83°·26 (in 1847), and was as high as 84°·11 in 1845, and the mean temperature of the four years is 83°·72. The coldest month was December, excepting in 1848, when January was the coldest. The hottest month was May, excepting in 1846, when April was the hottest; the mean temperature of April and May, for the four years, being respectively 87°·12 and 90°·27. For the years 1846 and 1847 the mean monthly increment to the maximum heat, and mean monthly decrement to the minimum heat, is gradual and regular, but in 1845 and 1847 there are instances of inversion; in 1845 March is hotter than April; September is hotter than August; in 1848 September is also hotter than August, instead of being cooler. This very high mean temperature of Calcutta is not of ready explanation, even after making an allowance for the want of night observations: situated on a broad river, in the midst of cultivated, well-wooded and moist plains, and within the influence of the sea; on the verge of the northern tropic, it might have been supposed that its position, in respect to latitude, would have affected its mean temperature. The sun is vertical at Calcutta in the first week in June and July, but Calcutta attains its maximum heat in May, while the sun is yet approaching, and the mean temperature is actually diminishing, while the sun is passing and repassing from the tropic, and while the heat ought to be accumulating from the lengthened days, as is shown in the following tabular statement:—

| Latitude N. | Longitude E. | Sun vertical. | Longest day. |
|---|---|---|---|
| | | | h m |
| Calcutta ..... 22° 34′ 40″ | 88° 28′ 15″ | June 5—July 7. | 13 23 |
| Bombay ..... 18 55 42 | 72 54 24 | May 15—July 28. | 13 08 |
| Madras..... 13 4 10 | 80 21 35 | April 25—August 18. | 12 46 |
| Aden..... 12 46 26 | 45 15 0 | | |

Admitting that the lengthened time for which the sun is nearly vertical over Calcutta might raise the mean temperature of May, June and July, there would be a corresponding diminution in the months of December, January and February, in the long nights, and the mean temperature of the year should not be raised by the

great heats of April and May; but such, nevertheless, would not appear to be the case, at least in the absence of night observations. It will be remarked also, that the return of the sun over Bombay in July does not prevent a reduction of three degrees in mean temperature; this however might be attributed to the rains commencing; but in its passage over Madras in August the continued mean monthly fall of the thermometer is not interrupted, although it will be recollected there is not any monsoon at Madras in August to correct the effect of the sun's passage. The slanting rays of the sun, within certain angles of incidence without the tropics, produce a heat of great intensity, even where the physical characters of the country do not lead us to expect such a result; for instance, on the banks of the broad Indus in Scinde the thermometer is known to rise in the shade to 110°—120° Fahr. Recently, at Peshawur, the following is the record of the thermometer in a house from the 7th to the 14th of May 1849:—

| | Sunrise. | 8 A.M. | Noon. | 4 P.M. | 9 P.M. | Latitude N. |
|---|---|---|---|---|---|---|
| Highest ..... | 75° | 89° | 102° | 104° | 86° | 33° 59′ |
| Lowest ..... | 67 | 84 | 96 | 98 | 78 | |

On the 16th of June, at 4 P.M., thermometer 109°; on the 25th of July, 109°; August 3rd, 4th and 13th, 104°; the extremes being 67° and 104°, the mean 87°, and the range 37°. A register for the whole month, by Dr. J. Malcolmson, gives the following facts; the maximum being 109° on the 6th in a tent, and 106° on the 24th and 31st in a house.

Register of the Thermometer at Peshawur for May 1849.

| Fahrenheit Thermometer. In the shade in a house in the city. | | | | | | | |
|---|---|---|---|---|---|---|---|
| Date. | Sunrise. | Noon. | 4 P.M. | Date. | Sunrise. | Noon. | 4 P.M. |
| 1 | 63° | 79° | 66° | 17 | 70° | 98° | 104° |
| 2 | 65 | 73 | 66 | 18 | 73 | 99 | 100 |
| 3 | 64 | 87 | 91 | 19 | 81 | 97 | 103 |
| 4 | 63 | 75 | 85 | 20 | 80 | 102 | 105 |
| 5 | 61 | 96 | 91 | 21 | 83 | 99 | 105 |
| 6 | 64 | 102 | 109 | 22 | 91 | 102 | 105 |
| 7 | 90 | 100 | 104 | 23 | 85 | 100 | 104 |
| 8 | 67 | 108 | 99 | 24 | 88 | 98 | 106 |
| 9 | 70 | 107 | 101 | 25 | 82 | 99 | 105 |
| 10 | 70 | 104 | 100 | 26 | 85 | 99 | 104 |
| 11 | 65 | 102 | 95 | 27 | 84 | 99 | 104 |
| 12 | 70 | 106 | 106 | 28 | 84 | 97 | 103 |
| 13 | 70 | 107 | 104 | 29 | 85 | 99 | 104 |
| 14 | 71 | 100 | 101 | 30 | 84 | 99 | 105 |
| 15 | 90 | 106 | 98 | 31 | 88 | 102 | 106 |
| 16 | 70 | 104 | 105 | | | | |

Note by Dr. J. Malcolmson.—The register was kept in a house, and that may account for the maximum being no higher than 109°.

Heavy rain, with thunder, lightning and hail, for the first four days in the month. Winds generally westerly, and south-west. Severe dust-storms occasionally.

On the 22nd of May 1849, at Ferozepore, lat. 30° 53′, on the Sutlege river, the thermometer stood at 104° in a good house, the usual precautions being taken against the hot winds. Even in August, at Peshawur, with thunder-storms and heavy rain on the 7th, 9th, 15th, 16th, 17th, 20th and 29th, and with several light showers besides, the maximum was 104° at 4 P.M., the minimum at sunrise 81°, the midday maximum 101°, and with a *midnight* maximum of 100°, and yet the Report says, "The month had not however been characterized, as would be supposed by the indications of the thermometer, by any unusual degree of heat *over those which had just preceded it*. It even did not range so high as in May, June and July*."

Even at Alten, in Finmark in Norway, in latitude 69° 58′, where the mean annual temperature is between 35° and 36° FAHR., and where in 1846 the thermometer sunk to 14°·8 below zero; on the 27th of July 1847, at noon, the thermometer in the shade rose to 84°·7 FAHR. Capt. SCORESBY, in his Arctic Voyages, somewhere mentions, I think, that the rays of the sun were sufficiently powerful to melt the pitch on the sunny side of his vessel, while the air was at a freezing temperature on the shady side. But these intense heats of summer are compensated for by a depression of temperature when the sun is at the southern tropic and the mean annual temperature is not raised. The high mean temperature of Calcutta, therefore, would seem to be influenced by local causes, independently of the vertical or oblique action of the sun, or the length of time the sun is above the horizon. But the anomalies of mean temperature are not limited to Calcutta. Aden, situated in latitude 12° 46′ 26″ N., longitude 45° 15′ E., on the shores of Arabia,—shores dreaded for their supposed intolerable heat, has a mean temperature (80°·2) lower than that of Bombay, Madras or Calcutta, with a less range of the thermometer, with a maximum heat only of 89° in May and October, and a minimum of 68°·5 in January! and most singularly the mean temperature for *every month* in 1848 is lower than the temperature of the corresponding month at Calcutta, and, with the exception of November, December and January, lower than at Madras or Bombay. From the maximum mean monthly heat in April 1830, at Calcutta, the temperature gradually declined until the mean monthly minimum in December, excepting in September and October, when the curve was interrupted by a rise of 1°·5 in the former month, and of 2°·3 in the latter; after December the temperature gradually rose to its mean maximum.

* Dr. WALLIN of Helsingfors, the traveller in Arabia, has furnished me with a copy of his register of the thermometer, from which I learn that at Bagdad, lat. 33° 20′ N., long. 44° 24′ E., the thermometer in the shade of a house on the second story, with a N.W. aspect upon the banks of the Tigris, on the 19th of July 1848, at 2 P.M. stood at 122°·9 FAHR., wind W.N.W., on the 13th and 18th at 120°·2, and on seven other days in the month of July at 118°·4; and the *lowest* heat in the month at 2 P.M. was 101°·3 on the 2nd of July, wind N.W., clear.

*Curves of Temperature at High Levels.*

Proceeding from the sea-level to considerable altitudes, we find that the mean temperature at Poona, in 1830, at 1823 feet above the sea-level, was 80°·28, differing only six-tenths from the mean temperature of Bombay for 1844, and less than one degree of Fahr. from the mean temperature of 1843 at Bombay. A difference of level of 1823 feet therefore gave a difference of less than one degree of temperature.

The comparison of the temperatures of the three stations of Mahabuleshwur, Mercara in Coorg, and Uttray Mullay in Travancore, all at the height of 4500 feet above the sea-level, and differing little in longitude, but several degrees in latitude, affords some interesting facts. The latitude of Uttray Mallay is *about* 8° 00′ N., long. 76° 00′ E., Mercara, lat. 12° 30′, long. 73° 30′, Mahabuleshwur, lat. 17° 58′, long. 73° 29′. The mean temperature of Uttray Mullay, situated nearest to the equator, is *lower* by 3°·35 than the mean temperature of Mercara, and 2°·66 lower than that of Mahabuleshwur, while the mean temperatures of Mercara and Mahabuleshwur are almost identical. The maximum heat of Mahabuleshwur, in both years recorded, is in April, while the mean of three years at Mercara fixes it in March. At Uttray Mullay the maximum heat, in 1845, was in April, while in 1846 it was in March. At 4140 feet above these levels, namely, at Dodabetta, the maximum heat was, in May, as in Bombay and Calcutta. The minimum heat, at the height of 4500 feet, was in December, at Mahabuleshwur and Mercara in all the years. At Uttray Mullay, in 1845, the minimum mean monthly heat was in June, the only instance of the kind in all the observations discussed in this paper; and in this same year January and October had the same mean temperature. In the next year the minimum heat was in January. At Dodabetta, at 8640 feet, in 1847, the minimum temperature was in December, but, with the exceptions of April and May, the mean monthly range was so small that most of the months were nearly the same in their mean heat. Mahabuleshwur and Mercara being within the S.W. monsoon, while Uttray Mullay and Dodabetta are subject to both S.W. and N.E. monsoons, the annual curves of temperature might be expected to vary considerably. At Mahabuleshwur and Mercara there is a gradual decrement of heat from the maximum point until the month of October, when the mean monthly temperature rises at both places, but falls after that month to the minimum of the year. The same thing occurs in Bombay and Poona, but there is no rise in October at Madras nor at Calcutta in 1846 or 1847; and in 1845 and 1848, when the gradual decrement of heat was interrupted, it occurred in September instead of October, as at the other places within the influence of the same monsoon. At Uttray Mullay and Dodabetta, within the influence of both monsoons, we find the annual curve of temperature interrupted in the first place in March, then in July, October and November in 1845, and in July, August and September in 1846. At Dodabetta the increase is quite gradual from December to May; but the natural decrement is interrupted in July, and the temperature rises in August, sinks in September, rises in October, and then falls to the minimum of the year. From these facts, it appears that the two monsoons derange the

curves of temperature at the different places, which might be expected otherwise to coincide with the sun's path in the ecliptic; but further observations from the hill stations may modify these conclusions.

*Range of Temperature and Hours of Maxima and Minima.*

Unless where hourly observations are taken, the exact periods of the occurrence of the maxima and minima cannot be determined; and though a self-registering thermometer will determine the range of temperature, yet the hours of the turning-points cannot be learnt from it. For the hours of the occurrence of the maxima and minima, therefore, I am limited to the hourly observations taken at Madras and Bombay; but for the range of temperature, without reference to specific times, I can avail myself of a maximum thermometer registered at Aden for 1848, and one at Calcutta registered since June 1848.

*Madras.—Hours of Maximum and Minimum Temperature.*

The usual impression in India is, that the maximum heat occurs about 2 P.M., and the minimum a little after sunrise. The Madras hourly observations for four years, from which the following Table is prepared, exhibit great anomalies in the hours of the occurrence of the maxima and minima. In the forty-eight months of monthly range there are seventeen records of the greatest heat occurring about noon (between $11^h\ 41^m$ and $12^h\ 41^m$); eighteen records between 1 and 2 P.M., and thirteen records between 2 and 3 P.M. In 1842 the maximum daily heat occurred only *once* about noon ($12^h\ 41^m$) on the 20th of April ($96^{\circ}{\cdot}5$). In 1843 it occurred at the same hour, or before it, in January, February, March, May and November. In 1844, at the same hour, in January, April, November and December. In 1845, in March, April, May, September, October, November and December; so that in fact the maximum daily heat, although it took place only at noon in the month of April in 1842, in the other three years, either in one year or the other, occurred at noon in all the months. There is not a single instance of the maximum daily heat occurring after $2^h\ 41^m$ P.M. The minimum heat of the month, in 1842, occurred in May at $2^h\ 41^m$ A.M. ($81^{\circ}{\cdot}1$), the only record of the kind in the year. In 1843 there is no similar record, but in 1844 there are two instances of the least heat taking place in July and August at $41^m$ past midnight, and one instance at $2^h\ 41^m$ A.M. in September. In 1845 there is a solitary case of the lowest temperature at $2^h\ 41^m$ A.M. In the whole four years there are only three instances of the minimum heat being at $3^h\ 41^m$ A.M., two at $4^h\ 41^m$ A.M., twenty-five at $5^h\ 41^m$ A.M., and twelve at $6^h\ 41^m$ A.M.; and one singular instance of the greatest cold in the month being as late as $7^h\ 41^m$ A.M. on the 14th of May 1844. It may be affirmed, therefore, that the greatest cold occurs at Madras most often at $5^h\ 41^m$ A.M. The monthly range of the thermometer does not differ very much in the different months of the year, nor does the range of the

thermometer in the same months in successive years exhibit very marked discrepancies, although there are some differences; for instance, in February 1842 the range was 20°·8, and in February 1845 only 14°·2. In April 1842 the range was 22°·0, and in April 1843 only 14°·8. It might have been expected that the greatest range, as at Bombay and Calcutta, would have occurred in the coldest months, and that the greatest discrepancies would have occurred in the comparisons of the same months in succeeding years, but such was not the case. The greatest monthly range in any month at Madras, twice occurred in the month of May in 1844 and 1845, namely, 25°·9 and 25°·6 respectively. The least range, 12°·5, took place in January 1843. The annual ranges varied only from 27°·0 in 1843 to 37°·1 in 1844*. For Bombay I have only hourly readings of the thermometer for 1843 and 1844. The maximum heat twice occurred at noon, on the 11th of August and 6th of December; twice at 1 P.M., on 31st of March and 29th of April; five times at 2 P.M., and three times at 5 P.M. There is not any conformity in the times or dates of these maxima with those of the same year at Madras. A remarkable feature in the minimum daily heat at Bombay is the comparatively late period of the morning at which it took place. On the 4th of January the minimum heat was at 8 A.M., in five other months it occurred at 7 A.M., in two months at 6 A.M., and once only at 5 A.M.; and entirely unlike the numerous instances at Madras, there is not a single case of the minimum heat falling before 5 A.M. in 1843. The greatest range of the thermometer was in the cold months and least in the monsoon; the maximum, 19°·3, was in January, and the minimum, 8°·4, in August. The annual range for 1843 was 24°·4. In 1844 the chief feature is, that the minimum heat in the month occurred at midnight on the 28th of August, and the minimum temperature occurred at 1 and 2 A.M. on the 22nd of July, as well as at 5 A.M.; twice only the least heat occurred as late as 7 A.M.; the maximum heat never occurred after 3 or before 1 P.M. The maximum heat was 91°·9 and the minimum 64°·7, the annual range therefore 27°·2. The greatest monthly range was in February, 20°·7, and the least in August, 8°·5. The monthly ranges of the two years had a close correspondence. The maximum heat observed in the sun in Bombay was 142°·6 at 1 P.M., 10th of November 1846.

*Calcutta Range of Temperature.*

Hourly observations not having been taken at Calcutta, and the records of a maximum and minimum thermometer having only appeared in the Asiatic Journal since June 1848, I can only give the range of temperature since that date; but I know nothing of the days or hours of record, excepting what is derived from a foot-note at page 550 of the Number of the Journal for June 1848. As at Bombay, the greatest monthly range was in the cold months and least in the monsoon months. Two

* A memorandum just received gives the mean temperature of Madras for 1848 at 83°·15; the maximum on the 20th of June 106°, at $3^h\ 41^m$ P.M., and the minimum 63°·5 on January 26th, at $6^h\ 41^m$ A.M.; the annual range therefore was 42°·5.

[*To face page* 333]

## Range of Thermometer and Hours of oc

| | Madras, 1842. | | | | | | | Madras, 1843. | | | | | | | Madras, 1844. | | | | | | | Madras, |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | Minimum. | | | Maximum. | | | | Minimum. | | | Maximum. | | | | Minimum. | | | Maximum. | | | | Minimum. | | | |
| | Therm. | Hour. A.M. | Date. | Therm. | Hour. P.M. | Date. | Range. | Therm. | Hour. A.M. | Date. | Therm. | Hour. P.M. | Date. | Range. | Therm. | Hour. A.M. | Date. | Therm. | Hour. P.M. | Date. | Range. | Therm. | Hour. A.M. | Date. | Therm. |
| | ° | h m | | ° | h m | | ° | ° | h m | | ° | h m | | ° | ° | h m | | ° | h m | | ° | ° | h m | | ° |
| January | 69·5 | 6 41 | 6 | 85·1 | 1 41 | 27 | 15·6 | 70·5 | 5 41 | 5 | 83·0 | 0 41 | 4 | 12·5 | 66·2 | 6 41 | 24 | 82·8 | 0 41 | 27 | 16·6 | 68·2 | 6 41 | 23 | 84·3 |
| February | 67·2 | 5 41 | 17 | 88·0 | 2 41 | 28 | 20·8 | 69·2 | 6 41 | 9 | 85·4 | 0 41 | 19 | 16·2 | 67·7 | 5 41 | 19 | 87·2 | 1 41 | 26 | 19·5 | 71·8 | 5 41 | 28 | 86·0 |
| March | 72·4 | 6 41 | 10 | 92·0 | 1 41 | 20 | 19·6 | 74·1 | 3 41 | 16 | 89·8 | 0 41 | 26 | 15·7 | 72·0 | 6 41 | 10 | 90·7 | 1 41 | 25 | 18·7 | 73·6 | 5 41 | 7 | 92·3 |
| April | 74·5 | 5 41 | 1 | 96·5 | 0 41 | 20 | 22·0 | 78·5 | 4 41 | 9 | 93·3 | 1 41 | 30 | 14·8 | 77·2 | 5 41 | 8 | 99·0 | 0 41 | 3 | 21·8 | 78·5 | 6 41 | 30 | 94·0 |
| May | 81·1 | 2 41 | 1 | 100·8 | 2 41 | 31 | 19·7 | 76·2 | 5 41 | 23 | 93·8 | A.M. 11 41 | 1 | 17·6 | 77·4 | 7 41 | 14 | 103·3 | 1 41 | 5 | 25·9 | 78·8 | 4 41 | 6 | 104·4 |
| June | 78·8 | 5 41 | 12 | 100·2 | 2 41 | 21 | 21·4 | 78·7 | 3 41 | 14 | 95·4 | 1 41 | 9 | 16·7 | 80·3 | 3 41 | 16 | 103·2 | 1 41 | 11 | 22·9 | 78·8 | 2 41 | 18 | 101·0 |
| July | 79·1 | 5 41 | 5 | 98·6 | 1 41 | 10 | 19·5 | 78·7 | 5 41 | 31 | 95·5 | 2 41 | 21 | 16·8 | 77·8 | 0 41 | 21 | 96·2 | 2 41 | 8 | 18·4 | 79·3 | 5 41 | 20 | 97·7 |
| August | 75·6 | 6 41 | 19 | 94·8 | 2 41 | 1 | 19·2 | 78·2 | 5 41 | 28 | 95·3 | 1 41 | 7 | 17·1 | 78·1 | 0 41 | 6 | 95·3 | 1 41 | 23 | 17·2 | 79·0 | 5 41 | 19 | 97·1 |
| September | 75·7 | 6 41 | 12 | 92·5 | 1 41 | 6 | 16·8 | 76·9 | 6 41 | 28 | 95·3 | 2 41 | 1 | 18·4 | 75·4 | 2 41 | 18 | 94·7 | 2 41 | 9 | 19·3 | 76·2 | 5 41 | 16 | 94·8 |
| October | 74·2 | 5 41 | 25 | 90·5 | 2 41 | 3 | 16·3 | 72·9 | 5 41 | 23 | 87·5 | 2 41 | 23 | 14·7 | 73·5 | 5 41 | 24 | 88·5 | 2 41 | 25 | 15·0 | 75·3 | 5 41 | 27 | 91·5 |
| November | 71·0 | 5 41 | 21 | 84·6 | 1 41 | 2 | 13·6 | 69·4 | 5 41 | 29 | 85·2 | 0 41 | 1 | 15·8 | 70·9 | 5 41 | 19 | 86·0 | A.M. 11·41 | 8 | 15·1 | 70·3 | 5 41 | 26 | 88·2 |
| December | 68·5 | 6 41 | 12 | 82·8 | 1 41 | 25 | 14·3 | 68·0 | 5 41 | 31 | 82·5 | 1 41 | 8 | 14·5 | 69·6 | 6 41 | 3 | 83·5 | 0 41 | 2 | 13·9 | 70·0 | 5 41 | 18 | 83·5 |
| Year | 67·2 | 5 41 | ... | 100·8 | 2 41 | ... | 33·6 | 68·0 | 5 41 | ... | 95·5 | 2 41 | ... | 27·0 | 66·2 | 6 41 | ... | 103·3 | 1 41 | ... | 37·1 | 68·2 | 6 41 | ... | 104·4 |

[Lieut.-Colonel Sykes's Discussion of the Meteorological Observations taken in India.]

occasional Minima and Maxima.

| ra, 1845. | | | | Bombay, 1843. | | | | | | | | Bombay, 1844. | | | | | | | | Aden, 1848. | | | Calcutta, 1848–49. | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Maximum. | | | | Minimum. | | | Maximum. | | | | | Minimum. | | | Maximum. | | | | | | | | | | | |
| Therm. | Hour. P.M. | Date. | Range. | Therm. | Hour. A.M. | Date. | Therm. | Hour. P.M. | Date. | Range. | | Therm. | Hour. A.M. | Date. | Therm. | Hour. P.M. | Date. | Range. | | Min. | Max. | Range. | Min. | Max. | Range. | |
| ° | h m | | ° | ° | h | | ° | h | | ° | | ° | h | | ° | h | | ° | | ° | ° | ° | ° | ° | ° | |
| 84·3 | 2 41 | 30 | 16·1 | 65·9 | 8 | 4 | 85·2 | 3 | 31 | 19·3 | | 66·0 | 6 | 12 | 83·9 | 1 | 13 | 17·9 | | 68·5 | 76·7 | 8·2 | 57·5 | 78·5 | 21·0 | January. |
| 86·0 | 1 41 | 21 | 14·2 | 70·9 | 7 | 18 | 85·6 | 2 | 2 | 14·7 | | 64·7 | 7 | 9 | 85·4 | 3 | 14 | 20·7 | | 69·0 | 77·8 | 8·8 | 64·6 | 83·5 | 19·9 | February. |
| 92·3 | 0 41 | 30 | 18·7 | 73·0 | 7 | 2 | 88·2 | 1 | 31 | 15·2 | | 70·4 | 6 | 3 | 87·0 | 1 | 29 | 16·6 | | 71·6 | 82·0 | 10·4 | 72·0 | 93·7 | 21·5 | March. |
| 94·0 | 0 41 | 11 | 15·5 | 79·0 | 6 | 3 | 90·0 | 1 | 29 | 11·0 | | 77·3 | 6 | 2 | 90·2 | 2 | 21 | 12·9 | | 75·5 | 85·8 | 10·3 | 79·4 | 99·4 | 20·0 | April. |
| 94·4 | 0 41 | 12 | 25·6 | 80·9 | 6 | 4 | 90·3 | 2 | 1 | 9·4 | | 81·9 | 5 | 10 | 91·9 | 2 | 27 | 10·0 | | 80·6 | 89·0 | 8·4 | 79·6 | 97·8 | 18·2 | May. |
| 91·0 | 1 41 | 6 | 22·2 | 80·5 | 6 | 19 | 90·0 | 2 | 10 | 9·5 | | 78·0 | 4 | 30 | 90·8 | 2 | 13 | 12·8 | | 82·5 | 88·5 | 6·0 | 81·1 | 92·8 | 11·7 | June. |
| 97·7 | 2 41 | 10 | 18·4 | 78·3 | 7 | 15 | 88·1 | 2 | 1 | 9·8 | | 78·0 | 5 | 22 | 87·2 | 2 | 2 | 9·2 | | 80·4 | 86·4 | 6·0 | 81·4 | 91·8 | 10·4 | July. |
| 97·1 | 1 41 | 28 | 18·0 | 77·5 | 7 | 22 | 85·9 | 12* | 11 | 8·4 | | 77·0 | Midnight | 28 | 85·5 | 2 | 26 | 8·5 | | 78·4 | 84·6 | 6·2 | 80·8 | 90·2 | 9·4 | August. |
| 94·8 | 0 41 | 2 | 18·6 | 76·4 | 6 | 29 | 87·6 | 2 | 23 | 11·2 | | 75·4 | 4 | 14 | 86·1 | 3 | 29 | 10·7 | | 81·6 | 88·2 | 6·6 | 80·7 | 92·4 | 11·7 | September. |
| 91·5 | 0 41 | 3 | 16·2 | 77·0 | 5 | 24 | 87·8 | 3 | 21 | 10·8 | | 75·3 | 5 | 28 | 90·5 | 1 | 4 | 15·2 | | 77·8 | 89·0 | 11·2 | 75·8 | 89·1 | 14·3 | October. |
| 88·2 | A.M. 11 41 | 6 | 17·9 | 76·5 | 6 | 30 | 88·0 | 3 | 6 | 16·5 | | 73·9 | 6 | 21 | 90·9 | 2 | 3 | 19·0 | | 73·7 | 83·1 | 9·4 | 68·3 | 84·9 | 16·6 | November. |
| 83·5 | 11 41 | 10 | 13·5 | 68·4 | 7 | 20 | 85·9 | 12* | 6 | 17·5 | | 69·8 | 7 | 9 | 87·8 | 1 | 19 | 18·0 | | 75·0 | 81·6 | 6·6 | 68·8 | 82·4 | 18·6 | December. |
| 94·4 | 0 41 | ... | 36·2 | 65·9 | 8 | ... | 90·3 | 2 | ... | 24·4 | | 64·7 | 7 | ... | 91·9 | 2 | ... | 27·2 | | 68·5 | 89·0 | 20·5 | 57·5 | 99·4 | 41·9 | Year. |

* Noon.

maxima ranges of 21°·5 and 21° occur in March and January, and the minimum, 9°·4, was in August. The annual range was nearly double that of Bombay, namely, 41°·9. The foot-note above alluded to has the following records:—

| | |
|---|---|
| 1846. Maximum heat in May . . . . . | 105°·0 |
| 1846. Minimum heat in January . . . . | 55·0 |
| 1847. Maximum heat in May . . . . . | 109·6 |
| 1847. Minimum heat in February . . . . | 50·0 |

The range in these two years, therefore, being respectively 50° and 59°·6 Fahr.; the thermometer rising higher and sinking lower than either at Madras, Bombay or Aden near the sea-level.

*Range of Temperature at Aden.*

Extending the comparison of thermometric range near the sea-level to Aden, in the latitude of Madras, but 35°·6 to the westward of Madras, it will be seen that, unlike Bombay or Calcutta, the greatest range is not in the cold months, nor in the months in which the maximum heat occurs, but in those months in which the mean temperature is comparatively moderate, viz. March, April and October; the smallest range however occurring, as at Calcutta and Bombay, in what are called the monsoon months at those places, namely, May, June, July, August and September, while in those months at Madras the greatest range of the thermometer takes place. The greatest monthly range at Aden, 11°·2, occurs in October, and the least monthly range, 6°·0, is almost identical in the consecutive months of June, July, August and September. The annual range is 20°·5. If the records of 1848 exhibit normal conditions, then the climate of the dreaded Aden is more equable than that of places on the sea-level on the coasts of India.

The annexed Table contains the elements of the preceding notices:—

*Range of Temperature at High Levels.*

With respect to the majority of the stations at different elevations above the sea, as hourly observations were not kept, and a maximum and minimum thermometer only used, at Mahabuleshwur and Dodabetta the *hours* of the occurrence of maxima and minima cannot be stated.

*Sattarah.—Range of Thermometer.*

At Sattarah, the results of four years' observations by Dr. MURRAY, from 1844 to 1847 inclusive, are as follows:—

| | Minimum temperature. | Maximum temperature. | Maximum daily range. | Maximum monthly range. |
|---|---|---|---|---|
| | ° | ° | ° | ° |
| January | 53·0 | 86·0 | 23·0 | 31·0 |
| February | 50·5 | 90·0 | 26·0 | 33·0 |
| March | 62·0 | 100·0 | 32·0 | 38·5 |
| April | 64·0 | 102·0 | 31·5 | 36·5 |
| May | 70·0 | 103·0 | 26·0 | 29·5 |
| June | 69·0 | 93·0 | 22·0 | 22·0 |
| July | 60·0 | 91·0 | 7·5 | 11·0 |
| August | 60·0 | 80·0 | 10·0 | 10·0 |
| September | 64·0 | 83·0 | 16·0 | 19·0 |
| October | 63·0 | 93·0 | 21·0 | 30·0 |
| November | 58·0 | 85·0 | 21·0 | 25·0 |
| December | 57·0 | 86·0 | 25·0 | 27·0 |
| Year | 50·5 | 103·0 | 32·0 | 38·5 |

The minima and maxima in temperature represent the highest and lowest state of the thermometer ever indicated in January in four years, and the same for the other months; and the maxima and minima are not necessarily in the same year. The ranges represent the greatest and least in any particular day or month.

The maximum temperature, at 2320 feet, exceeded that recorded in Bombay, and the daily and monthly range were greater, but considerably less than at Mahabuleshwur at 4500 feet. In four years at Sattarah the extreme range of the thermometer was 52°·5, from 50°·5 to 103°·0, while at Mahabuleshwur in fifteen years the range was only 47°·0. The minimum temperature does not appear to have been below 50°·5, while I have observed it about the latitude of Sattarah, and at 400 feet lower level, at 40°·5 in January; and at 3123 feet in May I had it rise, at 3½ P.M., to 105°.

The following is extracted from a synopsis of fifteen years' observations at Mahabuleshwur, from January 1829 to December 1843, from observations successively taken by Doctors WALKER, MOREHEAD and MURRAY:—

| Extreme daily range. | Extreme monthly range. | Extreme depression at night, thermometer exposed. | Months. | Maximum temperature. | Minimum temperature. | Range in fifteen years. |
|---|---|---|---|---|---|---|
| ° | ° | ° | | ° | ° | ° |
| 21·0 | 30·5 | 30·0 | January | 79·5 | 45·0 | 34·5 |
| 23·8 | 32·1 | 31·5 | February | 85·5 | 46·0 | 39·5 |
| 23·5 | 38·0 | 33·0 | March | 89·0 | 49·5 | 40·5 |
| 22·0 | 34·5 | 36·5 | April | 92·0 | 56·0 | 36·0 |
| 22·0 | 32·0 | 30·2 | May | 90·0 | 57·3 | 32·7 |
| 18·5 | 25·5 | ..... | June | 84·0 | 53·0 | 31·0 |
| 12·7 | 18·5 | ..... | July | 73·8 | 51·5 | 22·3 |
| 11·1 | 13·0 | ..... | August | 70·8 | 53·0 | 17·8 |
| 14·0 | 17·0 | ..... | September | 77·0 | 56·0 | 21·0 |
| 17·5 | 23·0 | 34·1 | October | 78·5 | 54·0 | 24·5 |
| 16·5 | 23·0 | 29·5 | November | 75·0 | 51·5 | 23·5 |
| 19·0 | 27·5 | 27·5 | December | 76·0 | 48·5 | 28·5 |
| 23·8 | 38·0 | 27·5 | Year | 92·0 | 45·0 | 47·0 |

*Mahabuleshwur.—Range of Thermometer.*

The range of the thermometer in fifteen years was 47° Fahr., from 92° in April to 45° in January, but it will be seen that the thermometer exposed to radiation at night had been as low as 27°·5, and in every month of the year, excepting the four monsoon months, verged upon the freezing-point; the maximum heat in the sun was 110° in April and May, at 9 A.M., but at midday it had risen to 127°. The extreme daily range never exceeded 23°·8, and the maximum monthly range was 38° Fahr. The record of the night thermometer at Mahabuleshwur giving instances of the temperature in five months of the year sinking below the freezing-point, although it is not described as being placed on the grass or ground, affords an explanation of an otherwise puzzling record in the Dodabetta observations, namely, "on the 15th, 16th, 17th and 22nd of November 1847, found ice around the office" (at sunrise?), although there is not any record of the thermometer below 45°·2 on the 16th at Dodabetta, and in the *hourly* observations of the 22nd the thermometer only once sank to 48°·6 at 11 o'clock at night; the extreme cold, therefore, must have been caused by radiation and evaporation*. An old officer, who had often resided at Mahabuleshwur, tells me that he has frequently witnessed hoar-frost on the ground at Mahabuleshwur, though he had never *remarked* the thermometer sinking below 45°. The highest temperature in the sun at Mahabuleshwur was 127° in March and May.

*Dodabetta.—Range of Thermometer.*

At Dodabetta the following are the maxima, minima and ranges:—

| | Minimum temperature. | Maximum temperature. | Maximum daily range. | Maximum monthly range. |
|---|---|---|---|---|
| 1847. | ° | ° | ° | ° |
| February | 41·2 | 61·0 | 12·0 | 19·8 |
| March | 43·5 | 67·0 | 15·5 | 23·5 |
| April | 47·0 | 66·5 | 16·7 | 19·5 |
| May | 46·0 | 65·8 | 15·3 | 19·8 |
| June | 44·0 | 60·0 | 11·8 | 16·0 |
| July | 44·3 | 59·0 | 13·9 | 14·7 |
| August | 44·5 | 59·1 | 14·1 | 14·6 |
| September | 41·8 | 59·0 | 10·6 | 17·2 |
| October | 42·8 | 58·8 | 10·3 | 16·0 |
| November | 42·9 | 61·1 | 13·1 | 18·2 |
| December | 41·0 | 60·4 | 15·5 | 19·4 |
| 1848. | | | | |
| January | 38·5 | 62·8 | 19·5 | 24·3 |
| Year | 38·5 | 67 | 19·5 | 28·5† |

Hence it is seen that the Dodabetta temperature, at 8642 feet, compared with that of Mahabuleshwur at 4500 feet, has a decidedly diminished daily, monthly and annual range. It so happens that the lowest but not the highest state of the thermo-

* There is not any record of the radiation thermometer in November at Dodabetta, but in February it appears to have been twice below the freezing-point.

† Annual range.

meter, and the greatest daily and monthly range, occur in the same month at Dodabetta, namely, January 1848. The lowest temperature in the year was 38°·5, the highest 67°, and the annual range 28°·5. The greatest monthly range was 24°·3.

*Aqueous Vapour.*

Preliminary to the discussion of the question of aqueous vapour, a few words are necessary on the caution requisite in generalizing on a limited number of facts, or on observations not extending over lengthened periods of time. The hourly observations of the wet bulb at Madras and Bombay, for 1843 and 1844, are apparently trustworthy and satisfactory, supposing the wet bulb theorem to be correct. Those at Calcutta were taken only twice daily, at $9^h\ 40^m$ A.M. and 4 P.M., and how far observations, taken twice only during the daytime, can be relied upon for the expression of normal conditions, will best be shown by the following comparison of observations of the wet bulb at Dodabetta at 8640 feet above the sea-level. The regular meteorological observations were recorded twice a day only, at $9^h\ 40^m$ A.M. and $3^h\ 40^m$ P.M., but on one day in each month independent observations were taken for twenty-four consecutive hours. In a table I have compared the means of the $9^h\ 40^m$ A.M. and $3^h\ 40^m$ P.M. observations with the means of the twenty-four consecutive hours for the same day. The discrepancies are considerable, and too numerous to admit of the supposition of their resulting from accident or carelessness. On the 21st and 22nd of January the hourly observations give a depression of the wet bulb of 9°·2. The twice a day observations give a depression of 9°·4; on the 21st and 22nd of March a depression respectively of 5°·7 and 7°·7; on the 21st and 22nd of April of 5°·2 and 4°·2; on the 21st and 22nd of May of 1°·8 and 1°·33; and on the 21st and 22nd of November of 7°·8 and 6°·1. A bare inspection of the several hygrometric records for Dodabetta will show the anomalous results in working out the dew-points, elastic force of vapour, and per-centage of vapour or fraction of saturation in the atmosphere by the tables founded on Dr. APJOHN's formula. The hourly observations also demonstrate, that on the same day, in a transient fog without rain, there shall not be any depression whatever of the wet bulb; while in the course of the twenty-four hours there may be a great depression. For instance, at noon, on the 21st of December 1847, there was not any depression, but at 9 the next morning there was a depression of 3°·2, the mean being 1°·6, while the mean of the twenty-four hours was 0°·7. At the former hour there was a fog, at the latter, partly a blue sky. Again, at 5 P.M., on the 21st of November, the depression was 1°·5, but at 8 P.M. the depression was 10°·9, the mean being 6°·2, the mean of the twenty-four hours 7°·8; in both cases there was nearly a blue sky. At noon, on the 21st of July, there was not any depression in a fog; at 5 A.M. of the 22nd a depression of 2°·0, and *yet it was raining*. On the 21st of April, at 8 P.M., the depression was nil, an hour after it was 5°·5; at both hours with nearly a blue sky, while at 7 A.M. of the 22nd the depression was 9°·5, with a cloudy sky. Supposing these to have been the only observations available for the respective days,

could any of them or their means have been safely taken to express normal conditions? Professor Orlebar, in his Meteorological Observations at Bombay for 1846, gives proofs of the necessity for caution in the use of the wet bulb: in the first place, he was obliged to abandon the records of the air-thermometer attached to the wet bulb from the irregular depression of the former, by the cold of the evaporating surface of the latter; and in the next place, on the comparison of the action of two wet bulbs, one inside the observatory and the other outside, he records discrepancies in March ranging from 3°·2 plus to 2°·6 minus; the comparisons in April and May exhibited minor discrepancies, excepting on the 27th of April at the 18th hour, when the discrepancy was 3° minus. Professor Orlebar having used Daniell's hygrometer simultaneously with the wet bulb for eight months in 1846, the means of comparison are afforded, and the following Table exhibits the results. I have taken the two daily observations at $9^h\ 12^m$ A.M. and $3^h\ 12^m$ P.M. on the first day of each month for the comparison.

| Dates. | | | Barometer. | Thermometers. | | Dew-point by | | Tension of vapour by | | Fraction of saturation or per-centage of moisture in the air by | |
|---|---|---|---|---|---|---|---|---|---|---|---|
| Months. | Day. | Local hours. | | Dry. | Wet. | Wet bulb. | Daniell's hygrometer. | Wet bulb. | Daniell's hygrometer. | Wet bulb. | Daniell's hygrometer. |
| | | h m | in. | ° | ° | ° | ° | | | | |
| January ..... | 1st | 9 12 | 30·092 | 79· | 72·8 | 70 | 66·8 | 0·726 | 0·655 | 75 | 67½ |
| | | 3 12 | 29·942 | 83·5 | 73·3 | 68·6 | 69·9 | 0·695 | 0·724 | 62 | 64½ |
| February ... | 1st | 9 12 | 29·987 | 76·3 | 71·6 | 69·4 | 73·0 | 0·713 | 0·801 | 80 | 90 |
| | | 3 12 | 29·879 | 80·4 | 72·0 | 68·05 | 71·0 | 0·682 | 0·751 | 67 | 74 |
| March..... | 1st | 9 12 | 30·003 | 79·6 | 73·5 | 70·8 | 75·1 | 0·746 | 0·856 | 75½ | 86½ |
| | | 3 12 | 29·878 | 83·3 | 75·6 | 72·35 | 75·5 | 0·785 | 0·867 | 70 | 78 |
| April ..... | 1st | 9 12 | 29·899 | 84·4 | 75·4 | 71·6 | 73·5 | 0·765 | 0·814 | 66½ | 70½ |
| | | 3 12 | 29·804 | 87·6 | 74·2 | 68·15 | 73·1 | 0·684 | 0·803 | 54 | 63½ |
| May ..... | 1st | 9 12 | 29·834 | 92·5 | 80·8 | 76·55 | 80·8 | 0·897 | 1·027 | 60½ | 69 |
| | | 3 12 | 29·731 | 96·8 | 80·5 | 74·4 | 76·9 | 0·838 | 0·907 | 50 | 54 |
| June ..... | 1st | 9 12 | 29·748 | 83·2 | 80·8 | 80·0 | 81·5 | 1·000 | 1·049 | 90 | 94½ |
| | | 3 12 | 29·668 | 90·7 | 84·4 | 82·45 | 81·5 | 1·081 | 1·049 | 78 | 75 |
| July ..... | 1st | 9 12 | 29·615 | 81·4 | 80·0 | 79·2 | 78·5 | 0·976 | 0·955 | 90 | 88½ |
| | | 3 12 | 29·585 | 81·8 | 79·0 | 78·0 | 78·8 | 0·939 | 0·964 | 88¾ | 91½ |
| August ..... | 2nd | 9 12 | 29·728 | 81·2 | 79·9 | 79·45 | 78·6 | 0·984 | 0·958 | 94¼ | 92 |
| | | 3 12 | 29·678 | 84·4 | 81·0 | 79·85 | 77·5 | 0·996 | 0·925 | 86¾ | 80½ |
| September ... | 1st | 9 12 | 29·735 | 84·0 | 80·0 | 78·6 | 77·5 | 0·957 | 0·925 | 84½ | 81½ |
| | | 3 12 | 29·666 | 83·8 | 80·0 | 78·7 | 76·3 | 0·959 | 0·890 | 85 | 79 |

These observations having been made by the instructed and practiced manipulators of the Bombay Observatory, claim to be worthy of confidence; but we find ourselves in doubt which of the two sets to use for the correction of the barometer and to determine the real amount of moisture in the atmosphere. It would appear, that when the depression of the wet bulb and of Daniell's hygrometer is small in the monsoon months, their results do not differ very widely, the wet bulb however giving a higher tension of vapour and greater per-centage of moisture or fraction of saturation in the atmosphere than Daniell's hygrometer; but in the cold and hot months of the year

this is reversed; considerable discrepancies occur in the results, and the tension of vapour is much higher (with one exception) and the per-centage of moisture much greater by DANIELL's hygrometer than by the wet bulb, the dew-point by the two instruments differing from 3° to 5°. On the 1st of February, in the morning, the two instruments differ ten per cent. in the amount of moisture in the atmosphere. In the afternoon they differ seven per cent., in both instances DANIELL's hygrometer giving the greatest amount. On August the 2nd and September the 1st, in the afternoon, the instruments differ above six per cent., but at this period of the year the wet bulb gives the greatest amount of moisture in the atmosphere and DANIELL's hygrometer the least. The greatest depression of the dew-point in the above observations was 22°·4 on the 1st of May at $3^h\ 12^m$ P.M. In a former paper in the Philosophical Transactions I mentioned a depression of 40°, from 67° to 27°, on the 13th of March 1828 at sunrise in the Hill Fort of Loghur, and of 61° on the 16th of February 1828 at 4 P.M. at Downde near Pairgaum on the Beema river.

I have put into juxtaposition with this table a comparison of the results of hourly observations at Dodabetta of the wet bulb, with the two regular observations made on the same day. In November the simultaneous dew-points by the two processes are 36°·1 and 42°·15; in January 30°·7 and 33°·2; in March 43°·3 and 39°·6, and in April 42°·2 and 40°·95. Whether therefore there be 59½ or 69 per cent. of moisture in the atmosphere in November; 71 or 61½ per cent. in March; or 73° or 78½ per cent. in April, nothing short of continued hourly observations, like those at Madras and Bombay, will enable the meteorologist to determine.

Dodabetta.—Simultaneous observations, 8640 feet, on the 21st and 22nd of each month.

| | Depression of the wet bulb by | | | |
|---|---|---|---|---|
| | Hourly observations. | Twice a day, ditto. | Dew-point by hourly. | Dew-point by twice a day. |
| January | 9·2 | 9·4 | 30·7 | 33·2 |
| February | 1·4 | 0·9 | 49·7 | 50·3 |
| March | 5·7 | 7·7 | 43·3 | 39·6 |
| April | 5·2 | 4·2 | 42·2 | 40·95 |
| May | 1·8 | 1·33 | 54·2 | 55·8 |
| June | 0·5 | 0·2 | 51·2 | 51·75 |
| July | 0·8 | 0·23 | 53·15 | 53·75 |
| August | 0·5 | 0·37 | 54·35 | 55·43 |
| September | 0·4 | 0·6 | 52·95 | 53·1 |
| October | 0·7 | 0·4 | 53·1 | 52·9 |
| November | 7·8 | 6·1 | 36·1 | 42·15 |
| December | 0·7 | 0·95 | 50·65 | 50·65 |

Any such high per-centage of moisture however was not the case on the plains of the Deccan, where the dew-point was determined by DANIELL's hygrometer.

The natives of the Deccan divide the year into three seasons—the Hewalla (cold), Oonalla (hot), and Pawsalla (wet) seasons; the per-centage of vapour was in the

Cold months, Nov., Decem., Jan., Feb. . . . . 46½ per cent. of moisture.
Hot months, March, April and May . . . . . 42½ per cent. of moisture.
Wet or monsoon months, June, July, Aug., Sept., Oct. . . 77·4 per cent. of moisture.

But another uncertainty is the numerical value to be given to the wet bulb readings, whether by Apjohn's formula or by the means of factors, which Mr. Glaisher of the Royal Observatory has adopted from a comparison of observations between the wet bulb and Daniell's hygrometer. Dr. Murray, in charge of the Sanatarium at Mahabuleshwur, at 4500 feet, observed with the wet bulb for nine years, and has given the mean monthly depression of the wet bulb for that period in the Journal of the Physical Society of Bombay. He does not give any details of the character of his instruments, or with what precautions he used them, and as from 250 to 300 inches of rain fall at Mahabuleshwur in the S.W. monsoon months, it might have been expected that the air would have been much nearer to a state of saturation in those months than appears to be the case at Dodabetta in the same months, in which only 29 to 30 inches of rain fall. Subjecting these observations to the two methods, it is seen that the results go very well together with small depressions of the wet bulb and at temperatures ranging from 65° to 75°, but with depressions above 10° they immediately diverge, and the divergence would increase with greater depressions and at lower temperatures of the air.

Mahabuleshwur.—Nine years' Means of the Wet Bulb.

| | Dry. | Depression. | Dew-point by Glaisher. | Dew-point by Apjohn. | Tension by Glaisher. | Tension by Apjohn. | Per-centage moisture by Glaisher. | Per-centage moisture by Apjohn. |
|---|---|---|---|---|---|---|---|---|
| January ..... | 69·2 | 9·8 | 54·5 | 53·35 | ·435 | ·418 | 61·4 | 59·0 |
| February ..... | 69·6 | 13·0 | 50·1 | 47·4 | ·376 | ·341 | 32·3 | 47·5 |
| March ..... | 75·3 | 15·7 | 51·75 | 49·35 | ·396 | ·365 | 45·9 | 42·3 |
| April ..... | 78·1 | 15·4 | 55·0 | 53·8 | ·442 | ·424 | 46·9 | 44·9 |
| May ..... | 76·4 | 9·5 | 62·15 | 62·4 | ·562 | ·566 | 62·9 | 63·3 |
| June ..... | 70·7 | 2·6 | 66·8 | 67·0 | ·655 | ·658 | 88·1 | 88·5 |
| July ..... | 68·8 | 1·8 | 66·1 | 66·2 | ·640 | ·641 | 91·5 | 91·6 |
| August ..... | 67·4 | 1·7 | 64·68 | 64·95 | ·611 | ·615 | 91·4 | 92·0 |
| September ..... | 67·9 | 2·7 | 63·58 | 63·95 | ·589 | ·596 | 86·7 | 87·7 |
| October ..... | 68·2 | 6·4 | 57·96 | 58·25 | ·489 | ·493 | 71·4 | 71·9 |
| November ..... | 67·3 | 7·7 | 54·98 | 54·95 | ·442 | ·442 | 66·4 | 66·4 |
| December ..... | 66·9 | 7·8 | 54·42 | 54·35 | ·434 | ·432 | 66·0 | 65·7 |
| Fifteen years ... | 70·4 | 7·84 | 58·64 | 58·25 | ·500 | ·493 | 67·9 | 66·9 |

Bearing therefore these discrepancies in mind, it may be justifiable to generalize so far only as to assert that two or three (or even four) observations with any meteorological instrument within the twenty-four hours, even under favourable circumstances, can do little more than give approximations to the truth; and that hourly observations, extending through four or five years at least, can alone satisfy the scientific

meteorologist, to enable him to determine the normal or abnormal atmospheric phenomena of the *locality* in which the observations are taken; and he will distrust the applicability of these *local* determinations to any other places situated beyond a certain circumscribed area.

With these remarks I proceed to consider the hygrometric features of certain widely separated stations in India, both at the sea-level and elevated at 1800 and 4500 and 8640 feet above the sea. The most marked feature is the singularly small monthly mean depression of the wet bulb, the high figures of the elastic force of vapour, and the great per-centage of moisture in the atmosphere; not only at the sea-levels of Madras, Bombay, Aden and Calcutta, but at Dodabetta, at 8640 feet above the sea, whether during the monsoons or during the cold and hot months, which are generally supposed to be the dry portion of the year, and the annexed Table exhibits the results.

At neither of the Presidencies is there a mean monthly per-centage of vapour at Madras below 67, at Bombay below 66, at Calcutta below 63, and at Dodabetta below 51, while the maximum at Dodabetta goes up to 98, and at Calcutta to 94; at Bombay it did not exceed 88, and at Madras, in two years, it only twice attained a mean maximum of 83 per cent. of moisture in the atmosphere. The mean annual per-centage of moisture in the air, it will be seen for the years 1843 and 1844, was at Madras respectively 75 and $74\frac{1}{2}$, at Bombay 76 and 76, at Calcutta 80 and 84, at Aden 71, at Mahabuleshwur $67^{\circ}\cdot9$, and at Dodabetta, for 1847–48, it was 90°. In the Deccan, in 1827, only 55°, as determined by DANIELL's hygrometer. The difference between the annual mean temperature of the air and the annual mean temperature of the dew-point, was—

| Madras. | | Bombay. | | Calcutta. | | Dodabetta. | Deccan. | Aden. | Mahabuleshwur. |
|---|---|---|---|---|---|---|---|---|---|
| 1843. | 1844. | 1843. | 1844. | 1843. | 1844. | 1847–48. | 1827. | 1848. | Means of 9 years. |
| ° 9 | ° 9·24 | ° 8·65 | ° 8·65 | ° 6·95 | ° 5·3 | ° 3·1 | 17° 9 | ° 7·5 | 12° 2 |

The air at Madras, Bombay and Calcutta, is unquestionably more moist than that of the interior; but the feeling and experience so little lead one to expect the high dew-points indicated, particularly in the cold and hot months, that some inaccuracy of observation or fallacy in deduction might be feared, were not the ability and zeal of the observers at Madras and Bombay, combined with the observations being hourly, a sufficient guarantee against error. At Calcutta, however, situated sixty miles from the sea, the hygrometric observations make the air much more moist even than at Madras and Bombay. This is contrary to probability, and may be owing to the means of the observations, made only twice a day, not giving the real mean of the twenty-four hours. At the peak or ridges of Dodabetta the air would appear to be nearly in a constant state of saturation; and there is a possibility in the circumstance, considering that it is the highest eminence in the peninsula of India and might be expected

| Months. | Madras. | | | | | | | | Bombay. | | | | | | | | Calcutta. | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | 1843. | | | | 1844. | | | | 1843. | | | | 1844. | | | | 1843. | | | | | | | |
| | Thermometer, dry. | Thermometer, wet. | Elastic force. | Per-centage of vapour. | Thermometer, dry. | Thermometer, wet. | Elastic force. | Per-centage of vapour. | Thermometer, dry. | Thermometer, wet. | Elastic force. | Per-centage of vapour. | Thermometer, dry. | Thermometer, wet. | Elastic force. | Per-centage of vapour. | Thermometer, dry. | Thermometer, wet. | Elastic force. | Per-centage of vapour. | Thermometer, dry. | | | |
| January ..... | 77°59 | 72°32 | ·726 | 79 | 75°71 | 69°57 | ·651 | 75 | 76°3 | 68°0 | ·598 | 69 | 75°4 | 67°5 | ·581 | 67 | 74°9 | 68°9 | ·674 | 79 | 74°1 | | | 6 |
| February ... | 77·90 | 71·86 | ·705 | 76 | 77·74 | 71·45 | ·694 | 75 | 78·0 | 70·7 | ·645 | 68 | 73·3 | 68·6 | ·608 | 68 | 81·4 | 71·8 | ·663 | 63 | 79·3 | | | 7 |
| March ..... | 81·52 | 75·22 | ·791 | 76 | 82·20 | 75·51 | ·796 | 75 | 79·7 | 73·0 | ·726 | 73 | 79·5 | 73·4 | ·743 | 75 | 86·9 | 79·9 | ·920 | 74 | 88·4 | | | 8 |
| April ..... | 85·19 | 78·93 | ·899 | 77 | 86·34 | 79·73 | ·921 | 76 | 84·2 | 77·9 | ·867 | 76 | 84·1 | 78·1 | ·876 | 77 | 91·3 | 83·2 | ·918 | 64 | 91·5 | | | 8 |
| May ..... | 85·62 | 79·06 | ·908 | 78 | 86·98 | 79·98 | ·925 | 75 | 85·9 | 79·8 | ·927 | 77 | 85·9 | 78·8 | ·885 | 73 | 91·2 | 84·2 | 1·066 | 75 | 89·0 | | | 8 |
| June ..... | 85·52 | 78·05 | ·860 | 73 | 88·58 | 78·82 | ·859 | 67 | 85·3 | 80·0 | ·943 | 79 | 85·3 | 79·9 | ·938 | 79 | 89·0 | 84·3 | 1·085 | 79 | 87·9 | | | 8 |
| July ..... | 85·79 | 76·73 | ·803 | 67 | 85·76 | 77·86 | ·850 | 72 | 82·0 | 78·4 | ·912 | 85 | 81·9 | 79·0 | ·938 | 88 | 87·0 | 82·9 | 1·052 | 84 | 85·1 | | | 8 |
| August ..... | 84·51 | 76·95 | ·826 | 72 | 85·25 | 77·94 | ·858 | 73 | 81·2 | 77·2 | ·872 | 84 | 81·6 | 78·0 | ·900 | 85 | 86·6 | 82·6 | 1·043 | 85 | 84·6 | | | 8 |
| September ... | 84·26 | 77·21 | ·839 | 74 | 82·97 | 77·37 | ·861 | 79 | 81·1 | 77·3 | ·876 | 84 | 80·7 | 77·0 | ·869 | 86 | 86·7 | 82·7 | 1·046 | 85 | 86·4 | | | 8 |
| October ..... | 80·72 | 76·50 | ·851 | 83 | 80·53 | 75·86 | ·828 | 82 | 82·2 | 76·5 | ·832 | 77 | 83·5 | 78·0 | ·879 | 79 | 86·4 | 80·6 | ·956 | 78 | 84·6 | | | 8 |
| November ... | 77·83 | 71·71 | ·702 | 76 | 79·17 | 72·41 | ·713 | 73 | 80·3 | 72·2 | ·690 | 68 | 80·8 | 72·1 | ·681 | 66 | 80·3 | 74·4 | ·772 | 76 | 82·1 | | | 7 |
| December ... | 75·89 | 70·73 | ·691 | 79 | 76·94 | 72·90 | ·755 | 83 | 76·7 | 68·6 | ·603 | 67 | 79·6 | 71·6 | ·676 | 68 | 74·3 | 69·1 | ·762 | 94 | 75·9 | | | 7 |
| | 81·81 | 75·44 | ·796 | 75 | 82·34 | 75·78 | ·803 | 74½ | 81·1 | 75·0 | ·736 | 76 | 81·2 | 75·1 | ·789 | 76 | 83·8 | 78·7 | ·905 | 80 | 84·07 | | | 8 |

[*To face page* 340]

| | | | | Aden, 187 feet. | | | | Deccan, mean height 1800 feet. | | | | Mahabuleshwur, 4500 feet. | | | | Dodabetta, 8640 feet. | | | | Dodabetta, 8640 feet. | | | | Month. |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | 1844. | | | 1848. | | | | Sunrise 9 to 10 A.M. and 4 to 5 P.M. 1827. | | | | Means of 9 years, 1835 to 1843 inclusive. | | | | 1847 to 1848. Monthly means. | | | | Hourly observations, 21st to 22nd. Monthly, 1847–48. | | | | |
| | Thermometer, wet. | Elastic force. | Per-centage of vapour. | Thermometer, dry. | Thermometer, wet. | Elastic force. | Per-centage of vapour. | Thermometer. | Daniell's hygrometer. | Elastic force. | Per-centage of vapour. | Thermometer, dry. | Thermometer, wet. | Elastic force. | Per-centage of vapour. | Thermometer, dry. | Thermometer, wet. | Elastic force. | Per-centage of vapour. | Thermometer, dry. | Thermometer, wet. | Elastic force. | Per-centage of vapour. | |
| | 68°7 | ·636 | 76 | 74°9 | 68°9 | ·634 | 74½ | 72°53 | 50°31 | ·377 | 47 | 69°2 | 59°4 | ·435 | 61·4 | 52°1 | 46°15 | ·277 | 69 | 49°5 | 40°3 | ·190 | 51½ | January. |
| | 72·8 | ·723 | 73 | 75·6 | 69·4 | ·643 | 74 | 75·19 | 44·39 | ·308 | 36 | 69·6 | 56·6 | ·375 | 52·3 | 52·3 | 50·8 | ·379 | 93 | 52·0 | 50·6 | ·369 | 91 | February. |
| | 81·3 | ·965 | 74 | 78·4 | 72·9 | ·737 | 77½ | 74·73 | 48·83 | ·358 | 42 | 75·3 | 59·6 | ·396 | 45·9 | 53·0 | 48·8 | ·323 | 78 | 53·3 | 47·6 | ·296 | 71 | March. |
| | 84·9 | 1·095 | 76 | 81·3 | 75·4 | ·800 | 76½ | 87·22 | 55·34 | ·447 | 36 | 78·1 | 62·7 | ·442 | 46·9 | 56·4 | 53·25 | ·393 | 84 | 52·4 | 47·2 | ·296 | 78 | April. |
| | 85·7 | 1·161 | 87 | 86·7 | 79·4 | ·902 | 73 | 84·75 | 64·54 | ·608 | 52 | 76·4 | 66·9 | ·561 | 62·9 | 57·2 | 54·95 | ·423 | 88 | 57·9 | 56·1 | ·444 | 91½ | May. |
| | 85·1 | 1·144 | 90 | 87·4 | 79·4 | ·895 | 71 | 79·99 | 72·48 | ·788 | 84 | 70·7 | 68·1 | ·655 | 88·1 | 52·5 | 51·8 | ·391 | 96 | 52·0 | 51·5 | ·389 | 97 | June. |
| | 83·7 | 1·109 | 93 | 86·5 | 77·8 | ·839 | 68½ | 77·03 | 71·69 | ·768 | 84 | 68·8 | 67·0 | ·640 | 91·5 | 52·60 | 52·15 | ·398 | 97 | 54·4 | 53·6 | ·415 | 96 | July. |
| | 83·3 | 1·096 | 94 | 85·5 | 76·0 | ·778 | 65½ | 76·21 | 71·03 | ·751 | 84 | 67·4 | 65·7 | ·611 | 91·4 | 53·10 | 52·5 | ·401 | 96 | 55·1 | 54·6 | ·432 | 97 | August. |
| | 84·3 | 1·123 | 92 | 86·1 | 78·0 | ·851 | 70½ | 77·24 | 71·11 | ·753 | 82 | 67·9 | 65·2 | ·589 | 86·7 | 52·45 | 51·75 | ·390 | 96 | 53·6 | 53·2 | ·413 | 98 | September. |
| | 82·8 | 1·073 | 93 | 83·2 | 75·7 | ·790 | 71½ | 77·71 | 58·68 | ·501 | 53 | 68·2 | 65·8 | ·489 | 71·4 | 53·30 | 52·8 | ·406 | 97 | 54·2 | 53·5 | ·415 | 96 | October. |
| | 78·9 | ·931 | 87 | 81·7 | 71·3 | ·642 | 60½ | 75·46 | 55·54 | ·451 | 54 | 67·3 | 59·6 | ·442 | 66·0 | 52·15 | 50·95 | ·378 | 94 | 51·0 | 43·2 | ·230 | 59½ | November. |
| | 71·8 | ·724 | 82 | 76·8 | 69·8 | ·644 | 71½ | 72·59 | 51·31 | ·390 | 49 | 66·9 | 59·1 | ·434 | 66·0 | 50·80 | 48·75 | ·341 | 86 | 51·8 | 51·1 | ·382 | 96 | December. |
| 07 | 80·25 | ·961 | 84 | 82·0 | 74·5 | ·758 | 71 | 77·55 | 59·60 | ·516 | 55 | 70·4 | 62·56 | ·500 | 66·9 | 53·16 | 51·2 | ·373 | 90 | 53·02 | 50·13 | ·352 | 87 | Year. |

to attract much vapour, nevertheless the greatest quantity of rain does not fall at Dodabetta. The mean of the hourly observations once a month, and the mean of the two observations daily throughout the year, giving respectively 87 per cent. and 90 per cent. of moisture in the air at Dodabetta, observation and expectation thus go pretty well together, and the records might be satisfactory, were there not doubts about the manipulations with the wet bulb. The hygrometric observations in the Deccan with DANIELL's hygrometer, which were taken by myself thrice daily, are quite in accord with the feelings and with the expectations of the observer, excepting for the month of March, in which the feelings indicate the air to be quite as dry as in the months of February or April, but which the hygrometer indicates to be 6 per cent. nearer to saturation than in either February or April. At Aden, in the latitude of Madras, on the arid coast of Arabia, where little rain falls, the mean monthly and annual per-centage of moisture appears unexpectedly high; the lowest per-centage ($60\frac{3}{4}$) is in November, and the next lowest $68\frac{1}{2}$ and $65\frac{1}{2}$ respectively in August and September. The maximum per-centage was $77\frac{1}{2}$ in March, and the mean for the year 71. These results have a certain relation to the phenomena at Madras, which is destitute of a S.W. monsoon. The mean maximum tension of vapour was ·902 in May at Aden.

The mean monthly and annual results at the several stations have no doubt a certain relation to truth, as it is seen that the per-centages of moisture or fractions of saturation in the atmosphere in the different months of the year have an increasing or diminishing amount as the several months approximate to, or recede from, the monsoon months of the year; this is sufficiently shown at Madras, where the monsoon months are the dry months at Bombay and in the Deccan. Nevertheless the amount of moisture in the atmosphere, deduced from the observations of the wet bulb, is so very great compared with the amount determined by the direct method by DANIELL's hygrometer (itself an imperfect instrument) in the Deccan, and at some of the stations is so little in accord with personal recollections and experience, that I cannot refrain from suspecting some error of observation, some mismanagement in the manipulations, or a fallacy in the formula by which the dew-point is deduced from the temperature of the wet bulb. The first cause of error that struck me was that arising from the proximity of the dry to the wet bulb, as noticed by Professor ORLEBAR in his Report of Meteorological Observations taken at the Bombay Observatory in 1846. He had a stand erected out of doors, 6 feet high, and with a thatched roof, and every precaution was taken to guard off radiation by layers of cotton and tow upon a board under the roof upon which the meteorologic instruments were placed; there was lateral access for the air all round. He soon found that the dry bulb, in the neighbourhood of the wet bulb, was almost always depressed below the neighbouring *standard* thermometer, and that the depression of the *dry* bulb was greater as the depression of the wet bulb below the standard was greater. Professor ORLEBAR explains this in the following words:—"This seems accountable only on the

supposition that heat is extracted from the air to form the shell of moisture round the wet bulb at a distance as far off as the dry bulb." These discrepancies amounted on the 3rd and 14th of November, at the 19th hour, Göt. mean time:—

| | | | | | | | |
|---|---|---|---|---|---|---|---|
| Standard . . . | 82°·4 | Dry . . . | 76·5 | Wet bulb . . . | 71·8 | Diff. . . . | 5°·9 |
| Standard . . . | 82·4 | Dry . . . | 75·4 | Wet bulb . . . | 69·3 | Diff. . . . | 7·0 |

Professor Orlebar therefore abandoned observing with the attached dry bulb. But supposing this cause of error to have been overlooked by other observers, the tension of vapour and the per-centage humidity would have been recorded by them greatly higher than the truth; and if we apply this source of error to the mean monthly and annual results in the comparative table I have given;—for instance, to the annual mean for Dodabetta, the 90 per cent. is reduced, for the first difference, to 64 per cent., and if the correction be made for 7°, by depression of the dry bulb below a standard owing to its proximity to the wet bulb, the 90 per cent. of moisture at Dodabetta is reduced to 60 per cent. Professor Orlebar says the dry bulb *always* stood below the standard (and he had determined that it was not owing to error in graduation of the thermometers), often to the extent of 2°, and even in the monsoon month of September I observe that on the 2nd it was 3°·4 minus. Any amount of error in depression would necessarily affect the numerical determinations of the tension of vapour and degree of humidity; but supposing it not to exceed 2°, even this small depression would reduce the 90 per cent. of moisture in the air at Dodabetta to 80 per cent. Supposing therefore that the same error was not discovered at the other places of observation as was discovered in Bombay, there is necessarily some ground for the expression of my doubts, whether the air really did hold at the different stations the quantity of moisture represented by the figures I have elaborated. But Professor Orlebar observed another source of error, contingent upon the *locality* of the wet bulb apparatus, whether placed within doors or out of doors. To determine the amount of error he placed a wet bulb *within* the observatory, observing simultaneously with the wet bulb *out* of doors upon the meteorologic stand. This was done hourly for March, April, and to the 10th of May. The reading was almost always plus with the wet bulb inside; on the 22nd of March, at 19th hour, to the extent of 3°·2, while at 18th hour it had been only 0·2 plus; but there were great irregularities in the readings, being plus or minus dependent apparently upon drafts of air within the observatory, which would depress the wet bulb or raise it. Also the "atmosphere within the room would tend to keep up a reading at any time to whatever it had been at a time preceding," and the latter, Professor Orlebar says, was the principal cause of the plus readings in-doors. Supposing this error of 3° to be applied as a correction to the reading of the annual means of the wet bulb at Bombay for 1843, the per-centage of moisture in the atmosphere would only be 65 instead of 76. The distinguished experimental philosopher Regnault has pointed out the same sources of error. He placed the dry and wet bulb in the open air in the court of the College of

France, in a closed room in the College, and in the theatre of the College, opening the windows. In the open air, with a temperature ranging from 7°·16 to 17°·88 Centigrade, and a depression ranging from 1°·86 to 9°·60, the results, by observation and by M. Regnault's tentative formula*, were sufficiently satisfactory; but in the closed chamber he says, "Les fractions de saturation calculées avec la formule †, sont ici beaucoup plus fortes que celles que l'on deduit des pesées directes de l'eau renfermée dans l'air; en d'autres termes la température $t'$ marquée par le thermomètre mouillé n'est pas assez abaissée par la vaporisation de l'eau que se fait à sa surface pour donner dans la formule la véritable force élastique $x$ de la vapeur. Cette circonstance tient évidemment à ce que l'air se trouve beaucoup moins agité qu'à l'extérieur."—Page 219. At page 220 M. Regnault adds, "Ces expériences démontrent de la manière la plus évidente que la formule ne peut pas rester la même pour les divers états d'agitation de l'air."

Here then is a second source of error; and it is somewhat curious that Professor Orlebar, in guarding against another grave source of error, which will be adverted to, himself contributes to an error of observation. He had observed the effect of wind blowing upon the wet bulb in unduly depressing the temperature, and to guard against this he says, "As it was equally essential that the bulb of this thermometer should not be exposed to the wind, and that it should be in the same body of air as the air-thermometer when the latter was exposed to the wind, a small mirror, about an inch square, was put on a little stand, and this being placed upon the tin board could be moved about by the observer into such a position that it might always *cut off the wind from the bulb of the wet thermometer* only" (page lxiii.). Now the wet bulb being thus screened, would be buried in its own vapour and the reading would necessarily be too high. When the air is perfectly calm the same would be the result without the screen, for there would be a shell or coat of saturated air round the bulb. I had occasion to notice this local character of aqueous vapour in my Meteorology of the Deccan, where I constantly witnessed it, as regulated in its distribution by nature. Speaking of dew, I said in the year 1828, "At Marheh in the Pergunnah of Mohol, garden produce (which is usually irrigated during the day-time) was covered with a copious dew every morning; the lands bordering the gardens for forty or fifty yards around were slightly sprinkled with it, *but there was not a vestige of it* in the fields constituting the rising ground north and south of the tract of garden land." Hence I inferred that "aqueous vapour had been taken up by the action of the sun during the day, *suspended over the spot*, and deposited by the lower temperature at night as dew upon the land in proportion to the supply obtained by day." My tents were within 200 yards of the fields where I observed these phenomena, but from the 11th to the 30th of January 1828, there was not any deposition of dew about them, excepting on the 13th of January. In consequence of these observations I was induced

* Annales de Chimie, tom. xv. p. 218.

† $x = f' - \frac{0{\cdot}429(t-t')}{610-t'}\mathrm{H}$.

to remark particularly the localities of dew at Poona and in its neighbourhood. In September and October I found that when there was not a trace of dew in the cantonment, there would be a deposition on the fields of standing grain half a mile distant, and when there was not any dew either in the cantonment or in the fields, it would yet be found on the banks of running rivulets and on the banks of the Mota Mola River; but with respect to the rivulets, "*fifteen or twenty feet from the water were the limits of the deposition.*" I gave numerous other instances of the local deposition of dew proximate to irrigated lands, or in the neighbourhood of water, indicating the suspension of vapours over the localities, in complete analogy with what occurs to the wet bulb thermometer when the air is calm. That agitation of the air is necessary to disperse the vapour surrounding a wet bulb, has been noticed by British chemists. BRAND says (page 111, last edition), "It is now established that the pressure of air is really an obstacle to evaporation, and that *a current* is useful, not by supplying new quantities of air, but *by removing the vapour* according as it is formed and leaving fresh spaces into which the vapours may expand." He elsewhere says (page 82), "Evaporation is proportional to the surface exposed; it is also accelerated by agitating the superincumbent air, as in the case of a brisk wind, or by artificial means. When the *air is tranquil the vapour rests upon the surface of the water, and it is the pressure of its own vapour on the surface of a liquid, and not that of the gaseous* atmosphere which stops the process." M. REGNAULT has demonstrated the truth of this in an elaborate manner. Accounting for the different results of observations in a closed and open chamber, he says the wet bulb was not sufficiently depressed in the closed chamber. "Cette circonstance tient évidemment à ce que l'air se trouve beaucoup moins agité qu'à l'extérieur*." After experimenting in a room with two windows open, he adds, as before stated, "Ces expériences démontrent de la manière la plus évidente que la formule ne peut pas rester la même pour divers états d'agitation de l'air." (P. 220.) The vapour therefore resting upon the wet bulb is a source of error, but the removal of it leads to one much more grave. M. REGNAULT, in reference to M. AUGUST's formula, says (p. 207), "La formule ne tient aucun compte de la vitesse du courant d'air; d'après cette formule, la différence de température devrait être la même, quelle que soit cette vitesse. Ce résultat parait impossible *à priori*. J'ai cherché à déterminer *par des expériences directes*, l'influence de cette vitesse et à reconnaitre si, à partir d'une certaine valeur de la vitesse, les différences de température des thermomètres sec et mouillé deviendraient indépendentes de la vitesse absolue du courant d'air, conséquence à laquelle on se trouve naturellement conduit par le raisonnement que M. AUGUST applique au calcul de la formule du psychromètre." M. REGNAULT then describes his apparatus and mode of making his experiments. He gives two series of experiments; in the second experiment the air being made to blow upon the wet bulb with a greater velocity than in the first. It will be sufficient to give the first and sixth figures of each series.

* Annales de Chimie, tom. xv. p. 219.

| | | $t$*. | $t'$. | $t-t'$. |
|---|---|---|---|---|
| 1st series. | 1st experiment | 14°·66 | 7°·28 | 7°·38 Centigrade thermometer. |
| | 2nd experiment | 14·96 | 4·33 | 10·63 Centigrade thermometer. |
| 2nd series. | 1st experiment | 21·48 | 10·78 | 10·70 Centigrade thermometer. |
| | 2nd experiment | 21·70 | 8·56 | 13·14 Centigrade thermometer. |
| In Fahrenheit's scale. | | | | |
| | | 58·37 | 45·10 | 13·27 |
| | | 58·93 | 39·79 | 19·14 |
| | | 70·66 | 51·40 | 19·26 |
| | | 71·06 | 47·41 | 23·65 |

In the first series, in the second experiment, the wind blows faster than in the first, and the wet bulb is reduced nearly 3°, and the difference between the wet and dry bulbs is increased from 7°·38 to 10°·63, while the temperature of the dry bulb is only raised 0°·30. In the second series the temperature of the wet bulb is reduced from 10°·78 to 8°·56, and the difference between the wet and dry is increased from 10°·70 to 13°·14, while the temperature of the dry bulb is only raised 0°·22. Upon these experiments M. Regnault says, "On voit que, pour une même température $t$ les températures $t'$ dependent beaucoup de la vitesse du courant d'air" (p. 209); and he further says (p. 210) that these depressions are less than he has found on other occasions with an increased velocity of the air; and on using dry air he found the depression $t-t'=13°·52$ instead of 5°·91, and another depression of 15°·60 instead of 8°·60. M. Regnault gives other experiments, and finishes by saying, "Il résulte de tout ce qui vient d'être dit, que l'agitation de l'air doit exercir une influence très-sensible sur les indications du psychromètre" (p. 211). The truth of M. Regnault's experiments are borne out by the experience of families in the Deccan (and no doubt elsewhere) in India in the fair season, who cool their wine and beer by the following simple process down to a temperature the cold of which makes the teeth ache in drinking. At any time of the day a thick layer of straw is put down on the ground in the shade of a building, but not in the lee of the wind. The bottles of wine or beer to be cooled are put upon the straw, some more straw is thinly and lightly shaken over the prostrate bottles, and the mass is sprinkled at intervals with water through the nozzle of a watering-pot with very fine apertures, thus dewing as it were the straw; the force of evaporation and the consequent cold is proportioned to the velocity and dryness of the wind; but even with a moderate wind the temperature of the liquors is soon greatly lowered; and in certain hot and therefore parching winds, even at a temperature of the air ranging from 85° to 90° Fahr., I have often, at Ahmednugger, had the temperature of the wine or beer (judging from my sensations at the moment) approaching to the freezing-point†. In this cooling process we have

* $t$. Temperature of dry thermometer. $t'$. Temperature of wet bulb.

† My sensations deceived me. While this paper is going through the press, I have received from a friend, commanding the Artillery at Ahmednugger, the following results of experiments he made at my request, with

the bottle of wine or beer corresponding to the bulb of the thermometer; the straw lying thinly over it represents the muslin, and the operations of the watering-pot complete the wet bulb apparatus, evaporation does the rest; but as the velocity and dryness of the wind regulate this, it is plain that such an instrument can only give uncertain and fallacious results when used to determine, with any pretension to accuracy, the fractional saturation of the atmosphere. I come now to a source of error in my reductions of the wet bulb observations which I have collected in this paper from various parts in India, a source of error that may operate with a greater or less power as the depression of the wet bulb is greater or less. I allude to the formula used for the reductions of the readings of the wet bulb. M. Regnault says that M. Gay-Lussac was the first to propose the determination of the dew-point by the observations of a dry and wet bulb apparatus*, but that to effect the object satisfactorily it would require extensive observations upon which to found tables. Subsequently to the period of M. Gay-Lussac's proposition, August, Professor at Berlin, occupied himself with the subject and published some papers, in which he sought to determine, upon theoretical considerations, the formula by which the elastic force of aqueous vapour, really existing in the air, could be found by the difference of temperature of a dry and wet bulb thermometer. The dry and wet bulb apparatus he called a Psychromètre. His chief memoir is published in the Annalen der Physik und Chemie, V. Band. Leipzig, 1825. It will suffice to say that he considered the wet bulb surrounded at all times with a coat of vapour of the same temperature as the bulb, which was, he stated, necessarily lower than that of the surrounding air,—that the successive supplies of air coming into contact with the wet bulb, parted with a portion of their heat and took the temperature of the wet bulb; but on the other hand, the air so supplied in vaporizing the water upon the surface of the wet bulb took from it a portion of its heat; and a stationary state of the temperature of the wet bulb was established by these two quantities of heat balancing each other.

August's formula was $x = \frac{1+\frac{\gamma}{\delta\lambda}(t-t')}{1+\frac{\varkappa}{\lambda}(t-t')} f' - \frac{\frac{\gamma}{\delta\lambda}(t-t')}{1+\frac{\varkappa}{\lambda}(t-t')} h$, where $t$ denotes the temperature of the dry bulb (in Centigrade degrees), $t'$ the temperature of the wet bulb, $\gamma$ the specific heat of dry air, $\delta$ the density of aqueous vapour, $\lambda$ the latent heat of aqueous vapour between the temperatures $t$ and $t'$, $\varkappa$ the specific heat of vapour, $h$ the height of the barometer, $f'$ the elastic force of vapour in saturated air at the temperature $t'$, and $x$ the elastic force of the vapour actually existing in the atmosphere; $x, f'$ and $h$ being expressed in inches, or in terms of any common unit.

the wet straw process, on the 21st of May 1850, and preceding days. Temperature of air in shade, free from radiation, 98° Fahr. Temperature of water in bottles under wet straw exposed to wind 65°, difference 33°. The dew-point by Apjohn's formula would be about 41°·7, and by Glaisher's factors about 48°·5. My friend says, "When the wind does not blow, the temperature of the water in the bottles, under the straw, cannot be got lower than 71° Fahr. When the wind blows, the bottles cool to 65° Fahr."

* Annales de Chimie et de Physique, 2nd series, t. xxi. p. 91.

With assumed values for $\gamma$, $\delta$ and $\lambda$, as the real values are not accurately known, and neglecting small quantities, and supposing $\varkappa=\gamma$, AUGUST's formula became

$$x=f'-\frac{0{\cdot}428(t-t')}{640-t}\,h,$$

for the determination of the elastic force and consequently the dew-point, and after certain comparisons of the dew-point from his formula with the direct dew-point from DANIELL's hygrometer, he found what he considered a sufficient agreement between them. In a comparative table* of the results by his formula and the results by DANIELL's hygrometer, they appear to go pretty well together, while the variations of temperature and of the depression of the wet bulb are small; but the moment the temperature exceeds 20° Centigrade (68° FAHR.), and the depression exceeds 5° (9° FAHR.), the discrepancy is very considerable; for instance, at bar. 755·3 millims. (29·736 inches), dry 28°·5 (83°·3 FAHR.), wet 21°·1 (69°·98 FAHR.), depression 7°·4 (13°·32 FAHR.), the tension of vapour by the formula is 14·181 millims. (·558 in. =dew-point 62°), and by DANIELL's hygrometer 12·087 millims. (·475 in.=dew-point 57°·15), the difference 2·094 millims (·083 in.). Even with a depression of only 0·6 (1°·08 FAHR.) the tension of vapour by the formula and by DANIELL is respectively 8·612 millims. (·339 in.), and 8·534 millims. (·335 in.), difference 0·078. These discrepancies induced M. REGNAULT to modify, in 1845, nearly twenty years afterwards, AUGUST's formula, and he in common with AUGUST assumed $\gamma=0{\cdot}2669$, $\delta=0{\cdot}622$ and $\varkappa=\gamma$, but $\lambda=610-t$. Substituting these numbers and neglecting small quantities, the formula became $x=f'-\frac{0{\cdot}429\,(t-t')}{610-t'}\,h$, and it is this formula that M. REGNAULT tests by his various experiments; and at the close of his able and elaborate paper he says, "Je ne pense pas que l'on puisse admettre comme base du calcul du psychromètre l'hypothèse fondamentale adoptée par AUGUST: à savoir, que tout l'air qui fournit de la chaleur au thermomètre mouillé descend jusqu'à la température $t'$ indiquée par celui-ci, et se sature complètement d'humidité. Il me parait probable que la portion de l'air que se refroidit ne descend pas jusqu'à $t'$, et qu'elle ne se sature pas d'humidité. Le rapport de la quantité de chaleur que l'air enlève à la boule par vaporisation de l'eau, à la quantité de chaleur qu'il perd en se refroidissant, est probablement d'autant plus grand que cet air est plus sec, parceque dans cet état, il est beaucoup plus avide d'humidité que quand il approche de son état de saturation.

"Enfin, la température de la boule mouillée est influencée encore autrement que par l'air immédiatement ambient, elle est soumise au rayonnement de l'enceinte dont l'influence sera variable suivant l'état d'agitation de l'air.

"Il me parait *impossible de faire entrer toutes ces circonstances dans le calcul théoretique de l'instrument*; est je crois qu'il est plus sage de ne faire servir les considérations théoretiques qu'à la recherche de la forme de la fonction, et à *déterminer ensuite les constantes par des expériences* faites dans les conditions déterminées. Cette

* Annalen der Physik, B. v. p. 87.

manière d'opérer me parait d'autant plus nécessaire, *qu'il reste beaucoup d'incertitude sur plusieurs des élements numériques que entrent dans le* calcul, notamment *sur la chaleur spécifique de l'air, sur celle de la vapeur, et sur la chaleur absorbée par l'eau lorsqu'elle se vaporise dans l'air.*"—(P. 212.)

These are the opinions of M. REGNAULT expressed twenty years after AUGUST had invented his formula, and after his own elaborate experiments; and I have preferred giving them in his own language to free myself from any possible misconstruction in translation. M. REGNAULT thought that AUGUST's formula modified by him, would meet some of the difficulties expressed by him in the above quoted opinions, and he gives tables of results, which, with a limited range of the thermometer and small depressions, are sufficiently satisfactory; but he candidly admits "l'accord a été *beaucoup* moins parfait dans les bas températures et dans l'air très humide;" in these cases M. REGNAULT says the fractions of saturation calculated are always above the fractions of saturation obtained by direct means, often to a very notable extent. M. REGNAULT got one of his pupils to try the psychrometer, under considerably diminished pressure, on the mountains in Switzerland, but the results were so little satisfactory that he does not give a detail of them. He induced also his friend M. IZARN, to compare the readings of the wet bulb in the Pyrenees, at a pressure of 700 millims. (27·559 in.), with the readings of an hygrometer invented by himself, which he calls "hygromètre condenseur," and which he considers to be free from the objections to which DANIELL's hygrometer is subject; and in a table given, the fractions of saturation are almost always much higher by the wet bulb than by the condenser, the depression in no case exceeding 3°·91. In a depression of 1°·97, the differences of the fraction of saturation are respectively 0·7542 and 0·7937. Finally, M. REGNAULT says that his modified formula may give the elastic force of $x$ a little too high, and that the coefficient 0·480 might be used instead when the fraction of saturation exceeds 0·40 Centigrade, but that the coefficient 0·429 gives results nearer to the truth where the fraction of saturation is below 0·40. When the wet bulb descends below zero, he considers that the value of $\lambda$ should be increased from 610 to 689, but in the present imperfect knowledge of the true numerical value of several of the elements he will not venture to put forth a new formula for the psychrometer (p. 227). Several other philosophers have also given formulæ: BURG from observation, $f''=f'-\cdot0004528(t-t')p$; BOHNENBERGER also from observation, $f''=f'-\cdot0003962(t-t')p$; also KUPFFER, ERMAN and KAMTZ.

On the 24th of November 1834 and 27th of April 1835, Dr. APJOHN of Dublin read to the Royal Irish Academy a very elaborate and able paper upon the theory of the moist bulb hygrometer. The results of his observations, experiments and theoretical considerations, induced him to adopt the formula

$$f''=f'-\frac{d}{87}\times\frac{p}{30};$$

at p. 426 of the volume of the Proceedings of the Royal Irish Academy for 1840, the formula is

$$f''=f'-\frac{48a(t-t')}{e}\times\frac{p-f'}{30};$$

and finally, with the coefficient

$$f''=f'-\cdot01147(t-t')\times\frac{p-f'}{30}*;$$

and with this formula† Colonel Boileau of the Bengal Engineers, in charge of the Magnetic Observatory at Simla, to aid meteorologists, has calculated a series of tables of the tension of vapour from minus 10° Fahr. to 170° Fahr. for 30° of depression of the wet bulb by tenths, and for variations of pressure from 19 inches to 31 inches. It was these tables I used in the reduction of the preceding wet bulb observations; and it was in the progress of their use, during several months' labour, that at certain temperatures doubts were raised in my mind respecting the accuracy of the formula, from supposing the fraction of saturation unreasonably high when the depression of the wet bulb was inconsiderable, and unreasonably low when the depression of the wet bulb was considerable. The tension of vapour at considerable depressions startled me, until at last I found in testing the tables that with a depression of the wet bulb of 19° at a temperature of 52° Fahr., and at a pressure of 29 or 30 inches, the results became impossible; that is to say, the tension of vapour of the dew-point arrived at by the formula had a greater numerical value than the tension of vapour at the temperature of the wet bulb, *e. g.*

| | Fahr. | Bar. in. |
|---|---|---|
| Dry bulb | 52° | 30 |
| Wet bulb | 33 | . . . . . 20640 |
| Difference | 19=(*a*)=·01147 | $(t-t')$=21794 |

It is objected that a depression of the *wet* bulb of 19°, at a temperature of 52°, never can occur in nature‡: but very considerable depressions, both of the wet

* Apjohn's formula is expressed in English measures: $f''$ is the force of aqueous vapour at the dew-point; $f'$ the tension of vapour at the temperature of evaporation; $a$ specific heat of air; $e$ the latent heat of aqueous vapour; $d$ the depression or difference between the temperature of the air and wet bulb $(t-t')$; $p$ the pressure of the air in inches.

† Differing little from August's formula, and converting it into the measures and scale used by August; for all practical purposes, the two formulæ are the same.

‡ In a synopsis of nine years' observations of the wet bulb at Mahabuleshwur, the following maximum depressions of the *wet* bulb occur in the respective months of the year:—

| Months. | Depression of the wet bulb. | Months. | Depression of the wet bulb. |
|---|---|---|---|
| | ° | | ° |
| January | 17·2 | July | 5·2 |
| February | 24·0 | August | 7·7 |
| March | 24·6 | September | 8·5 |
| April | 26·3 | October | 16·0 |
| May | 26·0 | November | 15·5 |
| June | 7·0 | December | 16·7 |

In a preceding page it was shown that water in bottles under wet straw, exposed to the wind at Ahmednugger, cooled down to 65° Fahr., the temperature of the air being 98°, difference 33°, barometer 28 inches, dew-point by Apjohn 41°·7, by Glaisher 48°·5.

bulb and of the dew-point, have been observed even in our damp climate at the Royal Observatory at Greenwich. For instance, in the records on the 6th of April 1845, at 6 P.M., the dry bulb was 52°·6, wet bulb 39°·2, and *dew-point* by DANIELL's hygrometer 22°. The depression of the wet bulb being 13°·4, the *dew-point* by APJOHN's formula would be 14°, by GLAISHER's factors 25°·8, and by DANIELL's hygrometer it is found to be 22°. Which of these dew-points is to be taken to give the real numerical value of the tension of vapour? At Greenwich, on the 3rd of June 1846, at 4 P.M., the dry bulb was 79°·1, and the dew-point by DANIELL's hygrometer 44°, the depression therefore 35°·1. But I have recorded in the Meteorology of the Deccan, a depression of 61° of DANIELL's hygrometer taking place before the deposition of dew; the temperature of the air being 90°, the dew-point 29°, at 4 P.M., on the 16th of February 1828, at Downd, near Pairgaon, on the Beema River*. Mr. GLAISHER, of the Royal Observatory, a most persevering and able observer, finding from experience that the formulæ in use with a constant coefficient did not give satisfactorily the dew-points at varying temperatures and varying depressions of the wet bulb, adopted a series of factors quite independent of theory, from the results of very extensive comparisons of simultaneous observations of the wet bulb with DANIELL's hygrometer. These comparisons extended over several years, and through several thousand observations. He found that "the dew-point temperature was so related to the temperatures of air and evaporation, that at the same temperature of the air, the difference of temperatures of air and of the dew-point, divided by the difference of the temperature of the air and evaporation, was constant, but that it was different at every different temperature." Arranging several thousand observations made during five years at Greenwich, and during three years at Toronto, and taking the mean value at every degree of temperature, he obtained a series of factors ranging from 8·5 at temperatures below 24° FAHR., up to 1·5 above 70° FAHR.; these were published in the volume of the Greenwich Magnetical and Meteorological Observations for 1842, 1843 and 1844. In 1847 Mr. GLAISHER published hygrometrical tables in which some slight alterations of the original factors were made, and he has since made some further slight modifications. For the limited range in temperature, depression of the wet bulb and pressure, in which the comparisons were made and the factors deduced, they are probably the very best agents (at least above the freezing-point) for giving a close approximation to the true value of the readings of the wet bulb; supposing always the wet bulb not to be subjected to the anomalous indications noticed by Professor ORLEBAR and M. REGNAULT. For considerable differences of barometrical pressure, and very considerable depressions of the wet bulb, the factors would require further correction. When the dew-point was obtained with difficulty by DANIELL's hygrometer, or in other words, when the depression of the temperature of evaporation was great, Mr. GLAISHER found that his method of determining his factors would not hold good, which he attributed to certain objec-

* Philosophical Transactions, Part I. for 1835, p. 184.

tions to DANIELL's hygrometer, and to which it is no doubt subject, but which are applicable to all temperatures and all depressions, objections which were urged by M. REGNAULT, and which induced him to invent his "hygromètre condenseur," an instrument which he pronounces to be free from the errors of DANIELL's instrument, but the use of which I have not heard of in England.

I have thus reviewed, *in extenso*, the possible, indeed the probable sources of error in the very high degree of humidity constantly in the air, as represented by the wet bulb observations made in India, and I have no hesitation in expressing my belief that the results, which I have obtained with the labour of some months, do not represent the real fractions of saturation of the air at the several places where the wet bulb was observed*; and I am the more confirmed in this opinion, with respect to the Neelgherries, by an officer now in London, who resided some time at Ootacamund and kept a meteorological register, who says that if the mean annual moisture in the air had amounted to anything like 90 per cent. it must have been most inconveniently felt in the clothes, hats, bedding and furniture of the residents; but so far from such being the case, that, with the exception of occasional fogs, the hills were looked upon as rather dry than otherwise. From my doubts respecting the correctness of the deduced fraction of saturation of the air at places in India, with the formulæ I have passed in review, I may possibly except the observations made in the Deccan with DANIELL's hygrometer, which observations have a semblance of truth, although the instrument may be imperfect. Even with a comparatively low mean annual percentage of 55 of moisture in the air, I would say such fraction of saturation was rather higher than the truth, for during some months of the year in the Deccan the air is so dry that it is difficult to prevent the disposition of the leaves of tables to curl up into hollow cylinders, and the nib of a quill pen is always most provokingly straddling out into the form of a pair of open compasses.

By reason of the above-noticed sources of error in the wet bulb itself, and of the inadequacy of the formulæ to give a satisfactory value to its readings, supposing the indications to be correct, I have deliberately *not* applied any corrections to the readings of the barometer on account of moisture. But even had the instrument been free from error and the formulæ exact, I still should have deemed it ineffectual to attempt to measure the moisture in a whole column of the atmosphere *from a local observation*† with a view to apply to the barometer, which represents the pressure of an entire column of the atmosphere, a correction for the tension of vapour‡. Further, I have doubts of the propriety of applying to the barometer a correction for

* Dr. M'CLELLAND says, "The wet bulb thermometer would add greatly to the value of these results, but there are discrepancies in the register of the instrument in use (at Calcutta) which *prove it to be imperfect*."—Calcutta Journal of Nat. Hist., vol. v. p. 554.

† "This instrument [wet bulb] simply indicates the conditions of the air of the place where it is situated: at 100 feet above it the conditions may be very different."—GLAISHER's Hygrometrical Tables, p. 16, edition of 1847.

‡ The capacity of air to hold water in solution, or in a state of vapour, diminishes with the temperature.

moisture *subtractively*, even were the tension of vapour satisfactorily determined for the *whole pressure*. The barometer *falls* with increasing saturation of the atmosphere with moisture, indicating the displacement of comparatively dry air by *dilated* vapour, the density of which is less than that of drier air, and a certain amount of pressure is taken off the barometer and the mercury falls on account of the diminished density and elasticity of humid air; but as soon as this vapour is condensed into rain the drier air resumes its ordinary density and elasticity, and the mercury mounts again. If the vapour came simply as an *addition* to the drier air, the density and pressure of the compound should increase, and the barometer should rise; but this is contrary to fact. I would therefore not apply a subtractive correction for that vapour, which has already acted directly upon the barometer in diminishing pressure by displacing denser air. The object of applying any corrections at all to the barometer, on account of moisture in the atmosphere, is stated to be to "obtain from them the pressure of the atmosphere of dry air*;" but as such a state of the air is a physical impossibility as long as there is a drop of water upon the earth to be vaporized, as evaporation goes on at all temperatures, it may be asked, what practical advantage can be obtained from any such determination? and the more so, may the question be asked, when experimenters are not in accord with respect to the numerical values of the tension of vapour at different temperatures to be applied as corrections†.

On the whole it appears very desirable that to DIRECT MEANS recourse should always be had, if possible, for the determination of the dew-point, to DANIELL's hygrometer, or to REGNAULT's condensing hygrometer; and short of this, that persevering comparisons should be made for years, in *extended* ranges of *temperature*, *depression* and *pressure*, and at different elevations, to obtain a more trustworthy wet bulb formula, or an unquestionable series of factors.

## *Rain.*

If it were necessary to suggest caution in generalizations from a limited number of local observations for the determination of the dew-point, caution is equally, if not more necessary in attempting to fix the normal rain-fall even in a narrow area, much less in a district or province. For instance, within the limits of part of the small island of Bombay, seven miles by two miles, the following is the result of observations with nine rain-gauges. The Fort and Esplanade are necessarily proximate; the Observatory at Colabah two miles distant, and the most remote gauge at the Government House at Parell, only five miles from the Fort, the other stations being intermediate between the Fort and Parell.

* GLAISHER's Hygrometrical Tables, p. 12, edition of 1847.

† At 32° FAHR. DALTON's tension of vapour, in inches of mercury, is 0·200, at 95°=1·59297, at 122°=3·500 in. The Physical Committee of the Royal Society adopted for 32° FAHR. 0·186, and for 95°=1·610, and 122° FAHR. 3·542; REGNAULT, at 32° FAHR., has 0·18124, and at 95° FAHR. 1·64380, and at 122°=3·619. KAEMTZ, at 32° FAHR., has 0·17999, and at 95° FAHR. 1·57789; of course different results are come at by the use of these different values.

## Bombay, 1849. Rain-fall.

| | Colabah Observatory. | Fort. | Esplanade. | Byculla. | Chinchpoogly. | Airy Cottage, Mazagon. | Agricultural garden, Parell. | Parell Flagstaff. | Parell Hill. |
|---|---|---|---|---|---|---|---|---|---|
| | in. | in. | in. | in. | in. | in. | in. | in. | in. |
| 1 | 0·86 | 0·36 | 0·28 | 0·40 | 0·00 | 0·35 | 0·00 | 0·00 | 0·00 |
| 2 | 0·00 | 0·00 | 0·00 | 0·00 | 0·00 | 0·04 | 0·35 | 0·00 | 0·30 |
| 3 | 0·39 | 0·14 | 0·00 | 0·06 | 0·00 | 0·03 | 0·05 | 0·06 | 0·05 |
| 4 | 0·39 | 0·55 | 0·76 | 0·58 | 0·00 | 0·70 | 0·66 | 1·23 | 0·55 |
| 5 | 0·31 | 0·21 | 0·12 | 0·08 | 0·00 | 1·50 | 0·55 | 0·80 | 0·55 |
| 6 | 0·00 | 0·00 | 0·00 | 0·02 | 0·00 | | 0·30 | 0·46 | 0·25 |
| 7 | 0·25 | 0·10 | 0·06 | 0·00 | 0·00 | 0·00 | 0·00 | 0·00 | 0·00 |
| 8 | 0·00 | 0·00 | 0·00 | 0·04 | 0·00 | 0·00 | 0·10 | 0·00 | 0·10 |
| 9 | 0·00 | 0·03 | 0·00 | 0·03 | 0·00 | 0·00 | 0·00 | 0·00 | 0·00 |
| 10 | 0·00 | 0·01 | 0·00 | 0·00 | 0·00 | 0·00 | 0·15 | 0·10 | 0·20 |
| 11 | 0·16 | 0·32 | 0·27 | 0·88 | 0·00 | 0·09 | 0·30 | 0·70 | 0·30 |
| 12 | 3·14 | 1·78 | 1·35 | 1·06 | 0·00 | 1·26 | 0·82 | 1·92 | 0·95 |
| 13 | 0·34 | 0·00 | 0·00 | 0·08 | 4·00† | 0·00 | 1·20 | 2·16 | 1·30 |
| 14 | 0·00 | 0·00 | 0·00 | 0·02 | 1·86 | 1·70 | 0·00 | 0·00 | 0·00 |
| 15 | 0·00 | 0·83 | 1·57 | 1·43 | 2·25 | 0·00 | 1·25 | 2·18 | 1·30 |
| 16 | 4·20 | 4·65 | 2·10 | 3·76 | 4·75 | 5·00 | 3·50 | 6·79 | 3·70 |
| 17 | 4·61 | 2·34 | 2·60 | 2·22 | 2·54 | 2·25 | 3·30 | 7·58 | 3·35 |
| 18 | 0·65 | 0·86 | 1·01 | 1·09 | 1·10 | 0·06 | 1·35 | 3·56 | 1·50 |
| 19 | 0·16 | 2·25 | 1·81 | 1·34 | 0·75 | 2·58 | 1·65 | 3·38 | 1·50 |
| 20 | 1·77 | 5·22 | 2·20 | 4·55 | 4·67 | 4·70 | 0·90 | 1·60 | 0·70 |
| 21 | 3·34 | 0·40 | 0·50 | 0·43 | 0·55 | 0·74 | 3·95 | 11·10 | 4·10 |
| 22 | 4·46 | 4·28 | 4·38 | 3·93 | 5·11 | 4·70 | 3·50 | 7·66 | 3·40 |
| 23 | 0·21 | 0·11 | 0·10 | 0·13 | 0·24 | 0·30 | 3·80 | 5·88 | 3·70 |
| 24 | 3·62 | 4·53 | 5·20 | 5·22 | 6·00 | 6·43 | 0·43 | 0·90 | 0·45 |
| 25 | 3·93 | 10·51 | 6·73 | 7·10* | 7·50‡ | 11·75§ | 5·40 | 13·72 | 5·50 |
| 26 | 5·72 | 1·26 | 1·50 | 0·85 | 0·85 | 1·05 | 4·95 | 9·00 | 4·90 |
| 27 | 1·25 | 1·27 | 1·86 | 3·35 | 2·55 | 2·70 | 1·25 | 1·90 | 1·25 |
| 28 | 2·22 | 2·54 | 3·00 | 2·28 | 2·80 | 3·25 | 6·25 | 11·50 | 6·10 |
| 29 | 2·78 | 1·90 | 2·50 | 2·13 | 2·20 | 2·90 | 2·10 | 2·85 | 2·15 |
| 30 | 1·41 | 1·55 | 2·15 | 1·42 | 2·55 | 2·70 | 2·15 | 3·40 | 2·40 |
| 31 | 2·47 | 3·68 | 4·50 | 4·57 | 3·75 | 4·40 | 2·35 | 3·15 | 2·45 |
| July | 48·67 | 51·68 | 46·55 | 49·05 | 56·02 | 61·23 | 52·50 | 102·14‖ | 53·00 |
| June | 23·37 | 22·82 | 23·34 | 19·40 | ..... | 25·56 | 28·54 | 46·60 | 26·71 |
| Totals | 72·04 | 74·50 | 69·89 | 68·45 | ..... | 86·79 | 81·04 | 148·74 | 79·71 |

It is seen that in June the fall of rain varied from 19·46 in. at Bycalla to 46·60 in. at the flagstaff at Parell, and in July from 46·55 in. on the Esplanade to 102·14 in. at the flagstaff at Parell; or omitting this as a doubtful return, to 61·23 in. at Airy Cottage, Mazagon; and the total of the two months varies from 68·15 in. to 86·79 (omitting the gauge at the Parell flagstaff) at Airy Cottage. I do not know whether the investigations were carried out for a whole monsoon, but in case the discrepancies continued, it would be difficult to determine the normal fall of rain in Bombay. But the anomaly is not confined to Bombay; Dr. Murray, in a paper published in the Journal of the Physical Society of Bombay, No. 9, p. 172, has the following

* Gauge overflowed. † No register kept for first thirteen days—4 inches set down at guess.

‡ Gauge overflowed.

§ The gauge was running over, but this seems pretty nearly all that fell. It poured in torrents from 5 P.M. on the 25th till 6 A.M. 26th.

‖ The difference here is the same as last month (twice as much of fall being set down here as fell everywhere else); and so enormous and unaccountable as to lead to the inference of some tremendous blunder.

observations respecting the fall of rain in the town of Sattarah and military cantonment adjoining: "The quantity of rain in the town of Sattarah usually exceeds that in the cantonment, situated a mile N.E., by 6 or 8 inches." Annexed are the results, to which he has added the fall at his own bungalow or house, equidistant between the town and cantonment, so that the three localities are within the range of a mile.

| Years. | 1844. | 1845. | 1846. | 1847. | 1848. |
|---|---|---|---|---|---|
| Town Hospital | ..... | 44·39 | 42·92 | 43·17 | 33·41 |
| Dr. MURRAY's bungalow | 36·06 | 40·24 | 39·52 | 40·98 | |
| Cantonment Hospital | ..... | 38·34 | 31·65 | 39·00 | 27·81 |
| Hill Fort, above the town of Sattarah... | ..... | ..... | ..... | ..... | 39·36 |

The increased fall of rain in the town of Sattarah, which is 2320 feet above the sea-level, is no doubt chiefly caused by the hill, 3200 feet above the sea-level, upon which the fort is situated, rising from the back of the town; but this will not account for the difference in the fall at the Bungalow and Cantonment Hospital. The facts show how necessary is a local knowledge of physical features before generalizations can be ventured upon safely.

In my former paper in the Philosophical Transactions I pointed out the remarkable differences in the fall of rain, twenty to twenty-five years ago on the sea coast, at the top of the Ghâts, and at Poona, thirty-five miles to the eastward of the Ghâts. Dr. MURRAY confirms my views in a much more detailed manner than I was enabled to attempt, in the following Table for the year 1848:—

| | Bombay. | Ghâts. | | Western Districts. | | | | | | | Eastern districts. | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | Mahabuleshwur. | | | | Sattarah. | | | Bhore. | Wye. | Phultun. | Jhutt. | Bijapoor. | Punderpoor. | Akalkote. |
| | Means of 33 years. | Sanatarium, means 14 years. | Sindola, 1848. | Meera. | Enteshwar. | Hill Fort. | Town. | Cantonment. | | | | | | | |
| January | ..... | 0·05 | | | | | | | | | | | | | |
| February | ..... | 0·20 | | | | | | | | | | | | | |
| March | ..... | 0·15 | ..... | ..... | ..... | ..... | 0·80 | 0·04 | | | | | | | |
| April | ..... | 1·31 | ..... | ..... | ..... | ..... | 0·74 | 0·76 | | | | | | | |
| May | 3·31 | 3·60 | 9·75 | 2·60 | 2·50 | 3·04 | 2·79 | 2·10 | 2·09 | 6·24 | ..... | ..... | 0·75 | 1·83 | |
| June | 22·26 | 46·53 | 41·70 | 10·93 | 5·98 | 4·10 | 3·71 | 3·26 | 2·37 | 2·20 | 4·30 | 1·59 | 0·80 | 2·02 | 3·68 |
| July | 25·04 | 92·10 | 74·28 | 22·90 | 19·83 | 18·77 | 14·64 | 12·02 | 13·20 | 9·05 | 2·70 | 3·07 | 3·67 | 4·38 | 4·65 |
| August | 17·08 | 72·33 | 47·81 | 6·16 | 6·02 | 5·00 | 2·60 | 2·55 | 5·19 | 1·61 | 1·24 | 4·82 | 8·52 | 6·21 | 4·83 |
| September | 11·25 | 31·32 | 6·17 | 2·30 | 1·80 | 1·46 | 2·14 | 1·40 | 0·91 | 0·96 | 3·66 | 2·64 | 4·01 | 4·35 | 2·84 |
| October | 1·19 | 4·58 | 7·23 | 2·75 | 2·27 | 4·64 | 4·89 | 3·28 | 1·50 | 2·75 | 2·45 | 3·88 | 4·64 | 8·35 | 5·32 |
| November | ..... | 2·07 | 4·37 | 1·85 | 0·19 | 2·91 | 1·57 | 1·71 | 4·15 | 2·25 | 3·59 | 2·17 | 3·78 | 2·49 | 2·30 |
| December | ..... | 0·05 | | | | | | | | | | | | | |
| Year | 76·82 | 254·05 | 185·16 | 49·64 | 38·69 | 39·38 | 33·41 | 27·81 | 29·42 | 20·73 | 24·18 | 18·17 | 25·42 | 28·55 | 25·45 |

With the exception of Bombay and the Sanatarium at Mahabuleshwur, the records are for the year 1848. The following are the respective elevations of the places above the sea-level:—

| Mahabuleshwur. | Sindola. | Meera. | Enteshwar. | Sattarah Fort. | Sattarah Town. | Sattarah Cantonment. | Bhore. | Wye. | Phultun. | Jhutt. | Bijapoor. | Punderpoor. | Akalkote. |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 4500 | 4600 | 2340 | 3700 | 3200 | 2320 | 2320 | 2350? | 2320? | 2000? | 2000? | 2000? | 2000? | 2000? |

Dr. Murray adds, "The prodigious influence of the Ghâts in modifying the amount of the S.W. monsoon rain, is perhaps nowhere more strikingly shown than in the N.W. parts of the Sattarah territory. If we draw a line nearly straight from west to east, from Mahabuleshwur, on the summit of the Ghâts, to Phultun, a distance of little more than forty miles, we shall find at the commencement of the line a rain-fall of 240 inches, at an altitude of 4500 feet; 180 inches at Sindola, *a mile distant*, and elevated 4600 feet; 50 inches at Paunchgunnee, at a further distance of eleven miles and an elevation of 4000 feet; 25 inches at Wye, four miles further east and 2300 feet in height above the sea, while at the extremity of the line at Phultun, thirty miles from Sattarah, and about the same level as Wye, the quantity is reduced to 7 or 8 inches." But Dr. Murray must have meant during the S.W. monsoon, as he had previously represented the fall of rain at Phultun at 24·18 in. in 1848, in 1847 at 24·04 in., and in 1846 at 18·09 in. Some inches of those amounts however are attributable to the Madras monsoon, which commences in October, when the Malabar coast monsoon terminates, and Phultun, from its easterly position, gets an uncertain sprinkling from the Madras side.

Dr. Murray, with a view to show not only the discrepancies in the total annual fall of rain at places within comparatively limited distances situated on the plateau of the Deccan, but the remarkable contrasts in the monthly fall at two proximate places, has given the following Table of the fall of rain at Sattarah and Phultun for 1846 and 1847, Phultun being thirty miles east of Sattarah:—

| | Sattarah. | | Phultun. | |
|---|---|---|---|---|
| | 1846. | 1847. | 1846. | 1847. |
| January | 0·18 | | | |
| February | 0·18 | ..... | ..... | 0·02 |
| March | ..... | 0·18 | ..... | 0·52 |
| April | ..... | 10·88 | 1·44 | 4·19 |
| May | 3·49 | 0·39 | 1·06 | 2·88 |
| June | 10·49 | 3·77 | 3·80 | 1·53 |
| July | 16·04 | 6·28 | 1·95 | 0·84 |
| August | 2·13 | 2·68 | ..... | 0·50 |
| September | 0·77 | 3·55 | 1·05 | 2·00 |
| October | 2·98 | 5·25 | 2·50 | 3·06 |
| November | 0·98 | 8·00 | 5·04 | 4·60 |
| December | 2·46 | 0·05 | 1·53 | 0·89 |
| Year | 39·52 | 40·98 | 18·09 | 24·04 |

Dr. Murray, in a paper published in the autumn Number of the Journal of the Physical Society of Bombay for 1849, adds to the proofs of the extraordinary discrepancies in the fall of rain in proximate localities. He states (page 18), "At the Sanatarium at Mahabuleshwur, at 4500 feet, the rain-fall during 1848 was 245 inches, being within 3 inches of the average fall during the preceding twenty years. At Sindola, the residence of Mr. Frere (the British minister), situated *a mile* east from

the Sanatarium, about 100 feet higher, with the *intervening* eminence of Mount Charlotte rising to a further height of 100 feet, the quantity of rain did not exceed 185 inches during the same period; hence a difference of 60 inches or 24 per cent. at two houses *situated at the same station.* The position of the ground explains the difference, but probably few people, on examining the localities, would have anticipated its amount. It shows the supreme importance of instituting multiplied observations, before deciding on the site of a sanitary hill station."

To add to the means of comparison, some other rain-fall localities from the sea-coast, and Konkun, or country between the Ghâts and the sea,—from the Ghâts and from the plateau of the Deccan, are annexed, being the mean fall for the years 1844–47.

| Sea-coast of Konkun. | | Konkun, somewhat inland. | | Western Ghâts. | | Western Ghâts, East branch. | Deccan. | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Bombay, sea-level. | Ratnagherry, 150 feet. | Tanna, sea-level. | Dapoolee, 900 feet. | Kundalla, 1740 feet, 1833 and 1835. | Mahabuleshwur, 4500 feet. | Paunchgunnee, 4000 feet, 1835, 1842 and 1843. | Sattarah, 2339 feet. | Kolapoor, 1847. | Poona, 1842 feet. | Nassick. | Belgaum, 2000 feet. | Dharwar. | Ahmednugger, 1900 feet. | Sholapoor, 1847. |
| 68·73 | 114·55 | 106·16 | 134·96 | 141·59 | 254·84 | 50·69 | 39·20 | 20·74 | 19·02 | 26·72 | 40·90 | 38·81 | 21·83 | 32·16 |

Tanna and Dapoolee are situated between the sea-coast and the foot of the Ghâts. Kundalla is on the crest of the Ghâts on the high road from Bombay to Poona. The places in the Deccan lie eastward of the Ghâts. Arranging the above places according to their supply of rain, it appears the greatest fall is on the crest of the Ghâts, increasing from 141·59 inches at Kundalla at 1740 feet to a mean fall of 254·84 inches at Mahabuleshwur, at 4500 feet. From the crest of the Ghâts the supply of rain decreases towards the sea-coast westward, but decreases in an infinitely greater ratio eastward on the plateau of the Deccan. Along the coast the supply of rain diminishes with the increase in latitude.

In further illustration of the unequal fall of rain in the Bombay Presidency, the returns for May, June and July 1849 are annexed. They are the latest I have received except from Bombay.

| | Bombay. | Poona. | Surat. | Nassick. | Asseerghur. | Ahmedabad. | Phoonda Ghât. | Mahabuleshwur. | Paunchgunnee. | Calcutta. |
|---|---|---|---|---|---|---|---|---|---|---|
| May ..... | 0·00 | 0·405 | 0·00 | 0·00 | 0·23 | 2·03 | 0·00 | 0·00 | ..... | 6·00 |
| June ..... | 22·82 | 9·055 | 11·16 | 8·63 | 5·45 | 4·10 | 50·00 | 59·90 | ..... | 13·0 |
| July ..... | 51·68 | 6·425 | 19·00 | 7·03 | 16·31 | 7·62 | 83·00 | 89·24 | ..... | 8·25 |
| Total ..... | 74·50 | 15·885 | 30·16 | 15·66 | 21·99 | 13·75 | 133·00 | 149·14 | 11·95 | 27·25 |

To General CULLEN of the Madras Artillery, and British minister, with the Rajah of Travancore, I am indebted for the following comparison of rain-fall at stations on the coast of Malabar and Coromandel:—

| | Years. | January. | February. | March. | April. | May. | June. | July. | August. | September. | October. | November. | December. | Total. |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 20 feet. Cochin. | 1842. | ... | ... | ... | 3·05 | 25·07 | 25·05 | 13·70 | 21·95 | 10·15 | 3·55 | 3·65 | ..... | 105·27 |
| | 1843. | 5·15 | ... | 2·00 | 4·50 | 27·15 | 37·32 | 21·05 | 4·27 | 7·75 | 9·45 | 0·10 | 5·75 | 124·49 |
| | 1844. | ... | 0·45 | 1·70 | 1·70 | 19·35 | 22·42 | 19·10 | 11·75 | 2·37 | 17·55 | 4·50 | 1·07 | 101·97 |
| | 1845. | 3·42 | ... | 5·80 | 2·20 | 3·57 | 31·37 | 16·10 | 11·22 | 1·67 | 11·85 | 0·92 | 4·45 | 92·60 |
| | 1846. | 0·02 | ... | 0·70 | 4·80 | 19·70 | 37·32 | 16·72 | 16·27 | 2·15 | 5·95 | 2·25 | 0·10 | 106·00 |
| Means ..... | ..... | 1·72 | 0·09 | 2·04 | 3·25 | 18·97 | 30·69 | 17·33 | 13·09 | 4·82 | 9·67 | 2·28 | 2·27 | 106·06 |
| 30 feet. Quilon. | 1842. | ... | 1·17 | 1·32 | 3·30 | 22·24 | 16·00 | 8·65 | 8·60 | 7·42 | 4·87 | 7·47 | ..... | 81·06 |
| | 1843. | 1·42 | 0·47 | 0·50 | 9·85 | 24·62 | 26·52 | 20·72 | 7·45 | 5·15 | 5·85 | 2·15 | 1·00 | 105·72 |
| | 1844. | ... | ... | 0·55 | 0·70 | 8·15 | 15·55 | 5·75 | 6·70 | 2·37 | 13·95 | 3·25 | 3·60 | 60·57 |
| | 1845. | 3·30 | ... | 4·65 | 0·25 | 4·85 | 13·80 | 9·55 | 3·95 | 0·45 | 15·35 | 1·85 | 3·70 | 61·70 |
| | 1846. | ... | ... | 2·90 | 1·60 | 22·70 | 17·65 | 10·55 | 3·80 | 1·30 | 9·40 | 4·75 | 0·10 | 74·75 |
| Means ..... | ..... | 0·94 | 0·33 | 1·98 | 3·14 | 16·51 | 17·90 | 11·04 | 6·10 | 3·34 | 9·88 | 3·89 | 1·68 | 76·76 |
| 30 feet. Allepy. | 1842. | 1·15 | 0·25 | 2·92 | 2·50 | 27·67 | 20·00 | 10·60 | 12·30 | 7·57 | 12·95 | 6·50 | 0·10 | 104·52 |
| | 1843. | 3·20 | 0·75 | 6·90 | 5·75 | 30·12 | 32·80 | 21·57 | 5·22 | 9·72 | 9·12 | 0·90 | 5·77 | 131·85 |
| | 1844. | 0·37 | 2·87 | 2·55 | 3·00 | 24·33 | 23·12 | 16·60 | 10·42 | 4·92 | 15·37 | 9·90 | 5·40 | 118·70 |
| | 1845. | 4·92 | 0·50 | 8·80 | 2·65 | 17·80 | 25·20 | 11·92 | 6·47 | 1·00 | 9·67 | 4·35 | 4·50 | 97·80 |
| | 1846. | 0·00 | 1·70 | 0·20 | 3·15 | 31·45 | 29·00 | 12·45 | 12·27 | 3·42 | 13·00 | 5·77 | 1·00 | 113·43 |
| Means ..... | ..... | 1·93 | 1·21 | 4·27 | 3·41 | 26·27 | 26·02 | 14·63 | 9·33 | 5·32 | 12·02 | 5·48 | 3·35 | 113·26 |
| 50 feet. Cape Comorin. | 1843. | 0·90 | ... | ... | ... | 6·50 | 0·80 | 0·95 | ..... | 0·65 | 4·80 | ..... | 4·60 | 19·20 |
| | 1844. | ... | ... | ... | ... | 1·20 | 3·00 | ..... | ..... | 1·00 | 7·50 | 4·60 | 2·20 | 19·50 |
| | 1845. | 0·20 | ... | 0·90 | ... | 1·30 | 2·20 | 0·70 | ..... | ..... | 10·70 | 1·40 | Heavy shower | 18·00 |
| | 1846. | ... | ... | 2·80 | 3·30 | 9·40 | 12·25 | 1·20 | 1·45 | ..... | 12·10 | 9·82 | 4·40 | 56·72 |
| Means ..... | ..... | 0·27 | ... | 0·92 | 0·75 | 4·55 | 4·56 | 0·71 | 0·36 | 0·41 | 8·77 | 3·95 | 2·80 | 28·35 |
| 60 feet. Vaurioor, close to Cape Comorin. | 1842. | 0·35 | 0·65 | ... | ... | 2·25 | 1·20 | ..... | 0·40 | 1·82 | 4·35 | 9·25 | ..... | 20·27 |
| | 1843. | 1·40 | 1·00 | 0·75 | 0·40 | 9·90 | 2·05 | 0·80 | 0·10 | 0·35 | 4·15 | 0·45 | 4·40 | 25·75 |
| | 1844. | ... | 0·50 | 0·20 | ... | 0·90 | 3·00 | 0·80 | ..... | 0·15 | 7·45 | 3·70 | 1·35 | 18·05 |
| | 1845. | 2·75 | ... | 3·65 | ... | 1·70 | 1·45 | 2·70 | ..... | 0·35 | 12·92 | 2·40 | 8·90 | 36·82 |
| | 1846. | ... | ... | 0·90 | 1·65 | 5·20 | 2·90 | 0·55 | ..... | ..... | 4·00 | 5·50 | 1·75 | 22·45 |
| Means ..... | ..... | 0·90 | 0·43 | 1·10 | 0·41 | 3·99 | 2·12 | 0·97 | 0·10 | 0·53 | 6·57 | 4·26 | 3·28 | 24·67 |
| 130 feet. Trevandrum. | 1842. | 3·70 | 0·35 | 0·85 | 3·60 | 13·70 | 9·50 | 4·25 | 3·75 | 6·30 | 3·05 | 8·30 | 0·35 | 57·70 |
| | 1843. | 0·80 | 0·02 | 2·52 | 8·80 | 17·12 | 16·62 | 12·90 | 2·55 | 3·10 | 7·52 | 2·05 | 11·42 | 85·45 |
| | 1844. | ... | ... | 1·10 | 0·30 | 4·55 | 6·15 | 3·80 | 5·67 | 3·75 | 15·17 | 4·40 | 2·15 | 47·05 |
| | 1845. | 4·40 | 0·77 | 3·40 | 0·85 | 4·55 | 15·80 | 4·30 | 0·90 | 0·15 | 18·52 | 3·92 | 5·00 | 62·57 |
| | 1846. | 0·10 | ... | 1·07 | 4·02 | 11·42 | 17·75 | 6·92 | 3·67 | 0·75 | 17·50 | 4·40 | 2·30 | 69·92 |
| Means ..... | ..... | 1·80 | 0·23 | 1·79 | 3·51 | 10·27 | 13·16 | 6·53 | 3·31 | 2·81 | 12·35 | 4·61 | 4·24 | 64·54 |
| 200 feet. Palemcottah. | 1842. | 1·20 | 0·19 | 1·05 | 0·45 | 0·55 | 0·02 | 0·01 | 0·03 | 2·50 | 6·60 | 9·62 | 0·95 | 23·12 |
| | 1843. | 4·02 | 2·50 | 0·77 | 1·90 | 5·65 | ..... | ..... | ..... | ..... | 7·15 | 1·65 | 3·95 | 26·90 |
| | 1844. | 0·20 | 0·55 | ... | 0·75 | 0·10 | 1·17 | 0·05 | ..... | 1·75 | 2·65 | 1·70 | 2·76 | 11·68 |
| | 1845. | 0·43 | ... | 5·27 | 0·55 | 1·62 | 0·15 | ..... | ..... | 0·65 | 6·17 | 2·02 | 8·75 | 25·63 |
| | 1846. | 0·80 | 1·35 | 0·57 | 2·30 | 4·05 | 0·07 | 0·07 | ..... | 0·30 | 1·80 | 5·97 | 0·65 | 17·75 |
| Means ..... | ..... | 1·33 | 0·92 | 1·53 | 1·05 | 2·39 | 0·28 | 0·03 | 0·006 | 1·05 | 4·87 | 4·19 | 3·41 | 21·06 |
| 600 or 700 feet. Shenkottah. | 1842. | 1·20 | 1·30 | ... | 2·05 | 3·90 | 5·65 | 2·80 | 1·40 | 3·10 | 3·20 | 14·85 | ..... | 39·45 |
| | 1843. | 4·15 | 0·80 | 2·45 | 4·15 | 11·20 | 4·80 | 6·20 | 1·05 | 1·15 | 7·15 | 1·50 | 3·50 | 48·10 |
| | 1844. | ... | ... | 2·40 | ... | 0·50 | 3·60 | ..... | 1·80 | 1·60 | 6·25 | 4·25 | 3·70 | 24·10 |
| | 1845. | 2·00 | ... | 4·40 | 2·20 | ..... | 3·80 | 4·65 | 0·35 | ..... | 13·40 | 4·05 | 5·85 | 42·70 |
| | 1846. | 0·57 | ... | 0·70 | 4·65 | 6·20 | 8·60 | 3·40 | 1·10 | 2·50 | 5·95 | 4·47 | 3·45 | 41·60 |
| Means ..... | ..... | 1·58 | 0·42 | 1·99 | 2·61 | 4·36 | 5·29 | 3·41 | 1·14 | 1·67 | 7·59 | 5·82 | 3·30 | 39·19 |

The stations extend along the Travancore or western coast from Cape Comorin, lat. 8° 4′, to Cochin, lat. 10° 30′. Of the three stations on the Tinnevally or Coromandel coast, Shenkottah is near Courtallum, immediately at the east base of the Ghâts, and about sixty miles from the sea-coast of Travancore; Palamcottah is about thirty miles from the east base of the Ghâts, is sixty miles from the western coast, and in the latitude of Quilon; Vaurioor is only three miles north and a little east of Cape Comorin. The western and eastern stations are separated by the Ghâts, which in some places rise to a height of 6000 feet, but within ten miles of Cape Comorin they break off into separate groups and peaks of greatly diminished height.

Bearing in mind the preceding extraordinary discrepancies, not only in the annual and monthly fall of rain in the same locality and in proximate localities, I proceed to place in juxtaposition the fall of rain at various places in India, from such returns as are within my reach, from places at the sea-level and at different elevations above the sea-level; and it may well be a question how far even the means of many years' observations in any one locality, exhibit normal conditions for the fall of rain in circumscribed areas, much less for districts or provinces.

The relative positions of the stations on the Malabar and Coromandel coasts having been previously stated, it only remains to notice the places somewhat inland. Poona, at 1823 feet, is about forty miles eastward of the western scarp of the Ghâts, and about sixty miles as the crow flies from the sea-shore. Kotergherry, at 6100 feet, is part of the Neelgherry mountains, and lies a little to the eastward of the ridges of Dodabetta at a lower level of 2340 feet. Dodabetta is part of the Neelgherries, and the highest point of the peninsula of India. Mahabuleshwur, Mercara and Uttra Mullay, at the common level of 4500 feet, are nearly in the same meridian, but lie between 9° and 18° north latitude, and are situated near to the western scarp of the Ghâts. (See annexed Table.)

The first feature of this Table is the almost total want of rain at every station in the month of February, with the exception of Kotergherry and Dodabetta, and it may be accounted for by this month being intermediate between the times of the S.W. and N.E. monsoons; the former, on the Malabar coast, commencing in May and ending in October, and the latter commencing on the Coromandel coast in October and ending in January. The other two intermediate months, March and April, have very limited falls of rain, excepting at Kotergherry, Uttray Mullay and Dodabetta, at which places the supply is very liberal; indeed at Kotergherry and Dodabetta the maximum monthly fall of the year appears to occur in April, a month that belongs to neither the Malabar nor Coromandel monsoons, but as the wind at Dodabetta was almost entirely from northerly and easterly points, the supply of rain may be more reasonably considered to appertain to the tail of the N.E., rather than to the commencement of the S.W. monsoon. Poona, at 1823 feet, and Mahabuleshwur in the Deccan and Mercara in Coorg, at 4500 feet, have scarcely a sprinkling from the N.E. monsoon, and the months of December, January, February, March and April, may be

| | Madras, sea-level. | | | | | Calcutta, 18 feet. | | | | | | | | | Bombay, sea-level. | Malabar Coast. | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | | 4 feet. | 40 feet. | 4 feet. | 40 feet. | 4 feet. | 4 feet. | 4 feet. | 4 feet. | 40 feet. | | Cochin, 20 feet. | Quilon, 30 feet. | Allepy, 30 feet. | Trevandrum, 130 feet |
| | 1842. | 1843. | 1844. | 1845. | Means of 22 years, 1822 to 1843. | 1843. | 1843. | 1844. | 1844. | 1845. | 1846. | 1847. | 1848. | 1848. | Means of 32 years, 1817 to 1849. Monsoons. | Means, 1842 to 1846. | Means, 1842 to 1846. | Means, 1842 to 1846. | Means, 1842 to 1846. |
| January ..... | 1·76 | 6·40 | 0·67 | 1·51 | 1·33 | 1·67 | 1·55 | 0·22 | 0·20 | 1·10 | 0·82 | 0·0 | 0·0 | 0·0 | ..... | 1·72 | 0·94 | 1·93 | 1·80 |
| February ... | 0·0 | 0·03 | 0·49 | 0·0 | 0·23 | 0·64 | 0·49 | 0·08 | 0·05 | 0·64 | 1·80 | 0·0 | 0·0 | 0·10 | ..... | 0·09 | 0·33 | 1·21 | 0·23 |
| March..... | 0·25 | 0·79 | 0·0 | 0·04 | 0·36 | 1·20 | 0·92 | 0·22 | 0·15 | 1·17 | 2·30 | 0·0 | 0·41 | 0·32 | ..... | 2·04 | 1·98 | 4·27 | 1·79 |
| April ..... | 0·00 | 0·04 | 0·00 | 0·04 | 0·63 | 2·42 | 2·04 | 3·13 | 2·63 | 7·30 | 0·57 | 2·33 | 1·31 | 1·12 | ..... | 3·25 | 3·14 | 3·41 | 3·51 |
| May ..... | 0·37 | 14·07 | 2·70 | 1·51 | 1·03 | 5·33 | 4·43 | 7·44 | 6·29 | 2·58 | 2·49 | 4·79 | 6·22 | 5·51 | ..... | 18·97 | 16·51 | 26·27 | 10·27 |
| June ..... | 1·51 | 1·93 | 2·66 | 2·36 | 2·03 | 8·64 | 7·62 | 12·13 | 9·95 | 10·66 | 12·14 | 12·01 | 13·52 | 12·68 | 22·26 | 30·69 | 17·90 | 26·02 | 13·66 |
| July ..... | 3·42 | 1·39 | 3·22 | 2·90 | 3·20 | 10·18 | 8·67 | 13·72 | 11·40 | 12·80 | 20·07 | 15·69 | 17·50 | 16·09 | 25·04 | 17·33 | 11·04 | 14·63 | 6·53 |
| August ..... | 3·07 | 2·20 | 2·66 | 2·01 | 5·24 | 20·05 | 17·99 | 26·91 | 22·89 | 15·36 | 13·26 | 15·09 | 9·22 | 7·00 | 17·08 | 13·09 | 6·10 | 9·33 | 3·31 |
| September ... | 5·56 | 4·14 | 12·42 | 4·09 | 4·76 | 11·19 | 9·92 | 5·02 | 4·25 | 4·80 | 9·97 | 10·95 | 4·74 | 4·10 | 11·25 | 4·82 | 3·34 | 5·32 | 2·81 |
| October ..... | 7·99 | 6·25 | 13·50 | 3·36 | 10·09 | 2·16 | 1·88 | 4·99 | 4·54 | 5·86 | 10·76 | 5·86 | 5·41 | 5·18 | *1·19 | 9·67 | 9·88 | 12·02 | 12·33 |
| November ... | 12·32 | 5·27 | 3·67 | 5·12 | 12·42 | 0·0 | 0·0 | 0·0 | 0·0 | 0·0 | 0·74 | 5·59 | 0·20 | 0·13 | ..... | 2·28 | 3·89 | 5·48 | 4·61 |
| December ... | 0·19 | 7·25 | 2·32 | 15·33 | 3·25 | 0·86 | 0·79 | 0·0 | 0·0 | 0·81 | 1·52 | 0·05 | 0·16 | 0·09 | ..... | 2·27 | 1·68 | 3·35 | 4·24 |
| Year ..... | 36·39 | 49·76 | 44·31 | 38·27 | 44·57 | 64·34 | 56·30 | 73·86 | 62·35 | 63·08 | 76·44 | 72·38 | 58·69 | 52·32 | 76·82 | 106·06 | 76·76 | 113·26 | 64·54 |

[Lieut.-Colonel SYKES's Discussion of Meteorological Observations taken in India.]

* This average is for t

FRANKLIN INSTITUTE LIBRARY

[*To face page* 358]

| evan-rum, feet. | Cape Comorin, 50 feet. | Coromandel Coast. | | | | Poona, 1823 feet. | | | | | Mahabuleshwur, 4500 feet. | | | Mercara in Coorg, 4500 feet. | Uttray Mullay, 4500 feet. | | Doda-betta, 8640 feet. | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| eans, 42 to 846. | 1843 to 1846. | Vauriocor, 60 feet. | Palamcottah, 200 feet. | Shenkottah, 600 or 700 feet. | Kotergherry, 6100 feet. | 1826. | 1827. | 1828. | 1829. | 1830. | Means of 15 years. | 1834. | 1842. | Means, 1838 to 1840. | 1845. | 1846. | 1847, 1848. | |
| 1·80 | 0·27 | 0·90 | 1·33 | 1·58 | 1·74 | 0·0 | 2·29 | 0·0 | 0·0 | 0·0 | 0·05 | 0·0 | 0·66 | 0·00 | 8·40 | 4·65 | 0·12 | January. |
| 0·23 | ..... | 0·43 | 0·92 | 0·42 | 13·88 | 0·0 | 0·0 | 0·0 | 0·0 | 0·0 | 0·25 | 0·25 | 0·0 | 0·45 | 0·15 | 0·45 | 7·43 | February. |
| 1·79 | 0·92 | 1·10 | 1·53 | 1·99 | 6·88 | 0·0 | 0·4 | 0·0 | 0·0 | 0·0 | 0·15 | 0·0 | 0·02 | 1·51 | 14·20 | 0·73 | 3·61 | March. |
| 3·51 | 0·75 | 0·41 | 1·05 | 2·61 | 18·56 | 0·0 | 0·0 | 0·0 | 0·0 | 1·04 | 1·31 | { Two showers. } | 0·0 | 2·60 | 1·37 | 9·60 | 19·80 | April. |
| 0·27 | 4·55 | 3·99 | 2·39 | 4·36 | No record. | 3·41 | 0·04 | 1·95 | 2·74 | 0·79 | 3·31 | 0·16 | 3·74 | 7·37 | 22·68 | 36·50 | 4·86 | May. |
| 3·66 | 4·56 | 2·12 | 0·28 | 5·29 | 0·41 | 3·30 | 13·47 | 1·63 | 4·86 | 5·57 | 46·53 | 32·03 | 37·86 | 30·40 | 52·15 | 51·05 | 4·55 | June. |
| 6·53 | 0·71 | 0·97 | 0·003 | 3·41 | 3·70 | 8·43 | 1·79 | 7·58 | 4·38 | 5·35 | 92·10 | 118·60 | 117·76 | 55·88 | 50·15 | 33·32 | 7·45 | July. |
| 3·31 | 0·36 | 0·12 | 0·006 | 1·14 | 2·66 | 1·03 | 2·01 | 3·35 | 3·21 | 1·72 | 72·33 | 75·91 | 77·75 | 27·00 | 25·57 | 21·12 | 9·32 | August. |
| 2·81 | 0·41 | 0·53 | 1·05 | 1·67 | 1·36 | 1·54 | 4·51 | 6·92 | 0·33 | 0·29 | 31·32 | 65·97 | 56·00 | 11·91 | 8·08 | 7·33 | 7·52 | September. |
| 2·35 | 8·77 | 6·51 | 4·87 | 7·59 | 12·33 | 1·90 | 4·33 | 6·34 | 1·81 | 3·07 | 4·58 | 9·29 | 7·48 | 4·60 | 70·70 | 38·25 | 12·49 | October. |
| 4·61 | 3·95 | 4·26 | 4·19 | 5·82 | 10·62 | 2·33 | 0·15 | 2·04 | 0·0 | 0·0 | 2·07 | 0·0 | 4·00 | 1·38 | 16·10 | 21·67 | 11·85 | November. |
| 4·24 | 2·80 | 3·28 | 3·41 | 3·30 | 9·57 | 0·40 | 0·0 | 0·0 | 1·20 | 0·0 | 0·05 | { One light shower. } | 0·0 | 0·25 | 21·00 | 10·20 | 12·28 | December. |
| 4·54 | 28·35 | 24·67 | 21·06 | 39·19 | 81·71 | 22·34 | 28·63 | 29·81 | 18·53 | 17·83 | 254·05 | 302·21 | 305·27 | 143·35 | 298·55 | 235·87 | 101·24 | Year. |

or the monsoon months only.

considered their dry months; but Mercara, lying much further south than Mahabuleshwur, would appear to benefit slightly from the terminal falls of the N.E. monsoon, or from the preliminary squalls of the S.W. monsoon. On the eastern or Coromandel coast, the months that are comparatively dry (or rather destitute of rain, for the wet bulb won't admit them to be dry) on the western coast, are necessarily the reverse of the eastern, and we thus see October, November, December and January, at Madras, and the other stations on the east coast, with a monthly fall of rain ranging from 0·90 to 15·13 inches. The mean annual fall at Madras, for twenty-two years, from 1822 to 1843, ranges from 18·45 inches in 1832 to 88·68 inches in 1827. Calcutta, although within the regular S.W. monsoon, appears to benefit more from the Coromandel monsoon in January than any other of the stations noticed in the Table. The Tables indicate that as the stations approximate towards each other, and lie nearer to the apex of the triangular-formed peninsula of India, excepting at Cape Comorin, so do they respectively benefit in an increasing ratio from the monsoons of either coast. For instance, Madras derives considerable advantage from the Malabar monsoon in the months of July, August and September, while Cochin, Quilon, Allepy and Trevandrum, on the Malabar coast, and the mountain stations of Uttray Mullay, Kotergherry and Dodabetta, lying between the Malabar and Coromandel coasts, are liberally supplied from the N.E. monsoon in the months of October, November and December, while Mercara and Mahabuleshwur, similarly situated as Uttray Mullay and Dodabetta, but in a higher latitude, and nearly in the same meridian, derive scarcely any benefit from the N.E. monsoon; indeed, north of the eighteenth parallel of latitude, that is to say of Poona, the rain-fall of the N.E. monsoon does not extend, at least as far as the returns I have been able to collect afford me the means of judging. Another feature of the Table indicates that the S.W. monsoon does not burst simultaneously along the whole line of the Malabar coast, but would appear to creep up slowly from Allepy towards Bombay, commencing in fact on the coast of Travancore partly in April, but absolutely in May, and rarely, if ever, commencing in Bombay before the first week in June; the S.W. monsoon therefore on the coast of Travancore and Malabar, precedes the time of its occurrence at Bombay by a month at least. I had thought that along the coast the quantity of rain diminished as the latitude increased, and the large annual fall at Allepy and Cochin, compared with the fall at Bombay, seemed to justify the opinion; but the fall at Cape Comorin, Trevandrum and Quilon, does not justify the opinion; and supposing that any such law held good on the Malabar coast, it plainly has not any existence on the Coromandel coast. It is certain, however, that as the tropic is approached on the western side of India, the annual fall of rain sensibly diminishes along the coasts of Kattywar and Cutch; and at the mouths of the Indus, not only is there no trace of the S.W. monsoon, but Lower Scinde would appear to resemble those singular tracts on the earth, the Deserts of Sahara and Gobi, and the coast of Chili, denominated "rainless." I regret not having been enabled to get more than one re-

gular meteorological register from the military cantonment at Kurrachee, situated near one of the mouths of the Indus; but the scanty information supplied to me affords sufficient proof that if Lower Scinde does not belong absolutely to the rainless districts, it approaches very nearly to them. Unfortunately, neither in the large cantonment at Kurrachee, nor at other stations in Scinde, up to 1849 were regular meteorological registers kept, excepting perhaps for mere temperature, or if kept they were not made available to the public. Casual observations have been made and sufficient attention paid to the rain-fall, or rather the absence of it, to enable us to say definitely, that to Lower Scinde the S.W. monsoon, in its usual sense, does not extend, and that the country does not appear to have other sources of supply. The following Table is arranged from the details in a letter dated Kurrachee, July 6th, 1848, noticing the occasional showers that fell from April 1847, a pluviometer having been set up, but apparently for very little purpose :—

Register of Rain at Kurrachee, from April 1847 to July 1848.

| 1847. | | | | | | | | 1848. | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| May. | June. | July. | August. | Sept. | Oct. | Nov. | Dec. | Jan. | Feb. | March. | April. | May. | June. | July. |
| None. | None. | A shower. | None. | None. | None. | None. | None. | None. | None. | None. | None. | None. | None. | A few drops. |

It thus appears, if the register be correct, that in fifteen months only two showers occurred, and those so light as not to be appreciable by the pluviometer.

The following extract from a subsequent letter, dated 1st of September 1849, to a certain extent is in harmony with the previous record :—

"We have had a few smart showers lately. Ever since June it has been constantly threatening rain; the sky has been always overcast, and both in July and August showers fell, but the whole fall for the season has hardly amounted to 3 inches; and yet in Upper Scinde, at Mooltan, in the Punjab, and generally in India, where the S.W. monsoon prevails, the usual averages have in some places been doubled."

In this year, at Bombay, the unusual quantity of 118·88 inches fell. The only other part of Scinde from which I have any record is from Kotri near to Hyderabad on the Indus, and the return transmitted to me is annexed. The public duties of the observer called him occasionally away from his station and prevented a continuous record, and it is only for 1846 that a year's observations are complete, and in 1847 four months were omitted.

Extract from a journal kept at Kotri near Hyderabad on the Indus, by Mr. Strath, engineer; for the months entered the blanks indicate the months of no observation.

| | 1845. | 1846. | 1847. | 1848. | 1849. |
|---|---|---|---|---|---|
| January ..... | ..... | None. | None. | ..... | None. |
| February ... | ..... | None. | ..... | ..... | None. |
| March ..... | ..... | * | None. | ..... | 0·35 in. |
| April ..... | ..... | None. | † | ..... | ‖ |
| May ..... | ..... | 1·75 in. | None. | | |
| June ..... | ..... | 6·33 in. | | | |
| July ..... | ..... | 0·27 in. | | | |
| August ..... | ..... | None. | ‡ | | |
| September ... | ..... | None. | None. | None. | |
| October ..... | ..... | None. | None. | § | |
| November ... | ..... | None. | None. | None. | |
| December ... | None. | None. | None. | None. | |
| | | 8·35 in. | | | 0·35 in. |

I am enabled, however, since the preceding notices were written, by the arrival in England of the medical returns from the Bombay army for 1847, to give an official and authentic record of the rain-fall and temperature at Kurrachee for 1847. It will be seen that for *eleven* months not a single shower fell, and that in one month only did rain fall, the record being in accord so far with the letter dated 6th of July 1848, differing, however, inasmuch as the rain in the official report is represented to have fallen in June and the latter in July.

| 1847. | Thermometer. | | | Rain. | Rain. |
|---|---|---|---|---|---|
| | Max. | Min. | Mean. | | |
| | ° | ° | ° | in. | |
| January ..... | 83 | 53 | 67 | | On 24th, 25th and 31st. |
| February ... | 74 | 59 | 67 | | |
| March ..... | 84 | 70 | 77 | | |
| April ..... | 84 | 75 | 79 | | Heavy showers, 23rd and 24th. |
| May ..... | 90 | 77 | 83 | | On 24th and 25th. |
| June ..... | 94 | 80 | 87 | 3·0 | |
| July ..... | 90 | 78 | 84 | | Slight showers. |
| August ..... | 95 | 82 | 88 | | |
| September ... | 90 | 80 | 86 | | |
| October ..... | 93 | 72 | 80 | | |
| November ... | 91 | 59 | 72 | | |
| December ... | 83 | 44 | 63 | | |
| Mean ..... | 88·42 | 69·08 | 77·75 | | |

In a review of the above rain-records we find some singular features. Along the western coast of India, from Cape Comorin to the mouth of the Indus, there is a paucity of rain at the former place, and an almost total absence of it at the latter,

* On the 4th of this month a few drops of rain fell at sunset.

† Rain during the night and light showers during the day.

‡ At sunset drops of rain.

§ At P.M. of the 7th heavy showers of rain with wind, thunder and lightning.

‖ On the 30th light showers.

while a few miles from Cape Comorin the annual supply amounts to 113 inches; and in the latitude of Bombay it does not fall below a mean of 76·82 inches for the monsoon alone, but proceeding along the coast northwards the supply further diminishes, or becomes irregular and uncertain in quantity, and at the mouths of the Indus almost disappears. Along the Coromandel coast the N.E. monsoon does not appear to supply much more than one-half of the fall on the Malabar coast, the mean of twenty-two years at Madras being 44·57 inches, the quantity slightly increasing with the latitude from Cape Comorin. Another marked feature is the greatly increased fall of rain with the increased elevation above the sea-level of the place of observation up to a certain height, beyond which the quantity of rain gradually diminishes as the place of observation is more elevated; at least such are the indications in the tract of land which lies between the sea-shore and the base of the Ghâts between Cape Comorin and Goozerat, and along the western face of the Ghâts themselves. The observation does not hold good however on the elevated lands to the eastward of the crest of the Bombay and Malabar Ghâts. Along the sea-coast the falls vary from 28·35 inches at Cape Comorin to 113·26 inches at Allepy, but increase at stations nearing the Ghâts at different elevations to more than 300 inches at 4500 feet, and above that height the falls gradually diminish in quantity. For instance, the

| | inches. |
|---|---|
| Mean of seven stations at sea-level, western coast, is . . . . . | 81·70 |
| At 150 feet, Rutnagherry, in the Konkun . . . . . | 114·55 |
| At 900 feet, Dapoolee, Southern Konkun . . . . . | 134·96 |
| At 1740 feet, Kundalla, the pass from Bombay to Poona . . . . | 141·59 |
| At 4500 feet, Mahabuleshwur, means of fifteen years . . . . . | 254·05 |
| At 4500 feet, Mercara in Coorg, means of three years . . . . . | 143·35 |
| At 4500 feet, Uttray Mullay*, in Travancore, means of two years . | 263·21 |
| At 6100 feet, Kotergherry, on the Neelgherries, one year . . . . | 81·71 |
| At 8640 feet, Dodabetta, highest point of Western India, one year | 101·24 |

Hence the elevation of the line of maximum fall would appear to be about 4500 feet, and above this level the supply of rain is diminished; Mahabuleshwur, Mercara and Uttray Mullay, although differing greatly in latitude, lie nearly in the same meridian, and are all at the same elevation. The comparative small fall at Mercara is accounted for by the fact of its not being so near the western scarp of the Ghâts as Mahabuleshwur and Uttray Mullay, and the effect of a station being placed a few

* Since the above was written I have received a letter from General Cullen, dated Trevandrum, 6th of January 1850, giving an account of the fall of rain for 1849 at the Uttray Mullay range.

| | inches. |
|---|---|
| At 500 feet, base of range | 99 |
| At 2200 feet, Attagherry | 170 |
| At 4500 feet, Uttray Mullay | 240 |
| At 6200 feet, Agusta Peak | 194 |

Showing at 6200 feet a fall of 46 inches less of rain than at 4500 feet.

miles east of the Ghâts upon the fall of rain has already been shown at Mahabuleshwur and Paunchgunny, the latter place being eleven miles eastward of the former, and at a lower level of only 500 feet, yet the mean fall of 15 years at Mahabuleshwur was 254·05 inches, and of the latter 50·69 inches. In 1849 the contrast was still greater, the fall at Mahabuleshwur amounting to the enormous quantity of 338·38 inches, while at Paunchgunny only 58 inches fell.

*Rain at different Elevations.*

Mr. Miller, in his Meteorology of the Lake Districts of Cumberland and Westmoreland, has adduced sufficient evidence to prove that the same law, if it be a law, obtains in England in mountainous districts, but Mr. Miller's elevation of maximum fall is about 2000 feet instead of 4500, as in India. This difference no doubt results from the differences of latitude and consequent mean temperature, and would indicate that the stratum of vapour supplying the maximum quantity of rain floats at a less height beyond the tropics than within them.

In a communication from Mr. Miller, dated June 7, 1849, he gives as follows the fall of rain at different heights in the Lake Districts of Cumberland and Westmoreland.

"The Mountain Gauges.

| No. | | In 13 months. 31st of December 1847 to 31st of December 1848. | Summer months. 1st of May to 31st of October. | Winter months. December 1847 to April 1848, and November and December 1848. |
|---|---|---|---|---|
| | | in. | in. | in. |
| XXI. | Sca Fell Pike, 3166 feet above the sea | 64·73 From 1st of May. | 49·46 | |
| XXII. | Great Gable, 2928 feet above the sea | 91·32 | 46·81 | 44·51 |
| XXIII. | Sprinkling Tarn, 1900 feet above the sea | 148·59 | 70·95 | 77·64 |
| XXIV. | Stye Head, 1290 feet above the sea | 138·72 | 60·35 | 78·37 |
| XXV. | Brunt Rigg, 500 feet above the sea | 109·19 | 43·18 | 66·01 |
| XIV. | Valley to the west, Wastdale | 127·47 | 50·16 | 77·81 |
| XIII. | Valley to the S.E., Eskdale | 95·71 | 37·69 | 58·02 |
| XXVI. | Seatollar Common, 1334 feet above the sea | 139·48 | 57·97 | 81·51 |
| XIX. | Valley, Seathwaite, Borrowdale | 177·55 | 68·96 | 108·59 |

"From the table for the summer months, it appears that between the 1st of May and the 31st of October, the gauge at 1290 feet has received 20½ per cent. more rain than the valley; at 1334 feet, 15½ per cent. more; at 1900 feet, 41½ per cent. more; at 2928 feet, 6 per cent. less; and at 3166 feet, 1 per cent. less than the valley.

"In the winter months, the gauge at 1290 feet has collected 0·5 per cent. more; at 1344 feet, 5½ per cent. more; at 1900 feet, 1 per cent. more; and at 2928 feet, 42½ per cent. less than the adjacent valley."

These results are in accordance with the observations I have given from India. In addition to the preceding from Mr. Miller, I annex his rain-records at lower levels

for the years 1845, 1846, 1847 and 1848, as they confirm, from European localities, the facts I have stated respecting the great discrepancies in the fall of rain at proximate stations.

Fall of Rain in the Lake Districts of Cumberland and Westmoreland at various heights up to 3166 feet. Wind almost uniformly from a westerly quarter.

| Years. | Whitehaven. | | | The Flosh, 3 miles south of Whitehaven. | Keswick, 238 feet. | Cockermouth. | Bassenthwaite Hills, 310 feet. | Vale of Gillerthwaite, Ennerdale, 360 feet. | Lowes-water, 336 feet. | Foot of Crummock Lake, 283 feet. | Gatesgarth, Buttermere, 326 feet. | Eskdale. | | Wastdale Head, 166 feet. | Westmoreland. | | | Borrowdale. | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | High Street, 90 feet. | Round Close, 489 feet. | Saint James's Church Steeple, 78 feet. | | | | | | | | | Centre of Vale, 150 feet. | Head of Vale. | | The Row, Troutbeck, 300 feet. | Ambleside, 190 feet. | Langdale Head, 250 feet. | Seathwaite, in Garden, at 6 inches, 1334 feet. | Seathwaite, in the Field, at 18 inches, 1324 feet. | Stonethwaite. | Seatoller Common, 1334 feet. |
| | in. | in. | in. | in. | in. | in. | in. | in. | in. | in. | in. | in. | in. | in. | in. | in. | in. | in. | in. | in. | in. |
| 1848. | 47·343 | 48·706 | 36·344 | 60·82 | 66·407 | 52·37 | 47·06 | 97·73 | 76·668 | 98·07 | 133·55 | 86·78 | 70·38 | 115·32 | 91·347 | 76·82 | 130·38 | 160·89 | 157·22 | 130·24 | 139·48 |
| 1847. | 42·921 | 43·023 | 30·713 | 47·80 | 58·286 | 42·55 | 44·45 | 80·13 | 66·209 | 82·32 | 106·25 | 58·66 | 74·93 | 96·24 | 78·004 | ..... | 112·95 | 139·24 | 126·80 | 106·21 | |
| 1846. | 49·134 | ..... | 35·422 | 55·16 | 67·678 | 52·41 | ..... | 83·87 | 70·249 | 96·47 | 121·90 | ..... | ..... | 106·93 | 77·719 | ..... | 127·40 | 143·51 | | | |
| 1845. | 49·207 | ..... | 33·480 | 53·00 | 62·212 | 46·93 | ..... | 76·88 | 69·542 | 87·48 | 124·13 | ..... | ..... | 108·55 | 76·305 | ..... | 136·00 | 151·87 | | | |

These records attest that in the town of Whitehaven the difference in the fall of rain in the High Street and on the steeple of St. James's Church in 1845, was 15·727 inches, and in 1848 the difference was 10·998 inches, while at the Flosh, only three miles south of Whitehaven, the fall was in excess in those years respectively over the fall in the High Street, 2·873 inches and 13·478 inches, while the excess over the fall on the steeple was 19·600 inches and 24·476 inches. In Borrowdale also, in a field adjoining a garden, in the years 1847 and 1848, the fall was in excess in the garden of 2·44 inches and 3·67 inches respectively. These facts suggest caution to all observers in other parts of England and elsewhere.

Professor PHILLIPS for some years made observations at York on the top of the Minster, the Museum, and on the ground, to determine the effect of elevation upon the rain-fall, but objections being taken to the results in respect to eddies of wind and other causes of error, he lifted rain-gauges into the air, independently of buildings, and the results of the observations for the years 1843 and 1844 he communicated to the British Association at York in 1844.

The sums of the rain-fall in the two years at different heights were,—

| | inches. |
|---|---|
| 24 feet. . . . . | 24·158 |
| 12 feet. . . . . | 26·039 |
| 6 feet. . . . . | 26·109 |
| 3 feet. . . . . | 26·298 |
| 1½ foot . . . . . | 26·559 |

The nearer the earth, therefore, the greater the amount of rain collected. Mr. MILLER's records at Whitehaven, giving for four years the amount of rain collected in the High Street and on the Church Steeple, confirm Professor PHILLIPS's observations, supposing the steeple to be 78 feet above the High Street. At Calcutta, in the

Surveyor-General's Office, similar observations were made at the respective heights of 4 feet and 40 feet, and I have inserted the results in the general rain-fall Table for four years. The sums were respectively 261·97 inches and 247·41 inches, and the annual means 65·49 inches and 61·85 inches.

Dr. Buist states that at the observatory in Bombay, in two rain-gauges, one at 3 feet from the ground, and the other above the observatory at 32 feet, the

| | inches. |
|---|---|
| Lower gauge for 1843 . . . | =56·24 |
| Upper gauge for 1843 . . . | =49·07 |
| Lower gauge for 1844 . . . | =66·51 |
| Upper gauge for 1844 . . . | =66·08 |

These results therefore are in accordance with Professor Phillips and Mr. Miller's observations, taken at limited heights, but entirely antagonist to Mr. Miller's own observations and those I have supplied in this paper from India for heights exceeding a few hundred feet. The supposed law may hold good for small differences in elevation on the plains, but the law is reversed in mountainous districts.

Two great features of my Rain-table demand express notice, the paucity of rain at Cape Comorin and at Kurrachee, at the extremities of nearly the same meridional line, and the prodigious fall of rain at the elevation of 4500 feet at three stations differing greatly in latitude, but situated nearly in the same meridian. I have not any satisfactory explanation to offer of the want of rain either at Cape Comorin or at Kurrachee. I am not at all acquainted with the physical character of the country about Cape Comorin, and cannot therefore express an opinion how far local circumstances occasion the phenomenon. I had thought that a very high mean temperature, with a limited range of the thermometer, might account for the want of rain at Kurrachee on the Indus, the vapour from the ocean not coming into an air cold enough to condense it; but the register of the thermometer for 1847 at Kurrachee shows that I could not found a satisfactory argument upon its records, for the maxima are not so great as at Calcutta, Madras and Bombay; the minima are lower, and the mean temperature is lower than at either of the places; some other cause therefore must be looked for than a high mean temperature. The clouds which constantly pass over Kurrachee, would appear not to be condensed until they impinge upon the Sulimanee Mountains, which run parallel to the right bank of the Indus. The explanation of the prodigious fall of rain at the level of 4500 feet is simple and satisfactory. The chief stratum of aqueous vapour brought from the equator by the S.W. monsoon is of a high temperature, and floats at a *lower* level than 4500 feet; indeed I have looked over, or upon the upper surface of the stratum at 2000 feet. It is dashed with considerable violence against the western mural faces of the Ghâts, and is thrown up by these barriers in accumulated masses into a colder region than that in which it naturally floats; it is consequently rapidly condensed and rain falls in floods. The uncondensed vapour which escapes up the chasms and over the crest of the Ghâts,

affords the precarious and scanty supply to the lands to the eastward, which the Tables show.

*Maximum Daily Rain-Fall.*

As might be looked for, the greatest fall of rain in any one day is met with in the records of those stations where there is the greatest annual fall, Mahabuleshwur and Uttray Mullay. At the former station the greatest fall in any one day in fifteen years was 13·06 inches on the 2nd of September 1833, but the months of June, July and August, have numerous instances of a daily fall of 11·32 inches, 12·76 inches, and 12·69 inches in those months respectively. The greatest monthly fall at Mahabuleshwur was 134·42 inches in July 1840. At Uttray Mullay the greatest daily fall in three years was 15·1 inches on the 14th of October 1845. On the 11th of December of the same year there was a fall in one day of 11·4 inches, and on the 9th of October 1844 the fall in one day was 9·0 inches. In 1846 there was not a daily fall approaching these figures. In Bombay, in 1845, the greatest daily fall was 4·71 inches on the 24th of July, and the next year, on the 16th of July, a daily fall occurred of 5·16 inches; but Dr. Buist mentions that on the 1st of July 1844 there was a fall of rain in twenty-four hours of 7·44 inches, two inches having fallen in seventy minutes; but this was on the first burst of the monsoon, which set in later than usual by three weeks. On the 10th of July, however, 9·43 inches fell, the greatest of the year. In the Deccan there is rarely a greater daily fall than two inches, but in the Sattarah records a maximum daily fall of 4·40 inches in four years is stated to have occurred in April; but this was in one of the squalls which are the precursors of the monsoon. Annexed is a comparison of the fall of rain in Bombay and at Mahabuleshwur for many years.

## Register of the Pluviometer at Bombay, from the year 1817 to 1849.

| Years. | June. | July. | August. | September. | October. | Total fall in June, July, August, September, and October of each year. | Mahabuleshwur, 4500 feet. |
|---|---|---|---|---|---|---|---|
| | in. | in. | in. | in. | in. | in. | |
| 1817. | 45·72 | 23·67 | 9·34 | 24·87 | ..... | 103·60 | |
| 1818. | 22·54 | 17·69 | 28·45 | 10·39 | 2·07 | 81·14 | |
| 1819. | 15·95 | 31·66 | 20·24 | 10·11 | ..... | 77·96 | |
| 1820. | 18·82 | 28·37 | 29·49 | 10·66 | ..... | 77·34 | |
| 1821. | 15·18 | 20·60 | 28·52 | 18·29 | ..... | 82·59 | |
| 1822. | 29·64 | 26·59 | 33·83 | 22·16 | ..... | 112·22 | |
| 1823. | 21·76 | 15·96 | 19·70 | 4·28 | ..... | 61·70 | |
| 1824. | 3·89 | 8·07 | 17·86 | 1·78 | 2·37 | 33·97 | |
| 1825. | 24·45 | 25·17 | 12·94 | 9·68 | ..... | 72·24 | |
| 1826. | 17·75 | 26·97 | 8·40 | 23·50 | 1·87 | 78·49 | |
| 1827. | 49·15 | 10·29 | 10·51 | 10·16 | 0·92 | 81·03 | |
| 1828. | 23·53 | 52·75 | 17·22 | 22·08 | 6·40 | 121·98 | |
| 1829. | 27·86 | 19·78 | 12·40 | 4·95 | 0·66 | 65·65 | 257·06 |
| 1830. | 20·96 | 32·46 | 10·66 | 7·78 | ..... | 71·86 | 232·93 |
| 1831. | 22·46 | 27·31 | 27·64 | 22·34 | 2·08 | 101·83 | 185·82 |
| 1832. | 13·63 | 48·05 | 4·65 | 7·11 | 0·65 | 74·09 | 226·87 |
| 1833. | 12·50 | 21·80 | 13·35 | 23·54 | 0·20 | 71·39 | 203·74 |
| 1834. | 14·16 | 21·83 | 18·05 | 12·55 | 3·88 | 70·47 | 297·31 |
| 1835. | 9·99 | 4·27 | 35·76 | 12·17 | 0·42 | 62·61 | 226·71 |
| 1836. | 21·36 | 24·53 | 37·41 | 4·69 | ..... | 87·99 | 243·56 |
| 1837. | 12·61 | 24·39 | 22·43 | 5·15 | ..... | 64·58 | 267·76 |
| 1838. | 29·70 | 8·70 | 7·34 | 5·04 | ..... | 50·78 | 180·17 |
| 1839. | 18·28 | 32·19 | 18·45 | 4·70 | ..... | 73·62 | 233·23 |
| 1840. | 25·04 | 24·24 | 4·20 | 7·55 | 2·12 | 63·15 | 284·43 |
| 1841. | 25·27 | 21·21 | 20·53 | 1·27 | 3·21 | 71·49 | 281·04 |
| 1842. | 16·84 | 26·45 | 37·10 | 10·41 | 4·36 | 95·16 | 304·90 |
| 1843. | 9·33 | 22·49 | 18·20 | 9·00 | 0·25 | 59·27 | 285·67 |
| 1844. | 14·17 | 35·52 | 6·55 | 9·16 | ..... | 65·40 | 262·32 |
| 1845. | 19·70 | 20·44 | 6·56 | 8·03 | ..... | 54·73 | 249·93 |
| 1846. | 31·71 | 40·56 | 5·60 | 8·45 | 1·16 | 87·48 | 288·34 |
| 1847. | 35·47 | 16·80 | 8·92 | 5·80 | 0·32 | 67·31 | 218·83 |
| 1848. | 42·37 | 13·83 | 7·87 | 4·01 | 5·34 | 73·42 | 245·01 |
| 1849. | 22·82 | 51·68 | 13·66 | 29·65 | 1·07 | 118·88 | 338·38 |
| Average for 33 years. | 22·26 | 25·04 | 17·08 | 11·25 | 1·19 | 76·82 | |

*Note.*—The Bombay register is only for the months of the monsoon, and it does not appear that any record has been kept of the fall in the other months annually. The record at Mahabuleshwur is for the whole year.

*Winds at Madras.*

Direction of the Wind at Madras, blowing from the different *quarters* of the compass, from hourly observations.

| | 1841. | | | | 1842. | | | | 1843. | | | | 1844. | | | | 1845. | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | N.W. | S.W. | S.E. | N.E. | N.W. | S.W. | S.E. | N.E. | N.W. | S.W. | S.E. | N.E. | N.W. | S.W. | S.E. | N.E. | N.W. | S.W. | S.E. | N.E. |
| Jan.... | ... | ... | ... | ... | 105 | 51 | 80 | 508 | 74 | 29 | 92 | 549 | 64 | 47 | 193 | 440 | 87 | 27 | 196 | 434 |
| Feb.... | ... | ... | ... | ... | 95 | 124 | 227 | 229 | 23 | 82 | 434 | 133 | 45 | 92 | 309 | 249 | 11 | 71 | 393 | 197 |
| March | 2 | 170 | 372 | 0 | 26 | 201 | 276 | 1 | 15 | 179 | 527 | 23 | 12 | 266 | 449 | 17 | 13 | 221 | 477 | 33 |
| April | 120 | 471 | 115 | 14 | 0 | 307 | 269 | 0 | 0 | 230 | 488 | 2 | 15 | 236 | 451 | 19 | 3 | 380 | 335 | 2 |
| May | 57 | 407 | 219 | 37 | 56 | 468 | 211 | 9 | 73 | 376 | 260 | 35 | 67 | 426 | 215 | 36 | 73 | 437 | 204 | 30 |
| June | 86 | 539 | 86 | 9 | 86 | 447 | 133 | 30 | 88 | 553 | 76 | 3 | 196 | 397 | 84 | 43 | 228 | 396 | 51 | 45 |
| July... | 144 | 511 | 76 | 13 | 96 | 578 | 62 | 13 | 121 | 562 | 54 | 7 | 127 | 498 | 111 | 8 | 128 | 498 | 108 | 10 |
| Aug. | 85 | 352 | 288 | 19 | 37 | 487 | 144 | 26 | 120 | 494 | 117 | 3 | 200 | 411 | 95 | 38 | 135 | 472 | 129 | 8 |
| Sept. | 115 | 356 | 182 | 43 | 91 | 377 | 174 | 76 | 153 | 355 | 168 | 44 | 114 | 359 | 187 | 60 | 93 | 371 | 228 | 28 |
| Oct.... | 265 | 93 | 145 | 241 | 101 | 203 | 221 | 219 | 194 | 183 | 119 | 248 | 171 | 251 | 125 | 197 | 83 | 274 | 229 | 158 |
| Nov. | 232 | 16 | 58 | 414 | 139 | 16 | 34 | 531 | 194 | 2 | 11 | 513 | 236 | 0 | 51 | 433 | 96 | 0 | 66 | 558 |
| Dec. | 219 | 0 | 10 | 515 | 157 | 16 | 70 | 501 | 207 | 19 | 144 | 374 | 246 | 8 | 64 | 426 | 149 | 14 | 104 | 477 |
| Total | ... | ... | ... | ... | 1039 | 3275 | 1901 | 2145 | 1262 | 3064 | 2490 | 1934 | 1493 | 2991 | 2340 | 1966 | 1099 | 3161 | 2520 | 1980 |

*Note.*—N.W. includes the winds blowing between N. and W. points, and the same applies to the other quarters.

The prevailing wind at Madras is the S.W., which wind brings to Bombay and the Malabar coast their monsoon rains, but which to Madras becomes mostly a *hot* wind after traversing the peninsula, and carries with it to Madras only a few showers. The S.W. wind begins to prevail at Madras over every other wind in the month of April, and mostly remains the dominant wind until the end of September: the S.E. wind then prevails until October, about the middle of which month the approaching N.E. or rainy monsoon of the Coromandel coast almost displaces the S.E. wind. Its full development takes place in November, and it remains the prevailing wind until February, when the S.E. regains its influence, and is greatly the dominant wind until April, when it is gradually displaced by the S.W. wind. The N.W. wind makes its appearance in every month of the year, chiefly in the months of the S.W. or Malabar monsoon, but least so in the months of March and April, in the years 1841 not in March, and 1842 not at all in April; the N.E. wind failed in the same months in the respective years. The N.W. is the quarter from whence Madras has the smallest amount of wind. The largely prevailing wind is the S.W., which, coming up from the equator, is the chief source of rain supply to India generally, but of which the Coromandel coast gets but a scanty proportion in consequence of the high western Ghâts intercepting and condensing the chief part of the vapour brought by that wind. The next prevailing wind is the S.E., and this equally blows from the equator upon Madras and the Coromandel coast; but it is nevertheless not the rain-bearing wind of the Madras monsoon, which is from the N.E., sweeping over the bay of Bengal from Burmah. The S.W. wind from the Indian Ocean is a rain-bearing wind, but

the S.E. wind, also from the Indian Ocean, is not a rain-bearing wind in the sense of a monsoon. By a comparison of the Wind-table with the Rain-table of Madras, it will be seen that in the months in which the S.E. winds prevail, February, March, April, September, and early part of October, the first three months are almost entirely rainless, and the little that falls in September is owing to occasional S.W. winds. This may be owing to the air over the peninsula in those months, from the position of the sun in the ecliptic being too hot to condense the S.E. vapour. On the contrary, the N.E. wind from the bay of Bengal comes loaded with vapour in November, December and January, and the sun being far south, the peninsula is rapidly cooling, and the vapour from the bay of Bengal being of a higher temperature than the air upon which it is thrown, is condensed. The valuable table from the Madras Observatory shows by inspection, the gradual changes of the wind from one quarter to another, and the total annual numbers under each quarter show considerable uniformity in successive years.

*Winds at Bombay.*

The following Table of the winds at Bombay, for the year 1843, is from the *hourly* observations taken by Dr. Buist, LL.D. Although the numbers of hours at which the winds blew are placed under the points N.W., S.W., S.E., N.E., the numbers embrace the winds within each quarter of the compass; for instance, N.W. embraces all the winds blowing between N. and W., and so on for the other quarters.

| | N.W. | S.W. | S.E. | N.E. |
|---|---|---|---|---|
| January | 382 | 56 | 11 | 157 |
| February | 397 | 15 | 32 | 132 |
| March | 451 | 30 | 28 | 138 |
| April | 442 | 94 | 17 | 47 |
| May | 380 | 273 | 12 | 1 |
| June | 85 | 438 | 73 | 7 |
| July | 133 | 491 | 0 | 0 |
| August | 184 | 460 | 2 | 3 |
| September | 98 | 390 | 43 | 53 |
| October | 280 | 41 | 50 | 253 |
| November | 224 | 1 | 51 | 348 |
| December | 130 | 0 | 64 | 382 |
| Year | 3184 | 2289 | 383 | 1521 |

The Table shows that the prevailing wind at Bombay, in 1843, was from the points between N. and W., having blown at 3184 hours. The next prevailing wind is from the points between S. and W., having blown for 2289 hours, being the rain-bearing wind of the so-called S.W. monsoon, from May to September inclusive; but in truth the wind most generally blows from the W.S.W., with a leaning to a point more westward, and a S.W. and by S. wind during the monsoon is of rare occurrence. The wind from the points between N. and E. is the next most prevalent. It begins to prevail in October, and continues prevalent as long as the N.E. monsoon blows at

Madras, on the opposite coast of India; it may be said to cease entirely when the Malabar monsoon approaches in May. The S.E. wind, unlike Madras, is little felt at Bombay, having blown at 383 hours only during 1843. Few as the occasions are on which it blew at Bombay, it would appear to have resulted from the veering of the N.E. wind through E. to a point southward of east; a wind strictly from the S. is scarcely known at Bombay. The N.W. wind, which is the dominant wind at Bombay and the least prevailing wind at Madras, blows at Bombay most in those months when it is least felt at Madras, namely, the first five months of the year, and in the months of March and April it almost disappears at Madras; but at Bombay in those months it blows at more hours than any other wind blows in any other two months of the year, excepting probably the W.S.W. in July and August. In January, February, March, April, and up to the third week in May, the wind from the N. to W. points blows from eleven to twenty-two hours daily, the remaining hours having the wind from the N. to E. points, constituting the land-wind, the N.W. being considered the sea-breeze. In part of October, November and December, the reverse is the case, the N.E. or land-wind prevailing from thirteen to nineteen hours daily, and the sea-breezes appearing between noon and 10 P.M. The suddenness with which the prevailing winds commence and terminate is a marked feature in the meteorology of Bombay. The wind from the S. to W. points begins suddenly the third or fourth week in May, and as suddenly terminates in the first or second week of October. The wind from the N. to E. points takes the place of the S.W. wind and terminates suddenly in May. The N.W. wind, owing to its being a daily alternating wind with the land-breeze, from the heating action of the sun upon the land daily, has a more continuous character throughout the year, appearing even in the monsoon months, when a few days' sunshine heats the land; it is however much less frequent in those months than when the sun bears with continued force upon the land.

*Winds at Calcutta.*

With regard to the winds at Calcutta, Dr. J. M'Clelland, in the fifth volume of the Calcutta Journal of Natural History, has given a reduction of the meteorological register kept at the Surveyor-General's Office, Calcutta, from the 31st of October 1843 to the 31st of October 1844; from his paper the following extracts are made in a condensed form:—

| | Wind at noon. | | | |
|---|---|---|---|---|
| | N.W. | S.W. | S.E. | N.E. |
| 1843. | | | | |
| November | 26 | 1 | 0 | 3 |
| December | 24 | 0 | 0 | 5 |
| 1844. | | | | |
| January | 25 | 0 | 3 | 3 |
| February | 23 | 2 | 0 | 4 |
| March | 1 | 20 | 8 | 0 |
| April | 0 | 26 | 3 | 1 |
| May | 0 | 24 | 4 | 3 |
| June | 5 | 21 | 3 | 2 |
| July | 1 | 17 | 11 | 1 |
| August | 1 | 17 | 13 | 0 |
| September | 4 | 19 | 5 | 2 |
| October | 4 | 7 | 6 | 3 |
| Year | 114 | 154 | 56 | 27 |

As these observations are only for noon in each day of the year, they are of little value; supposing them however to be typical of the variations of the wind, there is a certain accordance with the winds at Madras and Bombay in the respective months of the year, with respect to the winds blowing between the points S. and W., and with Bombay in the winds blowing between the points N. and W., excepting that the latter cease to prevail in March in Calcutta, but do not relax in Bombay until June. The winds of the S.W. monsoon would appear to commence in March in Calcutta, but not until May in Bombay. The tendency of the N.W. and S.W. winds in Calcutta, however, is rather to blow, the former from the N. and the latter from the S., than from intermediate points; out of 353 observations, the wind blew sixty-eight times from the N. and ninety-one times from the S., while the N.W. blew only thirty-four times and the S.W. wind only forty-two times. Judging from the Table, Calcutta is little affected by the winds of the N.E. monsoon. There is only a single instance of "no wind" at noon during the whole twelve months.

The following Table shows the direction of the wind at six different hours, and the relative duration of each wind throughout the year:—

| | N. | N.W. | W. | S.W. | S. | S.E. | E. | N.E. | Calm. | No. of observations. |
|---|---|---|---|---|---|---|---|---|---|---|
| Sunrise | 32 | 16 | 7 | 19 | 68 | 29 | 23 | 20 | 137 | 353 |
| $9^h\ 50^m$ A.M. | 50 | 29 | 42 | 49 | 75 | 34 | 23 | 37 | 3 | 351 |
| Noon | 58 | 34 | 53 | 42 | 90 | 19 | 29 | 26 | 1 | 352 |
| $2^h\ 40^m$ P.M. | 52 | 40 | 58 | 27 | 105 | 20 | 20 | 24 | 6 | 352 |
| $4^h$ P.M. | 53 | 42 | 45 | 36 | 93 | 34 | 31 | 12 | 6 | 352 |
| Sunset | 56 | 18 | 11 | 23 | 116 | 23 | 17 | 9 | 78 | 341 |
| Total | 310 | 179 | 216 | 190 | 536 | 150 | 145 | 118 | 231 | 2101 |
| Proportion of each | 51·6 | 29·8 | 36 | 32·6 | 89·3 | 26·5 | 24·1 | 19·6 | 38·5 | 350 |

From this Table the S.W. monsoon, which at Bombay has a disposition chiefly to

blow half a point to the westward of W.S.W., at Calcutta blows chiefly from the S., and the prevailing N.W. wind of Bombay becomes a northerly wind in Calcutta. The Table shows that almost the only hours of calm are at sunrise and at sunset.

*Winds at Mahabuleshwur.*

At Mahabuleshwur, at 4500 feet above the sea-level, the following is the mean monthly direction of the wind, as given by Dr. MURRAY in a synoptical view of fifteen years' observations:—

| | Direction. | Force. |
|---|---|---|
| January | Easterly. | Moderate. |
| February | E.N.E., N.N.W. | Moderate. |
| March | N.E., N.N.W. | Moderate. |
| April | N.E., N.N.W. | Moderate. |
| May | N.E., N.N.W. | Moderate. |
| June | W.S.W. | Moderate. |
| July | W.S.W. | High. |
| August | W.S.W. | High. |
| September | W.S.W. | Moderate. |
| October | Variable. | Light. |
| November | Easterly. | High. |
| December | Easterly. | High. |

From the generalities in the Table, it would not be safe to deduce any normal conditions from comparisons with the wind tables of Madras, Calcutta or Bombay. In the months of January, November and December, Mahabuleshwur would appear to share more largely in the easterly winds of Madras than in the N.W. winds of Bombay in those months; but in February, March, April and May, and the rest of the year, the station would appear to have much the same winds as prevail at Bombay. Its elevated position, therefore, does not remove it from the periodic currents of air of a lower level. Even Dodabetta, at its great elevation of 8640 feet, is partly subject to the periodic winds of Madras and Bombay, at least as far as one year's record of observations recorded *hourly* from OSLER's anemometer enables us to judge.

*Winds at Dodabetta.*

| | N.W. | S.W. | S.E. | N.E. |
|---|---|---|---|---|
| 1847. | | | | |
| February | 5 | 0 | 17 | 6 |
| March | 4 | 0 | 2 | 25 |
| April | 7 | 3 | 2 | 18 |
| May | 3 | 8 | 2 | 18 |
| June | 4 | 26 | 0 | 0 |
| July | 18 | 13 | 0 | 0 |
| August | 27 | 0 | 1 | 3 |
| September | 21 | 5 | 0 | 4 |
| October | 9 | 0 | 12 | 10 |
| November | 5 | 7 | 3 | 15 |
| December | 6 | 0 | 8 | 17 |
| 1848. | | | | |
| January | 2 | 0 | 16 | 13 |
| Year | 111 | 62 | 63 | 129 |

The winds of the S.W. monsoon, however, terminate in July instead of October. This is the more remarkable, as Dodabetta lies between Madras, where these winds are the prevailing winds of May, June, July, August and September, and Bombay, where the same winds prevail in the same months. It is probable, therefore, that Dodabetta is situated just above the upper surface of the stratum of wind and aqueous vapour which supplies the S.W. monsoon to Western India, and therefore has comparatively a small supply of rain from this source. But it is not situated (although on the western coast) above the stratum of wind and aqueous vapour which supplies the Coromandel coast during the N.E. monsoon, as it has the same prevailing winds between the N. and E. points in the same months as at Madras, from October to February, when the N.E. ceases at Madras, but continues at Dodabetta until late in May. The *prevalence* of winds from points between N. and W. in the months of July, August and September, is peculiar to Dodabetta: neither Mahabuleshwur, at 4500 feet, nor Madras, Bombay nor Calcutta has similar indications. However, as this so-denominated N.W. wind very frequently blows from only one or two points to the northward of west, the wind may belong to the monsoon of Western India, local physical circumstances having given it a slant. On the whole it may be said, that the peninsula of India, in its length and breadth and the atmosphere over it to the height of nearly 9000 feet, is subject to periodic winds; but at widely separated places, varying a point or two from the apparent normal winds, and commencing or terminating a week or two earlier or later. May, June, July, August and September have prevailing winds from points between W. and S.; October, November, December, January and February have prevailing winds from points between N. and E.; February, March and April, at Madras, have a prevailing wind from points between S. and E., as opposed to Bombay, where the wind in those months prevails from points between N. and W., with rare instances of a S.E. wind; while at Calcutta the N.W. wind terminates in February; but a series for years of hourly observations, like those at Madras, are necessary to give that confidence which cannot be given to deductions from the meteorological data at present available from India.

It is usually understood that very high winds materially depress the barometer, but the records at Dodabetta do not support this view. On the 17th and 18th of April 1847, the wind blew with a mean pressure of 21 lbs., and 14 lbs. respectively upon the square foot; but the barometer only fell from 21·955 on the 16th to 21·917 on the 17th, and rose to 21·984 on the 18th; and there was a maximum pressure from the wind on the 17th at one time of 35 lbs. 26th of May, maximum wind 28·5 lbs., barometer not affected more than 0·010 inch; 12th of June 30 lbs., 26th of July 32 lbs., 10th of September 35 lbs., and 14th of October 22 lbs.; but these pressures of the wind had little or no effect upon the barometer.

*Fogs.*

In the Madras observations there is not any mention made of fogs; and Captain Ludlow of the Madras Engineers, who recorded the observations, tells me that fogs are almost unknown at Madras, the nearest approach to a fog being an occasional mist on the ground, not visible more than 3 feet above the surface.

| | Madras. | Bombay. 1843. | Calcutta, 1843–44. | Mahabuleshwur, 15 years. | Dodabetta, 1847–48. | |
|---|---|---|---|---|---|---|
| | Fogs. | Fogs. | Fogs. | Fogs. | Fogs. | Dense fog. |
| January | 0 | 0 | 5 | 0 | 0 | 5 |
| February | 0 | 0 | 3 | 0 | 11 | 9 |
| March | 0 | 0 | 4 | 0 | 4 | 0 |
| April | 0 | 0 | 4 | 0 | 1 | 4 |
| May | 0 | 0 | 0 | Foggy last half. | 6 | 1 |
| June | 0 | 0 | 0 | Foggy. | 16 | 2 |
| July | 0 | 0 | 1 | Continued dense fogs. | 2 | 9 |
| August | 0 | 0 | 0 | Continued dense fogs. | 5 | 20 |
| September | 0 | 0 | 0 | Frequent light fogs. | 2 | 15 |
| October | 0 | 0 | 1 | First half light fogs. | 2 | 29 |
| November | 0 | 0 | 0 | 0 | 3 | 26 |
| December | 0 | 0 | 2 | 0 | 1 | 16 |
| Year | 0 | 0 | 20 | 0 | 53 | 136 |

At Bombay there are not any records of fogs in the hourly observations for 1843 nor 1844, but Dr. Buist informs me that mists are of regular occurrence in March; they begin early in February and continue for five or six weeks. They disappear after sunset, and are slightest from sunrise to noon*. At Calcutta, from Dr. M'Clelland's Report, there were only twenty instances in 1843–44, almost entirely at sunrise. At Mahabuleshwur, from the latter end of May until the middle of October, there is almost a continued fog with deluges of rain. At Dodabetta the prevalence of fogs is very remarkable, there being no less than 136 records of dense fogs and 53 of light fogs during the year. Of the dense fogs 52 occurred at $9^h\ 40^m$ A.M. and 85 at $3^h\ 40^m$ P.M.; 27 light fogs at $9^h\ 40^m$ A.M. and 25 at $3^h\ 40^m$ P.M.

*Electricity.*

I have not any data of a character to enable me to speak satisfactorily on the subject of the electric state of the air at the several stations.

I conclude with a rapid analysis of the preceding Tables.

In my paper published in the Philosophical Transactions in 1835 upon the Meteorology of the Deccan, I arrived at the following conclusions:—That Humboldt was mistaken in supposing, upon the authority of Horsburgh, that the diurnal atmo-

* I presume Dr. Buist means misty and comparatively semi-transparent *heated* air, as distinct from fogs.

spheric tides were suspended during the monsoon in Western India. The fact was also unquestionably established of the existence of four atmospheric tides within twenty-four hours,—two diurnal and two nocturnal, each consisting of a maximum and minimum tide, and the occurrence of these tides within the same limit hours as in America and Europe; the greatest mean diurnal oscillations taking place in the coldest months, and the smallest tides in the damp months of the monsoon in the Deccan, whilst at Madras the smallest oscillations were in the hottest months: it was shown also that these tides took place regularly without a single instance of interruption, whatever the thermometric or hygrometric indications might be, or whatever the state of the weather, even storms and hurricanes only modifying and not interrupting them. The anomalous fact was also shown of the mean diurnal oscillations being greater at Poona, at an elevation of 1823 feet, than at the level of the sea, in a lower latitude at Madras or Bombay, while at an elevation greater than Poona, the mean diurnal oscillations were *less* than at Poona. It was shown also that the seasons did not affect the limit hours of the tides; but it was shown at the same time that the turning-points of the tides were sometimes irregular; that a tide flowed for a longer or shorter period, and that there were numerous cases of a stationary state of the atmosphere at the hours when the tides should turn. It was shown that the maximum mean pressure of the atmosphere was greatest in December or January, gradually diminished to June, July or August, and subsequently increased to the coldest months. The trifling daily and annual range of the barometer, compared with the ranges in extra-tropical climates, was shown; also the more limited annual range of the thermometer in the Deccan than in Europe, but the existence of a greater daily range; the maximum mean temperature was in April or May, and then gradually declined to the coldest months; very considerable differences in the dewing-points within very narrow areas were shown; dew being frequently local and occurring under anomalous circumstances, and the great contrast between the dewing-points, on the sea-coast at Bombay and in the Deccan, was pointed out; the rain in the Deccan was not more than 28 per cent. of the quantity that fell in Bombay; the winds principally westerly and easterly, rarely from due north or south; and finally, the rarity of fogs was stated.

It is very satisfactory to find in the discussion of the meteorological observations in the present paper, from a very extended area, from different heights and from observations, some of which are hourly, and which run through several years at the same station, that after an interval of twenty years the accuracy of the former deductions should be established almost to the letter; but as some of the observations now discussed were from hourly records, continued through considerable periods of time, an opportunity has been afforded of investigating abnormal conditions, which the former limited number of diurnal observations did not permit; and from these sources a rapid review of what appear to be normal and abnormal conditions is now appended.—1st. The annual and daily range of the barometer diminishes from the sea-level up to

the greatest height observed, 8640 feet at Dodabetta, from a mean annual and mean daily range at Madras of 0·735 and 0·122 to 0·410 and 0·060 at Dodabetta;—the annual range would appear to increase, about and beyond the northern tropic, as the annual range at Calcutta (not by hourly observations) is 0·911: but the diurnal range is somewhat less (0·115) than at Madras. At no one of the places of observation, even taking the maximum pressure of one year with the minimum pressure of another year, does there appear to have been a range of pressure equivalent to an inch of mercury; nevertheless in the Cyclones, or rotatory storms, there occurs at times a range of pressure of nearly 2 inches of mercury within forty-eight hours; but it is shown from a comparison of the simultaneous records on board ship, where these great depressions were noted, with the records at the observatories on shore, that the great depressions occurred within very limited areas.

I had formerly shown that the times or turning-points of ebb and flow (if the terms be permitted) of the aërial ocean were occasionally retarded or accelerated, although the means fixed the turning-points within certain limit hours; but I was not aware that in the ebb or flow of the four daily tides, they ever retrograded or halted in their onward or retiring course. The hourly observations now satisfy us that abnormal conditions are of no infrequent occurrence,—that the tides at times flow or ebb for four, five, six or even seven and eight hours*,—that frequent instances occur of retrograde movements for short periods of time, as if the tide had met with a check and been turned back; and at the turning-points there are numerous instances of the atmosphere being stationary for a couple of hours.

The maximum pressure of the atmosphere is in the coldest months, December or January, but the minimum pressure is not in the hottest months, but in June or July. The barometric readings, when protracted †, show a gradual curve from December or January descending to June or July, and then ascending again to December or January, there being an occasional interruption in October or November; and as the curves at Madras, Bombay and Calcutta correspond, and as Madras has no S.W. monsoon, while Bombay has a S.W. monsoon, and as Bombay is destitute of the N.E. monsoon of Madras, it would appear that the general movements of the mass of the atmosphere are little influenced by any conditions of its lower strata; but the curve of pressure would seem to have some relation to the sun's place in the ecliptic.

The normal conditions of daily temperature are, that it is coldest in India at sunrise, and hottest between the hours of 1 and 3 P.M.; but the preceding tables show many aberrations from this rule. The regular increment or decrement of mean monthly heat from the maximum or minimum period is somewhat remarkable, as the curve is independent of the S.W. monsoon at Bombay and the N.E. monsoon at Ma-

* One instance at Aden of nine hours!

† To that very able and zealous meteorologist, Dr. Buist, LL.D. of Bombay, I am indebted for the protracted curves of pressure of the barometer appended to this paper. Plates XVII. XVIII. XIX. XX.

dras; and the passage of the sun twice over both places does not derange the curve. The anomalies of the annual mean temperatures of Madras, Bombay, Calcutta and Aden, not diminishing with the increase in the latitude of the respective places, are pointed out, and numerous instances are given of the very great power of the slanting rays of the sun beyond the tropic. As is the case with the barometric, so do the heat tables indicate that the annual and daily ranges of the thermometer diminish with the elevation of the place of observation above the sea-level, the elevated table-land of the Deccan however being an exception to this rule. At Mahabuleshwur, at 4500 feet, the temperature of *the air* was never below 45° with a maximum and minimum thermometer; and at Dodabetta the temperature of *the air* was never below 38°·5; nevertheless at both places ice and hoar-frost were frequently found on the ground at sunrise, resulting from the separate or conjoined effects of radiation and evaporation. I have already stated that I do not attach much value to the readings of the wet bulb, owing to the various sources of error in the instrument itself, and to the manifest sources of error in the existing theoretical formulæ for giving a numerical value to its readings to fix the tension of vapour in the atmosphere for the determination of the dew-point. No doubt the dew-points obtained by means of the wet bulb have a certain relation to the truth; and in some favourably concurring conditions may be as proximate to the truth as dew-points would be, obtained by direct means; but the elaborate experiments of Regnault show that in a calm in the open air or in a chamber, the wet bulb surrounds itself with its own humid atmosphere, and with a breeze blowing upon it the temperature of the wet bulb falls or alternates as the wind blows more or less rapidly upon it. Moreover, Professor Orlebar points out a source of error to which no doubt all the observations in India were more or less subject, namely, the proximity of the dry bulb to the wet bulb, and the cold from the latter in consequence depressing the temperature of the dry bulb, two, three, or more degrees below the temperature of the air, necessarily producing fallacious results. Making allowance for the defects of Daniell's hygrometer, the dew-points obtained by its means are infinitely more worthy of confidence than those obtained by means of the wet bulb. On the whole, I would not venture to say more with respect to normal conditions of moisture in India, than that the air of the sea-coast has always a much greater fraction of saturation than the lands of the interior, and that the elevated plateau of the Deccan is periodically subject to very great degrees of dryness.

The rain-tables are so extensive that it will only be necessary to point out some unexpected phenomena connected with the distribution of rain. It is found both on the sea-coasts and on the table-lands of the Deccan, that within very limited areas, the differences in the fall of rain may be very great. With nine rain-gauges employed in the small island of Bombay in the months of June and July, in the monsoon of 1849, the quantity collected in the different gauges ranged in July from 46 inches to 102 inches, and in June from 19 inches to 46 inches. At Sattarah, with three rain-

gauges within the distance of a mile, they differed in their contents several inches from each other; and at Mahabuleshwur and Paunchgunny, nearly on the same level, the latter place being only eleven miles to the eastward of the former, the difference in the annual fall of rain was respectively 254 inches and 50 inches! The normal conditions are, that there is a much greater fall of rain on the sea-coasts than on the table-lands of the Deccan, but that the Ghâts intervening between the coasts and the table-lands have three times the amount of the fall on the coasts, and from ten to fifteen times the amount of the fall on the table-lands of the interior; the paucity of the fall of rain at Cape Comorin and in the mouths of the Indus would also appear to be normal conditions.

The Tables must be referred to for the winds; the normal states are those of the S.W. and N.E. monsoons, and the influence of the latter is periodically felt at the height of 8640 feet, which height would appear just at the upper surface of the stratum of air constituting the S.W. monsoon; but hourly observations for lengthened periods of time are necessary from Dodabetta, to determine what really are the periodical winds at that height. From the points other than those between S. and W., and N. and E., there is also at the several stations a certain amount of periodicity in the winds; the winds that are common to different stations having only a slant more or less at the different stations; for instance, the S.W. and N.W. winds of Bombay blowing in the summer months in Calcutta incline rather to be S. and N. winds, than S.W. and N.W. winds; but to be enabled to speak with any precision upon this branch of the meteorology of India, and indeed upon most other branches with a comprehensive and philosophical object, hourly observations are necessary,—simultaneously taken with previously compared instruments by zealous observers; and having the records in a form common to all the observers, so as to admit of rigid comparisons:—when this is done, not only in India but in Europe, meteorologists will be in a better condition to generalize and propound normal conditions, than the state of our knowledge at present would justify, for it must be borne in mind that "Error latet in generalibus."

## XVI. *On the* Pelorosaurus; *an undescribed gigantic terrestrial reptile whose remains are associated with those of the Iguanodon and other Saurians in the Strata of Tilgate Forest, in Sussex.*

*By* Gideon Algernon Mantell, *Esq., LL.D., F.R.S., F.L.S.,*
*Vice-President of the Geological Society, &c.*

Received November 22, 1849,—Read February 14, 1850.

I HAD for a long while entertained the idea that among the fossil remains collected from the Wealden deposits of the South-East of England, there were indications of an enormous Lizard entirely distinct from the Iguanodon, Megalosaurus, Cetiosaurus, and other genera which have been named and more or less accurately determined; and I have at length obtained such evidence in support of my opinion, as induces me to submit to the Royal Society the data which appear to establish the existence of a terrestrial reptile contemporary with the Iguanodon, and which equalled, if not surpassed in magnitude, that colossal herbivorous Saurian.

I shall not on the present occasion enter upon those minute anatomical details which are indispensable for the solution of many of the difficult problems which but too often perplex and bewilder the palæontologist, but content myself with faithful descriptions and figures of such facts as will suffice to establish my proposition; in the hope that these guesses at truth, which recent investigations have suggested to my mind, may serve to direct future labourers in the right path of inquiry, and tend to enlarge our knowledge of that remarkable fauna which prevailed in the islands and continents of the Cretaceous, Wealden, and Oolitic ages.

The occurrence of very large isolated vertebræ, and portions of femora with medullary cavities, indicating animals of terrestrial habits, and of great size, and which, though assigned to the Cetiosaurus, could not properly be included in a genus of aquatic marine reptiles with solid bones like the Cetaceans, first suggested to me the probability of there having existed another genus of Saurians contemporary with those previously mentioned, and to which some of the supposed Cetiosaurian remains might belong. This idea, though vague, seemed to offer an explanation of certain discrepancies between some of my statements and those of other cultivators of this branch of comparative anatomy.

The stupendous humerus or arm-bone of a terrestrial reptile from the strata of Tilgate Forest, in Sussex, which I have now the honour to place before the Royal Society, will, I believe, establish the correctness of that opinion.

This splendid fossil was obtained from the locality in which was situated the

quarry represented in the frontispiece of my work on the Geology of the South-East of England, and that yielded to my early researches the teeth of the Iguanodon and numerous other highly interesting remains. The bone was imbedded in the fawn-coloured sandstone that prevails in the Wealden of that part of Sussex, at the depth of 25 feet beneath the surface of the soil. The distal part of the bone, to the extent of 2 feet, was discovered in 1847, by Mr. Peter Fuller of Lewes, and some months afterwards the middle portion was found at a higher level; a line of fault having traversed the rock and imbedded bone, and occasioned the subsidence of the portion previously met with. At length other fragments were discovered and extricated from the rock, and the whole replaced and cemented together in the admirable state in which the fossil now appears, by the intelligent collector in whose possession I had, a few weeks since, first the gratification of seeing this unique and stupendous relic from the Weald of my native county*.

This bone is the right humerus, and bears a closer resemblance in its general character to the analogous element in the Crocodile, than to that of the Lacertians. It is $4\frac{1}{2}$ feet long, and 32 inches in circumference at the distal extremity. It is in the ordinary state of mineralization of the bones from the Wealden sandstones, being of a rich umber colour, and very heavy from an impregnation of oxide of iron. The surface presents a smooth appearance, but upon close inspection is found to be finely striated: it evidently belonged to an animal arrived at maturity, but not aged†.

The inferior or distal end, and nearly three-fourths of the shaft, are perfect; but a considerable part is wanting on each side the proximal extremity. Fortunately the base of the salient deltoid process, so characteristic of the humerus in the Crocodiles, is well-defined (Plate XXI. fig. 1$^a$ *c*), and affords grounds for supposing that the upper part, which is deficient, did not materially differ from the recent type.

The transverse fracture through the middle of the shaft (Plate XXI. fig. 1$^a$ *f*) has been left disunited, to show the large medullary canal which is filled up with concreted sand; as is usually the case in the long bones of the Iguanodon from the same locality.

The thickness of the wall of the shaft at this section (Plate XXI. fig. 1$^a$) is 1 inch; the transverse diameter of the medullary cavity 3 inches. Mr. Fuller informs me that the canal extended to within one-third of the head of the bone, as in the femur of the Iguanodon.

The fossil, in its general form, is straighter than the humerus of the Crocodile, and the depressions between the condyles, both anteriorly and posteriorly, are relatively shallower. The surface for articulation with the fore-arm (Plate XXI. fig. 1 *b*) is

* I cannot refrain from expressing my warmest thanks to Mr. Fuller, for the gratifying compliment paid me (though a personal stranger) as the original explorer of the Geology of Sussex, in allowing me to possess this interesting fossil, although he had previously refused several liberal offers.

† Thin sections of the bone exhibit under the microscope the intimate structure beautifully preserved; the bone-cells, and Haversian canals, are as distinct as in recent bones.

smoother and more uniform, but as the epiphyses are wanting, and both extremities of the bone somewhat abraded by attrition, I am led to conclude that in the recent state, the radio-ulnar articulation must have closely resembled the crocodilian type.

In the posterior aspect (Plate XXI. fig. $1^b$), the double bend or curve so strikingly conspicuous in the shaft of the crocodilian arm-bone, is wanting; the deltoid ridge (Plate XXI. fig. $1^b$ *c*) commences much lower down, and above the fractured end of this process (fig. $1^b$ *c*) the bone expands into the wide flattened head, for articulation with the glenoid socket, formed by the union of the coracoid and scapula. Although the general character of the fossil corresponds in so many respects with that of the Crocodile, yet there are such marked discrepancies, that I have not ventured to introduce an outline indicative of the probable form of the parts that are deficient; for there is ample space for the commission of important errors in such a substitution, which might form a stumbling-block to future observers.

To facilitate comparison I have subjoined figures of the right humerus of the recent Gavial, and of the Iguanodon, and Hylæosaurus, reduced to an uniform scale: the arm-bone of the Gavial belongs to a skeleton 18 feet long, in the museum of that eminent physiologist, my friend Dr. Robert Grant.

It will be seen at a glance that the enormous bone under consideration differs essentially from the humeri of all the Saurians with whose remains it was found associated. The large medullary cavity at once separates it from the bones referred to the Polyptychodon and Cetiosaurus; for in these animals the long bones are composed of "coarse cancellous tissue without any trace of medullary cavity*."

These data appear to me sufficient to warrant the establishment of a new genus for the colossal air-breathing reptile to which this remarkable humerus belonged, and I propose the name of *Pelorosaurus*† to indicate the enormous magnitude of the original.

I now pass to the consideration of other parts of the skeleton, or, to express myself more correctly, of certain detached and isolated bones found in the same quarry with the gigantic humerus, and which, for reasons to be stated in the sequel, may with greater probability be assigned to the *Pelorosaurus*, than to any other of the colossal reptiles obtained from the Wealden deposits.

### *Anterior Caudal Vertebræ of the Pelorosaurus*, Plate XXII. and Plate XXIV. and XXV.

The vertebræ which I would assign to the *Pelorosaurus* with but little hesitation, are four anterior caudals of a very remarkable character, which I found many years since in the same stratum as the humerus above described, and at the distance of but a few yards. They were firmly imbedded and lying in various positions in a

* Reports on British Fossil Reptiles, 1841, p. 102. I have a series of bones from Brook in the Isle of Wight, through the kindness of my distinguished friend Sir R. I. Murchison, proving the existence of Cetiosauri in the Wealden; all the long bones are destitute of a medullary cavity.

† Πέλωρ *pelor*, monster, unusually gigantic.

large block of sandstone, and I succeeded, after much labour, in clearing them from the stone with their processes nearly entire; in the progress of my task a chevron bone of the crocodilian type, 10 inches long (Plate XXII. fig. 8), was laid bare and extricated.

When these splendid fossils were first discovered, I referred them to the Iguanodon; subsequently they were named by Professor Owen *Cetiosaurus brevis**; and lastly, Dr. Melville and myself, in my Memoir on the Iguanodon†, suggested the necessity of adopting a different specific appellation, and proposed that of "*Conybeari*;" we were unwilling to remove them from the genus Cetiosaurus, till corroborative evidence was obtained to justify the change.

The description of these vertebræ in detail will be found in the British Association Reports for 1841 (p. 97), and by Dr. Melville in the Philosophical Transactions, 1849 (p. 296); but without figures no adequate idea can be given of the originals‡. I have therefore annexed delineations on a reduced scale, $\frac{1}{4}$ *linear*, Plate XXII., and two views of the largest vertebra $\frac{3}{8}$ths the natural size, Plate XXIV. and XXV. I have been induced to add the two last drawings in order that the subject may be fully comprehended.

These vertebræ are distinguished by the subquadrangular form of the articulating facets of the centrum or body, and the relative shortness of the antero-posterior diameter (Plate XXII. fig. 7). The largest is $7\frac{1}{2}$ inches in the transverse, and $6\frac{3}{4}$ inches in the vertical diameter of the anterior face, and but 6 inches in the posterior: the length or antero-posterior dimension is but $3\frac{1}{2}$ inches. The height to the top of the spinous process is 13 inches. The diameter of the neural canal, for the spinal marrow, is 2 inches. The other three bones are somewhat smaller; the most distal being only 6 inches transversely.

These vertebræ are slightly concave in front, and almost flat behind; the upper part of the anterior face being the deepest, as shown in Plate XXII. fig. 5$^a$. The sides of the body are concave, both lengthwise and vertically, with a transverse median convexity, as seen in Plate XXII. fig. 5$^a$.

The inferior surface of the centrum (Plate XXII. fig. 6) is slightly concave in its antero-posterior diameter, and divided by a longitudinal sulcus into two ridges, whose terminations obscurely indicate the position of the hæmapophysial articulations. It is noticeable, that in vertebræ of such magnitude, well-defined articulating spaces for the chevron bone are not present.

The neural arch presents the most peculiar characters; it is large, and anchylosed to the anterior half of the upper surface of the centrum; the posterior part of which is left free, as shown in fig. 5$^c$ and 7, Plate XXII. The anterior oblique processes

* These vertebræ and the chevron bone, are placed in the same case as the bones of the Iguanodon, in the Gallery of Organic Remains of the British Museum.

† Philosophical Transactions, 1849, p. 297.

‡ Sir J. G. Dalyell very properly remarks, that "delineation should be the inseparable accompaniment of description in natural history."

(Plate XXII. fig. 5ª, *g*, *g*) project directly forwards, and advance over the exposed part of the body of the contiguous vertebra (Plate XXII. fig. 7); as there are no posterior oblique processes, the anterior are received in depressions on each side the spinous process (see Plate XXII. fig. 5 and 7 *h*, *h*). The transverse processes (*f*, *f*) are very strong and short, and project at nearly right angles from the body; the spinous process (*e*) is short and thick.

In Plate XXII. fig. 7, the four vertebræ are represented in a consecutive line, for the purpose of explaining the mode of articulation above described, but it is doubtful whether the two posterior bones are in their natural position; it seems probable that there was an intermediate vertebra between the second and third, and between the third and fourth, so that two more would be required to complete the series. The hæmapophysis or chevron bone, Plate XXII. fig. 8, is obviously too small for articulation with either of the above vertebræ; it is however important, as showing the crocodilian modification of this caudal element of the gigantic original.

*Median caudal vertebræ*, Plate XXIII. fig. 1 and 3, and Plate XXVI.—From the same quarry I obtained two vertebræ belonging in all probability to the middle part of the tail; and which, though scarcely large enough to appertain to the same individual as the above anterior caudal, present such characters as might be expected in the more distal part of the same region. The centrum of the largest specimen (Plate XXIII. fig. 10 and Plate XXVI.) is $7\frac{1}{4}$ inches long; the transverse diameter of the anterior face is 5 inches, the vertical $4\frac{1}{4}$ inches; height to the top of the spine $5\frac{1}{4}$ inches. Both the facets of the centrum are slightly concave, and are most deeply excavated in the upper part, as in the large anterior caudals. The neural arch is anchylosed to the anterior half of the body, the posterior part being uncovered. The inferior surface (Plate XXIII. fig. 10ª *c*) is concave antero-posteriorly, and two slightly elevated ridges terminate behind in distinct hæmapophysial surfaces (*k*, *k*), which are $1\frac{3}{4}$ inch apart, and are evidently fitted for articulation with a chevron bone of the type already described (Plate XXII. fig. 8).

*Distal caudal vertebra*, Plate XXIII. fig. 11.—In referring the unique caudal here figured to the same category as the preceding, I offer the suggestion as only probable. The centrum is of a subcylindrical form, $4\frac{1}{2}$ inches long, and slightly concave on both facets. The most remarkable feature in this bone is the anchylosis or rather confluence of the heads of the chevron bone with the body (Plate XXIII. fig. 11 *j*, *j*), a character common in fishes, but which, I believe, is unknown in reptiles, save in one genus, the fossil animal of Mæstricht, the Mosasaurus, whose occurrence in the English chalk was first ascertained in 1820, by my discovery of two concavo-convex caudals with confluent chevron bones*. The remarks of the illustrious Cuvier on the caudal vertebræ of the Mosasaurus, are in every respect applicable to the specimen under consideration. After mentioning the median caudals as having "*à leur face inférieure deux petites facettes pour porter l'os en chevron*," he describes the more

* Geology of the South Downs, Plates XXXIII. and XLI.

distal series which form a great part of the tail; in these "*l'os en chevron n'y est plus articulé, mais sondé, et fait corps avec elles**."

The structure of the spinal column of the Mosasaurus therefore proves that vertebræ having the chevron bone articulated by two distinct facets (as Plate XXII. fig. 8), may be followed, in a more distal part of the caudal region, by a series with the hæmapophysis anchylosed to the centrum (as in Plate XXIII. fig. 11).

*Femora and Tibiæ.*—From the Wealden strata of Tilgate Forest, Hastings, and the Isle of Wight, I have seen fragments of the distal extremity of femora with medullary cavities, which, though too imperfect to admit of accurate determination, were obviously those of a gigantic terrestrial reptile, distinct from the Iguanodon and Megalosaurus.

From Sandown Bay, in the Isle of Wight, I have the proximal end of a tibia of enormous size, the circumference of the head of the bone being 34 inches, a magnitude surpassing that required for a tibia to articulate with the largest known femur, and presenting such deviations in form from the tibiæ of the Iguanodon, as to render it highly probable that this bone belonged to the *Pelorosaurus*.

*Indications of the Pelorosaurus in the Oolitic strata.*—The general accordance of the terrestrial fauna and flora of the Oolitic period, (as proved by the remains of land animals and plants imbedded in the fluvio-marine deposits of that formation,) with those of the Cretaceous and Wealden, renders it probable that vestiges of most, if not all, of the genera and species of land reptiles that occur in the latter will be found in the former strata. Thus as the Iguanodon, Pterodactyles, with Clathrariæ and Dracænæ, are found in the Chalk, and the Megalosaurus, with Cycadeæ and Coniferæ, in the Wealden, traces of the *Pelorosaurus* may be expected to occur in the Oolite. To ascertain this fact, I availed myself of the liberal permission of my friend the Dean of Westminster to examine his splendid collection, and I repaired to Oxford and diligently inspected the numerous specimens of Saurian remains which it contains, especially those from the Wealden and Oolite.

To avoid prolixity I will but remark, that among immense quantities of huge vertebræ and bones of the extremities of unequivocally marine Saurians, as proved by the cancellated structure of their centres, and which had been properly referred to Pliosaurus, Cetiosaurus, &c., there are portions of femora, vertebræ, and tarsal phalangeal and ungueal bones, which appear to be distinct from those of any established genus. I refer especially to several caudal vertebræ resembling that from Tilgate Forest (Plate XXIII. figs. 9 and 10), which are probably of the *Pelorosaurus*, and large curved claw-bones, from 4 to 6 inches long. These were found at Chipping Norton, associated with vertebræ, &c. of Cetiosaurus, and were accordingly assumed to belong to the same genus of reptiles.

But the specimens which come more immediately within the scope of this inquiry are portions of femora from Enstone, which appear to differ from those of the Mega-

* Ossemens Fossiles, tome v. p. 327. Edit. 1824.

losaurus and Iguanodon. They belong to a huge terrestrial reptile, in which the *patellar* space is smooth, and not traversed by a deep furrow as in the femur of the latter. The structure of these fossils led me to examine with great care the enormous femur obtained by Mr. STRICKLAND from the Bradford clay at Enslow Bridge, on the Charwell, eight miles from Oxford. This specimen is now affixed to the wall in Dr. BUCKLAND's museum, at a considerable height from the floor, and therefore cannot be examined with facility. Unfortunately too the bone was found in so shattered a condition that it was necessary to cement its anterior face to a board. The posterior surface pressed flat, the condyles and popliteal space, and the outline of the sides of the shaft, are therefore the only characters now displayed; the proximal extremity or head is wanting. This bone exactly corresponds in length and width with the humerus of the *Pelorosaurus*. The condyloid extremity is the only portion in a normal state. The condyles (so far as I could ascertain from an elevated and inconvenient position on a ladder) are more equal, and wider apart, than in the Iguanodon and Megalosaurus; but the general appearance of the bone is so similar to that of the femur of the Iguanodon when shattered and pressed flat, that until I ascertained there were no indications of a median trochanter on the mesial border of the shaft, I could not convince myself it did not belong to that reptile. There were no visible traces of a medullary cavity, yet it seemed improbable that the shaft of this enormous and strong bone could have admitted of the degree of compression it had sustained, (for the entire thickness did not appear to exceed 3 or 4 inches,) if it was solid as in the Cetiosauri: Dr. BUCKLAND entirely concurred in this opinion.

To ascertain this important point I wrote to Mr. STRICKLAND, who very obligingly favoured me with an immediate reply. In answer to my inquiries, Mr. STRICKLAND stated, that upon comparing the femur with that of the Megalosaurus, it was evident that it belonged to a different genus: and he had labelled it "*Cetiosaurus*," from its resemblance to portions of femora and other bones found in the same locality, and so named in the Oxford Museum; and likewise, because in the crushed mass of bony fibre which filled the interior, he did not perceive any traces of a medullary cavity; but it is quite possible, Mr. STRICKLAND adds, "that such a cavity may have existed, though now so much obliterated by compression as to have escaped my observation."

The character of the condyloid extremity, and the general form of this bone, appear to me to separate it from the femur of the marine reptiles, to which it has been referred, provisionally, by this distinguished naturalist; if upon a more accurate examination a medullary cavity should be detected, there will be strong grounds for assigning this gigantic thigh-bone to the *Pelorosaurus*; on the contrary, if the shaft should prove to be solid throughout, the supposed relation of this femur to the humerus previously described, will of course be negatived.

*Summary.*—From the facts described he following inferences result:—

1st. Upon the evidence of the humerus alone, the existence during the Wealden

æra, of a stupendous terrestrial Saurian, generically distinct from any previously described; this reptile I propose to name *Pelorosaurus Conybeari*.

2ndly. The great probability that the four large anterior caudal vertebræ with the chevron bone, termed *Cetiosaurus brevis* by Professor Owen, and the two median caudals found in the same stratum as the humerus, and at no great distance from it, belong to the same species; and

3rdly. That certain large bones of Saurians from the oolitic deposits of Oxfordshire, at Enstone and at Enslow Bridge, and hitherto considered as Cetiosaurian, may appertain to the Pelorosaurus.

It may perhaps be expected that some estimate should be given of the probable magnitude of the reptile to which the humerus belonged; but calculations of the length and proportions of the original animal taken from a single bone, or from a few detached bones, can afford but vague and unsatisfactory results. With the view, however, of conveying some idea of the almost incredible bulk of the *Pelorosaurus*, it may be stated, that in the Gavial or Gangetic Crocodile, the length of the humerus is equal to one-eighteenth of the entire length of the animal from the snout to the end of the tail; thus in Dr. Grant's specimen the humerus is 1 foot long; the entire skeleton 18 feet. Computed by this standard the length of the Pelorosaurus would be 81 feet, and the girth of its body about 20 feet. But if we assume the length and number of the vertebræ as the scale, we should have a reptile of relatively very abbreviated proportions; but in either case, a Saurian far exceeding in size all living types, and equalling if not surpassing in magnitude the most colossal of the extinct forms.

From what has been advanced, we perceive that every addition to the zoology of the countries that flourished during the secondary geological ages, affords proof of the high development of the terrestrial reptiles, which appear to have enjoyed the same predominance in those ancient faunas, as the large Mammalia in those of the tertiary and human epochs. The trees and plants associated with the remains of the extinct Saurians, manifest by their affinity to existing forms, that the countries in which they grew possessed as pure an atmosphere, as high a temperature, and as unclouded skies, as those of our tropical climes. There are, therefore, no legitimate grounds to support the hypothesis that during the "Age of Reptiles"—the period when the reptilian class most prevailed—the earth was "in the state of a half-finished planet," and its atmosphere too heavy from an excess of carbon, for the respiration of warm-blooded animals! Such an opinion can only have originated from an imperfect view of the phenomena which these problems embrace. There is as great a discrepancy between certain existing faunas and those of modern Europe, as that presented by the Wealden: for example, those of Australia, Tasmania, New Zealand, and the Galapagos Islands.

By a singular coincidence, on the same day that I obtained the humerus of the *Pelorosaurus* from Tilgate Forest, I received from my eldest son in New Zealand, the most interesting collection of the remains of the extinct gigantic birds of those

islands that has reached this country: and I could but think, that had the respective localities and periods of these birds and reptiles,—both of a size far surpassing all other known types of their respective classes,—been interchanged, and the bones of the Dinornis of New Zealand referred to the Wealden epoch, what speculations would in all probability be hazarded to account for physical conditions assumed to be required by so marvellous a development in numbers and magnitude of the class Aves, to the almost entire exclusion of the Mammalia!

In attempting to explain the natural records of the ancient physical history of the globe and its inhabitants, by our acquaintance with the physiology, anatomy, and economy, of existing organic beings, we cannot be too often reminded of the caution of the sagacious Quetelet, that "our knowledge and our judgments are in general only founded on probabilities more or less great, which it is very important, but very difficult, to estimate at their just value."

FRANKLIN INSTITUTE LIBRARY

---

In conclusion I would beg to remark, that in adding another genus of terrestrial reptiles to those previously established as belonging to the Fauna of the Wealden, I am fully aware of the imperfect manner in which, from various unavoidable causes —especially the pressure of professional duties—my investigations have been carried out. But encouraged in my earliest researches by the illustrious founder of Palæontology, Baron Cuvier, and honoured by the highest award of the Geological Society, I felt reluctant to discontinue researches which no other naturalist seemed disposed to undertake, lest some important additions to our knowledge of the ancient physical condition of the earth and its inhabitants should be unrecorded and forgotten.

*Chester Square, Pimlico,*
*November* 1849.

## Description of the Plates.

### PLATE XXI.

*** The figures of this Plate are all on the same scale, which is $\frac{1}{4}$ linear the natural size.

Fig. 1. The right humerus of the *Pelorosaurus Conybeari*, obtained from the strata of Tilgate Forest in Sussex, by Mr. Peter Fuller of Lewes, and now in the possession of the author.

1ª. Anterior view.

1ᵇ. Posterior view.

1ᶜ. Transverse section of the shaft; *m*, the medullary canal filled with fawn-coloured sandstone.

The dimensions of this bone are as follow:—

Length 54 inches.

Circumference of the distal end 32 inches.

Transverse diameter of the same 13 inches.

Circumference of the shaft at the transverse section 17 inches.

——————————— the fractured end of the deltoid ridge 23 inches.

*a*. The head or proximal extremity.

*b*. Distal or radio-ulnar articulation.

*c*. Deltoid ridge.

*d*. Inner condyle.

*e*. Outer condyle.

*f*. Transverse fracture exposing the section seen in fig. $1^c$.

Fig. 2. Outline of the right humerus of a Gavial 18 feet long.

$2^a$. Anterior view.

$2^b$. Posterior view.

Fig. 3. Humerus of the Hylæosaurus.

Fig. 4. Humerus of the Igüanodon; from Philosophical Transactions, Part II. 1849, Plate XXXI. fig. 19*.

## PLATE XXII.

*** All the specimens here delineated are in the British Museum: the figures are reduced $\frac{1}{4}$ linear the natural size.

Anterior caudal vertebræ and chevron bone of the *Pelorosaurus*?

Fig. 5. The largest and most anterior bone of the series.

$5^a$. Perspective view showing the slightly concave anterior face of the body of the vertebra (*a*), the excavated form of the sides, the anterior oblique processes (*g*, *g*,) and the spinous process (*e*), with the pits or depressions for the reception of the heads of the oblique processes of the contiguous posterior vertebra (*h*).

$5^b$. Front view of the same fossil.

$5^c$. Posterior view, to show the remarkable character occasioned by the absence of oblique processes. The several parts in this and the vertebræ figured in the subsequent plates are thus indicated:—

*a*. Anterior articulating surface of the body or centrum.

*b*. Posterior face.

*c*. Inferior or visceral aspect of the body.

*d*. Neural arch, or neurapophysis.

* There is a typographical error both in the text and lithograph of this bone in the Philosophical Transactions, *loc. cit.*, as to the scale of the figure; it is marked reduced to $\frac{1}{12}$, it should be $\frac{1}{4}$ linear the natural size.

*e*. Spinous process.
*f*. Transverse process.
*g*. Anterior oblique process.
*h*. Depression on the spinous process, occupying the usual situation of the origin of the posterior oblique.
*i*. Spinal canal.
*j*. Chevron bone or hæmapophysis.
*k*. Hæmapophysial surfaces for articulation with the chevron bone.

Fig. 6. A vertebra seen on the inferior aspect.

Fig. 7. Four anterior caudal vertebræ placed in a consecutive series.

Fig. 8. A chevron bone 10 inches long, found imbedded in the same block of sandstone as the vertebræ.
8ª. Outer aspect.
8ᵇ. Inner aspect.
8ᶜ. Lateral view.

## PLATE XXIII.

*** The figures are ¼ linear the natural size.

Median and distal caudal vertebræ of the Pelorosaurus?

Fig. 9. A median or distal caudal vertebra with two eminences on the posterior end of the inferior aspect of the body, to articulate with a double-headed chevron of the crocodilian type.
9ª. Lateral view.
9ᵇ. Posterior face.
9ᶜ. View of the inferior surface.
*k*, *k*. The articulating facets to unite with the chevron bone.

Fig. 10. A larger vertebra of a similar type, obtained from the same locality in Tilgate Forest as the other specimens figured in this memoir, by my friend Capt. Lambart Brickenden, F.G.S.
10ª. Inferior surface.
10ᵇ. Lateral view.
10ᶜ. Anterior view, showing the neural arch.

Fig. 11. A caudal vertebra with the chevron bone anchylosed to the body, as in the distal caudals of the Mosasaurus.
11ª. Lateral view.
11ᵇ. View of the inferior surface.

## PLATE XXIV.

Perspective view of the largest anterior caudal, ⅛th the natural size.

## PLATE XXV.

Anterior view of the same.

## PLATE XXVI.

Perspective view of a median caudal vertebra of the Pelorosaurus, of the natural size; found in the same quarry and stratum as the specimens figured in the preceding Plates; by Capt. LAMBART BRICKENDEN.

## XVII. *On a Dorsal dermal Spine of the Hylæosaurus, recently discovered in the Strata of Tilgate Forest.*

*By* Gideon Algernon Mantell, *Esq., LL.D., F.R.S., F.L.S., Vice-President of the Geological Society, &c.*

Received June 13,—Read June 13, 1850.

In the highly interesting and unique specimen of part of the skeleton of the Hylæosaurus discovered by me in 1832, and now preserved in the Gallery of Organic Remains of the British Museum, the most striking peculiarity is a series of large thin angular processes extending nearly parallel with the left side of the vertebral column. These bones vary in length from 4 to 17 inches, and in form from a somewhat obtuse to an isosceles triangle: there are six or seven in a connected line, and several others detached and dispersed in the block. They terminate distally in a blunt apex, and are expanded at the base in the antero-posterior diameter, but unfortunately in every instance the proximal end is so imperfect that their mode of attachment to the other parts of the skeleton is not clearly demonstrable.

From the general resemblance of these processes to the dermal bones imbedded in the surrounding stone, I was induced to consider them as the remains of a dorsal crest formed by a series of erect dermal plates or spines, which extended along the back of the Hylæosaurus, in the same manner as the cartilaginous scaly dorsal fringe in the Iguana; an opinion which appeared to be corroborated by some detached specimens of a similar character that were subsequently discovered*.

Professor Owen, however, whilst admitting the probability of that suggestion, considered it more likely that the bones in question were abdominal ribs, remarking that "the want of symmetry, and the difference in size and form, in the four succeeding spine-shaped plates, agreed better with the costal than with the dermal hypothesis†." Mr. Broderip and other naturalists have regarded this opinion of Professor Owen as conclusive‡.

For reasons fully stated in my former memoirs on the Wealden Reptiles, it appeared to me highly improbable that these spines could have belonged to the costal system. In 1848 I had an opportunity, for the first time, of making sections of a specimen for microscopical examination, and I then found the internal structure to

* A comparison of these spines with the dermal crest of the *Cyclura*, is given in my original memoir on the Hylæosaurus; Geology of the South-East of England, 1832.

† British Association Report on Fossil Reptiles, by Professor Owen, 1841, p. 116.

‡ Zoological Researches, Chapter on Reptiles.

be identical with that of the dermal scutes of the Hylæosaurus, presenting "long, straight, spicular fibres, decussating each other in all directions, and representing, as it seems, the ossified ligamentous fibres of the original corium*."

At length, after the lapse of eighteen years, I have obtained one of these spines in which the proximal end or base is sufficiently entire to show the nature of its connection with the body of the reptile. This specimen (for which I am indebted to the liberality of Mr. Peter Fuller of Lewes) was found a few weeks since in the same quarry in Tilgate Forest, whence the first discovered skeleton of the Hylæosaurus was obtained; and there is reason to conclude that it may have belonged to the same individual, for several detached dermal scutes and spines of corresponding size and character, have from time to time been found in the sandstone near the spot.

This spine, if perfect, would be 15 inches in length; its base or proximal end is of an elliptical form, with a longitudinal median depression, which is bordered by a gentle rounded eminence; the articulating surface has the corrugated aspect that characterizes the ossified dermal scutes of the Hylæosaurus; and a comparison of the base of this spine with that of the unquestionable dermal bones, confirms the correctness of my original interpretation of the nature of these remarkable processes.

In the accompanying drawings the characters of the original are sufficiently defined, to render further description unnecessary.

This fact is of considerable interest, since it demonstrates in the dermal system of the extinct colossal Saurians of the secondary geological æras, a similar exaggerated development to that which prevails in the living diminutive representatives; but while in the existing Lizards the dermal appendages are flexible and cartilaginous, in the fossil reptiles they are rigid osseous spines; the difference arising from the ossification of the ligamentous fibres of the corium in the dermal bones and spines of the Hylæosaurus.

## Description of the Plate.

### PLATE XXVII.

Fig. 1. Lateral view of the dorsal dermal spine of the Hylæosaurus; reduced to one-half linear.

Fig. 2. View of the articulating surface of the base.

Fig. 3. Magnified view of a portion of the internal structure, showing the decussating ossified fibres of the corium, the bone-cells, and the Haversian canals, as exposed in a section seen by transmitted light.

*Chester Square, Pimlico,*
*June* 1850.

* See Wonders of Geology, 6th edition, p. 437.

# XVIII. *Supplementary Observations on the Structure of the* Belemnite *and* Belemnoteuthis.

*By* Gideon Algernon Mantell, *Esq., LL.D., F.R.S., F.L.S., Vice-President of the Geological Society, &c.*

Received November 5, 1849,—Read February 14, 1850.

As several eminent naturalists have expressed doubts of the correctness of my interpretation of some of the facts described in the Memoir on the Belemnite and Belemnoteuthis, published in the Philosophical Transactions, Part II. 1848, I am induced to lay before the Royal Society the following additional observations in confirmation of the opinions advanced in my previous communication on this subject.

That distinguished naturalist, Mr. J. E. Gray, has especially controverted my statement that the phragmocone of the Belemnites of the Oxford Clay* possessed a pair of elongated shelly processes, which extended beyond the peristome or upper border of the conical chambered shell; the aperture resembling in this respect that of certain species of Ammonites†. In the recently published "*Catalogue of the Mollusca in the Collection of the British Museum*‡," Mr. Gray remarks, "Dr. Mantell has figured a specimen which appears to have an elongated process on each side, like the processes on the sides of the mouth of certain Ammonites; but on examining his specimen I am very doubtful if this appearance does not arise from an accidental fracture of the upper part of the conical shell."

Since the publication of my former Memoir, three Belemnites with phragmocones, in which the parts in question are unequivocally manifest, have come under my observation. Two of these interesting fossils are in the Gallery of Organic Remains in the British Museum: the third is in my possession. In addition to these examples, evidence in proof that this structure is normal, and not the result of accident, has been afforded by numerous detached portions of belemnital phragmocones from the Oxford Clay and Lias, which display well-defined vestiges of the expanded bases of these processes: and that eminent palæontologist, Mr. John Morris of Kensington, informs me that he has recognized their presence in specimens from various strata and localities.

In the three examples above mentioned, that part of the process which extends

* The species of Belemnite to which my observations refer, Mr. Morris informs me is *Belemnites Puzosianus* of D'Orbigny, *B. Owenii* of Mr. Pratt.

† Philosophical Transactions, 1848, Plate XIII. fig. 3. p. 181.

‡ Part 1, *Cephalopoda Antepedia*, p. 124.

beyond the upper or basilar margin of the phragmocone is well defined; and in each of these specimens the extension of the longitudinal plates or bands may be distinctly traced downwards, almost to the distal end or apex, as a thin nacreous shelly plate, striated longitudinally, and having obliquely divergent lines on the ventral margin.

The finest specimen from Wiltshire in the British Museum (Plate XXVIII. fig. 1), like that discovered by my son*, consists of the osselet or guard (*b*) partially invested by its capsule, with the phragmocone in natural apposition: the latter is shattered and pressed almost flat, but preserves a conical outline, and has on the upper part the *right process* (*e*), which extends 5 inches above the peristome or border of the chambered cone: a portion of the left process is seen at *f*; *c*, denotes the lower termination of the process.

Fig. 2 represents the upper portion of this fossil of the natural size, and so clearly shows the parts described that further detail is unnecessary.

I would particularly direct attention to the evident extension of the base of the process (*x*, *x*, *x*) down the phragmocone as a nacreous band or plate finely striated. Under a slightly magnifying power this expansion appears like a thin shelly integument deposited on the external surface of the chambered cone, and is marked with curved diverging lines on the lateral border.

In the former Memoir the number and position of these processes could not be determined with precision; the specimens recently obtained show that there were but two,—one on each side the aperture or peristome,—and these were situated nearer to the dorsal than to the ventral aspect. The siphunculus always occupies the median and ventral side of the phragmocone; and its excentric apex is directed towards the same region, in which is also situated the sulcus of the guard (see Plate XXIX. fig. 5).

In the fragment of a large uncompressed belemnital phragmocone from Lyme Regis, for the loan of which I am indebted to Mr. Morris, the relative position of the parts above described is distinctly exhibited, Plate XXIX.: fig. 3, *f*, *f*, the remains of the lateral processes; *g*, the siphunculus, occupying the ventral aspect; *h*, the dorsal line.

The outline, Plate XXIX. fig. 4, is intended to express concisely the facts described.

With regard to the osselet (the distal solid part of which is generally termed the *guard* or *rostrum*), I would remark, that since my former communication I have inspected many hundred specimens from various localities, and have ascertained that although in detached examples (the ordinary condition in which these fossils occur) the rostrum appears to terminate by a well-defined line at the upper part, yet this is not really the case; for the same radiated structure originally extended upwards, and surrounded and protected the phragmocone as a sheath, and gradually became confluent with the investing capsule or periostricum; probably terminating in a horny flexible integument. A fragment of the receptacle taken from the upper part of a specimen, and which is not thicker than stout paper, is delineated under a mag-

* Philosophical Transactions, 1848, Plate XV. fig. 3.

nifying power of eight diameters in Plate XXIX. fig. 6. In this section are clearly seen the outer integument or periostricum (*a*), the radiated structure of the osselet (*b*), and the shell of the phragmocone (*c*). Among the numerous Belemnites I have examined, *not the slightest trace of an ink-bag or its contents, the sepia*, could be detected.

Belemnoteuthis.—Some uncompressed examples of the distal end of the phragmocones of this Cephalopod have lately been discovered, which must dispel any remaining doubts as to the generic distinction, first established by the late Mr. Channing Pearce in 1842, being based on natural characters.

The specimen figured, Plate XXIX. fig. 7, appears to me to afford conclusive evidence on the points in dispute. By a reference to my former paper, it will be seen that the longitudinal ridges, which are always present on the distal end of the phragmocone of the Belemnoteuthis, are regarded by those observers who contend that the latter belong to Belemnites, as plaits, or folds, originating from fracture and lateral compression. In the fossil before us these ridges are entire and well-defined; two are situated on the ventral and one on the dorsal region. Fig. 7* is a transverse section, enlarged four diameters, in which are shown the form of the ridges and the *radiated structure of the solid part of the phragmocone*: I scarcely need observe, that in the true Belemnite the cone is chambered to the extreme apex. These characters will remind the palæontologist of the very analogous organization of the *Beloptera* of the tertiary strata, alluded to in my former memoir*. In fact it is now proved that the Belemnoteuthis (as was originally suggested by Mr. Channing Pearce and Mr. Cunnington) possessed an osselet of a radiated structure containing a chambered siphunculated cone, but without an extended rostrum or guard; thus forming an interesting transition to the Belemnite, from which it is generically distinct†. From the facts before us, our knowledge of the organization of the genus *Belemnites* comprises the following structures:—

1. The investing periostricum or *capsule*, which enveloped the osselet, and extending upwards, constituted the external parietes of the receptacle.

2. The *Osselet*, characterized by its radiated structure, composed of trihedral prismatic fibres, which terminated distally in a solid rostrum having an alveolus or conical hollow to receive the lower portion of the chambered phragmocone, and proximally in a thin cup-like expansion, which became confluent with the capsule, and formed the receptacle for the viscera.

3. The *Phragmocone*, or conical siphunculated chambered internal shell, the apex of which occupied the alveolus of the rostrum, and the upper part expanded into a capacious chamber, from the basilar margin of which proceeded two elongated testaceous processes.

* Philosophical Transactions, 1848, p. 176.

† The *Conoteuthis Dupinianus* of M. D'Orbigny, from the Upper Neocomian strata of the Department d'Aube, appears, so far as can be determined by mere description, to approach very closely to the Belemnoteuthis. It is stated to have a long slender osselet, terminated by a chambered cone, but without a guard or rostrum.

Some of the specimens in the British Museum and in my own cabinet exhibit on the space around and between the processes, delicate striæ, apparently produced by the imprint of the muscular fibres of the mantle or other tissues; and these I believe are the only indications hitherto observed of the soft parts of the animal to which the Belemnite belonged.

In fine, the *Belemnite* is characterized by its rostrum and the investing capsule, and its phragmocone chambered to the extreme apex and having a pair of testaceous processes at the basilar margin of the peristome*; while the *Belemnoteuthis* has simply an osselet of a radiated fibrous structure, inclosing a conical chambered shell that terminates distally in a solid obtuse point†. Whether the Belemnite resembled the Belemnoteuthis in possessing an ink-bag, and having a body with eight uncinated arms and a pair of long tentacula, future discoveries can alone determine.

Although this communication may be devoid of interest to those who do not especially cultivate the department of natural science to which this inquiry belongs, it will not I trust be deemed unimportant by the palæontologist, since the new facts herein described tend to remove in some degree the obscurity which veils the original structure of a race of highly organized beings, that swarmed in the seas of every part of the globe‡ during the secondary geological periods, from the Lias to the Chalk inclusive, and which appears to have become extinct with the contemporary Cephalopoda, the Ammonites, at the close of the cretaceous epoch§.

*Chester Square, Oct.* 1849.

### *Additional Note.*

February 14, 1850.

Since the previous observations were communicated to the Secretary of the Royal Society, I have been so fortunate as to obtain from the Oxford Clay of Wiltshire, a Belemnite in which the two dorsal processes of the phragmocone are more perfectly displayed than in any specimen hitherto discovered (see Plate XXX.).

From the rarity of such fossils, and their extreme fragility and perishable nature,

* I do not mean to aver that similar processes exist in *every species* of Belemnite, for it is probable that, as in Ammonites, there may have been considerable diversity in the form and size of these appendages; and in some species the basilar margin of the peristome may have been destitute of them: my remarks exclusively refer to the species of Belemnites described in the text.

† The facts described in the text are of course directly opposed to the views expressed in the following extract from the Philosophical Transactions for 1844, p. 74: "The association of the spathose guards with crushed phragmocones *identical in structure* with those in connection with the fossil ink-bags and muscular parts."

‡ Belemnites have recently been discovered in limestone in the Middle Island of New Zealand, by my eldest son, Mr. Walter Mantell.—See Geological Journal for August, 1850.

§ Belemnites first appear in the Lias, where they suddenly attain their maximum development. Many species abound in the Oolitic or Jurassic formation: in the *Greensand* they are likewise abundant; in the *Galt* there are but two or three small species. In the Chalk strata a modification of the type, termed *Belemnitellæ*, appear, and with these the race seems to have become extinct; at least no traces of its existence have been detected in any newer deposits, save the *Belopteræ* of the tertiary previously mentioned. I am not aware that any examples of Belemnoteuthis have been found in the Lias: hitherto I have obtained specimens only from the Oxford Clay and contiguous strata.

it is important to preserve faithful representations taken whilst the specimens are fresh from the stratum, for when the clay contracts by drying, the delicate shelly structure of the phragmocone but too frequently shrivels and flakes off; I know of no means by which this decomposition can be prevented, and am therefore desirous of adding to the illustrations of this communication the accompanying drawing, by Mr. Mounsey, of the beautiful fossil above mentioned, in which are shown the elongated processes of the phragmocone in their natural position on each side the dorsal line; the interval between them is occupied by a thin pellicle of a dark integument marked with very fine diverging parallel striæ; this substance is probably the inner lining of the capsule of the sepiostaire in a carbonized state, a condition in which animal tissues so often occur in argillaceous deposits.

I likewise annex a drawing of another specimen (Plate XXIX. figs. 9, 10) of the distal termination of the osselet of the *Belemnoteuthis*, in which the alveolus or hollow occupied by the chambered shelly cone is exposed; the cavity is filled with calcareous spar, and is surrounded by a dense fibrous radiated structure, analogous to that of the osselet of the true Belemnite; an additional proof that in the Belemnoteuthis this investment is the osselet or guard of the phragmocone. After this evidence, the presumed generic identity of the Belemnite and Belemnoteuthis must, I conceive, be abandoned by every accurate observer; consequently the form and structure of the body and arms, and other soft parts of the Cephalopoda to which the Belemnites belonged, have yet to be discovered.

## Description of the Plates.

### PLATE XXVIII.

Fig. 1. Outline of a remarkably fine specimen of a Belemnite with the phragmocone and its elongated processes, from the Oxford Clay, Wilts. In the British Museum. The length of the original is 22 inches.

Fig. 2. Represents the basilar or upper portion of the above fossil of the natural size.
*e*. The right, and *f*. the left process.
*x*, *x*, *x*. The base of the process spread over the conical shell of the phragmocone.

### PLATE XXIX.

Fig. 3. Part of the phragmocone of a Belemnite from the Lias, in the collection of John Morris, Esq.
3ª. Lateral view of a portion of the same, showing the remains of one of the longitudinal processes on the shell of the phragmocone.

Fig. 4. Outline exhibiting all the known parts of the Belemnite in their relative position, the osselet being split asunder longitudinally, and one side removed to show the situation of the alveolus, &c.

Fig. 5. The rostrum of the osselet of *Belemnites Puzosianus* from the Oxford Clay, Trowbridge, Wilts. In this specimen the upper part of the guard is removed and exposes the distal extremity of the phragmocone lying in its natural position in the alveolus. The ventral aspect is delineated to show the form and situation of the sulcus or groove (the characteristic of this species) in that region: the siphunculus is on the front of the phragmocone in this view.

The several parts represented in the above figures are indicated as follow:—

*a*, *a*. The pair of elongated processes of the phragmocone.
*b*. Osselet, rostrum, or guard.
*b'*. The upward extension of the expanded osselet.
*c*, *c*. Siphuncle.
*d*, *d*. The phragmocone.
*e*. Section of the capsule or outer investment of the osselet.
*f*. The apical or distal termination of the phragmocone.
*g*. The alveolus or hollow in the rostrum in which the end of the phragmocone is situated.
*h*. Vertical section of the guard, showing its fibrous and radiated structure.
*i*. Ventral aspect.
*k*. Ventral sulcus or groove.
*l*. Section of the capsule investing the guard.

Fig. 6. Transverse section of a fragment from the upper part of the receptacle of the Belemnite near the base of the process; magnified eight diameters.

In this thin pellicle are seen, *a*. the Capsule; *b*. the radiated fibrous structure of the osselet distinctly visible, though taken several inches from above the line which is usually regarded as the termination of the spathose osselet; *c*. the shell of the phragmocone.

Fig. 7. The apical or distal end of the phragmocone of the Belemnoteuthis, showing the ventral aspect, and the pair of ridges: natural size.

7*. A transverse section of the same, displaying the internal radiated structure of the phragmocone and its solid apex: magnified four diameters.

** The two ventral ridges. This specimen is in my collection.

Figs. 9, 10. The apical portion of the osselet of the Belemnoteuthis, exposing the alveolus, or cavity occupied by the apex of the chambered cone, filled with spar, and surrounded by the dense, fibrous, radiated investment, analogous to that of the guard of the true Belemnite: the figures are magnified four diameters.

## PLATE XXX.

A Belemnite from the Oxford Clay of Wiltshire, showing the pair of dorsal processes in their natural position: size of the original.

## XIX. *On the Algebraic Expression of the number of Partitions of which a given number is susceptible.* By Sir J. F. W. Herschel, *Bart., K.H., F.R.S.*

Received April 18,—Read May 16, 1850.

(1.) BEFORE entering on the investigation which forms the object of this communication, it will be necessary to recall to recollection some general properties of the differences of the powers of the natural numbers, or of the numbers comprised in the general expression $\Delta^m 0^n$, which I have elsewhere demonstrated, as well as to establish certain preliminary theorems by the aid of those properties, which will be useful in the progress of the inquiry. I shall employ throughout the separation of the symbols of operation from those of quantity, as respects $\Delta$ and 0, in the manner followed in my paper "On the Development of Exponential Functions," published in the Philosophical Transactions, vol. cvi. p. 25 (1816), and further extended in its application in my "Collection of Examples of the Applications of the Calculus of Finite Differences," appended to the translation of Lacroix's Differential and Integral Calculus in 1820*, to which paper and collection the reader is referred for the demonstration of the fundamental properties in question.

(2.) Denoting by $F(x)$ any series of powers of $x$, such as

$$F(x)=Ax^a+Bx^b+Cx^c+\&c.,$$

and by $f(x)$ any other as

$$f(x)=Px^p+Qx^q+Rx^r+\&c.$$

the series

$$AP.\Delta^a 0^p+AQ.\Delta^a 0^q+BP.\Delta^b 0^p+\&c.,$$

continued till the terms vanish, by reason of the peculiar properties of the numbers $\Delta^a 0^p$ &c., will be abbreviatively represented by

$$F(\Delta)f(0);$$

and the following properties of the differences in question will be either found demonstrated in the works above cited, or may very easily be derived from the formulæ therein given :—

$$(1+\Delta)^x 0^y=x^y \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (1.)$$

$$(1+\Delta)^x F(\Delta)0^y=F(\Delta)(x+0)^y \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (2.)$$

$$(1+\Delta)^x F(\Delta)f(0)=F(\Delta)f(x+0) \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (3.)$$

$$(1+\Delta)^x f(0)=f(x) \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (4.)$$

$$\{\log(1+\Delta)\}^x F(\Delta)0^y=y.\underline{y-1}.....\underline{y-x+1}.F(\Delta)0^{y-x} \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (5.)$$

$$\{\log(1+\Delta)\}^x F(\Delta)f(0)=F(\Delta)\left(\frac{d}{d0}\right)^x f(0) \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (6.)$$

* A separate edition of this collection (now out of print) is in preparation.

(3.) Furthermore, if we observe that

$$1-(1+\Delta)^{p+q}=\{1-(1+\Delta)^{p}\}+(1+\Delta)^{p}\{1-(1+\Delta)^{q}\},$$

we shall have, by applying each of these operative symbols to $\mathrm{F}(\Delta)f(0)$,

$$\{1-(1+\Delta)^{p+q}\}\mathrm{F}(\Delta)f(0)=\{1-(1+\Delta)^{p}\}\mathrm{F}(\Delta)f(0)+\{1-(1+\Delta)^{q}\}\mathrm{F}(\Delta)f(p+0)\,; \quad (7.)$$

and therefore

$$\{1-(1+\Delta)^{p}\}\mathrm{F}(\Delta)f(q+0)-\{1-(1+\Delta)^{q}\}\mathrm{F}(\Delta)f(p+0)=\{(1+\Delta)^{p}-(1+\Delta)^{q}\}\mathrm{F}(\Delta)f(0); \quad (8.)$$

(4.) In the particular case where $\mathrm{F}(\Delta)=\frac{1}{\Delta}$, these become

$$\frac{1-(1+\Delta)^{p+q}}{\Delta}f(0)=\frac{1-(1+\Delta)^{p}}{\Delta}f(0)+\frac{1-(1+\Delta)^{q}}{\Delta}f(p+0)\,; \quad \ldots\ldots \quad (9.)$$

and

$$\frac{1-(1+\Delta)^{p}}{\Delta}f(q+0)-\frac{1-(1+\Delta)^{q}}{\Delta}f(p+0)=\frac{(1-\Delta)^{p}-(1+\Delta)^{q}}{\Delta}f(0). \quad \ldots \quad (10.)$$

(5.) Designating by $\mathrm{S}(x^n)$ the sum of the $n$th powers of the natural numbers from 1 to $x$ inclusive, or putting

$$\mathrm{S}(x^n)=1^n+2^n+\ldots\ldots x^n,$$

it is demonstrated (Examples, § 6. Ex. 23.) that

$$\mathrm{S}(x^n)=(-1)^n.\frac{1-(1+\Delta)^{-x}}{\Delta}0^n=(-1)^n.\left\{\frac{x}{1}.0^n-\frac{x(x+1)}{1.2}\Delta 0^n+\frac{x(x+1)(x+2)}{1.2.3}\Delta^2 0^n-\&c.\right\}; \quad \ldots \quad (11.)$$

and again, in § 8, Exp. 11 of the same work, that

$$\mathrm{S}(x^n)=(1+\Delta).\frac{(1+\Delta)^x-1}{\Delta}0^n. \quad \ldots\ldots\ldots\ldots\ldots \quad (12.)$$

(6.) Furthermore, it will be necessary to recall in what follows, the notation and conventions of 'circulating functions,' as explained in my paper on that subject, published in the Philosophical Transactions for 1818, vol. cviii. p. 144. Denoting by $s_x$ the sum of the $x$th powers of the $s$th roots of unity divided by $s$, or the function

$$\frac{1}{s}(\alpha^x+\beta^x+\gamma^x+\&c.),$$

where $\alpha$, $\beta$, $\gamma$, &c. are those roots, any function of the form

$$\mathrm{A}_x.s_x+\mathrm{B}_x.s_{x-1}+\ldots.\mathrm{N}_x.s_{x-s+1}$$

will circulate in its successive values as $x$ increases by units from 0: being expressed by $\mathrm{A}_x$ when $x$ is a multiple of $s$; by $\mathrm{B}_x$ when $x-1$ is such a multiple, and so on. If $\mathrm{A}_x$, $\mathrm{B}_x$, &c. be simply constant, the function may be termed a *periodic* one, since it assumes in periodic and constantly recurring succession the values A, B, C....N, A, B, &c. *ad infinitum*. If $s$ be a specified number, as 2, 3, &c., we shall not the less use the notations $2_x$, $3_x$, &c. to express the respective quantities $\frac{1}{2}(\alpha^x+\beta^x)$, $\frac{1}{3}(\alpha^x+\beta^x+\gamma^x)$, &c., where $\alpha$, $\beta$, &c. are the corresponding roots of unity. And we shall accordingly

have the following general relations, in which $P_x$ and $Q_x$ denote any circulating functions, such that

$$P_x = a_x.s_x + b_x.s_{x-1} + c_x.s_{x-2} + \&c\ldots,$$
$$Q_x = A_x.s_x + B_x.s_{x-1} + C_x s_{x-2} + \&c.$$
$$f(P_x, Q_x) = f(a_x, A_x).s_x + f(b_x, B_x).s_{x-1} + \&c., \quad \ldots\ldots\ldots (13.)$$

of which, particular cases are

$$f(P_x) = f(a_x).s_x + f(b_x).s_{x-1} + f(c_x).s_{x-2} + \&c. \quad \ldots\ldots\ldots (14.)$$
$$P_x^n = a_x^n.s_x + b_x^n s_{x-1} + c_x^n.s_{x-2} + \&c. \quad \ldots\ldots\ldots (15.)$$
$$Q_x^{P_x} = Q_x^{a_x}.s_x + Q_x^{b_x} s_{x-1} + Q_x^{c_x}.s_{x-2} + \&c. \quad \ldots\ldots\ldots (16.)$$
$$P_x Q_x = a_x.A_x.s_x + b_x.B_x.s_{x-1} + \&c. \quad \ldots\ldots\ldots (17.)$$

(7.) As special relations to which we shall refer, we have

$$s_x + s_{x-1} + \ldots\ldots s_{x-s+1} = 1, \quad \ldots\ldots\ldots (18.)$$

and since also ($y$ being any other index)

$$t_y + t_{y-1} + \ldots t_{y-t+1} = 1.$$

Therefore, multiplying and denoting by S the sum of all terms so originating,

$$S\{s_{x-i}.t_{y-j}\} = 1, \quad \ldots\ldots\ldots (19.)$$

$i$ having all values from $i=0$ to $i=s-1$, and $j$ all values from $j=0$ to $j=t-1$. And the same holds good for any number of indices $x$, $y$, $z$, &c.

(8.) If $n$ and $s$ be prime to one another, we shall also have

$$n_x + n_{x-s} + n_{x-2s} + \ldots n_{x-(n-1)s} = 1. \quad \ldots\ldots\ldots (20.)$$

For if the series of numbers $0, s, 2s, \ldots (n-1)s$ be divided by $n$, they will leave $s$ remainders, all different, and all less than $n$, so that among them will be found, though not in the same order, all the numbers $0, 1, 2, \ldots (n-1)$, whence, since

$$n_{x-i} = n_{x-sm-i},$$

the truth of the equation (20.) is apparent.

(9.) If $n$ be a multiple of $s$, or $n=ts$, then

$$n_x + n_{x-s} + n_{x-2s} + \ldots n_{x-\overline{t-1}.s} = s_x. \quad \ldots\ldots\ldots (21.)$$

But if $n$ and $s$ have a common measure $v$, so that $n=tv$, $s=qv$, then

$$n_x + n_{x-s} + \ldots n_{x-u+s} = v_x. \quad \ldots\ldots\ldots (22.)$$

Thus, for example,

$$6_x + 6_{x-2} + 6_{x-4} = 2_x; \quad 6_x + 6_{x-3} = 3_x$$
$$15_x + 15_{x-6} + \ldots 15_{x-24} = 3_x.$$

(10.) To find the product or other functional combination of circulating or periodic functions having different periods of circulation, they must be reduced to a common period. Thus, if $m$ represent the product of $s$ and $t$ divided by their greatest com-

mon measure, and the functions to be combined be

$$P_x = a_x.s_x + b_x.s_{x-1} + \&c.$$
$$Q_x = A_x.t_x + B_x.t_{x-1} + \&c.,$$

we have by equation (22.),

$$P_x = a_x.m_x + b_x.m_{x-1} + \ldots + a_x.m_{x-s} + b_x.m_{x-s-1} + \ldots \&c.$$
$$Q_x = A_x.m_x + B_x.m_{x-1} + \ldots + A_x.m_{x-t} + B_x.m_{x-t-1} + \ldots \&c.,$$

and consequently

$$f\{P_x, Q_x\} = f\{a_x, A_x\}.m_x + f\{b_x, B_x\}m_{x-1} + \&c.\ldots$$

For example,

$$(a.2_x + b.2_{x-1})(A.3_x + B.3_{x-1} + C.3_{x-2}) = aA.6_x + bB.6_{x-1} + aC.6_{x-2} + bA.6_{x-3} + aB.6_{x-4} + bC.6_{x-5}.$$

(11.) The readiest way in practice and the surest way to avoid mistakes, which in complex cases are very likely to occur, is to proceed by a much easier process, as in the following example. Suppose we would express the product of the three periodic functions

$$P_x = 2_x + 2.2_{x-1}, \quad Q_x = 3_x + 2.3_{x-1} + 3.3_{x-2}, \quad R_x = 4_x + 2.4_{x-1} + 3.4_{x-2} + 4.4_{x-3},$$

the product of 2, 3, 4 divided by the greatest common measure of 2 and 4 is 12, which will therefore be the period of the product. Write then the several coefficients in order as follows: for

| | | | | | | | | | | | | | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| $P_x$ | 1, | 2; | 1, | 2; | 1, | 2; | 1, | 2; | 1, | 2; | 1, | 2; | &c. |
| $Q_x$ | 1, | 2, | 3; | 1, | 2, | 3; | 1, | 2, | 3; | 1, | 2, | 3; | &c. |
| $R_x$ | 1, | 2, | 3, | 4; | 1, | 2, | 3, | 4; | 1, | 2, | 3, | 4; | &c. |
| | 1, | 8, | 9, | 8, | 2, | 12, | 3, | 16, | 3, | 4, | 6, | 24, | |

and we shall have for the product

$$12_x + 8.12_{x-1} + 9.12_{x-2} + 8.12_{x-3} + 2.12_{x-4} + \ldots\ldots 24.12_{x-11}.$$

If the signs of the coefficients, or any of them, differ, they must be of course annexed to each, and the proper sign affixed to each product.

(12.) If we denote by $\frac{x}{s}$ the integer part of the quotient of any number $x$ divided by another $s$, then, universally,

$$\frac{x}{s} = \frac{x}{s}.s_x + \frac{x-1}{s}s_{x-1} + \ldots \frac{x-s+1}{s}s_{x-s+1}; \quad \ldots\ldots\ldots\ldots \quad (23.)$$

$$= \frac{x}{s} - \frac{1}{s}\left\{0.s_x + 1.s_{x-1} + 2.s_{x-2} + \ldots \overline{s-1}.s_{x-s+1}\right\}$$

and therefore the remainder, in the same division, is expressed by

$$x - s.\frac{x}{s} = 0.s_x + 1.s_{x-1} + 2.s_{x-2} + \ldots \overline{s-1}.s_{x-s+1}. \quad \ldots\ldots\ldots \quad (24.)$$

(13.) If, again, we would express the integer part of the quotient in the division of

$\frac{x}{s}$ by a second integer division $t$, we have, putting $y$ for $\frac{x}{s}$,

$$\frac{y}{t}=\frac{y}{t}-\frac{1}{t}\left\{0.t_y+1.t_{y-1}+\ldots(t-1).t_{y-t+1}\right\}$$
$$=\frac{x}{st}-\frac{1}{st}\left\{0.s_x+1.s_{x-1}+\ldots.(s-1)s_{x-s+1}\right\}$$
$$-\frac{1}{t}\left\{0.t_y+1.t_{y-1}+\ldots\ldots(t-1).t_{y-t+1}\right\}; \quad \ldots\ldots\ldots \quad (25.)$$

and so on as far as we please.

(14.) The periodic function $0.t_y+1.t_{y-1}+$ &c. depends implicitly on $x$, because $y$ is dependent on $x$. Its value however (as well as that of any other implicit periodical function) is very easily obtained by following out the process explained in (art. 11). Suppose, for example, we had the more general periodic function of $y$,

$$q_y=a.t_y+b.t_{y-1}+\ldots.h.t_{y-t+1}.$$

Then we may write down the successive values of $x$, $y$, $q_y$ in order thus:

| | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| $x$ | 0, 1, 2, ... | $(s-1)$; | $s, s+1, \ldots.$ | $(2s-1)$; | $2s, \ldots\ldots$; | $ts, \ldots.$ |
| $y$ | 0, 0, 0, ... | 0; | 1, 1, .... | 1 ; | 2 , .....; | $t$ , .... |
| $q_y$ | $a, a, a, \ldots$ | $a$; | $b, b, \ldots.$ | $b$ ; | $c$ , .....; | $a$ , .... |

Thus we see that $q_y$ is a periodical function of $x$, having for its period $st$ instead of either $s$ or $t$ separately, the first $s$ coefficients being all alike and each $=a$, the next $s$ all alike and each $=b$, and so on; or

$$q_y=a\{(st)_x+\ldots(st)_{x-t+1}\}+b\{(st)_{x-s}+\ldots\ldots(st)_{x-2s+1}\}+\ldots\ldots+h\{(st)_{x-ts+s}+\ldots.(st)_{x-ts+1}\}. \quad (26.)$$

(15.) Hence we are enabled to express the value of $\frac{y}{t}$ explicitly as a periodic function of $x$; for by equation (25.), if we put $st=n$,

$$\frac{y}{t}=\frac{x}{n}-\frac{1}{n}\left\{0.s_x+1.s_{x-1}+\ldots.\overline{s-1}.s_{x-s+1}\right\}$$
$$-\frac{1}{n}\left\{0.t_y+s.t_{y-1}+\ldots.s.\overline{t-1}.t_{y-t+1}\right\}.$$

But by equation (21.) we have

$$s_x \;=n_x+n_{x-s}+n_{x-2s}+\ldots n_{x-ts+s}$$
$$s_{x-1}=n_{x-1}+n_{x-s-1}+\ldots\ldots n_{x-ts+s-1}, \text{ &c.};$$

and by the equation (26.) of the foregoing article,

$$t_y \;=n_x+n_{x-1}+\ldots.n_{x-s+1}$$
$$t_{y-1}=n_{x-s}+n_{x-s-1}+\ldots n_{x-2s+1}$$
$$t_{y-2}=n_{x-2s}+n_{x-2s-1}+\ldots.n_{x-3s+1}, \text{ &c.};$$

and consequently by substitution,

$$\frac{y}{t}=\frac{x}{sn}-\frac{1}{n}\left\{0.n_x+1.n_{x-1}+2.n_{x-2}+\ldots\ldots\overline{n-1}.n_{x-n+1}\right\}. \quad \ldots\ldots \quad (27.)$$

(16.) These relations premised, let it be required to express the sum of $x$ terms of the series

$$\varphi(a+b)+\varphi(a+2b)+\ldots\ldots\varphi(a+xb)=S_x.$$

Developing the several terms, we find

$$S_x=\varphi(a)\{1+1+\ldots\ldots x \text{ terms}\}$$
$$+\frac{b}{1}.\varphi'(a)\{1+2+3+\ldots\ldots x\}$$
$$+\frac{b^2}{1.2}\varphi''(a)\{1^2+2^2+3^2+\ldots\ldots x^2\}+\&c.$$

Substituting then for the series of powers of 1, 2, 3, &c. their values as given by equation (11.), and separating the symbols of operation from that of quantity, we get

$$S_x=\frac{1-(1+\Delta)^{-x}}{\Delta}\left\{\varphi(a).0^0-\varphi'(a).\frac{b}{1}.0^1+\varphi''(a).\frac{b^2}{1.2}.0^2-\&c.\right\}=\frac{1-(1+\Delta)^{-x}}{\Delta}\varphi(a-b.0). \quad (28.)$$

(17.) If we use in like manner equation (12.), it gives

$$S_x=(1+\Delta)\frac{(1+\Delta)^x-1}{\Delta}\varphi(a+b.0)=\frac{(1+\Delta)^x-1}{\Delta}\varphi(\overline{a+b}+b.0), \quad \ldots \quad (29.)$$

by employing the transformation of equation (3.), in which $x=1$, $f(0)=\varphi(a+b.0)$. Hence also, if

$$S_x=\varphi(a)+\varphi(a+b)+\ldots.\varphi(a+\overline{x-1}.b),$$

we find in like manner

$$S_x=\frac{(1+\Delta)^x-1}{\Delta}\varphi(a+b.0). \quad \ldots\ldots\ldots\ldots \quad (30.)$$

(18.) Let it next be required to find the sum of the series

$$S_y=\varphi(a+b)+\varphi(a+2b)+\ldots.\varphi(a+yb)$$

to $y$ terms, where $y=\frac{x}{s}$ the integer part of the quotient of an independent index number $x$, divided by any given number $s$. By equation (28.) we have

$$S_y=\frac{1-(1+\Delta)^{-y}}{\Delta}\varphi(a-b.0).$$

Now since

$$y=\frac{x}{s}s_{x-1}+\frac{x-1}{s}s_{x-1}+\ldots\ldots\frac{x-s+1}{s}s_{x-s+1}$$
$$=\frac{x}{s}-\frac{1}{s}\left\{0.s_x+1.s_{x-1}+\ldots.(s-1).s_{x-s+1}\right\}.$$

If we put

$$p=-\frac{x}{s}; \quad q=\frac{1}{s}\left\{0.s_x+1.s_{x-1}+\&c.\right\},$$

we get by equation (9.),

$$S_y=\frac{1-(1+\Delta)^p}{\Delta}\varphi(a-b.0)+\frac{1-(1+\Delta)^q}{\Delta}\varphi(\overline{a-pb}-b.0).$$

Now the first portion of this, since $p=-\frac{x}{s}$, is explicit in terms of $x$, but the other requires further development, for which we must have recourse to equation (16.), putting $Q_s=(1+\Delta)$ and $P_s=q=\frac{1}{s}(0.s_s+1.s_{s-1}+\&c.)$, where we find

$$(1+\Delta)^q=(1+\Delta)^0.s_s+(1+\Delta)^{\frac{1}{s}}.s_{s-1}+(1+\Delta)^{\frac{2}{s}}.s_{s-2}+\&c.$$

But we also have by equation (18.),

$$1= \quad s_s+ \quad s_{s-1}+ \quad s_{s-2}+\&c.$$

Therefore, subtracting and dividing by $\Delta$, and applying each term of operation to the term $\varphi(\overline{a-pb}-b.0)$ of quantity,

$$\frac{1-(1+\Delta)^q}{\Delta}\varphi(\overline{a-pb}-b.0)=\left\{0.s_s+\frac{1-(1+\Delta)^{\frac{1}{s}}}{\Delta}s_{s-1}+\frac{1-(1+\Delta)^{\frac{2}{s}}}{\Delta}s_{s-2}+\&c.\right\}\varphi(\overline{a-pb}+b.0)$$

$$=0.s_s+\frac{1-(1+\Delta)^{\frac{1}{s}}}{\Delta}\varphi(\overline{a-pb}-b.0).s_{s-1}+\frac{1-(1+\Delta)^{\frac{2}{s}}}{\Delta}\varphi(\overline{a-pb}-b.0).s_{s-2}+\&c. \quad (31.)$$

(19.) The expression for $S_y$ in the last article is general and entirely independent of any particular values assigned to $x$, $a$, $b$, $s$, the only relation established being that expressed by the equation $y=\frac{x}{s}$. Suppose therefore that in a certain proposed case we should have

$$a=x+s-1\,; \quad b=-s\,;$$

and therefore

$$pb=x\,; \quad a-pb=s-1,$$

and the expression for the sum of the series becomes

$$S_y=\frac{1-(1+\Delta)^{-\frac{x}{s}}}{\Delta}\varphi(x+s-1+s.0)$$

$$+\frac{1-(1+\Delta)^{\frac{1}{s}}}{\Delta}\varphi(\overline{s-1}+s.0).s_{s-1}$$

$$+\frac{1-(1+\Delta)^{\frac{2}{s}}}{\Delta}\varphi(\overline{s-1}+s.0).s_{s-2}+\&c.\,; \quad (32.)$$

in which expression the first member or non-periodical part is an explicit function of $x$ and $s$, and the periodical part has all its coefficients independent on $x$ and functions of $s$ alone.

(20.) The periodical part of $S_y$ is however susceptible of another form, better adapted for numerical calculation, into which it may be thrown by making $p=q=\frac{1}{s}$ in equation (9.), when it becomes

$$\frac{1-(1+\Delta)^{\frac{2}{s}}}{\Delta}f(0)=\frac{1-(1+\Delta)^{\frac{1}{s}}}{\Delta}f(0)+\frac{1-(1+\Delta)^{\frac{1}{s}}}{\Delta}f\left(\frac{1}{s}+0\right),$$

in which, for $f(0)$ writing $\varphi(\overline{s-1}+s.0)$, it becomes

$$\frac{1-(1+\Delta)^{\frac{3}{x}}}{\Delta}\varphi(\overline{s-1}+s.0)=\frac{1-(1+\Delta)^{\frac{1}{x}}}{\Delta}\left\{\varphi(s-1+s.0)+\varphi(s+s.0)\right\}.$$

Similarly,

$$\frac{1-(1+\Delta)^{\frac{3}{x}}}{\Delta}\varphi(s-1+s.0)=\frac{1-(1+\Delta)^{\frac{1}{x}}}{\Delta}\left\{\varphi(\overline{s-1}+s.0)+\varphi(s+s.0)+\varphi(\overline{s+1}+s.0)\right\},$$

and so on; the general form assumed by our equation (9.), on applying this process, being

$$\frac{1-(1+\Delta)^{\frac{m}{x}p}}{\Delta}f(0)=\frac{1-(1+\Delta)^{p}}{\Delta}\left\{f(0)+f(p+0)+f(2p+0)\ldots.+f(\overline{n-1}.p+0)\right\} \quad . \quad . \quad (33.)$$

Supposing, then, for brevity, we denote the combination $\frac{1-(1+\Delta)^{\frac{1}{x}}}{\Delta}$ by $\nabla$, and that we put

$$\dot{\psi}_1(s)=\varphi(s-1)\ ;\ \dot{\psi}_2(s)=\varphi(s-1)+\varphi(s)\ ;\ \dot{\psi}_3(s)=\varphi(s-1)+\varphi(s)+\varphi(s+1)\ ;\ \&c.,$$

then we shall have, finally,

$$\begin{aligned}S_s=\frac{1-(1+\Delta)^{-\frac{s}{x}}}{\Delta}\varphi\left\{\overline{x+s-1}+s.0\right\}&+0.s_s+s_{s-1}.\nabla\dot{\psi}_1(s+0.s)\\&+s_{s-2}.\nabla\dot{\psi}_2(s+0.s)\\&+\&c.\ ; \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (34.)\\=X+Y,&\end{aligned}$$

where X represents the non-periodical part, a function of $x$, and Y the periodical, whose coefficients are constant.

(21.) For the actual evaluation of these functions, all we have to do is to develope the operative characteristic in powers of $\Delta$, and the attached functions in powers of 0, and to apply them term by term to each other. As regards the function X, we find, by so doing,

$$\begin{aligned}X=\frac{1}{s}\Big\{&\frac{x}{1}.\varphi(x+s-1)-\frac{x(x+s)}{1.2}.\Delta 0.\frac{\varphi'(x+s-1)}{1}\\&+\left\{\frac{x(x+s)(x+2s)}{1.2.3}.\Delta^2 0^2-\frac{x(x+s)}{1.2}.s.\Delta 0^2\right\}.\frac{\varphi''(x+s-1)}{1.2}\\&-\left\{\frac{x(x+s)..(x+3s)}{1...4}\Delta^3 0^3-\frac{x(x+s)(x+2s)}{1.2.3}.s\Delta^3 0^3+\frac{x(x+s)}{1.2}.s^2.\Delta 0^3\right\}.\frac{\varphi'''(x+s-1)}{1.2.3}\\&+\&c.,\ . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (35.)\end{aligned}$$

in which it will be recollected that

$$\Delta 0=1\ ;\ \Delta 0^2=1,\ \Delta^2 0^2=2\ ;\ \Delta 0^3=1,\ \Delta^2 0^3=6\ ;\ \Delta^3 0^3=6\ ;\ \&c.\ \&c.$$

(22.) In like manner, denoting by $\dot{\psi}(s)$ in general, any of the functions $\dot{\psi}_1(s)$, $\dot{\psi}_2(s)$,

&c., we have

$$\nabla\psi(s+0.s)=-\frac{1}{s}\Big\{\psi(s)-\frac{s-1}{1.2}\Delta 0.\frac{\psi'(s)}{1}+\Big(\frac{\overline{s-1}.\overline{2s-1}}{1.2.3}\Delta^2 0^s-\frac{s-1}{1.2}.s.\Delta 0^2\Big).\frac{\psi''(s)}{1.2}$$
$$-\Big(\frac{\overline{s-1}.\overline{2s-1}.\overline{3s-1}}{1.2.3.4}.\Delta^3 0^s-\frac{\overline{s-1}.\overline{2s-1}}{1.2.3}.s\Delta^2 0^s+\frac{s-1}{1.2}.s^2.\Delta 0^2\Big).\frac{\psi'''(s)}{1.2.3}$$
$$+\&c.\Big\}. \qquad\qquad (36.)$$

Hence if we put

$$\Psi(s)=0.s_s+\psi_1(s).s_{s-1}+\psi_2(s).s_{s-2}+\ldots\ldots\psi_{s-1}(s)s_{s-s+1},$$

and denote by $\Psi'(s)$, $\Psi''(s)$, &c. the differential coefficients of $\Psi(s)$, *regarding the discontinuous functions* $s_s, s_{s-1}$, &c. *as incapable of differentiation*, we shall have, finally,

$$Y=-\frac{1}{s}\Big\{\Psi(s)-\frac{s-1}{1.2}\Delta 0.\frac{\Psi'(s)}{1}+\Big\{\frac{\overline{s-1}.\overline{2s-1}}{1.2.3}\Delta^2 0^s-\frac{s-1}{1.2}.s.\Delta 0^2\Big\}.\frac{\Psi''(s)}{1.2}$$
$$-\Big\{\frac{\overline{s-1}\ldots\overline{3s-1}}{1\ldots.4}\Delta^3 0^s-\frac{\overline{s-1}.\overline{2s-1}}{1.2.3}.s.\Delta^2 0^s+\frac{s-1}{1.2}s^2.\Delta 0^2\Big\}\frac{\Psi'''(s)}{1.2.3}$$
$$+\&c.\Big\}. \qquad\qquad (37.)$$

(23.) As regards $s$, in every part of the following investigation it will be regarded as a mere given integer number, so that the coefficients in $s$ will come to be calculated in absolute numbers and need give no further concern. It is otherwise with those in $x$, which mix themselves up with the $x$ contained in $\varphi(x+s-1)$ and its differential coefficients in a way requiring special examination, as functions of an independent variable. Let us therefore consider the term multiplied by $\left(\frac{d}{dx}\right)^n\varphi(x+s-1)$ in the development of $\varphi(x+\overline{s-1}-s.0)$. This term will be expressed in ARBOGAST's notation by

$$\frac{s^n.0^n}{1.2.\ldots\ldots n}\mathrm{D}^n\varphi(x+s-1),$$

and the corresponding term in X will be

$$\frac{s^n}{1.2\ldots n}.\mathrm{D}^n\varphi(x+s-1).\frac{1-(1+\Delta)^{-\frac{s}{s}}}{\Delta}0^n.$$

The development of this in factorials $x$, $x+s$, $x+2s$, &c., and functions $\varphi$, $\varphi'$, $\varphi''$, &c., is accomplished in equation (35.), but if we would effect it in powers of $x$ we must proceed as follows:—

Suppose $e=2{\cdot}7182818$, &c. Then we have

$$\frac{1-(1+\Delta)^{-\frac{x}{s}}}{\Delta}0^n=\frac{1-e^{-\frac{x}{s}.\log(1+\Delta)}}{\Delta}0^n$$
$$=\frac{x}{1.s}.\frac{\log(1+\Delta)}{\Delta}0^n-\frac{x^2}{1.2.s^2}.\frac{\{\log(1+\Delta)\}^2}{\Delta}0^n+\frac{x^3}{1.2.3}.\frac{\{\log(1+\Delta)\}^3}{\Delta}0^n-\&c.$$

But by equation (5.),

$$\frac{\{\log(1+\Delta)\}^{i+1}}{\Delta}0^n=\{\log(1+\Delta)\}^i.\frac{\log(1+\Delta)}{\Delta}0^n$$

$$=n(n-1)....(n-i+1).\frac{\log(1+\Delta)}{\Delta}0^{n-i},$$

and therefore the foregoing expression becomes

$$\frac{x}{s}.\frac{\log(1+\Delta)}{\Delta}0^n-\frac{n}{2}\left(\frac{x}{s}\right)^2.\frac{\log(1+\Delta)}{\Delta}0^{n-1}+\frac{n(n-1)}{2.3}.\&c.;$$

or, inverting the order of the terms,

$$(-1)^n.\left\{\frac{1}{n+1}\left(\frac{x}{s}\right)^{n+1}.\frac{\log(1+\Delta)}{\Delta}0^0-\left(\frac{x}{s}\right)^n.\frac{\log(1+\Delta)}{\Delta}0^1+\right.$$

$$\left.+\frac{n}{2}\left(\frac{x}{s}\right)^{n-1}.\frac{\log(1+\Delta)}{\Delta}0^2-\frac{n(n-1)}{2.3}\left(\frac{x}{s}\right)^{n-2}.\frac{\log(1+\Delta)}{\Delta}0^3+\&c.\right\}.$$

Now if $B_1$, $B_2$, $B_3$, &c. be the numbers of BERNOULLI in their order (the even values $B_2$, $B_4$, &c. being severally $=0$), we have

$$\frac{\log(1+\Delta)}{\Delta}0^0=1\,;\quad\frac{\log(1+\Delta)}{\Delta}0^1=-\frac{1}{2}\,;\quad\frac{\log(1+\Delta)}{\Delta}0^2=B_1=\frac{1}{6},$$

and so on. Consequently

$$\frac{1-(1+\Delta)^{-\frac{x}{s}}}{\Delta}0^n=(-1)^n.\left\{\frac{1}{n+1}\left(\frac{x}{s}\right)^{n+1}+\frac{1}{2}\left(\frac{x}{s}\right)^n+\frac{n}{2}B_1\left(\frac{x}{s}\right)^{n-1}+\right.$$

$$\left.+\frac{n(n-1)}{2.3}.B_2\left(\frac{x}{s}\right)^{n-2}+\frac{n(n-1)(n-2)}{2.3.4}B_3.\left(\frac{x}{s}\right)^{n-3}+\&c.\right\},\quad.\quad.\quad.\quad.\quad.\quad.\quad.\quad.\quad(38.)$$

the series on the right-hand side being continued to $n+1$ terms. This is in fact no other than EULER's expression for the sum of the series $1^n+2^n+3^n+$ &c. to a given number of terms represented by $\frac{x}{s}$, only that in the case here under consideration $\frac{x}{s}$ may be any fraction, while EULER's demonstration of the series in question is essentially confined to $\frac{x}{s}=$ a positive integer.

(24.) If we make $x=-1$, the foregoing expression becomes

$$\frac{1-(1+\Delta)^{\frac{1}{s}}}{s}0^n=\nabla 0^n=-\frac{1}{n+1}\left(\frac{1}{s}\right)^{n+1}+\frac{1}{2}\left(\frac{1}{s}\right)^n-\frac{n}{2}B_1.\left(\frac{1}{s}\right)^{n-1}-\frac{n(n-1)}{2.3}.B_2\left(\frac{1}{s}\right)^{n-2}+\&c.$$

$$=-\frac{1}{s^{n+1}}\left\{\frac{1}{n+1}-\frac{1}{2}.s+\frac{n}{2}B_1.s^2-\frac{n(n-1)}{2.3}B_2.s^3+\&c.\right\}\quad.\quad.\quad.\quad.\quad.\quad.\quad.\quad.\quad(39.)$$

continued to $n+1$ terms, inclusive of the vanishing ones having $B_2$, $B_4$, &c. for coefficients.

(25.) Thus the expression for X becomes

$$X=\frac{x}{s}\cdot\phi(x+s-1)-\frac{x^2+sx}{2.s}\phi'(x+s-1) \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (40.)$$

$$+\frac{2x^3+3sx^2+s^2x}{12.s}\phi''(x+s-1)$$

$$-\frac{x^4+2sx^3+s^2x^2}{24.s}\phi'''(x+s-1)$$

$$+\frac{6x^5+15x^4s+10s^2x^3+s^4x}{720.s}\phi^{iv}(x+s-1)-\&c.$$

$$Y=-\frac{1}{s}\left\{\Psi(s)-\frac{s-1}{2}\cdot\Psi'(s)+\frac{s^2-3s+2}{12}\cdot\Psi''(s)+\frac{s^3-2s+1}{24}\Psi'''(s)+\right.$$

$$\left.+\frac{s^4+10s^2-15s+6}{720}\cdot\Psi^{iv}(s)+\&c.\right\} \quad . \quad . \quad . \quad . \quad . \quad . \quad (41.)$$

(26.) We shall now proceed to the more immediate object of this paper, viz. the expression of the number of ways in which a given number $x$ is susceptible of partition, the number of parts being given.

Let $s$ be the number of parts into which $x$ is to be divided, and let ${}^s\Pi(x)$ represent the number of $s$-partitions of which it is susceptible. It is evident then that if $s=1$ there is but one possible, so that in all cases ${}^1\Pi(x)=1$.

If $s=2$, the partitions stand thus:

$$1,\ x-1\ ;\quad 2,\ x-2\ ;\quad 3,\ x-3\ ;\ \ldots.$$

whose number is $\frac{x}{2}$. Therefore we have

$${}^2\Pi(x)=\frac{x}{2}=\frac{x}{2}-\frac{1}{2}\cdot 2_{s-1}.$$

If $s=3$, the partitions so grouped as that none shall be twice repeated, will stand as follows:—

| | | |
|---|---|---|
| 1, 1, $x-2$ | 2, 2, $x-4$ | 3, 3, $x-6$, &c. |
| 1, 2, $x-3$ | 2, 3, $x-5$ | &c. |
| 1, 3, $x-4$ | &c. | |
| &c. | | |

The first column will consist of all the possible bipartitions of $x-1$, each associated with 1, and their number is therefore ${}^2\Pi(x-1)$. The second will consist of the bipartitions of $x-2$, exclusive of $(1,\ x-3)$, each associated with 2. Their number therefore will be identical with the total number of bipartitions of $x-4$, because, so far as the number of cases is concerned, it matters not whether we consider $x-4$ as parted into $(1,\ x-5)$, $(2,\ x-6)$, &c., or $x-2$ as parted into $(2,\ x-4)$, $(3,\ x-5)$, &c., the reason of which will be obvious on trying any particular case. The number of terms therefore in the second column will be ${}^2\Pi(x-4)$. In like manner that in the third will be ${}^2\Pi(x-7)$, the bipartitions of $x-3$ beginning with $(3,\ x-6)$, being

identical in number with those of $x-7$, beginning with $(1, x-8)$, and so on. Thus we have

$$^3\Pi(x)={}^3\Pi(x-1)+{}^3\Pi(x-4)+{}^3\Pi(x-7)+\&c.$$

Next, with respect to the number of terms to which the right-hand member of this equation is to be continued: it will be that of the columns, which will continue without repetition so long as the number $x-2m$ in the first combination $(m, m, x-2m)$ of any one of them shall be not less than $m$, or so long as $x-3m$ shall not be negative. Hence we must have $m=\frac{x}{3}$, since the next greater value of $m$, viz. $m=\frac{x}{3}+1$, will give the tripartition $\left(\frac{x}{3}+1, \frac{x}{3}+1, x-2\frac{x}{3}-2\right)$. Now $x$ cannot exceed $3.\frac{x}{3}$ by more than 2, so that $x-2\frac{x}{3}-2$ cannot exceed $\frac{x}{3}$, and must therefore be less than $\frac{x}{3}+1$. Hence we conclude that the number of tripartitions is derived from that of bipartitions by the equation

$$^3\Pi(x)={}^2\Pi(x-1)+{}^3\Pi(x-4)+\ldots{}^3\Pi(x-7)\ldots\text{.to}\frac{x}{3}\text{ terms.}$$

(27.) Applying a similar reasoning to the higher cases, we shall find as follows:—

$$\overset{s}{\Pi}(x)=\overset{s-1}{\Pi}(x-1)+\overset{s-1}{\Pi}(x-s-1)+\overset{s-1}{\Pi}(x-2s-1)\ldots\frac{x}{s}\text{ terms};\quad\ldots\quad(42.)$$

a relation which, with many others of greater generality, has also been arrived at by Mr. WARBURTON.

(28.) Suppose now we set out from the equation $^1\Pi(x)=1$, and proceed to derive from this value those of $^2\Pi(x)$, $^3\Pi(x)$, &c. in succession. It will be apparent from the course of the foregoing investigations, and from the nature of circulating functions, that the general expression for $\overset{s}{\Pi}(x)$ must consist of two portions, the one non-periodical, a function of $x$, and which may be represented by $\varphi(x)$, the other periodical or circulating, which we may denote by $Q_x$, so that we shall have in general to consider the following form of $\overset{s-1}{\Pi}(x)$,

$$\overset{s-1}{\Pi}(x)=\varphi(x)+Q_x,$$

from which to derive the value of $\overset{s}{\Pi}(x)$.

When we substitute this in the general expression (equation 42.), we get

$$\overset{s}{\Pi}(x)=\varphi(x-1)+\varphi(x-s-1)+\ldots..(y\text{ terms})$$
$$+Q_{x-1}+Q_{x-s-1}+\ldots..(y\text{ terms}),$$

where $y=\frac{x}{s}$. Now with respect to the first portion of this, if $\varphi(x)$ in any one case be a rational integral function of $x$, it will be so in all subsequent cases, as is evident from the course of the preceding investigations. This part of $\overset{s}{\Pi}(x)$ then has been already dealt with, and its complete expression is X+Y of equations (34. 35.), or (38. 39.).

(29.) We have therefore now only to consider the remaining portions, which we shall call Z, viz.

$$Z=Q_{x-1}+Q_{x-s-1}+\ldots. y \text{ terms},$$

$Q_x$ may represent any circulating function. Suppose it to be such that

$$Q_{x-1}=\chi_0(x).m_x+\chi_1(x).m_{x-1}+\ldots.\chi_{m-1}(x).m_{x-m+1},$$

and let any term of this, as $\chi_i(x)m_{x-i}$ (which for brevity we will write simply $\chi(x).m_z$, putting $z=x-i$), be separately considered. Let R be the portion of Z which originates from this term. Then

$$R=\chi(x).m_z+\chi(x-s).m_{z-s}+\chi(x-2s).m_{z-2s}\ldots.. (y \text{ terms}).$$

Let $ts=n$ be the first multiple of $s$, which is also a multiple of $m$. Then after $t$ terms the value of $m_z$, $m_{z-s}$, &c. will recur, and therefore R resolves itself into $t$ separate series, as follows:

$$\begin{aligned}R=&m_z\left\{\chi(x)+\chi(x-n)+\chi(x-2n)+\ldots.\left(\frac{\overline{y-1}}{t}+1\right)\text{terms}\right\}\\&+m_{z-s}\left\{\chi(x-s)+\chi(x-n-s)+\ldots\ldots\ldots\left(\frac{\overline{y-2}}{t}+1\right)\text{terms}\right\}\\&+m_{z-2s}\left\{\chi(x-2s)+\chi(x-n-2s)+\ldots.\left(\frac{\overline{y-3}}{t}+1\right)\text{terms}\right\}\\&+\text{ \&c. } (t \text{ series}).\end{aligned}$$

Now we have

$$\frac{y}{t}=\frac{y}{t}t_y+\frac{y-1}{t}t_{y-1}+\ldots\frac{y-t+1}{t}t_{y-t+1},$$

whence

$$\frac{y-1}{t}=\frac{y-1}{t}t_{y-1}+\frac{y-2}{t}t_{y-2}+\ldots\frac{y-t}{t}t_y=\frac{y}{t}-t_y;$$

and similarly,

$$\frac{y-2}{t}=\frac{y-2}{t}t_{y-2}+\frac{y-3}{t}t_{y-3}+\ldots.\frac{y-t-1}{t}t_{y-1}=\frac{y}{t}-(t_y+t_{y-1}),$$

and so on. But by equation (25.), since $st=n$, we have

$$\frac{y}{t}=\frac{x}{n}-\frac{1}{n}\left\{0.n_x+1.n_{x-1}+2.n_{x-2}+\ldots\overline{n-1}.n_{x-n+1}\right\}.$$

If therefore we put

$$\begin{aligned}\xi&=\frac{x}{n}\\p_x&=\frac{1}{n}\left\{0.n_x+1.n_{x-1}+\ldots.\overline{n-1}.n_{x-n+1}\right\}-1\\&=-\frac{1}{n}\left\{n.n_x+\overline{n-1}.n_{x-1}+\ldots.1.n_{x-n+1}\right\}\\q'_x&=n_x+n_{x-1}+\ldots.n_{x-s+1}\\q''_x&=n_x+n_{x-1}+\ldots.n_{x-2s+1}\\q'''_x&=n_x+n_{x-1}+\ldots.n_{x-3s+1}, \text{ \&c.,}\end{aligned}$$

we shall have

$$1+\frac{\overline{y-1}}{t}=\xi-(p_x+q'_x);\quad 1+\frac{\overline{y-2}}{t}=\xi-(p_x+q''_x);\text{ \&c.,}$$

and therefore by equation (27.),

$$\mathrm{R}=m_x.\frac{1-(1+\Delta)^{-\xi+p_x+q'_x}}{\Delta}\chi(x+n+n.0)$$
$$+m_{x-s}.\frac{1-(1+\Delta)^{-\xi+p_x+q''_x}}{\Delta}\chi(x+n-s+n.0)$$
$$+m_{x-2s}.\&c.+\&c.,$$

which resolves itself, by the transformation of equation (9.), into two sets of terms, $\mathrm{R}'+\mathrm{R}''$, viz.

$$\mathrm{R}'=m_x.\frac{1-(1+\Delta)^{-\xi}}{\Delta}\chi(x+n+n.0)+m_{x-s}.\frac{1-(1+\Delta)^{-\xi}}{\Delta}\chi(x+n-s+n.0)+\&c. \quad . \quad . \quad (43.)$$

and

$$\mathrm{R}''=m_x.\frac{1-(1+\Delta)^{p_x+q''_x}}{\Delta}\chi(n+n.0)+m_{x-s}.\frac{1-(1+\Delta)^{p_x+q''_x}}{\Delta}\chi(n-s+n.0)+\&c. \quad . \quad . \quad (44.)$$

(30.) If, in pursuance of the process followed in the development of Y, we put

$$\mathrm{X}(x)=m_x.\chi(x+n)+m_{x-s}.\chi(x+n-s)+\&c.\ (t \text{ terms}),$$

(denoting also by $\mathrm{X}_0(x)$, $\mathrm{X}_1(x)$ &c., what this expression becomes when for $z$ we put successively $x$, $x-1$, $x-2$, &c.), we shall have

$$\mathrm{R}'=\frac{1-(1+\Delta)^{-\frac{x}{n}}}{\Delta}\mathrm{X}(x+n.0)$$
$$=\frac{1}{n}\left\{x\mathrm{X}(x)-\frac{x(x+n)}{1.2}\Delta 0.\mathrm{X}'(x)+\left\{\frac{x(x+n)(x+2n)}{1.2.3}\Delta^2 0^2-\frac{x(x+n)}{1.2}.n\Delta 0^2\right\}.\frac{\mathrm{X}''(x)}{1.2}-\&c. \quad (45.)$$

The whole assemblage of such terms, giving $z$ all its values, from $x$ to $x-m+1$, therefore will constitute a circulating function explicit in $x$, and which we shall denote by $\mathrm{Z}'$.

As regards $\mathrm{R}''$, since $s$ and $t$ are given numerically, it constitutes a periodic function with constant coefficients, to obtain which we have only to consider that, supposing any one of the exponents $p_x+q_x$ to be represented by

$$a.n_x+b.n_{x-1}+c.n_{x-2}+\&c.,$$

we shall have by equation (16.),

$$\frac{1-(1+\Delta)^{p_x+q'_x}}{\Delta}=\frac{1-(1+\Delta)^{a}}{\Delta}.n_x+\frac{1-(1+\Delta)^{b}}{\Delta}.n_{x-1}+\&c.$$

(31.) In the particular case in which all the functions $\chi_0(x)$, $\chi_1(x)$, &c. are constant, we may consider them as being themselves the coefficients of a periodic function, such that

$$\chi_i=\chi_0.m_i+\chi_1.m_{i-1}+\ldots.\chi_{m-1}.m_{i-m+1},$$

so that if we should meet with such expressions as $\chi_m$, $\chi_{m+1}$, &c., they are to be taken as equivalent to $\chi_0$, $\chi_1$, &c., a mode of regarding a series of arbitrary constants occurring in a certain order which will tend greatly to simplify and add clearness to what follows. Now we have, generally $\chi_i$ being constant,

$$\frac{1-(1+\Delta)^{h}}{\Delta}\chi_i=-h.\chi_i.$$

Consequently, the terms $R_i'$ and $R_i''$ of $R_i$, corresponding to $\chi_i$ in the same way as $R'$ and $R''$ in general to $\chi$, will become

$$R_i' = \{m_x + m_{x-s} + \ldots . m_{x-ts+s}\} \cdot \frac{x}{n} \cdot \chi_i$$

$$R_i'' = -\{m_x + m_{x-s} + \ldots . m_{x-ts+s}\} \cdot p_x \cdot \chi_i$$
$$- m_x \{n_x + n_{x-1} + \ldots . n_{x-s+1}\} \cdot \chi_i$$
$$- m_{x-s} \{n_x + n_{x-1} + \ldots , n_{x-2s+1}\} \cdot \chi_i - \&c.,$$

in which it will be recollected that $z = x - i$.

(32.) Now if $v$ be the greatest common measure of $m$ and $s$ ($v$ being 1, if these numbers be prime to each other), we have

$$m_x + m_{x-s} + \ldots . m_{x-ts+s} = v_x,$$

and consequently the value of $R_i$ or $R_i + R_i'$ becomes

$$R_i = \left(\frac{x}{n} - p_x\right) \cdot \chi_i \cdot v_{x-i} - m_{x-i} \{n_x + \ldots . n_{x-s+1}\} \cdot \chi_i$$
$$- m_{x-s-i} \{n_x + \ldots . n_{x-2s+1}\} \cdot \chi_i$$
$$- \&c.$$

(33.) Assembling together similar results for $R_0$, $R_1$, .... $R_{m-1}$, we have

$$Z = \{\chi_0 . v_x + \chi_1 . v_{x-1} + \ldots . \chi_{m-1} . v_{x-m+1}\} \cdot \left(\frac{x}{n} - p_x\right)$$
$$- \{n_x + \ldots . n_{x-s+1}\} \{\chi_0 . m_x + \chi_1 . m_{x-1} + \ldots . \chi_{m-1} m_{x-m+1}\}$$
$$- \{n_x + \ldots . n_{x-2s+1}\} \{\chi_0 . m_{x-s} + \chi_1 . m_{x-s-1} + \ldots . \chi_{m-1} . m_{x-s+1}\}$$
$$- \{n_x + \ldots . n_{x-3s+1}\} \{\chi_0 . m_{x-2s} + \chi_1 . m_{x-2s-1} + \ldots . \chi_{m-1} . m_{x-2s+1}\}$$
$$- \&c.$$

Now because $m$ and $s$ have $v$ for a common measure, and that $n = ts$ is the first multiple of $s$, which is also a multiple of $m$, it follows that $n = \frac{s}{v} . m$, $\frac{s}{v}$ being an integer. Hence we have by equation (22.),

$$m_x = n_x + n_{x-m} + n_{x-2m} \ldots . + n_{x-n+m}$$
$$m_{x-1} = n_{x-1} + n_{x-m-1} + \ldots . . n_{x-n+m-1}$$
$$\&c. = \&c.$$

Substituting these therefore, and so arranging the terms that $n_x$ shall always stand first, the series within the brackets on the right-hand, in the expression for Z, become respectively

$$\chi_0 . n_x + \chi_1 . n_{x-1} + \ldots . . \chi_{n-1} . n_{x-n+1}$$
$$\chi_{m-s} . n_x + \chi_{m-s+1} . n_{x-1} + \ldots . . \chi_{m-s+n-1} . n_{x-n+1}$$
$$\chi_{m-2s} . n_x + \chi_{m-2s+1} . n_{x-1} + \ldots . \chi_{m-2s+n-1} . n_{x-n+1}, \&c.,$$

which being multiplied by their respective coefficients, $n_s+n_{s-1}+$ &c., we get for Z as follows:—

$$Z=\frac{x}{n}\left\{\chi_0.v_s+\chi_1.v_{s-1}+\ldots.\chi_{m-1}.v_{s-m+1}\right\} \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (46.)$$

$$-p_s.\{\chi_0.v_s+\chi_1.v_{s-1}+\ldots\chi_{m-1}.v_{s-m+1}\}$$
$$-\{\chi_0.n_s+\chi_1.n_{s-1}+\chi_2.n_{s-2}+\ldots.(s \text{ terms})\}$$
$$-\{\chi_{m-s}.n_s+\chi_{m-s+1}.n_{s-1}+\ldots\ldots\ldots(2s \text{ terms})\}$$
$$-\{\chi_{m-2s}.n_s+\chi_{m-2s+1}.n_{s-1}+\ldots\ldots(3s \text{ terms})\}$$
$$-\text{ \&c.}$$

The first line of this is a circulating function, linear in $x$ in all cases except when $v=1$, or $m$ and $s$ are prime to each other, in which case it loses its circulating character and becomes simply

$$\frac{x}{n}(\chi_0+\chi_1+\chi_2+\ldots\chi_{m-1}). \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (47.)$$

As regards the second line, we have

$$-p_s=\frac{1}{n}\left\{n.n_s+\overline{n-1}.n_{s-1}+\ldots1.n_{s-n+1}\right\};$$

and since $n$ is a multiple of $s$, and therefore of $v$, the multiplier within the brackets is readily reduced to a periodic function having $n$ for its period, such as $a.n_s+b.n_{s-1}+$ &c., which, multiplied by $-p_s$, gives

$$\frac{1}{n}\left\{na.n_s+\overline{n-1}.b.n_{s-1}+\text{\&c.}\right\},$$

except when $v=1$, in which case this expression reduces itself to

$$\frac{1}{n}(\chi_0+\chi_1+\ldots.\chi_{m-1})\{n.n_s+\overline{n-1}.n_{s-1}+\ldots.1.n_{s-n+1}\}. \quad . \quad . \quad . \quad . \quad . \quad (48.)$$

(34.) To apply the foregoing formulæ to the expression of particular cases as $\overset{2}{\Pi}(x)$, $\overset{3}{\Pi}(x)$, $\overset{4}{\Pi}(x)$, &c., we begin with $\overset{1}{\Pi}(x)=1$. Therefore, to find $\overset{2}{\Pi}(x)$, we have

$$\varphi(x)=1, \quad \varphi'(x) \text{ \&c.}=0, \quad \psi_1(s)=s-1, \quad s=2;$$

consequently

$$X=\frac{x}{2}; \quad \nabla(s+0.s)=-\frac{1}{2}; \quad Y=-\frac{1}{2}.2_{s-1},$$

and therefore

$$\overset{2}{\Pi}(x)=\frac{1}{2}(x-2_{s-1}). \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (49.)$$

(35.) For the case of $s=3$, we have

$$\varphi(x)=\frac{x}{2}; \quad \varphi'(x)=\frac{1}{2};$$

$$\psi_1(s)=\frac{s-1}{2}=1; \quad \psi_1'(s)=\frac{1}{2}; \quad \psi_2(s)=\frac{\overline{s-1}+s}{2}=\frac{5}{2}; \quad \psi_2'(s)=;;$$

and therefore

$$X=\frac{1}{6}\left\{x(x+2)-\frac{x(x+3)}{2}\right\}=\frac{x^2+x}{12}.$$

For Y we have

$$\Psi(s)=0.3_s+1.3_{s-1}+\frac{5}{2}.3_{s-2}$$

$$\Psi'(s)=0.3_s+\frac{1}{2}.3_{s-1}+3_{s-2}$$

whence by equation (37.),

$$Y=-\frac{1}{12}\left\{2.6_{s-1}+6.6_{s-2}+2.6_{s-4}+6.6_{s-5}\right\}.$$

For Z we have

$$Q_s=-\frac{1}{2}.2_{s-1} \quad Q_{s-1}=-\frac{1}{2}2_s$$

whence

$$m=2,\ s=3,\ ms=6,\ v=1,\ \chi_0=-\frac{1}{2},\ \chi_1=0$$

and by (45.), (46), (47.),

$$\begin{aligned}Z=&-\frac{x}{12}-\frac{1}{12}\left\{6.6_s+5.6_{s-1}+4.6_{s-2}+3.6_{s-3}+2.6_{s-4}+1.6_{s-5}\right\}\\&+\frac{6}{12}\left\{6_s+6_{s-2}\right\}+\frac{6}{12}\left\{6_{s-1}+6_{s-3}+6_{s-5}\right\}\\=&-\frac{x}{12}+\frac{1}{12}\left\{6_{s-1}+2.6_{s-2}+3.6_{s-3}-2.6_{s-4}+5.6_{s-5}\right\}\end{aligned}$$

adding all which parts together, we have X+Y+Z, or

$$\overset{3}{\Pi}(x)=\frac{1}{12}\left\{x^3-6_{s-1}-4.6_{s-2}+3.6_{s-3}-4.6_{s-4}-6_{s-5}\right\}. \quad . \quad . \quad . \quad . \quad . \quad (50.)$$

(36.) When $s=4$, we have, therefore,

$$\varphi(x)=\frac{x^2}{12}, \quad \varphi'(x)=\frac{2x}{12}, \quad \varphi''(x)=\frac{2}{12}$$

and, therefore, by equation (35.),

$$X=\frac{1}{48}\left\{x(x+3)^3-\frac{x(x+4)}{2}.2(x+3)+\left\{\frac{x(x+4)(x+8)}{6}.2-\frac{x(x+4)}{2}.4\right\}.\frac{2}{1.2}\right\}=\frac{x^3+3x^2-x}{144}.$$

For Y we have

$$\psi_1(s)=\frac{(s-1)^2}{12}=\frac{9}{12}; \quad \psi_1'(s)=\frac{2(s-1)}{12}=\frac{6}{12}; \quad \psi_1''(s)=\frac{2}{12}$$

$$\psi_2(s)=\frac{(s-1)^2+s^2}{12}=\frac{25}{12}; \quad \psi_2'(s)=\frac{2(s-1)+2s}{12}=\frac{14}{12}; \quad \psi_2''(s)=\frac{4}{12}$$

$$\psi_3(s)=\frac{(s-1)^2+s^2+(s+1)^2}{12}=\frac{50}{12}; \quad \psi_3'(s)=\frac{2(s-1)+2s+2(s+1)}{12}=\frac{24}{12}; \quad \psi_3''(s)=\frac{6}{12}$$

$$\Psi(s)=\frac{1}{12}\left\{0.4_s+9.4_{s-1}+25.4_{s-2}+50.4_{s-3}\right\}$$

$$\Psi'(s)=\frac{1}{12}\left\{0.4_s+6.4_{s-1}+14.4_{s-2}+24.4_{s-3}\right\}$$

$$\Psi''(s)=\frac{1}{12}\left\{0.4_s+2.4_{s-1}+4.4_{s-2}+6.4_{s-3}\right\},$$

whence by equation (37.),

$$\begin{aligned}
Y&=-\frac{1}{48}\left\{\Psi(s)-\frac{3}{2}\Psi'(s)+\frac{1}{2}\Psi''(s)\right\}\\
&=-\frac{1}{48}\left\{0.4_s+1.4_{s-1}+6.4_{s-2}+17.4_{s-3}\right\}\\
&=-\frac{1}{144}\left\{0.12_s+3.12_{s-1}+18.12_{s-2}+51.12_{s-3}+0.12_{s-4}+3.12_{s-5}+18.12_{s-6}+\right.\\
&\qquad\left.+51.12_{s-7}+0.12_{s-8}+3.12_{s-9}+18.12_{s-10}+51.12_{s-11}\right\}.
\end{aligned}$$

Lastly, for Z we have

$$\begin{aligned}
Q_s&=\left\{-0.6_s-1.6_{s-1}-4.6_{s-2}+3.6_{s-3}-4.6_{s-4}-1.6_{s-5}\right\}.\frac{1}{12}\\
Q_{s-1}&=\left\{-1.6_s-0.6_{s-1}-1.6_{s-2}-4.6_{s-3}+3.6_{s-4}-4.6_{s-5}\right\}.\frac{1}{12},
\end{aligned}$$

consequently

$$m=6,\ s=4,\ v=2,\ t=3,\ n=st=12$$

$$\chi_0=-\frac{1}{12},\ \chi_1=0,\ \chi_2=-\frac{1}{12},\ \chi_3=-\frac{4}{12},\ \chi_4=+\frac{3}{12},\ \chi_5=-\frac{4}{12},$$

and therefore, by equation (46.), which gives the value of Z in this case, putting Z′ for the first line of Z, Z″ for the second and Z‴ for the rest,

$$\begin{aligned}
Z'&=\frac{x}{144}\left\{-1.2_s-0.2_{s-1}-1.2_{s-2}-4.2_{s-3}+3.2_{s-4}-4.2_{s-5}\right\}\\
&=\frac{x}{144}\left\{(-1-1+3).2_s+(0-4-4).2_{s-1}\right\}\\
&=\frac{x}{144}\left\{2_s-8.2_{s-1}\right\}=\frac{x}{144}-\frac{9x}{144}.2_{s-1}\\
Z''&=(2_s-8.2_{s-1}).\frac{1}{144}\left\{12.12_s+11.12_{s-1}+10.12_{s-2}+\ldots..1.12_{s-11}\right\},
\end{aligned}$$

which, putting for $2_s$ and $2_{s-1}$ their values

$$12_s+12_{s-3}+12_{s-4}\ldots..+12_{s-10},$$

and

$$12_{s-1}+12_{s-3}+\ldots.12_{s-11}$$

becomes

$$\begin{aligned}
Z''=\frac{1}{144}\left\{12.12_s-88.12_{s-1}+10.12_{s-2}-72.12_{s-3}+8.12_{s-4}-56.12_{s-5}+6.12_{s-6}-\right.\\
\left.-40.12_{s-7}+4.12_{s-8}-24.12_{s-9}+2.12_{s-10}-8.12_{s-11}\right\};
\end{aligned}$$

and lastly,

$$\begin{aligned}
Z'''&=\frac{1}{12}\left\{1.12_s+0.12_{s-1}+1.12_{s-2}+4.12_{s-3}\right\}\\
&+\frac{1}{12}\left\{1.12_s+4.12_{s-1}-3.12_{s-2}+4.12_{s-3}+1.12_{s-4}+0.12_{s-5}+1.12_{s-6}+4.12_{s-7}\right\}\\
&+\frac{1}{12}\left\{-3.12_s+4.12_{s-1}+1.12_{s-2}+0.12_{s-3}+1.12_{s-4}+4.12_{s-5}-3.12_{s-6}+4.12_{s-7}\right.\\
&\qquad\left.+1.12_{s-8}+0.12_{s-9}+1.12_{s-10}+4.12_{s-11}\right\}
\end{aligned}$$

$$=\frac{12}{144}\Big\{-12_x+8.12_{x-1}-1.12_{x-2}+8.12_{x-3}+2.12_{x-4}+4.12_{x-5}-2.12_{x-6}+8.12_{x-7}+$$
$$+1.12_{x-8}+0.12_{x-9}+1.12_{x-10}+4.12_{x-11}\Big\}.$$

And assembling these several portions, $X+Y+(Z'+Z''+Z''')$, we get

$$\overset{4}{\Pi}(x)=\frac{1}{144}\Big\{x^3+3x^2-9x.2_{x-1}\Big\}+\frac{1}{144}\Big\{0.12_x+5.12_{x-1}-20.12_{x-2}-27.12_{x-3}+32.12_{x-4}$$
$$-11.12_{x-5}-36.12_{x-6}+5.12_{x-7}+16.12_{x-8}-27.12_{x-9}-4.12_{x-10}-11.12_{x-11}\Big\}. \quad (51.)$$

(37.) Proceeding now to the case where $s=5$, we have

$$\varphi(x)=\frac{x^3+3x^2}{144},\ \varphi'(x)=\frac{3x^2+6x}{144},\ \varphi''(x)=\frac{6x+6}{144},\ \varphi'''(x)=\frac{6}{144},$$

whence

$$\varphi(x+4)=\frac{(x+4)^2(x+7)}{144},\ \varphi'(x+4)=\frac{3(x+4)(x+6)}{144},\ \varphi''(x+4)=\frac{6(x+5)}{144},\ \varphi'''(x+4)=\frac{6}{144},$$

and executing the reductions, arising from the substitution of these in equation (35.), we find

$$X=\frac{x^4+10x^3+19x^2-22x}{2880}.$$

Again for Y we have

$$\psi_1(5)=\varphi(4);\ \psi_2(5)=\varphi(4)+\varphi(5);\ \psi_3(5)=\varphi(4)+\varphi(5)+\varphi(6),\ \&c.,$$

whence

$$\psi_1(5)=\frac{112}{144};\ \psi_2(5)=\frac{312}{144};\ \psi_3(5)=\frac{636}{144};\ \psi_4(5)=\frac{1126}{144}$$
$$\psi_1'(5)=\frac{72}{144};\ \psi_2'(5)=\frac{177}{144};\ \psi_3'(5)=\frac{321}{144};\ \psi_4'(5)=\frac{510}{144}$$
$$\psi_1''(5)=\frac{30}{144};\ \psi_2''(5)=\frac{66}{144};\ \psi_3''(5)=\frac{108}{144};\ \psi_4''(5)=\frac{156}{144}$$
$$\psi_1'''(5)=\frac{6}{144};\ \psi_2'''(5)=\frac{12}{144};\ \psi_3'''(5)=\frac{18}{144};\ \psi_4'''(5)=\frac{24}{144}$$
$$\Psi(5)=\frac{1}{144}\Big\{0.5_x+112.5_{x-1}+312.5_{x-2}+636.5_{x-3}+1126.5_{x-4}\Big\}$$
$$\Psi'(5)=\frac{1}{144}\Big\{0.5_x+72.5_{x-1}+177.5_{x-2}+321.5_{x-3}+510.5_{x-4}\Big\}$$
$$\Psi''(5)=\frac{1}{144}\Big\{0.5_x+30.5_{x-1}+66.5_{x-2}+108.5_{x-3}+156.5_{x-4}\Big\}$$
$$\Psi'''(5)=\frac{1}{144}\Big\{0.5_x+6.5_{x-1}+12.5_{x-2}+18.5_{x-3}+24.5_{x-4}\Big\}$$
$$Y=-\frac{4}{2880}\Big\{\Psi(5)-2.\Psi'(5)+\Psi''(5)+\frac{2}{3}\Psi'''(5)\Big\}$$
$$=-\frac{1}{2880}\Big\{0.5_x+8.5_{x-1}+128.5_{x-2}+456.5_{x-3}+1112.5_{x-4}\Big\}.$$

(38.) For Z we have

$$Q_s = -\frac{9x}{144}.2_{s-1}+\frac{1}{144}\Big\{0.12_s+5.12_{s-1}+\ldots\ldots-11.12_{s-11}\Big\}$$

$$Q_{s-1}=-\frac{9(x-1)}{144}.2_s+\frac{1}{144}\Big\{-11.12_s+0.12_{s-1}+5.12_{s-2}\ldots\ldots-4.12_{s-11}\Big\}.$$

It will be convenient to separate this into two parts, viz.

$$Q'_{s-1}=-\frac{9(x-1)}{144}.2_s,$$

and

$$Q''_{s-1}=\frac{1}{144}\Big\{-11.12_s+0.12_{s-1}+\&c.\Big\}.$$

First, then, for $Q'_{s-1}$, proceeding as in article 30, we have

$$z=x,\ \chi_0(x)=-\frac{9}{144}(x-1);\ \chi_1(x)=0.$$

$$X(x)=2_s.\chi_0(x+10)+2_{s-1}\chi_0(x+5)$$

$$=-\frac{9}{144}\Big\{(x+9).2_s+(x+4).2_{s-1}\Big\}$$

$$X'(x)=-\frac{9}{144}(2_s+2_{s-1})=-\frac{9}{144},$$

whence Z' consisting now of the single term R',

$$Z'=-\frac{9}{1440}\Big\{x^3+x(9.2_s+4.2_{s-1})-\frac{x(x+10)}{2}\Big\}$$

$$=-\frac{9}{2880}\Big\{x^3-2x+10x.2_s\Big\}.$$

As regards the other portion of Z, which in this case is R'', it has for its expression

$$-\frac{9}{144}2_s.\frac{1-(1+\Delta)^{p_x+q'_x}}{\Delta}(9+10.0)+2_{s-1}.\frac{1-(1+\Delta)^{p_x+q''_x}}{\Delta}(4+10.0).$$

Now, whatever be $h$ and $c$, we have always

$$\frac{1-(1+\Delta)^h}{\Delta}(c+10.0)=(5-c)h-5h^3.$$

In this, if we write for $h$ successively $h'=p_x+q'_x$ and $h''=p_x+q''_x$, and for $c$, 9 and 4, we find

$$Z''=+\frac{9}{144}\Big\{2_s(4h'+5h'^3)-2_{s-1}(h''-5h''^3)\Big\}.$$

But since $x=10$ and $s=5$, we have

$$h'=\frac{1}{10}\Big\{0.10_s+1.10_{s-1}+2.10_{s-2}+3.10_{s-3}+4.10_{s-4}-5.10_{s-5}-4.10_{s-6}-3.10_{s-7}-2.10_{s-8}-1.10_{s-9}\Big\}$$

$$h''=\frac{1}{10}\Big\{0.10_s+1.10_{s-1}+2.10_{s-2}+\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots+9.10_{s-9}\Big\}.$$

Substituting which in Z'' and employing the property of equation (14.) for the com-

putation of the coefficients, we find

$$Z''=\frac{9}{2880}\left\{\begin{matrix}2_x\{0.10_x+9.10_{x-1}+20.10_{x-2}+33.10_{x-3}+48.10_{x-4}-15.10_{x-5}-16.10_{x-6}-15.10_{x-7}-12.10_{x-8}-7.10_{x-9}\}\\+2_{x-1}\{0.10_x-1.10_{x-1}+0.10_{x-2}+3.10_{x-3}+8.10_{x-4}+15.10_{x-5}+24.10_{x-6}+35.10_{x-7}+48.10_{x-8}+63.10_{x-9}\}\end{matrix}\right\}$$

$$=\frac{9}{2880}\left\{0.10_x-1.10_{x-1}+20.10_{x-2}+3.10_{x-3}+48.10_{x-4}+15.10_{x-5}-16.10_{x-6}+35.10_{x-7}-12.10_{x-8}+63.10_{x-9}\right\}.$$

(39.) Finally, we have to consider the portion $Z''$ of Z originating in $Q''_{x-11}$, in which the values of $\chi_0$, $\chi_1$, &c. are given by the equation

$$\chi_i=\frac{1}{144}\left\{-11.12_i+0.12_{i-1}+5.12_{i-2}-20.12_{i-3}\ldots\ldots-4.12_{i-11}\right\},$$

the coefficients being those of equation (51.) in their order of circulation. We have also, since in this case $m=12$, $s=5$, and therefore prime to each other, $v=1$, $t=12$, $n=60$. Whence

$$\chi_0.v_x+\chi_1v_{x-1}+\ldots\ldots\chi_{m-1}v_{x-m+1}=\chi_0+\chi_1+\ldots\chi_{m-1}=-\frac{78}{144},$$

and therefore

$$Z'''=-\frac{26x}{2880}-\frac{26}{2880}\left\{60.60_x+59.60_{x-1}+58.60_{x-2}+\ldots\ldots1.60_{x-59}\right\}$$

$$-\frac{20}{2880}\left\{-11.60_x+0.60_{x-1}+5.60_{x-2}-20.60_{x-3}-27.60_{x-4}\right\}$$

$$-\frac{20}{2880}\left\{-36.60_x+5.60_{x-1}+16.60_{x-2}-27.60_{x-3}-4.60_{x-4}-11.60_{x-5}+0.60_{x-6}+5.60_{x-7}-20.60_{x-8}-27.60_{x-9}\right\}$$

$$-\frac{20}{2880}\left\{+5.60_x-20.60_{x-1}-27.60_{x-2}\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots-27.60_{x-14}\right\}$$

$$-\frac{20}{2880}\left\{+16.60_x-27.60_{x-1}-4.60_{x-2}\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots-27.60_{x-19}\right\}$$

$$-\frac{20}{2880}\left\{-27.60_x+32.60_{x-1}-11.60_{x-2}\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots-27.60_{x-24}\right\}$$

$$-\frac{20}{2880}\left\{-4.60_x-11.60_{x-1}+0.60_{x-2}\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots-27.60_{x-29}\right\}$$

$$-\frac{20}{2880}\left\{-11.60_x-36.60_{x-1}+5.60_{x-2}\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots-27.60_{x-34}\right\}$$

$$-\frac{20}{2880}\left\{0.60_x+5.60_{x-1}-20.60_{x-2}\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots-27.60_{x-39}\right\}$$

$$-\frac{20}{2880}\left\{+5.60_x+16.60_{x-1}-27.60_{x-2}\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots-27.60_{x-44}\right\}$$

$$-\frac{20}{2880}\left\{-20.60_x-27.60_{x-1}+32.60_{x-2}\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots-27.60_{x-49}\right\}$$

$$-\frac{20}{2880}\left\{-27.60_x-4.60_{x-1}-11.60_{x-2}\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots-27.60_{x-54}\right\}$$

$$-\frac{20}{2880}\left\{+32.60_x-11.60_{x-1}-36.60_{x-2}\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots\ldots-27.60_{x-59}\right\}$$

Assembling, finally, the several portions, X, Y, Z', Z'', Z''', of which $\overset{5}{\Pi}(x)$ consists, and reducing those periodic functions, which have 5 and 10 for their period, to a period of 60, we see

$$\overset{8}{\Pi}(x)=\frac{1}{2880}\Big\{x^4+10x^3+10x^2-30x-90x.2_x\Big\}$$
$$+\frac{1}{2880}\Big\{0.60_x+9.60_{x-1}+104.60_{x-2}-387.60_{x-3}-576.60_{x-4}+905.60_{x-5}$$
$$-216.60_{x-6}-351.60_{x-7}-256.60_{x-8}+9.60_{x-9}+360.60_{x-10}-31.60_{x-11}$$
$$-576.60_{x-12}+9.60_{x-13}+104.60_{x-14}+225.60_{x-15}-576.60_{x-16}+329.60_{x-17}$$
$$-216.60_{x-18}-351.60_{x-19}+320.60_{x-20}+9.60_{x-21}-216.60_{x-22}-31.60_{x-23}$$
$$-576.60_{x-24}+585.60_{x-25}+104.60_{x-26}-351.60_{x-27}-576.60_{x-28}+329.60_{x-29}$$
$$+360.60_{x-30}-351.60_{x-31}-256.60_{x-32}+9.60_{x-33}-216.60_{x-34}+545.60_{x-35}$$
$$-576.60_{x-36}+9.60_{x-37}+104.60_{x-38}-351.60_{x-39}+0.60_{x-40}+329.60_{x-41}$$
$$-216.60_{x-42}-351.60_{x-43}-256.60_{x-44}+585.60_{x-45}-216.60_{x-46}-31.60_{x-47}$$
$$-576.60_{x-48}+9.60_{x-49}+680.60_{x-50}-351.60_{x-51}-576.60_{x-52}+329.60_{x-53}$$
$$-216.60_{x-54}+225.60_{x-55}-256.60_{x-56}+9.60_{x-57}-216.60_{x-58}-31.60_{x-59}\Big\}\ldots\quad(52.)$$

(40.) The periodic function $0.60_x+\ldots$.&c. may be somewhat simplified by resolving it into the sum of three others, having respectively 10, 20 and 30 for their periods. For on inspecting its coefficients, we find that the differences of any two, distant from each other by 30, are alternately $+360$ and $-360$. Now if we suppose, generally, any such function as

$$a_0.60_x+a_1.60_{x-1}+\&c.$$

to be made up of the sum of three others,

$$p_0.30_x+p_1.30_{x-1}+\&c.$$
$$q_0.20_x+q_1.20_{x-1}+\&c.$$
$$r_0.10_x+r_1.10_{x-1}+\&c.,$$

we shall have, supposing $i$ any number of the series 0, 1, 2, ... 9,

$$p_i+q_i+r_i=a_i,\qquad p_{i+10}+q_{i+10}+r_i=a_{i+10},\quad p_{i+20}+q_i+r_i=a_{i+20}$$
$$p_i+q_{i+10}+r_i=a_{i+30},\quad p_{i+10}+q_i+r_i=a_{i+40},\qquad p_{i+20}+q_{i+10}+r_i=a_{i+50}$$

which give the following equations of condition among the coefficients $a$,

$$a_{30+i}-a_i=-(a_{40+i}-a_{10+i})=a_{50+i}-a_{20+i}$$

And if these be satisfied (as in this case they are), we have only further to establish the following relations between $p$, $q$, $r$, viz.

$$p_i+q_i+r_i=a_i$$
$$p_{i+10}=p_i+(a_{i+10}-a_{i+20});\quad p_{i+20}=p_i+(a_{i+20}-a_i)$$
$$q_{i+10}=q_i+(a_{i+30}-a_i).$$

Among the sixty coefficients therefore which this assumption places at our disposal, twenty remain arbitrary, and may be put $=0$.

Suppose, for example,

$$q_i=0,\quad p_{i+20}=0,$$

which give

$$p_i=a_i-a_{i+30},\quad p_{i+10}=(a_i-a_{i+30})+(a_{i+10}-a_{i+30})$$

$$q_{i+10}=a_{i+20}-a_i,\quad r_i=a_{i+30}.$$

These being calculated, the function $0.60_s+9.60_{s-1}+$&c. reduces itself to the following, which seems the simplest form it admits:

$$-320\{30_s-30_{s-3}+30_{s-5}-30_{s-8}+30_{s-8}-30_{s-9}+30_{s-10}-30_{s-11}+30_{s-13}$$
$$-30_{s-14}+30_{s-16}-30_{s-17}+30_{s-19}\}$$
$$+360\{20_{s-10}+20_{s-11}+20_{s-12}+20_{s-13}+20_{s-14}+\ldots..20_{s-19}\}$$
$$+\{320.10_s+9.10_{s-1}-216.10_{s-2}-31.10_{s-3}-576.10_{s-4}+585.10_{s-5}+104.10_{s-6}$$
$$-351.10_{s-7}-576.10_{s-8}+329.10_{s-9}. \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (53.)$$

(41.) The problem, "In how many ways can a given number be constructed," is reduced by the author of a short but interesting paper in the Cambridge Mathematical Journal, iv. p. 87*, to the integration of the equations of differences

$$u_{x,y}=u_{x-y,\,x+y} \text{ and } u_{x,y}-u_{x-y,y}=u_{x-1,\,y-1},$$

which last equation corresponds to the case where it is required to find in how many ways $x$ can be composed of numbers none greater and not all less than $y$. The analogy of this problem with that here treated is obvious, the function $u_{x,y}$ being in effect identical with that which in the above notation would be expressed by $\Pi'(x)$, $y$ corresponding to our $s$. Accordingly, as far as $y=4$, to which limit only the inquiry is there extended, the results are identical (the mode of expression excepted) with those of our equations (49.), (50.), (51.)†. The method there pursued (by the successive integration of equations of differences) would of course continue to afford similar results, but without some systematic processes of notation, transformation and reduction, such as those delivered in the foregoing pages, would speedily become too complicated to be followed out, though the sort of form which would ultimately be assumed by the result seems to have been clearly apprehended. Observing that in the cases of $y=2$, 3, 4, the results express in fact *the nearest integers* to certain rational fractions, such as $\frac{x^2}{12}$ in the case of $y=3$, $\frac{x^3+3x^2}{2}$ ($x$ even) and $\frac{x^3+3x^2-9x}{2}$ ($x$ odd) when $y=4$, it is suggested that "probably this simple species of description might be continued." This, on examination of the value above given, when $y$ or $s=5$, appears to be the case, but for higher values it will be necessary to enlarge the terms of the description, so as to take in circulating functions of higher orders, and with more complicated coefficients. To make this apparent, suppose $s=6$. Then, without going into the whole calculation (which however would not be materially more complicated than for $s=5$, and would lead, as in that case, to a final period of 60, only not reducible to the sum

* It bears no name, but I have reason to believe it to be the production of Professor DeMorgan.

† Mr. Warburton has also obtained expressions for the number of partitions as far as 4, and his results, *mutatis mutandis*, agree with the above.

of lower periods), it is easy to see, that besides a non-periodic portion of 5 dimensions in $x$, and a periodic one with 60 constant coefficients, there will also be a circulating portion of the form

$$a_s.6_s+b_s.6_{s-1}+\ldots f_s.6_{s-5},$$

whose coefficients may rise to the second dimension in $x$. In fact, if we execute the calculation of this portion by the foregoing processes, we find for the values of the coefficients

$$a_s=e_s=0\,;\quad b_s=d_s=-\frac{4500x^2+15750x}{172800}\,;\quad c_s=\frac{3209x}{172800}.$$

With regard to the constant coefficients of the periodic portion, it is easy to see, from the manner of their formation, that they must all fall very far short, in numerical magnitude, of the half of 172800, so that the whole effect of this periodical part does, in effect, go to adjust the final value to *the nearest integer* of the rational fraction arising from the assemblage of all the terms in $x$, and a similar reasoning will apply in all cases.

(42.) The number of partitions of which a given number $x$ is susceptible, admitting 0 into them as a component part, is the sum of the number of 1-partitions, bipartitions, tripartitions .... up to $s$-partitions. It may therefore be found, by adding together all the values of $\dot{\Pi}(x)$, from $s=1$ to $s=s$ inclusive. But it may also be obtained by formulæ in all respects similar to those above demonstrated; for if we take $\Pi_s(x)$ to represent this species of partition, we have, if $s=1$, $\Pi_1(x)=1$ as before. For $s=2$ the partitions stand $0, x$; $1, x-1$; $2, x-2$; ... $\left(\frac{x}{2}+1\right)$terms, that is,

$$\Pi_2(x)=\Pi_1(x)+\Pi_1(x-2)+\ldots\left(\frac{x}{2}+1\right)\text{terms}.$$

Similarly,

$$\Pi_3(x)=\Pi_2(x)+\Pi_2(x-3)+\ldots.\left(\frac{x}{3}+1\right)\text{terms},$$

and so on to

$$\Pi_s(x)=\Pi_{s-1}(x)+\Pi_{s-1}(x-s)+\ldots.\left(\frac{x}{s}+1\right)\text{terms},$$

of which the formulæ of (30.) and (31.), duly applied, give the value

$$\Pi_s(x)=\frac{1-(1+\Delta)^{-\frac{x}{s}}}{\Delta}\Pi_{s-1}(x+s+s.0)+\frac{1-(1+\Delta)_2}{\Delta}\Pi_{s-1}(s+s.0),$$

where

$$q=-\frac{1}{s}\left\{\overline{s-1}.s_{s-1}+\overline{s-2}.s_{s-2}+\ldots.1.s_{s-s+1}\right\},$$

which, developed, affords a calculable value of the function in question.

*Collingwood, April* 17, 1850.

## XX. *Experiments on the Section of the Glossopharyngeal and Hypoglossal Nerves of the Frog, and observations of the alterations produced thereby in the Structure of their Primitive Fibres.* By Augustus Waller, *M.D.* *Communicated by Professor* Owen, *F.R.S.*

Received November 22, 1849,—Read February 21, 1850.

THE object of the present observations is to describe certain alterations which take place in the elementary fibres of the nerve after they have been removed from their connection with the brain or spinal marrow.

The following is a brief summary of the opinions and researches of modern physiologists on alterations of the nerve-tubes.

Burdach* placed a ligature on the sciatic nerve of a frog, and after the lapse of a week found no alteration of the primitive fibres either above or below the ligature.

Steinruck† did the same, and states that in three cases the whole nerve was more slender than on the healthy side, and ascribed it to the atrophy of the neurolema.

Valentin‡ denies likewise that there is any alteration of the primitive fibres in the lower portion of the nerve.

Gunther and Schön§, whose researches are most interesting, state that the primitive fibres being examined towards the end of a week, after division of the nerve when it had lost its irritability, it was perceived that they had no longer the full round appearance of the sound ones. Here and there their contents appeared as if curdled; from eight to fourteen days after section these structural changes became still more evident, and continued to increase until the fibres appeared flat, broken up, entirely losing their transparency, their contents appearing as if disjointed.

Nasse‖ states, that five months after section of the sciatic nerve of a frog, the tubes below the section were broken up into granules and small clumps; that all the nerve-tubes were strongly granulated, in some the small granules being united into oval bodies, which appeared to be surrounded by a pale cylindrical membrane, which in some was wanting, owing probably to its disorganization.

Having in a former communication to the Royal Society described the nerves of the papillæ and of the muscular fibre in the frog's tongue in their normal condition,

* Beitrag zur Mikroskopischer Anatomie der Nerven, E. Burdach. Konigsberg, 1837, p. 42.

† De Nervorum Regeneratione. Berolini, 1838, p. 72.

‡ De Functionibus Nervor Cerebral, &c. Lib. iv. 1839, p. 127.

§ Müller's Archiv, 1840, Versuche und Bemerkungen über Regeneration der Nerven, p. 276.

‖ Ueber die Veränderungen der Nerven-fasern nach ihrer Durchschneidung, Müller, Arch. 1839, p. 409.

it is my intention at present to describe various alterations, as seen under the microscope, which take place in the structure of the same nerves after their continuity with the brain has been interrupted by section. The innervation of the frog's tongue is, as I have already shown, derived from two pairs of nerves, one arising from the brain, and traversing a foramen in the posterior part of the cranium, accompanied by the pneumogastric nerve. This pair corresponds to the glossopharyngeal in Man. In its course it descends until it reaches the hyoglossus muscle, when it is accompanied by the lingual vessels passing over part of the hyoid bone, and entering the tongue without giving off any branch to the throat. The other pair arises from the anterior part of the spinal marrow, traverses the first cervical foramen, and constitutes the first cervical pair of nerves. Following the example of Burdach, I regard this pair as corresponding to the hypoglossal in Man, and shall apply that term to it. It takes its course towards the tongue in a similar direction to that of the former pair, giving off several branches to the muscles of the neck and throat, and when it reaches the hyoglossus muscle it is considerably smaller than the glossopharyngeal. After attaining this muscle it runs parallel to the former nerve, passing below the hyoid bone in its transit to the tongue. For a more minute description I must refer to the paper of E. Burdach, of which a translation has appeared in the Annales des Sciences Naturelles.

*Division of the Glossopharyngeal Nerve.*

That division of these nerves produces some serious lesion is proved by the death of the animal, which generally takes place a few days after the operation. Considering the well-known tenacity of life possessed by these animals this was quite an unexpected result, for which I am unable at present to afford any satisfactory reason. We can only surmise, that besides their gustatory powers, they have others connected with respiration, in regulating the action of the tongue in closing the nares, for forcing the air into the lungs. Whatever may be the true explanation, it is impossible not to regard this result with surprise, when we consider the serious lesions which this animal is capable of undergoing at other points of the frame without loss of life. The usual time which it survives is variable, and depends greatly on the season of the year. If the examination takes place in summer, death frequently ensues on the fifth day; if in winter, not before the twentieth. For the purpose of avoiding this loss of life, I adopt the plan of dividing the glossopharyngeal on one side only of the tongue, and I find that it has the desired effect of preserving the life of the animal, while we can observe the same alterations on the corresponding side, as well as when both nerves are divided. Another advantage found in the division of a single nerve is, that on the uninjured side we have constantly at hand a means of comparison by which we can judge with certainty respecting any alterations that may be produced in the divided nerve. In cases of any doubt, it will always be found of the greatest service to examine at the same time a minute fragment from each side of the tongue.

The first effects of section of a glossopharyngeal nerve at the throat, are decreased

power of moving the tongue, diminished sensibility, generally very slight on the divided side, and symptoms indicative of some disturbance of the nutritive functions. The diminution of motor power is very slight, as is evident by the almost molecular tremor which still exists in any part irritated, and by the capability of retracting the tongue. The loss of sensation, which is also very slight, arises from the section of a few sensitive filaments which are contained in the glossopharyngeal nerve, and are distributed principally about the tubercular extremities. The lesions of nutrition and circulation on the side of the division are very variable and uncertain. Sometimes that half is œdematous, particularly towards the tubercle. Sometimes the papillæ are much injected and congested, while in other cases this side is more pale than the other. In many instances no difference can be detected between the two sides, until the organ has been slightly irritated, when on the divided side the vessels, and especially those of the fungiform papillæ, become congested and of a deeper red than on the other. Some of these differences probably arise from causes independent of the nervous lesion, as the vessels of the tongue which accompany these nerves are doubtless injured in some of the experiments.

FRANKLIN INSTITUTE LIBRARY

During the first two or three days after section, no alteration in the texture and transparency of the tubes of the papillary nerves can be detected. Generally, at the end of the third and fourth day, we detect the first alteration by a slightly turbid or coagulated appearance of the medulla, which no longer appears completely to fill the tubular membrane, which does not appear to be affected. These alterations of the medulla are best seen in a fragment to which a little distilled water has been added to render it more transparent. When examined twenty-four hours after death, the difference between these and the nerves on the healthy side is still more evident. Commencing decomposition on the healthy side causes the nerve-tubes to swell considerably, so as to attain nearly double their ordinary size. On the divided side the disorganized nerve retains nearly the same size and appearance as when fresh. Caustic potash, which dissolves all the tissues except the nerves, renders the altered nerves more transparent, and consequently the morphological changes are less apparent. Nevertheless, by comparative experiments made simultaneously, we may still detect a difference between the nerves of the two sides. In some cases, in about three or four days after section, I have traced the turbid state of the nerve from the fungiform papillæ into branches containing forty or fifty tubes, where it did not appear to terminate, but where the opacity of the nerve prevented my observing it any further. About five or six days after section, the alteration of the nerve-tubes in the papillæ has become much more distinct, by a kind of coagulation or curdling of the medulla into separate particles of various sizes. Sometimes the coagulated particles have an uneven spongy appearance, as if the component parts of the medulla, *i. e.* the white substance and the axis cylinder, were mixed together. Often they appear merely like separated particles of the medulla, such as are frequently effused from the ends of a divided nerve, and present the double contour and the central nucleus cha-

racteristic of the nervous medulla. In some cases the coagulated particles are very uniform in size and appearance, averaging $\frac{1}{7000}$th of an inch. In others, the limits between the maximum and minimum dimensions are far greater, namely, from $\frac{1}{3500}$th to $\frac{1}{12,500}$th of an inch. The diameter of the altered tubes, examined in the ordinary manner in water, is about a fourth smaller than that of the sound ones, and in many instances the tubular cylinders appear wanting, and the medullary particles to have escaped from the cylinder, and to be merely held together by the neurilema which surrounds the whole nerve. After the application of potash, the diameter of the altered and unaltered nerves is as nearly as possible the same. This equalization of the two is produced almost entirely by a decrease in the size of the sound tubes, which swell considerably in water, and afterwards contract by the application of the alkali. It is therefore probable that the difference of size at this stage between the altered and unaltered nerves arises from the former not absorbing so much within them as the latter. Whether this arises from a ruptured state of the membrane or from a chemical change of the medulla, is not evident. After the surrounding tissues have been removed by potash, the tubular membrane offers no signs of rupture, and the medulla appears less disorganized than before the denudation. The disjointed condition of the medulla is greatest towards the extremities. A portion of each nerve-tube is frequently so disorganized as to be carried away among the tissues dissolved by the alkali. The circular rim so frequently presented by the extremity of the tubes is absent. We often observe around the healthy nervous branches, and the papillary nerve in particular, a common sheath or neurilema fitting closely to the nerve. After disorganization has attained this degree, it appears to form a kind of loose pouch around the nerve and separated from it by an interval of $\frac{1}{3000}$th of an inch. This pouch appears to form the sole investment of the curdled medullary particles, which, as we have stated, previous to the action of the alkali, appear void of any tubular investment. As we ascend towards the brain the disorganization appears to decrease, the coagulated medulla is more apt to assume the oval form, and at some places it presents its double contour apparently unaffected. The effect of decomposition in the unaltered and altered nerve is similar to that in the former stage. In consequence of the above changes the disorganized nerve is more opake than the unaltered one. In the tubercles some of the ramifications of the tubes belonging to common sensation become disorganized after the section of the corresponding glossopharyngeals. These alterations take place in the same period and in the same manner as in the papillary nerves. With this exception, all the other nerves of the tongue, which comprise those of common sensation and of muscular action, remain unaltered. The muscular fibres of the papillæ are slightly altered at this period; their transverse striæ are not so distinct as on the healthy side, while their longitudinal ones are more so. The fibre itself is usually paler, narrower and more wavy in its course.

The capillaries are either much congested with dark blood, or they are completely empty and scarcely to be detected.

The epithelium and the ciliary filaments are unaltered.

On the seventh, eighth and ninth days the disorganization of the nervous structure continues to progress. In the papillæ the curdled particles of medulla become still more disconnected, and in parts are removed by absorption. The tubular sheath also is ruptured and disorganized near the extremities of the tubes. In the other ramifications of the glossopharyngeal, the medulla becomes more and more disjointed and collected into oval or circular coagulated masses.

On the tenth day and upwards we perceive another morphological state of the medulla. The coagulated particles lose their amorphous structure and assume a granulated texture. The granules, retained together by slight cohesion, are dark by transmitted light, but of a light white colour by reflexion, and average $\frac{1}{20,000}$th of an inch.

About the twentieth day the medullary particles are completely reduced to a granular state. The condition of the papillary nerve is represented in Plate XXXI. fig. 2, where we find the presence of the nervous element merely indicated by numerous black granules, generally arranged in a row like the beads of a necklace. In their arrangement it is easy to detect the wavy direction characteristic of the nerves. They are still contained in the tubular membrane, which is but very faintly distinguished, probably from the loss of the medulla and from atrophy of its tissue. The resistance of these granular bodies to chemical agents is most remarkable, for they remain unaffected by acids, alkalies and the ethers, which have so great an influence over the nervous medulla. These granules may be detected within the papillary nerves for a considerable period of time. I have seen them apparently unaltered in the papillæ upwards of five months after division of the nerve, reunion not having taken place.

*Division of the Hypoglossal Nerve.*

When the hypoglossal nerves are divided at their exit from the spine, all movements of the throat and tongue are abolished, and the process of respiration entirely at an end. The tongue may be drawn from the mouth remaining completely inert, pinching or cutting causing no appearance of pain. Hence we may conclude that this nerve is of a mixed nature, containing sensorial as well as motor filaments. Another experiment, which shows this more plainly, consists in dividing one hypoglossal nerve near the spine on one side, and on the other the glossopharyngeal at its exit from the cranium. Pinching and other modes of irritation cause no pain on the side where the hypoglossal is divided, while on the other undoubted pain is caused.

After division of the hypoglossals at the throat, the motor and sensorial powers of the tongue are not entirely lost. When drawn out of the mouth, the extremity only remains fixed between the jaws, flaccid and powerless. At the inner half the fibres are still contractile, on account of their belonging to the hypoglossus, which at its lower half receives a branch from the hypoglossal nerve above the point of section. By this

means, aided also by the mylohyoid muscle, which is left unaffected for the same reason, the inner half of the tongue still enjoys contractile powers.

Respiration is hurried and laboured, and death is the invariable result of division of these nerves, whether made at the spine or at the throat. In summer, the animals died at the end of two or three days.

Division of a single hypoglossal only causes paralysis of the corresponding half of the tongue, complete when the section is near the spine, and imperfect when at the throat. The animals generally survive after the section of one nerve.

The peripheric extremities of the hypoglossal nerves are most easily found at the inferior surface of the tongue. By removing a minute fragment at this region, we can observe, without any further preparation, ramifications of nerves, which are gradually reduced to a network of single tubules on the surface, among the capillary network. At the same time, among the muscular fibres are other ramifications, either crossing them in a transverse direction or running parallel. Like the former, they are reduced to single fibres, running in all directions without forming any free ends. It is at the under surface that the alterations of the hypoglossal must be studied.

During the four first days, after section of the hypoglossal nerve, no change is observed in its structure. On the fifth day the tubes appear more varicose than usual, and the medulla more irregular. About the tenth day the medulla forms disorganized, fusiform masses at intervals, and where the white substance of SCHWANN cannot be detected. These alterations, which are most evident in the single tubules, may be found also in the branches. After twelve or fifteen days many of the single tubules have ceased to be visible, their granular medulla having been removed by absorption. The branches contain masses of amorphous medulla.

We are naturally led to inquire, whether extraneous circumstances have any influence over the removal of the tissue. We find that in the summer-time, when the renewal of the tissues must be considerably more active, in consequence of the increased respiration and activity of the animals experimented upon, that the alteration is more rapid than in winter, when they are in a state of torpor and hybernation.

At present we have restricted our observations to the alterations which take place in the ramifications originating from two trunks, but we cannot suppose that this is a local phenomenon, and that other nerves do not participate in similar alterations, and that the brain itself, composed in great part of tubular fibres, must be excluded. Experiments on other nerves already enable me to affirm that such is not the case, and that they are to be found on other nerves, such as the sciatic, &c., and, moreover, that they are as extensive as the nervous system itself. It is impossible not to anticipate important results from the application of this inquiry to the different nerves of the animal system. But it is particularly with reference to nervous diseases that it will be most desirable to extend these researches. If one conviction impresses itself more firmly on the mind than another, it is that what we term functional diseases of

the nerves are in reality owing to certain organic and physical changes in the tubular fibre, which it will be the province of the microscope to ascertain. If a few days' inactivity of a nervous trunk, such as is produced by ligature or section, is sufficient to cause such disorganization of the medulla, how can we refuse to admit of its being altered in cases of prolonged paralysis?

*Kensington, October* 27, 1849.

## Description of the Plate.

### PLATE XXXI.

Fig. 1. Papillary nerve of frog, six days after ligature.

Fig. 2. Papillary nerve, three weeks after section, with muscular fibres in the interior of the capillary coil at the summit of the fungiform papilla.

Fig. 3. Disorganized muscular nerve, from the inferior surface of the tongue, five days after section. The muscular fibre has been omitted in this drawing.

## XXI. *Influence of Physical Agents on the development of the Tadpole of the Triton and the Frog.* By John Higginbottom, *Hon. Fellow of the Royal College of Surgeons of England.* *Communicated by* Thomas Bell, *Esq., Sec. R.S.*

Received April 6,—Read May 16, 1850.

An opinion has been generally entertained by physiologists that the tadpole of the Frog, when deprived of *the influence of light*, cannot arrive at its full development, or assume the form of the perfect frog.

I made a series of experiments in different positions and degrees of temperature, but particularly in a rock-cellar thirty feet deep, where no solar light ever entered; this situation was also favourable in point of temperature, being

48° Fahr. from March 11th to May 15th.
50° to 54° Fahr. from May 15th to July 6th, and
55° Fahr. from July 6th to October 31st.

My first experiments were performed on the tadpole of the Triton.

Exp. 1.—I found the tadpole of the *Triton punctatus* more tenacious of life than that of the *Triton cristatus*. I commenced with placing a number of the ova, enveloped in blades of grass in the manner usual with this animal, in three open shallow vessels containing water. One vessel I placed in a room where the mean temperature was 60° Fahr., another in the open air at a mean temperature of 50°, and the remaining one in a deep rock-cellar at 48°.

In the temperature of 60° Fahr. some of the tadpoles escaped from the ova in fourteen days, those at 50° in twenty-one days, and those at 48° in the rock-cellar in twenty-one days.

Although the tadpoles in the cellar at 48° escaped as early as those out of doors, they did not afterwards increase in growth, whilst those in the room at 60° and in the open air at 50° became more developed, the former of these having the anterior extremities in thirty-nine days, the latter in forty-nine days, whilst those in the cellar had no appearance of an extremity at the end of sixty-two days.

Exp. 2.—On the 4th of July I made another experiment with the ova of the Triton in the rock-cellar at its maximum temperature of 55° Fahr. I placed a number of ova in that situation; the tadpoles escaped in due time, but, as in the former experiment, they did not proceed in their development, having no appearance of anterior extremities in 105 days, when they died for want of proper food.

Exp. 3.—On the 11th of August I put twenty-four tadpoles of the Triton in water,

in an earthen vessel enveloped in four or five folds of black calico, so as to exclude the light, the mean temperature of the room being 65° Fahr. I placed the same number under a shed where the mean temperature of the atmosphere was 60°, and a similar number in the deep, dark rock-cellar then at a constant temperature of 55°.

In six days several of the tadpoles in the vessel in the room at 65° and in the open air at 60° were dead, and on examination I found that their branchiæ were absorbed, and their opercula nearly closed, and I concluded that they had died of asphyxia. I now took the precaution to place a stone in the centre of each vessel, so as to allow the tritons to leave the water as they lost their branchiæ. Two days afterwards the top of the stones had a number of tritons upon them in the vessels in the room and in the open air.

All those placed in the rock-cellar retained their branchiæ, not one having left the water, although I had placed stones for that purpose. No more tritons died after the stones had been placed in the vessels, as they afforded them the opportunity of leaving the water when the branchiæ were absorbed.

In about twenty-one days afterwards, during the month of September, two or three had left the water and were on the stones placed in the vessel *in the cellar*, fully proving that the animal came to its full development in the absence of light, though this development was retarded by the low temperature of 55°.

Exp. 4.—On the 25th of August I deprived three tritons, one of an anterior, another of a posterior extremity, and the third of the tail. I put these into a vessel, which I enveloped in five or six folds of black-glazed calico so as to exclude the light, and placed it in a dark part of a room where the maximum temperature was 70° Fahr. As it was then the time of the year when the full-grown tritons leave the water, I placed a quantity of clay and flat stones in the vessel with a little water at the lowest part, in order to allow them to remain in the water or out of it.

In a month the amputated limbs had undergone the reproductive process; in one a miniature posterior extremity furnished with toes had been formed, in another the tail, and in fourteen days later the anterior extremity and the toes of the third were reproduced.

I now began a series of experiments on the Frog (the *Rana Temporaria*); this batrachian being more manageable in regard to food, and arriving at its full development in much less time than the Triton, the former only requiring about ten weeks, the latter about five months.

I commenced my experiments and observations on the Frog in March 1848, ascertaining accurately the influence of air, food, temperature and light, *from the ovum to its full development*.

### *On the Influence of the Atmospheric Air.*

There are three modes of respiration in the tadpole of the Frog:—1st, the Branchial; 2nd, the Pulmonary; 3rd, the Cutaneous.

In the branchial state the body of the tadpole is very small, and at this period they flock to the sides of the vessel in which they are contained close to the edge of the water, nearly exposing the branchiæ to the atmospheric air, the lungs being as yet unemployed.

About a fortnight before the metamorphosis of the tadpole into the frog, its body is very large, and the cutaneous surface for respiration, including the tail, is very considerable; but when the development takes place, the body of the frog is again small, and there is not a sufficient surface for respiration, so that if the animal continues in the water, it becomes asphyxiated. Life then depends more on the pulmonary than the cutaneous respiration.

I found that the tadpole of the Frog soon dies in either aërated or boiled water if excluded from atmospheric air; those in aërated water live the longest; some of them I found at the top of the water, and on examination the lungs were observed to be inflated, whilst those tadpoles in the boiled water sank to the bottom of the vessel. Tadpoles put into boiled water exposed to the atmospheric air live as in aërated water.

### 2. *On the Influence of Food.*

The food of the tadpole is derived from two sources. The first is the gelatine of the ova, the second the plants growing in the water in which they are deposited.

1848.—On the 11th of March I put some spawn of the frog, newly deposited, into eight shallow earthenware vessels containing water; in four of them I added grass and duck-weed to serve as food for the future tadpoles, in the other four I put none. I observed in all the vessels that the tadpoles, after escaping from the ova, had about an equal growth, as long as any of the jelly-like substance of the ova remained; but after that was consumed, the tadpoles in the vessels where there was no grass were promptly retarded in their growth.

April 17th.—To prove whether the jelly of the ova was food for the young tadpoles, I separated a number from the jelly, putting the tadpoles in one vessel with water, and the jelly in another.

In thirteen days I found the tadpoles had not increased in size, and that some of them were very weak and nearly inanimate. On this day I placed them all with the jelly. In seven days the jelly was consumed, and some of the tadpoles had much increased in size, others of them had died from having been so long and at so early a period deprived of their *first food*.

After the tadpole has finished feeding on the jelly, nothing more is required for food than grass and duck-weed, the grass serving for food, the duck-weed both for food and as a shelter, and also probably yielding its influence as a living vegetable in the water. The grass is sufficient as food to produce the full development of the tadpole, which feeds upon the chlorophyle which adheres to the cells of the plant,

when the plant is in a state of decomposition, leaving the fibrous part. They generally feed on the under part of the plant with the abdomen upwards, owing to the position of the mouth.

I supplied the tadpoles with fresh water every third day, and with grass as often as necessary. In those vessels which were placed in the dark it was necessary to add grass more frequently, on account of the loss of the green colour it sustained in that situation.

I observed they did not feed so well at a low temperature. The life of the tadpole cannot be preserved very long with fresh water and air alone without proper food. I placed a number of tadpoles in eight vessels, of which four were excluded from the light, and four exposed to the light in different degrees of temperature; no food was put in any of the vessels after they had consumed the jelly. On the 11th of May, eight weeks and four days after the deposition of the spawn, the tadpoles remained very small, and the last of them died on that day.

The jelly appears to be quite essential as nutriment to sustain the early life of the tadpole. Had they been deprived of it, they would have died at a much earlier period, as proved by my former experiment*.

### 3. *On the Influence of Temperature.*

On the 11th of March 1848, I procured four round open earthenware vessels, each containing about three pints of water, and filled them about three parts full. In each I put a small quantity of the spawn of the frog just deposited, and I then placed them in four different degrees of temperature.

The *first* was placed near the ceiling in a shaded part of a room, where the mean temperature was 60° Fahr., six or eight folds of black-glazed calico being tied over it so as to exclude all light.

On the 20th of March (see Plate XXXII.) the tadpoles left the ova; on the 23rd the branchiæ were fully formed; on the 22nd of May the first was fully developed at a much earlier period than others placed in a lower part of the same room, exposed to the light at the mean temperature of 58° Fahr., and also earlier than in the pools.

The *second* was placed at the same time in a situation where the mean temperature was 56°. On the 20th of March, nine days after the deposition of the ova, the embryos were lengthened, indicating the head, body and caudal extremity, and lay in a curved position within the ova. On the 25th some escaped from the ova. On the 28th the branchiæ were fully formed, and on the 6th of April they were absorbed. On the 22nd of May the tadpoles had increased in size. On the 18th of August the first was fully developed.

The *third* vessel was put within a larger one and placed in the open air, on a shaded

* According to Mr. Brande (Philosophical Transactions for 1810), the jelly appears to be an intermediate substance between albumen and gelatine.

side of a house, and entirely covered with wood, so as to exclude all light, the mean temperature being 53° Fahr.

March 20th.—In nine days after the deposition of the ova, the embryos retained their globular form, but considerably increased in size.

On the 25th they had the elongated form within the ova; on the 31st they escaped. On the 4th of April the branchiæ were fully formed, and on the 11th they were absorbed. May 22nd, the tadpoles were increased in size. On the 28th of August the first was fully developed (see Plate XXXII.).

The *fourth* vessel I placed in the rock-cellar. The temperature was uniformly 48° Fahr. from the 11th of March to the 15th of May, 50° to 54° Fahr. from May 15th to July 6th, and 55° Fahr. uniformly from July to October 31st.

March 31st.—The tadpoles escaped from their ova on the same day as in that in the open air, the temperature being in the cellar uniformly 48° Fahr., in the open air 53° mean temperature.

On the 6th of April the branchiæ were formed, and on the 18th they were absorbed. On the 22nd of May the tadpoles were very small, but from that period to the 5th of September they grew much more rapidly. On the 31st of October the first was fully developed.

It will be observed (Plate XXXII.) that when the tadpole in the room was fully developed at the mean temperature of 60° Fahr., those in the open air were small at the mean temperature of 53°, but those in the cellar were smaller still, having been influenced by the low temperature of 48°; from March 11th to May 6th, when the temperature became constantly 55°, they advanced more rapidly in size until their full development.

November 17th.—Soon after this period the temperature in the rock-cellar was from 50° to 54° Fahr. for a month, and during that time there were no more tadpoles fully developed. One of them had three legs only; for upwards of three weeks the fourth leg could be seen distinctly under the skin when the animal moved, but it did not protrude.

All these results are displayed in Plate XXXII., in which the difference of temperature and its effects are registered.

### 4. *On the Influence of Light.*

With regard to the question of full development of the tadpole of the Frog in the absence of light, I am enabled by the most minute observation to state that it advances in growth equally well in the dark and in the light, and that absence of light has therefore no influence in retarding its development.

I have ascertained this by frequent experiments during the last two years; one experiment was made on an extensive scale.

I had six vessels with tadpoles, three exposed to the light in different degrees of temperature, and three from which the light was excluded.

At the first I was led to think the absence of light was even favourable to development, but I afterwards found that the difference depended on a slight increase of temperature owing to the vessel being covered. This fact is rendered obvious by the Plate, in which the temperature and absence of light are fully illustrated.

*Nottingham*,
*February* 5, 1850.

P.S. I made these experiments in 1848; they were repeated in the year 1849 with similar results.

## XXII. *On the Temperature of Man within the Tropics.*

*By* John Davy, *M.D., F.R.S., L. & E., Inspector-General of Army Hospitals.*

Received February 26,—Read May 2, 1850.

In a paper on the Temperature of Man, which I had the honour to submit to the Royal Society in 1845, and which was published in the Philosophical Transactions for the same year, I expressed the hope of being able to continue the inquiry in the West Indies, to which I was then about to proceed.

In the present communication I propose to lay before the Society the results of the trials made whilst there, viz. during a period of about three years and a half, exclusive of trifling interruptions, and of one prolonged through several weeks, between June 1847 and October of that year, owing to illness.

In making the trials, the same instrument as that before used was employed, and with like precautions to ensure accuracy, and as then, the subject of the observations was the same individual; also, as then, the pulse and respirations were noticed at the time, and invariably in the sitting posture.

The greater number of the observations were made in Barbados, in a house situated about half a mile from the sea-shore and a few feet only above its level,—where the mean annual temperature of the atmosphere is about 80° Fahr., and the range of temperature throughout the year from about 10° to 18° in the open air.

For the sake of comparison, I shall follow as closely as possible the order observed in my former paper in stating the results.

### 1. *Of the Variation of Temperature during the twenty-four hours.*

To ascertain this, observations were made commonly three times a day, viz. immediately on rising, about 6 a.m., before taking any food, and before making any exertion, even in dressing, clad merely in a light dress consisting of loose drawers and gown, which in that climate are almost always sufficient for comfort;—next, about 2 p.m., sometimes an hour earlier or later, and generally after occupation, either within doors at home, or at an office a mile and a half distant nearly, to which I went in a carriage,—the occupation being chiefly that of reading or writing, or some other requiring little bodily exertion;—next, the last thing before retiring to rest at night, which was commonly at 10 o'clock, rarely later than 11.

It may be further premised, that the manner of living, as to diet and the time of meals, was much the same as in England,—breakfasting commonly at 9 o'clock, dining about 5, without intermediate luncheon, and drinking tea about 7.

The following Table exhibits the observations made in accordance with the above,

daily, during a period of thirty-six months: in an Appendix, the observations as daily recorded will be given, omitting only those which may be considered abnormal, either owing to bodily ailment, or other cause of a special kind, requiring particular notice:—

| | Temperature under the tongue. | | | Pulse. | | | Respirations. | | | Temperature of air of room. | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | 6–7 A.M. | 12–2 P.M. | 9–11 P.M. | 6–7 A.M. | 12–2 P.M. | 9–11 P.M. | 6–7 A.M. | 12–2 P.M. | 9–11 P.M. | 6–7 A.M. | 12–2 P.M. | 9–11 P.M. |
| 1845. | | | | | | | | | | | | |
| July ..... | 98°2 | 99° | 98°2 | 56 | 61 | 60 | 14·7 | 15·5 | 16 | 78°3 | 81°5 | 79°4 |
| August ..... | 98 | 98·7 | 98·2 | 53·8 | 53·6 | 57·9 | 15 | 15·7 | 15·8 | 78·7 | 84 | 80·3 |
| September ... | 98 | 98·9 | 98·9 | 54·3 | 55 | 62·1 | 15·2 | 15·6 | 15·6 | 78·6 | 84·7 | 80·5 |
| October ..... | 97·9 | 99 | 98·8 | 53·4 | 56·3 | 61·3 | 14·6 | 15·9 | 16·8 | 78 | 85·4 | 81 |
| November ... | 98 | 98·6 | 98·7 | 53·3 | 56·5 | 61 | 14·8 | 15·6 | 16 | 78 | 83·4 | 79·9 |
| December ... | 98 | 98·6 | 98·6 | 53·8 | 55·2 | 66 | 14·4 | 15·5 | 15·7 | 75 | 81·8 | 77 |
| 1846. | | | | | | | | | | | | |
| January ..... | 98·2 | 99 | 98·7 | 54·3 | 58·5 | 61·7 | 14·6 | 15·7 | 15·6 | 74·3 | 82 | 78·2 |
| February ... | 98·1 | 99·1 | 98·6 | 55·1 | 57·1 | 59·9 | 14·3 | 15·5 | 15·2 | 74 | 83 | 76·6 |
| April ..... | 98·1 | 98·7 | 98·6 | 54 | 54·5 | 59·5 | 14·4 | 15·6 | 15·4 | 77 | 84 | 79 |
| May ..... | 98·2 | 98·9 | 98·9 | 56·2 | 55·2 | 61·4 | 15 | 15·8 | 15·6 | 78·7 | 85·8 | 80 |
| June ..... | 98·2 | 99 | 98·8 | 55·1 | 55·6 | 59·7 | 14·6 | 15·7 | 15·4 | 79 | 84·7 | 81 |
| July ..... | 98·2 | 99 | 98·9 | 54·5 | 54·5 | 60·7 | 14·7 | 16 | 15·3 | 78·8 | 84·8 | 81·4 |
| August ..... | 98·1 | 99 | 98·9 | 54·2 | 55·6 | 60·5 | 14·6 | 15·9 | 15·6 | 77·7 | 85·5 | 81·7 |
| September ... | 98 | 99 | 98·2 | 55 | 54 | 60·8 | 14·3 | 15·9 | 16 | 78·7 | 85·1 | 81·3 |
| October ..... | 98·2 | 99 | 99 | 52 | 55 | 61 | 14·4 | 15·4 | 15·3 | 78·2 | 85·1 | 81·2 |
| November ... | 98·1 | 98·9 | 98·8 | 56·2 | 55·4 | 60·1 | 14·6 | 15·8 | 15·6 | 77·4 | 84·4 | 80 |
| December ... | 98·1 | 98·9 | 98·9 | 55·3 | 55·3 | 63·5 | 14·5 | 15·8 | 15·8 | 76 | 80·5 | 77·4 |
| 1847. | | | | | | | | | | | | |
| January ..... | 98·1 | 98·9 | 98·8 | 54·8 | 55·3 | 60·8 | 14·4 | 15·4 | 15 | 74·6 | 81·3 | 77·3 |
| February ... | 98 | 98·8 | 98·8 | 55·5 | 57·6 | 61·7 | 14·2 | 15·5 | 15·3 | 73 | 81·5 | 76·3 |
| March ..... | 98·1 | 98·8 | 98·9 | 54·8 | 59·2 | 62·7 | 14·5 | 15·6 | 15 | 74·6 | 83·5 | 77·1 |
| April ..... | 98·1 | 98·7 | 98·8 | 55 | 56·4 | 62·3 | 14·2 | 15·5 | 15·6 | 74·7 | 82·2 | 77·1 |
| May ..... | 98·1 | 98·9 | 98·8 | 56·6 | 57·8 | 61·3 | 14·5 | 15·8 | 15·6 | 76·7 | 85 | 79·2 |
| October ..... | 98 | 99 | 99 | 54·7 | 56 | 55·7 | 14·5 | 15·1 | 15·7 | 77·7 | 84·8 | 80 |
| November ... | 98·1 | 98·8 | 98·8 | 53·3 | 54·8 | 59·2 | 14·5 | 15·1 | 15·2 | 76·7 | 82·3 | 79 |
| December ... | 98 | 98·8 | 98·3 | 52·9 | 53·5 | 58 | 14·1 | 14·6 | 15·3 | 74·5 | 81·1 | 76·9 |
| 1848. | | | | | | | | | | | | |
| January ..... | 98·1 | 98·9 | 98·8 | 54·5 | 56·8 | 59·3 | 14·1 | 14·9 | 15·2 | 74·1 | 80·5 | 76·6 |
| February ... | 98 | 98·8 | 98·8 | 54·9 | 57 | 59·7 | 14·5 | 15·1 | 15·5 | 73·6 | 82·1 | 77·5 |
| March ..... | 98 | 98·9 | 98·9 | 54·9 | 57·6 | 59·7 | 14·3 | 15·5 | 15·4 | 75·1 | 81·9 | 78·2 |
| April ..... | 98 | 98·9 | 98·9 | 54·9 | 57·7 | 60·9 | 14·7 | 15·2 | 15·3 | 74·8 | 82·9 | 78·1 |
| May ..... | 98·1 | 99 | 98·9 | 55·1 | 56·2 | 60·6 | 14·3 | 15 | 15·6 | 78·2 | 85·6 | 80·6 |
| June ..... | 98 | 98·8 | 99 | 51 | 56·1 | 56·8 | 14·1 | 14·8 | 14·9 | 77·5 | 84·7 | 80·4 |
| July ..... | 98 | 98·3 | 98·9 | 53 | 54·2 | 59·5 | 14 | 14·7 | 14·8 | 77·7 | 84·3 | 79·4 |
| August ..... | 98·1 | 99·1 | 99·1 | 55·4 | 56·3 | 59·5 | 13·9 | 15 | 14·7 | 78·4 | 85·3 | 80·9 |
| September ... | 98·1 | 99·1 | 99·1 | 54·4 | 57·3 | 60·4 | 14 | 15 | 15·2 | 78·9 | 86·2 | 81·7 |
| October ..... | 98·2 | 99·1 | 99 | 54·3 | 55·8 | 61 | 14·2 | 15 | 15·3 | 78·9 | 84·8 | 80·8 |
| November ... | 98·1 | 99·1 | 98·6 | 55·3 | 57·7 | 59·2 | 14·2 | 15·4 | 15·4 | 77 | 83·5 | 79 |
| | 98·07 | 98·9 | 99 | 54·4 | 56 | 60·3 | 14·4 | 15·4 | 15 | 76·7 | 83·6 | 79·8 |

These results, compared with those obtained in England, show marked differences, as will best appear by presenting them together.

| Mean temperature under the tongue in England. | | | Pulse. | | | Respirations. | | | Temperature of room. | | |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 7–8 A.M. | 3–4 P.M. | 12 P.M. | 7–8 A.M. | 3–4 P.M. | 12 P.M. | 7–8 A.M. | 3–4 P.M. | 12 P.M. | 7–8 A.M. | 3–4 P.M. | 12 P.M. |
| 98°74 | 98°52 | 97°92 | 57·6 | 55·2 | 54·7 | 15·6 | 15·4 | 15·2 | 50°9 | 54°7 | 62° |

| In Barbados:— | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 6–7 A.M. | 12–2 P.M. | 9–11 P.M. | 6–7 A.M. | 12–2 P.M. | 9–11 P.M. | 6–7 A.M. | 12–2 P.M. | 9–11 P.M. | 6–7 A.M. | 12–2 P.M. | 9–11 P.M. |
| 98·07 | 98·9 | 99 | 54·4 | 56 | 60·3 | 14·4 | 15·4 | 15 | 76·7 | 83·6 | 79 |

The observations from which these mean results are deduced are so consistent, as may be seen by reference to them in detail in the Appendix, as hardly to admit of doubt in relation to their accuracy.

Probably the low morning temperature of the body within the tropics, as shown above, may be owing principally to three circumstances,—to the depressing or lowering power of sleep,—to the light bed-covering used there, and the free circulation of the air in the room. A sheet and a thin coverlet were the only protection from the air; and the windows mostly being open, the outer air had free access, so that towards morning the temperature of the air of the room did not differ from that of the external air commonly more than two or three degrees. Moreover, the higher temperature observed at night, before going to rest, may have conduced to the lower morning temperature noticed on rising, as the lower temperature at night in England, with the opposite circumstances as to bed-clothing and air of sleeping-room, may have conduced to the higher morning temperature recorded there,—fluctuations these in accordance with well-known physiological laws.

2. *Of the Variation of Temperature during different seasons of the year.*

The following Table, formed from the first, exhibits the mean of the observed temperature during the several months comprised therein, as well as the mean of the in-door temperature.

| | Mean temperature under the tongue. | Air of room. | | Mean temperature under the tongue. | Air of room. |
|---|---|---|---|---|---|
| 1845. | | | 1847. | | |
| July ..... | 98°·43 | 76°·00 | January ..... | 98°·60 | 77°·70 |
| August ..... | 98·30 | 80·60 | February ... | 98·53 | 80·26 |
| September ... | 98·60 | 81·20 | March ..... | 98·60 | 77·40 |
| October ..... | 98·56 | 81·46 | April ..... | 98·53 | 78·00 |
| November ... | 98·46 | 80·56 | October ..... | 98·66 | 80·83 |
| December ... | 98·40 | 77·90 | November ... | 98·56 | 79·66 |
| 1846. | | | December ... | 98·36 | 77·36 |
| January ..... | 98·63 | 78·16 | 1848. | | |
| February ... | 98·60 | 77·88 | January ..... | 98·60 | 77·06 |
| April ..... | 98·46 | 80·00 | February ... | 98·53 | 77·73 |
| May ..... | 98·66 | 81·50 | March ..... | 98·60 | 78·40 |
| June ..... | 98·66 | 81·56 | April ..... | 98·60 | 78·26 |
| July ..... | 98·36 | 81·00 | May ..... | 98·66 | 81·46 |
| August ..... | 98·70 | 81·60 | June ..... | 98·60 | 80·86 |
| September ... | 98·40 | 81·36 | July ..... | 98·36 | 80·46 |
| October ..... | 98·73 | 81·50 | August ..... | 98·76 | 81·56 |
| November ... | 98·60 | 80·60 | September ... | 98·76 | 82·26 |
| December ... | 98·63 | 77·96 | October ..... | 98·76 | 81·50 |
| | | | November ... | 98·60 | 79·83 |
| | | | | 98·54 | 79·75 |

Comparing the temperature under the tongue with that of the air of the room, it will be seen that there is some accordance between them, though not a strict one, as if other circumstances than differences of atmospheric temperature have a marked

effect in modifying the temperature of the body within the tropics, where the variations of atmospheric temperature throughout the year are so inconsiderable—circumstances, for instance, of state of health, kind of life led as to exercise, diet, &c., and quality of atmosphere, as to degree of moisture or dryness, and the direction and force of the winds.

3. *Of the Effect of Active Exercise on the Temperature and of Rest after Exercise.*

On most occasions, when active exercise was taken, especially when on military duty, the dress worn was heavier and warmer than that in common use, to which partly the increase of temperature observed may be justly referred. This remark applies to the majority of the following observations:—

| | Tongue. | Pulse. | Respirations. | Air of room. |
|---|---|---|---|---|
| | ° | | | |
| December 17, 1846, 1 P.M. After attending an inspection of a regiment on parade, exposed to the sun about half an hour | 99·3 | 66 | 17 | 82 |
| December 28, 1846, 3 P.M. After returning from office in Barbados, with some difficulty in carriage, the latter part of the road being flooded, a torrent rushing over it, 4·39 inches of rain having fallen between 9 A.M. and 3h 30m P.M. | 99· | 56 | 17 | 75 |
| December 28, 1846, 4 P.M. The last hour sitting lightly clad | 98·1 | 52 | 16 | 77 |
| January 5, 1847, 1 P.M. After visiting hospitals | 99·3 | 54 | 16 | 82 |
| January 5, 1847, 4 P.M. The last hour sitting lightly clad, reading | 98·0 | 50 | 14 | 78 |
| January 6, 1847, 1 P.M. After inspecting an hospital | 99·2 | 54 | 15 | 82 |
| January 6, 1847, 4 P.M. Since 1 P.M. chiefly reading, lightly clad | 98·2 | 50 | 14 | 81 |
| March 26, 1847, 4 P.M. After inspecting hospitals, &c., occupied several hours, the greater part of the time walking | 99·8 | 70 | 16 | 85 |
| March 29, 1847, 6 A.M. After rising, before any exertion | 98·4 | 56 | 15 | 68 |
| March 29, 1847, 9 A.M. After a walk of three hours, ascending and descending a hill in the neighbourhood of Port of Spain, Trinidad; perspiring | 99·1 | 68 | 17 | 79 |
| March 29, 1847, 7h 30m P.M. After a ride of about four hours, most of the way at a quick pace; perspiring | 99·6 | 78 | 17 | 80 |
| April 3, 1847, 6 A.M. Just risen | 98·2 | 54 | 14 | 73 |
| April 3, 1847, 1 P.M. At the foot of the fall of the Marraca, in Trinidad, approached by a steep ascent through forest, an hour's walk, preceded by a ride at a quick pace of several miles; perspiring, temperature of hand 99°·5; that of the air (81° at the fall) was comparatively low from the evaporation of copious spray | 100· | 110 | 20 | 81 |
| April 3, 1847, 6h 15m P.M. On return from Marraca; the last few miles in an open carriage | 98·7 | 68 | 16 | 79 |
| April 10, 1848, 3h 30m P.M. After inspecting the hospital at St. Vincent and riding an hour or two | 99·4 | 62 | 16 | 85 |
| April 11, 1848, 3h 30m P.M. After visiting the barracks; perspiring | 99·4 | 78 | 17 | 84 |
| July 15, 1848, 1 P.M. After a ride of about an hour from Courland Bay, Tobago | 99·6 | 64 | 16 | 83 |
| July 15, 1848, 6h 30m P.M. After visiting barracks, &c. | 99·7 | 64 | 15 | 81 |

These results (many more of the like kind might be given) show how readily, when in health, the temperature of the body rises from active exercise and subsides on rest,—both, very much in the same manner and degree as in a cooler climate; and also, unless the exercise be severe, how the temperature is proportionally more affected than either the pulse or respiration.

### 4. *Of the Effect of Carriage Exercise on the Temperature.*

The carriage used was a light one adapted to the climate, open behind as well as in front, and well-protected from the sun, except when low, by a deep hood: the rate of going was commonly between six and seven miles an hour; a servant drove.

| | Tongue. | Pulse. | Respirations. | Air of room. |
|---|---|---|---|---|
| | ° | | | ° |
| January 28, 1846, 9 P.M. After coming from Mount Wilton, about 900 feet above the level of the sea | 97·9 | 70 | 15 | 73 |
| August 27, 1846, 5 P.M. After a drive of about sixteen miles, going to and returning from Villa Nova, in Barbados, in a cool situation about 700 feet above the level of the sea | 97·8 | 48 | 14 | 80 |
| September 3, 1846, 11 P.M. After coming from Villa Nova | 97·7 | 58 | 16 | 79 |
| November 18, 1846, 5 P.M. After a drive of about twenty-four miles in the heat of the day, going and returning, and some walking exercise in a low district of Barbados, fasting | 98·3 | 60 | 16 | 82 |
| November 18, 1846, 10 P.M. Feeling weary, after dinner, followed by tea... | 99·1 | 58 | 15 | 79 |
| November 21, 1846, 11$^{h}$ 30$^{m}$ P.M. After coming from Villa Nova | 97·7 | 58 | 16 | 79 |
| December 18, 1846, 5 P.M. After coming from Blackman's, situated like Villa Nova, and about the same distance; took a good deal of walking exercise there; the wind high | 98·6 | 70 | 15 | 80 |
| December 18, 1846, 9 P.M. Feeling weary, hot and thirsty | 99·7 | 80 | 16 | 79 |
| February 4, 1847, 12 P.M. After coming from Villa Nova | 97·5 | 58 | 15 | 74 |
| April 25, 1847, 10$^{h}$ 30$^{m}$ P.M. After coming from Villa Nova | 97·1 | 54 | 14 | 77 |
| June 14, 1848, 10 P.M. After coming from Villa Nova | 98·2 | 58 | 15 | 82 |

Many other instances, of which I have notes, might be adduced to show the effects of carriage exercise in lowering the temperature,—an effect previously observed in England. Those given, which were chiefly at night, were best marked, no doubt owing to the temperature of the air then being lower than by day, and the heat from the reflected and direct rays of the sun being then entirely avoided. When coming from the higher grounds of the interior of Barbados at night, and often when ascending them by day, the feeling of coolness was such as to render agreeable some additional clothing, which was always provided, though the difference of atmospheric temperature was only of a very few degrees. The latter observations, those of the 18th of November 1846 and of the 18th of December, are given as showing the tendency to augmentation of temperature of body in an undue degree after unusual depression, preceded by fatiguing exercise. The rise, so far as it was abnormal, was probably owing to the influence of the fatigue, for it was not witnessed if such exercise had not been taken.

### 5. *Of the Effect of Gentle Walking Exercise on the Temperature.*

The following observations were made when convalescing from illness (an anthrax with extensive sloughing and general derangement of health), a time when the body in a delicate state seems to be very readily acted on and to show the effects with unusual distinctness:—

| | Tongue. | Pulse. | Respirations. | Air of room. |
|---|---|---|---|---|
| | ° | | | ° |
| March 7, 1847, 6h 15m A.M. Just risen | 97·8 | 52 | 14 | 74 |
| March 7, 1847, 3 P.M. During the last two hours taking gentle exercise within doors, making some chemical experiments | 98·3 | 56 | 15 | 82 |
| August 17, 1847, 5h 45m A.M. Just risen | 97·8 | 62 | 15 | 77 |
| August 17, 1847, 7h 45m A.M. During last half hour walking slowly in shaded gallery, exposed to the wind; feelings agreeable; feet and hands warm | 97·8 | 68 | 16 | 80 |
| August 19, 1847, 5h 45m A.M. Just risen | 98·6 | 62 | 15 | 79 |
| August 19, 1847, 8 A.M. Last half hour walking in gallery; not exposed to the wind; perspiring gently | 98·4 | 70 | 17 | 81 |
| August 21, 1847, 5h 35m A.M. Just risen | 98·4 | 60 | 15 | 78 |
| August 21, 1847, 7h 30m A.M. After walking about half an hour; hands and feet glowingly warm | 98·2 | 76 | 17 | 81 |
| August 22, 1847, 5h 45m A.M. Just risen | 98·5 | 62 | 16 | 79 |
| August 22, 1847, 7h 45m A.M. After walking in gallery about half an hour, very lightly clad, exposed to the wind; hands and feet very warm | 98·2 | 78 | 17 | 82 |

To appreciate the effect of gentle exercise on the temperature, it requires to be mentioned and kept in mind, that had not such exercise been taken, the thermometer would have risen on its second application from ·3° to ·5° higher than at the first.

The feeling of increased warmth in the hands and feet from gentle exercise has been noticed in three instances. The diffusion of heat to the extremities, owing no doubt to a freer circulation of the warming medium—the blood—may partly account for the cooling effect under the tongue, and probably in the deep-seated parts from the exercise under consideration. The high temperature commonly observed in the extremities within the tropics, is a circumstance very deserving of note. In the daily observations appended, a record is given of the temperature of the hand during two months, noticed three times a day; from which it appears that on an average it was less than that under the tongue by only 1°. For the purpose of ascertaining the heat of the hand, the bulb of the thermometer was placed between the middle of the palm and the ball of the thumb, and so covered was gently pressed.

6. *Of the Effect of Change of the Temperature of the Atmosphere on the Temperature.*

In illustration of this effect, I shall notice only a very few of the observations obtained in the West Indies, corroborative of those collected many years ago in the island of Ceylon.

The situation of Villa Nova has already been mentioned: it was there that most of them were made, that spot being well-fitted for trials of the kind, the temperature there by day rarely exceeding 80°, even at the hottest time, and always below 80° at night, often requiring the closure of the bed-room windows, and occasionally a blanket in addition to the bed-clothes.

| | Tongue. | Pulse. | Respirations. | Air of room. |
|---|---|---|---|---|
| | ° | | | ° |
| November 15, 1847, 6 A.M. Just risen, at Villa Nova | 98 | 56 | 15 | 76 |
| November 15, 1847, 2 P.M. | 98·7 | 50 | 15 | 76 |
| November 15, 1847, 9h 30m P.M. | 97 | 58 | 16 | 76 |
| November 16, 1847, 6 A.M. | 98·4 | 54 | 15 | 76 |
| November 16, 1847, 1h 30m P.M. | 98·5 | 50 | 16 | 78 |
| November 16, 1847, 9h 30m P.M. Windows closed; feet and hands agreeably warm | 97·8 | 58 | 16 | 76 |
| November 17, 1847, 6h 15m A.M. | 98·3 | 54 | 14 | 75 |
| November 17, 1847, 9h 25m. At home, in the neighbourhood of Bridgetown | 98·8 | 54 | 16 | 77 |
| November 22, 1847, 1h 30m P.M. At home, variously occupied | 99·2 | 62 | 16 | 79 |
| November 22, 1847, 4 P.M. Last hour; sitting reading; raining; feel cold; hand 85° | 97·9 | 48 | 14 | 75 |
| December 24, 1847, 6 A.M. At home; just risen | 98·1 | 52 | 14 | 74 |
| December 24, 1847, 1h 3m P.M. At home; variously employed | 99·1 | 58 | 16 | 80 |
| December 24, 1847, 9h 30m P.M. Villa Nova; arrived there 5 P.M. | 97·8 | 56 | 14 | 74 |
| December 25, 1847, 6h 15m A.M. Villa Nova; just risen; slept warm; windows closed | 98·9 | 60 | 14 | 73 |
| December 25, 1847, 12 A.M. Agreeably cool | 98·5 | 54 | 14 | 76 |
| December 25, 1847, 5 P.M. A feeling almost of cold | 98·5 | 52 | 14 | 74 |
| December 25, 1847, 9h 30m P.M. | 97·85 | 52 | 15 | 74 |
| December 26, 1847, 6h 15m A.M. | 98·5 | 60 | 15 | 73 |
| December 26, 1847, 9h 15m P.M. At home; left Villa Nova at noon | 98·7 | 64 | 16 | 80 |

The observations made at Villa Nova, if compared with those made in England, will be found to approximate, especially as regards the morning and night temperature, and may be adduced in confirmation of the explanation given under Section 1, regarding the contrast of observed temperatures there adverted to.

### 7. *Of the Effect of Excited and Sustained Attention on the Temperature.*

A few instances may suffice to illustrate this effect, selecting those in which it was most strongly marked; between which and those least notable there is a fine gradation, according to degree of exertion of mind, which it would be difficult to appreciate on account of interfering disturbing circumstances.

| | Tongue. | Pulse. | Respirations. | Air of room. |
|---|---|---|---|---|
| | ° | | | ° |
| December 22, 1846, 3h 30m P.M. After delivering a discourse in public, in a well-aired room, lasting about an hour | 99·8 | 78 | 16 | 82 |
| December 22, 1846, 5h 20m P.M. | 98·9 | 58 | 15 | 80 |
| December 22, 1847, 6 A.M. Just risen | 98·1 | 52 | 13 | 75 |
| December 22, 1847, 3h 15m P.M. After delivering a discourse in the same place as the preceding and of about the same length | 100·3 | 90 | 15 | 82 |
| December 22, 1847, 9h 30m P.M. | 98·9 | 66 | 15 | 77 |
| December 23, 1847, 6 A.M. | 97·9 | 54 | 14 | 75 |
| June 24, 1848, 3h 30m P.M. After occupation similar to that last mentioned, and in the same place | 99·9 | 82 | 15 | 81 |
| August 30, 1848, 2 P.M. After delivering a chemical lecture in a close and crowded room | 100·1 | 84 | 15 | 88 |
| August 30, 1848, 9 P.M. | 99·4 | 62 | 14 | 82 |
| August 31, 1848, 6 A.M. | 98·2 | 58 | 14 | 80 |
| September 6, 1848, 2 P.M. Similarly occupied; the heat of the room greater; immediately after the pulse was 100 | 100·4 | 80 | 16 | 88 |
| September 6, 1848, 9 P.M. | 99·2 | 64 | 15 | 81 |
| September 7, 1848, 5h 45m A.M. | 98·2 | 54 | 14 | 78 |

The additional observations—those made some hours after the exertion—are given as illustrating an important fact, viz. the rapid manner in which, when the body is free from disease, the functions on rest return to their ordinary state; whilst, on the contrary, when disease is present, especially of an organic kind, even though latent in relation to the most obvious class of symptoms, indications of it may be obtained by attention to the temperature, pulse and respiration; and often, as in instances of pulmonary disease, in a very remarkable and decided manner.

### 8. *On the Effect of Cool and Well-ventilated Rooms, and of Close and Heated Rooms on the Temperature.*

As regards ventilation, and consequently coolness where there is a concourse of people, the cathedral church of Barbados, and Harrison's school-room adjoining, in which lectures were given on the opening of the "Reid School of Practical Chemistry," may be mentioned as good and bad examples. In illustration of the effects of each, I shall give a few observations on temperature, noted down when made, which was within about half an hour after quitting the church and the school, conveyed in a carriage, attending in the one divine service, in the other a lecture. The temperature of the air marked, as usual, was that of my sitting-room, which was cooler by several degrees than the school-room, but less cool commonly than the church.

| | Tongue. | Pulse. | Respirations. | Air of room. |
|---|---|---|---|---|
| | ° | | | ° |
| February 28, 1847, 1 P.M. Just come from church | 98·4 | 54 | 16 | 83 |
| March 7, 1847, 1 P.M. Just come from church | 98·5 | 54 | 15 | 84 |
| March 5, 1848, $2^h\ 45^m$ P.M. Just come from church | 98·5 | 56 | 15 | 82 |
| August 2, 1848, $2^h\ 30^m$ P.M. Just come from school-room | 99·8 | 66 | 13 | 85 |
| August 9, 1848, 2 P.M. Just come from school-room | 99·8 | 60 | 16 | 82 |
| August 16, 1848, $2^h\ 30^m$ P.M. Just come from school-room | 99·9 | 64 | 16 | 87 |
| October 18, 1848, $3^h\ 30^m$ P.M. Room less crowded | 99·5 | 58 | 15 | 82 |
| October 25, 1848, $5^h\ 15^m$ P.M. Room less crowded | 99·4 | 62 | 15 | 83 |

### 9. *On the Effect of taking Food and Wine on the Temperature.*

The effect of a meal in moderation, whether the light one of breakfast or the fuller and heavier one of dinner, was to raise the temperature; and this also when wine was sparingly used at the latter, viz. to the extent of two or three glasses; but when more freely drunk, as it commonly is in company, then often its influence on temperature appeared to be depressing. I shall give a few instances in illustration:—

| | Tongue. | Pulse. | Respirations. | Air of room. |
|---|---|---|---|---|
| | ° | | | ° |
| December 21, 1846, 10 P.M. Dinner at 6; wine chiefly champagne and Madeira; no headache; no malaise | 98·1 | 70 | 15 | 77 |
| February 6, 1847, 10 P.M. Dinner at 7; the wines similar | 97·8 | 70 | 15 | 71 |
| February 13, 1848, $11^h\ 30^m$ P.M. Dinner at 6; about seven miles distant in the country, from whence just returned; kind of wine not noticed | 97·3 | 64 | 16 | 78 |
| March 9, 1848, $10^h\ 30^m$ P.M. Dinner at 7; kind of wine not noted down | 97·9 | 64 | 15 | 77 |
| May 29, 1848, 12 P.M. Dinner at 7; wines chiefly champagne and claret | 98 | 72 | 16 | 79 |
| August 9, 1848, 11 P.M. Dinner at 7; the wines like the last | 98 | 70 | 15 | 79 |

It is deserving of remark, that whenever wine was used, except in great moderation, though never to the excess of an inebriating effect, on the following morning the temperature under the tongue was found to be more or less above the average, and the pulse commonly quicker than usual. It is also worthy of remark, that occasionally the effect at night was to increase the temperature of the body, and that in a marked manner; but whether from some peculiar quality of the wine used, or from some deranged state of the system or other adventitious circumstance, I have not been able to determine.

### 10. *Of the Effect of Sea-sickness on the Temperature.*

During a voyage from Barbados to St. Christopher, and from thence to Barbados in May and June 1848, in a transport, stopping at some of the intermediate islands, an opportunity offered of making some observations on the effect of sea-sickness, from which I suffered more or less on the several days noticed in the subjoined Table. The degree of sickness, often amounting to vomiting, was such as to render rising disagreeable. Little food was taken on those days, excepting chicken broth with some bread; no wine was drunk. The observations were made in the sitting posture in bed in a well-ventilated cabin.

| | Temperature under the tongue. | | | Pulse. | | | Respirations. | | | Temperature of cabin. | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | 6–7 A.M. | 12–2 P.M. | 6–10 P.M. | 6–7 A.M. | 12–2 P.M. | 6–10 P.M. | 6–7 A.M. | 12–2 P.M. | 6–10 P.M. | 6–7 A.M. | 12–2 P.M. | 6–10 P.M. |
| | ° | ° | ° | | | | | | | ° | ° | ° |
| May 14. | 98·7 | 98·9 | ..... | 58 | 68 | ... | 16 | 16 | ... | 81 | 83 | |
| 15. | 98·8 | ..... | ..... | 60 | ... | ... | 14 | ... | ... | 80 | ... | |
| 18. | 98·2 | 98·6 | ..... | 54 | 64 | ... | 14 | 15 | ... | 80 | 81 | |
| 26. | 98·7 | ..... | ..... | 60 | ... | ... | 15 | ... | ... | 79 | ... | |
| 27. | 98·8 | ..... | ..... | 60 | ... | ... | 15 | ... | ... | 79 | ... | |
| 31. | ..... | 98·7 | 99·1 | ... | 58 | 58 | ... | 15 | 14 | ... | 82 | 82 |
| June 1. | 98·6 | 98·8 | 99·3 | 58 | 56 | 58 | 14 | 15 | 15 | 81 | 83 | 83 |
| 2. | 98·7 | 98·3 | ..... | 56 | 58 | ... | 14 | 14 | ... | 81 | 80 | |
| 3. | 98·7 | 99·2 | 99·4 | 58 | 56 | 60 | 15 | 16 | 15 | 80 | 82 | 82 |
| 4. | 98·7 | ..... | ..... | 58 | ... | ... | 14 | ... | ... | 80 | ... | |
| | 98·65 | 98·75 | 99·23 | 57·55 | 60·28 | 58·66 | 14·44 | 15·14 | 14·66 | 80·24 | 81·71 | 82·33 |

It appears from these few observations, that under the influence of sea-sickness, the morning temperature was higher than ordinary and the pulse somewhat quicker; when the former was lowest, as on the 18th of May, then the vessel being in smooth water, there was scarcely any uneasiness experienced. Comparing the several observations, perhaps the inference may be justifiable, that the tendency of sea-sickness, when not in its severest form, is of an equalizing kind in relation to the temperature, pulse and respiration,—a tendency no doubt promoted by the little variation to which the sea atmosphere is liable, especially within the tropics. On so obscure a subject, however, as sea-sickness, this remark is offered with some hesitation.

11. *Of the Temperature at Sea, when not under the influence of Sea-sickness.*

In returning from the West Indies in the well-appointed steam-packet Clyde, I availed myself of the opportunity to continue the observations on temperature. The results are given in the following Table, commencing on the day after leaving St. Thomas, when all feeling of sea-sickness had ceased, and ending on the 2nd of December, the day before coming in sight of the coast of England. The weather during the greater part of the voyage was favourable: after leaving Fayal, on the 27th of November, it was more or less tempestuous; on the 29th and 30th, it was necessary to have the cabin ports closed. The observations were made in a well-ventilated cabin in the sitting posture,—the port commonly open excepting at night. The diet was fuller and more nourishing than that used in the West Indies, the appetite increasing on passing into a cooler climate; rather more wine was used, viz. a pint of sound Bordeaux at dinner; and the clothing was rendered warmer as required by diminution of warmth of atmosphere:—

| | Position of ship at noon. | | Temperature under the tongue. | | | Pulse. | | | Respirations. | | | Temperature of cabin. | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | Lat. N. | Long. W. | 6–7 A.M. | 12–2 P.M. | 10 P.M. | 6–7 A.M. | 12–2 P.M. | 10 P.M. | 6–7 A.M. | 12–2 P.M. | 10 P.M. | 6–7 A.M. | 12–2 P.M. | 10 P.M. |
| Nov. | ° ′ | ° ′ | ° | ° | ° | | | | | | | ° | ° | ° |
| 16. | 22 39 | 61 8 | 98·5 | 98·8 | 98·9 | 54 | 50 | 60 | 14 | 15 | 16 | 78 | 81 | 78 |
| 17. | 24 16 | 58 11 | 98·2 | 98·3 | 98·4 | 56 | 54 | 66 | 14 | 16 | 15 | 76 | 77 | 77 |
| 18. | 25 39 | 55 30 | 98·2 | 98·7 | 98·2 | 56 | 52 | 60 | 14 | 16 | 15 | 75 | 77 | 77 |
| 19. | 27 33 | 53 13 | 98·6 | 99·3 | ... | 52 | 72 | ... | 14 | 15 | ... | 77 | 79 | |
| 20. | 29 19 | 50 45 | 98·6 | 98·1 | 97·7 | 60 | 56 | 60 | 14 | 15 | 15 | 77 | 77 | 77 |
| 21. | 31 6 | 48 9 | 98·5 | 97·9 | 97·8 | 56 | 50 | 62 | 14 | 15 | 15 | 75 | 75 | 73 |
| 22. | 32 53 | 45 16 | 98·7 | 97·7 | 97·7 | 54 | 54 | 60 | 14 | 14 | 15 | 71 | 73 | 72 |
| 23. | 34 43 | 41 18 | 98·2 | 98 | 98·1 | 54 | 56 | 58 | 15 | 15 | 15 | 71 | 71 | 72 |
| 24. | 36 23 | 37 21 | 98·5 | 98·1 | 98·6 | 58 | 54 | 60 | 14 | 15 | 15 | 69 | 67 | 67 |
| 25. | 37 21 | 33 34 | 98·3 | 98·5 | ... | 52 | 56 | ... | 14 | 14 | ... | 64 | 66 | |
| 26. | 38 28 | 30 2 | 98·5 | 98·7 | ... | 56 | 56 | ... | 14 | 14 | ... | 66 | 69 | |
| 27. | 38 32 | 28 40 | 98·3 | 98·5 | 97·5 | 54 | 54 | 54 | 14 | 15 | 15 | 68 | 67 | 66 |
| 28. | 41 2 | 25 18 | 98·4 | 98·7 | 98·3 | 52 | 58 | 60 | 14 | 16 | 15 | 66 | 61 | 65 |
| 29. | 43 19 | 21 32 | 98·6 | 99·4 | 98 | 56 | 62 | 58 | 14 | 15 | 15 | 65 | 63 | 68 |
| 30. | 44 59 | 17 13 | 98·1 | 98·9 | 97·3 | 54 | 56 | 54 | 14 | 15 | 14 | 61 | 59 | 64 |
| Dec. | | | | | | | | | | | | | | |
| 1. | 46 33 | 12 7 | 98·4 | 98·9 | 97·9 | 54 | 60 | 56 | 14 | 14 | 14 | 59 | 59 | 63 |
| 2. | 48 33 | 6 44 | 98·7 | 98 | 97·6 | 58 | 62 | 48 | 14 | 15 | ... | 58 | 57 | 59 |

Comparing these results with those obtained in England and in the West Indies, they will be found to accord more with the former than the latter, the morning being on an average higher than those obtained at night. The small range of temperature is also worthy of note, and its decrease with diminution of atmospheric temperature. In those instances in which the variation was greatest, the higher temperature noted down, was in the middle of the day, commonly in connection with active walking exercise just before taken,—and the lower than ordinary at the same period of the day, was, after sitting for an hour or two exposed to the wind on deck.

*Conclusions.*

The following are some of the conclusions that appear to be either proved or rendered probable by the preceding results, or by those given in the Tables appended,—supposing, as it is believed, that, were the observations extended to many individuals, no material discrepancy would be witnessed.

1. That the average temperature of man within the tropics is a little higher, nearly 1°, than in a temperate climate, such as that of England.

2. That within the tropics, as had before been found in cooler regions, the temperature of the body is almost constantly fluctuating,—varying according to the variety of agencies to which it is subject, some of which are distinct, others obscure.

3. That the order of fluctuation observed there is different from that in a cooler climate, the minimum degree of temperature being commonly early in the morning, after the night's rest, and not at night previous to going to rest.

4. That all exertion, whether of body or mind, except it be very gentle, coming under the designation of passive rather than active exercise, has a heightening effect on the temperature, while the latter, the passive kind, has rather a lowering tendency, especially carriage exercise.

5. That heavy clothing, especially if tight and close, obstructing the admission and circulation of air, tends to raise the temperature unduly, especially under active exercise; and that close, ill-ventilated rooms, especially when crowded, have in a marked manner the same tendency.

6. That when the body is in a healthy state, then on rest after exercise or exposure to any other exciting cause, it rapidly recovers its normal condition as to temperature.

7. That when labouring under disease, however slight, the temperature is abnormally elevated; and that—judging from observations made, but not recorded, in the Tables—its undue degree is some criterion of the intensity of the diseased action.

8. That within the tropics there is comparatively little difference of temperature between the surface of the body, especially the extremities and the internal parts;—and that there the skin is more active in its function of transpiration and the kidneys are less active as secreting organs; with which it may be conjectured is connected a rapid production and desquamation of cuticle, and the absence, in great part or entirely, of lithic acid in the urinary secretion. This latter fact, however, may be explained in a different manner, on the supposition that the acid is not formed in the blood, or if formed, in a greatly diminished quantity.

9. That the effect of wine, unless used in great moderation, is commonly lowering, that is as to temperature, whilst it accelerates the heart's action, followed after a while by an increase of temperature.

10. That the tendency of sea-sickness is to check what may be considered the natural fluctuation of the temperature, and when severe, like disease, to elevate the temperature.

11. That the tendency of a sea voyage, apart from sea-sickness, is to equalize the temperature without elevating it, an equalization that is best witnessed in voyaging in a tropical sea, where the atmospheric temperature is so little variable.

12. That even at sea, with a change of atmospheric temperature, there is a tendency to change of temperature of the body, the average increasing in proceeding towards the tropics, and diminishing in receding from them.

These conclusions obviously admit of application, and that variously in relation to health and disease. It would be unsuitable to the occasion to dwell on this part of the subject; I shall merely remark, that it is a happy circumstance for man, and seems wisely ordered, that fluctuation of temperature should be connected with a healthy state of the system, and probably conducive to it, in whatever manner produced, whether by change of climate, or atmospheric variation, or by exercise, whether of body or mind. The excellent health which the crews of the West Indian steam-packets have, that are in constant transition from heat to cold, is a striking proof of this, and other instances of a like kind, were it necessary, might be adduced in confirmation.

*Lesketh How, Ambleside,*
*February* 14, 1850.

## Appendix.

The thermometer used in making the observations contained in these Tables, was compared with a standard one, and was found to require no correction in its scale for the degrees of temperature indicated when placed under the tongue.

| | | Temperature under the tongue and in hand. | | | | | | Pulse. | | | Respirations. | | | Temp. of air of room. | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | 6–7 A.M. | | 12–2 P.M. | | 9–11 P.M. | | 6–7 A.M. | 12–2 P.M. | 9–11 P.M. | 6–7 A.M. | 12–2 P.M. | 9–11 P.M. | 6–7 A.M. | 12–2 P.M. | 9–11 P.M. |
| | | Tongue. | Hand. | Tongue. | Hand. | Tongue. | Hand. | | | | | | | | | |
| July 1845. | 12. | 98°7 | 97°5 | 99°5 | 98° | 98°25 | 97°5 | 64 | 66 | 62 | 15 | 15 | 16 | 80° | 84° | 82° |
| | 13. | 98·35 | 97·5 | 99·1 | 98 | 98·5 | 98 | 58 | 54 | 64 | 17 | 15 | 16 | 79 | 78 | 80 |
| | 14. | 98·4 | 97·5 | 99·1 | 98 | 98·95 | 98 | 58 | 60 | 70 | 15 | 16 | 17 | 77 | 84 | 80 |
| | 15. | 98·7 | 98 | 99·3 | 98·5 | 99·2 | 98 | 60 | 76 | 76 | 15 | 16 | 16 | 78 | 83 | 80 |
| | 18. | 98·4 | 97·25 | 99·3 | 98 | 99·5 | 98·5 | 60 | 64 | 70 | 15 | 16 | 17 | 78 | 83 | 77 |
| | 19. | 98·4 | 97·5 | 99·2 | 98 | 99 | 97·5 | 62 | 62 | 60 | 16 | 16 | 16 | 77 | 83 | 79 |
| | 20. | 98·1 | 97·25 | 98·6 | 97·5 | 98·7 | 97·25 | 56 | 52 | 52 | 15 | 15 | 16 | 77 | 74 | 79 |
| | 21. | 98·6 | 97·5 | 99 | 97·5 | 98·8 | 97·5 | 54 | 64 | 54 | 15 | 15 | 16 | 78 | 83 | 80 |
| | 22. | 97·5 | 96 | 98·4 | 97·5 | 98·3 | 97 | 56 | 56 | 60 | 15 | 16 | 16 | 78 | 81 | 81 |
| | 23. | 97·8 | 97 | 98·9 | 97·5 | ..... | ..... | 54 | 60 | ..... | 16 | 16 | ..... | 79 | 84 | |
| | 24. | 97·9 | 96·25 | ..... | ..... | 98·4 | 97 | 54 | ..... | 54 | 15 | ..... | 16 | 79 | ..... | 79 |
| | 25. | 97·8 | 97 | 98·8 | 97·5 | 98·3 | 97·5 | 50 | 52 | 62 | 15 | 16 | 16 | 78 | 85 | 80 |
| | 26. | 98·1 | 97·5 | 99·1 | 98 | 98·7 | 97·25 | 62 | 60 | 54 | 14 | 15 | 16 | 78 | 85 | 81 |
| | 27. | 98·2 | 97 | 98·6 | 97 | 98·1 | 96·5 | 52 | 54 | 54 | 15 | 15 | 15 | 80 | 86 | 79 |
| | 28. | 98·2 | 96·5 | 98·7 | 97·25 | 98·4 | 97·5 | 54 | 54 | 64 | 15 | 15 | 16 | 78 | 84 | 80 |
| | 29. | 98·2 | 96·75 | ..... | ..... | 98·7 | 97·5 | 50 | ..... | 64 | 14 | ..... | 16 | 78 | ..... | 80 |
| | 30. | 98·1 | 96·5 | 98·9 | 97·5 | 98·4 | 97·5 | 50 | 62 | 50 | 14 | 16 | 50 | 78 | 85 | 79 |
| | 31. | 98·2 | 97 | 99·1 | 97·7 | 98·3 | ..... | 56 | 61 | 61 | 15 | 16 | 16 | 79 | 85 | 80 |
| | | 98·2 | 97·1 | 99 | 97·7 | 98·2 | 97·35 | 56 | 61 | 66·5 | 14·7 | 15·5 | 16 | 78·3 | 81·5 | 79·4 |
| August 1845. | 4. | 98·4 | 97 | 99 | 97·5 | 99 | 97·5 | 56 | 64 | 60 | 15 | 16 | 16 | 79 | 83 | 82 |
| | 5. | 98 | 96·5 | 98·7 | 97·25 | 98 | 96·5 | 52 | 52 | 52 | 15 | 15 | 15 | 78 | 85 | 78 |
| | 6. | 97·7 | 97 | 99·1 | 97·5 | 98 | 97 | 54 | 54 | 60 | 14 | 16 | 16 | 78 | 84 | 79 |
| | 7. | 98·25 | 97·5 | 98·7 | 97·7 | 98·7 | 98 | 60 | 54 | 54 | 16 | 16 | 15 | 78 | 85 | 82 |
| | 8. | 97·7 | 96·7 | 98·3 | 96·5 | 98·3 | 97·5 | 50 | 52 | 60 | 15 | 16 | 16 | 78 | 85 | 81 |
| | 9. | 98·2 | 97 | 98·5 | 97 | 98·6 | 97·5 | 52 | 54 | 62 | 15 | 16 | 16 | 79 | 84 | 80 |
| | 10. | 93·9 | 97 | 98·7 | 97·5 | 97·8 | 96·7 | 52 | 58 | 64 | 16 | 16 | 16 | 79 | 85 | 80 |
| | 11. | 98·5 | 97·5 | 98·8 | 97 | 98·5 | 97·25 | 60 | 52 | 56 | 16 | 15 | 16 | 80 | 85 | 80 |
| | 12. | 97·8 | 97 | 98·9 | 98 | 98·9 | 98 | 54 | 54 | 62 | 15 | 15 | 16 | 79 | 87 | 81 |
| | 13. | 97·9 | 97 | 98·8 | 97·5 | 98·3 | 97·5 | 54 | 52 | 58 | 14 | 15 | 16 | 78 | 83 | 80 |
| | 14. | 97·7 | 96·5 | 99 | 97·5 | 98·7 | 97·5 | 50 | 54 | 56 | 15 | 16 | 16 | 78 | 88 | 80 |
| | 15. | 97·8 | 97 | 98·7 | 97·75 | 98·7 | 97 | 52 | 52 | 54 | 14 | 15 | 16 | 79 | 85 | 81 |
| | 16. | 97·9 | 96·5 | 98·7 | 97·5 | 98·7 | 97·5 | 52 | 54 | 54 | 15 | 16 | 15 | 79 | 86 | 81 |
| | 17. | 97·9 | 97 | 98·4 | 97·25 | 98·2 | 97·3 | 54 | 50 | 62 | 15 | 16 | 15 | 79 | 82 | 80 |
| | 18. | 98·1 | 97 | 98·7 | 97 | 98·7 | 97·5 | 54 | 50 | 60 | 14 | 15 | 16 | 77 | 87 | 82 |
| | 19. | 98·3 | 97 | 98·4 | 97·5 | 98·5 | 97 | 54 | 50 | 60 | 14 | 15 | 15 | 78 | 87 | 82 |
| | 20. | 98·3 | 97·5 | 98·7 | 97·5 | 98·8 | 97·5 | 52 | 56 | 56 | 15 | 16 | 15 | 78 | 77 | 78 |
| | 21. | 98·2 | 97 | 98·5 | 97 | 98·4 | 97·5 | 56 | 54 | 58 | 15 | 15 | 16 | 78 | 82 | 78 |
| | 22. | 98 | 97 | 98·7 | 97·7 | 98·6 | 97·7 | 52 | 54 | 54 | 15 | 16 | 15 | 78 | 83 | 80 |
| | 23. | 98 | 97·7 | 99 | 98·5 | 98·5 | 97·7 | 52 | 54 | 54 | 15 | 16 | 15 | 78 | 85 | 81 |
| | 24. | 98·2 | 97·7 | 99 | 98 | 98·6 | 97·5 | 52 | 50 | 54 | 15 | 15 | 15 | 77 | 84 | 81 |
| | 25. | 98·1 | 97 | 98·7 | 97·5 | 98·7 | 97·5 | 54 | 56 | 56 | 16 | 15 | 16 | 78 | 84 | 77 |
| | 27. | 97·9 | 97 | 98·8 | 97·5 | 98·8 | 97·5 | 54 | 52 | 62 | 15 | 16 | 16 | 78 | 86 | 80 |
| | 28. | 98·1 | 97 | ..... | ..... | ..... | ..... | 60 | ..... | ..... | 16 | ..... | ..... | 78 | ..... | ..... |
| | 30. | 98·2 | ..... | 99 | ..... | 98·9 | ..... | 54 | 58 | 60 | 15 | 16 | 15 | 79 | 86 | 81 |
| | 31. | 97·9 | ..... | 98·6 | ..... | 99·2 | ..... | 54 | 50 | 60 | 15 | 15 | 16 | 80 | 86 | 82 |
| | | 98 | 97 | 98·7 | 97·4 | 98·16 | 97·4 | 53·8 | 53·6 | 57·9 | 15 | 15·7 | 15·8 | 78·7 | 84 | 80·3 |

| | | Temp. under the tongue. | | | Pulse. | | | Respirations. | | | Temperature of room. | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | 6–7 A.M. | 12–2 P.M. | 9–11 P.M. | 6–7 A.M. | 12–2 P.M. | 9–11 P.M. | 6–7 A.M. | 12–2 P.M. | 9–11 P.M. | 6–7 A.M. | 12–2 P.M. | 9–11 P.M. |
| | | ° | ° | ° | | | | | | | ° | ° | ° |
| September 1845. | 1. | 98 | 98·9 | 99·3 | 54 | 52 | 66 | 15 | 16 | 15 | 78 | 86 | 81 |
| | 2. | 98·3 | 99·3 | 99·9 | 60 | 56 | 70 | 14 | 15 | 15 | 79 | 86 | 81 |
| | 3. | 98·1 | 98·6 | 99·3 | 54 | 50 | 58 | 14 | 16 | 15 | 78 | 82 | 80 |
| | 4. | 98·1 | 99·1 | 99·1 | 60 | 56 | 66 | 15 | 15 | 16 | 79 | 85 | 80 |
| | 5. | 98 | 98·9 | 98·9 | 52 | 54 | 60 | 15 | 16 | 14 | 78 | 85 | 79 |
| | 6. | 98 | 98·3 | 99·1 | 46 | 50 | 66 | 14 | 15 | 16 | 79 | 80 | 81 |
| | 7. | 97·95 | 98·7 | 99 | 50 | 48 | 64 | 15 | 16 | 16 | 77 | 84 | 80 |
| | 8. | 98·2 | 99·1 | 98·6 | 54 | 50 | 60 | 15 | 15 | 16 | 77 | 86 | 80 |
| | 9. | 97·9 | 99·1 | 99 | 52 | 56 | 62 | 15 | 16 | 16 | 78 | 83 | 80 |
| | 10. | 98·1 | 98·9 | 98·5 | 54 | 56 | 70 | 15 | 16 | 16 | 78 | 85 | 80 |
| | 11. | 98·6 | 99 | 98·4 | 70 | 54 | 52 | 15 | 15 | 16 | 78 | 80 | 80 |
| | 12. | 97·8 | 98·9 | 98·6 | 52 | 52 | 60 | 15 | 15 | 15 | 78 | 85 | 78 |
| | 13. | 98·1 | 99·2 | 99 | 52 | 56 | 62 | 15 | 16 | 16 | 78 | 82 | 80 |
| | 14. | 97·9 | 98·6 | 98·9 | 52 | 52 | 62 | 15 | 16 | 15 | 78 | 84 | 80 |
| | 15. | 98·1 | 99 | 98·7 | 52 | 60 | 54 | 15 | 16 | 16 | 78 | 85 | 82 |
| | 16. | 98 | 98·5 | 98·6 | 60 | 60 | 60 | 16 | 16 | 15 | 78 | 85 | 82 |
| | 17. | 98·1 | 98·9 | 98·8 | 60 | 56 | 58 | 16 | 16 | 15 | 78 | 85 | 81 |
| | 18. | 98·2 | 99 | 99·3 | 56 | 60 | 70 | 15 | 15 | 16 | 79 | 87 | 82 |
| | 19. | 98·3 | 99 | 99·2 | 56 | 56 | 62 | 14 | 15 | 15 | 79 | 86 | 82 |
| | 20. | 98·4 | 99·5 | 99·3 | 54 | 58 | 60 | 15 | 16 | 16 | 77 | 86 | 77 |
| | 21. | 98·5 | 98·8 | 98·9 | 52 | 56 | 58 | 14 | 15 | 15 | 80 | 85 | 82 |
| | 22. | 98·2 | 99·4 | 99·4 | 52 | 62 | 76 | 15 | 16 | 15 | 79 | 84 | 81 |
| | 23. | 98·3 | 99·4 | 99 | 56 | 60 | 68 | 16 | 16 | 16 | 78 | 85 | 81 |
| | 24. | 98 | 98·8 | 98·3 | 52 | 52 | 51 | 15 | 16 | 15 | 80 | 86 | 80 |
| | 26. | 98·1 | 98·4 | 99 | 52 | 52 | 62 | 15 | 16 | 16 | 77 | 85 | 81 |
| | 27. | 97·9 | 98·5 | 98·7 | 54 | 58 | 62 | 15 | 16 | 16 | 78 | 85 | 82 |
| | 28. | 97·7 | 98·5 | 98·7 | 52 | 54 | 58 | 15 | 15 | 16 | 80 | 87 | 81 |
| | 29. | 97·9 | 98·9 | 98·9 | 52 | 52 | 62 | 15 | 15 | 15 | 78 | 86 | 80 |
| | 30. | 97·9 | 99·3 | 99·3 | 54 | 58 | 62 | 15 | 15 | 16 | 78 | 86 | 82 |
| | | 98 | 98·9 | 98·9 | 54·3 | 55 | 62·1 | 15·2 | 15·6 | 15·5 | 78·6 | 84·7 | 80·5 |
| October 1845. | 1. | 97·6 | 99·1 | 98·9 | 54 | 54 | 58 | 15 | 14 | 16 | 78 | 86 | 82 |
| | 2. | 97·9 | 99·3 | 99 | 54 | 62 | 60 | 15 | 15 | 15 | 78 | 86 | 81 |
| | 3. | 98 | 99 | 99 | 52 | 54 | 66 | 15 | 16 | 16 | 78 | 87 | 82 |
| | 4. | 97·9 | 98·8 | 98·7 | 51 | 56 | 62 | 14 | 16 | 16 | 78 | 86 | 80 |
| | 5. | 98·1 | 98·6 | 98·4 | 56 | 56 | 54 | 14 | 16 | 15 | 79 | 85 | 80 |
| | 6. | 97·9 | 99·1 | 98·7 | 56 | 66 | 60 | 14 | 15 | 15 | 79 | 84 | 84 |
| | 7. | 98·2 | ..... | 98·7 | 52 | ..... | 64 | 14 | ..... | 16 | 80 | ..... | 82 |
| | 8. | 98·5 | 98·6 | 98·8 | 52 | 56 | 56 | 15 | 15 | 16 | 78 | 86 | 82 |
| | 9. | 97·8 | 98·6 | 98·4 | 53 | 54 | 60 | 15 | 16 | 16 | 77 | 86 | 82 |
| | 10. | 98·2 | ..... | 98·9 | 54 | ..... | 68 | 15 | ..... | 16 | 78 | ..... | 82 |
| | 11. | 98 | 98·7 | 98·9 | 52 | 58 | 56 | 14 | 16 | 16 | 78 | 87 | 82 |
| | 12. | 97·9 | 98·7 | ..... | 52 | 52 | ..... | 15 | 16 | ..... | 78 | 86 | ..... |
| | 13. | 98 | 98·7 | 98·8 | 53 | 56 | 62 | 15 | 16 | 16 | 78 | 87 | 82 |
| | 14. | 98 | 99·1 | 98·8 | 52 | 56 | 62 | 14 | 15 | 16 | 77 | 87 | 81 |
| | 15. | 98·1 | 99 | 98·9 | 54 | 58 | 56 | 15 | 16 | 16 | 78 | 85 | 80 |
| | 16. | 98·2 | 98·8 | 98·9 | 54 | 62 | 62 | 15 | 17 | 15 | 79 | 86 | 81 |
| | 17. | 98·2 | 99·6 | 99·4 | 56 | 58 | 64 | 15 | 16 | 16 | 80 | 87 | 83 |
| | 18. | 97·9 | 98·9 | 99 | 52 | 60 | 76 | 14 | 16 | 17 | 80 | 82 | 77 |
| | 19. | 98 | 99·4 | 98·8 | 64 | 66 | 56 | 16 | 16 | 15 | 78 | 83 | 79 |
| | 20. | 98 | 99·7 | 98·6 | 56 | 62 | 70 | 15 | 16 | 16 | 77 | 84 | 79 |
| | 21. | 98 | 99·5 | 99 | 54 | 60 | 58 | 15 | 17 | 16 | 77 | 84 | 80 |
| | 22. | 97·9 | 98·9 | 98·8 | 50 | 60 | 60 | 14 | 17 | 17 | 77 | 86 | 82 |
| | 23. | 98·2 | 99·1 | 98·9 | 56 | 60 | 60 | 15 | 16 | 16 | 79 | 87 | 82 |
| | 24. | 98·1 | 99 | 99·4 | 58 | 60 | 62 | 14 | 16 | 16 | 79 | 87 | 82 |
| | 25. | 97·9 | 98·9 | 99·3 | 56 | 54 | 60 | 15 | 16 | 16 | 78 | 86 | 82 |
| | 26. | 97·9 | 98·7 | 98·9 | 50 | 60 | 52 | 15 | 16 | 15 | 78 | 84 | 80 |
| | 27. | 97·9 | 99·1 | 99·1 | 53 | 60 | 60 | 15 | 16 | 15 | 80 | 84 | 80 |
| | 28. | 97·7 | ..... | ..... | 54 | ..... | ..... | 15 | ..... | ..... | 78 | ..... | ..... |
| | 29. | ..... | 98·7 | 99 | ..... | 54 | 56 | ..... | 16 | 16 | ..... | 86 | 81 |
| | 30. | 97·8 | 98·7 | 99 | 52 | 58 | 62 | 15 | 17 | 16 | 78 | 85 | 81 |
| | 31. | 97·8 | 98·6 | 98·7 | 52 | 56 | 60 | 15 | 16 | 16 | 78 | 83 | 81 |
| | | 97·9 | 99 | 98·8 | 53·4 | 56·3 | 61·3 | 14·6 | 15·9 | 16·8 | 78 | 85·4 | 81 |

| | | Temp. under the tongue. | | | Pulse. | | | Respirations. | | | Temperature of room. | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | 6–7 A.M. | 12–2 P.M. | 9–11 P.M. | 6–7 A.M. | 12–2 P.M. | 9–11 P.M. | 6–7 A.M. | 12–2 P.M. | 9–11 P.M. | 6–7 A.M. | 12–2 P.M. | 9–11 P.M. |
| November 1845. | 1. | 97°8 | 98°7 | 99° | 54 | 56 | 60 | 15 | 16 | 16 | 78° | 85° | 81° |
| | 2. | 97·8 | 98·6 | 98·8 | 52 | 56 | 66 | 15 | 16 | 16 | 78 | 85 | 81 |
| | 3. | 97·9 | 98·8 | 99 | 52 | 60 | 66 | 15 | 17 | 16 | 79 | 86 | 82 |
| | 4. | 97·8 | 98·9 | 98·9 | 53 | 58 | 62 | 15 | 16 | 16 | 78 | 86 | 81 |
| | 5. | 97·9 | 99·1 | 99·1 | 54 | 56 | 64 | 15 | 16 | 16 | 80 | 85 | 82 |
| | 6. | 98 | 98·7 | 98·6 | 53 | 56 | 60 | 15 | 16 | 15 | 77 | 83 | 80 |
| | 7. | 98 | 98·7 | 98·7 | 54 | 56 | 60 | 15 | 15 | 16 | 78 | 80 | 80 |
| | 8. | 98·1 | 99·4 | 99 | 52 | 58 | 68 | 15 | 16 | 15 | 78 | 84 | 81 |
| | 9. | 98 | 98·6 | 98·5 | 52 | 54 | 56 | 15 | 15 | 15 | 77 | 83 | 80 |
| | 10. | 98·1 | 98·6 | 98·8 | 56 | 56 | 64 | 15 | 15 | 16 | 78 | 86 | 81 |
| | 11. | 98·2 | 98·8 | 98·8 | 56 | 56 | 64 | 14 | 16 | 16 | 79 | 86 | 81 |
| | 12. | 97·8 | 98·2 | 98·5 | 54 | 52 | 62 | 14 | 15 | 16 | 79 | 79 | 78 |
| | 13. | 98·2 | 98·8 | 98·5 | 54 | 56 | 58 | 15 | 16 | 16 | 79 | 83 | 81 |
| | 14. | 98 | 99·2 | 98·6 | 50 | 60 | 54 | 14 | 15 | 15 | 78 | 82 | 80 |
| | 15. | 97·9 | 98·6 | 98·2 | 54 | 54 | 58 | 15 | 15 | 16 | 78 | 81 | 79 |
| | 16. | 98 | 98·5 | 98·4 | 56 | 56 | 60 | 15 | 15 | 15 | 78 | 84 | 78 |
| | 17. | 98 | 98·5 | 98·9 | 52 | 56 | 62 | 15 | 15 | 15 | 78 | 81 | 79 |
| | 18. | 98 | 98·5 | 98·7 | 50 | 54 | 58 | 15 | 16 | 16 | 78 | 82 | 79 |
| | 19. | 98·1 | 98·9 | 98·6 | 54 | 60 | 60 | 15 | 16 | 15 | 77 | 84 | 80 |
| | 20. | 98 | 99 | 98·6 | 54 | 56 | 58 | 15 | 15 | 16 | 77 | 84 | 80 |
| | 21. | 97·9 | 98·3 | 98·9 | 54 | 54 | 60 | 14 | 16 | 16 | 77 | 84 | 80 |
| | 22. | 98 | 99·2 | 98·3 | 54 | 62 | 60 | 14 | 16 | 16 | 79 | 85 | 79 |
| | 23. | 98·5 | 98·8 | 98·5 | 54 | 56 | 60 | 15 | 15 | 16 | 78 | 85 | 77 |
| | 24. | 97·9 | 99 | 99·2 | 50 | 58 | 66 | 14 | 16 | 17 | 77 | 83 | 81 |
| | 25. | 98·4 | 99·1 | 98·6 | 54 | 58 | 58 | 16 | 17 | 16 | 78 | 85 | 78 |
| | 26. | 97·8 | 98·3 | 99 | 52 | 54 | 56 | 15 | 16 | 15 | 77 | 83 | 80 |
| | 27. | 98·5 | 98·6 | 99 | 52 | 54 | 62 | 14 | 16 | 16 | 78 | 83 | 80 |
| | 28. | 98·2 | 99·2 | 98·2 | 56 | 60 | 70 | 15 | 16 | 16 | 78 | 81 | 78 |
| | | 98 | 98·6 | 98·7 | 53·3 | 56·5 | 61 | 14·8 | 15·6 | 16 | 78 | 83·8 | 79·9 |
| December 1845. | 1. | 97·9 | 98·6 | 98·4 | 48 | 54 | 58 | 15 | 15 | 16 | 78 | 80 | 77 |
| | 2. | 97·9 | 98·4 | 98·5 | 52 | 52 | 60 | 14 | 15 | 16 | 77 | 82 | 79 |
| | 3. | 97·8 | 98·9 | 98·8 | 50 | 56 | 56 | 14 | 16 | 16 | 77 | 81 | 77 |
| | 4. | 98·1 | 98·7 | 98·5 | 54 | 56 | 60 | 14 | 16 | 16 | 77 | 79 | 79 |
| | 5. | 97·9 | 98·4 | 98·5 | 52 | 56 | 70 | 15 | 16 | 17 | 77 | 81 | 79 |
| | 6. | 98·1 | 98·7 | 98·4 | 52 | 56 | 60 | 14 | 15 | 16 | 77 | 81 | 79 |
| | 7. | 97·9 | 98·3 | 98·2 | 50 | 52 | 76 | 15 | 16 | 17 | 77 | 82 | 77 |
| | 8. | 98 | 98·5 | ..... | 64 | 60 | ... | 14 | 15 | ... | 75 | 82 | |
| | 9. | 98·4 | 98·5 | 98·9 | 52 | 56 | 56 | 14 | 15 | 16 | 75 | 83 | 77 |
| | 10. | 97·9 | 98·4 | 98·8 | 54 | 52 | 60 | 14 | 15 | 15 | 76 | 82 | 78 |
| | 11. | 97·9 | 98·9 | 98·4 | 56 | 56 | 62 | 14 | 16 | 15 | 75 | 83 | 79 |
| | 12. | 97·8 | ..... | ..... | 56 | ... | ... | 14 | ... | ... | 77 | ... | |
| | 13. | 97·9 | 98·4 | 98·8 | 54 | 54 | 62 | 15 | 15 | 15 | 97 | 81 | 78 |
| | 14. | 98 | 98·5 | 98·6 | 54 | 54 | 56 | 13 | 15 | 16 | 75 | 81 | 78 |
| | 15. | 97·7 | 98·3 | 98·9 | 50 | 54 | 60 | 14 | 15 | 15 | 70 | 80 | 77 |
| | 16. | 98·2 | 98·8 | 98·2 | 50 | 54 | 60 | 15 | 16 | 16 | 76 | 82 | 78 |
| | 17. | 98·4 | 98·8 | 98·6 | 52 | 58 | 66 | 15 | 16 | 16 | 77 | 83 | 78 |
| | 18. | 97·9 | 98·6 | ..... | 50 | 52 | ... | 15 | 15 | ... | 75 | 82 | |
| | 19. | 98·4 | 98·8 | 98·7 | 58 | 52 | 64 | 15 | 16 | 16 | 73 | 80 | 78 |
| | 20. | 97·8 | 98·8 | ..... | 52 | 50 | ... | 15 | 16 | ... | 74 | 82 | |
| | 21. | 98·1 | 98·9 | 98·6 | 66 | 56 | 60 | 16 | 16 | 15 | 73 | 80 | 74 |
| | 22. | 97·6 | 98·6 | 98·5 | 52 | 56 | 60 | 14 | 16 | 16 | 74 | 82 | 77 |
| | 23. | 97·9 | 98·6 | 99 | 60 | 54 | 56 | 14 | 16 | 15 | 73 | 82 | 76 |
| | 24. | 97·8 | 98·6 | 98·6 | 54 | 58 | 56 | 14 | 16 | 15 | 74 | 82 | 78 |
| | 25. | 98·3 | 99·2 | 98·9 | 52 | 60 | 66 | 15 | 16 | 16 | 74 | 81 | 76 |
| | 26. | 98·1 | 98·7 | 99·2 | 52 | 56 | 58 | 14 | 14 | 15 | 74 | 80 | 76 |
| | 27. | 98·2 | 99·3 | 98·4 | 54 | 58 | 60 | 15 | 15 | 16 | 73 | 82 | 75 |
| | 28. | 98·3 | ..... | 98·6 | 56 | ... | 70 | 14 | ... | 15 | 72 | ... | 75 |
| | 29. | 98·1 | 98·4 | 98·5 | 52 | 52 | 58 | 14 | 15 | 16 | 72 | 82 | 78 |
| | 30. | 98·3 | 98·5 | 98·4 | 54 | 58 | 76 | 15 | 16 | 16 | 75 | 82 | 78 |
| | 31. | 98·2 | 98·6 | 98·6 | 60 | 56 | 66 | 15 | 16 | 17 | 76 | 82 | 76 |
| | | 98 | 98·6 | 98·6 | 53·8 | 55·2 | 66 | 14·4 | 15·5 | 15·7 | 75 | 81·3 | 77 |

| | | Temp. under the tongue. | | | Pulse. | | | Respirations. | | | Temperature of room. | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | 6–7 A.M. | 12–2 P.M. | 9–11 P.M. | 6–7 A.M. | 12–2 P.M. | 9–11 P.M. | 6–7 A.M. | 12–2 P.M. | 9–11 P.M. | 6–7 A.M. | 12–2 P.M. | 9–11 P.M. |
| January 1846. | 1. | 98·2 | 98·5 | 99·2 | 54 | 56 | 78 | 15 | 15 | 16 | 72 | 83 | 79 |
| | 2. | 98 | ..... | ..... | 52 | ..... | ..... | 14 | ..... | ..... | 76 | | |
| | 3. | 98·5 | 99 | 98·8 | 56 | 62 | 66 | 15 | 15 | 17 | 74 | 80 | 78 |
| | 4. | 98·1 | 98·8 | 98·8 | 56 | 56 | 62 | 15 | 16 | 16 | 76 | 82 | 77 |
| | 5. | 98·2 | 99·1 | 98·5 | 56 | 60 | 76 | 15 | 16 | 15 | 75 | 83 | 78 |
| | 6. | 98·3 | 98·9 | 98·7 | 54 | 60 | 70 | 15 | 16 | 16 | 72 | 81·5 | 78 |
| | 7. | 98·3 | 99 | 98·7 | 56 | 60 | 62 | 14 | 16 | 15 | 76 | 81 | 78 |
| | 8. | 98·2 | 98·8 | 98·5 | 54 | 56 | 62 | 15 | 16 | 16 | 74 | 82 | 77 |
| | 9. | 98·3 | 99·3 | ..... | 58 | 66 | ..... | 15 | 16 | ..... | 76 | 82 | |
| | 18. | 98·2 | 99·1 | 98·6 | 52 | 60 | 58 | 15 | 16 | 15 | 76 | 84 | 78 |
| | 19. | 98·2 | 98·7 | 98·9 | 54 | 58 | 60 | 14 | 16 | 15 | 76 | 82 | 79 |
| | 20. | 98·2 | 99·1 | 98·7 | 54 | 60 | 60 | 14 | 16 | 16 | 76 | 83 | 79 |
| | 23. | 98·3 | 98·9 | 98·5 | 56 | 60 | 56 | 14 | 15 | 15 | 75 | 83 | 79 |
| | 24. | 98·1 | 98·9 | 99·2 | 56 | 60 | 60 | 15 | 16 | 15 | 76 | 82 | 79 |
| | 25. | 98·1 | 98·7 | 98·9 | 50 | 52 | 52 | 14 | 15 | 15 | 75 | 81 | 78 |
| | 26. | 98·2 | ..... | ..... | 54 | ..... | ..... | 14 | ..... | ..... | 75 | | |
| | 29. | 98·3 | 98·9 | ..... | 52 | 52 | ..... | 14 | 16 | ..... | 72 | 82 | |
| | | 98·2 | 99 | 98·7 | 54·3 | 58·5 | 61·7 | 14·6 | 15·7 | 15·6 | 74·3 | 82 | 78·2 |
| February 1846. | 3. | 98·3 | 99·6 | 98·7 | 54 | 62 | 74 | 15 | 16 | 16 | 72 | 82 | 76 |
| | 4. | 97·9 | 98·8 | ..... | 58 | 54 | ..... | 15 | 15 | ..... | 73 | 78 | |
| | 5. | 98·5 | 99·1 | 98·5 | 60 | 56 | 56 | 14 | 16 | 15 | 74 | 82 | 75 |
| | 6. | 98·3 | 99·3 | 98·5 | 56 | 58 | 58 | 14 | 16 | 15 | 73 | 81 | 76 |
| | 7. | 98·3 | 99·3 | 98·8 | 52 | 56 | 66 | 14 | 16 | 16 | 72 | 82 | 76 |
| | 8. | 98·2 | 99·3 | 98·2 | 52 | 58 | 70 | 14 | 16 | 16 | 72 | 85 | 76 |
| | 9. | 98·3 | 99·2 | 98·9 | 62 | 62 | 64 | 15 | 15 | 16 | 76 | 85 | 78 |
| | 10. | 97·9 | 99 | ..... | 50 | 56 | ..... | 14 | 16 | ..... | 75 | 82 | |
| | 12. | 98 | 98·8 | 98·8 | 52 | 52 | 50 | 14 | 15 | 15 | 72 | 82 | 75 |
| | 13. | 98·2 | 98·6 | 98·6 | 52 | 54 | 62 | 14 | 15 | 15 | 73 | 84 | 75 |
| | 14. | 98·3 | 99·1 | 98·5 | 58 | 56 | 56 | 14 | 16 | 15 | 75 | 84 | 76 |
| | 15. | 97·9 | ..... | 98·8 | 52 | ..... | 60 | 14 | ..... | 15 | 75 | ..... | 81 |
| | 16. | 98 | 99·3 | 99·1 | 52 | 60 | 62 | 14 | 16 | 15 | 75 | 84 | 78 |
| | 17. | 98·1 | 98·8 | 98·4 | 58 | 58 | 60 | 14 | 15 | 15 | 75 | 83 | 76 |
| | 18. | 98·1 | 99 | 98·5 | 56 | 56 | 56 | 15 | 16 | 15 | 75 | 83 | 78 |
| | 19. | 98 | 99·1 | 98·6 | 52 | 56 | 60 | 15 | 16 | 15 | 75 | 83 | 78 |
| | 20. | 98 | 99·3 | 98·4 | 56 | 60 | 66 | 14 | 15 | 16 | 75 | 85 | 79 |
| | 21. | 98·3 | 99·3 | 98·8 | 56 | 58 | 70 | 14 | 16 | 16 | 76 | 83 | 78 |
| | 22. | 98 | 98·8 | 99·1 | 58 | 56 | 62 | 15 | 15 | 15 | 75 | 85 | 80 |
| | 23. | 98·4 | 99·2 | 98·8 | 56 | 58 | 56 | 14 | 16 | 14 | 77 | 85 | 78 |
| | | 98·1 | 99·1 | 98·6 | 55·1 | 57·1 | 59·9 | 14·3 | 15·5 | 15·2 | 74 | 83 | 76·6 |

| | | Temp. under the tongue. | | | Pulse. | | | Respirations. | | | Temperature of room. | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | 6–7 A.M. | 12–2 P.M. | 9–11 P.M. | 6–7 A.M. | 12–2 P.M. | 9–11 P.M. | 6–7 A.M. | 12–2 P.M. | 9–11 P.M. | 6–7 A.M. | 12–2 P.M. | 9–11 P.M. |
| April 1846. | 9. | 97·8 | 98·3 | 98·5 | 52 | 54 | 56 | 14 | 15 | 15 | 74 | 79 | 77 |
| | 10. | 98·2 | 98·5 | 98·6 | 56 | 56 | 52 | 15 | 14 | 15 | 77 | 83 | 78 |
| | 11. | 98·2 | 98·8 | ..... | 56 | 58 | ..... | 14 | 16 | ..... | 77 | 84 | |
| | 12. | 98·4 | 99 | 98·6 | 56 | 54 | 64 | 14 | 16 | 16 | 77 | 85 | 80 |
| | 13. | 98·1 | 99·2 | 99 | 54 | 56 | 72 | 15 | 16 | 16 | 78 | 84 | 77 |
| | 14. | 98·1 | 99·3 | 98·2 | 52 | 58 | 70 | 14 | 16 | 16 | 76 | 83 | 79 |
| | 15. | 98·3 | 98·7 | 98·5 | 54 | 52 | 62 | 14 | 15 | 15 | 77 | 84 | 79 |
| | 16. | 97·9 | 98·8 | 98·7 | 56 | 52 | 64 | 14 | 15 | 16 | 77 | 85 | 79 |
| | 17. | 98·1 | 98·6 | 98·4 | 54 | 52 | 60 | 14 | 15 | 15 | 77 | 84 | 79 |
| | 18. | 98·1 | 99·3 | 98·5 | 52 | 56 | 58 | 14 | 16 | 15 | 77 | 84 | 80 |
| | 19. | 98·2 | 98·6 | 98·3 | 56 | 54 | 56 | 14 | 16 | 16 | 77 | 82 | 79 |
| | 20. | 98·2 | 98·6 | 98·5 | 50 | 52 | 52 | 15 | 15 | 15 | 77 | 83 | 79 |
| | 21. | 98·3 | 98·9 | 98·8 | 52 | 54 | 58 | 15 | 16 | 15 | 76 | 84 | 79 |
| | 22. | 98·3 | 98·9 | 98·6 | 56 | 56 | 54 | 15 | 15 | 14 | 75 | 83 | 79 |
| | 23. | 98·3 | 99·3 | ..... | 52 | 56 | ..... | 14 | 15 | ..... | 77 | 85 | |
| | 24. | 99·3 | 99·1 | 98·6 | 60 | 54 | 60 | 16 | 16 | 16 | 77 | 86 | 80 |
| | 25. | 98·1 | 99 | 98·8 | 52 | 56 | 62 | 14 | 16 | 16 | 78 | 85 | 81 |
| | 26. | 98·3 | 99·1 | 98·8 | 54 | 54 | 56 | 14 | 17 | 16 | 77 | 85 | 82 |
| | 27. | 98·2 | 99·1 | 99 | 52 | 56 | 58 | 14 | 17 | 15 | 79 | 85 | 81 |
| | 28. | 98·2 | 98·8 | ..... | 54 | 56 | ..... | 15 | 16 | ..... | 78 | 86 | |
| | 29. | ..... | 98·9 | 98·7 | ..... | 50 | 54 | ..... | 16 | 15 | ..... | 85 | 80 |
| | 30. | 98·1 | 98·6 | 98·6 | 54 | 50 | 62 | 15 | 15 | 16 | 77 | 82 | 79 |
| | | 98·1 | 98·7 | 98·6 | 54 | 54·5 | 59·5 | 14·4 | 15·6 | 15·4 | 77 | 84 | 79 |
| May 1846. | 1. | 98·1 | 98·5 | 99 | 54 | 54 | 62 | 15 | 16 | 16 | 77 | 82 | 79 |
| | 2. | 98·1 | 99·1 | 99 | 54 | 56 | 66 | 14 | 16 | 15 | 76 | 85 | 78 |
| | 3. | 98·4 | 98·9 | 99·2 | 54 | 56 | 64 | 15 | 16 | 15 | 77 | 85 | 80 |
| | 4. | 98·1 | 99 | 99 | 52 | 56 | 62 | 15 | 16 | 16 | 76 | 85 | 81 |
| | 5. | 98·2 | 99 | 98·8 | 56 | 54 | 66 | 15 | 16 | 16 | 77 | 84 | 81 |
| | 6. | 98·1 | 98·9 | ..... | 52 | 54 | ..... | 15 | 15 | ..... | 77 | 86 | |
| | 7. | 98·3 | 99 | 98·5 | 60 | 56 | 72 | 16 | 16 | 16 | 79 | 86 | 81 |
| | 8. | 98·2 | 98·8 | 98·7 | 56 | 56 | 58 | 15 | 16 | 16 | 78 | 86 | 80 |
| | 9. | 98·2 | 98·8 | ..... | 56 | 56 | ..... | 15 | 16 | ..... | 79 | 86 | |
| | 10. | 98·1 | 99·1 | 99·3 | 54 | 56 | 60 | 15 | 16 | 16 | 79 | 86 | 81 |
| | 11. | 98·1 | 98·9 | 99·1 | 56 | 56 | 64 | 15 | 17 | 16 | 78 | 86 | 81 |
| | 12. | 98·4 | 99·1 | 98·7 | 54 | 56 | 58 | 15 | 16 | 16 | 79 | 86 | 82 |
| | 13. | 98·1 | 98·5 | 98·4 | 54 | 48 | 54 | 15 | 16 | 15 | 78 | 84 | 81 |
| | 14. | 98·6 | 99·1 | 98·9 | 54 | 60 | 60 | 15 | 16 | 16 | 78 | 86 | 81 |
| | 15. | 98·3 | 98·9 | 98·4 | 52 | 54 | 80 | 14 | 15 | 16 | 78 | 86 | 81 |
| | 16. | 98·1 | 99·1 | 98 | 56 | 58 | 60 | 16 | 16 | 16 | 79 | 87 | 82 |
| | 17. | 98·3 | 98·9 | 98·1 | 62 | 54 | 72 | 14 | 17 | 16 | 80 | 88 | 81 |
| | 18. | 98 | 99·2 | 98·6 | 70 | 56 | 56 | 14 | 16 | 16 | 77 | 88 | 82 |
| | 19. | 98·1 | 98·7 | 98·9 | 54 | 54 | 60 | 15 | 16 | 16 | 80 | 87 | 82 |
| | 20. | 98·1 | ..... | ..... | 56 | ..... | ..... | 14 | ..... | ..... | 79 | | |
| | 21. | 98·2 | 99 | 98·4 | 54 | 58 | 54 | 15 | 16 | 15 | 80 | 87 | 81 |
| | 22. | 98·4 | 98·7 | 98·8 | 54 | 50 | 58 | 15 | 16 | 16 | 79 | 88 | 77 |
| | 23. | 98·4 | 99·1 | 98·7 | 60 | 56 | 70 | 15 | 16 | 16 | 81 | 87 | 82 |
| | 24. | 98·2 | 99 | 98·5 | 58 | 56 | 56 | 15 | 16 | 15 | 79 | 88 | 82 |
| | 25. | 98·2 | 99·1 | ..... | 56 | 56 | ..... | 14 | 16 | ..... | 79 | 88 | |
| | 26. | 98·3 | 98·6 | 98·5 | 60 | 52 | 58 | 15 | 15 | 15 | 79 | 79 | 81 |
| | 27. | 98·4 | 99·1 | 98·7 | 56 | 56 | 56 | 14 | 14 | 15 | 80 | 82 | 82 |
| | 28. | 98·3 | 99 | 99 | 56 | 56 | 60 | 15 | 16 | 14 | 81 | 86 | 84 |
| | 29. | 98·4 | 99·4 | 98·8 | 60 | 60 | 60 | 15 | 16 | 16 | 82 | 88 | 83 |
| | 30. | 98·5 | 99·3 | 99·3 | 56 | 56 | 62 | 15 | 16 | 16 | 80 | 87 | 83 |
| | 31. | 98·2 | 99 | 99 | 54 | 52 | 58 | 15 | 15 | 16 | 80 | 85 | 76 |
| | | 98·2 | 98·9 | 98·8 | 56·1 | 55·2 | 62 | 15 | 15·8 | 15·6 | 78·7 | 85·8 | 80 |

| | | Temp. under the tongue. | | | Pulse. | | | Respirations. | | | Temperature of room. | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | 6–7 A.M. | 12–2 P.M. | 9–11 P.M. | 6–7 A.M. | 12–2 P.M. | 9–11 P.M. | 6–7 A.M. | 12–2 P.M. | 9–11 P.M. | 6–7 A.M. | 12–2 P.M. | 9–11 P.M. |
| | | ° | ° | ° | | | | | | | ° | ° | ° |
| June 1846. | 1. | 98·3 | 99·5 | 99·2 | 52 | 56 | 62 | 14 | 16 | 16 | 79 | 87 | 83 |
| | 3. | 99·4 | 99·4 | 98·9 | 58 | 58 | 56 | 15 | 15 | 15 | 80 | 88 | 83 |
| | 4. | 98·2 | 99·5 | 98·7 | 58 | 68 | 64 | 15 | 17 | 16 | 82 | 88 | 82 |
| | 7. | 98·2 | 98·7 | 98·9 | 60 | 54 | 70 | 15 | 15 | 16 | 78 | 82 | 82 |
| | 8. | 98·4 | 99·1 | 98·7 | 54 | 58 | 60 | 15 | 15 | 16 | 79 | 86 | 81 |
| | 9. | 98·4 | 99 | 98·8 | 54 | 54 | 60 | 15 | 16 | 15 | 79 | 86 | 81 |
| | 10. | 98·3 | 98·9 | 98·7 | 50 | 56 | 58 | 14 | 16 | 16 | 79 | 84 | 79 |
| | 11. | 98·2 | ..... | ..... | 56 | ..... | ..... | 15 | ..... | ..... | 78 | | |
| | 12. | 98·5 | 99 | 98·6 | 58 | 54 | 90 | 16 | 14 | 17 | 79 | 86 | 82 |
| | 13. | 98·4 | 98·9 | 98·7 | 66 | 56 | 60 | 14 | 16 | 15 | 80 | 85 | 82 |
| | 14. | 98·4 | 98·5 | ..... | 58 | 52 | ..... | 15 | 15 | ..... | 80 | 87 | |
| | 15. | 98 | 98·7 | 98·9 | 52 | 50 | 59 | 14 | 16 | 16 | 80 | 85 | 82 |
| | 16. | 98·2 | 99·1 | 98·7 | 52 | 56 | 56 | 14 | 16 | 16 | 79 | 82 | 80 |
| | 17. | 98·4 | 99 | 98·7 | 58 | 58 | 56 | 15 | 16 | 14 | 79 | 85 | 81 |
| | 18. | 98·1 | 98·7 | ..... | 52 | 52 | ..... | 15 | 16 | ..... | 77 | 81 | |
| | 20. | 98·1 | ..... | ..... | 56 | ..... | ..... | 15 | ..... | ..... | 79 | | |
| | 23. | 98·3 | 98·6 | 98·9 | 50 | 54 | 58 | 14 | 16 | 15 | 79 | 82 | 79 |
| | 24. | 98·1 | 98·8 | 98·8 | 58 | 54 | 56 | 15 | 16 | 15 | 79 | 85 | 82 |
| | 25. | 98·1 | 99·1 | ..... | 56 | 56 | ..... | 15 | 16 | ..... | 79 | 85 | |
| | 26. | 98·3 | 98·5 | 98·8 | 54 | 54 | 54 | 15 | 16 | 16 | 79 | 84 | 81 |
| | 27. | 98·2 | 98·9 | 98·8 | 54 | 56 | 52 | 14 | 16 | 14 | 79 | 86 | 78 |
| | 28. | 98 | 98·7 | 98·5 | 52 | 52 | 52 | 14 | 15 | 15 | 79 | 85 | 81 |
| | 29. | 98·1 | 99·2 | 98·7 | 52 | 54 | 62 | 14 | 16 | 15 | 79 | 83 | 80 |
| | 30. | 97·9 | 99·1 | ..... | 54 | 62 | ..... | 14 | 15 | ..... | 77 | 86 | |
| | | 98·2 | 99 | 98·8 | 55·1 | 55·6 | 59·7 | 14·6 | 15·7 | 15·4 | 79 | 84·7 | 81 |
| July 1846. | 2. | 98·3 | 99 | 99·3 | 62 | 56 | 62 | 15 | 16 | 16 | 79 | 84 | 81 |
| | 3. | 98·3 | 98·9 | ..... | 54 | 54 | ..... | 15 | 15 | ..... | 79 | 86 | |
| | 4. | 98·1 | 98·9 | 98·5 | 54 | 52 | 75 | 14 | 16 | 16 | 79 | 86 | 82 |
| | 5. | 98·3 | 98·6 | ..... | 52 | 54 | ..... | 15 | 16 | ..... | 79 | 86 | |
| | 6. | 98·5 | 99 | 98·8 | 60 | 56 | 56 | 16 | 16 | 16 | 79 | 86 | 82 |
| | 7. | 98 | 98·6 | 98·4 | 52 | 56 | 80 | 15 | 17 | 16 | 79 | 85 | 80 |
| | 8. | 98·3 | 98·8 | 98·6 | 60 | 50 | 52 | 15 | 15 | 15 | 78 | 83 | 81 |
| | 9. | 98·2 | 98·9 | 99 | 54 | 56 | 60 | 14 | 16 | 15 | 79 | 86 | 81 |
| | 10. | 98 | 98·6 | 98·8 | 54 | 54 | 54 | 14 | 17 | 16 | 79 | 86 | 81 |
| | 11. | 98 | ..... | ..... | 56 | ..... | ..... | 14 | ..... | ..... | 80 | | |
| | 12. | 98·4 | 99 | 99·3 | 54 | 54 | 60 | 16 | 15 | 15 | 78 | 85 | 82 |
| | 13. | 98·2 | 99 | 99 | 52 | 56 | 60 | 15 | 15 | 16 | 79 | 86 | 81 |
| | 14. | 97·7 | 98·7 | 98·9 | 54 | 54 | 56 | 15 | 16 | 15 | 79 | 86 | 80 |
| | 15. | 98·4 | 99 | 98·9 | 56 | 56 | 80 | 14 | 17 | 15 | 80 | 86 | 82 |
| | 16. | 98·4 | 98·9 | 98·9 | 56 | 56 | 58 | 15 | 16 | 16 | 79 | 82 | 82 |
| | 17. | 98·1 | 98·8 | 99·1 | 50 | 56 | 56 | 14 | 15 | 16 | 76 | 84 | 81 |
| | 18. | 98·1 | 98·6 | 99 | 52 | 56 | 58 | 15 | 16 | 16 | 79 | 86 | 82 |
| | 19. | 98·1 | ..... | 99 | 52 | ..... | 58 | 14 | ..... | 16 | 79 | ..... | 82 |
| | 20. | 98·3 | 99·1 | 99·3 | 52 | 58 | 56 | 15 | 17 | 15 | 78 | 86 | 82 |
| | 21. | 98 | 98·8 | ..... | 54 | 56 | ..... | 14 | 17 | ..... | 79 | 85 | |
| | 23. | 98·3 | 98·8 | 99 | 56 | 56 | 58 | 15 | 15 | 17 | 79 | 84 | 81 |
| | 24. | 98·3 | 98·8 | 99·1 | 54 | 50 | 64 | 15 | 16 | 15 | 78 | 83 | 82 |
| | 25. | 98·2 | 98·6 | 99 | 54 | 52 | 56 | 15 | 17 | 16 | 79 | 83 | 81 |
| | 26. | 98·2 | 98·8 | 98·8 | 50 | 50 | 58 | 15 | 15 | 15 | 79 | 85 | 81 |
| | 27. | 98·1 | 99 | 98·9 | 54 | 54 | 56 | 15 | 17 | 15 | 79 | 84 | 82 |
| | 28. | 98·2 | 99·2 | 98·7 | 52 | 58 | 68 | 14 | 16 | 15 | 78 | 84 | 81 |
| | 29. | 98·4 | 98·9 | ..... | 54 | 52 | ..... | 14 | 16 | ..... | 79 | 84 | |
| | | 98·2 | 99 | 98·9 | 54·5 | 54·5 | 60·7 | 14·7 | 16 | 15·3 | 78·8 | 84·8 | 81·4 |

| | | Temp. under the tongue. | | | Pulse. | | | Respirations. | | | Temperature of room. | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | 6–7 A.M. | 12–2 P.M. | 9–11 P.M. | 6–7 A.M. | 12–2 P.M. | 9–11 P.M. | 6–7 A.M. | 12–2 P.M. | 9–11 P.M. | 6–7 A.M. | 12–2 P.M. | 9–11 P.M. |
| August 1846. | 1. | 98·2 | 98·8 | 98·5 | 56 | 54 | 70 | 15 | 16 | 17 | 78 | 86 | 82 |
| | 2. | 98·1 | 98·7 | 99·2 | 54 | 54 | 62 | 15 | 15 | 16 | 79 | 87 | 81 |
| | 3. | 98·2 | 99·1 | 99·2 | 52 | 58 | 60 | 14 | 17 | 16 | 79 | 86 | 82 |
| | 4. | 98·1 | 98·9 | 98·9 | 54 | 56 | 64 | 15 | 16 | 16 | 79 | 86 | 82 |
| | 5. | 98·2 | 99·2 | 98·9 | 52 | 54 | 60 | 15 | 16 | 15 | 79 | 83 | 79 |
| | 6. | 98·2 | 99 | 99·1 | 54 | 56 | 70 | 15 | 16 | 16 | 75 | 84 | 81 |
| | 7. | 97·9 | 99·1 | 99 | 52 | 60 | 60 | 15 | 16 | 15 | 77 | 86 | 82 |
| | 8. | 98·3 | 98·7 | 98·7 | 58 | 56 | 60 | 15 | 16 | 16 | 79 | 83 | 80 |
| | 9. | 98·1 | 98·6 | 98·8 | 54 | 54 | 56 | 15 | 15 | 16 | 79 | 85 | 81 |
| | 10. | 98·2 | 98·9 | 98·9 | 54 | 54 | 60 | 15 | 16 | 15 | 79 | 87 | 83 |
| | 11. | 98·2 | 98·4 | 99 | 54 | 54 | 62 | 14 | 14 | 16 | 78 | 83 | 81 |
| | 12. | 98·3 | 99·2 | 98·9 | 56 | 60 | 64 | 15 | 16 | 16 | 80 | 86 | 82 |
| | 13. | 98·5 | 99·1 | 98·8 | 56 | 54 | 60 | 15 | 15 | 16 | 79 | 84 | 81 |
| | 14. | 98·1 | 98·9 | 99·2 | 54 | 58 | 64 | 15 | 17 | 16 | 79 | 86 | 82 |
| | 15. | 98·4 | 99 | 98·7 | 54 | 58 | 54 | 15 | 16 | 15 | 80 | 87 | 82 |
| | 16. | 98·3 | ..... | 98·8 | 54 | ..... | 56 | 15 | ..... | 16 | 80 | ..... | 83 |
| | 17. | 98·3 | 98·9 | 98·9 | 54 | 56 | 54 | 14 | 16 | 16 | 79 | 85 | 79 |
| | 18. | 98 | 98·8 | 98·9 | 54 | 52 | 64 | 15 | 16 | 16 | 77 | 86 | 83 |
| | 19. | 98·4 | 99·2 | 99 | 56 | 56 | 60 | 14 | 16 | 16 | 80 | 86 | 82 |
| | 20. | 98·3 | 98·9 | ..... | 54 | 52 | ..... | 15 | 16 | ..... | 79 | 86 | |
| | 21. | 98·4 | 99·3 | 99·1 | 62 | 60 | 62 | 16 | 17 | 16 | 80 | 88 | 83 |
| | 22. | 98·2 | 99 | 99·3 | 54 | 54 | 60 | 14 | 16 | 16 | 79 | 86 | 81 |
| | 23. | 98·2 | 98·8 | 98·8 | 54 | 54 | 60 | 14 | 17 | 16 | 79 | 87 | 78 |
| | 24. | 98·2 | 99·1 | 99·2 | 54 | 54 | 54 | 14 | 16 | 16 | 79 | 87 | 82 |
| | 25. | 98·2 | 99·4 | 98·8 | 52 | 54 | 60 | 14 | 16 | 16 | 78 | 82 | 80 |
| | 26. | 98·3 | 98·9 | 99 | 54 | 54 | 62 | 14 | 15 | 15 | 78 | 84 | 83 |
| | 27. | 98·2 | 98·7 | 98·8 | 54 | 58 | 60 | 14 | 16 | 16 | 78 | 82 | 78 |
| | 28. | 98·3 | 99 | 98·5 | 54 | 54 | 54 | 15 | 16 | 16 | 78 | 86 | 82 |
| | 29. | 98·3 | 98·9 | 98·9 | 54 | 56 | 60 | 14 | 15 | 15 | 79 | 84 | 81 |
| | 30. | 98·2 | ..... | ..... | 56 | ..... | ..... | 15 | ..... | ..... | 79 | | |
| | 31. | 98 | 99·1 | 99 | 58 | 58 | 64 | 15 | 16 | 16 | 79 | 86 | 82 |
| | | 98·1 | 99 | 98·9 | 54·2 | 55·6 | 60·5 | 14·6 | 15·9 | 15·6 | 78·7 | 85·5 | 81·7 |
| September 1846. | 1. | 98·2 | 99 | 98·8 | 56 | 58 | 56 | 14 | 17 | 16 | 79 | 86 | 79 |
| | 2. | 98·2 | 98·8 | 99 | 54 | 56 | 56 | 14 | 16 | 16 | 79 | 85 | 83 |
| | 3. | 98·2 | 99·1 | ..... | 54 | 54 | ..... | 15 | 16 | ..... | 78 | 85 | |
| | 4. | 98 | 99·2 | 99·2 | 52 | 56 | 62 | 15 | 16 | 16 | 78 | 85 | 84 |
| | 5. | 98·2 | 98·9 | 98·9 | 54 | 54 | 78 | 15 | 17 | 17 | 80 | 87 | 83 |
| | 6. | 98·1 | 98·9 | 98·8 | 56 | 56 | 60 | 15 | 15 | 15 | 80 | 87 | 79 |
| | 7. | 98·1 | 98·9 | 98·4 | 54 | 52 | 54 | 15 | 15 | 16 | 80 | 84 | 79 |
| | 8. | 97·7 | 98·8 | 99·2 | 52 | 54 | 60 | 15 | 15 | 16 | 78 | 86 | 83 |
| | 9. | 98·4 | 98·9 | 98·7 | 56 | 56 | 62 | 15 | 15 | 15 | 79 | 86 | 82 |
| | 10. | 98 | 99 | 98·9 | 54 | 56 | 54 | 14 | 15 | 15 | 80 | 87 | 83 |
| | 11. | 98·3 | 99·1 | 98·8 | 54 | 60 | 62 | 15 | 16 | 16 | 81 | 83 | 81 |
| | 12. | 98·2 | 98·6 | 99·1 | 56 | 52 | 58 | 14 | 14 | 14 | 80 | 82 | 81 |
| | 13. | 98·2 | 98·7 | 98·5 | 54 | 50 | 56 | 15 | 15 | 16 | 78 | 86 | 82 |
| | 14. | 98·3 | 99·1 | 98·1 | 56 | 54 | 64 | 15 | 16 | 16 | 78 | 86 | 81 |
| | 15. | 98·5 | 98·8 | 98·9 | 52 | 56 | 56 | 15 | 16 | 16 | 79 | 85 | 82 |
| | 16. | 97·9 | ..... | 98·5 | 56 | ..... | 60 | 15 | ..... | 16 | 78 | ..... | 80 |
| | 17. | 98·2 | 99·3 | 98·6 | 58 | 60 | 60 | 15 | 16 | 16 | 79 | 85 | 80 |
| | 18. | 98·2 | 99·1 | 98·9 | 54 | 56 | 60 | 15 | 16 | 16 | 78 | 84 | 81 |
| | 19. | 98·2 | 99 | 99·2 | 54 | 52 | 58 | 14 | 15 | 15 | 79 | 86 | 82 |
| | 20. | 98·3 | 99·2 | 98·7 | 52 | 58 | 56 | 14 | 15 | 15 | 77 | 86 | 80 |
| | 21. | 98·3 | 99·2 | 99 | 58 | 60 | 60 | 15 | 16 | 15 | 79 | 86 | 78 |
| | 22. | 98·2 | 98·9 | 98·8 | 56 | 56 | 56 | 15 | 16 | 16 | 79 | 85 | 79 |
| | 23. | 98·6 | 99 | 99 | 54 | 52 | 80 | 14 | 15 | 17 | 79 | 85 | 81 |
| | 24. | 98·5 | 99·4 | 99·2 | 62 | 58 | 60 | 15 | 15 | 16 | 78 | 86 | 82 |
| | 25. | 98·3 | 99·1 | 98·7 | 60 | 62 | 60 | 15 | 16 | 15 | 80 | 82 | 79 |
| | 26. | 98·1 | 99·2 | 98·5 | 56 | 56 | 80 | 14 | 16 | 16 | 77 | 84 | 79 |
| | 27. | 98·5 | 99·1 | 99 | 62 | 54 | 62 | 15 | 16 | 16 | 78 | 85 | 82 |
| | 28. | 98·2 | 99 | 99·1 | 54 | 56 | 62 | 14 | 15 | 15 | 79 | 85 | 81 |
| | 29. | 98 | 99·1 | 98·7 | 52 | 56 | 56 | 15 | 15 | 16 | 77 | 85 | 80 |
| | 30. | 98·2 | 98·7 | 98·7 | 54 | 58 | 56 | 15 | 16 | 16 | 77 | 85 | 81 |
| | | 98 | 99 | 98·8 | 55 | 54 | 60·8 | 14·3 | 15·9 | 16 | 78·7 | 85·1 | 81·3 |

| | | Temp. under the tongue. | | | Pulse. | | | Respirations. | | | Temperature of room. | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | 6–7 A.M. | 12–2 P.M. | 9–11 P.M. | 6–7 A.M. | 12–2 P.M. | 9–11 P.M. | 6–7 A.M. | 12–2 P.M. | 9–11 P.M. | 6–7 A.M. | 12–2 P.M. | 9–11 P.M. |
| | | ° | ° | ° | | | | | | | ° | ° | ° |
| October 1846. | 1. | 98·1 | ..... | ..... | 52 | ..... | ..... | 15 | ..... | ..... | 79 | | |
| | 2. | 98·4 | 98·8 | 98·7 | 54 | 54 | 54 | 15 | 16 | 15 | 78 | 82 | 80 |
| | 4. | 97·9 | 98·5 | 58 | 52 | 54 | 15 | 15 | 15 | 15 | 77 | 83 | 79 |
| | 5. | 98·3 | 99·1 | 99 | 56 | 56 | 64 | 15 | 15 | 16 | 77 | 85 | 80 |
| | 6. | 98·1 | 98·7 | ..... | 52 | 54 | ..... | 14 | 15 | ..... | 78 | 86 | |
| | 7. | 98·5 | 99·1 | 98·9 | 62 | 58 | 60 | 15 | 16 | 16 | 79 | 84 | 80 |
| | 8. | 98·4 | 99·3 | 99 | 52 | 56 | 74 | 15 | 16 | 16 | 78 | 85 | 81 |
| | 9. | 98·3 | 99·2 | 99·3 | 52 | 56 | 62 | 15 | 16 | 15 | 78 | 86 | 82 |
| | 10. | 97·9 | 98·9 | 98·8 | 54 | 56 | 72 | 15 | 15 | 16 | 78 | 86 | 79 |
| | 11. | 98·2 | ..... | ..... | 56 | ..... | ..... | 15 | ..... | ..... | 78 | | |
| | 13. | 98·2 | 99 | 99·4 | 50 | 56 | 64 | 14 | 16 | 15 | 79 | 86 | 82 |
| | 14. | 98·3 | 98·7 | ..... | 50 | 56 | ..... | 14 | 15 | ..... | 78 | 87 | |
| | 15. | 98·4 | 98·9 | 98·9 | 60 | 54 | 62 | 14 | 16 | 16 | 80 | 86 | 81 |
| | 16. | 98·5 | 98·7 | 99 | 52 | 56 | 62 | 14 | 15 | 16 | 80 | 85 | 81 |
| | 17. | 98·1 | 99 | 98·7 | 50 | 52 | 56 | 14 | 16 | 15 | 78 | 86 | 81 |
| | 18. | 98·2 | 98·9 | 99 | 50 | 56 | 56 | 14 | 14 | 15 | 77 | 86 | 80 |
| | 19. | 98 | 98·9 | 99·1 | 52 | 54 | 60 | 14 | 15 | 15 | 76 | 86 | 80 |
| | 20. | 98·3 | 99·1 | ..... | 52 | 56 | ..... | 14 | 16 | ..... | 78 | 86 | |
| | 21. | 98·2 | 98·9 | 99·2 | 60 | 52 | 60 | 16 | 15 | 16 | 79 | 88 | 83 |
| | 22. | 98 | 98·8 | 98·8 | 52 | 50 | 60 | 14 | 16 | 15 | 80 | 87 | 82 |
| | 23. | 98·1 | 99 | 98·8 | 50 | 56 | 56 | 14 | 16 | 16 | 78 | 87 | 81 |
| | 24. | 98·3 | 99 | 98·4 | 54 | 60 | 64 | 15 | 15 | 17 | 79 | 83 | 80 |
| | 25. | 98·2 | 98·8 | 99 | 52 | 54 | 60 | 14 | 16 | 15 | 80 | 83 | 82 |
| | 26. | 98·2 | 98·9 | ..... | 54 | 52 | ..... | 14 | 15 | ..... | 78 | 84 | |
| | 27. | 98·2 | 98·7 | 99·2 | 54 | 54 | 62 | 14 | 15 | 17 | 78 | 85 | 81 |
| | 28. | 97·8 | 98·8 | 98·9 | 52 | 54 | 56 | 14 | 15 | 16 | 77 | 85 | 82 |
| | 29. | 98·2 | ..... | 98·6 | 54 | ..... | 70 | 14 | ..... | 15 | 79 | ..... | 81 |
| | 30. | 98·3 | 98·6 | ..... | 60 | 58 | ..... | 14 | 16 | ..... | 79 | 85 | |
| | 31. | 98·1 | 99·4 | 98·7 | 60 | 62 | 56 | 15 | 16 | 16 | 76 | 82 | 78 |
| | | 98·2 | 99 | 99 | 52 | 55 | 61 | 14·4 | 15·4 | 15·3 | 78·2 | 85·1 | 81·2 |
| November 1846. | 1. | 98·2 | 99·2 | 98·6 | 56 | 58 | 58 | 15 | 16 | 16 | 75 | 84 | 79 |
| | 2. | 98·1 | 99·2 | 98·7 | 54 | 58 | 56 | 14 | 16 | 15 | 77 | 85 | 81 |
| | 3. | 98 | 98·7 | 98·8 | 54 | 52 | 58 | 14 | 14 | 16 | 77 | 85 | 81 |
| | 4. | 98·3 | 99·1 | ..... | 54 | 54 | ..... | 15 | 16 | ..... | 78 | 85 | |
| | 5. | 98 | 99·3 | 99·1 | 54 | 56 | 60 | 15 | 16 | 15 | 79 | 85 | 80 |
| | 6. | 98 | 98·7 | ..... | 54 | 52 | ..... | 14 | 15 | ..... | 78 | 86 | |
| | 7. | 97·9 | 99·1 | 98·8 | 56 | 50 | 52 | 14 | 16 | 15 | 75 | 82 | 78 |
| | 8. | 98 | 98·5 | 98·9 | 52 | 52 | 54 | 14 | 15 | 15 | 77 | 83 | 80 |
| | 9. | 98·2 | 98·8 | 99·1 | 56 | 56 | 60 | 15 | 16 | 15 | 78 | 86 | 81 |
| | 10. | 98 | 99·2 | 99·2 | 56 | 60 | 62 | 15 | 16 | 16 | 78 | 87 | 82 |
| | 11. | 98·1 | 99·2 | 99 | 56 | 60 | 60 | 15 | 16 | 16 | 79 | 87 | 82 |
| | 12. | 98 | ..... | ..... | 52 | ..... | ..... | 14 | ..... | ..... | 78 | | |
| | 13. | 98·3 | 99·1 | 99·4 | 52 | 54 | 64 | 15 | 16 | 16 | 79 | 87 | 82 |
| | 14. | 98·3 | 98·9 | ..... | 56 | 56 | ..... | 15 | 17 | ..... | 78 | 87 | |
| | 15. | 98·5 | 99·1 | 98·9 | 66 | 58 | 60 | 15 | 15 | 16 | 78 | 86 | 82 |
| | 16. | 98·3 | 99 | 98·8 | 56 | 56 | 60 | 14 | 16 | 16 | 79 | 87 | 80 |
| | 17. | 98·2 | 98·2 | 98·6 | 56 | 52 | 56 | 15 | 15 | 15 | 79 | 78 | 79 |
| | 18. | 98·4 | ..... | ..... | 56 | ..... | ..... | ..... | 14 | | | | |
| | 19. | 98·1 | 99 | 99 | 58 | 60 | 66 | 15 | 16 | 16 | 79 | 79 | 80 |
| | 20. | 97·9 | ..... | 98·8 | 66 | ..... | 62 | 16 | ..... | 16 | 79 | ..... | 81 |
| | 21. | 98 | 98·7 | ..... | 56 | 54 | ..... | 14 | 16 | ..... | 78 | 85 | |
| | 22. | 98·4 | 98·7 | 99·1 | 58 | 58 | 58 | 14 | 16 | 15 | 78 | 85 | 81 |
| | 23. | 98·2 | 98·7 | 98·9 | 56 | 56 | 62 | 15 | 16 | 16 | 77 | 84 | 81 |
| | 24. | 98·2 | 98·9 | 98·8 | 56 | 56 | 58 | 15 | 16 | 16 | 78 | 85 | 80 |
| | 25. | 98 | 98·8 | 99 | 56 | 54 | 60 | 15 | 15 | 15 | 76 | 83 | 78 |
| | 26. | 97·9 | 99·1 | 98·4 | 56 | 60 | 70 | 15 | 17 | 16 | 76 | 83 | 79 |
| | 27. | 98·3 | 98·8 | 98·7 | 56 | 56 | 58 | 15 | 17 | 16 | 78 | 84 | 81 |
| | 28. | 98·1 | 98·6 | 99·2 | 54 | 54 | 62 | 14 | 15 | 16 | 75 | 84 | 80 |
| | 29. | 98·1 | 98·9 | 98·8 | 54 | 54 | 64 | 15 | 16 | 16 | 77 | 83 | 80 |
| | 30. | 98·3 | ..... | 98·8 | 54 | ..... | 62 | 15 | ..... | 16 | 76 | ..... | 80 |
| | | 98·1 | 98·9 | 98·8 | 56·2 | 55·4 | 60·1 | 14·6 | 15·8 | 15·6 | 77·4 | 84·4 | 80 |

| | | Temp. under the tongue. | | | Pulse. | | | Respirations. | | | Temperature of room. | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | 6–7 A.M. | 12–2 P.M. | 9–11 P.M. | 6–7 A.M. | 12–2 P.M. | 9–11 P.M. | 6–7 A.M. | 12–2 P.M. | 9–11 P.M. | 6–7 A.M. | 12–2 P.M. | 9–11 P.M. |
| December 1846. | 1. | 98°3 | 98°9 | 98°6 | 54 | 54 | 62 | 15 | 16 | 16 | 78° | 79° | 78° |
| | 2. | 98·3 | 99·2 | ..... | 56 | 64 | ..... | 15 | 16 | ..... | 78 | 77 | |
| | 3. | 98 | 98·8 | 98·9 | 54 | 54 | 68 | 15 | 15 | 16 | 75 | 79 | 79 |
| | 4. | 97·9 | 98·5 | ..... | 54 | 52 | ..... | 15 | 15 | ..... | 77 | 77 | |
| | 5. | 98·3 | 98·7 | 98·8 | 64 | 56 | 74 | 16 | 16 | 17 | 77 | 81 | 78 |
| | 6. | 98·2 | 98·4 | 99 | 60 | 54 | 64 | 15 | 16 | 15 | 78 | 80 | 78 |
| | 7. | 98·1 | 98·8 | 98·8 | 54 | 50 | 76 | 15 | 15 | 16 | 76 | 79 | 78 |
| | 8. | 97·9 | 98·8 | 98·9 | 50 | 50 | 60 | 15 | 15 | 16 | 76 | 80 | 75 |
| | 9. | 97·9 | 99·3 | 98·7 | 52 | 56 | 60 | 14 | 16 | 16 | 75 | 82 | 78 |
| | 10. | 98 | 99 | 98·9 | 50 | 56 | 56 | 15 | 15 | 15 | 75 | 82 | 78 |
| | 11. | 97·9 | 98·7 | 98·5 | 56 | 52 | 60 | 15 | 15 | 16 | 75 | 82 | 77 |
| | 12. | 97·9 | 98·7 | 98·8 | 54 | 56 | 60 | 15 | 16 | 15 | 75 | 82 | 78 |
| | 13. | 98·1 | 98·7 | 99·2 | 56 | 56 | 64 | 15 | 16 | 16 | 75 | 82 | 77 |
| | 14. | 97·9 | 98·8 | 99·1 | 54 | 56 | 58 | 15 | 16 | 16 | 75 | 82 | 79 |
| | 15. | 98·1 | 98·5 | 98·5 | 56 | 54 | 60 | 15 | 16 | 15 | 75 | 77 | 76 |
| | 16. | 98·1 | 99·2 | 99 | 54 | 60 | 64 | 15 | 16 | 16 | 76 | 82 | 78 |
| | 17. | 98·3 | ..... | 98·7 | 56 | ..... | 56 | 15 | ..... | 16 | 77 | ..... | 78 |
| | 18. | 98·1 | ..... | ..... | 56 | ..... | ..... | 15 | ..... | ..... | 76 | | |
| | 19. | 98·2 | 98·8 | 99·2 | 54 | 56 | 62 | 14 | 17 | 16 | 76 | 84 | 79 |
| | 20. | 98·3 | 98·7 | ..... | 56 | 62 | ..... | 15 | 16 | ..... | 78 | 83 | |
| | 21. | 98·3 | 98·7 | ..... | 56 | 62 | ..... | 15 | 16 | ..... | 78 | 83 | |
| | 22. | 98·7 | ..... | ..... | 68 | ..... | ..... | 16 | ..... | ..... | 77 | | |
| | 23. | 97·9 | 98·9 | 98·9 | 62 | 54 | 62 | 15 | 17 | 16 | 76 | 82 | 78 |
| | 24. | 97·9 | 98·8 | 99·1 | 52 | 54 | 62 | 14 | 15 | 16 | 76 | 82 | 78 |
| | 25. | 98·3 | 98·7 | ..... | 52 | 54 | ..... | 14 | 15 | ..... | 76 | 81 | |
| | 28. | 98 | 99 | 99 | 52 | 56 | 70 | 15 | 17 | 16 | 75 | 75 | 77 |
| | 29. | 98·1 | ..... | ..... | 52 | ..... | ..... | 14 | ..... | ..... | 77 | | |
| | 30. | 97·9 | 98·9 | 98·6 | 60 | 56 | 58 | 14 | 15 | 16 | 73 | 81 | 71 |
| | 31. | 98·1 | 98·8 | 98·9 | 52 | 56 | 56 | 15 | 16 | 14 | 73 | 80 | 78 |
| | | 98·1 | 98·9 | 98·9 | 55·3 | 55·3 | 63·5 | 14·5 | 15·8 | 15·8 | 76 | 80·5 | 77·4 |
| January 1847. | 1. | 98·4 | 98·8 | 98·7 | 56 | 54 | 66 | 14 | 16 | 16 | 73 | 82 | 78 |
| | 2. | 98·3 | 98·8 | ..... | 64 | 56 | ..... | 14 | 16 | ..... | 76 | 82 | |
| | 3. | 98·5 | ..... | 99 | 60 | ..... | 60 | 15 | ..... | 15 | 76 | ..... | 78 |
| | 4. | 98·1 | 98·9 | 98·9 | 56 | 56 | 60 | 15 | 16 | 16 | 77 | 82 | 79 |
| | 5. | 98·1 | 99·3 | 98·7 | 54 | 54 | 56 | 14 | 16 | 14 | 76 | 82 | 78 |
| | 6. | 98·3 | 99·2 | 99·1 | 54 | 54 | 60 | 14 | 15 | 16 | 76 | 82 | 78 |
| | 7. | 98 | 99·1 | 98·9 | 50 | 60 | 60 | 14 | 16 | 15 | 76 | 82 | 77 |
| | 8. | 98·3 | 98·9 | 98·9 | 52 | 58 | 62 | 14 | 16 | 16 | 76 | 83 | 78 |
| | 9. | 98·5 | 99·5 | 98·9 | 58 | 62 | 62 | 15 | 16 | 16 | 75 | 83 | 77 |
| | 10. | 97·9 | 98·4 | 98·5 | 56 | 52 | 56 | 14 | 15 | 14 | 75 | 79 | 76 |
| | 11. | 98·4 | 98·8 | 98·5 | 60 | 54 | 54 | 15 | 16 | 15 | 75 | 79 | 77 |
| | 12. | 97·9 | 98·9 | 98·9 | 54 | 56 | 60 | 15 | 16 | 16 | 74 | 81 | 77 |
| | 13. | 98 | 99 | 98·9 | 54 | 56 | 62 | 15 | 16 | 15 | 74 | 81 | 78 |
| | 14. | 97·9 | 98·9 | 99·1 | 50 | 56 | 64 | 14 | 16 | 15 | 74 | 82 | 77 |
| | 15. | 98 | 98·8 | 98·9 | 52 | 52 | 58 | 14 | 15 | 15 | 74 | 81 | 77 |
| | 16. | 98·3 | 98·8 | 99 | 52 | 52 | 58 | 14 | 14 | 14 | 74 | 82 | 77 |
| | 17. | 98·5 | 99 | 98·8 | 60 | 54 | 66 | 15 | 15 | 14 | 74 | 81 | 77 |
| | 18. | 98 | 99 | 98·9 | 54 | 54 | 62 | 14 | 14 | 14 | 74 | 81 | 77 |
| | 19. | 98·3 | ..... | ..... | 56 | ..... | ..... | 15 | ..... | ..... | 75 | | |
| | 21. | 98·3 | 99 | 98·7 | 56 | 54 | 62 | 15 | 16 | 15 | 73 | 79 | 77 |
| | 22. | 98·2 | ..... | ..... | 56 | ..... | ..... | 15 | ..... | ..... | 74 | | |
| | 23. | 98 | 98·6 | 99 | 54 | 48 | 64 | 14 | 14 | 16 | 74 | 81 | 78 |
| | 24. | 98 | 98·4 | 98·6 | 52 | 54 | 60 | 14 | 15 | 15 | 74 | 81 | 77 |
| | 25. | 98·5 | 99·2 | 99·1 | 54 | 56 | 68 | 14 | 15 | 15 | 75 | 82 | 77 |
| | 26. | 97·9 | 98·9 | 98·7 | 54 | 56 | 56 | 14 | 16 | 15 | 74 | 82 | 77 |
| | 28. | 98·1 | ..... | ..... | 56 | ..... | ..... | 14 | ..... | ..... | 74 | | |
| | 29. | 97·9 | 99·1 | ..... | 52 | 64 | ..... | 14 | 16 | ..... | 73 | 80 | |
| | 30. | 98·5 | 98·9 | 99·3 | 58 | 58 | 66 | 14 | 15 | 15 | 73 | 82 | 76 |
| | 31. | 97·9 | 98·4 | 98·5 | 54 | 52 | 58 | 15 | 15 | 15 | 74 | 81 | 77 |
| | | 98·1 | 98·9 | 98·8 | 54·8 | 55·3 | 60·8 | 14·4 | 15·4 | 15 | 74·6 | 81·3 | 77·3 |

| | | Temp. under the tongue. | | | Pulse. | | | Respirations. | | | Temperature of room. | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | 6–7 A.M. | 12–2 P.M. | 9–11 P.M. | 6–7 A.M. | 12–2 P.M. | 9–11 P.M. | 6–7 A.M. | 12–2 P.M. | 9–11 P.M. | 6–7 A.M. | 12–2 P.M. | 9–11 P.M. |
| February 1847. | 1. | 97·9 | 99·2 | 98·7 | 52 | 60 | 60 | 14 | 16 | 15 | 73 | 82 | 75 |
| | 2. | 97·9 | 99·2 | 98·3 | 56 | 60 | 60 | 14 | 16 | 15 | 72 | 82 | 74 |
| | 3. | 98·1 | ..... | ..... | 56 | ..... | ..... | 14 | ..... | ..... | 71 | | |
| | 4. | 97·9 | 98·9 | ..... | 56 | 62 | ..... | 14 | 15 | ..... | 71 | 81 | |
| | 5. | 97·9 | 99 | 99·1 | 56 | 56 | 64 | 14 | 16 | 16 | 71 | 81 | 74 |
| | 6. | 97·7 | 99 | ..... | 58 | 56 | ..... | 14 | 15 | ..... | 70 | 79 | |
| | 7. | 98·1 | 98·5 | 99·1 | 58 | 60 | 60 | 15 | 15 | 15 | 71 | 81 | 75 |
| | 8. | 97·8 | 98·7 | 99 | 54 | 56 | 64 | 14 | 16 | 16 | 73 | 82 | 75 |
| | 9. | 97·8 | 99·2 | 98·9 | 54 | 60 | 64 | 14 | 16 | 15 | 72 | 81 | 78 |
| | 10. | 98·2 | 98·8 | 98·9 | 56 | 54 | 64 | 14 | 15 | 15 | 74 | 82 | 78 |
| | 11. | 98·2 | 98·9 | 99·1 | 56 | 54 | 62 | 14 | 16 | 16 | 73 | 83 | 77 |
| | 12. | 98·2 | 98·7 | 98·6 | 58 | 56 | 58 | 15 | 16 | 15 | 74 | 80 | 76 |
| | 13. | 98·3 | 98·5 | ..... | 56 | 50 | ..... | 14 | 14 | ..... | 72 | 80 | |
| | 14. | 98·2 | 98·7 | 98·8 | 58 | 56 | 56 | 16 | 14 | 15 | 74 | 79 | 75 |
| | 15. | 98·1 | 98·8 | 98·7 | 54 | 60 | 58 | 14 | 16 | 15 | 71 | 82 | 76 |
| | 16. | 97·7 | 98·5 | 98·8 | 58 | 54 | 60 | 15 | 16 | 15 | 74 | 82 | 78 |
| | 17. | 98 | 98·8 | 99·1 | 58 | 58 | 58 | 15 | 16 | 15 | 75 | 82 | 77 |
| | 18. | 97·8 | 98·9 | 98·6 | 54 | 58 | 76 | 14 | 16 | 16 | 74 | 82 | 78 |
| | 19. | 97·8 | 98·8 | 98·8 | 58 | 58 | 60 | 16 | 16 | 15 | 74 | 81 | 77 |
| | 20. | 98·2 | ..... | ..... | 58 | ..... | ..... | 14 | ..... | ..... | 74 | | |
| | 21. | 98·2 | ..... | ..... | 54 | ..... | ..... | 15 | ..... | ..... | 75 | | |
| | 23. | 98 | 99 | 98·9 | 56 | 54 | 64 | 14 | 16 | 16 | 76 | 83 | 79 |
| | 24. | 97·9 | 98·9 | 98·9 | 52 | 60 | 62 | 14 | 15 | 15 | 75 | 83 | 77 |
| | 25. | 98·2 | 99·3 | ..... | 54 | 64 | ..... | 14 | 16 | ..... | 74 | 82 | |
| | 26. | 98·1 | 98·9 | 99·2 | 56 | 56 | 62 | 14 | 14 | 15 | 74 | 81 | 76 |
| | 27. | 97·9 | 98·8 | 98·1 | 56 | 56 | 60 | 14 | 15 | 16 | 72 | 82 | 76 |
| | 28. | 98 | 98·4 | ..... | 54 | 54 | ..... | 14 | 16 | ..... | 74 | 83 | |
| | | 98 | 98·8 | 98·8 | 55·5 | 57·6 | 61·7 | 14·2 | 15·5 | 15·3 | 73 | 81·5 | 76·3 |
| March 1847. | 1. | 98 | 98·9 | 99·3 | 52 | 54 | 64 | 15 | 16 | 15 | 74 | 83 | 76 |
| | 2. | 98·1 | 98·6 | 98·7 | 54 | 56 | 56 | 14 | 16 | 15 | 75 | 84 | 78 |
| | 3. | 98·2 | 99 | 98·6 | 54 | 60 | 80 | 14 | 15 | 16 | 75 | 83 | 78 |
| | 4. | 98·4 | 98·7 | 99 | 62 | 60 | 66 | 15 | 16 | 16 | 76 | 83 | 78 |
| | 5. | 98·1 | 98·8 | 99·2 | 52 | 54 | 68 | 14 | 16 | 16 | 75 | 84 | 77 |
| | 6. | 97·9 | 98·8 | 98·5 | 54 | 56 | 62 | 14 | 15 | 15 | 75 | 84 | 77 |
| | 7. | 98·2 | 98·5 | 98·9 | 54 | 54 | 64 | 14 | 15 | 15 | 74 | 84 | 77 |
| | 8. | 98·1 | 98·8 | 98·9 | 54 | 54 | 62 | 14 | 15 | 16 | 74 | 84 | 76 |
| | 9. | 97·9 | 98·7 | 98 9 | 54 | 52 | 56 | 14 | 16 | 15 | 74 | 83 | 78 |
| | 10. | 98·4 | 98·8 | 98·9 | 56 | 56 | 66 | 15 | 16 | 16 | 75 | 84 | 78 |
| | 11. | 98·1 | 98·8 | 98·9 | 56 | 50 | 64 | 15 | 16 | 16 | 74 | 83 | 76 |
| | 12. | 98·1 | ..... | ..... | 54 | ..... | ..... | 15 | ..... | ..... | 74 | | |
| | 13. | 98·2 | 99·2 | 99·3 | 56 | 58 | 60 | 15 | 15 | 15 | 74 | 83 | 78 |
| | 14. | 98·2 | 98·9 | 98·5 | 56 | 60 | 60 | 15 | 15 | 15 | 75 | 84 | 79 |
| | 15. | 98 | 99·1 | 99·2 | 56 | 62 | 60 | 15 | 16 | 16 | 76 | 85 | 78 |
| | 16. | 98·3 | 98·8 | 98·4 | 54 | 54 | 60 | 15 | 16 | 15 | 75 | 83 | 76 |
| | 17. | 98·4 | 99·2 | 98·8 | 56 | 54 | 62 | 15 | 15 | 16 | 73 | 75 | 76 |
| | 18. | 98 | 98·8 | 99·1 | 52 | 56 | 70 | 14 | 16 | 16 | 75 | 84 | 78 |
| | 19. | 98·2 | 98·7 | 98·8 | 52 | 54 | 60 | 15 | 16 | 16 | 75 | 83 | 78 |
| | 20. | 98·2 | 98·8 | 98·9 | 56 | 52 | 62 | 15 | 15 | 16 | 76 | 83 | 77 |
| | 21. | 98·2 | 98·7 | 98·9 | 52 | 52 | 60 | 14 | 15 | 15 | 74 | 83 | 77 |
| | 23. | 98·1 | 99·1 | 98·7 | 58 | 60 | 60 | 14 | 16 | 15 | 75 | 83 | 76 |
| | 24. | 98·1 | 99·2 | ..... | 60 | 64 | ..... | 14 | 16 | ..... | 75 | 82 | |
| | | 98·1 | 98·8 | 98·9 | 54·8 | 59·2 | 62·7 | 14·5 | 15·6 | 15 | 74·6 | 83·5 | 77·1 |

| | | Temp. under the tongue. | | | Pulse. | | | Respirations. | | | Temperature of room. | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | 6–7 A.M. | 12–2 P.M. | 9–11 P.M. | 6–7 A.M. | 12–2 P.M. | 9–11 P.M. | 6–7 A.M. | 12–2 P.M. | 9–11 P.M. | 6–7 A.M. | 12–2 P.M. | 9–11 P.M. |
| April 1847. | 1. | 98·3 | 99 | 99·1 | 52 | 70 | 66 | 14 | 17 | 15 | 72 | 78 | 75 |
| | 2. | 98·2 | 98·7 | 98·1 | 54 | 56 | 66 | 14 | 16 | 16 | 76 | 81 | 74 |
| | 3. | 98·2 | 98·7 | 99·2 | 54 | 68 | 70 | 14 | 16 | 16 | 73 | 79 | 75 |
| | 4. | 98·2 | 98·6 | 98·3 | 54 | 52 | 66 | 15 | 14 | 16 | 72 | 86 | 72 |
| | 5. | 98 | ..... | ..... | 54 | ..... | ..... | 14 | ..... | ..... | 70 | | |
| | 8. | 98·1 | 98·3 | 98·6 | 54 | 54 | 60 | 14 | 15 | 15 | 74 | 83 | 77 |
| | 9. | 97·9 | 98·7 | 98·8 | 54 | 54 | 60 | 14 | 15 | 15 | 75 | 83 | 78 |
| | 10. | 98·2 | 98·2 | 99 | 52 | 52 | 66 | 14 | 15 | 16 | 74 | 78 | 76 |
| | 11. | 98·3 | 98·6 | 98·8 | 50 | 54 | 56 | 14 | 15 | 16 | 74 | 81 | 78 |
| | 12. | 98 | 98·7 | 98·4 | 56 | 54 | 56 | 15 | 16 | 15 | 75 | 83 | 77 |
| | 13. | 97·8 | 98·7 | 98·7 | 54 | 54 | 64 | 14 | 15 | 16 | 73 | 77 | 78 |
| | 14. | 97·9 | 98·7 | 98·7 | 56 | 56 | 64 | 14 | 15 | 15 | 76 | 82 | 77 |
| | 15. | 97·9 | 99·2 | 99 | 54 | 64 | 70 | 15 | 15 | 15 | 75 | 82 | 78 |
| | 16. | 98·3 | 98·5 | 98·8 | 54 | 54 | 60 | 15 | 15 | 16 | 75 | 82 | 78 |
| | 17. | 97·7 | 99 | ..... | 58 | 56 | ..... | 14 | 15 | ..... | 75 | 83 | |
| | 18. | 98·2 | 98·4 | 99·1 | 60 | 56 | 60 | 15 | 15 | 15 | 75 | 83 | 79 |
| | 19. | 98·3 | 98·7 | 99 | 56 | 56 | 62 | 15 | 16 | 16 | 75 | 84 | 78 |
| | 20. | 98·2 | 98·9 | 99·1 | 56 | 58 | 54 | 13 | 16 | 15 | 75 | 81 | 77 |
| | 21. | 97·5 | 99 | 98·8 | 54 | 60 | 58 | 14 | 17 | 16 | 76 | 83 | 78 |
| | 22. | 98·2 | 98·7 | 98·5 | 56 | 54 | 62 | 14 | 16 | 16 | 75 | 83 | 78 |
| | 23. | 98·1 | 98·7 | 99·1 | 58 | 54 | 70 | 14 | 16 | 16 | 76 | 84 | 79 |
| | 24. | 98·3 | 99 | 98·8 | 54 | 56 | 70 | 14 | 15 | 15 | 76 | 84 | 78 |
| | 25. | 98·2 | ..... | ..... | 56 | ..... | ..... | 14 | ..... | ..... | 75 | | |
| | 26. | 98·6 | 98·7 | 99 | 56 | 56 | 62 | 14 | 16 | 16 | 76 | 83 | 79 |
| | 27. | 98 | 99 | 98·9 | 54 | 54 | 60 | 14 | 16 | 15 | 76 | 84 | 78 |
| | 28. | 97·9 | 99 | ..... | 56 | 56 | ..... | 14 | 15 | ..... | 75 | 84 | |
| | 29. | 98·4 | 98·9 | 98·9 | 58 | 54 | 56 | 15 | 16 | 15 | 76 | 85 | 78 |
| | 30. | 98·2 | 98·8 | 99·2 | 58 | 54 | 58 | 14 | 16 | 15 | 76 | 83 | 78 |
| | | 98·1 | 98·7 | 98·8 | 55 | 56·4 | 62·3 | 14·2 | 15·5 | 15·6 | 74·7 | 82·2 | 77·1 |
| May 1847. | 1. | 97·8 | 99·2 | 98·5 | 56 | 58 | 58 | 14 | 16 | 16 | 76 | 84 | 79 |
| | 2. | 98·3 | 98·7 | 98·7 | 56 | 52 | 62 | 14 | 15 | 15 | 77 | 84 | 79 |
| | 3. | 98·4 | 98·8 | 99·2 | 54 | 58 | 60 | 14 | 16 | 16 | 76 | 85 | 79 |
| | 4. | 98·1 | 98·7 | 98·3 | 56 | 60 | 52 | 14 | 16 | 15 | 75 | 83 | 77 |
| | 5. | 98·4 | 98·9 | 98·9 | 58 | 56 | 60 | 14 | 16 | 16 | 75 | 84 | 79 |
| | 6. | 98·4 | 98·7 | ..... | 56 | 58 | ..... | 15 | 17 | ..... | 76 | 84 | |
| | 7. | 98·4 | 98·9 | 99·2 | 56 | 58 | 58 | 15 | 17 | 15 | 77 | 85 | 79 |
| | 8. | 98·2 | 99·2 | 99·2 | 54 | 60 | 72 | 15 | 16 | 16 | 77 | 85 | 79 |
| | 9. | 98 | 99·2 | 99 | 54 | 60 | 66 | 15 | 16 | 16 | 77 | 84 | 78 |
| | 10. | 98·1 | 98·9 | 98·7 | 60 | 58 | 58 | 15 | 15 | 16 | 75 | 83 | 78 |
| | 11. | 98 | 98·7 | ..... | 56 | 58 | ..... | 15 | 16 | ..... | 75 | 84 | |
| | 12. | 98·2 | 98·8 | 98·9 | 58 | 56 | 66 | 14 | 16 | 15 | 76 | 84 | 79 |
| | 13. | 97·9 | 99·1 | 98·9 | 56 | 56 | 64 | 15 | 15 | 16 | 77 | 84 | 79 |
| | 14. | 98·1 | 98·9 | 98·6 | 54 | 64 | 58 | 15 | 16 | 15 | 78 | 87 | 80 |
| | 15. | 98·1 | 99·1 | 98·7 | 56 | 62 | 58 | 15 | 16 | 15 | 78 | 86 | 79 |
| | 16. | 98·2 | 98·8 | 99·2 | 54 | 58 | 62 | 15 | 15 | 16 | 78 | 86 | 80 |
| | 17. | 98·1 | 99·1 | 99·2 | 56 | 58 | 64 | 15 | 16 | 16 | 77 | 87 | 80 |
| | 18. | 98·3 | 98·6 | 98·7 | 56 | 54 | 58 | 14 | 16 | 15 | 77 | 84 | 79 |
| | 19. | 98·4 | 99 | ..... | 56 | 62 | ..... | 14 | 16 | ..... | 77 | 87 | |
| | 20. | 98·1 | 98·7 | 99·2 | 60 | 56 | 64 | 15 | 16 | 16 | 78 | 86 | 81 |
| | 21. | 98·1 | 98·9 | ..... | 58 | 60 | ..... | 14 | 15 | ..... | 78 | 86 | |
| | 22. | 98·3 | 98·8 | 98·6 | 62 | 56 | 66 | 14 | 16 | 16 | 78 | 87 | 82 |
| | 23. | 98·2 | 98·8 | 99·1 | 60 | 54 | 60 | 15 | 15 | 15 | 79 | 85 | 80 |
| | 24. | 98·4 | ..... | ..... | 58 | ..... | ..... | 14 | ..... | ..... | 77 | ..... | |
| | | 98·1 | 98·9 | 98·8 | 56·6 | 57·8 | 61·3 | 14·5 | 15·8 | 15·6 | 76·7 | 85 | 79·2 |

| | | Temp. under the tongue. | | | Pulse. | | | Respirations. | | | Temperature of room. | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | 6–7 A.M. | 12–2 P.M. | 9–11 P.M. | 6–7 A.M. | 12–2 P.M. | 9–11 P.M. | 6–7 A.M. | 12–2 P.M. | 9–11 P.M. | 6–7 A.M. | 12–2 P.M. | 9–11 P.M. |
| October 1847. | 1. | 98·2 | 99 | 99·2 | 56 | 56 | 60 | 15 | 16 | 17 | 77 | 85 | 81 |
| | 2. | 98·2 | 99 | 99·1 | 56 | 58 | 60 | 15 | 15 | 17 | 78 | 86 | 83 |
| | 3. | 98 | 98·9 | 98·6 | 56 | 56 | 56 | 14 | 15 | 16 | 78 | 85 | 81 |
| | 4. | 98·3 | 98·9 | 99·2 | 58 | 58 | 60 | 15 | 15 | 16 | 78 | 87 | 81 |
| | 5. | 98·5 | 98·8 | 98·8 | 56 | 56 | 56 | 15 | 15 | 16 | 78 | 83 | 78 |
| | 6. | 98 | 98·7 | 99 | 56 | 52 | 64 | 14 | 16 | 17 | 77 | 85 | 79 |
| | 7. | 98 | 99 | 98·5 | 54 | 56 | 54 | 15 | 15 | 16 | 78 | 86 | 78 |
| | 8. | 98·2 | 99·6 | 98·9 | 56 | 62 | 58 | 15 | 16 | 16 | 77 | 83 | 81 |
| | 9. | 98 | 99·1 | 98·8 | 56 | 54 | 54 | 15 | 16 | 15 | 78 | 86 | 82 |
| | 10. | 98·3 | 99 | 98·7 | 54 | 56 | 58 | 15 | 15 | 16 | 79 | 87 | 81 |
| | 11. | 98·5 | 98·8 | 99·1 | 56 | 58 | 56 | 15 | 16 | 16 | 80 | 83 | 81 |
| | 12. | 98·4 | 98·8 | 98·7 | 56 | 58 | 54 | 15 | 14 | 16 | 78 | 86 | 79 |
| | 13. | 98 | 99·2 | 98·8 | 52 | 60 | 60 | 14 | 15 | 16 | 78 | 85 | 80 |
| | 14. | 98·2 | 99 | 98·8 | 58 | 58 | 15 | 16 | 16 | 16 | 77 | 85 | 80 |
| | 15. | 98 | 98·8 | 98 | 54 | 56 | 58 | 15 | 15 | 16 | 77 | 84 | 80 |
| | 16. | 98·1 | 99·1 | 98·6 | 56 | 54 | 56 | 15 | 17 | 16 | 78 | 86 | 80 |
| | 17. | 98 | 98·9 | 99·1 | 54 | 56 | 60 | 15 | 15 | 16 | 78 | 86 | 80 |
| | 18. | 97·9 | 98·7 | 98·6 | 54 | 52 | 56 | 15 | 15 | 16 | 78 | 86 | 80 |
| | 19. | 98·1 | 99 | 98·7 | 54 | 52 | 54 | 14 | 15 | 16 | 78 | 87 | 81 |
| | 20. | 98 | 99·2 | 98·6 | 52 | 58 | 54 | 14 | 15 | 15 | 78 | 86 | 82 |
| | 21. | 98 | 99 | 99·1 | 52 | 56 | 60 | 14 | 15 | 16 | 78 | 85 | 80 |
| | 22. | 98·1 | 99 | 98·4 | 58 | 54 | 56 | 14 | 15 | 15 | 78 | 84 | 79 |
| | 23. | 97·9 | 99·6 | 98·9 | 52 | 58 | 60 | 14 | 15 | 15 | 77 | 86 | 80 |
| | 24. | 98·1 | 98·9 | 98·5 | 56 | 56 | 54 | 15 | 15 | 15 | 77 | 85 | 80 |
| | 25. | 97·7 | 98·5 | 98·3 | 54 | 50 | 54 | 15 | 15 | 15 | 79 | 79 | 78 |
| | 26. | 97·9 | 98·2 | 98·6 | 52 | 54 | 54 | 14 | 15 | 15 | 77 | 80 | 79 |
| | 27. | 97·9 | 99·2 | 98·4 | 56 | 56 | 54 | 15 | 14 | 15 | 77 | 85 | 77 |
| | 28. | 98·1 | 98·7 | 98·7 | 54 | 52 | 56 | 14 | 15 | 15 | 77 | 83 | 79 |
| | 29. | 98 | 98·8 | 98·8 | 54 | 58 | 58 | 14 | 14 | 15 | 77 | 82 | 80 |
| | 30. | 98·1 | 98·8 | 99 | 56 | 58 | 60 | 14 | 15 | 16 | 76 | 85 | 80 |
| | 31. | 98 | 98·9 | 98·8 | 52 | 60 | 58 | 14 | 14 | 15 | 77 | 85 | 81 |
| | | 98 | 99 | 99 | 54·7 | 56 | 55·7 | 14·5 | 15·1 | 15·7 | 77·7 | 84·8 | 80 |
| November 1847. | 1. | 98·2 | 99·7 | 99·1 | 56 | 66 | 60 | 15 | 15 | 16 | 77 | 84 | 79 |
| | 2. | 98·3 | 99 | 98·9 | 54 | 62 | 58 | 14 | 15 | 15 | 77 | 83 | 82 |
| | 3. | 98·1 | 98·7 | 98·9 | 56 | 50 | 58 | 15 | 15 | 16 | 78 | 86 | 82 |
| | 4. | 98 | 98·9 | 99·1 | 54 | 52 | 58 | 14 | 14 | 15 | 78 | 86 | 82 |
| | 5. | 98 | 98·8 | 98·9 | 50 | 56 | 56 | 15 | 15 | 15 | 78 | 86 | 80 |
| | 6. | 98·2 | 99·4 | 98·8 | 56 | 54 | 62 | 14 | 15 | 16 | 78 | 86 | 82 |
| | 7. | 98·3 | 99·3 | ..... | 56 | 62 | ..... | 14 | 16 | ..... | 79 | 87 | |
| | 8. | 98 | 98·8 | 98·9 | 56 | 56 | 60 | 14 | 14 | 15 | 78 | 84 | 79 |
| | 9. | 98 | 98·5 | 98·9 | 56 | 52 | 54 | 14 | 16 | 16 | 78 | 86 | 81 |
| | 10. | 98·2 | 99 | 98·9 | 56 | 56 | 56 | 14 | 15 | 16 | 79 | 86 | 81 |
| | 11. | 98·4 | 98·8 | 98·8 | 58 | 58 | 56 | 14 | 15 | 16 | 79 | 85 | 81 |
| | 12. | 98·2 | 99·3 | 99 | 56 | 56 | 62 | 14 | 15 | 15 | 79 | 84 | 81 |
| | 13. | 98·4 | 99·5 | 99 | 58 | 60 | 58 | 15 | 16 | 16 | 79 | 86 | 81 |
| | 14. | 98·6 | 99·1 | 98·6 | 60 | 58 | 56 | 15 | 16 | 15 | 78 | 83 | 78 |
| | 15. | 98 | 98·7 | 97·7 | 56 | 50 | 58 | 15 | 15 | 16 | 75 | 76 | 76 |
| | 16. | 98·4 | 98·5 | 97·8 | 54 | 50 | 58 | 15 | 16 | 16 | 76 | 78 | 76 |
| | 17. | 98·3 | 98·5 | 98·8 | 54 | 52 | 54 | 14 | 15 | 16 | 75 | 79 | 77 |
| | 18. | 98·2 | 99·4 | ..... | 54 | 62 | ..... | 15 | 16 | ..... | 77 | 83 | |
| | 19. | 98·2 | 98·5 | 98·6 | 58 | 52 | 58 | 15 | 15 | 15 | 75 | 82 | 76 |
| | 20. | 98·1 | 98·9 | 99 | 52 | 56 | 58 | 15 | 15 | 15 | 74 | 83 | 78 |
| | 21. | 98 | 98·2 | 98·5 | 56 | 54 | 64 | 14 | 15 | 16 | 74 | 77 | 77 |
| | 22. | 98·2 | 99·2 | 98·6 | 56 | 62 | 60 | 14 | 16 | 16 | 75 | 78 | 77 |
| | 23. | 98·2 | 99·2 | 98·7 | 60 | 70 | 60 | 15 | 15 | 16 | 75 | 83 | 78 |
| | 24. | 98·2 | 98·8 | 99·3 | 54 | 54 | 64 | 14 | 15 | 16 | 75 | 75 | 79 |
| | 25. | 98·2 | 99·2 | 99 | 54 | 56 | 66 | 15 | 15 | 17 | 77 | 83 | 79 |
| | 26. | 98·2 | 98·9 | 98·5 | 54 | 56 | 56 | 14 | 15 | 15 | 77 | 82 | 78 |
| | 27. | 98 | 98·6 | 98·7 | 54 | 56 | 62 | 15 | 15 | 16 | 74 | 81 | 78 |
| | 28. | 98 | 98·6 | 98·3 | 54 | 54 | 56 | 14 | 15 | 15 | 75 | 82 | 76 |
| | 29. | 98·1 | 98·9 | 99 | 52 | 54 | 68 | 15 | 15 | 15 | 77 | 77 | 78 |
| | 30. | 98·4 | 99·3 | 98·6 | 58 | 58 | 54 | 15 | 14 | 15 | 76 | 81 | 78 |
| | | 98·1 | 98·8 | 98·8 | 53·3 | 54·8 | 59·2 | 14·5 | 15·1 | 15·2 | 76·7 | 82·3 | 79 |

| | | Temp. under the tongue. | | | Pulse. | | | Respirations. | | | Temperature of room. | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | 6–7 A.M. | 12–2 P.M. | 9–11 P.M. | 6–7 A.M. | 12–2 P.M. | 9–11 P.M. | 6–7 A.M. | 12–2 P.M. | 9–11 P.M. | 6–7 A.M. | 12–2 P.M. | 9–11 P.M. |
| December 1847. | 1. | 98·1 | 98·7 | 98·9 | 52 | 56 | 62 | 14 | 15 | 15 | 77 | 83 | 77 |
| | 2. | 97·9 | 98·6 | 98·6 | 52 | 52 | 58 | 14 | 15 | 16 | 74 | 81 | 68 |
| | 3. | 97·9 | 99·2 | 99·2 | 52 | 58 | 68 | 14 | 14 | 16 | 75 | 73 | 77 |
| | 4. | 97·9 | 98·7 | 98·7 | 52 | 54 | 60 | 15 | 15 | 16 | 74 | 82 | 73 |
| | 5. | 97·7 | 99·1 | 97·8 | 54 | 60 | 56 | 14 | 15 | 14 | 68 | 82 | 73 |
| | 6. | 98·2 | 98·4 | 98·5 | 56 | 58 | 56 | 14 | 15 | 16 | 72 | 83 | 78 |
| | 7. | 97·9 | 98·6 | 98 2 | 56 | 54 | 56 | 14 | 15 | 16 | 77 | 83 | 78 |
| | 8. | 98·1 | 99·1 | 98·8 | 54 | 58 | 58 | 14 | 15 | 15 | 77 | 84 | 78 |
| | 9. | 98 | 99·2 | 98 5 | 54 | 62 | 58 | 15 | 16 | 15 | 76 | 83 | 77 |
| | 10. | 98·2 | 98·7 | 98·5 | 54 | 54 | 60 | 15 | 15 | 16 | 76 | 83 | 78 |
| | 11. | 98·3 | 98·8 | 98·6 | 54 | 54 | 60 | 15 | 15 | 16 | 77 | 81 | 78 |
| | 12. | 98·3 | 98·9 | 98·7 | 54 | 50 | 58 | 14 | 14 | 16 | 77 | 81 | 77 |
| | 13. | 98·2 | 99·1 | 98·8 | 56 | 56 | 60 | 14 | 15 | 15 | 79 | 80 | 78 |
| | 14. | 98 | 98·9 | 98·4 | 52 | 52 | 64 | 14 | 14 | 16 | 73 | 77 | 77 |
| | 15. | 97·9 | 99·2 | 98 | 52 | 58 | 64 | 14 | 15 | 16 | 76 | 80 | 77 |
| | 16. | 97·9 | 98·8 | 98·6 | 52 | 56 | 60 | 14 | 15 | 16 | 75 | 80 | 76 |
| | 17. | 98·1 | 98·7 | 98·7 | 52 | 54 | 60 | 15 | 15 | 15 | 76 | 81 | 77 |
| | 18. | 97·9 | 98·2 | 98 5 | 54 | 50 | 56 | 14 | 15 | 15 | 76 | 81 | 77 |
| | 19. | 98·1 | 98·9 | 98·5 | 52 | 60 | 58 | 14 | 15 | 15 | 75 | 82 | 77 |
| | 20. | 98·2 | 98·7 | 98·6 | 56 | 56 | 60 | 14 | 14 | 16 | 76 | 82 | 78 |
| | 21. | 98 | 98·8 | 98·7 | 52 | 56 | 58 | 14 | 15 | 15 | 75 | 82 | 78 |
| | 22. | 98·1 | ..... | 98·9 | 52 | ..... | 66 | 13 | ..... | 15 | 75 | ..... | 77 |
| | 23. | 97·9 | 98·8 | 98·1 | 54 | 56 | 62 | 14 | 14 | 15 | 75 | 82 | 76 |
| | 24. | 98·1 | 99·1 | ..... | 52 | 58 | ..... | 14 | 16 | ..... | 74 | 80 | ..... |
| | 27. | 98·1 | 98·5 | 98·7 | 54 | 52 | 56 | 14 | 14 | 15 | 73 | 81 | 76 |
| | 28. | 97·9 | 98·4 | 98·3 | 52 | 56 | 58 | 14 | 15 | 15 | 74 | 82 | 76 |
| | 29. | 98 | 98·4 | 98·9 | 50 | 52 | 62 | 14 | 14 | 15 | 73 | 81 | 75 |
| | 30. | 97·7 | 99·2 | 99·4 | 50 | 60 | 58 | 14 | 15 | 15 | 73 | 81 | 78 |
| | 31. | 98·1 | 98·5 | 98·4 | 52 | 50 | 58 | 14 | 15 | 15 | 75 | 79 | 78 |
| | | 98 | 98·8 | 98·3 | 52·9 | 53·5 | 58 | 14 1 | 14·6 | 15·3 | 74 5 | 81·1 | 76·9 |
| January 1848. | 1. | 98 | 99 | 98·8 | 56 | 60 | 66 | 14 | 15 | 14 | 76 | 80 | 77 |
| | 2. | 98·1 | 99·2 | 98·9 | 54 | 56 | 60 | 15 | 15 | 15 | 75 | 81 | 78 |
| | 3. | 98 | 99·1 | 99 | 54 | 60 | 66 | 14 | 15 | 15 | 76 | 82 | 78 |
| | 4. | 98·2 | 99 | 98·8 | 52 | 56 | 58 | 14 | 15 | 15 | 75 | 80 | 76 |
| | 5. | 98·1 | 99·1 | 99 | 52 | 58 | 58 | 14 | 14 | 16 | 75 | 80 | 76 |
| | 6. | 97·9 | 99·1 | 98·5 | 54 | 58 | 58 | 14 | 15 | 15 | 75 | 80 | 78 |
| | 7. | 98·2 | 98·7 | 98·8 | 56 | 54 | 58 | 14 | 15 | 15 | 74 | 81 | 78 |
| | 8. | 98·3 | 99·1 | 98·8 | 56 | 62 | 64 | 14 | 16 | 16 | 75 | 83 | 78 |
| | 9. | 98·3 | 98·8 | 99·1 | 52 | 56 | 60 | 15 | 15 | 16 | 74 | 82 | 78 |
| | 10. | 98·4 | 98·3 | 98·8 | 54 | 58 | 60 | 14 | 15 | 16 | 73 | 81 | 71 |
| | 11. | 97·9 | 98·4 | 98·5 | 52 | 54 | 60 | 14 | 16 | 15 | 73 | 81 | 75 |
| | 12. | 98·1 | 98·3 | 98·7 | 58 | 54 | 66 | 14 | 15 | 16 | 73 | 82 | 77 |
| | 13. | 97·9 | 98·6 | 98·5 | 54 | 58 | 64 | 14 | 16 | 15 | 74 | 80 | 77 |
| | 14. | 98 | 99·1 | 98·9 | 56 | 60 | 56 | 14 | 16 | 14 | 73 | 81 | 77 |
| | 15. | 98 | 98·9 | 99 | 56 | 62 | 60 | 14 | 16 | 15 | 73 | 81 | 78 |
| | 16. | 98·3 | 99 | 98·7 | 56 | 52 | 58 | 14 | 15 | 16 | 75 | 80 | 78 |
| | 17. | 98·1 | 98·8 | 98·8 | 54 | 56 | 60 | 15 | 15 | 15 | 75 | 75 | 75 |
| | 18. | 97·9 | 98·6 | 98·9 | 56 | 56 | 56 | 14 | 15 | 16 | 73 | 77 | 77 |
| | 19. | 98·3 | 98·8 | 98·8 | 54 | 54 | 58 | 14 | 15 | 15 | 74 | 80 | 77 |
| | 20. | 98·3 | 99 | 98·5 | 56 | 58 | 56 | 14 | 15 | 16 | 74 | 81 | 77 |
| | 21. | 97·9 | 98·6 | 98·8 | 54 | 58 | 58 | 14 | 16 | 16 | 74 | 80 | 78 |
| | 22. | 98·1 | 98·7 | 98·7 | 56 | 56 | 58 | 14 | 15 | 15 | 74 | 82 | 78 |
| | 23. | 98·1 | 99·1 | 98·7 | 56 | 58 | 54 | 14 | 14 | 14 | 73 | 81 | 76 |
| | 24. | 98 3 | 99 | 98·8 | 52 | 54 | 60 | 14 | 14 | 15 | 73 | 79 | 76 |
| | 25. | 97·8 | 98·9 | 98·4 | 52 | 54 | 60 | 14 | 15 | 15 | 73 | 80 | 76 |
| | 26. | 98·2 | 98·9 | 99 | 53 | 56 | 56 | 14 | 15 | 16 | 73 | 81 | 77 |
| | 27. | 97·9 | 98·8 | 98·8 | 56 | 54 | 56 | 14 | 15 | 15 | 69 | 80 | 74 |
| | 28. | 98 | 98·8 | 98·9 | 54 | 56 | 62 | 14 | 15 | 15 | 68 | 80 | 76 |
| | 29. | 98 | 99·3 | 99·1. | 54 | 60 | 62 | 14 | 16 | 15 | 72 | 80 | 74 |
| | 30. | 98·3 | 99·3 | 98·8 | 56 | 56 | 56 | 14 | 14 | 15 | 71 | 82 | 77 |
| | 31. | 98·1 | 98·9 | 99 | 54 | 56 | 54 | 15 | 15 | 15 | 74 | 82 | 78 |
| | | 98·1 | 98·9 | 98·8 | 54·5 | 56·8 | 59·3 | 14·1 | 14·9 | 15·2 | 74·1 | 80·5 | 76·6 |

| | | Temp. under the tongue. | | | Pulse. | | | Respirations. | | | Temperature of room. | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | 6–7 A.M. | 12–2 P.M. | 9–11 P.M. | 6–7 A.M. | 12–2 P.M. | 9–11 P.M. | 6–7 A.M. | 12–2 P.M. | 9–11 P.M. | 6–7 A.M. | 12–2 P.M. | 9–11 P.M. |
| February 1848. | 1. | 98°4 | 99° | 98°8 | 56 | 56 | 56 | 14 | 15 | 15 | 73° | 81° | 78° |
| | 2. | 98·2 | 99 | 98·8 | 54 | 58 | 56 | 15 | 15 | 15 | 73 | 83 | 75 |
| | 3. | 97·9 | 99·2 | 98·9 | 56 | 60 | 58 | 15 | 15 | 15 | 75 | 82 | 78 |
| | 4. | 98 | 98·8 | 98·6 | 54 | 62 | 56 | 14 | 16 | 15 | 74 | 81 | 78 |
| | 5. | 98·1 | 98·8 | 98·9 | 56 | 60 | 62 | 14 | 16 | 15 | 73 | 83 | 77 |
| | 6. | 98 | 98·8 | 98·8 | 56 | 56 | 60 | 14 | 15 | 16 | 72 | 82 | 77 |
| | 7. | 98 | 98·9 | 99·3 | 56 | 54 | 62 | 14 | 14 | 16 | 73 | 81 | 78 |
| | 8. | 98 | 99·2 | 98·8 | 57 | 58 | 56 | 14 | 16 | 15 | 73 | 83 | 77 |
| | 9. | 98·1 | 98·7 | 99·2 | 56 | 58 | 64 | 15 | 15 | 16 | 74 | 83 | 78 |
| | 10. | 97·9 | 99·6 | 99 | 54 | 54 | 56 | 14 | 15 | 16 | 74 | 81 | 77 |
| | 11. | 98 | 98·5 | 98·9 | 55 | 56 | 62 | 15 | 15 | 16 | 74 | 80 | 78 |
| | 12. | 98·1 | 98·5 | 99 | 56 | 54 | 64 | 15 | 16 | 17 | 73 | 81 | 77 |
| | 13. | 98 | 98·4 | 98·5 | 52 | 56 | 56 | 14 | 15 | 16 | 73 | 81 | 77 |
| | 14. | 98 | 99·4 | 98·9 | 56 | 58 | 60 | 14 | 15 | 16 | 74 | 83 | 78 |
| | 15. | 98 | 98·6 | 99·3 | 52 | 56 | 64 | 15 | 15 | 15 | 74 | 83 | 77 |
| | 16. | 98 | 98·7 | 98·9 | 57 | 56 | 62 | 15 | 15 | 16 | 73 | 82 | 78 |
| | 17. | 98·3 | 99 | 99·2 | 58 | 58 | 58 | 16 | 16 | 16 | 75 | 81 | 78 |
| | 18. | 98·1 | 98·3 | 98·8 | 54 | 52 | 58 | 15 | 15 | 15 | 73 | 77 | 77 |
| | 19. | 97·9 | 99·2 | 98·7 | 52 | 56 | 56 | 14 | 15 | 16 | 73 | 81 | 77 |
| | 20. | 98 | 99 | 98·7 | 56 | 54 | 56 | 14 | 15 | 15 | 74 | 81 | 78 |
| | 21. | 97·7 | 98·9 | 98·9 | 52 | 56 | 58 | 15 | 16 | 16 | 73 | 81 | 77 |
| | 22. | 97·8 | 99·2 | 99·1 | 52 | 58 | 62 | 15 | 14 | 15 | 73 | 83 | 78 |
| | 23. | 98·2 | 99 | 98·9 | 56 | 56 | 64 | 15 | 15 | 16 | 75 | 82 | 79 |
| | 24. | 97·9 | 99·1 | 99 | 54 | 64 | 64 | 14 | 16 | 16 | 74 | 83 | 79 |
| | 25. | 97·9 | 98·7 | 99 | 58 | 56 | 58 | 15 | 15 | 15 | 74 | 82 | 78 |
| | 26. | 97·9 | 98·7 | ..... | 54 | 56 | ..... | 15 | 16 | ..... | 74 | 81 | |
| | 27. | 97·8 | 99·2 | 99 | 56 | 56 | 60 | 14 | 15 | 15 | 74 | 82 | 78 |
| | 28. | 98·1 | 98·8 | 98·8 | 54 | 54 | 62 | 14 | 15 | 15 | 75 | 77 | 77 |
| | 29. | 97·8 | 98·6 | 98·9 | 52 | 56 | 62 | 15 | 15 | 15 | 74 | 81 | 78 |
| | | 98 | 98·8 | 98·8 | 54·9 | 57 | 59·7 | 14·5 | 15·1 | 15·5 | 73·6 | 82·1 | 77·5 |
| March 1848. | 1. | 98 | 98·8 | 99·3 | 54 | 56 | 62 | 15 | 16 | 16 | 75 | 83 | 79 |
| | 2. | 98·1 | 99·6 | 99·2 | 56 | 58 | 66 | 15 | 16 | 16 | 76 | 84 | 80 |
| | 3. | 98·2 | 98·8 | 99 | 56 | 56 | 64 | 15 | 15 | 17 | 76 | 83 | 80 |
| | 4. | 97·8 | 98·9 | ..... | 52 | 56 | ..... | 14 | 15 | ..... | 73 | 81 | |
| | 5. | 98·1 | 99·5 | 99 | 60 | 56 | 60 | 14 | 15 | 16 | 74 | 82 | 78 |
| | 6. | 97·9 | 98·7 | 98·6 | 56 | 56 | 56 | 14 | 15 | 15 | 74 | 82 | 79 |
| | 7. | 97·8 | 98·3 | 98·9 | 52 | 56 | 56 | 14 | 15 | 15 | 74 | 82 | 77 |
| | 8. | 97·9 | 99·5 | 99 | 52 | 74 | 58 | 14 | 16 | 15 | 74 | 83 | 79 |
| | 9. | 98·1 | 99·4 | ..... | 54 | 60 | ..... | 14 | 14 | ..... | 76 | 82 | |
| | 10. | 98·4 | 99·1 | 99 | 58 | 56 | 62 | 15 | 14 | 15 | 75 | 83 | 78 |
| | 11. | 98·1 | 99 | 98·7 | 54 | 60 | 62 | 14 | 16 | 16 | 74 | 81 | 78 |
| | 12. | 98·1 | 98·9 | 98·9 | 54 | 62 | 60 | 15 | 15 | 16 | 74 | 83 | 78 |
| | 13. | 98 | 98·9 | 99·1 | 56 | 56 | 60 | 14 | 15 | 16 | 73 | 82 | 78 |
| | 14. | 98·1 | 98·9 | 99 | 58 | 60 | 62 | 15 | 16 | 15 | 75 | 82 | 79 |
| | 15. | 98 | 98·8 | 98·7 | 56 | 56 | 56 | 14 | 15 | 15 | 76 | 83 | 78 |
| | 16. | 98·3 | 98·7 | 99·2 | 56 | 58 | 62 | 15 | 16 | 16 | 76 | 80 | 77 |
| | 17. | 98·1 | 98·7 | 98·9 | 54 | 54 | 62 | 14 | 14 | 15 | 75 | 83 | 79 |
| | 18. | 98·1 | ..... | ..... | 56 | ..... | ..... | 14 | ..... | ..... | 76 | | |
| | 19. | 98·2 | 99·2 | 99 | 56 | 60 | 54 | 15 | 15 | 15 | 75 | 83 | 82 |
| | 20. | 98·2 | 98·7 | 98·6 | 54 | 54 | 54 | 14 | 16 | 15 | 75 | 76 | 77 |
| | 21. | 98 | 98·7 | 99·1 | 52 | 56 | 56 | 15 | 16 | 15 | 73 | 82 | 78 |
| | 22. | 98 | 99 | 99 | 56 | 56 | 58 | 15 | 15 | 16 | 75 | 82 | 79 |
| | 23. | 98·1 | 98·8 | 98·9 | 54 | 58 | 60 | 14 | 15 | 15 | 77 | 83 | 79 |
| | 24. | 98·3 | 98·9 | 99 | 54 | 56 | 62 | 14 | 15 | 16 | 75 | 82 | 78 |
| | 25. | 98 | 98·6 | 98·9 | 56 | 56 | 56 | 14 | 15 | 15 | 76 | 79 | 78 |
| | 26. | 98·2 | 98·9 | 98·5 | 54 | 58 | 60 | 14 | 15 | 14 | 75 | 81 | 79 |
| | 27. | 97·9 | 98·7 | 99·1 | 52 | 52 | 56 | 14 | 15 | 15 | 75 | 83 | 78 |
| | 28. | 97·9 | 99·1 | 98·8 | 52 | 54 | 60 | 14 | 15 | 15 | 76 | 84 | 80 |
| | 29. | 98 | 99·2 | 99·2 | 54 | 64 | 66 | 14 | 16 | 16 | 77 | 85 | 77 |
| | 30. | 98·2 | 99·1 | 99·1 | 54 | 56 | 60 | 14 | 15 | 14 | 77 | 83 | 78 |
| | 31. | 98 | 99·4 | 99 | 58 | 58 | 62 | 14 | 15 | 15 | 78 | 79 | 75 |
| | | 98 | 98·9 | 98·9 | 54·9 | 57·6 | 59·7 | 14·3 | 15·5 | 15·4 | 75·1 | 81·9 | 78·2 |

| | | Temp. under the tongue. | | | Pulse. | | | Respirations. | | | Temperature of room. | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | 6–7 A.M. | 12–2 P.M. | 9–11 P.M. | 6–7 A.M. | 12–2 P.M. | 9–11 P.M. | 6–7 A.M. | 12–2 P.M. | 9–11 P.M. | 6–7 A.M. | 12–2 P.M. | 9–11 P.M. |
| April 1848. | 1. | 98·2 | 99 | 98·6 | 56 | 58 | 58 | 15 | 15 | 14 | 75 | 79 | 78 |
| | 2. | 98·1 | 99·2 | 99 | 60 | 56 | 58 | 14 | 16 | 15 | 73 | 81 | 77 |
| | 3. | 97·9 | 98·8 | 98·9 | 54 | 56 | 60 | 15 | 15 | 16 | 71 | 81 | 77 |
| | 4. | 98 | 98·7 | ..... | 54 | 58 | ..... | 14 | 15 | ..... | 71 | 81 | |
| | 5. | 98·2 | 98·8 | 98·9 | 60 | 60 | 64 | 15 | 16 | 15 | 72 | 83 | 78 |
| | 6. | 98·1 | 99·3 | 98·7 | 56 | 58 | 64 | 14 | 15 | 16 | 73 | 85 | 79 |
| | 7. | 98·2 | 99·2 | 99·2 | 56 | 58 | 64 | 15 | 15 | 16 | 76 | 85 | 79 |
| | 8. | 97·8 | 99·3 | 99·3 | 54 | 58 | 58 | 15 | 15 | 15 | 77 | 83 | 81 |
| | 9. | 98·4 | ..... | ..... | 58 | ..... | ..... | 15 | ..... | ..... | 75 | | |
| | 25. | 98·1 | 98·9 | 98·9 | 54 | 54 | 62 | 14 | 15 | 15 | 75 | 80 | 77 |
| | 26. | 98 | 98·7 | 98·9 | 52 | 56 | 60 | 15 | 16 | 16 | 77 | 85 | 81 |
| | 27. | 98 | 98 | 99 | 54 | 58 | 60 | 15 | 15 | 15 | 78 | 84 | 79 |
| | 28. | 97·9 | 99 | 98·9 | 52 | 58 | 60 | 14 | 15 | 15 | 77 | 85 | 79 |
| | 29. | 97·7 | 98·5 | 98·8 | 52 | 56 | 62 | 14 | 16 | 15 | 76 | 84 | 79 |
| | 30. | 97·9 | 99 | 99·1 | 52 | 64 | 62 | 15 | 16 | 16 | 77 | 85 | 82 |
| | | 98 | 98·9 | 98·9 | 54·9 | 57·7 | 60·9 | 14·7 | 15·2 | 15·3 | 74·8 | 82·9 | 78·1 |
| May 1848. | 1. | 98·3 | 99·1 | 98·7 | 52 | 58 | 60 | 14 | 15 | 15 | 78 | 86 | 81 |
| | 2. | 97·9 | 98·7 | 98·6 | 52 | 56 | 58 | 15 | 15 | 16 | 79 | 85 | 79 |
| | 3. | 98·1 | 98·7 | 99 | 56 | 54 | 60 | 14 | 15 | 16 | 77 | 85 | 80 |
| | 4. | 97·9 | 98·8 | 99 | 52 | 56 | 54 | 14 | 16 | 16 | 78 | 87 | 82 |
| | 5. | 98 | 99·2 | 99 | 56 | 54 | 60 | 15 | 16 | 15 | 79 | 85 | 81 |
| | 6. | 98·2 | 99 | 99·1 | 54 | 56 | 70 | 15 | 14 | 16 | 79 | 86 | 81 |
| | 7. | 98 | 99·1 | 99 | 58 | 56 | 60 | 14 | 15 | 16 | 78 | 86 | 82 |
| | 8. | 98·1 | 98·8 | 99·1 | 54 | 56 | 60 | 14 | 15 | 15 | 78 | 86 | 82 |
| | 9. | 98·3 | 99·3 | 98·4 | 56 | 58 | 58 | 15 | 15 | 15 | 79 | 85 | 78 |
| | 10. | 98·4 | 99·2 | 99 | 58 | 58 | 66 | 15 | 14 | 16 | 78 | 84 | 80 |
| | 11. | 98·2 | ..... | ..... | 58 | ..... | ..... | 14 | ..... | ..... | 78 | | |
| | | 98·1 | 99 | 98·9 | 55·1 | 56·2 | 60·6 | 14·3 | 15 | 15·6 | 78·2 | 85·6 | 80·6 |
| June 1848. | 7. | 98 | 98·6 | ..... | 56 | 60 | ..... | 15 | 16 | ..... | 78 | 81 | |
| | 8. | 98 | 98·9 | 98·6 | 52 | 58 | 62 | 14 | 15 | 15 | 78 | 84 | 81 |
| | 9. | 97·9 | 98·6 | 98·8 | 54 | 58 | 64 | 14 | 16 | 14 | 77 | 85 | 82 |
| | 10. | 98·8 | 98·9 | 99 | 54 | 58 | 60 | 15 | 15 | 16 | 78 | 85 | 80 |
| | 11. | 97·8 | 99 | 98·9 | 52 | 56 | 56 | 14 | 14 | 14 | 77 | 86 | 81 |
| | 12. | 97·9 | 98·9 | 98·9 | 52 | 54 | 58 | 14 | 15 | 14 | 78 | 83 | 80 |
| | 13. | 98·1 | 99 | 98·7 | 54 | 62 | 58 | 14 | 15 | 15 | 78 | 86 | 81 |
| | 14. | 98·1 | 98·9 | ..... | 54 | 58 | ..... | 14 | 14 | ..... | 78 | 86 | |
| | 15. | 98 | 98·5 | 99·3 | 50 | 52 | 56 | 14 | 14 | 15 | 79 | 85 | 78 |
| | 16. | 97·9 | 98·7 | 99·1 | 52 | 54 | 62 | 14 | 15 | 15 | 77 | 86 | 80 |
| | 17. | 97·9 | 98·8 | 99 | 54 | 60 | 76 | 14 | 15 | 15 | 77 | 86 | 81 |
| | 18. | 98 | 98·9 | 98·9 | 56 | 58 | 56 | 14 | 14 | 16 | 77 | 85 | 81 |
| | 19. | 98 | 98·7 | 99 | 52 | 54 | 58 | 14 | 15 | 15 | 78 | 79 | 80 |
| | 20. | 98 | 99·1 | 98·7 | 50 | 56 | 62 | 14 | 15 | 15 | 77 | 85 | 81 |
| | 21. | 97·9 | 98·8 | 99 | 50 | 56 | 60 | 14 | 15 | 15 | 78 | 85 | 80 |
| | 22. | 98 | 98·7 | 99·2 | 50 | 56 | 60 | 14 | 15 | 15 | 77 | 85 | 82 |
| | 23. | 98 | 98·9 | 99 | 54 | 54 | 56 | 14 | 14 | 14 | 78 | 86 | 82 |
| | 24. | 98·1 | ..... | 98·9 | 54 | ..... | 62 | 14 | ..... | 15 | 79 | ..... | 79 |
| | 25. | 97·8 | 98·6 | 98·8 | 52 | 56 | 56 | 14 | 16 | 15 | 78 | 83 | 81 |
| | 26. | 97·9 | 98·9 | 99·2 | 52 | 52 | 60 | 14 | 15 | 14 | 78 | 84 | 81 |
| | 27. | 98·2 | 98·9 | 98·8 | 54 | 54 | 58 | 14 | 15 | 14 | 77 | 86 | 80 |
| | 28. | 97·9 | 98·9 | 98·8 | 50 | 54 | 58 | 14 | 15 | 15 | 77 | 85 | 79 |
| | 29. | 97·9 | 98·8 | 99·2 | 52 | 56 | 60 | 14 | 14 | 16 | 75 | 86 | 89 |
| | 30. | 97·8 | 99 | 99·3 | 54 | 54 | 62 | 14 | 14 | 15 | 77 | 86 | 80 |
| | | 98 | 98·8 | 99 | 51 | 56·1 | 56·8 | 14·1 | 14·8 | 14·9 | 77·5 | 84·7 | 80·4 |

| | | Temp. under the tongue. | | | Pulse. | | | Respirations. | | | Temperature of room. | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | 6–7 A.M. | 12–2 P.M. | 9–11 P.M. | 6–7 A.M. | 12–2 P.M. | 9–11 P.M. | 6–7 A.M. | 12–2 P.M. | 9–11 P.M. | 6–7 A.M. | 12–2 P.M. | 9–11 P.M. |
| July 1848. | 1. | 97°9 | 99°1 | 98°9 | 48 | 54 | 58 | 14 | 15 | 15 | 79° | 86° | 82° |
| | 2. | 98·1 | 98·3 | 98·9 | 58 | 52 | 56 | 14 | 15 | 14 | 78 | 87 | 82 |
| | 3. | 98·2 | 99 | 99·1 | 52 | 56 | 64 | 13 | 13 | 15 | 78 | 84 | 81 |
| | 4. | 98·1 | 98·6 | 98·5 | 52 | 54 | 78 | 13 | 15 | 15 | 76 | 79 | 79 |
| | 5. | 98·3 | 98·9 | 98·5 | 60 | 54 | 58 | 14 | 15 | 15 | 75 | 84 | 79 |
| | 6. | 98·1 | 99 | 99·1 | 52 | 52 | 58 | 14 | 14 | 14 | 78 | 85 | 81 |
| | 7. | 97·9 | 98·9 | 99·1 | 52 | 56 | 58 | 14 | 14 | 15 | 78 | 83 | 81 |
| | 8. | 98·1 | 99 | 98·5 | 51 | 54 | 72 | 14 | 15 | 14 | 78 | 84 | 81 |
| | 9. | 98·2 | ..... | 99·3 | 56 | ..... | 58 | 14 | ..... | 15 | 78 | ..... | 82 |
| | 10. | 98·2 | 98·9 | 99·1 | 52 | 54 | 58 | 14 | 16 | 15 | 77 | 85 | 80 |
| | 11. | 97·8 | 98·7 | 99 | 50 | 56 | 54 | 14 | 14 | 14 | 77 | 85 | 80 |
| | 12. | 98 | ..... | ..... | 50 | ..... | ..... | 14 | ..... | ..... | 77 | | |
| | 26. | 97·9 | 99 | 99·4 | 54 | 56 | 58 | 14 | 15 | 15 | 77 | 85 | 80 |
| | 27. | 98 | 98·9 | 98·7 | 54 | 56 | 58 | 14 | 15 | 15 | 77 | 85 | 80 |
| | 28. | 98·2 | 99 | 98·9 | 54 | 56 | 56 | 15 | 15 | 15 | 79 | 85 | 82 |
| | 29. | 98·2 | 98·4 | 98·9 | 54 | 50 | 52 | 14 | 15 | 15 | 79 | 85 | 81 |
| | 30. | 98·1 | 98·9 | 98·5 | 54 | 50 | 54 | 14 | 13 | 15 | 78 | 83 | 81 |
| | 31. | 98·1 | 99·2 | 99 | 52 | 58 | 58 | 14 | 14 | 15 | 78 | 85 | 80 |
| | | 98 | 98·3 | 98·9 | 53 | 54·2 | 59·5 | 14 | 14·7 | 14·8 | 77·7 | 84·3 | 79·4 |
| August 1848. | 1. | 97·8 | 99 | 98·7 | 52 | 54 | 56 | 14 | 15 | 15 | 78 | 85 | 80 |
| | 2. | 97·8 | ..... | 98·5 | 52 | ..... | 76 | 13 | ..... | 15 | 78 | ..... | 79 |
| | 3. | 98·3 | 98·7 | 98·7 | 54 | 54 | 54 | 14 | 15 | 14 | 78 | 86 | 80 |
| | 4. | 98·1 | 98·7 | 98·6 | 54 | 52 | 54 | 15 | 15 | 14 | 79 | 82 | 81 |
| | 5. | 98·1 | 99 | 98·9 | 56 | 52 | 56 | 14 | 15 | 15 | 78 | 85 | 80 |
| | 6. | 97·8 | 99 | 99 | 52 | 54 | 58 | 13 | 14 | 15 | 76 | 85 | 81 |
| | 7. | 98·2 | 99 | 99·6 | 56 | 58 | 66 | 14 | 15 | 15 | 78 | 86 | 81 |
| | 8. | 98·1 | 99·1 | 99 | 56 | 54 | 60 | 14 | 16 | 15 | 79 | 85 | 80 |
| | 9. | 98·2 | ..... | ..... | 54 | ..... | ..... | 15 | ..... | ..... | 79 | | |
| | 10. | 98·3 | 98·9 | 98·7 | 66 | 54 | 58 | 15 | 15 | 15 | 77 | 83 | 80 |
| | 11. | 97·9 | 99·1 | 99·2 | 54 | 54 | 58 | 14 | 15 | 16 | 77 | 86 | 81 |
| | 12. | 98·1 | 99·3 | 99·1 | 54 | 56 | 58 | 14 | 15 | 15 | 79 | 86 | 82 |
| | 13. | 98·2 | 98·9 | 98 9 | 56 | 54 | 60 | 14 | 14 | 15 | 79 | 86 | 83 |
| | 14. | 98·2 | 99 | 99·6 | 56 | 58 | 62 | 14 | 15 | 15 | 80 | 85 | 82 |
| | 15. | 98 | 99·2 | 98·8 | 56 | 58 | 62 | 14 | 15 | 16 | 79 | 86 | 80 |
| | 16. | 98·2 | ..... | ..... | 56 | ..... | ..... | 14 | ..... | ..... | 79 | | |
| | 17. | 98·2 | 99·7 | 99·7 | 58 | 60 | 58 | 14 | 14 | 14 | 79 | 84 | 81 |
| | 18. | 98·1 | 99·2 | 99·1 | 54 | 58 | 58 | 15 | 14 | 15 | 79 | 86 | 79 |
| | 19. | 98·1 | 99·3 | 99·2 | 54 | 56 | 56 | 14 | 15 | 15 | 79 | 86 | 81 |
| | 20. | 98·2 | 99 | ..... | 54 | 54 | ..... | 14 | 15 | ..... | 78 | 81 | |
| | 22. | 98·2 | 99·1 | 99·5 | 54 | 56 | 66 | 14 | 16 | 15 | 80 | 87 | 82 |
| | 23. | 98·1 | ..... | ..... | 56 | ..... | ..... | 14 | ..... | ..... | 78 | | |
| | 24. | 98·1 | 99·4 | 99·4 | 60 | 60 | 60 | 14 | 16 | 15 | 77 | 86 | 82 |
| | 25. | 98·1 | 99·4 | 98·8 | 56 | 56 | 54 | 14 | 15 | 15 | 79 | 86 | 82 |
| | 26. | 98·2 | 99·3 | 99·2 | 54 | 66 | 60 | 14 | 16 | 15 | 79 | 87 | 82 |
| | 27. | 98·1 | 99·1 | 99·2 | 52 | 60 | 56 | 13 | 15 | 15 | 78 | 86 | 79 |
| | 28. | 98·1 | 99·4 | 99·6 | 56 | 60 | 66 | 14 | 15 | 15 | 78 | 86 | 82 |
| | 29. | 98·2 | ..... | 98·9 | 56 | ..... | 70 | 14 | ..... | 14 | 79 | ..... | 80 |
| | 30. | 98·2 | ..... | 99·4 | 56 | ..... | 66 | 14 | ..... | 14 | 79 | ..... | 82 |
| | 31. | 98·2 | 99·1 | 99·4 | 58 | 60 | 66 | 14 | 15 | 14 | 80 | 87 | 82 |
| | | 98·1 | 99·1 | 99·1 | 55·4 | 56·3 | 59·5 | 13·9 | 15 | 14·7 | 78·4 | 85·3 | 80·9 |

| | | Temp. under the tongue. | | | Pulse. | | | Respirations. | | | Temperature of room. | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | 6–7 A.M. | 12–2 P.M. | 9–11 P.M. | 6–7 A.M. | 12–2 P.M. | 9–11 P.M. | 6–7 A.M. | 12–2 P.M. | 9–11 P.M. | 6–7 A.M. | 12–2 P.M. | 9–11 P.M. |
| September 1848. | 1. | 98° | 99°·2 | 99° | 52 | 56 | 64 | 14 | 15 | 16 | 78° | 87° | 81° |
| | 2. | 98·1 | 99 | 99·2 | 54 | 52 | 60 | 14 | 15 | 16 | 78 | 88 | 81 |
| | 3. | 98 | 99·3 | 99 | 52 | 54 | 60 | 14 | 14 | 14 | 79 | 88 | 84 |
| | 4. | 98·1 | 99·6 | 99·4 | 52 | 62 | 60 | 14 | 14 | 15 | 80 | 87 | 82 |
| | 5. | 98·2 | 99·4 | 99·4 | 56 | 66 | 64 | 14 | 15 | 16 | 79 | 87 | 80 |
| | 6. | 98 | ..... | 99·2 | 54 | ..... | 64 | 14 | ..... | 15 | 79 | ..... | 81 |
| | 7. | 98·2 | 99·6 | 99·6 | 54 | 60 | 62 | 14 | 16 | 15 | 78 | 88 | 82 |
| | 8. | 98·5 | 99·5 | 99·2 | 56 | 60 | 58 | 14 | 15 | 15 | 79 | 88 | 86 |
| | 9. | 98·3 | 99·5 | 99·6 | 56 | 60 | 66 | 15 | 15 | 15 | 83 | 89 | 84 |
| | 10. | 98·3 | 99 | 99·3 | 56 | 56 | 66 | 15 | 16 | 15 | 80 | 89 | 82 |
| | 11. | 98·3 | 97·9 | 99·2 | 56 | 60 | 66 | 14 | 15 | 15 | 80 | 89 | 82 |
| | 12. | 97·9 | 99·2 | 99·3 | 52 | 58 | 60 | 14 | 15 | 14 | 80 | 88 | 83 |
| | 13. | 98·1 | ..... | ..... | 54 | ..... | ..... | 14 | ..... | ..... | 79 | | |
| | 14. | 98 | 99·3 | 99 | 56 | 60 | 62 | 14 | 15 | 15 | 78 | 86 | 81 |
| | 15. | 98·5 | 99·2 | 98·9 | 54 | 56 | 72 | 14 | 15 | 16 | 79 | 85 | 81 |
| | 17. | 98 | 99 | 98·9 | 54 | 54 | 66 | 14 | 15 | 15 | 76 | 85 | 82 |
| | 18. | 98·3 | 99·4 | 99·9 | 54 | 58 | 74 | 14 | 15 | 16 | 79 | 84 | 82 |
| | 19. | 98·5 | 98·8 | 99·3 | 58 | 56 | 70 | 14 | 15 | 14 | 79 | 80 | 81 |
| | 20. | 98·3 | 98·9 | 98·7 | 58 | 54 | 66 | 14 | 15 | 16 | 80 | 84 | 82 |
| | 21. | 98·3 | 99 | 98·8 | 58 | 52 | 56 | 14 | 15 | 16 | 81 | 86 | 82 |
| | 22. | 98·1 | 98·7 | 99·2 | 52 | 52 | 60 | 14 | 15 | 16 | 81 | 86 | 82 |
| | 23. | 98 | 98·9 | ..... | 52 | 56 | ..... | 14 | 16 | ..... | 78 | 86 | |
| | 24. | 98·5 | 98·7 | 99·1 | 62 | 56 | 62 | 14 | 15 | 15 | 80 | 86 | 80 |
| | 25. | 98 | 99·3 | 99·1 | 52 | 56 | 56 | 14 | 16 | 15 | 78 | 85 | 82 |
| | 26. | 98·2 | 99·2 | 98·8 | 54 | 52 | 56 | 14 | 15 | 15 | 78 | 85 | 80 |
| | 27. | 98·1 | ..... | ..... | 52 | ..... | ..... | 14 | ..... | ..... | 77 | | |
| | 28. | 98·3 | 98·8 | 99·3 | 54 | 56 | 58 | 14 | 16 | 15 | 75 | 85 | 80 |
| | 29. | 98·5 | 99·2 | 99·3 | 54 | 58 | 60 | 14 | 15 | 15 | 78 | 86 | 82 |
| | 30. | 98·2 | 98·8 | 99 | 52 | 58 | 66 | 14 | 16 | 15 | 79 | 85 | 82 |
| | | 98·1 | 99·1 | 99·1 | 54·4 | 57·3 | 60·4 | 14 | 15 | 15·2 | 78·9 | 86·2 | 81·7 |
| October 1848. | 1. | 98·3 | 98·8 | 98·8 | 56 | 56 | 66 | 14 | 15 | 16 | 79 | 86 | 83 |
| | 2. | 98·2 | 99 | 98·7 | 52 | 56 | 60 | 14 | 14 | 15 | 79 | 82 | 80 |
| | 3. | 98·2 | 99 | ..... | 52 | 56 | ..... | 14 | 15 | ..... | 78 | 86 | |
| | 4. | 98·4 | 99·3 | 99·2 | 60 | 56 | 60 | 15 | 15 | 15 | 79 | 87 | 84 |
| | 5. | 98·5 | ..... | 99·3 | 54 | ..... | 72 | 14 | ..... | 15 | 82 | ..... | 83 |
| | 6. | 98·1 | 99·3 | 99·1 | 50 | 56 | 58 | 14 | 16 | 15 | 80 | 87 | 82 |
| | 7. | 98·3 | 99·2 | 99·4 | 54 | 54 | 60 | 15 | 15 | 15 | 80 | 87 | 80 |
| | 8. | 97·9 | 99·1 | 98·8 | 52 | 58 | 58 | 14 | 16 | 15 | 78 | 84 | 80 |
| | 9. | 98·1 | 99·4 | 99·4 | 54 | 56 | 60 | 14 | 15 | 15 | 76 | 87 | 81 |
| | 10. | 97·9 | 99·2 | 98·7 | 54 | 52 | 58 | 15 | 15 | 15 | 80 | 84 | 81 |
| | 11. | 98·3 | 99·5 | 99·9 | 54 | 58 | 60 | 14 | 16 | 15 | 79 | 87 | 81 |
| | 12. | 98·1 | 99·4 | 99·3 | 54 | 58 | 64 | 15 | 15 | 16 | 79 | 86 | 80 |
| | 13. | 98·1 | 99 | 99·1 | 56 | 58 | 62 | 14 | 16 | 15 | 79 | 87 | 78 |
| | 14. | 98·3 | 99·3 | ..... | 54 | 58 | ..... | 14 | 16 | ..... | 78 | 88 | |
| | 15. | 98·2 | 98·9 | 99·3 | 56 | 58 | 66 | 14 | 14 | 16 | 78 | 86 | 82 |
| | 16. | 97·9 | 98·8 | 98·6 | 54 | 52 | 58 | 14 | 14 | 15 | 80 | 80 | 78 |
| | 17. | 98 | 99·1 | 99 | 52 | 54 | 60 | 14 | 16 | 15 | 77 | 86 | 80 |
| | 18. | 98·5 | ..... | 98·6 | 58 | ..... | 58 | 15 | ..... | 16 | 78 | ..... | 80 |
| | 19. | 98·1 | 98·9 | 99·2 | 56 | 58 | 62 | 15 | 15 | 16 | 78 | 85 | 82 |
| | 20. | 98·1 | 98·9 | 98·7 | 58 | 58 | 64 | 14 | 15 | 16 | 79 | 80 | 79 |
| | 21. | 98·4 | 98·6 | 98·9 | 54 | 52 | 62 | 15 | 15 | 16 | 77 | 86 | 82 |
| | 22. | 98·3 | ..... | 99·1 | 56 | ..... | 58 | 14 | ..... | 16 | 79 | ..... | 80 |
| | 23. | 98·2 | 98·8 | 98·9 | 52 | 52 | 56 | 14 | 15 | 15 | 79 | 82 | 80 |
| | 24. | 98·4 | 99·1 | 98·4 | 56 | 54 | 60 | 14 | 15 | 15 | 77 | 83 | 79 |
| | 25. | 98·5 | ..... | ..... | 52 | ..... | ..... | 14 | ..... | ..... | 77 | | |
| | 26. | 98·2 | 99·3 | 99·3 | 58 | 56 | 66 | 14 | 15 | 15 | 76 | 86 | 82 |
| | 27. | 98 | 99·1 | 98·8 | 54 | 56 | 58 | 14 | 14 | 15 | 77 | 86 | 81 |
| | 28. | 98·1 | 99·1 | 99·1 | 52 | 56 | 62 | 14 | 15 | 16 | 78 | 87 | 83 |
| | 29. | 98·4 | 99·5 | ..... | 54 | 58 | ..... | 14 | 15 | ..... | 80 | 83 | |
| | 31. | 98·3 | 98·8 | 98·8 | 52 | 52 | 60 | 14 | 15 | 15 | 78 | 77 | 79 |
| | | 98·2 | 99·1 | 99 | 54·3 | 55·8 | 61 | 14·2 | 15 | 15·3 | 78·9 | 84·8 | 80·8 |

FRANKLIN INSTITUTE LIBRARY

| | | Temp. under the tongue. | | | Pulse. | | | Respirations. | | | Temperature of room. | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | 6–7 A.M. | 12–2 P.M. | 9–11 P.M. | 6–7 A.M. | 12–2 P.M. | 9–11 P.M. | 6–7 A.M. | 12–2 P.M. | 9–11 P.M. | 6–7 A.M. | 12–2 P.M. | 9–11 P.M. |
| November 1848. | 1. | 98°2 | 99°3 | 99° | 50 | 58 | 60 | 14 | 16 | 15 | 77° | 85° | 81° |
| | 2. | 98·1 | 99 | ..... | 52 | 56 | ..... | 14 | 15 | ..... | 78 | 82 | |
| | 3. | 98·5 | 98·8 | 98·5 | 58 | 56 | 58 | 15 | 15 | 15 | 77 | 82 | 78 |
| | 4. | 98·2 | 99·1 | ..... | 50 | 58 | ..... | 14 | 15 | ..... | 77 | 84 | |
| | 5. | 98·1 | 99·4 | 98·5 | 62 | 58 | 58 | 15 | 16 | 16 | 78 | 86 | 79 |
| | 6. | 98·1 | 99·2 | 98·4 | 56 | 58 | 58 | 14 | 15 | 15 | 77 | 83 | 78 |
| | 7. | 98 | 98·9 | ..... | 58 | 56 | ..... | 14 | 15 | ..... | 77 | 83 | |
| | 8. | 98·2 | 99·3 | 98·9 | 54 | 62 | 62 | 14 | 16 | 16 | 76 | 83 | 79 |
| | 9. | 98·1 | ..... | ..... | 58 | ..... | ..... | 14 | ..... | ..... | 78 | | |
| | | 98·1 | 99·1 | 98·6 | 55·3 | 57·7 | 59·2 | 14·2 | 15·4 | 15·4 | 77 | 83·5 | 79 |

## *Postscript to Dr.* DAVY'S *Paper on the Temperature of Man.*

Received May 8,—Read May 16, 1850.

The thermometer with which the preceding observations were made was broken immediately after my return to England, when travelling by railway, no special precaution having been taken in the packing of it, as by inclosing it in elastic horse-hair; and in consequence I had not the means at once of making further trials on temperature for the purpose of comparison. Recently, having had another thermometer constructed as delicate as that before used and divided with the same minuteness—each degree of FAHRENHEIT into ten parts—I have been enabled to continue the trials; as yet, however, only for one month, that of April, without interruption. They have been made thrice daily, at about the same hours as those recorded in my former paper. The results, under ordinary circumstances of health, exercise, &c., have accorded with those then obtained, the highest temperature having been found to be immediately on rising in the morning after the night's rest, and the lowest at night, just before retiring to rest. This accordance will probably be received in proof that the difference of results in the West Indies and in England has been mainly owing to difference of climate and the habits of life connected therewith; and apart from these, to no change in the individual, the subject of the trials.

*May* 4, 1850.

## XXIII. *On the Oils produced by the Action of Sulphuric Acid upon various Classes of Vegetables.* By JOHN STENHOUSE, *Esq., Ph.D., F.R.S.*

Received March 28,—Read April 18, 1850.

NEARLY thirty years ago DÖBEREINER observed, when preparing formic acid by distilling a mixture of starch, peroxide of manganese and sulphuric acid, that the liquid which passed into the receiver contained a small quantity of oil which rendered it turbid. To this oil DÖBEREINER gave the somewhat fanciful name of "artificial oil of ants," though the very limited quantity in which he was enabled to procure it prevented him from determining almost any of its properties.

My attention was first directed to the subject in 1840, when I found that the oxide of manganese was quite unnecessary, and that this oil could be readily prepared by operating on most vegetable substances with slightly diluted sulphuric acid. In this way I succeeded in procuring considerable quantities of the oil from wheaten and oaten flour, from saw-dust, bran, chaff, &c., and was thus enabled to subject it to a more detailed examination. The oil, when analysed, was found to have the formula $C_5 H_2 O_2$, or the triple of this, $C_{15} H_6 O_6$, presenting the remarkable circumstance of a volatile aromatic oil containing oxygen and hydrogen in the proportions to form water. This proved it to differ essentially from other known oils, all of which contain an excess of hydrogen.

Dr. FOWNES took up the subject in 1845, and made the interesting discovery, that when the oil was agitated with a considerable excess of aqueous ammonia and set aside for a few hours, it was converted into a bulky crystalline mass, becoming $C_{15} H_6 O_3 N_1$ by the absorption of one equivalent of nitrogen and the elimination of three equivalents of oxygen which had united with the hydrogen of the ammonia. To this compound Dr. FOWNES gave the name of furfuramide, and to the oil itself that of furfurol. Dr. FOWNES also made the still more important discovery, that when furfuramide is boiled for a short time with dilute potash lye, it is without any alteration of its per-centage composition, but merely by a new arrangement of its component elements converted into a crystalline base, furfurine, the formula of which is $C_{30} H_{12} O_6 N_2$.

Furfurol was also examined in 1848 by M. CAHOURS, who, in addition to confirming Dr. FOWNES's discoveries, observed that when a stream of sulphuretted hydrogen is passed through an alcoholic solution of furfuramide, the half of the oxygen in that body is removed and replaced by sulphur. This new compound, which he called thiofurfurol, precipitates as a crystalline powder and has the formula $C_{10} H_4 S_2 O_2$.

M. Cahours also found that when thiofurfurol is distilled it is entirely decomposed, producing a beautifully crystalline substance containing no sulphur. Its formula is $C_{18}$ $H_8$ $O_4$, or some multiple of these numbers.

As furfurol, both from its composition and properties, occupies a somewhat isolated position in regard to other essential oils, it appeared to me not improbable that it would be found on more extended investigation not to stand really alone in nature, but to be one of a series of similar oils. This consideration induced me about six months ago to resume its examination, and, as will presently be seen, the expectation I had formed was not altogether without foundation. Before detailing these researches, however, I shall shortly state a few additional observations which I have recently made upon furfurol and some of its compounds.

Furfurol is most advantageously prepared by distilling one part of bran with rather more than half its weight of sulphuric acid diluted with two parts of water. I find, however, that furfurol may be also produced with muriatic acid, though in practice it is more advantageous to employ sulphuric acid, as it remains in the retort and does not distil over with the oil, as is the case with muriatic acid.

The arrangement for preparing furfurol on a considerable scale which I have found most suitable, is the following. About 32 lbs. of wheaten bran and 20 lbs. of sulphuric acid diluted with twice its bulk of water, were introduced into a large three-necked Woulf's-bottle made of salt-glazed earthenware. These bottles are usually employed as condensers in the manufacture of muriatic and nitric acids, and are capable of containing from twenty to thirty gallons each. A leaden pipe connected with a tolerably large steam-boiler is passed through a perforated cork to near the bottom of the stone-ware bottle, from the top of which, on the opposite side, a second pipe is carried into the worm of a condensing apparatus, which is kept cool by means of a plentiful supply of cold water. The steam from the boiler is then passed through the mixture of the acid and the bran, which soon becomes hot and then boils, when a weak aqueous solution of furfurol passes over into the condensing apparatus and is collected in the usual way: the whole of the oil usually comes over in from 16 to 18 hours. This weak liquid is pretty strongly acid, and requires to be exactly neutralized with pounded chalk, and to be rectified till about the half of it has distilled over. It is important to avoid adding an excess of chalk, and rather to leave the liquid slightly acid, as an excess of chalk sets free the ammonia present in the solution, which, combining with the furfurol, oxidizes it, and thus greatly diminishes the amount which would otherwise be obtained. The first portion only of the liquid which distils over is preserved, as that which remains in the still contains scarcely any oil. The now somewhat stronger solution of the oil is then supersaturated with common salt and again cautiously rectified. The first portions of the liquid which come over yield a considerable amount of oil, and by repeatedly saturating the weaker solutions with salt and rectifying, the whole of the oil they contain may be pretty readily obtained. The 32 lbs. of bran yielded from 12 to 13 ozs. of furfurol. I have invariably found

that crude furfurol always contains a considerable quantity of acetone, a circumstance which appears to have escaped the notice of preceding experimenters.

In addition to the substances which had been previously employed for preparing furfurol, I may mention that I have obtained it from oil-cake, from cocoa-nut husk, and from the raspings of mahogany. The two first substances, from their cheapness and the large quantity of oil which they yield, are very well fitted for this purpose. The furfurol from mahogany, though smaller in quantity, is pretty free from resin, and is therefore more readily purified than that from bran or oil-cake.

Crude furfurol, from whatever source it is prepared, always contains a quantity of another essential oil, which has a much higher boiling-point and does not form a crystallizable amide. This second oil is exceedingly oxidizable, and every time it is distilled a considerable portion of it is changed into a brownish resin, which instantly strikes a deep red colour when mixed with a few drops of cold muriatic, nitric or sulphuric acids. In a previous paper I mentioned this reaction as characteristic of furfurol, and in this statement I have been followed by Dr. Fownes. It is a mistake, however, as furfurol never yields this deep red colour with acids when it has been freed from this accompanying oil, which, as it appears to be invariably formed along with furfurol, I shall call meta-furfurol.

Furfurol may be pretty readily freed from this oil by being repeatedly rectified with water; the meta-furfurol, as it is much less volatile, remains chiefly in the retort, where it is rapidly oxidized. Two, or at most three rectifications, are therefore sufficient to render furfurol perfectly free from meta-furfurol. The absence of meta-furfurol may be easily ascertained by boiling an aqueous solution of furfurol with an excess of lime for a few minutes. The furfurol is immediately oxidized, and the solution acquires a deep yellow colour. If this solution is then treated with an excess of muriatic or sulphuric acids, not the slightest reddening is produced if the furfurol is free from meta-furfurol, but if even a trace of this latter oil is present, the characteristic deep red colour immediately appears. When pure furfurol is added to strong muriatic or sulphuric acid in the cold, it instantly changes to a brownish black colour, being rapidly oxidized, but not the slightest reddening is visible. Meta-furfurol is also much less soluble in water than furfurol. It also dissolves with difficulty in aqueous ammonia, with which it forms no crystallizable amide, but is rapidly changed into a brownish amorphous resin. When meta-furfurol is digested with strong nitric acid, it is changed into a nitrogenated crystallizable acid, which is either oxypicric acid, or a closely analogous compound. It yields chloropicrine when it is treated with either muriatic acid or hypochlorite of lime. Furfurol, on the contrary, when digested with nitric acid, is wholly converted into oxalic acid. Crude furfurol made from bran contains a good deal of meta-furfurol, but the crude furfurol from mahogany and other hard woods is comparatively free from meta-furfurol.

Furfurol stains the skin of a deep yellow colour, but if the part moistened with it is also touched with a few drops of aniline it becomes of a bright red colour. The

same effect is also produced when paper, white silk, linen or cotton cloth is similarly treated. The red colour begins to appear in the course of a few minutes and remains for some days, after which it changes to a brownish yellow. I regard this coloration as an effect of mutual oxidation, for I have failed in procuring any crystalline compound similar to furfuramide, either with aniline or with some others of the volatile alkaloids.

*Double Chloride of Furfurine and Platinum.*

Dr. Fownes, who first prepared this salt, states that a solution of hydrochlorate of furfurine, when treated with a slight excess of bichloride of platinum, forms a nearly insoluble bright yellow precipitate. This is true only when the double salt is produced by mixing cold aqueous solutions. When however chloride of platinum is poured into a hot solution of muriate of furfurine in weak spirits, the same salt is slowly deposited on the cooling of the liquid in bright yellow needles, often an inch in length, and closely resembling carbazotate of potash in appearance.

I. 0·4265 grm. salt prepared in the way just described and dried *in vacuo*, gave 0·089 platinum=20·86 per cent. platinum.

II. 0·326 grm. salt prepared in the way just described and dried *in vacuo*, gave 0·0670 platinum=20·55 per cent. platinum.

The calculated quantity for the formula $C_{30}\,H_{12}\,N_2\,O_6+HCl+PtCl$, is 20·82 platinum per cent. Dr. Fownes found 20·45. There can be no doubt, therefore, notwithstanding the difference in their mode of preparation and crystalline state, that both salts are identical.

*Nitrate of Furfurine.*

Dr. Fownes also analysed nitrate of furfurine crystallized from an aqueous solution. It then forms irregular long acicular crystals arranged in stars. From alcohol it is deposited in large very regular rhombic prisms, which possess great lustre, and may be readily obtained nearly an inch in length. If the spirituous solution out of which the salt has crystallized is very strong, its crystals, which are at first perfectly transparent, on being kept for some time in a dry atmosphere become quite opake, but if they are crystallized out of dilute spirits they retain their transparency.

0·2905 grm. salt crystallized out of spirits and dried *in vacuo*, gave 0·580 carbonic acid and 0·109 water.

| | | Found numbers. |
|---|---|---|
| C | 54·35 | 54·45 |
| H | 3·93 | 4·16 |

The formula of this salt is $C_{30}\,H_{12}\,N_2\,O_6+NO_5+HO$.

It is plain therefore that the nitrate, whether it is crystallized out of water or weak spirits, does not vary in composition after it has been dried *in vacuo*.

*Fucusol.*

It has been satisfactorily ascertained by various experimenters that furfurol is not produced by the action of acids on either the amylaceous or saccharine portions of the vegetables which yield it. Neither do the lignine, the gluten or the other nitrogenous principles of plants, at all contribute to its formation. The source of furfurol requires to be referred therefore to some other very generally diffused proximate principle. Dr. Fownes has thrown out the conjecture, that the substance which yields furfurol is the *matière incrustante* of M. Payen, viz. the matter with which the interior of the cells of plants is lined. This is a hypothesis which I feel disposed to regard as exceedingly probable, though it must be confessed that the *matière incrustante* is not a simple proximate principle, but consists, according to M. Payen, of four kindred substances, no one of which the present state of our knowledge enables us with any great degree of certainty to prepare absolutely pure.

Now as it appeared very probable that the *matière incrustante* of the different great classes of plants would be found on examination to be analogous but not identical, I thought it likely that the oils derivable from them would also prove not identical with furfurol, though probably very analogous to it in their nature and properties. The Algæ therefore, as possessing a structure which differs very widely from ordinary herbaceous plants, were selected in the first instance as a very good test of the truth of this hypothesis. A quantity of the commonest sea-weeds, consisting chiefly of *Fucus nodosus*, *F. vesiculosus*, *F. serratus*, &c., were cut into pieces and introduced along with a good deal of sulphuric acid diluted with two parts of water, into the apparatus described in a preceding part of this paper. Steam was then passed through the mixture during sixteen to eighteen hours, so long indeed as the liquid which distilled over appeared to contain any considerable amount of oil. The acid liquor which collected in the receiver was nearly neutralized with pounded chalk, and the oil separated from it exactly in the same way as with furfurol.

The crude oil from Fuci, which I shall call fucusol, always contained a considerable amount of acetone, which required to be removed by washing it with water, carefully rectifying it at a low temperature, and rejecting the first portions of the oil which distilled over. I may mention in passing, that I have invariably found acetone to be a constant product, and that to a considerable extent, of the action of sulphuric acid upon vegetable substances. Crude fucusol also contains a quantity of meta-furfurol, or at any rate of a very similar oil, from which it requires to be freed by being repeatedly rectified along with water, precisely in the same way as furfurol. The sea-weeds yielded only about a fourth part of the oil which a similar quantity of bran would have done.

When dried by standing over fused chloride of calcium and then rectified, fucusol possesses the following properties. When newly distilled it is nearly colourless, but in a few days, especially if exposed to the light, it becomes brownish yellow, and in the course of a few weeks of a deep brown colour. If the fucusol is not quite free

from meta-furfurol it colours still more rapidly, and in the course of a few days becomes perfectly black; pure fucusol may however be kept in hermetically sealed vessels for any length of time without change. Its specific gravity at 13½° C. is 1·150. I found that of furfurol at the same temperature 1·1636. Dr. Fownes makes it 1·1648 at 60° Fahr. When heated in a glass retort containing some thin slips of copper, fucusol boils regularly and uniformly between 171° and 172° C. As the boiling proceeds, the oil grows coloured, and a small portion of it is destroyed by every distillation, being converted into a dark-coloured resin which remains in the retort. I found the boiling-point of furfurol from bran to be 166° C., while Messrs. Fownes and Cahours found it only to be 162½° C. Neither of these gentlemen make any mention of the acetone which is always present in crude furfurol; I do not however affirm that the oil examined by these chemists contained acetone, though, judging from the lowness of its boiling-point, I think this by no means improbable.

Fucusol very closely resembles furfurol both in its taste and smell, though the odour of fucusol is much fainter and more agreeable. Fucusol requires 14 parts by weight of water at 13° C. to dissolve it, while furfurol dissolves in 11 parts of water at the same temperature. Furfurol dissolves in 9 times its weight of pretty concentrated liquor ammoniæ at 13½° C., while fucusol requires 12 times its weight of the same liquid for its solution. The difference therefore between the oils in regard to solubility is considerable. Fucusol also shows much less stability, and is therefore more readily decomposed than furfurol. With muriatic acid, fucusol strikes a pale green colour, which on standing becomes greenish black. Nitric acid gives it a pale yellow colour, sulphuric acid a greenish brown, which in time becomes bluish black. Solution of potash turns it first yellow, then pale red, and lastly dark red. Lime and soda produce similar results. If however the fucusol contains any meta-furfurol, it instantly strikes a bright red colour with either muriatic, nitric or sulphuric acids. Fucusol stains the skin of a deep yellow colour, which is tolerably persistent. If these yellow spots are moistened with aniline, they immediately become bright red, exhibiting the same reaction as furfurol. Pure fucusol when dried was analysed.

I. 0·2605 grm. oil gave 0·594 carbonic acid and 0·104 water.

II. 0·254 grm. oil gave 0·583 carbonic acid and 0·105 water.

III. 0·228 grm. oil gave 0·521 carbonic acid and 0·092 water.

| | Calculated numbers. | | Found numbers. | | |
|---|---|---|---|---|---|
| | | | I. | II. | III. |
| 15 C | 1125 | 62·50 | 62·19 | 62·59 | 62·32 |
| 6 H | 75 | 4·17 | 4·43 | 4·59 | 4·48 |
| 6 O | 600 | 33·33 | 33·38 | 32·82 | 33·20 |
| | 1800 | 100·00 | 100·00 | 100·00 | 100·00 |

It is plain therefore, from the results of these analyses, that the formula of fucusol is $C_{15}\,H_6\,O_6$, and consequently that furfurol and fucusol are isomeric compounds.

*Fucusamide.*

When fucusol is intimately mixed with eight or nine times its bulk of pretty concentrated aqua ammoniæ, the oil and ammonia combine to form a slightly yellow crystalline mass. As fucusol is less soluble in liquor ammoniæ than furfurol, it requires a greater quantity of ammonia, and both liquids must be brought thoroughly into contact, otherwise the fucusol is apt to be acted on chiefly at the surface, while the interior of the mass contains a portion of nearly unaltered oil. The amide, which I shall call fucusamide, may be readily obtained in pretty long needles radiating from a centre by crystallizing it out of hot spirits of wine, in which it is very soluble. In appearance it closely resembles furfuramide, but is a much less stable compound.

I. 0·413 grm. amide dried *in vacuo*, gave 1·02 carbonic acid and 0·174 water.

II. 0·332 grm. amide dried *in vacuo*, gave 0·809 carbonic acid and 0·138 water.

III. 0·357 grm. amide dried *in vacuo*, gave 0·884 carbonic acid and 0·152 water.

0·402 grm. amide dried *in vacuo* by Will's method, gave 0·655 double chloride of platinum and ammonia=10·23 per cent. nitrogen.

| | Calculated numbers. | | I. | II. | III. |
|---|---|---|---|---|---|
| 15 C | 1125 | 67·17 | 67·35 | 66·46 | 67·53 |
| 6 H | 75 | 4·47 | 4·67 | 4·61 | 4·72 |
| 3 O | 300 | 17·91 | 17·75 | 18·70 | 17·52 |
| 1 N | 175 | 10·45 | 10·23 | 10·23 | 10·23 |
| | 1675 | 100·00 | 100·00 | 100·00 | 100·00 |

The formula of fucusamide is therefore $C_{15}\ H_6\ O_3\ N_1$, being identical with that of furfuramide.

*Thiofucusol.*

M. Cahours observed, that when furfuramide is dissolved in spirits of wine, and a current of sulphuretted hydrogen sent through the solution, a whitish granular precipitate falls, which consists of a compound in which the half of the oxygen in furfuramide is replaced by sulphur. On passing a current of sulphuretted hydrogen through a cold alcoholic solution of fucusamide, a corresponding compound was formed, which closely resembles thiofurfurol in appearance and properties.

0·477 grm. thiofucusol dried *in vacuo*, gave 0·929 carbonic acid and 0·170 water.

0·6045 grm. thiofucusol dried *in vacuo*, gave 1·26 sulphate of baryta=28·65 sulphur.

| | Calculated numbers. | | Found numbers. |
|---|---|---|---|
| 10 C | 705 | 53·58 | 53·12 |
| 4 H | 50 | 3·58 | 3·95 |
| 2 S | 400 | 28·58 | 28·65 |
| 2 O | 200 | 14·26 | 14·28 |
| | 1355 | 100·00 | 100·00 |

*Pyrofucusol.*

When thiofurfurol is destructively distilled it is decomposed with the formation of a curious substance called pyrofurfurol, which crystallizes in long needles and contains no sulphur. M. Cahours's formula for it is $C_{18} H_8 O_4$. Thiofucusol, when distilled, yields a similar compound, which I shall call pyrofucusol. It also crystallizes in long needles, and has probably the same composition as pyrofurfurol, though from the very small quantity at my disposal I was unable to ascertain this by analysis.

*Fucusine.*

When pure fucusamide, which should be nearly colourless, having only a slightly yellowish shade, is boiled for 20 minutes or half an hour with moderately strong soda or potash lye, no ammonia is evolved, and the amide is changed into a light brownish-coloured oil, which solidifies on the cooling of the liquid. It consists of a salifiable base, which I shall call fucusine, combined with a quantity of a brownish resin. This crude fucusine, when separated from the lye in which it has been boiled, is always soft, even at low temperatures, and does not exhibit the least approach to crystallization. At the temperature of 10° C. it is exceedingly tenacious, and may be easily drawn into threads, which resemble those of half-dried molasses. If we attempt to separate fucusine from adhering resin by boiling it with water and filtering, we find, on the cooling of the solution, that a yellowish amorphous resin is deposited on the sides and bottom of the vessel. This method therefore, by which furfurine is so readily purified and obtained in a crystalline state, does not at all succeed with fucusine. Though I made many attempts, I was equally unsuccessful in crystallizing crude fucusine either from alcoholic or etherial solutions. If the fucusamide which has been employed in the preparation of fucusine is so impure as to have a brownish colour, it is next to impossible to extract any pure fucusine from it. In this repect therefore fucusine differs very considerably from furfurine, which, even when very impure, solidifies on cooling to a hard crystalline mass; and if it is digested with a little animal charcoal and crystallized two or three times out of boiling water, it is deposited on the cooling of its solution in long slender colourless needles. Fucusine, on the other hand, so long as it is mixed with a little resinous matter, does not crystallize at all, and even when perfectly pure does not crystallize nearly so readily as the analogous base.

The way in which I succeeded in purifying fucusine, was by preparing some of its salts, which crystallize pretty readily, even from impure solutions. The salt best adapted for this purpose is the nitrate, and the mode of proceeding was the following. The crude fucusine was digested with a very slight excess of dilute nitric acid at a heat little higher than was necessary to melt it. The crude fucusine was constantly stirred with a spatula, so as to bring every portion of it into contact with the acid liquid. The mixture was then allowed to cool for a few minutes till the resinous matter had solidified, when the liquid portion was poured off into a second basin, where it soon deposited a quantity of hard shining crystals. By repeatedly digesting

the crude fucusine with the acid mother-liquors out of which the crystals of nitrate had been deposited, successive crops of crystals may be readily obtained. These are still further purified by being repeatedly crystallized out of hot water, and they may be easily obtained in large shining rhombic prisms when deposited from an alcoholic solution. By dissolving the colourless crystals of pure nitrate of fucusine in water, and slightly supersaturating the solution with ammonia, fucusine gradually subsides in white, short flattish prisms forming small stars.

When pure fucusine is dissolved in boiling water, the solution, so soon as it begins to cool, grows turbid, and in the course of a few hours the fucusine is deposited in short flattish prisms arranged in fan-shaped figures on the sides and bottom of the vessel. Its mode of crystallizing strongly contrasts with that of furfurine, which, so soon as its solution begins to cool, forms long slender needles which in a short time fill the whole of the liquid. Furfurine may be obtained from pure furfuramide with little more than a trace of adhering resin, but even from nearly colourless fucusamide I was seldom able to procure much more than two-thirds of fucusine, the remainder being changed into a dark-coloured tenacious resin.

The cold aqueous solution of fucusine is distinctly alkaline to test-paper, and its alcoholic solution, as might have been expected, is still more strongly so. Fucusine and furfurine are nearly equally soluble in boiling water, but fucusine dissolves in 2·400 parts by weight of water at 8° C., while furfurine requires 4·800, or exactly twice the quantity at the same temperature. This is one reason that while a hot aqueous solution of furfurine, on cooling, is filled with long slender crystals of that base, a much smaller portion of fucusine crystallizes out, as twice as much of it is retained in the cold solution. Fucusine is however considerably less soluble in dilute spirits, at ordinary temperatures, than furfurine.

I. 0·393 grm. fucusine dried *in vacuo*, gave 0·97 carbonic acid and 0·162 water.

II. 0·457 grm. fucusine dried *in vacuo*, gave by Will's process 0·75 ammonio-chloride of platinum = 10·30 nitrogen.

| | Calculated numbers. | | Found numbers. |
|---|---|---|---|
| 30 C | 2250·0 | 67·17 | 67·30 |
| 12 H | 149·7 | 4·47 | 4·58 |
| 2 N | 350·4 | 10·45 | 10·30 |
| 6 O | 600·0 | 17·91 | 17·82 |
| | 3350·0 | 100·00 | 100·00 |

It is plain from the result of this analysis, that fucusine and furfurine are also isomeric compounds.

*Nitrate of Fucusine.*

This is one of the salts of fucusine which crystallizes most readily. I have already detailed the mode of preparing and purifying it, and shall not therefore repeat it again. When crystallized out of a hot aqueous solution, it forms long prisms tapering towards their extremities, and united by their broad ends so as to form large stars. But when crystallized out of spirits of wine, it forms large rhombic prisms of great regularity of structure and adamantine lustre. When deposited from strong spirits of wine, these

crystals become opake when dried, but when crystallized out of weak spirits, they retain their transparency. When dried under the air-pump and subjected to analysis, the salt was found to have the same formula as the corresponding salt of furfurine, viz. $C_{30}\,H_{12}\,N_2\,O_6+NO_5+HO$.

0·488 grm. salt gave 0·972 carbonic acid and 0·1875 water.

| | Calculated numbers. | Found numbers. |
|---|---|---|
| C | 54·30 | 54·32 |
| H | 3·99 | 4·26 |

When the nitrate of fucusine is heated in the water-bath to 100° C., it soon becomes coloured and decomposes.

Through the kindness of Professor W. H. Miller of Cambridge, which I have often formerly experienced, I am enabled to subjoin the annexed figures and measurements of the crystals of the nitrates of fucusine and furfurine.

*Nitrate of Fucusine.*

*Prismatic*:—The symbols of the simple forms are,—*a* 100, *u* 011, *m* 110, *s* 111.

The angles between normals to the faces are,—

| | ° | ′ |
|---|---|---|
| $uu'$ | 64 | 0 |
| $ma$ | 47 | 51 |
| $mm'$ | 84 | 18 |
| $sa$ | 68 | 6 |
| $su$ | 21 | 54 |
| $ss'$ | 43 | 48 |
| $ss''$ | 60 | 42 |
| $s's''$ | 71 | 0 |




*Cleavage*:—*a*, very perfect; *u*, *s*, less perfect.

*Nitrate of Furfurine.*

*Prismatic*:—The symbols of the simple forms are,—*a* 100, *b* 010, *e* 101, *t* 310, *n* 320, *s* 111: *a* truncates the edge $tt''$.

The angles between normals to the faces are,—

| | ° | ′ |
|---|---|---|
| $ea$ | 70 | 40 |
| $ee'$ | 38 | 40 |
| $nb$ | 47 | 50 |
| $tb$ | 65 | 40 |
| $ab$ | 90 | 0 |
| $nn'$ | 84 | 20 |
| $tt'$ | 48 | 40 |
| $sa$ | 72 | 8 |
| $ss'$ | 35 | 44 |
| $sb$ | 67 | 39 |
| $ss''$ | 44 | 42 |
| $s's''$ | 58 | 44 |

*Cleavage*:—*b*, very perfect; *a*, *t*, less perfect.

*Muriate of Fucusine.*

Muriate of fucusine is an extremely soluble salt, which crystallizes, when very concentrated, in short slender needles arranged in stars.

*The Double Platinum Salt.*

When bichloride of platinum is added to a cold aqueous solution of hydrochlorate of fucusine, a crystalline yellow precipitate immediately subsides. But if the solutions of the two salts are hot, and especially if some spirits of wine are added to the mixture, the double platinum salt is slowly deposited in large broad four-sided prisms. These prisms are very thin, having two broad sides and two very narrow ones. They are usually united together at the one extremity, while the other is square and regular. The double hydrochlorate of fucusine and platinum does not at all resemble in appearance the corresponding salt of furfurine, which, as formerly stated when crystallized out of weak spirits, forms long needle-shaped crystals like those of carbazotate of potash.

0·3733 grm. salt dried *in vacuo*, gave 0·518 carbonic acid and 0·109 HO.

0·6595 grm. salt dried *in vacuo*, gave 0·650 chloride of platinum and ammonia =0·4085 nitrogen.

0·640 grm. salt dried *in vacuo*, gave 0·580 chloride of silver=0·1434 CL.

I. 0·416 grm. salt gave 0·086 platinum=20·67 per cent.

II. 0·5025 grm. salt gave 0·1035 platinum=20·58 per cent.

III. 0·409 grm. salt gave 0·840 platinum=20·53 per cent.

| | Calculated numbers. | | Found numbers. |
|---|---|---|---|
| 30 C | 2250·0 | 37·97 | 37·84 |
| 13 H | 162·5 | 2·74 | 3·21 |
| 6 O | 600·0 | 10·12 | 9·70 |
| 2 N | 350·0 | 5·90 | 6·18 |
| 3 Cl | 1329·0 | 22·45 | 22·40 |
| Pt | 1233·5 | 20·82 | 20·67 |
| | 5925·0 | 100·00 | 100·00 |

The formula of the double platinum salt therefore is $C_{30}\,H_{12}\,N_2\,O_6+HCl+PtCl_2$.

*The Acid Oxalate of Fucusine.*

This salt may be pretty readily prepared from crude fucusine by digesting it with an excess of oxalic acid. The hot filtered solution deposits, on cooling, the acid oxalate in long needle-shaped crystals arranged in stars. These crystals are usually coloured at first, but by repeated digestions with animal charcoal they are rendered colourless, when they have a silky lustre. They are not very soluble in cold water, but readily dissolve in boiling water and in hot spirits. Their solution is distinctly acid to test-paper.

0·3155 grm. salt dried *in vacuo*, gave 0·664 carbonic acid and 0·120 water.
0·336 grm. salt dried *in vacuo*, gave 0·419 double chloride of Pt and ammonia.

| | Calculated numbers. | | Found numbers. |
|---|---|---|---|
| C | 34 | 57·01 | 57·08 |
| H | 14 | 4·06 | 4·22 |
| N | 2 | 7·74 | 7·82 |
| O | 14 | 31·19 | 30·88 |
| | | 100·00 | 100·00 |

The formula of this salt therefore is $C_{30}H_{12}N_2O_6+2C_2O_3+2HO$. It is the binoxalate of fucusine with two equivalents of water. The neutral oxalate is much more soluble than the acid salt, but the crystalline form of both salts is the same.

The perfect isomerism which subsists between furfurol and fucusol, extending as it does to the products of their decomposition, is certainly not a little astonishing, and may perhaps induce some chemists still to regard them as identical substances. I was, in fact, for a long time inclined to the same opinion, and it was only after a careful comparative examination of both oils, and especially of their respective bases, that I was led to conclude that they are only very analogous, but not identical compounds.

*Oil from Moss.*

A quantity of common Sphagnum was digested in a distilling apparatus with dilute sulphuric acid, exactly in the way already so fully described. It yielded a considerable quantity of an oil, which, so far as I could judge, is identical with fucusol. It formed amide with ammonia, which, when it was boiled with an alkaline lye, yielded a similar difficultly crystallizable base, whose double platinum salt crystallized in the same thin flat prisms as those of fucusine.

*Oil from Lichens.*

A quantity of *Lichen Islandicum*, along with several species of *Usnea*, *Ramalinia fraxinea*, &c., were also digested with sulphuric acid. They yielded an oil which appeared to be identical with fucusol, judging from its characters and those of its amide, base and platinum salt.

*Oil from Ferns.*

The common fern, *Pteris aquilina*, when digested with sulphuric acid, also yielded an oil which formed an amide and a base, crystallizing readily in long slender needles, closely resembling those of furfurine. I felt at first much inclined to regard this oil as identical with furfurol, but as the double platinum salt of its base does not crystallize in the same form as the corresponding salt of furfurine, but in broad flat prisms, I strongly suspect that it is different from both fucusol and furfurol.

The results of the preceding investigation, imperfect as they confessedly are, seem to me to indicate some curious botanical relations; for it appears highly probable that the *matière incrustante*, or some such principle, is the same in all phanerogamous

plants, as it yields an identical product of decomposition, viz. furfurol when it is digested with sulphuric or muriatic acids.

The *matière incrustante* in Fuci, on the other hand, though analogous, appears to be not identical with the corresponding principle in phanerogamous plants, as it yields fucusol instead of furfurol; and this seems also to be the case with the *matière incrustante* of mosses and lichens, both of which families approximate much more closely in their botanical structure to the Algæ than to ordinary phanerogamous plants. As might almost have been expected, therefore, both mosses and lichens appear to yield fucusol, or at any rate an exceedingly similar oil, which is certainly not furfurol. Ferns, on the contrary, whose woody structure differs from that of either mosses, algæ, or lichens, and approaches pretty closely to that of ordinary phanerogamous plants, appear to yield an oil with properties intermediate between those of furfurol and fucusol.

Note received September 4, 1850, from Professor Miller of Cambridge.

I consider it very probable that the crystals of nitrate of fucusine do not belong to the prismatic system, but are twin crystals of the oblique system. The faces of the form *s* are however too imperfect to settle this point.

The angles between normals to the faces are,—

| | ° | ′ |
|---|---|---|
| *ma* | 47 | 52 |
| *mm*′ | 84 | 16 |

I have re-examined the crystals with all possible care, but cannot pretend to correct the angles which the faces of the forms *s*, *u* make with each other, and with the faces of the forms *a*, *m*.

Corrected angles between the normals to the faces of nitrate of furfurine (*not* from solution in alcohol) are,—

| | ° | ′ |
|---|---|---|
| *ea* | 71 | 5 |
| *ee*′ | 37 | 50 |
| *nb* | 47 | 54 |
| *tb* | 65 | 41 |
| *ab* | 90 | 0 |
| *nn*′ | 84 | 12 |
| *tt*′ | 48 | 18 |
| *sa* | 72 | 44 |
| *ss*′ | 34 | 32 |
| *sb* | 66 | 16 |
| *ss*″ | 47 | 28 |
| *s*′*s*″ | 60 | 0 |

The values of the angles between the faces of the form *s* are very uncertain.

*Opake Crystals of Nitrate of Furfurine.*

Crystals obtained from a solution in alcohol, which effloresced readily, and became in consequence opake.

These crystals belong to the anorthic system.

The symbols of the simple forms are,—*s* 100, *r* 010, *x* 001, *u* 011, *z* 101, *e* 110, *t* 111.

The angles between normals to the faces are,—

| | ° | ′ |
|---|---|---|
| *se* | 58 | 50 |
| *re* | 65 | 50 |
| *sr*′ | 55 | 20 |
| *xs* | 76 | 50 |
| *zx* | 57 | 17 |
| *zs*′ | 45 | 53 |
| *te* | 47 | 58 |
| *xt* | 51 | 14 |
| *xe*′ | 80 | 48 |
| *ur* | 52 | 49 |
| *ux* | 60 | 21 |
| *xr*′ | 66 | 50 |
| *us*′ | 69 | 57 |
| *tu* | 55 | 31 |
| *st* | 54 | 32 |
| *ze*′ | 54 | 43 |
| *uz* | 49 | 40 |
| *eu* | 75 | 37 |



# XXIV. *On the Development and Homologies of the Molar Teeth of the Wart-Hogs* (Phacochœrus), *with Illustrations of a System of Notation for the Teeth in the Class* Mammalia. *By Professor* Owen, *F.R.S. &c.*

Received November 12, 1849,—Read February 7, 1850.

In a paper by Everard Home, Esq., read before the Royal Society, May 30, 1799, some observations were communicated upon the form, structure and succession of the teeth of the Wart-Hogs of Africa, now included in the genus of the Hog-family called *Phacochœrus*, but noticed in that paper as a single species under the name of *Sus Æthiopicus*. The observations are illustrated by two plates. The first (tab. xviii.) gives "a side view of the skull of the *Sus Æthiopicus* (half the natural size), to show the situation and appearance of the large grinder, and the remains of the alveoli belonging to the fangs of the preceding one*." The second (tab. xix.) gives a "side view of the skull of the young *Sus Æthiopicus*, to show the mode in which the grinders come forward as the large one increases in size†." This plate includes also a side view and a transverse section of the crown of the large full-grown grinding tooth.

The conclusions drawn from the facts given are, that the *Sus Æthiopicus* resembles the Elephant "in the whole number of grinding teeth belonging to each side of the jaw being confined in a case of bone, so as to form one large grinding surface, and the teeth being pushed forward from behind, instead of a second set being formed immediately under the fangs of the first, as in other animals; which are peculiarities not met with in any teeth hitherto described, except those of the Elephant‡." The grinding teeth of the *Sus Æthiopicus* are described to be "four in number on each side of the jaw"§;.... the fourth or last large tooth is considered to be a second set of teeth, which, as it advances forwards, pushes the other teeth before it;.... "the most anterior of these, as soon as its body is worn away, has its fangs removed by absorption and drops out: the same thing takes place with the second and third; and, in this way, room is made for the large one to supply the place of all the others‖." The mode in which they succeed one another is stated to be illustrated by the side view of the jaw given in tab. xix., in which the fangs of the different teeth are exposed.

I have shown in my 'Odontography'¶, that the facts detailed in Home's paper were insufficient to enable him to explain all the necessary circumstances respecting the curious mode of dentition of the Wart-Hogs; that other stages of dentition, unknown to that author, had demonstrated a second set of teeth formed under the fangs of some

* Philosophical Transactions, 1799, p. 256. † Ibid. p. 257. ‡ Ibid. p. 247.
§ Ibid. p. 250. ‖ Ibid. p. 250. ¶ Vol. i. p. 554.

of the first set, or above them in the upper jaw; and also that the subsequent shedding of the teeth in advance of the last large grinder was not in the order in which they are pushed out in the Elephant, the Wart-Hogs deviating very remarkably from that and all other quadrupeds in this respect.

In the course of subsequent researches and comparisons, I have determined the original specimens in the British Museum and that of the Royal College of Surgeons, which were drawn and engraved to illustrate Home's paper, by which I have ascertained that the drawings were taken from two distinct species of *Phacochœrus*; and I have been able to detect certain inaccuracies in the reduced figures in the engravings, which give countenance, not afforded by the specimens themselves, to the ideas of the mode of succession of the teeth described in Home's paper. I propose, therefore, to give a more precise description of the subjects of the beautiful engravings, tab. xviii. and xix. of the Philosophical Transactions for 1799, and to add the additional facts and illustrations of the peculiarities of the dentition characteristic of the two species of Wart-Hog, and which determine the true number, kinds and succession of the grinding-teeth in both species.

Tab. xvii. (Philosophical Transactions, 1799) gives a view of the skull of an old *Phacochœrus Æliani*, Van der Hoeven, the common species of Nubia, Abyssinia, Senegal and Cordofan, and sometimes called the North African Wart-Hog. It is well characterized by having, when fully grown, six functional incisors in the under jaw and two incisors (*i.* 1.) in the upper jaw, together with forms and proportions of the other teeth, which will be subsequently adverted to. The characteristic incisors are sufficiently indicated in the figure; the large posterior grinders are alone retained in the molar series of both jaws.

Tab. xix. fig. 1 (Philosophical Transactions, 1799) gives a view of the cranium of a younger individual of the *Phac. Pallasii*, Van der Hoeven, the Wart-Hog most common, though not peculiar to the Cape and the Guinea coast districts. The molar teeth which are exposed in this figure are, taking them from before backwards, the last premolar, the symbol of which is *p* 4; the first true molar, *m* 1; the second true molar, *m* 2; and the last true molar, *m* 3.

The teeth are drawn somewhat reduced in size, but not in a just proportion to the reduction of the size of the cranium and of the upper tusks; nor are the relative lengths of the crown and fangs correctly given. The crown of the first true molar, *e. g.*, is represented of the same length as that of the fourth premolar which precedes it, and nearly of the same length as that of the second true molar, whereas in the original specimen it is much shorter in consequence of having been longer in use. Had the differences which these teeth actually show in the extent of the abrasion of their respective crowns been appreciated and duly considered, it might have excited the suspicion that the second tooth, with an almost exhausted crown and much-absorbed fangs, would be shed before the first tooth, the summit of whose long, obtuse and cement-covered crown had only recently been subject to the wear of mastication.

The grinder, which is the subject of figs. 2 and 3, tab. xix., is the last molar from the right side, lower jaw, of the *Phac. Æliani*, of the natural size.

To determine whether any successional teeth were developed above or beneath the fangs of pre-existing teeth destined to be displaced by such development, in other words, whether a true deciduous series and a premolar series of teeth existed in the Wart-Hogs, required an examination of the jaws of an individual younger than the youngest specimen examined and figured by Home.

The subject of Plate XXXIII. fig. 1 of the present communication is of the required immaturity, and, with the other specimens to be described, supplies those links in the series which were wanting for the explanation of the entire course of the truly remarkable dentition of the genus *Phacochærus*.

Fig. 1 shows a side view of the teeth in the young *Phac. Æliani*; the grinding surface of the molar teeth in use is given, from the upper jaw in fig. 2, and from the under jaw in fig. 3. These teeth include all the milk-molars which are developed, together with the first permanent true molar. The milk-molars are 3—3 in number in the upper jaw, and 2—2 in the lower jaw. The first true molar, *m* 1, is also fully developed and in use in both jaws. The summit of the second true molar (*m* 2) is just appearing above the socket.

The length of the skull exhibiting this instructive phase of dentition is 10 inches.

The milk-molars answer to the teeth of the typical dentition symbolized by *d* 2, *d* 3, and *d* 4 in the upper jaw, and to *d* 3 and *d* 4 in the lower jaw.

The first is implanted by two fangs, the second by three, the third by four fangs; the shape of these teeth is sufficiently illustrated by the figures.

Their rate of increase in size from the first to the last is considerable, yet not equal to that manifested in the true molars. Upon examining the substance of the jaws above the deciduous molars of the upper jaw and beneath those of the lower jaw, two formative alveoli and the trace of a third were detected in the upper jaw, one above *d* 4, containing the crown of a premolar; the other above *d* 3, and the rudimental cell above *d* 2. The matrix, which the latter might have contained, had not begun to be calcified. A small formative socket was found beneath the last milk-molar of the lower jaw containing the crown of a premolar. The gubernacular canal from this socket opened between the fangs on the inner side of the milk-tooth. A second still smaller socket of an anterior premolar was beneath the interspace between the two milk-molars.

The true nature of the molar behind the milk-teeth in both jaws was plainly shown by its long fangs extending beyond the parallel of the formative sockets of the successors of the milk-teeth, and widely open at their ends: this tooth has no vertical successor and is the first true molar, *m* 1. Only the crown of the second true molar (*m* 2) is formed at the stage here described; and a few detached columns of the still larger and more complex third molar (*m* 3) were all that were calcified in its commencing formative alveolus.

In none of the other members of the Hog family is the first true molar ($m\,1$) so much worn down at the corresponding early stage of development of the second true molar, and it is upon this precocious growth of the first true molar that the chief peculiarity of the order of shedding of the teeth of the *Phacochœri* depends.

In the *Phac. Æliani*, the penultimate and last milk-teeth ($d\,3$, $d\,4$) in the upper jaw are displaced and succeeded by corresponding premolars, which therefore answer to $p\,3$ and $p\,4$ of the typical series. The anterior small milk-grinder, $d\,2$, is sometimes succeeded by a minute premolar, but occasionally this is abortive, or absorbed before it cuts the gum. In the lower jaw both milk-molars ($d\,3$ and $d\,4$) are succeeded by the corresponding premolars $p\,3$, $p\,4$, at least in the *Phac. Æliani*.

The stage of dentition of the *Phac. Æliani*, given in figs. 1, 2 and 3, corresponds with that in the common Hog, illustrated by the teeth in the lower jaw in Plate XX. fig. 1 of the Philosophical Transactions for 1801. In that figure the last grinder in place is the first true molar, $m\,1$; the penultimate is the last milk-molar, $d\,4$; the next is $d\,3$, the next $d\,2$; and a little in advance of this, between it and the rudimental canine, is the small anterior premolar, $p\,1$. The germs of the other premolars, $p\,2$, $p\,3$ and $p\,4$, are shown in their formative sockets beneath the deciduous teeth they are destined to replace.

If the symbols above given be marked upon the teeth in the figure cited, the homologies of those in the reduced dentition of the young Wart-Hog will be readily appreciated. The teeth developed in the lower jaw of that species are,—$d\,3$, $d\,4$, $p\,3$, $p\,4$ and $m\,1$: in both jaws $m\,2$ has only its crown developed, and $m\,3$ only the commencement of its crown. The teeth which are suppressed in the *Phac. Æliani* are, in the lower jaw, $d\,1$, $d\,2$, $p\,1$ and $p\,2$. In the upper jaw $d\,1$ and $p\,1$ are suppressed, and sometimes also $p\,2$.

The next stage of dentition (Plate XXXIV. figs. 4 and 5) shows the shedding of the deciduous molars to be concomitant with the coming into place of the second true molar, $m\,2$; it is well illustrated in the cranium of a young *Phac. Æliani* from Senegal in the Museum of Comparative Anatomy in the Garden of Plants: in which each of the three deciduous molars of the upper jaw have been succeeded by a premolar ($p\,2$, $p\,3$, $p\,4$, fig. 4), and the same with regard to the two deciduous molars in the lower jaw ($p\,3$, $p\,4$, fig. 5). The anterior angle of the crown of the last huge molar has also begun to protrude from the formative alveolus, so that the permanent or second molar series now shows $\frac{6-6}{5-5}=22$, which is the greatest number of grinders presented at any given time in the genus *Phacochœrus*. The first true molar, $m\,1$, is however worn to near the fangs, and its grinding surface, as compared with that in Plate XXXIII. fig. 2, begins to be simplified. The homologies of the teeth at this period are indicated by the symbols attached to them in the figures.

The stage of dentition of the young *Phac. Pallasii*, figured by Home in tab. xix. of his memoir, is a little more advanced than that of the *Phac. Pallasii* above de-

scribed; but although scarcely half the grinding surface of the last molar, *m* 3, has come into use, all the premolars in advance of the last, *p* 4, have been shed, Plate XXXIV. fig. 8.

In the specimen of *Phac. Æliani*, of which the grinding surface of the teeth is figured in Plate XXXIV. figs. 6 and 7 of the present memoir, although the major part of the last large grinder is in use, the penultimate premolar (*p* 3) is retained as well as the last (*p* 4). The molar series here shows 5—5 in the upper jaw and 4—4 in the lower jaw; their homologies are indicated by the symbols attached. By reason of the precocious development of *m* 1, we now find it quite worn down to the fangs; and in the lower jaw (fig. 7) it is wedged between *p* 4 and *m* 2 into a space which is two-thirds less than the antero-posterior extent of the crown of the same tooth shown in the younger specimen (Plate XXXIII. fig. 2). The reduction of size of *m* 1 is however quite intelligible by observing the much-constricted neck from which the long fangs are continued in that specimen (see *m* 1, fig. 1).

The figures of the grinding surface (figs. 6 and 7) suffice for the characteristic forms of the grinding-teeth now in use.

The specimen of *Phac. Æliani* (No. 773. Mus. Coll. Chir.) shows the last remnant of *m* 1 wedged into the diminished interspace between *p* 4 and *m* 2, and the corresponding interspace in the lower jaw, from which such remnant of the first true molar has been shed.

The skull of an older *Phac. Æliani* (No. 772) shows the displacement of the first true molar in both jaws and the reduction of the molar series to $\frac{4-4}{3-3}$; the teeth being *p* 3, *p* 4, *m* 2 and *m* 3 above (fig. 9), *p* 4, *m* 2 and *m* 3 below (fig. 10). There is no vacuity now in the series to show a true molar to have been shed, as it has been in so unusual an order.

The next stage of dentition which I have observed in this species is the loss of the anterior premolar *p* 3, and the great wearing down of *m* 2 (fig. 11), and in one instance in the lower jaw *m* 2 was shed before *p* 3.

The skull of a male *Phacochœrus* in the British Museum*, from the Cape de Verd, measuring 16 inches 6 lines in length, with the incisors of the *Phac. Æliani*, viz. $\frac{1-1}{3-3}$, and the same broad and shallow posterior channel upon the canines $\frac{1-1}{1-1}$, shows the same numerical molar formula as No. 772, but the teeth are different in the upper jaw, they are *p* 3, *p* 4, *m* 2 and *m* 3; in the lower jaw they are *p* 3, *p* 4 and *m* 3; both first and second true molars being shed in this jaw, whilst the last two premolars are retained.

In the skull of a female *Phacochœrus*, 13½ inches in length, from South Africa, in the British Museum, but with the incisive formula of the *Phac. Æliani*, the molar

* The term *Phacochœrus Æthiopicus* is retained for the species represented by this skull in the British Museum.

series is $p\frac{1}{1}$, $m\frac{2-2}{2-2}$; the teeth in both jaws being $p$ 4, $m$ 2 and $m$ 3: here the penultimate premolar has been shed before the penultimate true molar, the socket of which however alone indicates it in the lower jaw.

In a still older specimen, $p$ 3 and $m$ 2 have been shed in both jaws, and the dental series is reduced to $\frac{2-2}{2-2}$; the teeth being $p$ 4, $m$ 3 on each side of both jaws (fig. 12).

Finally, $p$ 4 is shed, and only the great posterior molar remains, as in the old *Phac. Æliani* figured in tab. xviii. of Home's memoir.

It is interesting and suggestive thus to observe that an analogous duration or longevity, so to speak, characterizes the last tooth of both premolar and true molar series; an analogy so little to be expected from their different size and widely different original position in the jaws, by which characters, Home, not sufficiently extending his observations and trusting to the analogy of the Elephant, was misled.

With respect to the *Phac. Pallasii*, my opportunities of tracing the course of dentition are not so extensive as with regard to the *Phac. Æliani*. I have observed none younger than the specimen figured by Home (tab. xix.), and am not acquainted, therefore, with the characters of its deciduous dentition.

All the four teeth on each side of the upper jaw of that specimen, and there are the same number in the lower jaw, belong to the permanent series; tracing them from before backwards they are $p$ 4, $m$ 1, $m$ 2 and $m$ 3 in both jaws. The homologue of $p$ 3 in the upper jaw of *Phac. Æliani*, if it be developed, is sooner shed in the *Phac. Pallasii* than in the *Phac. Æliani*. From the defects that have been pointed out in Home's reduced figures of these teeth, more accurate views of them of the natural size may be acceptable, especially as they have not been elsewhere represented. I subjoin, therefore (Plate XXXIV. fig. 8), a side view and a view of the grinding surface of each. These figures, also, preclude the necessity of verbal description. I will only state that $p$ 4, in the upper jaw, is implanted by three fangs, and is relatively smaller than its homologue in *Phac. Æliani*: $p$ 4 in the lower jaw offers corresponding differences with its homologue in *Phac. Æliani*; $m$ 2 has a narrower crown in relation to its antero-posterior extent than in *Phac. Æliani*; and a similar and more compressed form distinguishes the third molars in both jaws of the *Phac. Pallasii*. In the skull of a female Phacochœrus, called 'Haruja,' from Caffraria, in the British Museum, which differs from the typical *Phac. Æliani* of North Africa in having only two incisors in each ramus of the lower jaw, the following is the dental formula:—

$$i\frac{1-1}{2-2},\ c\frac{1-1}{1-1},\ p\frac{2-2}{1-1},\ m\frac{2-2}{2-2}:$$

the grinders of the upper jaw are $p$ 3, $p$ 4, $m$ 2 and $m$ 3: those of the lower jaw are $p$ 4, $m$ 2 and $m$ 3. The first true molar has been shed, and its place obliterated in both jaws.

There is a stuffed skin of this species which shows the same number of incisors, viz. $\frac{1-1}{2-2}$.

I have seen no stage of dentition of the *Phac. Pallasii* corresponding with figs. 6 and 7 of *Phac. Æliani*. The next example, after the stage figured by Home, is shown in a skull from the Guinea Coast, in which the grinding series includes 3—3 in both jaws, like that in the upper jaw of the *Phac. Pallasii* and lower jaw of the *Phac. Æliani*, figured in 'Les Dents des Mammifères' of M. F. Cuvier, Tab. 87. These teeth, in each case, are *p* 4, *m* 2 and *m* 3 on each side of both jaws. In the specimen before me, *p* 4 is much worn, and is pressed into close contact with *m* 2. The anterior half of the grinding surface of this tooth is worn down to the common dentinal base, and both the anterior and posterior surfaces of the crown are excavated by the pressure of the two contiguous teeth, as in fig. 10. That a large grinder, like *m* 1, figs. 4, 5 and 6, should have been interposed between the first and second grinders in the specimen here described, could never have been suspected without a knowledge of those earlier stages of the dentition of the genus which have been described.

Baron Cuvier describes the molar teeth of the Phacochere as being three on each side of both jaws in the 4to edition of the 'Ossemens Fossiles' (1822)*, and the same numerical formula is retained in the posthumous 8vo edition of 1834†. With regard to the mode of succession of these teeth, the Baron adopts the conclusions of Sir Everard Home; and in both editions of the 'Règne Animal,' after noticing the similarity of composition of these teeth with the grinders of the Elephant, he adds that they, in like manner, succeed one another from behind forwards‡.

His brother, M. Fr. Cuvier, adopting the same view in the 'Dents de Mammifères,' describes the dentition of the Wart-Hogs as differing altogether from that of the rest of the Hog-tribe. "Nous voici arrivés," he writes, "à un système de dentition tout à fait différent de celui des sangliers" (p. 213): he adopts the specimens represented in the pl. 87 above cited, and describes the figures of that plate as exemplifying the normal adult dentition of the genus§. The anterior of the three grinders is described as the 'première mâchelière' (p. 214); and the second as 'la seconde mâchelière,' the latter being said to be composed of four tubercles, which by usage present four little elliptical or circular figures surrounded by enamel. And this, indeed, is the case at the extreme stage of attrition which he has figured; but, at an earlier period of usage, the crown of the tooth presents ten of those enamel-girted circular or elliptical islands of dentine, surrounding two, three, or four median ones (figs. 4, 5, 6, *m* 2). The last large molar presents twenty-five of these islands in the upper jaw in three linear series, nine being central, and twenty-six in the lower jaw, nine

* Tom. ii. p. 123. † Tom. iii. p. 235. ‡ Tom. i. p. 244.

§ In this he is followed by Lesson (Manuel de Mammalogie, p. 340), Fischer (Synopsis Mammalium, p. 423) and other systematic mammalogists, who assign molars $\frac{3-3}{3-3}$ as one of the characters of the genus *Phacochœrus*.

also being central, and the islands smaller and more regularly disposed. This tooth extends to within one or two lines of the thin compact inferior bony wall of the deep ramus of the jaw, where the constituent columns terminate in the basal openings of as many pulp-cavities, with the exception of the first four, which are blended together, and from which no root has begun to be developed. It is therefore plain that this large and singularly complex grinder will continue to serve the purposes of mastication long after the shedding of the molar in advance, and the substance of which is already wasting away by the pressure of the larger tooth. We shall see, in the next specimen, that that molar is actually worn away and shed, whilst the smaller grinder in advance of it remains.

In the lower jaw of the specimen (No. 775 A.), the gum has grown over the sockets of the second true molar between the persistent remnant of the fourth premolar and the third true molar. In the upper jaw the last remnant of the second true molar remains on the right side, the crown having been worn to its base and the fangs absorbed.

Thus, in the *Phac. Pallasii*, as in the *Phac. Æliani*, the last of the premolar series, like the last of the true molar series, is distinguished by its longevity, although inferior in this respect to the large true grinder which continues to do the work of mastication to the end of the animal's existence.

The analogy of the Phacocheres to the Elephants in the superior size, complexity, and duration of the last grinders is close and interesting; but it does not extend to the horizontal mode of succession, in other words to the absence of premolars or vertical successors of deciduous teeth, as Home led Cuvier to believe. In the development and succession of these premolars, and in the shape, proportions and position of the true deciduous teeth, the Wart-Hogs much more closely and essentially agree with the rest of the *Suidæ*. They differ, however, as we have seen, in the inferior number of both milk-molars and premolars which are developed, and in the speedier loss of all the true molars in advance of the last large one; but, in the order of shedding of those teeth, more especially in the very early displacement of the first true molar, and the total obliteration of its place in the series by the approximation of the last premolar to the second true molar, and in the subsequent displacement of this tooth with the approximation of the last premolar to the last true molar, the genus *Phacochœrus* is quite peculiar and different from all other Mammalia.

The author, who first called the attention of naturalists to the peculiarities of the dentition of the *Phacochœri*, has indicated another difference between the Wart-Hog and the common Hog, by affirming that the latter has a molar tooth developed behind the third true molar, at least in the lower jaw; which, if it were so, would have shown the common Hog to differ, also, from almost every other placental mammal with two sets of teeth*. In the description of Plate XX. of the Philoso-

* The *Megalotis Lalandii* is the only example, as far as I have observed, of the constant occurrence of *four* true molars on each side the lower jaw: the typical number *three* being retained above.

phical Transactions for 1801, Home states that "fig. 3 represents the jaw in a still more advanced stage of its growth, with the tooth which was only forming in the second figure now come to its full size, and in its proper place in the row of teeth: there is also a new cell formed for a succeding tooth*." The original specimen from which the figure is taken is preserved in the Hunterian Collection, and it shows that the supposed formative cell is one of a series of the medullary cells of the cancellous structure of this part of the jaw; it is itself subdivided into smaller cells, and is not a simple cavity like the true cell of a forming tooth. It is also represented of twice its natural size in the figure cited, not having been reduced in proportion to the other parts of the jaw.

The latest author on the subject of the dentition of the *Phacochœri*, has ascribed to that part of their structure a character which would have added a still more remarkable anomaly to it, viz. that the last true molar represents both that tooth and the penultimate one in the Wild Boar and other herbivorous mammals†.

To this conclusion M. de Blainville was necessarily led by his determination of the antecedent teeth. Thus in a *Phacochœrus* with the dentition answering to that represented in figs. 4 and 5 of the present memoir, he regards the teeth marked $p\,3$, $p\,4$ and $m\,1$ as belonging to the deciduous series, 'dents de lait‡,' and the rest as belonging to the second dentition; $p\,2$ being described as a small, speedily lost, false molar, $m\,2$ as the first or antepenultimate true molar, and $m\,3$ as the penultimate and last true molars, "already blended together, although not yet protruded from their formative alveolus§."

With regard to the five teeth in the lower jaw, the first, $p\,3$, is described as the first tooth of the second dentition; the two following, $p\,4$ and $m\,1$, as milk teeth; the fourth, $m\,2$, as the antepenultimate molar of the second dentition, and the last, $m\,3$, as the penultimate and last molar coalesced. The dentition ascribed to the adult *Phacochœrus* is that phase which is illustrated in figs. 9 and 10, Plate XXXIV. of the present memoir, of which the numerical formula is $\frac{4-4}{3-3}=14$. M. de Blainville, struck by the resemblance in the degree of attrition which the molar, $m\,2$, presents to the antepenultimate molar, $m\,1$, in the adult common Hog, deems them homologous, and deduces from that resemblance another argument for the homology of the last great molar of the Phacochere with the penultimate and last molars combined of the Hog‖.

* Philosophical Transactions, 1801, p. 331.

† Ostéographie des Ongulogrades, *Hippopotamus* and *Sus*, 4to, 1847. ‡ Ibid. p. 148. § Ibid. p. 148.

‖ "Mais quelle est la signification de cette dent par rapport à ce qui existe chez la sanglier? C'est la une question qui, malgré son intérêt, n'a pas même encore été soulevée.

"J'ai cru un moment qu'on pourrait la considérer comme représentant les trois arrière-molaires qui se seraient soudées de manière à n'en former qu'une, les trois molaires qui la précèdent étant alors celles de remplacement. Cette façon de voir était surtout appuyée sur la composition de cette dent à la mandibule où l'on peut voir dans les cannelures latérales des séparations plus marquées, paraissant indiquer l'antépénultième, la pénultième et la dernière avec son talon.

"Mais en réfléchissant sur le caractère sérial des espèces de ce genre, il m'a semblé que cette opinion devait

But had the preceding stage of dentition, which is represented in fig. 7, Plate XXXIV., presented itself to the observation of M. de Blainville, that acute observer would doubtless have seen that *m* 1,—the true homologue of the much-worn antepenultimate molar of the common Hog,—presented the same abraded condition. And the actual difference is as follows, viz. that, owing to its earlier development in the *Phacochœrus*, the true antepenultimate molar, *m* 1, is sooner worn out and shed; whilst, from the very long period during which the last molar is adapted to perform the work of mastication, the penultimate molar, *m* 2, undergoes the same exhaustive usage and premature expulsion.

I have figured in parallel juxtaposition the molar series of a Phacochere and a Wild Boar, in plate 141 of my 'Odontography,' to illustrate the corresponding extent of abrasion in the first or antepenultimate true molar (*m* 1) at the period when the last true molar has come into place in the Wart-Hog, and when two of the premolar series are retained; and I have indicated my conclusions as to the signification or homology of each of the teeth by the symbols, the aptness and exactitude of which all my later researches have convinced me of. With regard to the deciduous teeth of the Phacochere and other diphyodont mammals, I may remark that there is but one mode of determining and of distinguishing them from the premolars and true molars of the second dentition, in cases where some of the latter are obviously present, as in the young Phacochere with a grinding series of $\frac{6-6}{5-5}$ (see figs. 4 and 5) or of $\frac{5-5}{4-4}$ (as in Plate XXXIII.): that mode is to excavate the substance of the jaws above the fangs of the upper teeth and beneath those of the lower ones, as in the skull represented in Plate XXXIII., and in the lower jaw figured in my 'Odontography,' pl. 141, fig. 1*. The deciduous tooth is demonstrated by the formative

être modifiée, et que dans cette dent il ne fallait voir que les deux dernières, et alors la terminale aurait son talon dans la proportion convenable.

"Ce qui milite encore en faveur de cette manière devoir, c'est que la dent sur laquelle porte davantage l'usure dans le sanglier, l'antépénultième ou cinquième, a son analogue chez le sanglier d'Ethiopie dans la dent qui précéde la dent complexe, et qui serait en effet l'antépénultième, celle-ci représentant la pénultième soudée à la dernière.—*Loc. cit.* p. 148.

* "Le système dentaire de cet animal a été fort incomplètement figuré sans description par Everard Home (Lect. on Comp. Anatom. t. 11. pl. 38 et 39), M. G. Cuvier lui a consacré un court paragraphe (Ossem. Foss. t. 11. p. 132, sans figures), et M. Owen s'est borné à représenter la couronne des molaires supérieures du côté droit (Odontographie, pl. 140, fig. 31), mais personne n'en a soupçonné la signification." M. de Blainville had overlooked pl. 141, where that signification is given: but he adds in a supplementary note,—"Il relève, comme inexacte, l'assertion de M. Ruppell, que dans tous les individus des deux sexes, jeunes et adultes, il y a quatre molaires en haut et trois en bas; et en effet il en décrit une de plus, en reconnaissant que dans la première dentition il n'y en a que trois à la machoire et deux à la mandibule. Du reste M. R. Owen accepte la distinction spécifique du *S. Æliani* et du *S. Pallasii*; le premier pourvu et le second dépourvu de dents incisives, mais sans autres différences vraiment spécifiques." If, however, the difference cited be of specific value, as M. de Blainville seems here to admit, others were not needed for accepting the conclusion. I may, however, add that the upper canines of the *Phac. Pallasii* have the groove on their upper surface narrower than in the *Phac. Æliani*, and that the premolars are relatively smaller.

socket containing the germ of its successor in a vertical line with it; this is more especially the case with the last or hindmost deciduous tooth, because the hindmost premolar, its successor, is late in coming into place, and the contiguous true molar, which is always formed much sooner, is characterized by its deeply implanted fangs, and by the absence of any formative socket in vertical relation to them. Without the dissection of the jaws figured in Plate XXXIII., I could have had no true or scientific knowledge of the nature of the teeth there symbolized. As I availed myself of symbols to denote the signification or homology of the teeth of the *Phacochœrus* in my 'Odontography' (pages 549 to 557, pl. 140, 141), I shall sum up or indicate in the same way the results of the additional observations recorded in the foregoing pages.

*Phases of the molar series of the genus* Phacochœrus.

Phase

I. Plate XXXIII. $\frac{5-5}{4-4}$ viz. $\begin{cases} d\,2, d\,3, d\,4, m\,1, m\,2. \\ d\,3, d\,4, m\,1, m\,2. \end{cases}$

II. Plate XXXIV. figs. 4 and 5, $\frac{6-6}{5-5}$ viz. $\begin{cases} p\,2, p\,3, p\,4, m\,1, m\,2, m\,3. \\ p\,3, p\,4, m\,1, m\,2, m\,3. \end{cases}$

III. Plate XXXIV. figs. 6 and 7, $\frac{5-5}{4-4}$ viz. $\begin{cases} p\,3, p\,4, m\,1, m\,2, m\,3. \\ p\,4, m\,1, m\,2, m\,3. \end{cases}$

IV. Plate XXXIV. fig. 13 (*Phac. Pallasii*), $\frac{4-4}{4-4}$ viz. $p\,4, m\,1, m\,2, m\,3.$

V. Plate XXXIV. figs. 9 and 10, $\frac{4-4}{3-3}$ viz. $\begin{cases} p\,3, p\,4, m\,2, m\,3 \\ p\,4, m\,2, m\,3 \end{cases}$ $\left(\text{or} \begin{cases} p\,3, p\,4, m\,2, m\,3. \\ p\,3, p\,4, m\,3. \end{cases}\right)$

VI. Plate XXXIV. fig. 11, $\frac{3-3}{3-3}$ viz. $p\,4, m\,2, m\,3.$

VII. Plate XXXIV. fig. 12, $\frac{2-2}{2-2}$ viz. $p\,4, m\,3.$

VIII. $\frac{1-1}{1-1}$ viz. $m\,3.$

The above symbols express, with regard to the first phase, I. *e. g.*, that there are five grinders on each side of the upper jaw, and four grinders on each side of the under jaw: that those above answer to the second, third, and fourth deciduous molars, and to the first and second permanent true molars; and that those below answer to the third and fourth deciduous molars, and to the first and second true molars,—of the typical dentition. With regard to the second phase, the symbols express that there are six grinders on each side of the upper, and five grinders on each side of the under jaw: those above answering to the second, third and fourth premolars, and to the first, second and third true molars; those below answering to the third and fourth premolars, and the first, second and third true molars—of the typical dentition.

As to the fourth phase with four grinders on each side of both jaws, these answer,

in both, to the fourth premolar, and to the first, second and third true molars of the typical dentition of the placental Diphyodonts.

These explanations will serve to render the symbols of the remaining phases readily understood by those who may not have studied the principles of dental notation which I communicated to the 'British Association' in 1848, and have more fully exemplified in the article 'Teeth' of the 'Cyclopædia of Anatomy and Physiology;' their utility will be obvious when they are found to express, in a few lines, facts in Comparative Anatomy which would require almost as many pages if recounted by ordinary description.

This system of anatomical notation is the practical fruit of the discovery or determination of a type or common pattern of dentition to which the teeth of a certain proportion of the Animal Kingdom could be referred, and of a concomitant attainment of the power to trace a particular tooth under every modification and disguise of size and shape, throughout the different species of those animals. Every tooth, thus capable of being individualized and determined, merits and, for the purposes of description, requires to have a proper name, and can be signified by a symbol, which is still more convenient for those purposes.

The dental system manifests this regular and determinable character in a large proportion of the mammalian Class; but not in any animal of inferior organization. Like the definition of a species, the definition of a tooth or other part of an organism becomes possible only when its characters are constant and definite, and is easy in proportion as those qualities are exalted. The definition of a mineral species is more difficult than that of a vegetable species, and the definition of a species of low cellular plant is more difficult than that of the highly organized dicotyledon. In proportion as wholes rise in the scale of nature or of life, their recognition and definition becomes easier, and the like obtains also of their parts. As animals ascend in the scale of complexity their organs and parts become more definite; and homologies are more extensively, easily and satisfactorily determinable.

We cannot point out in one species of Echinus the answerable spine of any given spine in another species, nor can we determine the homology of a tufted foot from one species of the many-jointed Annelides to another; but in insects each particular leg may be determined through all its modifications of form and function throughout the class. So, likewise, with the teeth: the same individual tooth cannot be traced from fish to fish, or from reptile to reptile; the teeth in the cold-blooded classes differ too much in their number in different individuals, and too little in their development and succession, to yield the requisite characters to the homologist who keeps his faculty of comparison under due control. In those Mammalia, likewise, as *e. g.* the Cachalots, Dolphins and Armadillos, in which the teeth are very variable in number and often very numerous, but without any definite order of shedding and replacement, no particular tooth can be identified and traced from one species to another.

The class *Mammalia* presents, in fact, two primary conditions of the dental system, according to which it might be divided into,—

1st. Those that generate one set of teeth, or the 'Monophyodonts*,' and

2nd. Those that generate two sets, or 'Diphyodonts†.'

The 'Monophyodonts' include the orders *Monotremata* and *Bruta* (or the *Edentata* of Cuvier) and the *Cetacea vera* of Cuvier.

The Diphyodonts include the *Marsupialia, Rodentia, Insectivora, Cheiroptera, Ruminantia, Pachydermata, Sirenia, Carnivora, Quadrumana* and *Bimana.*

I would not be misunderstood, however, as proposing this difference as a basis of classification: such dental characters are associated with too few corresponding differences of organization to lead to a natural binary division of the Mammalia. But, as regards the philosophy of the organs in question, considered in that class, the differences above enunciated form one of the highest generalizations, and the exigencies of clear and brief description require such general ideas to have their appropriate signs or names.

The Diphyodont Mammals, then, are characterized by having a first set of teeth, commonly called the 'milk-teeth' or 'deciduous teeth,' and a second set called the 'permanent teeth.' But the development of the latter, in relation to the milk-teeth, presents two modifications; some of the permanent teeth are found in the same vertical line with the milk-teeth, push them out and take their place; others are formed one after another behind the milk-teeth, in what may be called the same horizontal line, and come into place without pushing out any deciduous predecessors. Here, therefore, we have certain characters from development for particular teeth, and when to these characters are added others of equal constancy, derived from relative position, it will be readily understood how such characters, when clearly appreciable and firmly maintained through a series of comparisons, should enable the homologist to point out the very tooth in Man which becomes the great carnassial tooth in the jaw of the Tiger or the great complex grinder in that of the Wart-Hog. With respect to the accessory characters, one of the best is afforded by the relation of certain teeth to the constituent dentigerous bones of the complex jaws. Implantation in the premaxillary bone, or premaxillary part of the upper jaw, *e. g.*, characterizes the tooth called 'incisor,' whatever be its shape or size; and the true and constant character of such tooth being thus determined, the name 'incisor' becomes its arbitrary sign and loses all its primitive signification as descriptive of a particular shape or use. In like manner the tooth at the fore part of the maxilla, or the maxillary part of the upper jaw which coalesces with the premaxilla in Man, is called the 'canine.' The molar series, according to the characters of development and succession above described, is divided into 'milk-molars,' 'premolars' and 'true molars.' The two latter kinds constitute the adult or permanent set of molars. Now these, in the diphyodont mammals, do not exceed $\frac{7-7}{7-7}=28$, *i. e.* seven on each side of both jaws. In the marsupial Diphy-

* Μόνος *once*; φύω *I generate*; ὀδούς, *tooth.* † Δὶς *twice*; φύω and ὀδούς.

odonts three of the seven on each side of both jaws are 'premolars,' four are 'true molars.' In the placental Diphyodonts four of the seven on each side of both jaws are 'premolars,' and three are 'true molars.' The exceptions, by way of excess to this typical number, are few and are confined to the marsupial order, *e. g.* in the Myrmecobius: the deviations from the type by deficiency are numerous, especially in the placental series. But to whatever point the number may be reduced, the teeth that are retained may be identified with their homologues in the typical series. This power is fortunately given by the constancy in respect of their existence of the contiguous teeth of the premolar and molar series, those, *e. g.* marked *p* 4 and *m* 1 in Plate XXXIII.; and by the absent teeth being taken from a definite part of each of those series, viz. from the fore part of the premolars and from the back part of the true molar series.

The Bears and some Carnivora offer a partial exception in the occasional retention of *p* 1 when *p* 2 and *p* 3 may be absent, but *p* 4 is constantly present.

Thus it needs only to determine, in any given species of diphyodont mammal, the last premolar and the first true molar, as has been done in the young Phacochere, Plate XXXIII., in order to know the homologies of the rest. The true molars are counted from before backwards,—'first,' 'second,' 'third:' the premolars from behind forwards,—'fourth,' 'third,' 'second,' 'first,' or as far as the series may extend. In Man, *e. g.* it stops at the third; the first and second, which exist in the Hog, being absent, but all the true molars are present. The teeth being thus determined their symbols can be applied to them, *m* 1, *m* 2, *m* 3, for the molars,—*p* 4, *p* 3, *p* 2, *p* 1, for the premolars. It needs only to apply the symbols to one side of each jaw, the teeth being symmetrically repeated on the opposite side: and in most cases they are alike in both jaws. The right canine is the homotype of the left canine, as the right arm is of the left arm, agreeably with the principle of 'bilateral symmetry:' the first true molar in the lower jaw is the homotype of the first true molar of the upper jaw, as the leg is the homotype of the arm, in accordance with the law of the composition of the vertebrate framework of a successive series of essentially similar segments. In whatever direction or to whatever degree two or more of these segments may deviate from the type, the same elements may be discerned in them beneath those modifications. If the neural arch be vastly expanded, as in the cranial vertebræ of mammals, we trace the broad and bifid neural spine from one to the other, and recognise, *e. g.* the frontal bones and parietal bones as homotypal elements. If the diverging appendages be the seat of adaptive development, as in the occipital and pelvic vertebræ, we find the same plan of modification is followed, and we can trace the homotypal parts, *e. g.* *humerus* and *femur*, *radius* and *tibia*, *ulna* and *fibula*, *carpus* and *tarsus*, as also the homotypal ossicles in the carpus and tarsus, even when the common plan is so varied in such appendages, as to produce the different powers and functions which characterize the leg and the arm in Man.

So, likewise, when two costal arches are converted into jaws and made to support teeth, we find the same laws of development so strictly followed as to enable us to

determine the homotypal teeth in those two jaws with the same certainty as the homologous teeth in the jaws of different species.

When the mouth is shut the teeth in the lower jaw are a little in advance of their homotypes in the upper jaw; thus in the Carnivora the great canine tooth of the lower jaw always passes in front of the canine above. Even in the human subject this characteristic relative position is shown by the molars and premolars, when the upper incisors are produced beyond the lower ones.

The existing species of Mammalia that retain the typical formula of dentition, viz.

$$i\frac{3-3}{3-3}, c\frac{1-1}{1-1}, p\frac{4-4}{4-4}, m\frac{3-3}{3-3}=44,$$

are few: but that formula was much less frequently departed from in the species of placental Mammalia which were first introduced into this planet. This is a very significant fact, and became manifest in the course of working out such typical formula by tracing and comparing the development of the teeth in the recent species.

In the oldest known strictly carnivorous mammal, *e. g.* the *Hyænodon*, remains of which have been discovered in the newer eocene deposits of Hampshire, and in the miocene formations of France, the complete typical dentition is retained, and each of the three true molars presents the peculiar trenchant form of crown which characterizes the single tooth called by Cuvier 'le dent carnassière' in the Lion: here, therefore, we use the term 'molar' in the same technical or arbitrary sense as the term 'incisor' when applied to the tusks of the Elephant or the prongs of the Hippopotamus. In the mixed-feeding *Amphicyon*, a larger extinct miocene Carnivore, allied to the Plantigrades, the three true molars have broad tuberculate crowns. Almost all the herbivorous genera of the eocene and miocene tertiary periods had the typical number and kinds of teeth, as, *e. g.*, *Anoplotherium*, *Palæotherium*, *Dichodon*, *Chœropotamus*, *Dichobune*, *Anthracotherium*, *Hyopotamus*, *Hyracotherium*, *Oplotherium*, *Merycopotamus*, *Hippohyus*, &c. When a modern genus or family has been represented as far back as the miocene period by extinct species, it is usual to find some nearer approach made by such species to the typical dentition than is made by the existing species. Thus, in existing Ruminants, the first premolar is suppressed; but in the ancient *Dorcatherium* it was retained. In the modern *Hippopotami* the incisors are reduced to $\frac{2-2}{2-2}$, and the first premolar is speedily lost; in the oldest known representatives of the genus—the *Hexaprotodon* of the Himalayan tertiary beds—the incisors were in the typical number $\frac{3-3}{3-3}$, as the name imposed upon it by its discoverers, Cautley and Falconer, indicates, and the first premolar was long retained; the whole dentition, in short, presented the typical formula.

The existing species of the gigantic Proboscidian family, viz. the Asiatic and African Elephants, are totally devoid of incisors in the lower jaw, and all their grinding-teeth succeed each other horizontally; so that it is only by a more than proportional in-

crease of size that the antepenultimate grinder is recognizable as the first of the true molar series, and the antecedent smaller grinders as the homologues of the milk-molars of other Diphyodonts, which milk-molars have no vertical successors in the Elephants. In certain Mastodons, however, which are the earliest known forms of the Proboscidian family, the last milk-molar was displaced by a vertical successor or premolar. Two incisors, moreover, were developed in the lower jaw of the young Mastodons, one of which was retained in the male of the *Mastodon giganteus* of North America, and both in that of the *Mastodon longirostris* of Europe.

The human dentition deviates from the typical formula by the suppressed development of several teeth; as might be anticipated from the characteristic shortness of the jaws, which is such as only to allow space for the comparatively few teeth retained, in close juxtaposition, without any break in the series.

The numerical formula is

$$i\frac{2-2}{2-2}, c\frac{1-1}{1-1}, p\frac{2-2}{2-2}, m\frac{3-3}{3-3}=32;$$

the principal phases in the development of this dentition may be symbolized as follows:—

I. 3 years old, $i\frac{2-2}{2-2}, c\frac{1-1}{1-1}, m\frac{2-2}{2-2}=20;$

all of the deciduous series, the molars answering to $d3$ and $d4$ of the typical dentition.

II. 7 years old, $i\frac{2-2}{2-2}, c\frac{1-1}{1-1}, m\frac{3-3}{3-3}=24;$

the molars being $d3$, $d4$, $m1$.

III. 10 to 12 years old, $i\frac{2-2}{2-2}, c\frac{1-1}{1-1}, m\frac{3-3}{3-3}=24;$

the molars being $p3$, $p4$, $m1$, and the milk incisors and canines replaced by the permanent ones.

IV. 12 to 16 years old, $i\frac{2-2}{2-2}, c\frac{1-1}{1-1}, m\frac{4-4}{4-4}=28$, viz. $p3$, $p4$, $m1$, $m2$.

V. 18 to 30 years old, $i\frac{2-2}{2-2}, c\frac{1-1}{1-1}, m\frac{5-5}{5-5}=32$, viz. $p3$, $p4$, $m1$, $m2$, $m3$.

The teeth which are wanting in Man to complete the typical formula are $i3$, $p1$ and $p2$. The teeth in Man which answer to the carnassials of the Lion and other Feræ are $p4$ in the upper jaw, or the second bicuspis of human anatomy, and $m1$ in the lower jaw, or the first multicuspid molar. The tooth which is homologous to the great complex molar of the Wart-Hog is $m3$ in both jaws.

The symbols here proposed to denote the kinds of teeth are, it is hoped, so plain and simple as to present no obstacle to the ready comprehension of the facts which have been recorded by means of them. Had those facts been explained by means of the usual phrases or definitions of the teeth, *e. g.* "the second deciduous molar repre-

senting the fourth of the typical dentition," instead of *d* 4, and so on, the descriptions must have run to much greater length, and have levied such a tax upon the attention and memory as to have proportionally enfeebled the judgment and impaired the power of seizing and appreciating the results of the comparisons.

Each year's experience strengthens my conviction that the rapid and successful progress of anatomy depends greatly on the determination of the nature or homology of the parts observed, and on the concomitant acquisition of the power of denoting them by symbols equivalent to their single substantive names.

In my work on the 'Archetype of the Vertebrate Skeleton,' I have denoted most of the bones by simple numerals, which, if generally adopted, might take the place of names: and all the propositions, *e. g.* relative to the centrum of the occipital vertebra, might be predicated as effectually and intelligibly of the figure 1 as of the word 'basioccipital.' The symbols of the teeth are fewer, are easily understood and remembered, render unnecessary the endless repetition of the verbal definition of the parts, harmonize conflicting synonyms, serve as a universal language, and express the author's meaning in the fewest and clearest terms.

The Entomologist has long found the advantage of such signs as ♂ and ♀, signifying male and female, and the like; and it is time that the Anatomist should avail himself of this powerful instrument of thought, instruction and discovery, from which the Chemist, the Astronomer and the Geometrician have obtained such important results.

## Description of the Plates.

### PLATE XXXIII.

Fig. 1. Side view of the skull of a very young *Phacochœrus Æliani*, natural size, with the outer walls of the alveoli removed to expose the deciduous molars, premolars and true molars, *in situ*.

Fig. 2. The grinding series, composed of milk-molars and true molars, from the upper jaw.

Fig. 3. The same from the lower jaw. (The symbols are explained in the text.)

### PLATE XXXIV.

Fig. 4. Grinding surface and side view of the crowns of the molar series of the upper jaw of a young *Phacochœrus Æliani*.

Fig. 5. Grinding surface and side view of the crowns of the molar series of the lower jaw of the same skull.

Fig. 6. View of the grinding surface of the upper molar series of a full-grown but young *Phacochœrus Æliani*.

Fig. 7. A similar view of the molar series of the lower jaw of the same specimen.

Fig. 8. Side view and view of the grinding surface of the molar series of a similarly aged *Phacochœrus Pallasii*.

Fig. 9. View of the grinding surface of the upper molar series of an older *Phacochœrus Æliani*.

Fig. 10. Similar view of the lower molar series of the same animal.

Fig. 11. View of the grinding surface of the upper molar series of an older *Phacochœrus Pallasii*.

Fig. 12. Similar view of the upper molar series of a still older *Phacochœrus Æliani*.

(The symbols are explained in the text, especially at p. 491.

## XXV. *Observations on the Nebulæ.* By The Earl of Rosse, *Pres. R.S., &c. &c.*

Received June 19,—Read June 20, 1850.

In laying before the Royal Society an account of the progress which has been made up to the present date in the re-examination of Sir John Herschel's Catalogue of Nebulæ published in the Philosophical Transactions for 1833, it will be necessary to say something of the qualities of the instrument employed.

The telescope has a clear aperture of 6 feet, and a focal length of 53 feet. It has hitherto been used as a Newtonian, but in constructing the galleries provision was made for the easy application of a little additional apparatus to change the height of the observer, so that the focal length of the speculum remaining the same, the instrument could be conveniently worked as a Herschelian.

Although with an aperture so great in proportion to the focal length, the performance of a parabolic speculum placed obliquely would no doubt be very unsatisfactory, still additional light is so important in bringing out faint details, that it is not improbable in the further examination of the objects of most promise with the full light of the speculum, *undiminished by a second reflexion*, some additional features of interest will come out.

The second reflexion is accomplished in the usual way by a surface of speculum metal; some experiments have been made, suggested by Jamin's paper in the Annales de Chimie for 1848, to procure a surface of silver suited to the purpose, but without complete success. Arrangements also have been for some time in contemplation with the view of effecting the second reflexion occasionally by a small glass prism; and about a year ago a prism was procured from Munich for the purpose: in both cases there would be a great saving of light; but I am speaking of the instrument as it is, not as it may become, if further improved.

The tube reposes at its lower end upon a very massive universal joint of cast iron, resting on a pier of stonework buried in the ground; and it is counterpoised so that it can be moved in polar distance with great facility. A quick motion in polar distance is given by a windlass below, and a slow motion is given by hand above for measurements. The extreme range of the tube in right ascension at the equator is one hour; but greater as the polar distance diminishes. The quick movement in right ascension is given below by a wheel turned by a workman, and the slow motion by hand above; the instrument is therefore completely under the dominion of the observer. The tube is slung entirely by chains, and is perfectly steady even in a gale of wind.

As the chain which governs the movement of the telescope passes over a pulley capable of being brought by a little subsidiary apparatus into a line drawn from the

axis of motion parallel to the axis of the earth, the movement of the telescope can be rendered almost exactly equatorial: there was some mechanical advantage in placing the pulley a little out of that line; and for such measurements as we have required, we have found the movement of the telescope sufficiently equatorial without the subsidiary apparatus, and therefore have not up to the present time made use of it. When the telescope is in the meridian, as it moves in polar distance it is guided by a cast-iron arc of a circle about 85 feet diameter nicely planed. The arc is composed of pieces 5 feet long, each adjusted independently in the meridian by the transit instrument, and secured to massive stonework. The horizontal axis of the great universal joint gives motion to an index which points to polar distances on an arc of 6 feet radius, by which the telescope is very quickly set in polar distance. A 20-inch circle with a very delicate level, attached to the telescope, performs the same office, more slowly but with greater accuracy; and also gives polar distances with considerable precision when duly corrected. The whole mounting was planned especially with a view of carrying on a regular system of sweeping, for which it is peculiarly adapted; but the known objects which require examination are so numerous that hitherto we have been fully occupied with them; and the discovery of new nebulæ has as yet formed no part of the systematic work of the observatory.

As yet the telescope is not provided with a clock movement. A clock movement was part of the original design, and there would have been no serious difficulty in carrying it out; but the want of it has not been very much felt, and there were other matters requiring more immediate attention.

Various micrometers have been tried, but upon the whole the common wire micrometer with thick lines succeeds the best. The thick lines are formed by coiling very fine silver wire four times round the forks, soldering it there, and then removing the lower half of the coil. A little spirit varnish unites the fine wires into a thin ribbon with a straight edge, perhaps as perfect as can be made. The micrometer is used without illumination; and I have never failed to see the lines in the darkest night; but of course measurements with thick lines are inferior in point of accuracy to measurements with thin lines in an illuminated field. Unfortunately any micrometrical contrivance which either diminishes the light of the telescope, or renders the field less dark, extinguishes the faint details of the nebulæ, which even with an aperture of 6 feet are often barely perceptible. There have been many ingenious attempts to make fine lines visible in a perfectly dark field, but they have not, at least as far as my experience goes, been entirely successful.

The telescope has two specula, one about three and a half, and the other a little more than four tons weight. Each speculum was originally provided with a system of levers to afford it an equable support: it was placed upon this system before it was ground, and it has rested upon it ever since. The system of levers is a combination of three systems in every respect similar, resting on three points under the centres of gravity of the three equal sectors into which the speculum may be supposed to be

divided. Each system consists of one triangle with its point of support directly under its centre of gravity, upon which it freely oscillates. This triangle carries at its angles three similar points of support for three other triangles, under their centres of gravity, and they again at their angles carry in a similar way cast-iron platforms formed of thin ribs so as to make a kind of irregular open-work grating, supported under their centres of gravity. These platforms are all of equal area though not of similar shape. As there are three systems there are therefore twenty-seven platforms, which together make a circular disc about an inch in diameter less than the speculum: when arranged however a little apart so as not to touch, they make a disc about the same diameter as the speculum. Each platform is coated with greased cloth, and may be considered as bearing up one twenty-seventh of the weight of the speculum. Between the platforms and the speculum pieces of tin plate are inserted to diminish the friction as much as possible. The platforms being of open-work, they do not prevent the water in which the speculum is immersed from freely carrying away the heat as it is developed during the process of polishing, which is essential.

It is evident that a speculum so supported will be practically free from strain while in a horizontal position, provided the due action of the levers is not interfered with by any disturbing force; it will be very much in the same condition as if floating in a vessel of mercury; when it ceases to be horizontal however new forces come into play: part of the weight must then be resisted by pressure against the edge. Four very strong segments of cast iron, each about one-eighth of the circumference, were adjusted to the edge by screws, the segments bearing upon the massive castings which sustained the three primary supports of the lever apparatus. Provision was made to allow a little motion perpendicular to the plane of the speculum, to guard as much as possible against strain from the elasticity of the lever apparatus, which was however very small, the yielding being less than one-fortieth of an inch.

The two specula of 3 feet aperture I have so long employed are mounted on a similar principle: they have however fewer points of support, and by a little sacrifice of the condition of perfect equilibrium, the whole system of levers was thrown without difficulty almost exactly into one plane. They are free from perceptible flexure in the different positions of the instrument. With the two specula of 6 feet diameter the case was otherwise. The 3-feet specula, weighing each about thirteen hundred weight, were very much stiffer, in proportion to their weight, than the 6-feet specula. To have made the 6-feet specula of equal proportionate stiffness, either they should have been enormously heavy, or the material should have been so disposed as to give greater stiffness than when simply cast into the shape of a solid disc. Some years ago it was ascertained by experiments, but on a small scale, that it would be practicable to dispose of three-fourths of the material of a speculum so as to secure a great increase of stiffness; the form adopted was a system of hexagonal cells. Whether on a great scale the difficulties would be too serious to be surmounted is a question; however it is with solid discs we have had to deal. The relative stiffness of

speculum metal and wrought iron is about five to six three-tenths; yet strange as it may appear, so delicate is the optical test, that strong pressure of the hand at the back of a speculum, four tons weight, and nearly six inches thick, produces flexure sufficient to distort the image of a star. It is obvious, therefore, that a slight inequality in the action of the lever apparatus supporting a 6-feet speculum would produce an amount of flexure sufficient to destroy definition. It has not been found possible so to secure the 6-feet specula as to prevent a slight change of place in a plane parallel to the plane of the levers, and as the levers are not all in one plane as in the case of the 3-feet specula, and a considerable amount of friction exists between the speculum and its lever supports, when the speculum changes place, however slightly, there will be a force tending to disturb the equal actions of the levers. It has been found that when the speculum changes its place one-thirtieth of an inch, still adhering to its levers, unmistakeable distortion will be produced. We have occasionally observed, even during a night's work, the sudden appearance, and the as sudden disappearance of the rudiments of focal lines, the undoubted evidences of flexure; but we have not found that flexure, even to the extent of materially disfiguring the image of a large star, interferes much with the action of the speculum on the faint details of nebulæ, although it greatly lessens its power in bringing out minute points of light, and in showing resolvability where under favourable circumstances resolution had been previously effected.

In the spring of 1848 the heavier of the two specula for nearly three months performed admirably, very rarely exhibiting the slightest indication of flexure. It then remained inactive for some time before and after the solstice, and when we again commenced observing it was found to be in a state of strain; the friction between the lever apparatus and the speculum had no doubt in the meantime increased considerably, and the levers being therefore unable to adjust themselves to some slight but permanent change in the place of the speculum, they no longer supported it equably. It was cautiously raised a little by screws for the purpose of re-adjusting the levers, and to our surprise the unequal strain of the screws was found to have produced permanent flexure, so that the speculum did not again perform well till after it had been reground. From the experiments of Mr. Eaton Hodgkinson and others, we should have been prepared for a change of figure in a mass of cast iron, but with a material so brittle and so elastic as speculum metal, the result was quite unexpected. Recently, in supporting the lighter of the two specula, twenty-seven triangles have been substituted for the twenty-seven platforms, each triangle carrying at its angles three brass balls, so that the speculum rolls freely on eighty-one balls, which support it pretty nearly equably. This appears to be a great improvement, but I will not dwell further on the subject. To describe the experiments which have been made with a view of discovering the best means of supporting very large specula, a question of great theoretical and practical difficulty, would occupy too much space, and would require elaborate engravings; it would besides be foreign to the object of this paper.

The same considerations also forbid any more minute description of the telescope and its mounting.

From what has been said, it is evident that the 6-feet specula being occasionally in a state of strain, were not uniform in their action. There was however another cause of unequal action. The 6-feet specula, after they have been polished, cannot be tested till they have been removed from the laboratory to the telescope, there to await a good night, the great focal length making it impossible to test them while on the engine. Now it has often happened that a speculum which has subsequently proved to be incapable of very fine definition, has remained in the telescope during a succession of moderately good nights, when a great deal of work was done, awaiting a night when the air was in a state to warrant a decisive opinion. Such a speculum might do good work, but it would not resolve difficult nebulæ, neither would it bring out faint points of light, even when wide apart. There is still another cause of the unequal action of our specula far more serious, the varying state of the atmosphere. When the air is unsteady, minute stars are no longer points, the diffused image is much fainter, and single stars, easily seen when the air is steady, are no longer visible. When many minute stars are crowded together the whole become blended, and instead of a resolved nebula we have merely a diffused, perhaps bright nebulosity. The transparency of the air varies also quite as much; and the aspect of the nebulæ changes from night to night, just as the appearance of a distant building alters as the details of the architecture are more or less obscured by the intervening mist. With these facts, the Society will not be surprised should it be in our power at a future time to communicate some additional particulars, even as to the nebulæ which have been the most frequently observed.

The sketches which accompany this paper are on a very small scale, but they are sufficient to convey a pretty accurate idea of the peculiarities of structure which have gradually become known to us: in many of the nebulæ they are very remarkable, and seem even to indicate the presence of dynamical laws we may perhaps fancy to be almost within our grasp. To have made full-sized copies of the original sketches would have been useless, as many micrometrical measures are still wanting, and there are many matters of detail to be worked in before they will be entitled to rank as astronomical records, to be referred to as evidence of change, should there hereafter be any reason to suspect it.

Much however as the discovery of these strange forms may be calculated to excite our curiosity, and to awaken an intense desire to learn something of the laws which give order to these wonderful systems, as yet, I think, we have no fair ground even for plausible conjecture; and as observations have accumulated the subject has become, to my mind at least, more mysterious and more inapproachable. There has therefore been little temptation to indulge in speculation, and consequently there can have been but little danger of bias in seeking for the facts. When certain phenomena can only be seen with great difficulty, the eye may imperceptibly be in some

degree influenced by the mind; therefore a preconceived theory may mislead, and speculations are not without danger. On the other hand, speculations may render important service by directing attention to phenomena which otherwise would escape observation, just as we are sometimes enabled to recognize a faint object with a small instrument, having had our attention previously directed to it by an instrument of greater power. The conjectures therefore of men of science are always to be invited as aids during the active prosecution of research.

It will be at once remarked, that the spiral arrangement so strongly developed in Plate XXXV. H. 1622, 51 Messier, fig. 1, is traceable, more or less distinctly, in several of the sketches. More frequently indeed there is a nearer approach to a kind of irregular interrupted annular disposition of the luminous material than to the regularity so striking in 51 Messier; but it can scarcely be doubted that these nebulæ are systems of a very similar nature, seen more or less perfectly, and variously placed to the line of sight. In general the details which characterize objects of this class are extremely faint, scarcely perhaps to be seen with certainty on a moderately good night with less than the full aperture of 6 feet: in 51 Messier, however, and perhaps a few more, it is not so. A 6-feet aperture so strikingly brings out the characteristic features of 51 Messier, that I think considerably less power would suffice, on a very fine night, to bring out the principal convolutions. This nebula has been seen by a great many visitors, and its general resemblance to the sketch at once recognized even by unpractised eyes. Messier describes this object as a double nebula without stars; Sir William Herschel as a bright round nebula, surrounded by a halo or glory at a distance from it, and accompanied by a companion; and Sir John Herschel observed the partial subdivision of the *s. f.* limb of the ring into two branches. Taking Sir J. Herschel's figure, and placing it as it would be if seen with a Newtonian telescope, we shall at once recognise the bright convolutions of the spiral, which were seen by him as a divided ring. We thus observe, that with each successive increase of optical power, the structure has become more complicated and more unlike anything which we could picture to ourselves as the result of any form of dynamical law, of which we find a counterpart in our system. The connection of the companion with the greater nebula, of which there is not the least doubt, and in the way represented in the sketch, adds, as it appears to me, if possible, to the difficulty of forming any conceivable hypothesis. That such a system should exist, without internal movement, seems to be in the highest degree improbable: we may possibly aid our conceptions by coupling with the idea of motion that of a resisting medium; but we cannot regard such a system in any way as a case of mere statical equilibrium. Measurements therefore are of the highest interest, but unfortunately they are attended with great difficulties. Measurements of the points of maximum brightness in the motling of the different convolutions must necessarily be very loose; for although on the finest nights we see them breaking up into stars, the exceedingly minute stars cannot be seen steadily, and to identify one in each case would be im-

possible with our present means. The nebula itself, however, is pretty well studded with stars, which can be distinctly seen of various sizes, and of a few of these, with reference to the principal nucleus, measurements were taken by my assistant, Mr. JOHNSTONE STONEY, in the spring of 1849, during my absence in London; for some time before the weather had been continually cloudy. These measurements have been again repeated by him this year, 1850, during the months of April and May. Just as was the case last year, in February and March the sky was almost constantly overcast. He has also taken some measures from the centre of the principal nucleus to the apparent boundary of the coils, in different angles of position. The micrometer employed was furnished with broad lines formed of a coil of silver wire in the way I have described, seen without illumination. Some of the stars in the nebula are so bright, I have little doubt they would bear illumination; if so, their positions with respect to some one star might be obtained with great accuracy of course by employing spiders' lines; this season however it is too late to make the attempt. Several of these stars are no doubt within the reach of the great instruments at Pulkova and at Cambridge, U.S., and I hope the distinguished astronomers who have charge of them will consider the subject worthy of their attention. Their better climate gives them many advantages, of which not the least is the opportunity of devoting time to measurements without any serious interruption to other work. I need perhaps hardly add, that measurements taken from the estimated centre of a nucleus, and still more from the estimated termination of nebulosity, are but the roughest approximations; they are however the only measurements nebulosity admits of, and if sufficiently numerous, I think they will bring to light any considerable change of place, or form, which may occur.

The spiral arrangement of 51 MESSIER was detected in the spring of 1845. In the following spring an arrangement, also spiral but of a different character, was detected in 99 MESSIER, Plate XXXV. fig. 2. This object is also easily seen, and probably a smaller instrument, under favourable circumstances, would show everything in the sketch. Numbers 3239 and 2370 of HERSCHEL's Southern Catalogue are very probably objects of a similar character, and as the same instrument does not seem to have revealed any trace of the form of 99 MESSIER, they are no doubt much more conspicuous. It is not therefore unreasonable to hope, that whenever the southern hemisphere shall be re-examined with instruments of great power, these two remarkable nebulæ will yield some interesting result.

The other spiral nebulæ discovered up to the present time are comparatively difficult to be seen, and the full power of the instrument is required, at least in our climate, to bring out the details. It should be observed that we are in the habit of calling all objects spirals in which we have detected a curvilinear arrangement not consisting of regular re-entering curves; it is convenient to class them under a common name, though we have not the means of proving that they are similar systems. They at present amount to fourteen, four of which have been discovered this spring; there are besides other nebulæ in which indications of the same character have been

observed, but they are still marked doubtful in our working list, having been seen when the air was not very transparent; 51 MESSIER, Plate XXXV. fig. 1, is the most conspicuous object of that class.

The question may perhaps suggest itself whether there is not something in the aspect of a spiral nebula, which forces upon us the conviction that it is a system with an organization quite different from that of any known cluster. The only answer I am enabled to give to that question is, that in the exterior stars of some clusters there appears to be a tendency to an arrangement in curved branches, which cannot well be unreal, or accidental. Nos. 480, 1916, 1968, 1972, are the objects in which I observe that peculiarity noted down in our list of observations as suspected. As to 1968, Sir JOHN HERSCHEL uses the following words in his Catalogue, "has hairy-looking curvilinear branches." Careful drawings based on measurements would settle the question, whether the suspected curvilinear distribution of the stars is real or not; this would also perhaps settle another question of interest, whether the distribution of the stars in these objects is reconcileable with the hypothesis of an equal distribution of the stars of the system; as yet however there has not been time to make the required measurements. In passing from the spiral to the regular annular nebulæ, we perceive we are at once engaged with objects of a very different character: still here even there seems to be something like a connecting link; the great round planetary nebula, H 838, Plate XXXVII. fig. 11, with a double perforation appears to partake of the structure both of the annular and spiral nebulæ. There were but two annular nebulæ known in the northern hemisphere when Sir JOHN HERSCHEL's Catalogue was published; now there are seven, as we have found that five of the planetary nebulæ are really annular. Of these objects, the annular nebula in Lyra is the one in which the form is by far the most easily recognized. I have not yet sketched it with the 6-feet instrument, because I have never seen it under favourable circumstances: the opportunities of observing it well on the meridian are comparatively rare owing to twilight. It was however observed seven times in 1848 and once in 1849. The only additional particulars I collect from the observations, are that the central opening has considerably more nebulosity in it than it appeared to have with the 3-feet instrument, and that there is one pretty bright star in it, *s. f.* the centre, and a few other very minute stars. In the sky round the nebula and near it there are several very small stars which were not before seen, and therefore the stars in the dark opening may possibly be merely accidental. In the annulus, especially at the extremities of the minor axis, there are several minute stars, but there was still much nebulosity not seen as distinct stars.

The other annular nebula of HERSCHEL's Northern Catalogue is a much fainter object: it has been observed but once with the large instrument, August 1, 1848; but the evidence of resolution appears to have been more complete; many stars were seen in the annulus; one of them was very conspicuous. That a faint nebula should be more easily resolvable than a bright one is not unusual, neither is it contrary to probability; faintness may be owing to distance, or to a wider separation of the stars,

either physically or optically; in the latter case it is not unlikely that in a faint nebula they might be seen separate with an instrument of great aperture, while in the brighter and more closely packed nebula they were blended together, owing to imperfect definition, arising out of the state of the air, or instrument. As an example, the dumb-bell is a bright nebula: on three exceedingly fine nights succeeding each other at short intervals, the stars in the brighter parts of the nebula were better shown with 3 feet aperture than they have since been with 6 feet. Very fine nights, when the air seems to set no limits to magnifying power, are extremely rare, and the dumb-bell has not been seen with the great instrument on such nights. On the other hand, on all ordinary nights, a variety of details are shown by the great instrument which were not seen on the finest nights with the smaller instrument. There is another fact I may perhaps add, that while high magnifying power brings out minute stars it extinguishes faint nebulosity. The optical reason is obvious; but in sketching the dumb-bell nebula in 1845 that fact was overlooked, and but one eye-piece was used, a very high one; had there been a low one also used the sketch would have been more complete. To return to the annular nebulæ. The five planetary nebulæ we have ascertained to be annular, are as follows: 464, Plate XXXVIII. fig. 12, has two stars within it; 2075 has one star a little following the centre; 2241, Plate XXXVIII. fig. 13, has no star, but is surrounded with a faint external annulus; 2050 has a perforation not round nor quite symmetrical with the star; 838, Plate XXXVII. fig. 11, has two stars and two perforations. In no instance is the central opening quite dark. The planetary nebula, 2047, is marked in our journal as annular, but the observation is without date and other particulars, and therefore I do not consider it altogether trustworthy. In 2098, Plate XXXVIII. fig. 14, another planetary nebula, we have not detected any perforation, but it has ansæ, which probably indicate a surrounding nebulous ring seen edgeways, just as 450, Plate XXXVIII. fig. 15, has apparently a nebulous ring seen on the flat; and if the annular nebulæ are really hollow shells, the nebulous ring would cover the comparatively transparent centre; 365 and 2037 have never been observed.

Passing from the annular nebulæ to the nebulous stars, there are two objects well-worthy of especial notice.

Sir John Herschel very accurately describes a nebulous star thus:—"A sharp and brilliant star concentrically surrounded by a perfectly circular disc or atmosphere of faint light, in some cases dying away insensibly on all sides, in others almost suddenly terminated*." No. 450 of Sir John Herschel's Catalogue is one of these nebulous stars, and is there thus described:—"A star of the 8th magnitude, exactly in the centre of an exactly round and bright atmosphere, 25″ diameter. The star is quite stellar, not a mere nucleus. Another star, 8th magnitude, distant 100″, and about 85° n p, has no such atmosphere.—A most remarkable object."

Plate XXXVIII. fig. 15 represents this wonderful object as seen with the 6-feet telescope. It has been several times examined, and as yet we have not seen the

* Outlines of Astronomy, p. 605.

slightest indication of resolvability. The outer ring is seen on a pretty good night completely separated from the nucleus surrounding the brilliant point or star. The light is very bright, and always appeared to be flickering, owing no doubt to the unsteadiness of the atmosphere. There is a small dark space to the right of the star, which indicates a perforation similar perhaps to that discovered in Nos. 838, 2050, and others. The annular form of this object was detected by Mr. JOHNSTONE STONEY, my assistant, when observing alone, and the sketch is his; I have however since had ample opportunities of satisfying myself that the object has been accurately represented. Plate XXXVIII. fig. 16 represents the other nebulous star, $\iota$ Orionis: the remarkable feature in this object, the dark cavity, not symmetrical with the star, was also discovered by Mr. JOHNSTONE STONEY when observing alone with the 3-feet telescope: I have since seen it several times and sketched it. The components of $\iota$ Orionis have not been laid down micrometrically, or even with care by the eye, but the dark cavity with respect to the stars is faithfully represented. If the dark cavity was symmetrical with the stars, it might perhaps be thought by some that the phenomenon was optical, but as it is the thing is impossible. A small double star $nf$ has similar openings, but they are not so easily seen. These openings appear to be of the same character as the opening within the bright stars of the trapezium of Orion, the stars being at the edges of the opening. Had the stars been situated all together within the openings, the suspicion would perhaps have suggested itself more strongly that the nebula had been absorbed by the stars. As it is, I think we can hardly fail to conclude that the nebula is in some way connected with these bright stars, in fact that they are equidistant, and therefore, if the inquiries about parallax, now proceeding with so much activity, should result in giving us the distances of these bright stars, we shall have the distance of this nebula.

The long elliptic or lenticular nebulæ are very numerous; I have given three sketches of remarkable objects of this class: the appearance of Plate XXXVII. fig. 7 suggests the idea of an elliptic annular system seen very obliquely. A series of very elliptic shells enveloping the nucleus, seen somewhat obliquely, would perhaps also present the same aspect. The dark chink in Plate XXXVII. fig. 8 might indicate either a real opening, the system being an elliptic ring, or merely a line of comparative darkness, the section through the axis of a very long narrow elliptic shell. In Plate XXXVII. fig. 9 there is a well-marked stratification, which might possibly be the appearance, Plate XXXVII. fig. 7, on the first supposition, would present if seen in another direction. It is to be hoped that as observations multiply, and these extraordinary objects which abound in the heavens are seen in various directions, we shall gradually become acquainted with their real form. At present further conjectures would be to no purpose.

The remaining sketch, Plate XXXVIII. fig. 17, is the dumb-bell nebula as seen with the 6-feet telescope: the sketch is by Mr. JOHNSTONE STONEY, and the form of the nebulosity and its various gradations of intensity have been represented with considerable fidelity. There was no subsequent opportunity of marking in the stars,

and therefore they have been inserted at random to complete the general effect, and many minute details are still wanting to make the figure complete.

As we have proceeded with our task of re-examining Sir JOHN HERSCHEL's Catalogue, several groups of nebulæ have been discovered, although new objects have not been as yet sought for. In some cases a nebulous connection has been detected between the individuals of the group, in others not. Sketches have been made and some measures taken. The whole subject of the grouped or knotted nebulæ is one of deep interest; but we have not proceeded sufficiently far with it to make it worth while to enter upon it in the present paper, and it only remains to point out a defect common to all the sketches which might mislead if not specially noticed. In sketching we necessarily employ the smallest amount of light possible, very feeble lamp-light, especially where the objects or their details are of the last degree of faintness. To see the sketch as we proceed it is often necessary to mark it too strongly: this would be of little moment if the excess of colour was always in the same proportion, especially as different eyes form a very different estimate of the relative intensities of a nebula and its representation on paper, but it is not so; the contrast between the faint and bright nebulæ and between the faint and bright parts of the same nebula is very liable to be made too slight. The most important error to guard against is that of supposing that the well-marked confines of the nebula on paper really represent the boundaries of the object in space in all cases. Frequently there is a very gradual fading away at the edge, the last trace of which is either a luminous mist becoming rarer till imperceptible; a gauge-like tissue of the faintish imaginary flocculi, or hairy filaments, which become finer and more scattered till they cease to be visible, showing that the real boundary has not been seen, and that the form of the object would alter if additional optical power could be brought to bear upon it. The same remark applies to the faint interior details, in most cases probably only in part seen.

Plate XXXV. figs. 1 and 2 are seen on a scale of half an inch to a minute; the others are on no regular scale: they are about the size of the figures which accompany Sir JOHN HERSCHEL's Catalogue, the smaller however have been somewhat enlarged where there were details which otherwise could not have been well represented.

Annexed are a few remarks relating to each figure, which seem to make the information conveyed by it more complete: they are for the most part extracts selected from our journal of observations; in a few cases, however, to save space, merely the substance is given.

Where the 3-feet instrument was employed it is specially mentioned; in every other case it was the 6-feet instrument.

Plate XXXV. fig. 1, H. 1622.—This object has been observed twenty-eight times with the 6-feet instrument; it had been repeatedly observed previously with the 3-feet instrument.

September 18, 1843.—Observed with the 3-feet instrument; power single lens,

1-inch focus; a great number of stars clearly visible in it, still HERSCHEL's rings not apparent, at least no such uniformity as he represents in his drawing.

April 11, 1844.—Observed with the 3-feet instrument, two friends assisting; both saw centre clearly resolved.

April 26, 1848.—6-feet instrument. Saw the spirality of the principal nucleus very plainly; saw also spiral arrangement in the smaller nucleus.

The following measurements were taken by my assistant, Mr. JOHNSTONE STONEY, in the spring of 1849 and 1850.

| | Mean of the observations of position. | No. of observations. | Greatest difference between observations and the mean. | Mean of the observations of distance. | No. of observations. | Greatest difference between observations and the mean. |
|---|---|---|---|---|---|---|
| | ° ′ | | ° ′ | ′ ″ | | ″ |
| N. n. | 16 34 | 4 | 3 27 | 4 22·2 | 4 | 9·6 |
| N. 1. | 52 4 | 1 | ..... | 2 6·6 | 1 | |
| N. 2. | 54 0 | 4 | 1 57 | 5 0·0 | 4 | 5·4 |
| N. 3. | 104 20 | 2 | 2 3 | 2 45·6 | 2 | 3·6 |
| N. 4. | 111 57 | 2 | 0 40 | 4 3·6 | 2 | 0·6 |
| N. 5. | 165 35 | 2 | 0 31 | 1 43·2 | 2 | 1·1 |
| N. 6. | 191 42 | 1 | ..... | 3 54·0 | 1 | |
| N. 7. | 211 2 | 1 | ..... | 2 36·6 | 1 | |
| 7, 8. | 270 42 | 1 | ..... | 0 34·8 | 1 | |
| N. 9. | 231 32 | 4 | 3 35 | 1 23·4 | 3 | 6·6 |
| 9, 10. | 197 57 | 1 | ..... | 0 27·0 | 1 | |
| N. 11. | 279 21 | 4 | 4 18 | 1 49·8 | 3 | 22·2 |
| 11, 12. | 225 27 | 1 | ..... | 0 12·6 | 1 | |
| N. 13. | 281 37 | 2 | 0 22 | 3 59·0 | 1 | |
| 14, 15. | 297 15 | 1 | | | | |
| N. 15. | 310 34 | 4 | 4 17 | 2 55·8 | 4 | 13·8 |
| N. α | | | | 3 22·8 | 2 | 0·1 |
| N. β ..... | 5 7 | ... | ..... | 1 28·2 | 3 | 3·0 |
| N. γ | | | | 2 37·8 | 3 | 2·4 |
| N. δ | | | | 1 46·2 | 1 | |
| N. ε | | | | 2 46·8 | 1 | |
| N. ζ ..... | 95 7 | ... | ..... | 1 40·8 | 1 | |
| N. η | | | | 3 15·6 | 1 | |

*Observations.*—There is a great discrepancy between the measured position of 11 and 12 and the rough diagram made at the time of observation.

N. 13 is twice noticed in the observing-book.

Once N. 11, 13 is taken as one position; the other times N. 11 and 13 are taken separately, N. 13 being made 1° 40′ less than N. 11; hence 270° 31′ is a more probable position for N. 13 than that given in the Table.

The Greek letters are perpendiculars from N. on tangents to the outsides of the convolutions, the tangents from α, β, γ being vertical, that is, parallel to the position 95° 7′, and those for δ, ε, ζ, η horizontal, *i. e.* parallel to position 5° 7′.

The greater part of the observations were made when the eye was affected by lamplight, which made it difficult to estimate correctly the centre of the nucleus; it was of importance that no time should be unnecessarily spent, and after the lamp had been used a new measure was taken, as it was judged that the object was sufficiently seen. With the brighter stars this would frequently happen before the nucleus was

well defined, as all impediments to vision seem to affect nebulæ much more than stars the light of which would be estimated as of the same intensity. In the foregoing list the greatest discrepancies are in the measures of bright objects, and this is probably the proper account of it. No stars have been inserted in the sketch which are not in the table of measurements. The general appearance of the object would have been better given if the minute stars had been put in from the eye-sketch, but it would have created confusion.

Plate XXXV. fig. 2, H. 1173.—This nebula has been repeatedly observed with the 6-feet instrument.

March 11, 1848.—Spiral with a bright star above; a thin portion of the nebula reaches across this star and some distance past it. Principal spiral at the bottom, and turning towards the right.

March 20, 1848.—Spirality very evident, though night bad: nebula not traced to upper star.

April 16, 1849.—Took measures of the stars 1, 2.

April 17, 1849.—Took measures of the stars 1, 2, 3, 4 from the nucleus; they are as follows:—

| No. | Mean of observations of position from north in direction n. f. s. p. | No. of observations. | Greatest difference between mean and observation. | Mean of observations of distance. | No. of observations. | Greatest difference between mean and observation. |
|---|---|---|---|---|---|---|
| | ° ′ | | ° ′ | ″ | | ″ |
| 1. | 34 1 | 1 | ..... | 2 54·6 | 2 | 9·6 |
| 2. | 80 35 | 2 | 0 18 | 1 46·3 | 3 | 14·4 |
| 3. | 117 3 | 3 | 0 23 | 1 48·4 | 4 | 13·6 |
| 4. | 177 57 | 1 | ..... | 2 48·1 | 1 | |

Three very minute stars in the eye-sketch have not been inserted, not having been measured.

Plate XXXVI. fig. 3, H. 604.—This nebula was observed frequently with the 3-feet instrument, but nothing remarkable seems to have been made out, except the resolvable character of the nucleus. It was first observed with the great telescope, March 24, 1846, and a tendency to an annular or spiral arrangement discovered; night bad; March 5, 1848, sketched.

March 9, 1848.—"Night excellent, a spiral seen in an oblique direction, resolved well, particularly towards the centre, where it is very bright; Dr. Robinson observing." Observed March 3, 1850; badly seen.

With the single exception of March 3, 1850, we have unfortunately no recent observation of this extraordinary object: it has been passed over, because to observe it, except on a very fine night, would be waste of time.

Plate XXXVI. fig. 4, H. 2205.—Observed frequently, and by many friends. The drawing represents the object with considerable accuracy.

"September 10, 1849.—Spiral, but query whether this is not more properly an annular than a spiral nebula."

The details are faint, but can be seen on any moderately fine night.

Plate XXXVI. fig. 5, H. 131.—This figure represents the central portion of a very large nebula. The nebula itself has not been sufficiently examined, but as yet no other portion appears to have a spiral, or indeed any regular arrangement. The sketch is not very accurate, but represents sufficiently well the general character of the central portion.

"September 6, 1849.—A spiral.

"September 16, 1849.—New spiral; $\alpha$ the brightest branch; $\gamma$ faint; $\delta$ short but pretty bright; $\beta$ pretty distinct; $\epsilon$ but suspected; the whole involved in faint nebula, which probably extends past several knots which lie about it in different directions. Faint nebula seems to extend very far following: drawing taken.

"September 10, 1849.—An attempt at a drawing taken: fog.

"October 1849.—The whole nebula in flocculi."

Plate XXXVII. fig. 6, H. 444.—"December 19, 1848.—Bright star between; tails and curved filaments; perhaps annulus around the two nebulæ.

"December 22, 1848.—Sketch made.

"February 11, 1849.—Lower streak seems to reach the filaments of right-hand nucleus."

Plate XXXVII. fig. 7, H. 854.—"March 31, 1848.—A curious nebula with a bright nucleus; resolvable; a spiral or annular arrangement about it; no other portion of the nebula resolved. Observed April 1, 1848, and April 3, with the same results."

Plate XXXVII. fig. 8, H. 1909.—"April 27, 1848.—A very bright resolvable nebula, but none of the component stars to be seen distinctly even with a power of a thousand. A perfectly straight and longitudinal division in the direction of the major axis. Resolvability most strongly indicated towards the nucleus.

"May 2, 1848.—Not seen so well as on April 27. Darkness in the middle, along the major axis barely visible.

"April 1849.—A long ray elliptical. Major axis perhaps eight times minor axis. Surface somewhat broken up, and a slight darkness in the direction of the major axis: night indifferent: at intervals a few stars faintly perceptible."

Plate XXXVII. fig. 9, H. 1397.—This sketch was made with great care by my assistant, Mr. Johnstone Stoney, and I have no doubt it is very accurate. Observed and sketched, April 19, 1849. It had been previously observed, March 26, 1848, by my former assistant, Mr. Rambaut, and I find the following note by him:—"A most extraordinary object, masses of light appear through it in knots."

Plate XXXVII. fig. 10, H. 399.—Observed December 22, 1848, February 11, 1849, and January 16, 1850, when the drawing was taken. The two comparatively dark spaces, one near the vertex and the other near the base of the cone, are very remarkable.

Plate XXXVII. fig. 11, H. 838.—September 27, 1843.—(3-feet telescope.) Night pretty good; a star in the centre and apparently ragged outline.

March 7, 1848.—(6-feet telescope).—Night bad: aurora. Darkness in the centre; star not certainly seen; outline ragged.

March 11, 1848.—Seen by Dr. Robinson and my former assistant, Mr. Rambaut; sketch made of it. "Two stars considerably apart in the central region; dark penumbra around each spiral arrangement, with stars as apparent centres of attraction; stars sparkling in it, resolvable; night excellent." Note by Mr. Rambaut: "March 5, 1848.—Saw two dark and very large spots in the middle; Lord Rosse remarked that all round its edge the sky appeared darker than the average."

"March 11, 1848.—Remarkably fine night; a brilliant star in the centre; also star to the right; round each a black space (see sketch)." Note by Mr. Rambaut: "March 25, 1848.—Air steady, but slight haze; large star visible. Only at one clear interval could I get a glimpse of the spiral arrangement of this nebula, which I should have totally overlooked had I not seen it so plainly on a former occasion.

"March 26, 1848.—Second bright star visible; spiral arrangement hardly perceptible; not seen so well as on the 11th of March.

"March 27, 1848.—Not seen so well as last night; second star seen at rare intervals, power 468.

"March 28, 1848.—Night hazy, could not see second star."

"March 31, 1848.—Caught one glimpse of second star, but saw the large star very plainly.

"April 1, 1848.—Night hazy; spiral arrangement little more than suspected; nebula very faint.

"April 3, 1848.—Small star distinctly seen; spirals tolerably well brought out; hazy, but air steady.

"April 6, 1848.—First star seen easily, though hazy; the second only occasionally; spiral arrangement hardly discernible.

"January 1850.—Seen very imperfectly; only one of the stars seen.

"March 9, 1850.—Second star only seen for a moment." Several attempts were made to procure measures of position and distance of the two stars this spring, but in vain, the season was so unfavourable. In 1848, the micrometer requiring illumination, no attempt was made. With the micrometer as at present mounted there would not have been the slightest difficulty in procuring measures.

Fig. 12, H. 464.—"Annular nebula at the edge of the cluster M. 46. Sketched December 22, 1848 annular, two stars in it.

"January 27, 1849.—A third star suspected in brightest part.

"January 29, 1849.—Third star strongly suspected.

"February 13, 1849.—Observed, nothing further.

"March 16, 1849.—Saw but two stars in it."

Fig. 13, H. 2241.—"October 31, 1848.—Has a central spot, at moments very dark.

"December 13, 1848.—Nothing more, except perhaps that faint external annulus extends further than had been seen before.

FRANKLIN INSTITUTE LIBRARY

"December 14, 1848.—Note by Mr. Johnstone Stoney:—'Three stars near it, somewhat in this fashion; showed it to Sir James South.'

"December 16, 1848.—Sketches made by Lord Rosse and Mr. Johnstone Stoney.

"December 19, 1848.—Drawing confirmed."

Fig. H. 14, 2098.—"Observed October 23, 1848, and sketch made.

"October 25, 1848.—Sketch confirmed.

"August 16, 1849.—Position of ring taken with an eye-piece furnished with a level and a position circle. Inclination of ring to horizon 9°."

Fig. 15, H. 450.—"February 20, 1849.—Most astonishing. The star perhaps a little nearer the *n p* edge. Drawing made; breadth of ring less on *f* side.

"February 22, 1849.—Observed again; dark space to the right of star.

"January 16, 1850.—Observed; examined with the 700 and 900 eye-pieces; both the dark and the bright rings seemed unequal in breadth; the light appeared unsteady and flickering. The night was rather foggy, but the sky black."

Fig. 16, H. 361.—"January 28, 1849.—ι Orionis. Dark space in the nebula containing nearest companion; light nearly equable; sketch made; 3-feet telescope employed. All the stars in the neighbourhood are nebulous, of these two a little *s p*, last seem to have dark spaces as in figure. To the *n f* of this there is another smaller double star, suspected to have similar dark spaces to ι Orionis.

"February 16, 1849.—Three-feet telescope confirmed observation of January 28, 1849.

"March 17, 1849.—Large triple star to south of nebula Orionis; confirmed observation of opening in its atmosphere, also the openings at double star *s p* last."

Fig. 17, H. 2060.—"Observed September 9, 1849. Drawing commenced.

"September 16, 1849.—Drawing proceeded with; examined also with 3-feet telescope to find if any evidence of change since drawing in Philosophical Transactions was taken; none decisive."

*List of some remarkable Nebulæ.*

Spiral or curvilinear.

H. 142, 262, 327, 695, 749, 910, 1002, 1211, 1312, 1368, 1451, 1570, 1776, 2172.

With dark spaces.

264, 368, 491, 514, 692, 731, 788, 857, 887, 1107, 1225, 1909, 2241.

Ray with split.

1041, 1149, 1357.

Knotted nebulæ.

84, 257, 320, 409, 446, 581, 1274, 1901.

## XXVI. *On the Structure and Use of the Ligamentum Rotundum Uteri, with some observations upon the change which takes place in the Structure of the Uterus during Utero-gestation.* *By* G. Rainey, *M.R.C.S., Demonstrator of Anatomy at St. Thomas's Hospital.* *Communicated by* Joseph Henry Green, *Esq., F.R.S.*

Received January 15,—Read April 11, 1850.

PRIOR to the discovery of the striated character of voluntary muscle, about 1765, by Fontana, physiologists were unacquainted with any certain mark by which they could distinguish this variety of muscle from many other structures; and physiology being at that period in advance of anatomy, the question of the muscularity of many parts was obliged to be decided by their function instead of by their structure; but in the present state of minute anatomy, improved as it has been of late by the researches of microscopists, physiology and anatomy are made to move more in parallelism; this is especially the case with respect to the muscular system, so that if a muscle be made up of a bundle of fascicles of nearly equal size, and each one be marked transversely with parallel striæ, it is known to act either directly in obedience to the will, or to be capable of being called into operation through excito-motory influence, whilst a muscle consisting merely of an aggregation of fibres more or less distinctly nucleated, is known to act independently of the will; hence muscles are now named according to their function, voluntary and involuntary; or according to their structure, striped and unstriped. In the class of striped muscles physiologists are agreed to place the voluntary muscles, the upper part of the human œsophagus, and the heart; in that of unstriped ones, the muscular coat of the intestinal canal, the bladder, the uterus and round ligaments. As it respects the parts included in the latter division of this classification, I am obliged to dissent altogether in reference to the structure of the round ligaments of the uterus, having found in every subject in which I have examined them (the number being about a dozen) well-marked muscular fibres of the striped variety, in fact that they correspond in all respects to regular voluntary muscles: with this conviction I am desirous to communicate the result of my observations to the Royal Society. I may also add, that I have in my possession numerous preparations, microscopic as well as ordinary dissections, in which the accuracy of the facts stated in this paper are easily demonstrable.

The so-called round ligament of the uterus, regarded as a muscle, may be said to arise by three fasciculi of tendinous fibres; the inner one from the tendon of the internal oblique and transversalis near to the symphysis pubis, the middle one from the superior column of the external abdominal ring near to its upper part, and the

external fasciculus from the inferior column of the ring just above GIMBERNAT's ligament; from these attachments the fibres pass backwards and outwards, soon becoming fleshy; they then unite into a rounded cord, which crosses in front of the epigastric artery and behind the lower border of the internal oblique and transversalis muscles, from which it is separated by a thin fascia continuous with the fascia transversalis; it then gets between the layers of peritoneum forming the broad ligament of the uterus, along which it passes backwards, downwards, and inwards to the anterior and superior part of the uterus, into which its fibres, after spreading out a little, may be said to be inserted.

The striated muscular fibres are not confined merely to the surface of the round ligament, as if only accessory to some more important part of it, but they form almost the whole of its substance, and are more particularly distinct near to its centre; nor do they extend completely to the uterus, but after passing between the layers of the broad ligament to about the distance of an inch or an inch and a half from its superior part, they gradually lose their striated character, and degenerate into fasciculi of granular fibres mixed with long threads of fibro-cellular tissue. Plate XXXIX. fig. 1 is an accurate representation of some muscular fibres taken from the centre of the round ligament, where it is situated between the layers of the broad ligament, about one inch and a half from the uterus. Fig. 2 is also a representation of some muscular fibres taken from a part rather nearer to the uterus, showing the manner in which the striped muscular fibre terminates in the granular fibres above mentioned. This structure of the round ligaments is not, as might be expected, confined to the human species. In the Monkey these ligaments are composed almost entirely of striped muscular fibre, which extends all along them nearly as far as the uterus. The uterus in a monkey which I examined was very small, but the round ligaments were proportionally large: the primary fasciculi of muscular fibres were pale but very distinctly striated. In the Dog, as most probably in other animals in which the uterus divides into cornua extending into the abdomen considerably beyond the brim of the pelvis, the round ligaments, instead of passing downwards to be attached to the pelvis, as they are in the human subject, in whom the uterus is situated below its brim, pass from the extremities of the cornua of the uterus upwards, or rather forwards to the last rib. Hence in these instances, these ligaments, or rather muscles, may be said to arise from the last rib, and from the aponeurosis of the diaphragm, by a thin triangular expansion, partly tendinous, and partly muscular (the fibres of the muscle being pale but of the striped kind), and to be inserted into the cornua of the uterus, having the same relation to the Fallopian tubes and ligaments of the ovaries as in the animals which have a simple uterus. In the Sheep and the Cow the attachments of the round ligaments are similar to those in the Dog, and composed likewise of muscular fibres distinctly striated. Besides striped muscular fibres these ligaments contain numerous vessels, also some nerves and absorbents. The arterial trunks are large, but the capillaries into which they ultimately divide have the same size and arrangement as

those of ordinary muscle. The lymphatics are situated on the outer side of the ligament; their glands are sometimes of considerable length, and even pass through the external abdominal ring; connecting all these parts together, there is a considerable quantity of areolar tissue, especially where the striated muscular fibres are absent, or are about to terminate. In this part the detection of these fibres will be facilitated by examining the part in glycerine, which renders the fibro-cellular tissue more transparent without impairing in any considerable degree the distinctness of the striated muscle*. It is generally said that the round ligament passes through the external abdominal ring, and "is LOST in the cellular tissue of the mons veneris and labia pudendi." It is true that the vessels supplying it, and a nerve, and some lymphatics, and frequently a gland, pass through the external abdominal ring, but the substance of the ligament is situated altogether above it so as in part to close it, and thus to tend very much to prevent the protrusion of intestine at this part, whilst it would facilitate its passage through the crural ring by directing it towards GIMBERNAT's ligament; hence probably the reason why females are more liable to femoral than to inguinal hernia.

Those who have written upon the office of the round ligaments of the uterus, regarding them either as made up of muscular fibres of the same kind as those of the uterus itself, or considering them as composed merely of "condensed cellular tissue," have considered their office, either as subservient to the process of utero-gestation, or as acting merely as mechanical supports to the uterus, that is, as uterine suspensory ligaments. Now the presence of voluntary (striped) muscular fibre in these so-called ligaments, proves that neither of these suppositions is correct, since striped or voluntary muscular fibre would be as unfit for the one purpose as it would be superfluous for the other; hence there can be but little doubt that these ligaments, or rather muscles, are concerned in some way or other with the act of copulation, rather than with those changes which are so slowly induced in the uterus during utero-gestation. Considering the position of the points of attachment of the round ligaments,

* Besides the structures just mentioned, these fibres are mixed with several pale, and much less distinctly striated ones, which resemble in all respects the tissue of the Dartos. The fibres of the Dartos are generally considered merely as fibro-cellular tissue, but they seem to possess characters by which they can be distinguished from other tissues. These fibres, both from the scrotum and the round ligament, the upper part especially, when examined by the microscope in water, appear to be made up of very fine threads of wavy fibre, mixed with extremely minute granules or molecules, by which their distinctness of outline is much obscured and rendered much less apparent than in the fibres of common areolar tissue; they are also more collected into bundles than is fibro-cellular tissue; but these same fibres, when examined in glycerine, become corrugated, resembling somewhat striped muscle; in some instances, indeed, the resemblance is so great, that it is difficult, if not impracticable, to distinguish between a bad specimen of striped muscular fibre and a good one of this tissue. Common fibro-cellular tissue is not corrugated by glycerine, but only rendered more transparent.

The distance to which the striped fibre extends towards the uterus, and the degree of its distinctness, differ very much in different subjects; in one subject I found it not more than an inch from the uterus. In the employment of glycerine to aid the detection of striped muscle and the corrugated tissue, it is sometimes necessary to allow these structures to remain in the glycerine a few minutes before its full effect is produced.

and the direction of their fibres, it is evident that their combined action will bring the uterus nearer to the symphysis pubis, and thus tend to draw it somewhat from the vagina, in this way increasing the length of the latter. Now the only way in which I can imagine that these changes in the position of these parts assist in sexual intercourse, is by their causing the semen to be attracted more into the upper part of the vagina and vicinity of the os uteri. [Since the communication of this paper to the Royal Society I have been informed that this opinion is not new, but that this view of the use of the round ligament had been published by M. Velpeau*, and that it is also partly in accordance with that of Maygriers†.] This supposition seems to accord with the position and attachments of the round ligaments in those animals in which the uterus extends into the cavity of the abdomen beyond the brim of the pelvis, as was noticed in the Dog, the Sheep and the Cow, where their action would, obviously, be the same in drawing the uterus from the vagina, and in tending to elongate the latter, as in the human subject in whom the angles of the uterus are below the level of the broad ligaments. In such an act the muscular fibres of the round ligaments could scarcely be said to be voluntary; but still they would be as much so as the other muscles concerned in the same process, that is, as those of the male organs of generation. In these instances muscles are said to act under excito-motory influence, but muscles which are thus excited have the same structure as those more obviously under the control of the will, namely, striped fibres.

*Some observations upon the change which takes place in the Structure of the Uterus during Utero-gestation.*

The fasciculi of fibres composing the upper part of the round ligament separate as they approach the fundus of the uterus, become spread out over its surface, and ultimately blend with its fibres. Although the fibres of the round ligament are generally said to be of the same kind as those of the uterus, I have not been able to perceive much similarity, either with those of the unimpregnated or the impregnated uterus, the fibres in both these states of the uterus being peculiar. The proper tissue of the unimpregnated uterus is so remarkably dense that there is considerable difficulty in unraveling it sufficiently to display the true character of its fibres, and sections thin enough to admit of being seen as a transparent object by the microscope, give no distinct idea of its real nature. Its characters can be best understood by breaking up portions of the uterus with needles, and examining them in glycerine, but still they should be first seen in water; also the arteries of the uterus should be fully injected (these are remarkably tortuous, and possessed of very thick coats), otherwise the tissue of the small vessels, and the nuclei in the coat of the capillaries, may be examined instead of, and mistaken for, the proper fibre of the uterus. Any part of the unimpregnated uterus, after having been thus treated, will be seen to be made up

* Anatomie Chirurgicale, 1833, vol. ii. p. 372.

† Nouvelles Démonstrations d'Accouchements, p. 62.

of fusiform nucleated fibres, contained in a matrix of exceedingly coherent granular matter; these are well represented in fig. 3. The average breadth of one of these fibres, at its dilated or nucleated part, is about $\frac{1}{1000}$th of an inch; their length cannot be ascertained with certainty, as it is impossible to estimate the degree of curtailment which they suffer in being separated from the granular matrix in which they lie imbedded. Their structure and size are about the same in every part of the uterus from which I have taken them, so that they are easily recognizable as the peculiar fibres of the unimpregnated uterus. Now comparing these fibres with those forming the walls of the impregnated one, at the full, or at a very advanced period of impregnation, it will be seen that these fibres are become greatly increased in size, deprived of nuclei, and more loosely connected together; they lie in separate planes, which cross each other in various directions; they are accompanied with vessels of various sizes, also with more or less fibro-cellular tissue. The size of these fibres is moderately uniform, but those near to the external surface are rather smaller than those more deeply seated. A fibre detached from the rest measured about $\frac{1}{40}$th of an inch in length and about $\frac{1}{1000}$th in breadth at its widest part; for the breadth varies much in different parts of the same fibre, being alternately large and small; at their extremities they taper off to a very fine point; their colour is yellowish, and when minutely examined, they appear to be made up of very small irregular granules and extremely slender threads blended together without any definite arrangement (see fig. 4). Acted upon by acetic acid they give no indication whatever of being nucleated, therefore in this respect they differ from the common form of organic muscular fibre*. The two kinds of fibres, represented in figs. 3 and 4, were both drawn under the same magnifying power, in order to show, by a comparison of their dimensions, that the increase which takes place in the individual fibres in these different states of the uterus, is quite sufficient to account for the amount of augmentation of the entire organ, without supposing, as some physiologists do, that organic muscular fibres, not present in the inactive state of the uterus, are absolutely formed during the various stages of its enlargement; it also, besides being supported by the fact just stated, perfectly accords with the laws of development, and harmonizes with the changes which are going on simultaneously in the walls of the impregnated uterus and its contents; the unimpregnated uterus being, according to this notion, little more than an assemblage of embryonic nucleated fibres, wholly inactive, until after the reception of the ovum, when, being aroused by an appropriate stimulus, they are called into active operation, and become developed simultaneously and proportionally to the development of the fœtus contained within it, so that when the one has arrived at a state requiring to be expelled, the other has acquired the utmost degree of fitness necessary to effect its expulsion. Now after the expulsion of the fœtus, since, according to the laws of de-

* Professor Kölliker has described the fibres both of the unimpregnated and impregnated uterus. The latter he has described and figured as having nuclei, which I have never been able to verify although I have examined these fibres with the greatest possible care.

velopment, it is as impossible that these fibres of the impregnated uterus can return again to their primitive or embryonic condition, as that a full-formed fœtus could relapse into the state of an ovum, they must necessarily become absorbed, and therefore a new set of embryonic fibres would require to be formed for the expulsion of the next ovum, so that each fœtus will have, according to this conclusion, its own peculiar expulsory fibres. This view is perfectly in accordance with the late researches of Drs. Sharpey and Weber on the membrana decidua; and it agrees with the same function in vegetables, in which the part corresponding to the uterus in animals is always cast off after its contents have been brought to maturity, and separated from the parent plant.

## Description of the Plate.

### PLATE XXXIX.

Fig. 1. Represents some muscular fibres taken from the central part of the round ligament of the uterus of the human subject, where it is situated between the layers of the broad ligament.

Fig. 2. Represents some muscular fibres taken from a part of the round ligament nearer to the uterus than those shown in fig. 1: there the termination of the striated fibres in fasciculi of granular ones is shown.

Fig. 3. Represents nucleated fibres taken from the unimpregnated human uterus, and the granular matrix in which they are imbedded.

Fig. 4. Represents fibres taken from the impregnated human uterus at the eighth month of pregnancy.

## XXVII. *On the Communications between the Cavity of the Tympanum and the Palate in the* Crocodilia (*Gavials, Alligators and Crocodiles*).

*By Professor* Owen, *F.R.S. &c.*

Received December 20, 1849,—Read February 28, 1850.

THERE are three perforations which succeed each other along the middle line of the base of the cranium in the Crocodilian Reptiles. The hindmost (Plate XL. fig. 1, *v*), situated in the basioccipital, near the condyle, is the smallest and least constant in size and existence: it gives passage to a vein, which traverses a vertical canal in the bone homotypal with the vertical vascular canal that opens upon the under surface of the bodies of the vertebræ of the trunk. The next foramen in advance, *e*, is larger and on a lower level; it is constantly present and is regular in its size and position: it perforates the fore part of the basioccipital close to the basisphenoid. The third or anterior foramen, *n*, is the largest, and opens on a still lower plane: it is formed entirely by the pterygoids, which it perforates in a forward direction, and is the posterior aperture of the nasal passages.

There exists a difference of opinion as to the nature of these latter foramina, and especially as to the function of the middle foramen, *e*, viz. that which perforates the basioccipital close to the basisphenoid. Cuvier describes it in his celebrated chapter on the Osteology of the Crocodile, in the last volume of the 'Ossemens Fossiles,' p. 78, 4to, 1824, as leading to "a canal which traverses the body of the sphenoid, and terminates by two branches opening into the 'sella turcica,' and, at p. 133, he refers to it in the cranium of the 'Gavial de Caen' (*Teleosaurus cadonensis*, Geoffroy), as an arterial foramen ('le trou des artères')." The continuators of Cuvier, in the posthumous edition of the 'Leçons d'Anatomie Comparée,' t. ii. p. 523, describe the foramen in question more accurately, as leading to a canal which bifurcates as it ascends; one of the branches traversing obliquely the body of the sphenoid, whilst the other perforates the basilar part of the occipital, and opens into the cavity of the internal ear. They do not state where the branch terminates which traverses the basisphenoid*, nor what passes through either canal.

In the description of the tympanic cavity of the Crocodile†, no mention is made of this communication, or of the Eustachian tube, which is described in the Saurians

* I use here, and throughout this paper, the English equivalents of the French phrases defining the bones of the Crocodile's skull, according to the table of synonyms, No. 1, in my work 'On the Archetype of the Vertebrate Skelton,' 8vo, 1848.

† *Op. cit.*, tom. iii. p. 512.

generally as communicating with the palate by a wide and short canal (p. 511). But in a supplementary paragraph to Cuvier's description of the foramina in the base of the skull of the Crocodile, the osseous aperture of the Eustachian tube is stated to be perforated in the exoccipital, near its junction with the basioccipital, and to be situated below the anterior condyloid foramen*.

In the 'Report on British Fossil Reptiles,' communicated to the British Association in 1841†, I described the foramen in the basioccipital, *e*, as the common terminal canal of the Eustachian tubes, and the foramen in advance of it, *n*, as the posterior aperture of the nasal canals.

In the 'Abhandlungen über die Gavial-artigen Reptilien des lias-formation,' fol. 1841, by Professors Bronn and Kaup, it is argued at great length (pp. 12, 16, 24) that the median foramen, *e*, is the true posterior aperture of the nostrils; and a letter from Professor De Blainville, dated December 8th, 1841, is cited by those authors in support of their view, in which letter Cuvier's determination, that it was 'an arterial foramen,' is rejected, and Professor Bronn's opinion is stated to be completely confirmed by the appearances in the original fossil skull of the *Teleosaurus* from Caen, described and figured by Cuvier.

Besides the median foramina above specified, there are several lateral foramina, in symmetrical pairs, in the same part of the base of the skull of the Crocodile. One on each side the base of the condyle, Plate XL. fig. 1, *p*, is the 'precondyloid foramen,' which gives exit to the hypoglossal nerve: external to this is a larger foramen, *t*, through which pass the eighth pair of nerves and a vein from the tympanic cavity; below these, and still in the exoccipital (2), is the foramen, *c*, described by the continuators of Cuvier as the bony outlet of the Eustachian canal; and still lower down, in the suture between the basioccipital (1) and basiphenoid (5), is the foramen, *el*, which I have not found noticed by any anatomical author.

The decisive test of the nature of these latter foramina, *el*, and of the different opinions respecting the foramina, *c*, *c*, and the median foramina, *e* and *n*, was, of course, to be sought for in the results of an accurate anatomical examination of the parts in the recent Crocodile. I have, accordingly, availed myself of the opportunities liberally afforded to me by the Council of the Zoological Society, to dissect for this purpose specimens of an Alligator (*Alligator lucius*) and a Crocodile (*Crocodilus acutus*) which have died at the Zoological Gardens; the examination being made after injecting the vessels of the head with coloured wax.

The entocarotid arteries (Plate XL. fig. 2, *c*) enter the foramina (fig. 1 *c*, *c*) situated, one in each exoccipital bone, 2, at the side of the base of the condyle, below

* "Le trou condyloïdien est dans l'occipital latéral, et en dehors de lui est un trou assez grand pour des vaisseaux. L'ouverture osseuse de la trompe d'Eustache est au dessous des précédents, aussi dans l'occipital latéral, et tout près du point de réunion de cet os avec le basilaire et le sphénoïde."—Leçons d'Anat. Comp. tom. ii. p. 524, 1837.

† Reports, 8vo, p. 96.

the outlet for the hypoglossal and eighth pair of nerves, *t* and *p*. In a young Crocodile, with a head of eleven inches in length, the common trunk, fig. 2, *cc*, of both carotids is continued along the under surface of the cervical vertebræ as far as the dentata, where it bifurcates into the two carotids: these diverge, ascend, inosculate with the vertebral artery, *v*, and subdivide into the ectocarotid, *ec*, and entocarotid. The latter artery, *c*, at the first part of its course, extends obliquely forwards inwards and upwards, protected by a bony canal, half an inch in length, which terminates by projecting freely as a tube of a line in length (Plate XLI. fig. 4, *c*), opening into the cavity of the tympanum beneath the bony plate, 16, to which I have restricted the term 'petrosal*.' The artery emerging from the bony canal extends forward across the base of the tympanic cavity, covered only by a reflexion of its lining membrane, for about a third of an inch, and then enters a second bony canal, opening into the fore part of the tympanum, and continued to the 'sella turcica,' where the carotid enters the cranial cavity, as is shown in Plate XL. fig. 3, *c*.

No artery enters the single median foramen, Plate XL. fig. 1, *e*, situated close to the suture between the basioccipital and basisphenoid. The soft palate which covers this part, immediately behind the true posterior nares, forms a subcircular protuberance with a single central aperture (Plate XLI. fig. 5); this aperture is also partly closed by a valvular membranous prominence, *x*, which reduces its area to a crescentic form. This orifice in the soft palate is not, as I had supposed, continued exclusively from the bony orifice in question, *e*, immediately above it; but is the common palatal outlet of three canals, one of which, *e*, is median, extending into the bony canal, figs. 6 and 7, *e*, which ascends into the substance of the basisphenoid; the other two, *el*, are membranous for the extent of eight lines, and diverge as they ascend to penetrate the fissures, fig. 7, *el*, one on each side of the larger median foramen, and which lead to canals, fig. 7, *el'*, extending upwards between the basioccipital and basisphenoid.

From the inferior openings, Plate XL. fig. 1, *el*, of these canals in the dry skull, grooves lodging their membranous prolongations are continued to the common median fossa into which the middle osseous canal, fig. 7, *e'*, opens by the foramen, *e*, in question. Dissections of the recent parts demonstrated that this foramen, like the two lateral canals, communicated by a membranous tube (fig. 5, *e*) with the surface of the palate and would receive air from the mouth. It was next to be determined where the air would be conducted by those tubes; and the passage leading from the median foramen was first traced. In an alligator with a head 14 inches in length, the foramen, *e*, leads to a canal lined by a continuation of the palatal membrane, which ascends along the suture between the basioccipital and basisphenoid, for nearly 2 inches, and then bifurcates; one branch inclining forward into the basisphenoid, the other rising vertically into the basioccipital, and both in the same

* It was probably the observation of this structure in the dry skull that misled the continuators of Cuvier into the belief that the canal, *c*, was the osseous part of the Eustachian tube.

median plane. I followed out the further course of these canals in the skull of a *Crocodilus acutus* of about the same size as the recent Alligator. Figure 7, Plate XLI. shows the common median canal extending from *e* to *e'*, where it divides. Each of these branches subdivides, and sends its subdivisions, one to the right the other to the left, to communicate with the tympanic cavity. The lateral canals, *el'*, which commence below at *el*, one on each side of the median foramen, communicate with the lateral subdivisions, *eo*, of the posterior or basioccipital branch of the common median canal; a small rhomboidal sinus, *eo'*, being formed at their point of union, from which a short canal is continued to the tympanic cavity. Thus each lateral canal, *el'*, with each posterior lateral subdivision, *eo*, of the basioccipital branch of the median canal, has a common opening into the base of the tympanic cavity of its own side. Each lateral subdivision, *es*, fig. 8, Plate XLII., of the anterior or basisphenoid branch of the median canal opens into the tympanic cavity at *es*, fig. 10, in advance of the preceding orifice. The lining membrane of these several canals here becomes continuous with that of the tympanic cavity.

Thus it was seen that no passage from the median orifice or canal in question, *e*, figs. 1 and 7, between the basioccipital and basisphenoid, conducted to the nasal passages, but that all the branches from that common orifice opened into the tympanic cavity: at the same time it was demonstrated, that the communication between the tympanum and the palate, commonly called the 'Eustachian tube,' was more complex in the Alligator and Crocodile than had been suspected, or than was known to exist in any other animal. It may be described as follows:—From each tympanic cavity two passages are continued downward, one from the fore part, Plate XLII. fig. 10, *es*, the other from the floor, *ib. eo*, of the cavity. The anterior canal, *es*, passes downwards and inwards, expands and again contracts before it unites with its fellow from the opposite side at *es'*, fig. 8, to form a median canal, *es'* to *e'*, which passes from the basisphenoid to the space or broad suture between that bone and the basioccipital, where it terminates in the single subvertical canal, *e'* to *e*, descending along that suture to the median foramen in question, *e*, fig. 1.

The opening at the floor of the tympanic cavity, *eo*, fig. 10, leads to a short canal, *eo*, figs. 7 and 8, which curves towards its fellow from the opposite tympanum, but first swells into the rhomboid sinus, fig. 7, *eo'*, and divides; one branch descends almost vertically, *el'*, and terminates by the small foramen, *el*, fig. 1, in the osseous groove or channel leading to the central aperture and fossa; the other branch, *eo* to *eo'*, fig. 8, continues the course inwards and downwards until it meets its fellow at the median line of the basioccipital at *eo'*, and forms the posterior primary division of the common median canal, *eo* to *e*: this soon joins the anterior division, at *e'*, to form that common canal, which then descends and terminates by slightly expanding into the foramen, *e*, at the middle of the fossa between the basioccipital and basisphenoid; which fossa receives also the grooves lodging the membranous canals from the lateral fissures. Finally, the three bony canals terminate by their membranous continuations

*e* and *el*, fig. 5, Plate XLI., in the single Eustachian valvular outlet, *x*, on the soft prominence behind the posterior nares, *n*.

The canals from the lateral orifices, *el*, are partially divided by a longitudinal ridge of bone projecting into them from their anterior wall: and the dilated lateral branches of the alisphenoid division of the median canal, *es*, are impressed by a longitudinal groove. I may also remark, that at the upper part of their place of confluence or termination, there is a median fossa leading to a small vascular canal.

The tympanum of the Crocodiles, Plate XLII. fig. 10, is very extensive, by reason of the air-cells continued from it, not only into the mastoid, but across the basi-occipital and basisphenoid*, and into the exoccipital, supraoccipital†, alisphenoid and parietal bones‡.

By the dissection of a young Gavial of the Ganges, preserved in spirits, and a comparison of this with sections of the cranium of a full-grown specimen, I have satisfied myself that the third median system of Eustachian tubes, as well as the two lateral tubes, exist in the Gavials as in the Alligators and true Crocodiles; only in the Gavial the common terminal canal of the median system is shorter, as is shown in Plate XLII. fig. 9, *e*, *es*, *eo*.

It appears to have been still shorter in the extinct *Teleosauri*; the posterior primary division of the canal which penetrates the basioccipital forms, in the section of the skull of the Caen Teleosaur, a subcircular depression, which is filled with the matrix in the Parisian specimen. The anterior primary division, answering to *es*, fig. 9, plainly perforates the substance of the basisphenoid, as it ascends obliquely forwards, and therefore can by no means be regarded as the posterior termination of the nasal passages, which, in the *Teleosauri*, are surrounded exclusively by the pterygoids, as in all the existing forms of *Crocodilia*.

With regard to the homologies of the above described complex Eustachian or palato-tympanic air-passages in the *Crocodilia*, the lateral bony canals, *el'*, fig. 7, terminating at the grooves, *el*, answer to the simple Eustachian tubes of lizards and mammals: the median canal, *e*, *e'*, with its dichotomous divisions, is a speciality peculiar to the *Crocodilia*.

I forbear, with my present limited experience of the living habits and actions of the Crocodilian Reptiles, to offer any hypothesis as to the function of the complex canals which conduct the air and would convey its sonorous vibrations from the nose to the ear: but one peculiarity I may suggest, as being probably related to the structures in question, in which the Crocodiles and Gavials differ from all the Lizard-tribe, viz. that of habitually floating with the operculated meatus externus submerged, and only the eyes and the prominent nostril exposed above the surface of the water. Any noise in the air that might reach the floating reptile would, under such conditions, be conveyed to the tympanum by the canals conducting to that cavity from near the

* On the Archetype of the Vertebrate Skeleton. 8vo. Van Voorst, fig. 9, p. 22, 1 and 5.
† *Ibid.* 3.
‡ *Ibid.* fig. 19, p. 120, 6 and 7.

hinder opening of the long nasal passage; and it may also be remembered, that there is a peculiar valve in the Crocodiles which shuts off all communication between that passage and the mouth.

## Description of the Plates.

### PLATE XL.

Fig. 1. A view of the hinder part of the base of the skull of a Crocodile, showing:—
- *v*. The venous foramen.
- *e*. The median Eustachian foramen.
- *el*. The lateral Eustachian foramina (the canal, *el'*, is laid open on the right side).
- *n*. The posterior nasal aperture.
- *c*. The carotid foramina.
- *p*. The precondyloid nervous foramina.
- *t*. The foramen jugulare.
- 1. The basioccipital.
- 2. The exoccipital.
- 5. The basisphenoid.
- 24. The pterygoid. The bristle ending at this figure is passed through the median canal and right subdivision of its basioccipital branch through the sinus of communication with the lateral canal, which is laid open between *t* and *c*.

Fig. 2. A view of an injected preparation of the *Crocodilus acutus*, showing the course of the carotids *cc*, vertebral artery *v*, and entocarotid *c*, to its foramen, and through the posterior bony canal into the tympanic cavity.

Fig. 3. Showing the emergence of the entocarotids, *c*, from their anterior bony canals opening into the sella turcica, their sinuous course forwards, and confluence into the single artery continued into the rhinencephalic division of the cranium.

### PLATE XLI.

Fig. 4. A section of the skull of a *Crocodilus biporcatus*, showing the free or prominent tubular termination of the posterior bony carotid canal in the tympanic cavity; *c*, a style passed through the canal; 16, the petrosal.

Fig. 5. A section of the bony and soft parts of the palate of an Alligator (*All. lucius*), showing the posterior nares, *n*, the common median valvular aperture, *x*, of the median, *e*, and the two lateral, *el*, Eustachian canals; bristles are passed along the membranous portions of these tubes.

Fig. 6. The opposite side of the same section, showing the median bony Eustachian canal, *e*, the lateral membranous Eustachian canals, *el*, cut off where they join the lateral bony canals, and the pterygoid air-cells, *pt*, communicating with the posterior nares, *n*, *n*.

Fig. 7. A section of the cranium of the *Crocodilus acutus*, showing the course of the median Eustachian canal, *e*, to its bifurcation at *e'*, the division of the basi-occipital branch, *e'* to *eo*; the course of the left lateral Eustachian canal, *el'*, to its communication, at the rhomboidal sinus, *eo'*, with the tympanic branch of the basioccipital division of the median Eustachian canal.

## PLATE XLII.

Fig. 8. A vertical section of the cranium of the *Crocodilus biporcatus*, a little to the left of the median line, showing part of the left tympanic branches, *es*, *eo*, and the orifices, *es'*, *eo'*, of the right tympanic branches, of the primary divisions of the median canal, *e'* to *e*.

Fig. 9. A vertical median section of the cranium of a Gavial, *Gavialis gangeticus*, showing the basioccipital division, *eo*, and the basisphenoid division, *es*, of the median Eustachian canal, *e*.

Fig. 10. A vertical section of the tympanic cavity of the *Crocodilus biporcatus*, showing bristles inserted into the basioccipital branch, *eo*, and basisphenoid branch, *es*, of the Eustachian tube; *c*, the entry of the entocarotid canal.

# XXVIII. *On the Structure of the Dental Tissues of the Order Rodentia.*

*By* John Tomes, *Surgeon-Dentist to the Middlesex Hospital.*
*Communicated by* William Bowman, *Esq.*, *F.R.S.*

Received February 19,—Read May 30, 1850.

FRANKLIN INSTITUTE LIBRARY

In a memoir on the Structure of the Dental Tissues of Marsupial Animals, printed in the second Part of the Philosophical Transactions for 1849, I pointed out certain peculiarities in the structure of the enamel common, with one known exception only, throughout that order of quadrupeds, and found in other mammalian teeth in a few isolated cases only*.

* Having in a former paper† stated that the continuation of the dentinal tubes into the enamel appears to be a constant character in the teeth of marsupial animals, excepting only in those of the Wombat, I can now add that I have found it to hold good in many other members of the families from which I have already given examples; and also in members of those families which are not mentioned in my paper; and moreover, that further research has exposed no other exception to the rule than that which I have already cited.

I find that in *Macropus penicillatus* most, if not all, of the coronal dentinal tubes are continued into the enamel, and in the latter part of their course are bent rectangularly downwards towards the fang of the tooth. In *Halmaturus Derbianus* the dentinal tubes are continued into the enamel, but are not subject to the terminal flexure observed in the preceding example. The dental tissues of the *Dasyurus viverrinus* closely resemble those of the *Dasyuri* already described. The teeth of *Didelphis californica* and *Didelphis cancrivora*, approach very closely in structure to those of the *Didelphis virginiana*.

I am indebted to Mr. Gould for opportunities of examining the teeth of *Myrmecobius fasciatus*, *Perameles nasuta* and *Chœropus*. In each of these creatures the dentinal tubes are continued into the enamel. In *Phascolarctos fuscus*, the dentinal tubes that proceed towards the tubercles of the teeth are continued in considerable numbers into the enamel; but on the sides of the teeth their continuation is less frequent. Here the enamel fibres are more strongly marked, and larger than in any other marsupial tooth that I have examined.

Several specimens of fossil marsupial teeth have been examined, and are found to correspond in structure with those of the recent species, to which the fossil ones are most nearly related.

*November* 24, 1849.

† Philosophical Transactions, Part II. for 1849.

It is the purpose of the present communication to lay before the Society results obtained from an examination of the teeth of various members of the order Rodentia. I have had the opportunities necessary for extended researches in this division of Odontography, partly through the assistance of numerous friends, but principally through the liberality of the Council of the Zoological Society, who granted me the privilege of examining teeth from the duplicate specimens of their large collection of skulls. At the time I commenced the investigation, there seemed but little hope of finding any strongly marked and characteristic differences of structure in the dental tissues of the several families of this order of quadrupeds. The teeth of many rodents had already been submitted to the microscope, and the results published*. I had not proceeded far, however, in the investigation of this highly interesting subject, before it became apparent to me that the family Hystricidæ and the Sect. Bathyergina of Waterhouse have a constant and exclusive character in the structure of the enamel; that the Sciuridæ have another character; that the first and second sections of the family Muridæ possess a third; and that the remaining sections of that family possess a fourth well-marked character, and the Leporidæ a fifth. I am told by Mr. Waterhouse that these results are of great importance, as affording evidence on the position of several species whose place in the order has not been definitely fixed, either by their external characters or by the structure of the skull, and hence they have been variously placed by naturalists, and even by the same author at different times.

Before entering on a description of the structural characters that pertain to the teeth of the rodential families, or of individual teeth, it will be desirable to state those conditions which are common to the whole order, otherwise it would be necessary to repeat frequently the same fact. It has long been known that the incisors of Rodentia have the property of unlimited growth, and that the rate of growth equals the rate of loss by wear; hence the exposed portion of the tooth is, in the normal state of the dental apparatus, maintained of uniform length. The pulp-cavity in a longitudinal section of the tooth is irregularly conical or wedge-shaped, and in a transverse section corresponds in some measure with the outline of the tooth. The dentinal tubes pass from every part of the cavity outwards and upwards towards the surface in more or less curved lines.

The tubes which proceed from the cavity near the base of the tooth, are in many cases perceptibly larger than those that are situated higher up; hence it follows, that, as the latter were once near the base of the tooth, the dentinal tubes undergo a diminution of calibre after their formation. In the teeth of the Sciuridæ, I have found a difference of size amounting to a third or half between the tubes near the base and those near the surface, in wear. Professor Owen has observed that the tubes in the posterior or lingual half give off larger and more numerous branches than those constituting the anterior half of the tooth. My own observations lead to the conclusion, that this difference does not always exist near the surface of the pulp-cavity,

* Odontography, Prof. Erdl.

but is generally present towards the outer surface of the tooth. The tubes in the anterior half gradually diminish in calibre from their commencement, while those in the posterior half retain their dimensions until they arrive near the surface, where they break up into branches.

At and near the apex of the pulp-cavity the development of dentinal tubes is suspended. The tooth at this point is rendered solid by the conversion of the pulp into a clear laminated subgranular mass, into which very few, if any tubes are continued; and the few that are sometimes found are usually small in size, irregular in form and direction, and never reach the centre. The ends of the dentinal tubes are perfectly sealed up, and their connection with the pulp-cavity and its vascular contents completely cut off in the manner shown in Plate XLIII. fig. 1. The perfected part of the tooth is rendered by this process in the fullest sense of the word extra-vascular. A similar condition may be seen in the molars of persistent growth, and offers a striking difference to the condition of the rooted teeth, in which the dentinal tubes retain their connection with the pulp-cavity until the tooth becomes diseased or dead, or the crown worn down by mastication. In the latter case, as the crown wears down, the pulp is converted into secondary dentine, in which but few tubes exist, and these do not reach a vascular surface like that which lies in contact with the surface of the pulp-cavity in the normal state of the tooth.

Professor Owen*, after describing the manner in which the incisor teeth of rodents are developed, says, "The tooth thence projecting consists of a body of compact dentine, sometimes with a few short medullary canals continued into it from the persistent pulp-cavity, with a plate of enamel laid on its anterior surface, and a general investment of cement, which is very thin upon the enamel, but less thin, in some rodents, upon the posterior and lateral parts of the incisor."

The medullary canals described by Professor Owen, pursue a course parallel with the dentinal tubes, form a narrow loop, and return to the pulp-cavity. The dentinal tubes never radiate from them, but enter through the medium of lateral branches only (fig. 5). Hence the teeth so constituted do not form an exception to the law, that the incisors of rodents are formed of a single denticle†, which, exclusive of the enamel, is comparable to an Haversian system.

* Odontography, page 399.

† It is proposed to restrict the term *dentinal system* to a canal from which dentinal tubes radiate (fig. 2), and *denticle* to a dentinal system coated with enamel or cementum; and that a tooth composed of a series of dentinal systems, each coated with enamel and united into one tooth by cementum, shall be described as a tooth composed of denticles. The molars of the Capybara afford an excellent example of a tooth constituted in the latter manner, while the Orycteropus affords an equally good example of a tooth compounded of a series of dentinal systems—a tooth in which we have a number of medullary canals from which dentinal tubes radiate, the terminal branches of which inosculate with the terminal branches from neighbouring systems, either by confluence or the intervention of small cells (fig. 2). Teeth composed of a series of dentinal systems may or may not have an external investment of enamel; in the Orycteropus enamel is absent, while in the *Labyrinthodon*, *Varanus* and *Lepidosteus*, it is present near the upper extremity of the tooth, The dentinal systems commonly run into each other at some

In those rodents whose molars are of persistent growth, whether the tooth is composed of denticles or confluent denticles, the dentinal tubes of that part of the tooth which is protruded and exposed to wear, are cut off from their connection with the pulp-cavity in the same manner as in the incisors. This beautiful provision of nature for rendering solid and extra-vascular parts that are about to be exposed to mechanical abrasion from external objects, is not confined to the teeth of rodents, or to dental tissues alone.

The Orycteropus has teeth which are permeated by a series of canals, which take a parallel course at tolerably regular intervals in the length of the tooth. From each canal a system of dentinal tubes radiates, the terminal branches of which inosculate with corresponding ones from neighbouring systems. In the protruded portion of the tooth, the medullary canals are rendered solid by the development of a clear non-tubular tissue, whereby the once open extremities of the tubes are closed (fig. 2).

The teeth of reptiles of the genus *Varanus* are at their middle part and base composed of a series of dentinal systems, as are those of the Labyrinthodon* (fig. 3). In

parts, in the same manner as the Haversian systems do in bone. But there are many instances in which parallel dentinal systems are united to each other, throughout their whole length, by a thin longitudinal lamina of dentine, the tubes of which belong as much to the one as to the other system, while the free parts of each system are coated with enamel, and this with cement. The molar teeth of the Water-Rat and Ondatra offer good examples. It is desirable to have a term to express this condition; *confluent denticles* would, I think, answer the purpose, and *confluent dentinal systems* where a like condition is observed, without the presence of enamel or cementum as a uniting medium.

* It has been usual to describe the tooth of the Labyrinthodon as being divided into numerous compartments, by tortuous inflections of the cementum from the surface towards the centre. I believe it is admitted by writers on Odontography, that when enamel and cementum are present in the same tooth, the latter tissue holds a position external to the enamel. Professor Owen, in his paper on the teeth of the Labyrinthodon, printed in the Geological Transactions, says of the Ichthyosaurus, "In this extinct Saurian the external layer of cement (for the enamel ceases at the base of the crown) is inflected at pretty regular distances around the circumference of the tooth towards its centre:" then again, "The plan and principle of the structure of the tooth of the Labyrinthodon are the same as those of the tooth of the Ichthyosaurus, but are carried out to the highest degree of complication." But in a beautiful series of sections of the tooth of the *Labyrinthodon Jaegeri* in the possession of Dr. Mantell (to whom I am indebted for their use), it is clearly shown that the division of the tooth into numerous compartments takes place within a general investment of enamel, external to which the cementum would be placed if it existed on this part of the tooth.

The inflections of the cementum, observed by Professor Owen in the tooth of the Ichthyosaurus, and compared by him to the supposed inflection in the tooth of the Labyrinthodon, take place, as he observes, below the terminal line of the enamel; hence the two cases do not admit of comparison. Similar cells to those which occupy the line which lie between the dentinal system and serve as a medium of connection between the dentinal tubes of adjoining systems in the latter animal, are found in equal or even greater numbers near the periphery of the dentine, and within the enamel of very many teeth. Hence the presence of these cells in the tooth of the Labyrinthodon is not sufficient to prove the existence of cement between the dentinal systems, unless it is at the same time shown that they are external to the enamel, or that that tissue is absent. The tooth of the Labyrinthodon is in truth made up at its apex of a single dentinal system coated with enamel; below, it is divided into numerous systems, which have a peculiar and characteristic outline and position. Each system usually coalesces at one part of its circumference with a neighbouring system, by a narrow vertical process of

fish we have the teeth of the Dendrodus, the Lepidosteus, Myliobates, and sharks of the genus *Lamna*, also composed of a series of dentinal systems. In all of these the open extremities of the dentinal tubes are closed previous to the part being exposed by wear. A similar condition, in a beautiful state of preservation, is found in many fossil fish teeth, especially in the Cestracions. I cannot refrain from noticing one other instance of this condition. The antlers of the Stag are composed of Haversian systems of medullary or vascular canals, surrounded by concentric laminæ of osseous tissue interspersed with lacunæ, the canaliculi of which anastomose freely, and those situated near a vascular canal terminate by open mouths on its surface. Previous to the shedding of the antler, each of the larger canals becomes lined with a layer of transparent, dense and almost structureless tissue, which completely closes the mouths of the canaliculi and cuts off the connection of the elaborate system of tubes and lacunæ with the vascular canals (fig. 4).

The division of the enamel of the incisors into two layers, described by Professor Owen, I have found common throughout the order, excepting in the incisors of the Hares and the Rabbit: the Lagomys I have not had an opportunity of examining, but from their close relation to the Hares, it is more than probable that in their incisors the enamel is not divided into an outer and inner layer.

The term layer is open to objection, as the two parts are made up of continuous fibres. In the inner part they decussate, while in the outer they are parallel, but their continuity may be distinctly traced (fig. 6 to 50). In the molars of many Hystricine teeth, the usual order is reversed; in the inner portion the fibres are parallel, and in the outer part of the enamel they decussate.

Professor Owen, in the passage cited; and in other parts of his great and valuable work, states that the cementum is continued over the enamel in the incisors of rodents, and objects to some of Professor Erdl's figures printed in his work on the Microscopic Structure of the Molars of *Rodentia*, because this tissue is left out. He says Professor Retzius failed to recognize the cementum from its being coloured. Professor Owen*, in his description of the incisor of the Water Vole, says, "The layer of cement becomes thinner at the margin of the enamel, where it is continued from the dentine upon that part, but soon increases in thickness, acquiring the bright brown tint, and separated by a well-defined line from the outer clear layer of the enamel."

I have sought with care for cementum on the anterior surface of the incisors of the Water Vole, of which the foregoing quotation is a description, and also in numberless other teeth, but have failed to find that tissue. In most, if not in all incisors of rodents, cementum may be seen investing the posterior surface, and it may be traced

dentine, much in the same manner as the confluent denticles of the molar teeth of *Rodentia* are united. In the teeth of the *Lepidosteus* and Lizards of the genus *Varanus*, the dentine of the middle and basal portions is divided into systems somewhat in the same manner as in the Labyrinthodon, and in the upper part of the tooth within a general circumferential investment of enamel. I have in my possession sections from two species of *Varanus*, *V. Bellii* and *V. Niloticus*, in which this point is incontrovertibly shown. I am indebted to the kindness of Dr. Andrew Smith for the teeth of these species.

* Odontography, page 405.

on to the edge of the enamel, where it speedily thins and is lost. The bright brown coloured part is very distinct in many teeth, and when the section is thick and a little oblique looks like a distinct layer; but if the section be reduced in thickness, all appearance of a layer will be lost. The colour graduates insensibly into the enamel, and no defined line of separation between the coloured and colourless parts can be distinguished. The colour has the aspect of a stain, deepest at the surface, and fading as it proceeds inwards. In a favourable section, the enamel fibres may be traced through the coloured part to the surface of the tooth, as shown in many of the figures. In the molar teeth of continuous growth, the cement may be traced over the whole surface of the enamel, and as a thin transparent layer devoid of lacunæ. In these teeth it is however separated from the enamel by a sharply-marked boundary line. In no instance have I found it graduated into the latter tissue in the manner Professor Owen supposes it to be in the coloured external portion of the enamel of the incisors. In the incisors of the Wombat, the cementum is continued over the enamel, but the two tissues are separated from each other by a sharply-marked line. The cementum is nowhere graduated into, or "blended with*" the enamel. It is more than probable that the thin transparent and almost structureless basement tissue of the enamel-pulp becomes calcified with the attached columns of the pulp itself, but this tissue is quite distinct from the cementum matrix, and exists in those teeth in which we have an external investment of cement.

The rootless molars of rodents have generally a very close resemblance in structure to the incisors, especially in the structure of the enamel. But the rooted molars are less like the front teeth, and in many instances cannot be distinguished by their structure from other small teeth. In the Rat-tribe, however, the enamel near its terminal edge assumes an arrangement similar to that of the incisors. In those molars which have an intermediate character, the structure of the enamel in the upper part of the tooth resembles that of the rootless molars†.

* Odontography, page 405.

† In describing individual teeth, it will be necessary to repeat frequently the same expression, I will therefore state once for all the meaning I attach to such terms. Thus by a vertical or longitudinal section of an incisor, I mean a section from back to front through the median line of the long axis of the tooth; by an oblique section through the long axis of the tooth or oblique longitudinal section, I mean that the section should pass from the mesian side of the anterior to the outer side of the posterior surface of the tooth, or *vice versâ*; by longitudinal section from the anterior surface, I mean a section by which a portion of the anterior convex surface is removed with a portion of enamel at each end of the section; by a transverse section, a section at a right angle with the long axis of the tooth; by an *oblique transverse section*, or a section parallel with the surface in wear, a section crossing the long axis of the tooth obliquely from back to front. The surface in wear will be described as the upper surface, both in upper and lower teeth; and the angle at which the enamel layer leaves the dentine, will be that formed between the enamel lamellæ and the surfaces of the dentine immediately above them.

When the thickness of the enamel and the dentine is given, the measurements will be taken from back to front, throuhg the centre of the long axis of a transverse section.

Teeth obtained from the Zoological Society are indicated by the Society's name being affixed to the name of the species.

In the genera *Sciurus* and *Pteromys*, I have examined the dental tissues of many species, and find the teeth so like the one to the other, that the microscope affords no aid in the distinction of species. Under these circumstances it will be necessary to describe minutely the structure of the component tissues of the teeth of one species only.

*Sciurus niger*, Linn. (Zoological Society).—The anterior surface of the incisors is coated with an extremely thin layer of enamel, scarcely exceeding in thickness the 428th part of an inch. The dentine measured from the front to the back, is about the 8th part of an inch in thickness. A longitudinal section, taken from the centre of an upper incisor, exhibits the dentinal tubes in their length. Those destined for the anterior half commence at the surface of the pulp-cavity, and proceed with slight secondary undulations, and a decreasing calibre upwards towards the enamel. In the earlier part of their course, a few short, minute, rectangular branches are given off, and are soon lost; but when nearing the enamel, the tubes break up into a lash of branches, which pass onwards with but slight divergence, and after becoming excessively minute, are lost at the juncture of the external tissue; a few, however, terminate by forming loops. The dimensions of the dentinal tubes vary at different parts of the same tooth. At the lower part of the pulp-cavity the tubes destined for the anterior and posterior surfaces have a diameter of the 6000th of an inch, while those that proceed from the upper and narrowed part of the pulp-cavity, and from the central line of the solid part of the tooth, seldom exceed the 14,000th of an inch, and are often reduced to a scarcely perceptible line. Usually they do not preserve this small size, but quickly dilate to the 10,000th or 12,000th of an inch; these conditions are not however peculiar to the teeth of this group. The tubes that form the posterior part of the incisors give off branches pretty freely throughout the whole of their course, and when near the surface break up into a rich plexus of anastomosing tubules, in addition to which they occasionally dichotomize. Many of the earlier branches are small and short, but a few are large, go off at a right angle, and may be traced for some distance crossing the course of the neighbouring tubes. In the median line of the sides of the tooth, independent of the secondary curves or undulations, the dentinal tubes pursue a tolerably straight course, as do those in the median line of the anterior and posterior surface. But the dentinal tubes of the anterior halves of the sides describe one large curve, the convexity of which is turned towards the anterior surface of the tooth; and those composing the posterior part of the tooth follow a similar curve, the convexity of which is directed towards the posterior surface; similar relations between the tubes and the several parts of the incisor may be observed in the teeth of other rodents.

Professor Owen*, when treating on the teeth of rodents, says, "The substances of the incisor diminish in hardness from the front to the back part of the tooth; the enamel consists of two layers, of which the anterior and external is denser than the

* Odontography, page 399.

posterior layer." He does not however anywhere state that the incisors of Sciuridæ have any structural peculiarity resident in the enamel, by which their teeth are distinguished from those of other rodents; neither am I aware that any subsequent author has noted its existence. Nevertheless so great a peculiarity exists throughout this family of Rodents, that a vertical section of an incisor, either of a *Sciurus*, *Pteromys*, *Tamias* or *Spermophilus*, may be recognized at first sight as belonging to the family Sciuridæ.

It has been usual to describe the enamel fibres from the view obtained in a longitudinal section of the tooth, from which circumstance the true structure has not been recognized. The supposed fibres are composed of layers of fibres, and each layer of a single series, the fibres of which are parallel to each other, and at right angles with those composing the layers immediately above and below. In the outer part of the enamel the fibres of all the layers become parallel, and the lamination ceases.

The enamel layers, as seen in a vertical section of an incisor of *Sciurus niger*, and portrayed in fig. 6, are about the 6000th of an inch in thickness, and have straight and even margins. They form a right angle with the surface of the dentine, increasing slightly in thickness in their course outwards (fig. 6 E). Each layer is composed of a single series of squarish fibres, laid side by side, and closely united. During the first part of their course they are straight and parallel, and proceed to the right in one layer and the left in the next, at such an angle as to produce a square pattern over the inner part of the enamel. The appearance thus produced in the central part of the enamel of a transverse section is shown in fig. 7 E. On the side of the incisor the decussation is less strongly marked, and at the thin terminal edges is almost lost. The fibres, after traversing in a diagonal course in the horizontal plane of the tooth two-thirds of the thickness of the enamel, turn abruptly upwards and outwards at an angle of 45 degrees with their original direction. In this, the outer third of their course, the whole of the fibres become parallel, and in proceeding outwards make a gentle curve, the convexity of which is turned towards the cutting edge of the tooth. In the change of direction, the fibres which have followed a diagonal course make an angle not only in the vertical, but in the horizontal plane of the tooth, while those situated near the terminal edge of the enamel are bent in the vertical plane only.

The colouring matter resident in the enamel of the incisors of squirrels, is seen in a thin transverse section to be confined to the outer third, and looks like a stain in the terminal ends of the fibres, which diminishes in intensity from without inwards until it is lost.

In a vertical section through the centre of an incisor, viewed by transmitted light, the superimposed laminæ of enamel fibres will, to an inexperienced eye, appear as parallel fibres; a little patience will however enable the observer to see that they are composed of fibres cut obliquely (fig. 6 E). In places, faint transverse markings will be seen, which indicate the oblique sections of the fibres. Not unfrequently, however, the lateral union of the fibres is so perfect, that in the layers near the cutting edge of

the tooth no transverse marking can be traced. If a section be made obliquely in the vertical plane of the tooth, so as to cut the fibres of one set of layers in their length and the others transversely, we shall have straight fibres with intervening rows of fibres cut across (fig. 8 E). If the section be taken from the protruded portion of the tooth, the cut extremities will be nearly square; but if it be taken from near the base, where the enamel has not attained its full solidity, they will have a less regular outline. Sections of this kind show that the fibres are a little longer than broad, and that the longer axis is placed in the length of the tooth.

A vertical section will however show most strongly the peculiarities that belong to this family of rodents, namely, the small relative amount of enamel, the uniform character of the layers, the uniform lines that mark their junction, and their straight and rectangular course outwards from the surface of the dentine, together with the angle at which they are bent in the external portion of the enamel.

An incisor in which these several conditions of the enamel are found to exist, may I think be safely pronounced to belong to a species included in the family Sciuridæ, and in all probability a member of the genus *Sciurus* or *Pteromys*.

The molar teeth of *S. niger* present no sufficient peculiarity in the structure of the dentine to render a description necessary. Neither can I find any point of difference worthy of notice in the corresponding teeth of *S. vulgaris, capistratus* or *cinereus*. In *S. erythropus* the dentinal tubes are continued, the 1500th of an inch, into the enamel, and in this short course branch in the manner shown in fig. 11 E. I have not found this peculiarity in any other squirrel which has come under my notice.

The cementum of the molar teeth is not very abundant, even at the extremity of the fang; I cannot discover that it is continued over the surface of the enamel. If a vertical section of a molar tooth from either of the species I have named be carefully examined, it will be seen that the cementum, where it commences in a thin layer, at the neck of the tooth is composed of uniform rods, directed from without inwards and a little downwards. When this tissue is thicker the rods are seen near the surface, but are lost amongst the lacunæ and their canaliculi. The cemental rods are subgranular in structure, and exceed the enamel fibres in dimension. They average the 3450th of an inch in diameter, and are portrayed in fig. 10 C. I am not aware that this character of the cementum has been previously noticed, it is not however confined to the molars of the Sciuridæ.

In the molar teeth of Squirrels the enamel is far less peculiar than in the incisors, and offers no strongly marked characters by which the teeth can be recognized. The fibres are less regular in form, less clear and transparent, and less free from minute cells than in the front teeth; neither have we a terminal portion taking suddenly an altered direction; nor is there any evidence that the fibres are arranged in parallel layers transverse to the long axis of the tooth. Their course is however, throughout, more or less waved; and although many cross each other, yet all do not; and when they do, the definite and constant angle preserved in the incisors is not observed in the molar

teeth. A vertical section of a molar of *S. niger* exhibits the usual characters of the dental tissues in these teeth (fig. 9). In *S. cinereus* the enamel fibres are in a vertical section, seem to be minutely granular, well-marked, and subject to one or two gentle curves near the surface; they are in the outer part of the tooth very strongly marked, from being highly granular, and less perfectly united laterally than in some other teeth.

*Tamias Lysteri*, Rich. (Zoological Society).—I have been able to procure a lower incisor only of this creature. The structure of the tooth very closely resembles the incisors of squirrels: the dentine is similar, as are the enamel layers both in shape and arrangement; and the component fibres of the contiguous layers cross each other at the same angle. The decussation however ceases, and the parallel arrangement is assumed in about the middle of the enamel; this difference, if found constant in all the species, will serve to distinguish the Tamias from the Squirrels.

*Spermophilus* (Zoological Society).—The structure in the incisors of this animal deviates a little from that in the Squirrels; in thickness, the enamel, as seen in a transverse section, is about 300th and the dentine the 12th of an inch; the dentine is much the same as in the genus *Sciurus*, excepting that the dentinal tubes of the anterior half of the tooth measure about the 7500th of an inch in diameter, while in the posterior half they average the 6000th of an inch: the enamel is different, and advances a step towards another type. The enamel layers incline upwards at an angle of 78°, instead of preserving the rectangular position, and they are less regular in their course, and less uniform in size than in the former genus. A transverse section shows that the component fibres of the adjoining layers decussate one another throughout the inner half of the enamel, and then become parallel. An oblique section in the long axis of the tooth will expose alternate straight fibres and rows of ends of fibres cut transversely; and in the latter it may be observed that they have an oval rather than a square section, the long diameter of which is one-third greater than the short; this is best seen near the cutting edge of the tooth. If the section be taken from near the base, the fibres in their transverse section are more circular, less compressed, and much less intimately united to their fellows, while at the opposite extremity of the tooth they are so closely connected, that in places the enamel seems a dense transparent structureless mass.

The enamel layers in a vertical section have a thickness of about the 5000th of an inch. In a transverse section, the fibres have a diameter of about the 10,000th of an inch in their smaller, and the 5000th in their greater diameter.

*Arctomys Empetra*, Schreb. (Zoological Society).—In a lower incisor the enamel has an average thickness of 75th of an inch, and the dentine the $\frac{3}{10}$th of an inch. The dentinal tubes have an average diameter of the 10,000th of an inch: I do not find any difference in the dimensions of the dentinal tubes at the anterior and posterior parts of the incisor. They terminate at the enamel in a peripheral layer of minute irregular cells, much in the manner shown in fig. 12 and 13. Those directed towards the back

part of the tooth, in the terminal fifth of their course, form a rich plexus of branches, and finally terminate in minute irregular cells. Then comes a thin investment of transparent cementum, which terminates at the margin of the enamel. The dentine is dotted throughout with fine cellular markings, which seem to indicate the form of the cells of the dentinal pulp previous to its calcification, and give a coarse appearance to the tissue. The dental tissues of this tooth are not distinguishable from those of the next species.

*Arctomys pruinosus*, Gmel. (Zoological Society).—In an upper incisor the enamel averages the 75th, and the dentine the 5th of an inch; as the dentine closely resembles that of the Quebec Marmot, the description need not be repeated. The enamel exhibits a considerable departure from that of the Sciuridæ, though not wholly different in type of structure. The fibres in the first part of their course are arranged in parallel layers, which have a thickness of about the 4580th of an inch, as seen in a longitudinal section and illustrated in fig. 12 E. The layers lie at right angles with the surface of the dentine, and extend across the inner two-fifths of the enamel, at which point the uniform lamelliform arrangement is broken up by a change in the direction of the component fibres. In a transverse section of the tooth the component fibres of the enamel layers are seen arranged in a single series, lying side by side, and crossing those of the adjoining layers at an angle so as to form a diamond pattern over the inner part of the tissue (fig. 13). The decussating fibres of the superimposed layers, after traversing the inner two-fifths of the enamel, change their direction, become more parallel, and in waved course advance upwards and outwards till they reach the surface of the tooth. But although the course is much more parallel in the outer three-fifths than in the inner two-fifths of the enamel, yet if the focus of the instrument be carefully changed, alternate layers of fibres may be seen crossing each other at an angle to form very elongated and irregular diamond-shaped figures.

The line at which the change of direction takes place is not definitely marked as in the Sciuridæ and many other rodents. In a longitudinal section, it will be seen that the fibres in the terminal part of their course are directed upwards at an angle of 70° with the surface of the dentine, and that small cells are scattered through this part of the enamel. In addition to these minute irregularly disposed cells, lines of cells may be seen commencing at the surface of the dentine, pursuing a curved course, and finally crop out at the surface of the enamel: I have not seen similar out-cropping lines of cells in the enamel of any other rodential teeth. The enamel fibres may in a transverse section be traced through the coloured portion of the enamel to the surface of the tooth.

*Castor fiber*, Linn. (Zoological Society).—In an upper incisor the enamel is about the 100th and the dentine the 5th of an inch in thickness.

It has been observed by Professor Owen, that vascular canals are continued from the pulp-cavity a short distance into the dentine. In the specimen before me, the middle third of the dentine is traversed by vascular canals, which turn short upon

themselves and return to the pulp-cavity not far from whence they started. The canals in radiating from the pulp-cavity pass directly outwards and a little upwards parallel with the course of the dentinal tubes, excepting where they turn to reverse their course, in doing which they do not occupy more than twice or thrice their own diameter. I have not observed that they ever branch or anastomose with neighbouring canals; many indeed so quickly return to the pulp-cavity, that there would scarcely be space enough for branching, while others advance a considerable distance.

The dentinal tubes destined for the anterior part of the tooth commence with a diameter of about the 7500th of an inch and give off branches in the earlier part of their course, which connect themselves with the vascular canals. The disposition to branch ceases however after they have passed the vascular portion of the dentine, and is not resumed until they come near the enamel, when they form a plexus, towards the surface of which is a layer of elongated cells, placed obliquely both to the course of the tubes and the surface of the dentine; the cells are shown in their relative position in fig. 14. Previous to the formation of the peripheral plexus, the dentinal tubes make several curves in a contour line with the length of the tooth. This point is not shown in the figure, as it occurs internal to the part represented. The dentinal tubes of the posterior part of the tooth commence with a diameter of about the 6000th of an inch.

The vascular canals measure from the 750th to the 2500th of an inch in diameter. Those situated near the worn surface are the smallest, from being lined or filled with a transparent tissue, into which the branches of the dentinal tubes do not penetrate.

In the enamel we find a further deviation from the Sciuroid type than was observed in the Marmots. The layers of enamel fibres no longer lie at a right angle with the surface of the dentine, but are directed upwards at an angle of 60°, and moreover describe a slight sigmoid curve, which terminates a little short of the centre of the enamel, from whence the fibres become parallel and proceed at an angle of 30° with the surface of the dentine. These appearances are best seen in a longitudinal section, and are shown in fig. 14 E. In a transverse section made parallel with the course of the layers, as seen in a longitudinal section, the arrangement of the fibres composing the layers becomes apparent. Each layer is composed of a single series of fibres, which pass in straight lines alternated to the right and left in the adjoining layers, and produce an infinite number of minute square tracings over the inner portion of the enamel. When near the middle the decussation ceases, the fibres become parallel and proceed upwards and outwards; but instead of proceeding directly outwards, they bear towards the median line of the skull, as shown in fig. 15. In examining the fibres in the terminal part of their course, a section must be made parallel with their length.

The enamel fibres, as seen in a transverse section, measure about the 6000th of an inch, and may be traced to the surface.

Professor Owen says, "In a transverse section of the incisor (of the Beaver), the

distinction between the two layers of enamel is still more obvious: the fibres of the inner half, being cut across, give the appearance of fine decussation, oblique lines; while those of the outer half run transversely to the surface, and are crossed by traces of concentric layers*." That the appearance of decussation here mentioned is due to the crossing of fibres, and not to the direction of the section, is proved beyond doubt by taking a thin transverse section and breaking it across the centre, when the fibres of the layers included in the section may be viewed projecting from the broken edges; or it may be even more distinctly demonstrated by removing a little of the partially calcified enamel from the lower portion of the tooth, and placing it with a drop of water between two pieces of glass.

In the dentine of the molar teeth of the Beaver, I can find no characteristic peculiarity that needs description. The root of the tooth is composed partly of cementum, into which the dentine graduates, and through which vascular canals lead to the pulp-cavity.

The fibres of the enamel correspond in arrangement with the external portion of those which form the enamel of the incisor teeth, and like them have a greater and less diameter, the former of which is placed in the length of the tooth.

The enamel fibres are usually directed upwards at an angle of 30° with the surface of the dentine, and near the surface curve a little outwards; but they may be found in some parts of the tooth making two slight curves before arriving at the surface.

Near the upper part of the tooth the fibres are so closely united, that the enamel in places seems almost structureless; but toward the roots, and where it is reflected into the depressions, the fibres are sufficiently distinct to be examined and measured.

The enamel, where it attains its greatest thickness, is marked by oblique lines, which proceed from within outwards and speedily crop out on the surface. They appear to result from a difference of density rather than from the presence of minute cells, such as are found in the incisors of the Marmots.

The cementum of the molars is granular, plentifully supplied with lacunæ, and arranged in concentric laminæ round the vascular canals and the roots of the tooth; here and there a slight tendency to the arrangement in rods, similar to that of the Sciuridæ, may be observed.

*Spalax typhlus*, Pall. (Zoological Society).—This animal, though placed by Mr. Waterhouse in a section between *Murina* and *Arvicolina* in the family Muridæ, resembles the Beaver in the structure of the enamel more closely than any other animal, which circumstance offers a sufficient reason for describing the dental tissue in this place.

In an upper incisor the dentinal tubes present an oval transverse section with the long diameter placed in the long axis of the tooth. The long diameter attains the 5000th, while the short diameter does not exceed the 10,000th of an inch. In their passage outwards they describe a sigmoid curve, with the general direction a little

* Odontography, page 407.

upwards, and from their commencement at the pulp-cavity give off rectangular branches which take a downward course. When near the enamel, the dentinal tubes bend upwards and emit branches from the convex surface only, as shown in fig. 16 D. These are lost at the junction of the enamel and dentine, and terminate without the presence of peripheral cells, such as are found in the Beaver.

The enamel in the inner part of the tissue is arranged in transverse layers, which in a longitudinal section are seen to proceed from the surface of the dentine at an angle of 73°. Each layer measures about the 6000th of an inch in thickness, and extends about half-way to the surface, where the component fibres of the different layers assume a more parallel arrangement. The layers in a favourable section have even margins, but if the section inclines slightly from the centre of the tooth in either direction, the margins will be a little irregular; indeed this observation applies with equal force to similar sections of other rodential teeth.

In a transverse section the contiguous layers cross each other at a right angle, and at places look as though plaited, as in the Sciuridæ. In the outer division of the enamel, the fibres proceed in straight lines to the surface (fig. 17). An oblique section in the length of the incisor will expose alternate layers of straight fibres, and fibres divided transversely; the appearances thus produced are delineated in fig. 16 A. On the whole, the enamel is more transparent and the structure is less distinctly marked than in any other incisor I have as yet described; indeed the peripheral division in a longitudinal section frequently seems structureless.

The enamel varies a little in thickness in different parts of the tooth, the average being about the 200th of an inch, the inner or decussating and outer or parallel being nearly equal in breadth.

The rooted molars of the Spalax present a slight structural resemblance to those of the Sciuridæ. The dentinal tubes leave the pulp-cavity with about the 7500th of an inch, which is preserved till they arrive near the enamel. In the upper and middle part of the tooth the tubes describe a sigmoid curve in passing outwards, and give off branches during the two outer thirds of their course. In a longitudinal section, the enamel is seen to be composed of fibres which pass upwards and outwards with a slight curve, and have a diameter of the 6000th of an inch.

The cement resembles that of squirrels' molars in being composed of rods arranged transversely to the length of the tooth.

In the family Muridæ of Waterhouse*, a distinguishing character in the enamel runs through the various sections, excepting the three first, the fifth and seventh, and in the first of those (genus *Myoxus*) it exists partially. The teeth of the Dormice are in structure intermediate between those of the Squirrel-tribe and the Rat-tribe. The incisors of the Jerboas are however wholly different from any other members of this family, and the incisors of Bathyergina resemble those of the Hystricidæ. The Spalax I have already described.

* Johnston's Physical Atlas.

*Myoxus avellanarius* (Linn).—In the upper incisors of the Dormouse may be observed the first indications of the peculiar arrangement of the enamel layers, which holds in the great majority of the members of the family Muridæ.

The arrangement of the component layers of the enamel is, however, not alike in the incisors of the upper and lower jaws; hence a description of each is needed.

In the upper incisors, the enamel is composed of flexuous layers of fibres arranged transversely to the long axis of the tooth. In a longitudinal section each layer is seen to proceed upwards, then obliquely outwards, and afterwards again upwards, the general direction being at an angle of 70° with the surface of the dentine. The layers have serrated margins through the first curve, but during the after part of their course the margins are even, as in the Sciuridæ. The layers, after extending the 500th of an inch across the enamel, are broken up and the fibres are continued in parallel lines through the 750th of an inch to the surface, and at an angle of 30° with the surface of the dentine: these characters are shown in fig. 18 E.

The enamel layers are subject to a little variety in thickness, the average being about the 7500th of an inch; and here and there a layer may be found which gradually diminishes till it comes to a point and is lost before reaching the external portion of the enamel. An oblique section in the length of the tooth may be made at such an angle as to expose one layer of fibres in their length and the adjoining layer cut transversely. This view is shown in fig. 19. It will be seen that the fibres have a greater breadth than thickness.

In a transverse section the component fibres of one layer are shown crossing those of the layer above and below at a right angle, thus producing a square pattern over the lamelliform portion of the enamel, which is represented in fig. 20. The fibres give a transverse measurement of the 8823rd of an inch. The fibres in the outer division of the enamel are straight, and lean obliquely towards the median line of the skull.

In the lower incisors of this little creature the position of the enamel layers is reversed. A transverse section exhibits them extended in the length of the tooth, presenting an appearance similar to that seen in a longitudinal section of the corresponding upper tooth, excepting that they make but one curve with a flattened and slightly enlarged middle portion (fig. 22). A longitudinal section of a lower incisor presents an appearance similar to a transverse section of the corresponding upper tooth, as shown in fig. 21.

The dentine of the incisors of the Dormouse is not sufficiently peculiar to render a minute description necessary. The tubes are perceptibly larger at the lower than at the upper part of the tooth, and those in the posterior half of the tooth retain their full dimensions till near their termination.

The enamel is about the 300th, and the dentine the 23rd of an inch thick.

In the molar teeth, the lamelliform arrangement of the enamel exists in a perceptible degree near the terminal edge only, and so far establishes a resemblance to the molars of the Rat-tribe. The dentine offers no peculiarity worthy of notice in this communication.

FRANKLIN

*Jerboa Ægyptius.*—The teeth of this animal present great structural peculiarities. The upper and lower incisors are subject to the same difference in the arrangement of the lamellæ of the enamel as the corresponding teeth of the Dormouse; while the molars resemble in structure the teeth of marsupial animals. In the long axis of a transverse section of an incisor, the enamel measures the 150th and the dentine from the 17th to the 20th of an inch.

The dentinal tubes radiate from the pulp-cavity without exhibiting a specific peculiarity. Many of those distributed to the anterior as well as those to the lateral and posterior parts of the tooth, dichotomize once or twice in the early part of their course, and afterwards give off small branches. When near the enamel the dentinal tubes break up into a rich plexus of branches, many of which uniting, form a series of loops, and give a greater opacity to this than to any other part of the section. External to this plexus the dentine is comparatively transparent and traversed by a diminished number of dentinal tubes, a few of which are continued into the enamel; these, after following the course of the lamellæ, are lost in the peripheral portion of that tissue. The dentinal tubes at their largest parts do not exceed the 7500th of an inch.

The peculiar character of the enamel of the upper incisor is best seen in a longitudinal section, in which the lamellæ are shown proceeding from the dentine in straight lines directed obliquely upwards at an angle of 60°. In this section each layer appears slightly fibrous and a little indefinite in outline; in both respects differing from the teeth of this and the preceding family. These conditions are partly due to the presence of tubes continued from the dentine, and are portrayed in fig. 23.

The layers, after proceeding for about the 250th of an inch across the enamel, suddenly change their direction, and the component fibres lose the lamelliform arrangement, become parallel, and in tolerably straight lines pass upwards at an angle of 21° with the surface of the dentine. In this, the external part of the enamel, the tissue is very transparent, the fibres are rather indistinct, and the indistinctness increases the nearer we approach the worn extremity of the tooth. Here and there one or two tubes may be seen emerging from the lamelliform portion, and advancing into the outer transparent part of the enamel, but they are soon lost in their own minuteness.

An oblique longitudinal section may be so made as to expose alternate layers of fibres cut in their length, and the intervening ones cut transversely. The latter are oval, and present a long diameter of about the 5550th and a short diameter of about the 8824th of an inch. And it will also be seen, that although the fibres have their long axes placed in the length of the tooth, and hence transversely to the adjoining fibres longitudinally exposed, yet that the long axes are not at a right angle or any constant angle with them, but present various degrees of obliquity, as shown in fig. 24. This want of regularity in the arrangement of the fibres no doubt contributes to the fibrous appearance of the layers in the longitudinal section of the tooth, in which the component fibres are of course cut across with various degrees of obliquity.

In a transverse section of an upper incisor the fibres of the alternate layers are

seen crossing each other at something short of a right angle; in the inner and in the outer part of the enamel they are seen proceeding in straight lines to the surface, without inclining to either side.

A thin layer of cement may be distinguished on the posterior part of the tooth, but is lost when it has passed over the terminal edge of the enamel.

In the lower incisors of the Jerboa the enamel lamellæ are arranged in the long axis of the tooth, much in the same manner as in the corresponding teeth of the Dormouse. A longitudinal section will expose the decussation of the fibres of the contiguous layers, the one set proceeding upwards and outwards, and the other downwards and outwards. The fibres in the external division of their course lose the lamelliform arrangement and proceed upwards and outwards in a gentle curve (fig. 26).

An oblique section in the length of the tooth will cut across the layers in their breadth, and show them arranged in lines parallel with the surface of the dentine. Each layer has in this view a denticulated margin, similar to the lamellæ in the Rats.

A transverse section of a lower incisor exposes the enamel lamellæ divided transversely to their length. Those which arise from the median side of the tooth are directed forwards and towards the median line, while those that start from the anterior and outer surface of the dentine, are directed in a curved line outwards in an opposite course. Each layer thickens slightly as it advances outwards, and exhibits slightly serrated margins.

The component fibres have their long axes placed obliquely (fig. 28). Transverse sections made with different degrees of obliquity, will give variety in the appearance of the enamel layers. Thus a longitudinal section of one set of fibres, and a transverse section of another may be obtained, as partly shown in fig. 28. But if the section be oblique to each axis of the tooth, the enamel may present a confused intersection of lines, from which little or nothing can be made out. This observation may be applied with equal truth to similar sections of other rodential teeth.

The dentinal tubes in the lower incisor are oval in section, and have the long diameter placed transversely to the length of the tooth, hence they appear larger in the transverse than in the longitudinal section (figs. 26 and 28). In the molar teeth, the dentinal tubes leave the pulp-cavity for the crown of the tooth with a diameter of about the 10,000th of an inch, and are very closely packed. They give off very few, if any branches, till near the periphery of the dentine, and here they are far from numerous, as compared with those seen in other molar teeth. The branches are short and bristle-like, and the parent tubes, or a large branch, is usually continued into the enamel. The dentinal tubes of the fangs commence with a similar diameter to those of the crown of the tooth, but they speedily dilate to the 7500th of an inch, and give off branches during the greater part of their course.

Previous to entering the enamel the dentinal tubes are reduced to about the

15,000th of an inch, which dimensions are retained after they have passed with that tissue. The tubes pass onwards with slight tortuosities in a line with the direction of the enamel fibres, until they reach the outer third, when they are lost or turn suddenly at a right angle, and after advancing a short distance downwards, disappear. These conditions are shown in fig. 29. The fibres of the enamel show no disposition towards a lamelliform arrangement, excepting near the terminal edge, where the lamellæ have, in a longitudinal section, serrated margins. The fibres leave the surface of the dentine on the sides of the tooth at an angle of about 50°, and in the outer third of their course come a little outwards. In the depression on the masticating surface, they proceed at a right angle from the surface of the dentine.

The molars of the Jerboa, though like those of marsupial animals in having the dentinal tubes continued into the enamel, differ from them in having serrated lamellæ in the enamel near its terminal edge, and hence may be distinguished both as not belonging to the marsupial order, and as belonging to the Muridæ.

I have been obliged to make upwards of twenty sections of the teeth of this interesting animal before I could fully satisfy myself on the various points of the dental structures; indeed in the early part of the investigation I despaired of making out the arrangement of the component fibres of the enamel.

The next animal on the list is *Pedetes Cafer*, but as the teeth resemble more closely the teeth of the Hystricidæ than any other group of animals, and are altogether dissimilar to those of the Muridæ, I shall postpone the description till I have gone through my specimens of Hystricine rodents.

The teeth which have come within my reach from members of the following genera, *Mus*, *Hapalotis*, *Gerbillus*, *Hydromys*, *Hesperomys*, *Arvicola* and *Lemmus*, so closely resemble each other in the general characters of the structure of the dental tissues, that it will be necessary to describe minutely those of a typical species only, and afterwards to note any specific differences that are found in teeth from other members of these genera. I will therefore take the teeth of the common Rat (*Mus decumanus*) as being typical of the family, and also on account of the ease with which the teeth may be obtained by any subsequent observer.

*Mus decumanus*.—From a longitudinal section of a lower incisor, we learn that the dentine presents no specific or generic peculiarities. The dentinal tubes from their commencement give off numerous minute pilose branches, and terminate near the surface of the dentine by forming a dense plexus of minute ramifications. Their course is straight, or nearly so, excepting the secondary undulation, which exists in a greater or less degree in almost every specimen of dentine that has come under my observation. The tubes are oval in their transverse section, having a short diameter of about the 15,000th of an inch, and a long diameter which is placed in the length of the tooth, and averages the 10,000th of an inch.

In the anterior part of the tooth the tubes gradually diminish in diameter from their commencement, while those in the posterior part retain their original size till

near their termination, when they form a plexus, but less dense than that in the anterior part of the tooth.

The enamel is seen to be composed of fibres arranged in serrated lamellæ, which leave the surface of the dentine with a short but gentle curve, and then proceed upwards and outwards in nearly a straight line till about to terminate in the outer division of the enamel, when they make a slight sigmoid curve with the terminal portion directed upwards, their general course being at an angle of 50° with the surface of the dentine (fig. 30).

At the outer fifth of the thickness of the enamel the layers are broken up, and their component fibres take a parallel course upwards and outwards, and with a slight curve, which is strongest near the outer extremity, when they reach the surface of the tooth, their general courses being at an angle of 30° with the surface of the dentine.

Each lamella commences at the surface of the dentine with a diameter of about the 7500th of an inch, which gradually increases till at the distal extremity it attains the 6000th of an inch. The margins of the lamellæ are strongly serrated, and the projections of one layer fit into corresponding depressions in the contiguous lamellæ. This peculiar form and arrangement, as exhibited in a longitudinal section, may be regarded as typical of the enamel of this family of Rodentia.

In an oblique transverse section cut nearly parallel with the worn surface of the tooth, it may be seen that each layer is composed of a single series of enamel fibres, and that the fibres of contiguous layers cross each other at such an angle as to produce a diamond pattern over the lamelliform portion of the enamel; and also that the fibres curve a little in their course outwards (fig. 31). The upper and lower surfaces of the component fibres of each lamella appear to be a little uneven, and these irregularities no doubt contribute to the development of the serrations observed in the longitudinal section of the tooth, but in the section now under consideration these appearances are seen but obscurely. When the crossing sets of fibres have arrived within the 750th of an inch of the surface, the decussation ceases and they proceed outwards in parallel lines directed obliquely towards the median line of the skull; and in the latter 3000th of an inch of their course they turn directly outwards in a line with the long axis of the section.

If a section be so made as to display one set of fibres in their length, and the adjoining ones divided transversely, the latter will exhibit an oval section, while the former are seen to be armed with minute processes which fit into the small interspaces that would otherwise be left between the non-touching surfaces of the oval fibres. These conditions are shown in fig. 32. To these lateral processes the serrated margins of the lamellæ, as seen in the longitudinal section, are due, as are the irregularities of surface seen in the transverse section.

The outer ends of the enamel fibres are best seen in the middle and lower part of the tooth. Near the cutting edge, in the outer portion of the enamel, the union between

the component fibres is so perfect that all appearance of structure is lost. This observation applies equally to other scalpriform teeth. The coloured surface presents the character of a stain, through which the fibres are continued. If the section be tolerably thick and a little oblique, the two cut edges will give the appearance of a coloured lamina. But the structure of the enamel may be demonstrated, though in a less complete manner, by taking a little of the soft partially developed tissue from the base of the tooth, and with a little water placing it between two slips of glass. The decussation of the fibres will be then shown, and some will present a beaded outline; small portions may also be found in which development is more forward, and some of the fibres armed with small lateral processes will appear in the field of the microscope. Some of these appearances are shown in fig. 33.

The upper have a somewhat thicker coat of enamel than the lower incisors; it averages about the 211th of an inch, of which the lamelliform portion occupies about the 333rd and the outer or fibrous portion the 666th of an inch.

In a longitudinal section the lamellæ leave the surface of the dentine at an angle of 55°, which is a little wider than that formed by the corresponding parts in the lower incisors. The layers describe a gentle curve upwards and outwards, and the margins are serrated through the greater part of their course, but less strongly than in the corresponding lower teeth; in addition to which the layers are frequently marked by transverse lines. Towards the outer part of their course, the serrations become faint and ultimately give place to a smooth outline. The fibres in the outer part of the enamel run at an angle of 25° with the surface of the dentine.

In the molar teeth the dentine presents no generic peculiarity, neither does the enamel about the cusps of the teeth, but at and near its terminal edge on the neck of the tooth, the lamelliform arrangement with the serrated edges holds good, both in the Rat and in other rooted molars of the genera *Mus*, *Hapalotes*, *Hydromys* and *Hesperomys*. The cementum about the neck of the tooth is arranged in rods, similar to those already described in the corresponding teeth of the Squirrels.

The teeth of *Mus rattus* present no structural peculiarities by which they can be distinguished from *M. decumanus*, neither do those of the following rodents, excepting in size:—*Mus Alexandrinus*, *sylvaticus*, *musculus*, *minutus* and *fusipes*. In examining the molar teeth of *Mus giganteus*, I find a peculiarity which may perhaps be specific. The fibrous enamel on one side of the cusps is separated from the dentine by a layer of perfectly transparent and apparently structureless enamel, which is thickest near the apices of the cusps, and gradually thins till it is lost at the bottom of the fissures. On the sides of the tooth the serrated laminæ of the enamel are strongly marked, and extend through a larger portion of the tissue than is common in the corresponding teeth of any other rat which I have examined.

In the teeth of *Hapalotes albipes* and *longicaudatus* of New South Wales, I find a very close structural resemblance to those of the Rat, the principal difference being in the more blunted shape of the serrations of the enamel lamellæ, and the greater

frequency and strength of their transverse markings. In a longitudinal section of a lower incisor the layers leave the dentine at an angle of 40°, and have a thickness of about the 7500th of an inch. The whole thickness of the enamel is about the $\frac{1}{1800}$ths of an inch, of which $\frac{1}{1800}$ths is occupied by the lamelliform, and $\frac{8}{1800}$ths by the outer or fibrous portion of the enamel. The latter lies at an angle of 15° with the surface of the dentine.

It will be seen, on referring to the description of the corresponding teeth and sections of *Mus decumanus*, that the angle at which the laminæ of enamel fibres leave the surface of the dentine, is sufficiently different from that in the *Hapalotes* to distinguish the teeth of these creatures from each other.

The molars of the *Hapalotes* resemble those of the Rat. I am indebted to the kindness of Mr. Gould for an opportunity of examining the teeth of these animals.

*Gerbillus Shawii* (Devern.) stands next on my list. The dentine of the incisors of this small rodent is peculiar in having a few vascular canals extended from the pulp-cavity a short distance into its substance, which in a transverse section gives an uneven outline to the surface of the pulp-cavity. The dentinal tubes give off branches throughout the whole of their course, are interspersed with small cells, and are subject to irregular secondary undulations; in addition to which, the whole substance of the dentine has a cellular appearance as though the developmental cells had retained their outline during the process of calcification, instead of becoming confluent and homogeneous.

In a longitudinal section the laminæ leave the surface of the dentine at an angle of 55°, and curve upwards and outwards through about $\frac{6}{1800}$ths of an inch: they then give place to the fibrous portion in which the fibres curve upwards and outwards, their general course being at an angle of 20° with the surface of the dentine.

The laminæ are bordered by blunt serrations, and are subject to transverse markings, in both particulars resembling the enamel of the corresponding teeth of the *Hapalotes* more closely than that of the Rat.

In a transverse section the enamel of the incisors could not be distinguished from that in the Rat.

In the molar teeth the dentinal tubes are continued into the enamel the 1500th of an inch. In no part of the latter tissue could I distinguish a lamelliform arrangement in the enamel.

The teeth of *Hydromys chrysogaster* of New South Wales resemble those of the Rat. The incisors of the Hamster, *Cricetus fumentarius* (Pall.), can scarcely be distinguished from those of *Mus decumanus*.

*Hesperomys Darwinii* (Waterhouse) possess teeth so like in minute structure to those of *Mus decumanus* that a special description is unnecessary.

*Geomys umbrinus* (Rich.), though not placed by Mr. Waterhouse in the family Muridæ, have incisors so Rat-like, that it would require the presence of sections of the teeth of this creature and of the Rat to distinguish the one from the other, and even then there would be some difficulty in finding characteristic differences

sufficiently well-marked to render the conclusion trustworthy if any doubts were thrown on the authenticity of either of the specimens.

*Arvicola amphibius* (Linn.).—It would be extremely difficult to point out the characters by which sections of the incisor teeth of this creature could be distinguished from the corresponding ones of several teeth I have already described, especially those of the common Rat (*M. decumanus*). The serrated enamel lamellæ leave the dentine at nearly the same angle; the serrations are perhaps finer and less strongly marked, and the lamellæ are more frequently crossed by equidistant transverse lines. The rootless molar teeth, however, are sufficiently different from those of the Rat. In a longitudinal section, it will be seen that on one side of each denticle the enamel is composed of an inner lamelliform portion, with the edges of the lamellæ serrated as in the incisors, and another portion in which the enamel fibres are parallel; while on the opposite and posterior surface of the denticles the lamellæ are absent, and the enamel fibres pass across the structure in a curved line to the surface. In a transverse section, it is seen that the two conditions pass insensibly into each other at the bottom of the longitudinal grooves, where the component denticle coalesces, and also immediately behind the longitudinal ridges which mark the sides of the teeth.

In the Field Vole, *Arvicola nivalis* (Martin), the teeth, both molars and incisors, structurally resemble those of the *A. amphibius*.

The incisors of the Bank Vole, *Arvicola glareolus* (Schreb.), are rat-like; but in the molar teeth the serrated lamelliform arrangement of the enamel is very indistinct. In the lower incisors the serrations of the lamellæ are shallow, while the transverse markings are rather strong. The appearances presented in a longitudinal section are delineated in fig. 34.

The incisors of *Lemmus Norwegicus*, Desm. (Zoological Society), do not offer any structural differences from the preceding group worthy of description.

*Fiber zibethicus* (Linn.).—This animal is placed by Mr. Waterhouse in the family Muridæ, section *Arvicolina*. The dental tissues do not well accord with that position, but seem to indicate a nearer relation to the Beaver and Dormouse. In the molar teeth, however, the enamel in places resembles that in the corresponding organs of *Arvicola amphibius* and *A. nivalis*, but the serrated lamelliform arrangement is not as uniform or as well-marked as in those animals. Yet Mr. Waterhouse's arrangement of Rodentia is, with but few exceptions, so strongly corroborated by the structure of the dental tissues, that in this case, where there is conflicting testimony in these tissues as to where they should be placed, I shall do well to describe them in the position he has assigned to the animal.

In the upper incisors, a few vascular canals radiate from the pulp-cavity into the dentine, but they are far less numerous, and run a shorter course than in the corresponding teeth of the Beaver. The dentinal tubes resemble those of the latter animal, excepting that they terminate at the enamel, without the presence of a peripheral layer of cells.

A longitudinal section exhibits the enamel lamellæ passing outwards in an irre-

gular sigmoidal curve, their general direction being at an angle of 80° with the surface of the dentine. Immediately on leaving the dentine the layers make a short curve upwards and outwards, during which the margins are serrated; the serrations then become indistinct or altogether cease, and the layers pursue a tolerably straight course till near their termination, when they turn upwards, after which the component fibres become parallel and advance to the surface at an angle of 33° with the dentine.

On looking carefully over a longitudinal section, parts will be found in which the transverse direction of the lamellæ appear to be reversed. Fibres, or layers of fibres, will be seen running for a short distance obliquely in the long axis of the tooth.

In a transverse section the fibres of the alternate layers are seen to cross each other obliquely, so as to produce a diamond pattern over the lamelliform portion of the enamel. In the earlier part of their course the fibres curve a little, but afterwards become straight. In the outer part of the enamel the fibres pass directly outwards without leaning to the one side or the other.

In the lower incisors the structure of the enamel not unfrequently presents a confused appearance, as though the lamellæ were subject to some irregularity in arrangement. In a longitudinal section the enamel layers are seen leaving the surface of the dentine at an angle of 50°, and in their course curve a little outwards. The margins are pretty strongly marked with small oblique serrations and oblique transverse lines. The lamellæ have a thickness of about the 5000th of an inch. The enamel has a thickness of about the $\frac{9}{1800}$ths, the lamelliform portion of which is about the $\frac{7}{1500}$ths of an inch. In a transverse section parallel with the course of the lamellæ, the decussation of the alternate layers of fibres may be seen; and in a section a little more oblique, the fibres in the terminal part of their course may be seen passing in straight lines obliquely outwards from the median side of the tooth. In the dentine of the lower incisors, the vascular canals are much less abundant than in that of the corresponding upper teeth.

The confluent denticles of the molar teeth are coated with enamel, which is very irregularly lamelliform, with serrations so indistinctly marked and inconstant, that the appearance scarcely merits the name. A longitudinal section will best exhibit this view. In a transverse section, parts may be found in which the decussation of adjoining layers of fibres is visible, but generally the fibres seem to follow a much less regular and constant course; and in places they are parallel, as in the outer part of the enamel of the incisors. However, when we find the decussation, it will be situated on the anterior surface of the denticles; so far the structure resembles that found in the corresponding teeth of the Water-Rat, and, as in that animal, the enamel on the posterior surface of the denticles is uniformly free from the lamelliform arrangement. Near the masticating surface of the molar teeth the enamel fibres are so intimately blended, that little or no structure can be discerned.

The cementum, in no part of the tooth very abundant, is occupied by very large irregular cells and vascular canals. The latter are very large, have nodulated mar-

gins, and run principally in the transverse axis of the tooth. The tissue of the cementum, as seen in a transverse section, is unusually clear and transparent.

I am indebted to Mr. Waterhouse for a list of those rodents which he considers the most typical species of the several divisions of his family Hystricidæ, and have been fortunate in obtaining the teeth of all he has enumerated, excepting *Echimys*.

In the dentine of these teeth, I find nothing that is characteristic of the group. But the enamel is very peculiar, and the peculiarity is constant in each species I have examined. So strongly is the family characteristic marked by the peculiar arrangement of the fibres of this tissue, that it is necessary to have seen the structure in one hystricine tooth only, to be enabled to recognize at first sight the tooth of any other species as a member of the same group. We no longer see in a longitudinal section of an incisor uniform laminæ separated in the lamelliform portion of the tissue by well-defined lines, but in their stead find thick and confluent layers of obliquely placed fibres, which in a transverse section are seen to pursue a serpentine course from the dentine towards the surface, near to which they become straight and parallel as in the corresponding part of the enamel of the teeth previously described. Hence in this as in the preceding group, I need describe minutely the structure of the incisors of one species only. The molar teeth offer greater variety in the arrangement of the component tissues, and may require farther notice.

*Hystrix cristata* (Linn.).—In the incisors, the enamel attains a thickness of about the 45th and the dentine the 4th of an inch. The latter tissue offers no striking peculiarities; near the enameled surface it is tenanted by obliquely placed elongated cells, similar to those found in the incisors of the Beaver and many other teeth: they are shown in fig. 35 D.

In a longitudinal section, the enamel presents a very beautiful and, as compared with the tissue as it occurs in the preceding families, a very novel appearance. Large confluent laminæ of from the 1000th to the 1500th of an inch in thickness, leave the dentine at an angle of 80°. Each layer is composed of enamel fibres directed obliquely, and the obliquity varies in the adjoining layers, but corresponds in the alternate ones, in the manner delineated in fig. 35 E. But the fibres are not oblique in one direction only; one extremity of each fibre may be traced to dip into or under those of the contiguous layers, while the other extremity is usually cut obliquely across, and exhibits a diameter of about the 5000th of an inch. When within the 250th of an inch of the surface the layers gradually disappear, and their component fibres take a parallel course, and at an angle of 30° proceed to the surface.

In an oblique transverse section parallel with the course of the enamel laminæ, the appearances are even more striking than in the longitudinal one. The enamel looks as though the fibres were thrown into waves, the furrows of which commence at the surface of the dentine, and proceeding obliquely outwards, crop out where the fibres become parallel, and form the external portion of this tissue; their direction is shown in fig. 36. A close inspection of a favourable section will enable the observer

to see that the enamel fibres pursue a serpentine course, and in the lamelliform portion describe three tolerably uniform curves (fig. 36 E.). Then again, by altering the focus of the microscope, without changing the position of the section, it may be seen that the fibres immediately above and below those already observed, pursue a similar serpentine course, but arranged so that the concavities and convexities point in opposite directions, like the two sides of the figure 8. The appearance thus produced is shown in fig. 39, which in this particular must be regarded as a diagram rather than an accurate portrait. This crossing and re-crossing in curved lines, together with the cropping out of the curves of the contiguous fibres, produces a most complex appearance; and if the section be not parallel with the length of the fibres, the structure appears, to one who has not given attention to the subject, so confused as to defy explanation. If the section be so made as to expose in their length the enamel fibres of the middle of the anterior part of the tooth, those near the sides will be cut obliquely and present a penniform arrangement. An oblique longitudinal section will exhibit the fibres of alternate layers divided almost transversely, while those of the intermediate ones are exposed, taking an oblique course: this point is shown in fig. 37. In addition to the peculiarities already enumerated, small rounded cells are scattered through the enamel of this and most other Hystricine teeth.

The dentine of the molar teeth of *Hystrix cristata* is peculiar in having its tubes unusually free from lateral branches during the greater part of their course. The secondary undulations are strongly marked; and on approaching the enamel, the terminal branches are comparatively few in number and large in size, and commonly pass the 750th of an inch into the enamel.

Near the termination of the dentine in the root of the tooth, the dentinal tubes radiate from a number of centres, and the tissue graduates into the cementum, which is very abundant in this situation, and forms a considerable portion of the root.

In a longitudinal section the enamel fibres are seen to proceed upwards and outwards in parallel lines till near the surface, when they assume a similar arrangement to that seen in the incisor teeth. When the enamel is thin, the lamelliform arrangement is scarcely seen; but where it exists in a tolerably thick layer, the confluent laminæ commence near the dentine. It should be remarked that in the Hystricine molar teeth, the usual position of the fibrous and lamelliform divisions of the enamel is reversed. Hitherto we have found the fibrous enamel placed externally; but here and in the succeeding family, the lamelliform enamel occupies the external position in the molar teeth.

*Hystrix prehensilis* (Linn.).—The incisors in microscopic structure closely resemble those of the common Porcupine. In the molar teeth, the dentinal tubes are continued about the 1000th of an inch into the enamel.

*Dasyprocta Aguti* (Linn.).—A longitudinal section of an incisor shows that the dentine of the anterior part of the tooth is bordered by a layer of obliquely placed elongated cells, about the 750th of an inch broad. The enamel is composed of con-

fluent laminæ of obliquely placed enamel fibres, which have a diameter of about the 5000th of an inch, while the layers have a thickness of from the 1362nd to the 2150th of an inch, and leave the dentine at an angle of 65°. In the outer division of this tissue the fibres lie at an angle of 35° with the surface of the dentine.

Prof. Owen describes the structure of the teeth of the Agouti from a longitudinal section of an upper incisor, and says, "The fibres composing the inner and more opake part of the enamel proceed obliquely, but almost transversely across that substance, with a gentle curve in the opposite direction to the last curve of the contiguous dentinal tubes, viz. with the convexity towards the crown: the fibres of the peripheral layer of the enamel make a slight bend towards the crown; these enamel fibres are as thick as two of the dentinal tubes with their interspaces; their ends are lost in the clear peripheral substance to which the distinct, apparently structureless brown layer of cement is attached, and to which the colour of the convex surface of the incisor is due*."

Had Prof. Owen made transverse sections of this tooth, he would I think have been led to give a wholly different account of the enamel; he would have seen the waved appearance which closely corresponds with that I have described in the incisor teeth of the Porcupine, and is produced by a similar flexuous arrangement of the component fibres; he would also have seen that the brown colour is resident in, and is due to a stain in the terminal ends of the enamel fibres. The enamel of the molar teeth of this animal resembles that of the corresponding teeth of the Porcupine.

*Dasyprocta Acouchy* (Erxl.). The dental tissues of this creature closely resemble those of the preceding species.

*Cœlogenys Paca* (Schreb.).—The dentine of the incisor teeth does not differ very perceptibly from that of the corresponding teeth of the Agouti and Porcupine. It measures about the 5th of an inch, while the lamelliform portion of the enamel is about the 107th, and the fibrous 300th of an inch in thickness. In a longitudinal section the confluent layers of enamel fibres leave the dentine at an angle of 70°, and the fibres in the outer fibrous part of the tissue lie at an angle of 40°. The layers have a thickness of from the 1000th to the 1667th of an inch; and the fibres are about the 5000th of an inch in diameter. In an oblique transverse section the waves of the enamel fibres are more strongly marked than in the enamel of the Porcupine, as shown in fig. 38.

An oblique longitudinal section shows with great distinctness alternate layers of fibres divided more or less transversely, and intermediate ones pursuing an oblique course. Fig. 37 illustrates faithfully this strongly-marked and peculiar appearance.

*Capromys Fournieri* (Desm.).—The dentine terminates at the enamel without the presence of oblique elongated cells, but small rounded cells are present and intermingled with the terminal anastomosing branches of the dentinal tubes. The dentine of a lower incisor measures about the $\frac{3}{25}$th, the lamelliform portion of the enamel the

* Odontography, page 404.

83rd, and the external about the 500th of an inch. In a longitudinal section the confluent laminæ leave the dentine at an angle of 55°, while fibres of the outer part are placed at an angle of 20° with the surface of the dentine (fig. 40). The layers have a thickness of from the 1500th to the 3000th of an inch.

*Myopotamus Coypus*, Molina (Zoological Society).—The dentine of the incisors at its anterior termination is occupied by small rounded cells, with which the terminal branches of the dentinal tubes freely communicate, and in addition to which many areolar-shaped cavities exist similar to those found in imperfectly developed human and other dentine*.

The enamel presents the true Hystricine character, but the layers in a longitudinal section are more confluent than in the teeth previously described. They leave the dentine at an angle of 56°, and the fibres in the outer portion of the texture lie at an angle of 40° with the surface of the dentine.

In an oblique transverse section of an incisor parallel with the worn surface of the tooth, the fibres are seen to make four undulations, but they are less deep than those seen in the *Porcupine* and *Paca*. Near the terminal edge of the enamel on the sides of the tooth, in this as in other Hystricine incisors, the fibres make but one or two gentle curves. The confluent laminæ, as seen in a longitudinal section, have an average thickness of about the 1000th of an inch, and the enamel fibres a diameter of the 5000th of an inch.

I find in the enamel of this tooth here and there irregularly rounded interspaces, vacant or occupied by a transparent structureless mass. This perhaps may be a peculiarity confined to the individual specimen. The dentine of the lower incisor has a thickness from back to front of the 3rd, the lamelliform portion of the enamel the 40th, and the external fibrous part the 500th of an inch. The cementum is continued from the sides of the tooth a short distance upon the enamel, but does not blend with the terminal ends of the enamel fibres. On the contrary, the two tissues are separated by a well-defined line.

*Octodon Degus*, Molina (Zoological Society).—In the lower incisors the dentinal tubes of the anterior half of the tooth terminate in fine branches, with which few if any cells are intermingled. The tubes at their commencement in the pulp-cavity are comparatively large, and attain a diameter of about the 5000th of an inch.

The enamel of this small tooth is truly Hystricine in character. The confluent layers leave the dentine at an angle of 45°, which in the outer fibrous part of the texture is reduced to 20°. The 1500th of an inch is the average breadth of the layers, the component fibres of which have a diameter of from the 7500th to the 5000th of an inch. The dentine has a thickness of about the $\frac{1}{15}$th, the lamelliform portion of enamel the 116th, and the external part the 750th of an inch.

In the molar teeth the enamel fibres describe a faint sigmoid curve in their passage

* Lectures on Dental Physiology and Surgery.

outwards, where the tissue exists as a thin layer; but in those parts in which it is more abundant in quantity, the fibres in the external part of their course assume the confluent lamelliform arrangement.

*Schizodon fuscus* (Waterh.).—In the incisor teeth, a few vascular canals are continued from the pulp-cavity into the posterior half of the dentine. The dentinal tubes branch from their commencement and terminate in the anterior part of the tooth in fine tubules without the presence of peripheral cells. They have a diameter of about the 6000th of an inch.

The enamel has a general resemblance to that described in the last species. The confluent laminæ have a thickness of about the 2300th of an inch and leave the dentine at an angle of 50°, which in the fibres of the exterior is reduced to 15°. The dentine has a thickness of about the 15th, and the enamel the 166th of an inch, of which 13 parts are lamelliform and 5 parts fibrous and external.

In the molar teeth the enamel fibres advance one third of their course in parallel lines, and then fall into the confluent lamelliform arrangement, but with less precision than in the incisor teeth.

*Spalacopus Pœppigii* (Wagner).—The dental tissues of the incisor teeth of this animal resemble pretty closely those of the preceding species. The posterior half is not however permeated by vascular canals. The enamel has a thickness of about the 150th of an inch, of which seven-tenths is lamelliform, and three-tenths external and fibrous. The inner part of the external division is tenanted by small rounded cells, which confuse the fibrous character of the part. The laminæ lie at an angle of 50° with the surface of the dentine, while the fibres of the outer part pass upwards at an angle of 25°, and finally turn outwards and advance to the surface at an angle of 90°.

*Habrocoma Bennettii* (Waterh.).—In the incisors of this creature, a few vascular canals are continued from the pulp-cavity for a short distance into the posterior half of the dentine. The dentinal tubes give off short branches from their commencement, undulate irregularly, and are not very uniform in size. They end without the presence of an anterior peripheral layer of cells. The confluent layers of enamel fibres leave the dentine at an angle of 50°, and have a thickness of about the 1666th of an inch. The fibres of the outer portion of this texture lie at an angle of 15°, the thickness of this part being about $\frac{2}{14}$ths, while the lamelliform portion occupies $\frac{12}{14}$ths of the whole thickness, which measures about the 108th of an inch in thickness: fig. 42 and 43 show the texture in a longitudinal and a transverse section. The molar teeth of this species of *Habrocoma* closely resemble those of *Schizodon fuscus*.

*Chinchilla lanigera* (Molina).—The dental tissues both of the molar and incisor teeth strongly resemble those of the four preceding species. In the incisor the dentine is without a peripheral layer of cells in the anterior half, and without vascular canals in the posterior half of the tooth. In a longitudinal section the confluent layers of enamel fibres have a thickness of about the 1500th of an inch, and leave the dentine

at an angle of 50°, which is diminished to 20° in the fibres of the outer portion of the tissue. In a transverse section, it is seen that the fibres in the outer part of the enamel are directed obliquely from the median line of the skull. The enamel fibres have a diameter of about the 6000th of an inch, and are intermingled in the lamelliform portion of the tissue with minute rounded or oval cells, which contribute to give the structure a confused appearance.

*Cavia Aperea* (Erxl.).—A layer of obliquely placed cells occupies the periphery of the enamel-coated anterior of the incisors. The dentinal tubes have slightly irregular parietes, and the intervening tissue has a mottled cellular appearance. In the posterior half of the tooth, the tubes as they approach the periphery throw out numerous characteristic thick branches, which from their number and size render a section of this part very opake.

The enamel is strongly Hystricine in character, and is dotted over with minute rounded and branchless cells*. In a longitudinal section of a lower incisor, the confluent laminæ leave the dentine at an angle of 45°, which is reduced to 20° in the fibres of the external part of the tissue, and the layers are about the 1500th of an inch thick: these characteristics are shown in fig. 44. The whole thickness of the enamel amounts to the 170th of an inch, of which two-thirds is occupied by the lamelliform portion of the tissue.

In the upper incisors the angle of 60° is that at which the lamellæ leave the surface of the dentine, while the terminal extremities of the fibres lie at an angle of 20° with the dentine. The enamel does not exceed the 212th of an inch in thickness, of which five-sevenths is lamelliform.

*Cavia Kingii* (Bennett).—The dental tissues of this animal are very similar in structural character to those of the common Guinea Pig. The enamel is however less crowded with cells, and hence is much more transparent.

*Hydrochærus Capybara* (Erxl.).—Many vascular canals are continued from the pulp-cavity into the posterior half of the dentine in the incisor teeth of this great rodent. A few branches pass from the dentinal tubes throughout the whole of their course, and become more numerous near the periphery of the tissue, which in the anterior part of the tooth is bordered by a dense layer of irregular-shaped cells, that occupy a line the 500th of an inch thick, as shown in fig. 46.

The enamel exhibits the true Hystricine character, both in the longitudinal and transverse sections, but less strongly marked than in any of the previously described teeth belonging to animals of this group. The laminæ are more confluent, and the component fibres occupy a less oblique and more parallel position than we have been accustomed to see them; in a longitudinal section the enamel near the dentinal surface is crowded with small cells, and the laminæ are at this part indistinctly marked. A little farther out they become more strongly developed, and have the

* The cells in the enamel of this and in all the species described in this paper, have no proper parietes, and should be regarded as interspaces rather than cells in the sense now attached to that term.

appearance of being in pairs, the fibres of which proceed obliquely outwards from a central line common to the two, as shown in fig. 46. In the outer division of the tissue the component fibres are so intimately united, that in places only can their course be traced. In a longitudinal section the lamellæ leave the dentine at an angle of 70°, which is reduced to 30° in the outer part of this substance. The layers have a thickness of about the 700th of an inch, and the component fibres a diameter of the 7500th of an inch. The whole thickness of the enamel amounts to the 79th of an inch, of which $\frac{4}{5}$ths is lamelliform.

In a transverse section of an upper incisor, the enamel fibres are seen to make one bold sigmoid curve in the lamelliform portion of the tissue. In fig. 45, a layer of fibres is shown with as much of the one immediately beneath as could be seen without shifting the focus of the instrument.

The enamel of the molar teeth exhibits much the same structural appearance as that of the incisors, excepting that the cells which occupy the inner part of the tissue in the latter teeth, are absent in these.

*Brathyergus maritimus*, Gml. (Zoological Society).—This animal has been placed by Mr. Waterhouse in a section immediately preceding Hystricidæ*. The teeth are however Hystricine in structural character, and might be described either in this place or at the beginning of the family.

The dentine of the anterior parts of the tooth is bordered by a narrow layer of cells. The dentinal tubes have small hair-like branches through the whole of their course. In a longitudinal section of an upper incisor confluent layers of enamel fibres leave the surface of the dentine at an angle of 50°, and after extending about the 210th of an inch, are insensibly lost in the parallel arrangement of the fibres in the unusually thick external division of the tissue, which in this tooth amounts to the 120th of an inch in thickness, as shown in fig. 47. The tissue is dotted near the surface with minute cells. A transverse section is not altogether unlike a corresponding one from the incisor of the *Capybara*.

*Pedetes Cafer* (Pall.).—This animal is placed by Mr. Waterhouse in the family *Muridæ*, section *Dipodina*. The dental tissues of the incisor teeth have the Hystricine character strongly marked, while those of the molars are intermediate between the Hystricidæ and Leporidæ. The true position of the tissues in this family can only be determined after the majority of the species have been examined, which in itself will be a work of some labour, apart from the difficulty of obtaining authentic specimens. In the absence of correct information of its position, I have as a matter of convenience placed my description at the end of the Hystricine group.

In the incisors the dentine has several minor points of peculiarity. The pulp-cavity in a transverse section of a lower incisor approaches a triangular figure with the angles extended and rounded at their extremities, two of which are directed to the lateral anterior angles of the tooth, and the third extends in the median line into the

* Johnston's Physical Atlas.

posterior half, in addition to which the walls of the cavity have two deep indentations on the median side and one on the outer side of the tooth. From each of the angles a line of small vascular canals is continued a short distance into the dentine, which tissue is marked by numerous concentric and broad, but ill-defined and interrupted contour lines, which follow the involutions of the surface of the pulp-cavity. They seem to be produced by a greater density of the tissue in these than at other parts. The dentine has a generally diffused cellular appearance. The dentinal tubes have an irregular outline, and have small lateral branches throughout the whole of their course. When divided transversely they show thick and strongly-marked parietes, and have an internal diameter of about the 6000th and an external one of the 3000th of an inch. On nearing the enamel, the tubes give off larger and more numerous branches, and ultimately terminate in small oval or rounded branching cells.

In the upper incisors the vascular canals are more abundant in the posterior than in the anterior part of the tooth. The pulp-cavity is occupied near its apex with secondary dentine, the tubes of which proceed from the surface towards the centre and give off many branches; when viewed by transmitted light they resemble tufts of moss. The enamel is strongly Hystricine in character. In a longitudinal section of a lower incisor the confluent laminæ leave the dentine at an angle of 60°, which in the external division of the tissue is reduced to 25°. The enamel has a thickness of the 79th of an inch, of which $\frac{4}{5}$ths is lamelliform. The component fibres of the lamellæ have a diameter of about the 7500th of an inch.

The dentinal tubes in the molar teeth proceed from the pulp-cavity in nearly a straight course upwards and outwards at an angle of 20°. When within the 500th of an inch of the enamel, they turn a little more outwards and afterwards a little upwards, thus describing a small final curve, the convexity of which is directed towards the base of the tooth. But few branches pass off till the dentinal tubes make their final curve, when many leave both their convex and concave sides. Vascular canals are continued from the pulp-cavity into the dentine, as in the incisor teeth. The arrangement of the component fibres of the enamel in the molars is peculiar, and probably characteristic of the tooth of this creature. In a longitudinal section the fibres in the first two-fifths or half of their curve are straight and parallel, and lie at an angle of 40° with the surface of the dentine. Afterwards they suddenly fall into the confluent lamelliform arrangement, and with this disposition reach the surface of the tooth, as shown in fig. 48. In the folds which lie between the confluent denticles, the enamel is thinner than on the exterior of the tooth; the loss of thickness is principally at the expense of the outer lamelliform portion. In a transverse section the fibres of the lamelliform portion are seen to make a open letter *f* curve, which is reversed in direction in the contiguous layers, but parallel, or nearly so, in the alternate ones. The appearances seen in this section are delineated in fig. 49. Both in the transverse and longitudinal sections the lamelliform portion of the enamel is crowded with small branchless cells.

The uniform presence and more constant breadth of the inner fibrous portion of the enamel is rather unusual in Hystricine teeth, while it is constant and exists in even a greater degree in the molars of the Hare. In this particular therefore the molars of the Helamys show a slight relation to those of the Leporidæ.

Leporidæ.—In this family of rodents my observations have been confined to members of the genus *Lepus*. The incisors exhibit a type of enamel which I have seen in the teeth of no other rodents. This tissue is no longer divided into an outer and inner portion, with the component fibres arranged in lamellæ in one and not in the other, and at different angles in the two parts; but, on the contrary, the fibres without a lamelliform arrangement proceed with but slight flexures from the surface of the dentine to the outer surface of the enamel. Neither is the enamel dotted over with cells, as is that of Hystricine teeth in the lamelliform portion of the texture.

*Lepus timidus* (Linn.).—In the Hare the dentine is permeated by vascular canals, both in the anterior and posterior half of the incisors; but they are more numerous in the latter than in the former part. These canals become in the extruded portion of the tooth lined by a layer of dense non-tubular tissue, presenting the appearances delineated in fig. 51. The anterior enameled part of the incisors is bordered by a peripheral plexus of branches interspersed with a few branching cells, and the posterior half by a plexus of branches without cells. In a longitudinal section, such as that shown in fig. 50, the dentinal tubes from their commencement in all parts of the tooth branch, but in a transverse section the branches seem rather less numerous; hence it would appear that they extend principally in the long axis of the tooth. Prof. Owen has observed that "the tubes which pass to the opposite or posterior surface of the tooth are less numerous, less parallel, and less closely packed together; they send out more and larger branches, which decussate each other in an elegant arborescent manner*." In addition to these peculiarities, the tubes are sensibly larger in the lateral and posterior than in the anterior part of the tooth. In a longitudinal section, such as that shown in fig. 50, the enamel fibres may be traced through the whole thickness of the tissue. Generally their course is straight, or nearly so, and at an angle of from 50° to 70° with the surface of the dentine, but in places the angle is varied, and the fibres are a little bent in the one or other direction. The tissue is rendered rather unusually transparent by the close union of the component fibres, and its comparative freedom from small cells.

A corresponding section from an upper incisor differs from the one already described principally in the diminished thickness of the enamel. The enamel fibres have a diameter of about the 6800th of an inch.

The molar teeth of the Hare have dentine, which is traversed by vascular canals, that extend from the pulp-cavity to near the peripheral surface of the tissue. Previous to the part coming into wear the canals are lined with a non-tubular tissue, and ultimately become almost or quite obliterated. The dentinal tubes are sensibly larger,

* Odontography, page 405.

and branch much more freely than in the incisors: I do not know a more beautiful microscopic object than a fine longitudinal section of the molar tooth of a common Hare. The enamel, where it exists as a thin layer lining the inflected parts of the confluent denticles, is composed of short fibres, which leave the dentine at a wide angle, and towards their terminal extremities turn a little downwards. But when this tissue invests the outer and more exposed parts of the tooth the amount is much greater; in these parts the enamel is divisible into two portions, the inner of which is composed of straight, uniform and parallel fibres, and the outer part of continuations of the same fibres, but bent about somewhat irregularly, and approaching in places to a confluent lamelliform arrangement. The appearances presented in a transverse section of a molar tooth are delineated in fig. 52; but even in this the arrangement of the enamel fibres in the outer portion of the tissue is regular as compared with what is seen in many parts of the tooth. In the outer part the fibres have the appearance of being smaller than those which lie next the dentine, as shown in the figure.

*Lepus cuniculus* (Linn.).—The dental tissues in the teeth of the Rabbit so closely resemble those of the Hare, that I doubt the possibility of telling the one from the other, excepting by the external form and size of the entire tooth. The vascular canals are perhaps less numerous in the Rabbit.

Of the following animals I have been able to obtain the molar teeth only.

*Lepus Americanus*, Erxl. (Zoological Society).—The vascular canals are very numerous and extend to within a short distance of the enamel, where they usually terminate in dilated extremities. In their passage they branch rectangularly and anastomose with neighbouring canals, a circumstance I have not before observed in the vessels of vascular dentine. Each canal becomes surrounded by a layer of transparent tissue, in which are a few lacunæ very similar to those seen in the cement; eventually the canals are lost by the encroaching inwards of the transparent tissue, and lines of branching cells alone remain to mark their former position.

The enamel could not be readily distinguished from that seen in the molars of *Lepus timidus*; a tendency to confluent lamelliform arrangement of the fibres is found in places, and as it appears in a longitudinal section is shown in fig. 53.

In the molar teeth of *Lepus aquaticus* (Bachm.) and *Lepus sylvaticus* (Bachm.), I find no characteristic differences in the dental tissue by which they could be distinguished from each other, or from the teeth of either of the preceding species of Hares.

Before leaving the subject of Hares' teeth, I should state that occasionally fine supplemental enamel fibres may be seen crossing the course of the ordinary ones at a right angle. They do not exceed the 15,000th of an inch in diameter, and are not constantly present; indeed I have only seen them near the basal half of the tooth, where the enamel is not perfectly hardened.

The facts which are recorded in the foregoing pages have been gathered from

careful and repeated observations made upon upwards of 350 sections, cut from the teeth of various members of the order Rodentia. When a doubt as to the nature of a tissue has arisen, I have made numerous sections from different parts, and in different directions of the same tooth. In some instances I have made as many as twenty-five from the teeth of one species; and have seldom contented myself with less than three sections.

The conclusions which these researches justify depend mainly on the accuracy with which the observations have been made and recorded.

Fortunately, preparations of dental tissues can be preserved for an unlimited period: hence my statements can at any time be tested by an examination of my own or corresponding sections.

Those who will go over the field of observation through which I have passed, will I do not doubt justify me in the following conclusions:—viz. That the teeth of some species of the order have specific structural characters by which they can be distinguished from any other known teeth. That in the teeth of all the Rodentia, excepting the family Leporidæ, a portion of the enamel has a lamelliform arrangement of its fibres. That the enamel lamellæ have a different and distinctive character in each of the larger groups, and that the variety of structure is constant throughout the members of the same group; we may take for examples, the Sciuridæ, the Muridæ, and Hystricidæ, in each of which the structure of the enamel is different, and in each is highly distinctive. And that the varieties in the structure of the dental tissues, with a few isolated exceptions, justify and accord with the arrangements of the members of the order into the several divisions proposed by Mr. Waterhouse, and deduced by him from the relations of the several parts of the skull.

The manner in which these various modifications in the structure of the enamel are brought about in its development, together with the adaptation of the varied forms of enamel-tissue to the wants of its possessors, will form the subjects of a future communication.

*Feb.* 16, 1850.

EXPLANATION OF THE FIGURES, in each of which D refers to the dentine, and E to the enamel.

## PLATE XLIII.

Fig. 1. The middle portion of a transverse section of the lower incisor of *Tamias Lysteri*, showing the manner in which the dentinal tubes are disconnected from the pulp-cavity in that part of the tooth which is about to come into wear by the development of a laminated subgranular tissue. 150 linear.

Fig. 2. A transverse section of a dentinal system, A, and peripheral portion of two contiguous ones, B and C, from the tooth of Orycteropus, showing the manner in which the connection of the dentinal tubes with the surface of the pulp-cavity is cut off by the development of a laminated mass of transparent and apparently structureless tissue.

Fig. 3. A transverse section of a dentinal system, A, and a portion of a contiguous one, B, from the tooth of *Labyrinthodon Jaegeri*, showing the disconnection of the tubes with the pulp-cavity in A, and the process, C, by which this is connected with a contiguous system; also the peripheral line of cells which intervene and partially connect the terminal branches of the tubes of adjoining systems. (This drawing was made from a section, No. 4 of a series lent to me by Dr. MANTELL.) 75 linear.

Fig. 4. A transverse section of a Haversian system from a Stag's antler which had been cast, showing the transparent tissue lining the canal, and thus cutting off the connection of the canaliculi with the surface of the canal.

Fig. 5. A transverse section from the extruded portion of a molar tooth of *Lepus timidus*, showing that the medullary canals of vascular dentine become lined with a dense non-tubular tissue previous to the part coming into wear.

Fig. 6. A portion of a longitudinal section from an upper incisor of *Sciurus niger*, showing, D, the dentine, E, the enamel lamellæ in their rectangular position, and F, the terminal or fibrous part of the enamel, in which the extent of the colour is marked by a vertical line. 225 linear.

Fig. 7. A transverse section of the same tooth, showing, D, the dentine, and E, the enamel, in which the component fibres of two layers, the decussation and their continuance in the external part of the tissue, are seen. 225 linear.

Fig. 8. An oblique longitudinal section from the base of the same tooth, in which E, the alternate layers of the enamel lamellæ, are cut transversely and longitudinally. In this part of the tooth the external part of the enamel is not fully developed.

Fig. 9. A portion of a longitudinal section from the crown of a molar tooth of *Sciurus niger*, showing, D, the dentine, and E, the enamel, with the fibres interspersed with irregular cells.

Fig. 10. A longitudinal section from the fang of the same tooth, showing, D, the dentine, and C, the cementum, in the outer portion of which the tissue is arranged in rods, and is free from lacunæ.

Fig. 11. A portion of a longitudinal section from the crown of a molar tooth of *Sciurus erythropus*, showing, D, a part of the dentine with the tubes combined into E, a portion of the enamel.

Fig. 12. A portion of a longitudinal section of an upper incisor of *Arctomys pruinosus*, showing, D, the dentine, E, the enamel, with the lamellæ leaving the surface of the dentine at a right angle, and F, the outer fibrous division of the enamel. 150 linear.

Fig. 13. A transverse section from the same tooth, showing, D, the dentine, and E, the enamel.

Fig. 14. A portion of a longitudinal section from the upper incisor of *Castor fiber*, showing, D, the dentine with a peripheral layer of cells, E, the lamelliform portion, and F, the outer fibrous portion of the enamel.

Fig. 15. A transverse section from the same tooth, showing, D, the dentine, E, the enamel, with the decussation of the component fibres of two laminæ, and F, the outer part of the enamel.

## PLATE XLIV.

Fig. 16. A portion of a longitudinal section from an upper incisor of *Spalax typhlus*, showing a peripheral portion of dentine with the downward direction of the branches of the dentinal tubes, and E, the enamel; A, an oblique longitudinal section, showing the fibres of alternate laminæ divided transversely. 150 linear.

Fig. 17. A transverse section from the same tooth; D, the dentine, E, the enamel. 150 linear.

Fig. 18. A longitudinal section from an upper incisor of a Dormouse (*Myoxus avellanarius*); D, peripheral portion of dentine, E, the enamel, showing the curved enamel lamellæ and the fibres in the outer part of the tissue. 300 linear.

Fig. 19. An oblique longitudinal section from the same tooth, showing at E alternate layers of enamel fibres divided transversely with the intermediate ones exposed in their length. 300 linear.

Fig. 20. A transverse section of the same tooth. 300 linear.

Fig. 21. A longitudinal section of a lower incisor of *Myoxus avellanarius*, showing at E the decussation of the parallel layers of enamel fibres, and the downward direction of the external ends.

Fig. 22. A transverse section of the same tooth, showing the outward course of the enamel lamellæ, their serrated margins near the dentine, and their vertical position.

Fig. 23. A vertical section from the upper incisor of a Jerboa (*Dipus Ægyptius*), showing, D, the dentine at its anterior peripheral surface, and E, the enamel with a few tubes continued into the outer part. 150 linear.

Fig. 24. An oblique longitudinal section, showing enamel fibres divided transversely and longitudinally. 300 linear.

Fig. 25. A transverse section of an upper incisor of the Jerboa, showing, D, the dentine, and E, the enamel, with the decussation of the fibres of contiguous layers in the lamelliform portion of the tissue, and their parallel course in the outer part of the enamel. 150 linear.

Fig. 26. A longitudinal section of a lower incisor of the Jerboa from near the base of the tooth, showing, D, the dentine, and E, the enamel, with the lamellæ arranged in the length of the tooth. 150 linear.

Fig. 27. Enamel fibres scraped from the partially calcified tissue near the base of the tooth. 600 linear.

Fig. 28. A transverse section of a lower incisor of the Jerboa, showing the enamel lamellæ divided transversely with the fibres of alternate layers cut obliquely, and the intervening one longitudinally.

Fig. 29. Plate XLV. A longitudinal section of a molar of the Jerboa, showing the periphery of the dentine and the dentinal tubes continued into the enamel, with the manner of termination of the tubes in the latter texture.

Fig. 30. A longitudinal section of a lower incisor of a Rat (*Mus decumanus*), showing, D, the terminal portion of the dentine, and E, the enamel, with its serrated lamellæ and its outer fibrous portion. 300 linear.

Fig. 31. An oblique transverse section from the same tooth, showing the crossing of the fibres of contiguous layers, and the pattern thus produced. 300 linear.

Fig. 32. A section from the same tooth, in which the fibres of alternate layers are divided transversely, and the intermediate ones exposed in their length, and show minute denticulations.

Fig. 33. Enamel fibres in various stages of development, obtained from the partially calcified tissue about the base of the incisor.

Fig. 34. A longitudinal section from a lower incisor of the Bank Vole (*Arvicola glareolus*), showing at E the denticulated character of the enamel lamellæ and their transverse markings.

## PLATE XLV.

Fig. 35. A longitudinal section of the upper incisor of the Porcupine (*Hystrix cristata*), in which is shown, D, the terminal portion of the dentine with its obliquely placed elongated cells, and E, the enamel with its confluent layers of obliquely placed fibres and the parallel fibres of the outer portion of the tissue. 120 linear.

Fig. 36. A transverse section from the same tooth, showing, D, the dentine, and E, the enamel fibres pursuing a serpentine course in the lamelliform part of the tissue, and a straight parallel course in the external division of the tissue. 120 linear.

Fig. 37. An oblique longitudinal section from a lower incisor of the Spotted Cavy (*Cœlogenys Paca*), showing, D, the dentine with its peripheral layer of cells, and E, the enamel with the confluent layers, and with the fibres of alternate ones divided more or less transversely.

Fig. 38. An oblique transverse section from the same tooth, showing, D, the dentine, and E, the enamel with the fibres in their waved course in the lamelliform portion, and parallel course in the outer portion of the tissue.

Fig. 39. An oblique transverse section from a lower incisor of *Capromys Fournieri*, showing, D, the dentine, and E, the enamel, which in this figure is rather a diagram illustrating the arrangement of the enamel fibres, than a faithful delineation of the appearance presented in the section.

Fig. 40. A longitudinal section from the same tooth, showing, D, the dentine, and E, the enamel, with its confluent laminæ and the oblique constituent fibres.

Fig. 41. An oblique transverse section from the same tooth, showing at E the appearance assumed by the enamel laminæ near the sides of the tooth when the fibres are exposed in their length in the middle part of the section.

## PLATE XLVI.

Fig. 42. An oblique transverse section from the upper incisor of *Habrocoma Bennettii*, showing, D, the dentine, and E, the enamel, with the direction of the enamel fibres.

Fig. 43. A longitudinal section from the upper incisor of *Habrocoma Bennettii*, showing, D, the dentine, and E, the enamel with its confluent laminæ. 150 linear.

Fig. 44. Plate XLV. A longitudinal section from a lower incisor of the Guinea Pig (*Cavia Aperea*), showing, D, the peripheral portion of the dentine with its terminal layer of oblique elongated cells, and E, the enamel and its confluent laminæ. 200 linear.

Fig. 45. A transverse section from an upper incisor of the Capybara (*Hydrochœrus Capybara*), showing, D, the dentine, and E, the enamel. 150 linear.

Fig. 46. A longitudinal section from the same tooth, showing the peripheral layer of cells, D, and E, the enamel with the penniform character of the confluent lamellæ. 150 linear.

Fig. 47. A longitudinal section from an upper incisor of *Brathyergus maritimus*, showing, D, the dentine, and E, the enamel with its peculiar Hystricine enamel laminæ, and the large amount of the external division of the tissue. 150 linear.

Fig. 48. A longitudinal section of a molar of *Pedetes Cafer*, showing, D, the dentine, and E, the enamel, with the inner portion fibrous, and the outer lamelliform.

Fig. 49. A transverse section from the same tooth ; D, the dentine, and E, the enamel.

Fig. 50. A longitudinal section from a lower incisor of the Hare (*Lepus timidus*), showing, D, the dentine, and E, the enamel fibres, without a lamelliform arrangement, and without a division into an external and internal portion. 200 linear.

Fig. 51. A vascular canal surrounded by a layer of non-tubular tissue, as seen in a longitudinal section of an incisor of the Hare. 300 linear.

Fig. 52. A transverse section from a molar of the Hare (*Lepus timidus*), showing, D, the dentine with its large tubes, and E, the enamel with the fibres in the inner portion parallel, and in the outer curved and irregularly Hystricine. 200 linear.

Fig. 53. A longitudinal section from a molar of *Lepus Americanus*, showing the irregular lamelliform character of the outer portion of the enamel. 200 linear.

## XXIX. *Sequel to a paper on the Reduction of the Thermometrical Observations made at the Apartments of the Royal Society.* By James Glaisher, *Esq., F.R.S., of the Royal Observatory, Greenwich.*

Received December 14, 1849,—Read February 28, 1850.

In a paper which the Royal Society did me the honour to publish in the last volume of its Transactions, I gave the results found from all the thermometrical observations which have been taken at the Apartments of this Society; and I stated that I had made some progress in the connection of this series of results with those deduced from the observations at the Royal Observatory, Greenwich. Since that time I have reduced the two series of observations to one and the same series, and I have now the honour to lay the results from their combination before the Society.

In my former paper I stated that no observations had been taken between the years 1781 and 1786. Had the particulars of these years been about their average values, their omission would not have materially affected the final results, but on examination I found that those years were distinguished by very severe weather, and that their omission would have a sensible effect; I have therefore supplied these particulars, as detailed below.

I also stated that it was doubtful whether the temperatures, as determined for Somerset House, were influenced by local causes. I have endeavoured to collect information upon this subject, and of which I shall speak presently.

I shall adopt the same plan in the arrangement of the final results, which I pursued in my former paper, and present them for monthly, quarterly and yearly periods. The numbering of the Tables is continued from the former paper. It may tend to clearness if I speak of each preliminary investigation separately.

### *Determination of the Mean Temperature of the Air at Lyndon in Rutlandshire, the longitude of which place is* 0° 3′ *East of Greenwich and the latitude is* 52° 32′ *North, for every month in the years from* 1771 *to* 1799.

The results of meteorological observations taken by Thomas Barker, Esq., at Lyndon in Rutlandshire, and which seems to have been taken with care, were published in the volumes of the Philosophical Transactions for the years 1772 to 1799. From these papers I have determined the mean monthly temperatures of the air, and which are shown in the following Table:—

TABLE VIII.—Mean monthly temperature of the Air at Lyndon in Rutlandshire, from the year 1771 to the year 1798.

| Year. | January. | Feb. | March. | April. | May. | June. | July. | August. | Sept. | October. | Nov. | December. |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | ° | ° | ° | ° | ° | ° | ° | ° | ° | ° | ° | ° |
| 1771. | 30·5 | 34·0 | 35·0 | 40·0 | 56·2 | 56·6 | 61·5 | 59·7 | 52·7 | 47·5 | 41·2 | 41·2 |
| 1772. | 32·8 | 34·8 | 38·8 | 43·5 | 50·3 | 62·0 | 62·0 | 61·0 | 55·7 | 52·7 | 43·7 | 39·3 |
| 1773. | 37·5 | 35·5 | 41·2 | 45·5 | 49·2 | 58·2 | 60·5 | 62·2 | 54·5 | 48·5 | 39·5 | 38·0 |
| 1774. | 31·2 | 37·8 | 41·0 | 46·5 | 51·5 | 60·2 | 61·0 | 61·2 | 54·2 | 48·2 | 39·0 | 35·8 |
| 1775. | 38·7 | 42·5 | 41·5 | 49·7 | 55·0 | 62·7 | 64·0 | 59·7 | 57·8 | 47·5 | 37·8 | 37·5 |
| 1776. | 27·5 | 38·2 | 43·2 | 47·8 | 52·0 | 59·2 | 63·8 | 60·0 | 55·2 | 49·8 | 41·2 | 38·8 |
| 1777. | 33·5 | 34·2 | 43·2 | 45·0 | 54·0 | 57·7 | 61·5 | 61·5 | 57·7 | 49·8 | 42·7 | 35·2 |
| 1778. | 34·5 | 35·8 | 40·0 | 46·0 | 55·5 | 62·2 | 66·0 | 62·5 | 52·2 | 44·8 | 43·2 | 42·0 |
| 1779. | 36·0 | 44·5 | 44·2 | 49·2 | 54·0 | 58·2 | 65·5 | 65·0 | 59·0 | 50·8 | 40·8 | 36·7 |
| 1780. | 29·5 | 35·0 | 45·5 | 43·0 | 55·8 | 58·8 | 63·5 | 64·0 | 58·5 | 48·5 | 38·0 | 36·7 |
| 1781. | 34·0 | 40·7 | 43·0 | 48·5 | 53·2 | 63·5 | 64·5 | 64·0 | 57·5 | 48·8 | 42·0 | 40·8 |
| 1782. | 39·5 | 35·0 | 39·0 | 42·0 | 49·8 | 60·5 | 61·2 | 58·0 | 56·2 | 45·5 | 35·0 | 36·0 |
| 1783. | 37·5 | 39·8 | 38·0 | 49·2 | 50·0 | 61·0 | 67·7 | 62·0 | 55·3 | 49·3 | 42·8 | 34·8 |
| 1784. | 29·8 | 32·5 | 36·5 | 43·3 | 58·5 | 58·8 | 61·5 | 57·5 | 58·0 | 44·2 | 41·0 | 30·8 |
| 1785. | 36·7 | 31·0 | 34·2 | 47·5 | 54·2 | 62·0 | 64·2 | 58·8 | 57·5 | 47·2 | 40·5 | 35·0 |
| 1786. | 36·5 | 36·8 | 34·5 | 46·0 | 54·0 | 62·2 | 61·0 | 60·2 | 52·0 | 45·0 | 37·0 | Ther. broken. |
| 1787. | 37·2 | 42·5 | 44·2 | 46·0 | 53·8 | 60·0 | 62·5 | 61·8 | 59·0 | 50·2 | 38·8 | 39·0 |
| 1788. | 38·5 | 39·0 | 39·0 | 50·8 | 59·3 | 61·5 | 65·5 | 62·0 | 57·5 | 50·2 | 42·0 | 34·2 |
| 1789. | 34·5 | 40·5 | 36·0 | 47·0 | 56·8 | 60·0 | 63·0 | 63·0 | 56·8 | 48·0 | 39·8 | 42·0 |
| 1790. | 39·0 | 42·8 | 44·8 | 43·8 | 55·2 | 61·5 | 63·0 | 62·5 | 55·2 | 50·2 | 42·2 | 40·8 |
| 1791. | ..... | 39·8 | 43·2 | 50·5 | 52·0 | 59·8 | 61·5 | 63·0 | 58·0 | 47·8 | 42·2 | 33·0 |
| 1792. | 36·5 | 38·8 | 43·2 | 51·5 | 52·2 | 57·8 | 62·5 | 64·2 | 54·0 | 48·8 | 44·8 | 40·2 |
| 1793. | 36·5 | 40·5 | 40·2 | 43·0 | 53·2 | 60·0 | 68·2 | 62·5 | 55·0 | 53·8 | 43·2 | 41·0 |
| 1794. | 34·5 | 45·5 | 45·2 | 52·0 | 53·5 | 62·5 | 69·0 | 61·8 | 54·8 | 49·5 | 43·5 | 37·2 |
| 1795. | 26·8 | 32·8 | 39·8 | 46·8 | 54·5 | 58·0 | 60·2 | 64·5 | 61·8 | 54·0 | 41·0 | 44·5 |
| 1796. | 44·8 | 40·5 | 40·5 | 51·2 | 51·0 | 60·5 | 62·5 | 62·5 | 60·0 | 47·2 | 40·5 | 32·0 |
| 1797. | 38·0 | 38·2 | 40·0 | 45·8 | 55·0 | 57·8 | 66·8 | 63·0 | 55·0 | 48·0 | 41·2 | 40·2 |
| 1798. | 38·5 | 38·8 | 41·2 | 51·5 | 56·8 | 65·8 | 64·5 | 64·2 | 58·5 | 51·0 | 40·5 | 33·2 |

During twenty of these years simultaneous observations were taken at the Apartments of this Society. The following Table of comparison of results is formed by comparing the numbers in the preceding Table with those for the same months in Table I. of my paper in the Philosophical Transactions, Part II., 1849.

TABLE IX.—Comparison of the mean monthly temperature of the Air at the Apartments of the Royal Society, with the mean monthly temperature of the Air at Lyndon.

| Years. | January. | | | February. | | | March. | | | April. | | | May. | | | June. | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | Mean temperature of the air. | | | Mean temperature of the air. | | | Mean temperature of the air. | | | Mean temperature of the air. | | | Mean temperature of the air. | | | Mean temperature of the air. | | |
| | Somerset House. | Lyndon. | Higher at Somerset House. | Somerset House. | Lyndon. | Higher at Somerset House. | Somerset House. | Lyndon. | Higher at Somerset House. | Somerset House. | Lyndon. | Higher at Somerset House. | Somerset House. | Lyndon. | Higher at Somerset House. | Somerset House. | Lyndon. | Higher at Somerset House. |
| | ° | ° | ° | ° | ° | ° | ° | ° | ° | ° | ° | ° | ° | ° | ° | ° | ° | ° |
| 1774. | 33·1 | 31·2 | +1·9 | 39·4 | 37·8 | +1·6 | 43·9 | 41·0 | +2·9 | 47·9 | 46·5 | +1·4 | 52·2 | 51·5 | +0·7 | 61·0 | 60·2 | +0·8 |
| 1775. | 42·0 | 38·7 | +3·3 | 43·3 | 42·5 | +0·8 | 42·8 | 41·5 | +1·3 | 50·8 | 49·7 | +1·1 | 55·2 | 55·0 | +0·2 | 63·5 | 62·7 | +0·8 |
| 1776. | 28·6 | 27·5 | +1·1 | 41·4 | 38·2 | +3·2 | 44·8 | 43·2 | +1·6 | 48·3 | 47·8 | +0·5 | 51·7 | 52·0 | −0·3 | 59·6 | 59·2 | +0·4 |
| 1777. | 35·5 | 33·5 | +2·0 | 37·2 | 34·2 | +3·0 | 45·7 | 43·2 | +2·5 | 45·1 | 45·0 | +0·1 | 53·4 | 54·0 | −0·6 | 57·2 | 57·7 | −0·5 |
| 1778. | 36·4 | 34·5 | +1·9 | 37·0 | 35·8 | +1·2 | 41·2 | 40·0 | +1·2 | 48·0 | 46·0 | +2·0 | 55·9 | 55·5 | +0·4 | 62·2 | 62·2 | 0·0 |
| 1779. | 36·4 | 36·0 | +0·4 | 46·7 | 44·5 | +2·2 | 48·1 | 44·2 | +3·9 | 51·8 | 49·2 | +2·6 | 55·8 | 54·0 | +1·8 | 58·9 | 58·2 | +0·7 |
| 1780. | 30·2 | 29·5 | +0·7 | 36·7 | 35·0 | +1·7 | 50·3 | 45·5 | +4·8 | 44·7 | 43·0 | +1·7 | 57·2 | 55·8 | +1·4 | 60·0 | 58·8 | +1·2 |
| 1781. | 37·8 | 34·0 | +3·8 | 41·7 | 40·7 | +1·0 | 43·7 | 43·0 | +0·7 | 47·2 | 48·5 | −1·3 | 54·2 | 53·2 | +1·0 | 63·4 | 63·5 | −0·1 |
| 1787. | 38·3 | 37·2 | +1·1 | 40·9 | 42·5 | −1·6 | 43·9 | 44·2 | −0·3 | 45·5 | 46·0 | −0·5 | 52·4 | 53·8 | −1·4 | 58·7 | 60·0 | −1·3 |
| 1788. | 39·0 | 38·5 | +0·5 | 40·1 | 39·0 | +1·1 | 39·7 | 39·0 | +0·7 | 50·6 | 50·8 | −0·2 | 57·4 | 59·3 | −1·9 | 59·5 | 61·5 | −2·0 |
| 1789. | 35·0 | 34·5 | +0·5 | 41·3 | 40·5 | +0·8 | 35·5 | 36·0 | −0·5 | 45·2 | 47·0 | −1·8 | 54·3 | 56·8 | −2·5 | 55·7 | 60·0 | −4·3 |
| 1790. | 40·2 | 39·0 | +1·2 | 42·6 | 42·8 | −0·2 | 44·3 | 44·8 | −0·5 | 42·0 | 43·8 | −1·8 | 53·7 | 55·2 | −1·5 | 57·7 | 61·5 | −3·8 |
| 1791. | 41·4 | No obs. | ..... | 40·2 | 39·8 | +0·4 | 43·2 | 43·2 | 0·0 | 49·9 | 50·5 | −0·6 | 50·5 | 52·0 | −1·5 | 58·5 | 59·8 | −1·3 |
| 1792. | 36·5 | 36·5 | 0·0 | 38·8 | 38·8 | 0·0 | 43·2 | 43·2 | 0·0 | 50·0 | 51·5 | −1·5 | 50·7 | 52·2 | −1·5 | 55·3 | 57·8 | −2·5 |
| 1793. | 36·9 | 36·5 | +0·4 | 41·1 | 40·5 | +0·6 | 40·4 | 40·2 | +0·2 | 43·5 | 43·0 | +0·5 | 51·8 | 53·2 | −1·4 | 56·3 | 60·0 | −3·7 |
| 1794. | 34·9 | 34·5 | +0·4 | 46·1 | 45·5 | +0·6 | 45·4 | 45·2 | +0·2 | 50·7 | 52·0 | −1·3 | 51·7 | 53·5 | −1·8 | 58·5 | 62·5 | −4·0 |
| 1795. | 25·5 | 26·8 | −1·3 | 35·5 | 32·8 | +2·7 | 39·7 | 39·8 | −0·1 | 46·2 | 46·8 | −0·6 | 53·0 | 54·5 | −1·5 | 54·6 | 58·0 | −3·4 |
| 1796. | 46·9 | 44·8 | +2·1 | 41·0 | 40·5 | +0·5 | 40·1 | 40·5 | −0·4 | 49·4 | 51·2 | −1·8 | 51·2 | 51·0 | +0·2 | 57·0 | 60·5 | −3·5 |
| 1797. | 37·0 | 38·0 | −1·0 | 37·0 | 38·2 | −1·2 | 39·0 | 40·0 | −1·0 | 45·8 | 45·8 | 0·0 | 52·4 | 55·0 | −2·6 | 55·7 | 57·8 | −2·1 |
| 1798. | 39·4 | 38·5 | +0·9 | 39·3 | 38·8 | +0·5 | 41·8 | 41·2 | +0·6 | 50·3 | 51·5 | −1·2 | 54·7 | 56·8 | −2·1 | 62·1 | 65·8 | −3·7 |

| | July. | | | August. | | | September. | | | October. | | | November. | | | December. | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | ° | ° | ° | ° | ° | ° | ° | ° | ° | ° | ° | ° | ° | ° | ° | ° | ° | ° |
| 1774. | 62·8 | 61·0 | +1·8 | 61·5 | 61·2 | +0·3 | 55·8 | 54·2 | +1·6 | 50·1 | 48·2 | +1·9 | 40·5 | 39·0 | +1·5 | 38·5 | 35·8 | +2·7 |
| 1775. | 64·0 | 64·0 | 0·0 | 62·1 | 59·7 | +2·4 | 59·5 | 57·8 | +1·7 | 49·5 | 47·5 | +2·0 | 41·5 | 37·8 | +3·7 | 40·7 | 37·5 | +3·2 |
| 1776. | 63·8 | 63·8 | 0·0 | 62·0 | 60·0 | +2·0 | 55·6 | 55·2 | +0·4 | 52·8 | 49·8 | +3·0 | 44·0 | 41·2 | +2·8 | 41·5 | 38·8 | +2·7 |
| 1777. | 61·5 | 61·5 | 0·0 | 63·7 | 61·5 | +2·2 | 59·2 | 57·7 | +1·5 | 52·6 | 49·8 | +2·8 | 45·0 | 42·7 | +2·3 | 37·2 | 35·2 | +2·0 |
| 1778. | 68·0 | 66·0 | +2·0 | 64·8 | 62·5 | +2·3 | 54·5 | 52·2 | +2·3 | 47·3 | 44·8 | +2·5 | 46·0 | 43·2 | +2·8 | 44·2 | 42·0 | +2·2 |
| 1779. | 65·9 | 65·5 | +0·4 | 65·2 | 63·0 | +0·2 | 61·8 | 59·0 | +2·8 | 53·2 | 50·8 | +2·4 | 43·2 | 40·8 | +2·4 | 41·6 | 36·7 | +4·9 |
| 1780. | 64·2 | 63·5 | +0·7 | 67·0 | 64·0 | +3·0 | 60·4 | 58·5 | +1·9 | 51·3 | 48·5 | +2·8 | 40·8 | 38·0 | +2·8 | 38·0 | 36·7 | +1·3 |
| 1781. | 66·3 | 64·5 | +1·8 | 64·3 | 64·0 | +0·3 | | | | | | | | | | | | |
| 1787. | 62·4 | 62·5 | −0·1 | 62·4 | 61·8 | +0·6 | 55·5 | 59·0 | −3·5 | 49·9 | 50·2 | −0·3 | 40·9 | 38·8 | +2·1 | 41·0 | 39·0 | +2·0 |
| 1788. | 61·6 | 65·5 | −3·9 | 61·2 | 62·0 | −0·8 | 57·0 | 57·5 | −0·5 | 50·4 | 50·2 | +0·2 | 41·9 | 42·0 | −0·1 | 30·4 | 34·2 | −3·8 |
| 1789. | 59·8 | 63·0 | −3·2 | 61·5 | 63·0 | −1·5 | 55·7 | 56·8 | −1·1 | 48·1 | 48·0 | +0·1 | 40·0 | 39·8 | +0·2 | 43·0 | 42·0 | +1·0 |
| 1790. | 60·1 | 63·0 | −2·9 | 61·2 | 62·5 | −1·3 | 55·0 | 55·2 | −0·2 | 50·8 | 50·2 | +0·6 | 43·3 | 42·2 | +1·1 | 40·4 | 40·8 | −0·4 |
| 1791. | 60·5 | 61·5 | −1·0 | 62·7 | 63·0 | −0·3 | 57·9 | 58·0 | −0·1 | 47·9 | 47·8 | +0·1 | 42·6 | 42·2 | +0·4 | 36·2 | 33·0 | +3·2 |
| 1792. | 59·6 | 62·5 | −2·9 | 63·5 | 64·2 | −0·7 | 56·5 | 54·0 | +2·5 | 50·0 | 48·8 | +1·2 | 44·5 | 44·8 | −0·3 | 41·4 | 40·2 | +1·2 |
| 1793. | 65·9 | 68·2 | −2·3 | 60·3 | 62·5 | −2·2 | 53·9 | 55·0 | −1·1 | 53·2 | 53·8 | −0·6 | 44·2 | 43·2 | +1·0 | 42·4 | 41·0 | +1·4 |
| 1794. | 66·3 | 69·0 | −2·7 | 60·7 | 61·8 | −1·1 | 54·8 | 54·8 | 0·0 | 49·6 | 49·5 | +0·1 | 44·6 | 43·5 | +1·1 | 38·2 | 37·2 | +1·0 |
| 1795. | 59·9 | 60·2 | −0·3 | 62·1 | 64·5 | −2·4 | 61·9 | 61·8 | +0·1 | 54·7 | 54·0 | +0·7 | 42·0 | 41·0 | +1·0 | 46·2 | 44·5 | +1·7 |
| 1796. | 59·6 | 62·5 | −2·9 | 61·2 | 62·5 | −1·3 | 60·2 | 60·0 | +0·2 | 47·8 | 47·2 | +0·6 | 41·6 | 40·5 | +1·1 | 31·8 | 32·0 | −0·2 |
| 1797. | 64·3 | 66·8 | −2·5 | 60·3 | 63·0 | −2·7 | 55·7 | 55·0 | +0·7 | 48·3 | 48·0 | +0·3 | 42·7 | 41·2 | +1·5 | 42·6 | 40·2 | +2·4 |
| 1798. | 62·2 | 64·5 | −2·3 | 62·8 | 64·2 | −1·4 | 57·6 | 58·5 | −0·9 | 51·1 | 51·0 | +0·1 | 41·3 | 40·5 | +0·8 | 35·1 | 33·2 | +1·9 |

By taking the means of the differences of the results, we find that the reading of the thermometer in air at the Apartments of the Royal Society in

| | |
|---|---|
| January was higher than at Lyndon by . . . . | 1°·0 |
| February was higher than at Lyndon by . . . . | 0·8 |
| March was higher than at Lyndon by . . . . . | 0·8 |
| April was lower than at Lyndon by . . . . . | 0·2 |
| May was lower than at Lyndon by . . . . . | 0·6 |
| June was lower than at Lyndon by . . . . . | 1·7 |
| July was lower than at Lyndon by . . . . . | 1·0 |
| August was higher than at Lyndon by less than . | 0·1 |
| September was higher than at Lyndon by . . . | 0·4 |
| October was higher than at Lyndon by . . . . | 1·0 |
| November was higher than at Lyndon by. . . . | 1·0 |
| December was higher than at Lyndon by. . . . | 1·6 |

*Determination of the Mean Temperature of each month at the Apartments of the Royal Society for those months when no observations were made there.*

By applying the above numbers to those in Table VIII. when no observations were taken at the Apartments of the Royal Society, the following Table is formed:—

TABLE X.—Showing the approximate mean monthly temperature of the Air at the Apartments of the Royal Society.

| Year. | Approximate mean temperature of the air. | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | January. | Feb. | March. | April. | May. | June. | July. | August. | Sept. | October. | Nov. | Dec. |
| 1771. | 31°·5 | 34°·8 | 35°·8 | 39°·8 | 55°·6 | 54°·9 | 60°·5 | 59°·7 | 53°·1 | 48°·5 | 42°·2 | 42°·8 |
| 1772. | 33·8 | 35·6 | 39·6 | 43·3 | 49·7 | 60·3 | 61·0 | 61·0 | 56·1 | 53·7 | 44·7 | 40·9 |
| 1773. | 38·5 | 36·5 | 42·0 | 45·3 | 48·6 | 56·5 | 59·5 | 62·2 | 54·9 | 49·5 | 40·5 | 39·6 |
| 1781. | ..... | ..... | ..... | ..... | ..... | ..... | ..... | ..... | 57·9 | 49·8 | 43·0 | 42·4 |
| 1782. | 40·5 | 35·8 | 39·8 | 41·8 | 49·2 | 58·8 | 60·2 | 58·0 | 56·6 | 46·5 | 36·0 | 37·6 |
| 1783. | 38·5 | 40·6 | 38·8 | 49·0 | 49·4 | 59·3 | 66·7 | 62·0 | 55·7 | 50·3 | 43·8 | 36·4 |
| 1784. | 30·8 | 33·3 | 37·3 | 43·1 | 57·9 | 57·1 | 60·5 | 57·5 | 58·4 | 45·2 | 42·0 | 32·4 |
| 1785. | 37·7 | 31·8 | 35·0 | 47·3 | 53·6 | 60·3 | 63·2 | 58·8 | 57·9 | 48·2 | 41·5 | 36·6 |
| 1786. | 37·5 | 37·6 | 35·3 | 45·8 | 53·4 | 60·5 | 60·0 | 60·2 | 52·4 | 46·0 | 38·0 | |

And these numbers may be considered as being very nearly the true values; they are reduced to the same zero as those in Table I. of my former paper, and form a part of that series of values.

*Determination of the Mean Temperature of the Air at Epping for every month from the year* 1821 *to* 1840.

Let us now proceed to compare the results of observations taken simultaneously towards the end of the Royal Society's series, made as nearly as possible under the

same circumstances as those at Lyndon at the beginning of that series, with the view of determining whether an agreement exists in the differences at those different epochs, and also for the purpose of assisting to determine whether London be really warmer than the country, as affirmed. The observations which most fully satisfy these conditions are those made by Mr. Thomas Squire of Epping. This gentleman, on my request to furnish me with the monthly means of his observations for comparison with those of this Society, most promptly and obligingly sent me the monthly mean from twenty-eight years' observations taken on every day at $8^h$ in the morning.

The thermometer with which the observations were made was placed in the shade, at the height of 5 feet above the ground, facing the N.E., and an open country.

These numbers I have reduced to mean values by the application of corrections, for that purpose (see my paper in Philosophical Transactions, Part I. 1848) then I further reduced them to the elevation at Somerset House and for difference of latitude, and in this way the next Table was formed.

Table XI.—Mean monthly temperature of the Air at Epping reduced to the elevation and latitude of Somerset House, for the year 1821 to 1848.

| Year. | January. | Feb. | March. | April. | May. | June. | July. | August. | Sept. | October. | Nov. | Dec. | Year. |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 1821. | 38°5 | 34°8 | 43°0 | 50°2 | 49°4 | 53°1 | 58°4 | 64°1 | 62°7 | 50°7 | 47°3 | 43°5 | 49°6 |
| 1822. | 39·0 | 43·0 | 46·9 | 48·9 | 57·6 | 65·3 | 64·1 | 62·7 | 58·1 | 52·6 | 46·6 | 33·9 | 51·6 |
| 1823. | 31·5 | 38·3 | 41·5 | 47·1 | 57·1 | 56·8 | 60·3 | 61·5 | 57·1 | 48·4 | 43·8 | 39·6 | 48·6 |
| 1824. | 38·0 | 38·8 | 41·6 | 46·2 | 52·1 | 56·8 | 62·9 | 61·9 | 59·9 | 51·0 | 46·7 | 42·2 | 49·8 |
| 1825. | 38·9 | 38·2 | 41·7 | 51·0 | 56·7 | 60·6 | 65·4 | 64·3 | 62·6 | 51·8 | 41·0 | 40·2 | 51·0 |
| 1826. | 31·8 | 42·3 | 43·4 | 50·6 | 53·1 | 63·9 | 66·3 | 66·1 | 59·8 | 53·7 | 40·2 | 42·7 | 51·2 |
| 1827. | 33·8 | 32·3 | 44·9 | 50·6 | 56·0 | 59·8 | 64·2 | 61·3 | 59·2 | 53·8 | 42·5 | 41·2 | 50·2 |
| 1828. | 40·7 | 41·8 | 44·7 | 49·8 | 57·0 | 61·9 | 62·8 | 61·5 | 60·1 | 50·7 | 44·8 | 45·2 | 51·8 |
| 1829. | 31·9 | 38·8 | 40·3 | 46·0 | 56·7 | 60·5 | 60·8 | 58·9 | 54·4 | 49·0 | 38·9 | 32·4 | 47·3 |
| 1830. | 31·4 | 34·4 | 46·4 | 50·7 | 56·8 | 56·2 | 63·9 | 59·1 | 55·2 | 52·1 | 43·1 | 35·3 | 48·7 |
| 1831. | 34·9 | 41·2 | 45·5 | 51·3 | 54·7 | 60·3 | 62·1 | 63·8 | 58·2 | 56·2 | 42·7 | 42·3 | 50·2 |
| 1832. | 36·8 | 37·0 | 41·8 | 48·9 | 53·4 | 59·8 | 61·1 | 61·8 | 58·3 | 52·2 | 53·6 | 43·1 | 50·3 |
| 1833. | 35·2 | 42·9 | 38·9 | 47·9 | 60·4 | 59·8 | 60·7 | 57·9 | 55·0 | 51·6 | 43·1 | 45·8 | 49·9 |
| 1834. | 45·6 | 40·1 | 45·1 | 47·6 | 57·7 | 61·5 | 64·0 | 63·2 | 60·5 | 51·9 | 44·4 | 41·3 | 51·9 |
| 1835. | 38·6 | 41·4 | 42·3 | 48·8 | 54·7 | 60·7 | 64·2 | 64·5 | 58·9 | 48·8 | 43·7 | 35·7 | 50·2 |
| 1836. | 37·9 | 37·0 | 44·5 | 46·1 | 52·6 | 61·0 | 62·6 | 60·3 | 55·6 | 49·7 | 42·1 | 40·4 | 49·2 |
| 1837. | 38·4 | 40·1 | 37·4 | 42·4 | 50·4 | 60·7 | 62·5 | 62·3 | 57·6 | 51·5 | 39·5 | 41·9 | 48·7 |
| 1838. | 28·6 | 32·9 | 42·5 | 44·8 | 53·7 | 60·2 | 62·4 | 62·1 | 57·5 | 51·1 | 40·4 | 38·7 | 47·9 |
| 1839. | 37·2 | 39·0 | 41·3 | 45·1 | 51·3 | 61·7 | 62·6 | 61·0 | 57·7 | 50·7 | 46·3 | 40·1 | 49·5 |
| 1840. | 39·2 | 38·0 | 39·4 | 50·1 | 56·4 | 62·1 | 61·0 | 64·2 | 54·2 | 46·4 | 42·6 | 32·6 | 48·9 |
| 1841. | 33·6 | 36·3 | 46·5 | 48·8 | 59·1 | 58·1 | 60·9 | 62·6 | 60·2 | 49·8 | 42·2 | 40·0 | 49·8 |
| 1842. | 33·1 | 40·1 | 44·8 | 47·3 | 55·1 | 64·7 | 62·4 | 67·3 | 59·4 | 44·9 | 42·4 | 44·1 | 50·4 |
| 1843. | 39·6 | 35·9 | 43·1 | 49·5 | 54·5 | 58·0 | 62·6 | 64·5 | 62·1 | 48·0 | 43·1 | 44·1 | 50·4 |
| 1844. | 38·5 | 33·9 | 42·3 | 51·8 | 54·4 | 62·0 | 63·6 | 59·4 | 59·2 | 47·9 | 43·5 | 33·9 | 49·3 |
| 1845. | 38·9 | 32·2 | 36·8 | 47·7 | 51·2 | 62·8 | 61·6 | 59·3 | 56·5 | 50·1 | 44·6 | 40·0 | 48·5 |
| 1846. | 42·7 | 42·2 | 43·9 | 48·4 | 56·1 | 67·3 | 65·4 | 64·5 | 60·6 | 50·5 | 44·4 | 31·2 | 51·5 |
| 1847. | 35·0 | 35·0 | 40·8 | 45·4 | 57·0 | 58·3 | 64·9 | 61·7 | 54·2 | 52·8 | 45·3 | 41·8 | 49·4 |
| 1848. | 35·0 | 42·6 | 43·0 | 48·9 | 59·4 | 60·1 | 62·5 | 59·3 | 56·6 | 51·7 | 40·5 | 41·9 | 50·2 |

During twenty-two of these years observations were taken at Somerset House, and the following Table exhibits the simultaneous results with their differences.

TABLE XII.—Comparison of the mean monthly temperature of the Air at Somerset House and at Epping.

| Year. | January. | | | February. | | | March. | | | April. | | | May. | | | June. | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | Mean temperature of the air at | | | Mean temperature of the air at | | | Mean temperature of the air at | | | Mean temperature of the air at | | | Mean temperature of the air at | | | Mean temperature of the air at | | |
| | Somerset House. | Epping. | Higher at Somerset House. | Somerset House. | Epping. | Higher at Somerset House. | Somerset House. | Epping. | Higher at Somerset House. | Somerset House. | Epping. | Higher at Somerset House. | Somerset House. | Epping. | Higher at Somerset House. | Somerset House. | Epping. | Higher at Somerset House. |
| | ° | ° | ° | ° | ° | ° | ° | ° | ° | ° | ° | ° | ° | ° | ° | ° | ° | ° |
| 1821. | 36·1 | 33·5 | +0·6 | 37·4 | 34·8 | +2·6 | 43·9 | 43·0 | +0·9 | 51·5 | 50·2 | +1·3 | 50·1 | 49·4 | +0·7 | 55·0 | 53·1 | +1·9 |
| 1822. | 41·4 | 39·0 | +2·4 | 44·7 | 43·0 | +1·7 | 48·4 | 46·9 | +1·5 | 47·8 | 48·9 | −1·1 | 56·9 | 57·6 | −0·7 | 63·5 | 65·3 | −1·8 |
| 1823. | 33·4 | 31·5 | +1·9 | 39·5 | 38·3 | +1·2 | 40·9 | 41·5 | −0·6 | 43·9 | 47·1 | −3·2 | 55·7 | 57·1 | −1·4 | 56·3 | 56·8 | −0·5 |
| 1824. | 39·0 | 38·0 | +1·0 | 37·6 | 38·8 | −1·2 | 40·6 | 41·6 | −1·0 | 44·9 | 46·2 | −1·3 | 50·6 | 52·1 | −1·5 | 55·9 | 56·8 | −0·9 |
| 1825. | 40·0 | 38·9 | +1·1 | 39·5 | 38·2 | +1·3 | 39·6 | 40·7 | −1·1 | 49·8 | 51·0 | −1·2 | 54·7 | 56·7 | −2·0 | 59·8 | 60·6 | −0·8 |
| 1826. | 33·6 | 31·8 | +1·8 | 43·6 | 42·3 | +1·3 | 44·3 | 43·4 | +0·9 | 50·1 | 50·6 | −0·5 | 51·1 | 53·1 | −2·0 | 63·8 | 63·9 | −0·1 |
| 1827. | 35·0 | 33·8 | +1·2 | 33·0 | 32·3 | +0·7 | 44·2 | 44·9 | −0·7 | 47·9 | 50·6 | −2·7 | 53·8 | 56·0 | −2·2 | 58·5 | 59·8 | −1·3 |
| 1828. | 41·4 | 40·7 | +0·7 | 41·6 | 41·8 | −0·2 | 44·6 | 44·7 | −0·1 | 47·6 | 49·8 | −2·2 | 55·4 | 57·0 | −1·6 | 60·9 | 61·9 | −1·0 |
| 1829. | 32·3 | 31·9 | +1·4 | 39·8 | 38·8 | +1·0 | 40·1 | 40·3 | −0·2 | 44·8 | 46·0 | −1·2 | 55·6 | 56·7 | −1·1 | 59·9 | 60·5 | −0·6 |
| 1830. | 32·3 | 31·4 | +0·9 | 35·6 | 34·4 | +1·2 | 45·0 | 45·5 | −0·5 | 49·4 | 50·7 | −1·3 | 55·8 | 56·8 | −1·0 | 56·2 | 56·2 | 0·0 |
| 1831. | 36·0 | 34·9 | +1·1 | 42·6 | 41·2 | +1·4 | 41·6 | 41·8 | −0·2 | 49·2 | 51·3 | −2·1 | 53·9 | 54·7 | −0·8 | 60·3 | 60·3 | 0·0 |
| 1832. | 38·9 | 36·8 | +2·1 | 38·3 | 37·0 | +1·3 | 38·7 | 38·9 | −0·2 | 48·3 | 48·9 | −0·6 | 52·6 | 53·4 | −0·8 | 60·1 | 59·8 | +0·3 |
| 1833. | 36·1 | 35·2 | +0·9 | 43·8 | 42·9 | +0·9 | 41·1 | 45·1 | −0·0 | 46·3 | 47·9 | −1·6 | 60·5 | 60·4 | +0·1 | 60·7 | 59·8 | +0·9 |
| 1834. | 46·0 | 45·6 | +0·4 | 41·6 | 40·1 | +1·5 | 42·1 | 42·3 | −0·2 | 46·1 | 47·6 | −1·5 | 58·0 | 57·7 | +0·3 | 62·0 | 61·5 | +0·5 |
| 1835. | 39·6 | 38·6 | +1·0 | 42·6 | 41·4 | +1·2 | 44·8 | 44·5 | +0·3 | 47·5 | 48·8 | −1·3 | 54·0 | 54·7 | −0·7 | 60·9 | 60·7 | +0·2 |
| 1836. | 38·8 | 37·9 | +0·9 | 38·3 | 37·0 | +1·3 | 36·9 | 37·4 | −0·5 | 44·4 | 46·1 | −1·7 | 53·9 | 52·6 | +1·3 | 59·9 | 61·0 | −1·1 |
| 1837. | 38·8 | 38·4 | +0·4 | 41·7 | 40·1 | +1·6 | 42·6 | 42·5 | +0·1 | 40·2 | 42·4 | −2·2 | 48·9 | 50·4 | −1·5 | 59·0 | 60·7 | −1·7 |
| 1838. | 30·5 | 28·6 | +1·9 | 34·3 | 32·9 | +1·4 | 40·1 | 41·3 | −1·2 | 42·7 | 44·8 | −2·1 | 51·8 | 53·7 | −1·9 | 58·1 | 60·2 | −2·1 |
| 1839. | 38·8 | 37·2 | +1·6 | 40·5 | 39·0 | +1·5 | 38·7 | 39·4 | −0·7 | 42·0 | 45·1 | −3·1 | 51·0 | 51·3 | −0·3 | 59·6 | 61·7 | −2·1 |
| 1840. | 40·6 | 39·2 | +1·4 | 39·5 | 38·0 | +1·5 | 47·9 | 46·5 | +1·4 | 48·9 | 50·1 | −1·2 | 54·6 | 56·4 | −1·8 | 60·4 | 62·1 | −1·7 |
| 1841. | 36·1 | 33·6 | +2·5 | 36·6 | 36·3 | +0·3 | 45·4 | 44·8 | +0·6 | 47·4 | 48·8 | −1·4 | 57·9 | 59·1 | −1·2 | 57·2 | 58·1 | −0·9 |
| 1842. | 34·8 | 33·1 | +1·7 | 42·2 | 40·1 | +2·1 | 43·6 | 43·1 | +0·5 | 45·7 | 47·3 | −1·6 | 54·3 | 55·1 | −0·8 | 64·2 | 64·7 | −0·5 |
| 1843. | 41·3 | 39·6 | +1·7 | 37·5 | 35·9 | +1·6 | | | | 48·6 | 49·5 | −0·9 | 52·8 | 54·5 | −1·7 | 56·4 | 58·0 | −1·6 |

| Year. | July. | | | August. | | | September. | | | October. | | | November. | | | December. | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | Mean temperature of the air at | | | Mean temperature of the air at | | | Mean temperature of the air at | | | Mean temperature of the air at | | | Mean temperature of the air at | | | Mean temperature of the air at | | |
| | Somerset House. | Epping. | Higher at Somerset House. | Somerset House. | Epping. | Higher at Somerset House. | Somerset House. | Epping. | Higher at Somerset House. | Somerset House. | Epping. | Higher at Somerset House. | Somerset House. | Epping. | Higher at Somerset House. | Somerset House. | Epping. | Higher at Somerset House. |
| | ° | ° | ° | ° | ° | ° | ° | ° | ° | ° | ° | ° | ° | ° | ° | ° | ° | ° |
| 1821. | 58·7 | 58·4 | +0·3 | 63·0 | 64·1 | −1·1 | 60·7 | 62·7 | −2·0 | 51·6 | 50·7 | +0·9 | 48·9 | 47·3 | +1·6 | 45·7 | 43·5 | +2·2 |
| 1822. | 63·5 | 64·1 | −0·6 | 62·6 | 62·7 | −0·1 | 57·1 | 58·1 | −1·0 | 53·3 | 52·6 | +0·7 | 49·5 | 46·6 | +2·9 | 37·8 | 33·9 | +3·9 |
| 1823. | 60·1 | 60·3 | −0·2 | 61·6 | 61·5 | +0·1 | 56·5 | 57·1 | −0·6 | 48·9 | 48·4 | +0·5 | 44·3 | 43·8 | +0·5 | 41·3 | 39·6 | +1·7 |
| 1824. | 63·5 | 62·9 | +0·6 | 61·3 | 61·9 | −0·6 | 58·8 | 59·9 | −1·1 | 51·1 | 51·0 | +0·1 | 47·5 | 46·7 | +0·8 | 43·2 | 42·2 | +1·0 |
| 1825. | 66·2 | 65·4 | +0·8 | 63·1 | 64·3 | −1·2 | 61·0 | 62·6 | −1·6 | 52·1 | 51·8 | +0·3 | 42·5 | 41·0 | +1·5 | 42·0 | 40·2 | +1·8 |
| 1826. | 66·6 | 66·3 | +0·3 | 64·7 | 66·1 | −1·4 | 57·4 | 59·8 | −2·4 | 53·7 | 53·7 | 0·0 | 41·2 | 40·2 | +1·0 | 43·2 | 42·7 | +0·5 |
| 1827. | 64·5 | 64·2 | +0·3 | 60·3 | 61·3 | −1·0 | 58·0 | 59·2 | −1·2 | 53·1 | 53·3 | −0·7 | 42·8 | 42·5 | +0·3 | 45·5 | 41·2 | +4·3 |
| 1828. | 62·9 | 62·8 | +0·1 | 60·3 | 61·5 | −1·2 | 58·6 | 60·1 | −1·5 | 51·2 | 50·7 | +0·5 | 45·6 | 44·8 | +0·8 | 45·9 | 45·2 | +0·7 |
| 1829. | 61·1 | 60·8 | +0·3 | 59·0 | 58·9 | +0·1 | 54·3 | 54·4 | −0·1 | 48·8 | 49·0 | −0·2 | 40·6 | 38·9 | +1·7 | 36·3 | 32·4 | +3·9 |
| 1830. | 64·0 | 63·9 | +0·1 | 59·5 | 59·1 | +0·4 | 54·6 | 55·2 | −0·6 | 52·2 | 52·1 | +0·1 | 45·7 | 43·1 | +2·6 | 36·3 | 35·3 | +1·0 |
| 1831. | 65·3 | 62·1 | +3·2 | 64·6 | 63·8 | +0·8 | 57·5 | 58·2 | −0·7 | 56·3 | 56·2 | +0·1 | 45·6 | 42·7 | +2·9 | 43·4 | 42·3 | +1·1 |
| 1832. | 62·2 | 61·1 | +1·1 | 62·3 | 61·8 | +0·5 | 57·7 | 58·3 | −0·6 | 52·5 | 52·2 | +0·3 | 45·0 | 43·6 | +1·4 | 43·8 | 43·1 | +0·7 |
| 1833. | 62·1 | 60·7 | +1·4 | 58·8 | 57·9 | +0·9 | 54·6 | 55·0 | −0·4 | 49·6 | 51·6 | −2·0 | 44·8 | 43·1 | +1·7 | 46·0 | 43·8 | +2·2 |
| 1834. | 65·1 | 64·0 | +1·1 | 63·6 | 63·2 | +0·4 | 59·4 | 60·5 | −1·1 | 51·8 | 51·9 | −0·1 | 45·4 | 44·4 | +1·0 | 42·4 | 41·3 | +1·1 |
| 1835. | 65·4 | 64·2 | +1·2 | 64·6 | 64·3 | +0·1 | 58·2 | 58·9 | −0·7 | 49·3 | 48·8 | +0·5 | 44·3 | 43·7 | +0·6 | 36·3 | 35·7 | +0·6 |
| 1836. | 63·9 | 62·6 | +1·3 | 60·2 | 60·3 | −0·1 | 54·5 | 55·6 | −1·1 | 48·7 | 49·7 | −1·0 | 42·8 | 42·1 | +0·7 | 41·0 | 40·4 | +0·6 |
| 1837. | 62·3 | 62·5 | −0·2 | 61·4 | 62·3 | −0·9 | 56·1 | 57·6 | −1·5 | 51·9 | 51·5 | +0·4 | 42·4 | 39·5 | +2·9 | 42·6 | 41·9 | +0·7 |
| 1838. | 61·5 | 62·4 | −0·9 | 60·9 | 62·1 | −1·2 | 55·5 | 57·5 | −2·0 | 51·3 | 51·1 | +0·2 | 42·1 | 40·4 | +1·7 | 40·0 | 38·7 | +1·3 |
| 1839. | 61·2 | 62·6 | −1·4 | 60·2 | 61·0 | −0·8 | 56·7 | 57·7 | −1·0 | 50·2 | 50·7 | −0·5 | 46·0 | 46·3 | −0·3 | 41·0 | 40·1 | +0·9 |
| 1840. | 59·8 | 61·0 | −1·2 | 63·4 | 64·2 | −0·8 | 55·2 | 54·2 | +1·0 | 48·1 | 46·4 | +1·7 | 44·7 | 42·6 | +2·1 | 34·7 | 32·6 | +2·1 |
| 1841. | 59·0 | 60·9 | −1·9 | 61·3 | 62·6 | −1·3 | 58·5 | 60·2 | −1·7 | 50·7 | 49·8 | +0·9 | 44·5 | 42·2 | +2·3 | 42·0 | 40·0 | +2·0 |
| 1842. | 61·5 | 62·4 | −0·9 | 67·6 | 67·3 | +0·3 | 57·5 | 59·4 | −1·9 | 47·2 | 44·9 | +2·3 | 44·2 | 42·4 | +1·8 | 45·3 | 44·1 | +1·2 |

By taking the mean of the numbers in each column of differences, we find that the temperature of the air at the Apartments of the Royal Society in

| | |
|---|---|
| January was higher than at Epping reduced to the same level by . . | 1°·3 |
| February was higher than at Epping reduced to the same level by . | 1·2 |
| March was lower than at Epping reduced to the same level by less than | 0·1 |
| April was lower than at Epping reduced to the same level by . . . | 1·5 |
| May was lower than at Epping reduced to the same level by . . . | 1·0 |
| June was lower than at Epping reduced to the same level by . . . | 0·6 |
| July was higher than at Epping reduced to the same level by . . . | 0·2 |
| August was lower than at Epping reduced to the same level by . . . | 0·3 |
| September was lower than at Epping reduced to the same level by . | 1·0 |
| October was higher than at Epping reduced to the same level by . . | 0·2 |
| November was higher than at Epping reduced to the same level by . | 1·4 |
| December was higher than at Epping reduced to the same level by . | 1·5 |

And the mean temperature of the whole period was nearly of the same value at both places.

Having obtained these results, and finding that during the time the sun was situated north of the equator the temperature at the Apartments of the Royal Society was lower than at Epping, and that it was higher during the time the sun had south declination, I requested Mr. Squire to furnish me with full particulars with respect to the position of his instrument to the sun and to surrounding objects: the following is the information he gave me:—

"The thermometer hangs near the north angle of a small projecting pier of a wall, nearly close to the brickwork, facing the N.E., and an open country. At the back of the wall is a grape-vine, and when in leaf, it so shades the wall that its temperature is not much affected by the sun's rays; but, before the vine is in leaf, it may raise the temperature a trifle; yet from some casual observations scattered over my journal as tests, I do not find that the said thermometer is sensibly influenced by the heat of the sun at 8 A.M., the time of reading the instrument. On the 13th of May, 1847, I moved the thermometer a few feet from its former position on the wall, with the same aspect, but, at the back of this part of the wall, there is a sort of grotto or summer-house, which is covered by thatch and completely interrupts the sun's rays from the wall; hence its present situation may perhaps be considered more eligible for a mean temperature than its former position, but I do not find any difference worth notice."

The general fact, however, of a higher winter temperature, and of a lower summer temperature at the Apartments of the Royal Society, is satisfactorily proved by both sets of comparisons, and it is evident that the same cause has been in operation at both times, and to the same amount. There can be no doubt that this cause is the vicinity of the river Thames to the locality of the observations.

*Determination of the Monthly Mean Temperature of the water of the Thames by night and by day, from the year* 1846 *to the year* 1849.

The observations to determine the temperature of the Thames water are made by Lieut. Sanders, R.N. The instruments consist of one maximum thermometer and of one minimum thermometer, suspended from the sides of the Dreadnought Hospital Ship, in a perforated trunk placed at about 2 feet below the surface of the water. The range of temperature during the day is usually about 2°, and the simple arithmetic mean of the readings of the maximum and minimum thermometers shows the mean temperature of the water.

Table XIII.—Mean monthly temperature of the water of the Thames.

| Month. | 1846. | | | 1847. | | | 1848. | | | 1849. | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | Mean of all the readings in each month. | | Mean temperature of the water. | Mean of all the readings in each month. | | Mean temperature of the water. | Mean of all the readings in each month. | | Mean temperature of the water. | Mean of all the readings in each month. | | Mean temperature of the water. |
| | Max. | Min. | | Max. | Min. | | Max. | Min. | | Max. | Min. | |
| January.... | 44°·3 | 42°·0 | 43°·2 | 37°·1 | 35°·5 | 36°·3 | 35°·7 | 35°·1 | 35°·4 | 41°·6 | 39°·6 | 40°·6 |
| February... | 45·3 | 42·5 | 43·9 | 38·9 | 37·2 | 38·1 | 41·8 | 40·3 | 41·1 | 44·2 | 42·6 | 43·4 |
| March..... | 48·2 | 46·3 | 47·3 | 42·1 | 41·4 | 41·8 | ..... | ..... | ..... | 45·7 | 44·1 | 44·9 |
| April ..... | 51·5 | 49·4 | 50·5 | 46·9 | 46·4 | 46·7 | 51·1 | 50·2 | 50·6 | 47·9 | 44·8 | 46·3 |
| May ..... | 59·9 | 57·2 | 58·6 | 58·6 | 57·0 | 57·8 | 62·5 | 61·0 | 61·8 | 58·9 | 55·7 | 57·3 |
| June ..... | 73·0 | 70·8 | 71·9 | 65·5 | 61·9 | 63·7 | 63·6 | 62·6 | 63·1 | 65·2 | 63·3 | 64·3 |
| July ..... | 67·4 | 66·1 | 66·7 | 70·6 | 66·5 | 68·6 | 66·0 | 65·0 | 65·5 | 67·8 | 66·1 | 67·0 |
| August ... | 68·3 | 66·7 | 67·5 | 66·1 | 64·4 | 65·3 | 63·0 | 62·0 | 62·5 | 64·9 | 62·7 | 63·8 |
| September. | 64·7 | 63·5 | 64·1 | 57·0 | 56·5 | 56·8 | 59·5 | 58·8 | 59·1 | 61·4 | 58·7 | 60·0 |
| October ... | 54·2 | 52·8 | 53·5 | 53·3 | 53·0 | 53·2 | 53·7 | 50·8 | 52·2 | 52·8 | 49·5 | 51·2 |
| November. | 47·6 | 46·0 | 46·8 | 47·9 | 47·3 | 47·6 | ..... | ..... | ..... | 47·1 | 44·1 | 45·6 |
| December. | 37·6 | 34·9 | 36·3 | 42·5 | 41·5 | 42·0 | 43·9 | 40·5 | 42·2 | 40·3 | 36·8 | 38·6 |

By comparing the means of these numbers for the four years, with the means of the readings of the maximum and minimum thermometers in air at the Royal Observatory, for the same months, we find that the mean lowest readings of the water were higher in the twelve months respectively by 3°·9; 4°·6; 7°·7; 12°·3; 11°·5; 16°·7; 12°·4; 10°·4; 10°·7; 6°·8; 6°·3 and 4°·9, than the mean of the lowest readings of the air; and it was lower than the mean maximum readings of the air by 3°·2; 4°·6; 5°·3; 9°·2; 6°·0; 7°·5; 8°·1; 6°·7; 7°·4; 6°·0; 4°·7 and 3°·0, in the respective months from January. These numbers are very large, and will fully account for the little higher temperature possessed by places in the vicinity of the river, and these differences of temperature are probably the fruitful source of the London fogs.

Mr. Sanders, at my request, has taken daily observations of the temperature of the air at 32 feet above the water of the Thames at the hours of 6 A.M. and 6 P.M. during the years 1847 and 1848, and at the hours of 9 A.M. and 9 P.M. in the year 1849. The result of these observations, compared with simultaneous observations taken at the Royal Observatory, is as follows:—that the temperature of the air 32 feet above

the water, exceeds that at the observatory at 6 A.M. by 1°·6; 1°·0; 0°·8; 0°·3; 0°·6; 0°·7; 0°·9; 0·°8; 0°·2; 0°·0 and 0°·8, in the twelve months respectively; and at 6 P.M. by 1°·2; 0°·8; 1°·0; 0°·8; 0°·7; 0°·8; 0°·6; 0°·8; 1°·3; 1°·0; 1°·7 and 0°·9, in the twelve months respectively; that at 9 A.M. it was in excess in January by 1°·3; February by 1°·5; March by 0°·6; April by 0°·4; May by 2°·2; June by 0°·4; and in October by 0°·5; that it was of a lower temperature in July by 0°·7; August by 0°·5; and in September by 0°·1; that at 9 P.M. it was always of a higher temperature: the excesses were 0°·1; 0°·3; 0°·7; 0°·3; 1°·9; 2°·9; 1°·5; 3°·2; 1°·2 and 1°·3 respectively.

From these numbers, it seems that during the night hours, at all seasons of the year, the temperature of the air at the Dreadnought Hospital Ship is higher than at the Observatory, and that it is below only during the midday hours.

At times of extreme temperature the effect of the water upon the temperature of the air is very great. On February 12, 1847, the temperature of the air at my house, which is situated about one mile and a half from the river, was 6°·0; the lowest reading, 32 feet above the water of the Thames, was 16°·0; the temperature of the water was 33°; its heating effect upon the air in its immediate vicinity amounted to 10°; at the Observatory the reading was 10°·5; and the heat of the water of the Thames seems to have influenced the temperature of the air at the Observatory to the amount of 4°. Some time since, on comparing the temperatures of the air as recorded in the Philosophical Transactions in the year 1814, with corresponding temperatures as observed at Greenwich, I doubted the accuracy of the former in many instances, on account of their much higher values; these investigations have now led me to believe that the temperatures, as recorded in the Philosophical Transactions for that year, are correct.

TABLE XIV.—Comparison of the mean temperature of the Air at St. John's Wood, and at the Royal Observatory, Greenwich.

| Month. | 1841. | | | 1842. | | | 1843. | | |
|---|---|---|---|---|---|---|---|---|---|
| | Mean temperature of the air. | | | Mean temperature of the air. | | | Mean temperature of the air. | | |
| | At Royal Observatory, Greenwich. | At St. John's Wood. | In excess at St. John's Wood. | At Royal Observatory, Greenwich. | At St. John's Wood. | In excess at St. John's Wood. | At Royal Observatory, Greenwich. | At St. John's Wood. | In excess at St. John's Wood. |
| January ..... | 33°·6 | 34°·3 | +0°·7 | 32°·9 | 32°·4 | −0°·5 | 39°·9 | 39°·1 | −0°·8 |
| February ... | 35·3 | 36·5 | +1·2 | 40·8 | 40·3 | −0·5 | 36·0 | 36·1 | +0·1 |
| March ..... | 46·2 | 46·6 | +0·4 | 44·9 | 44·3 | −0·6 | 42·9 | 42·9 | 0·0 |
| April ..... | 47·0 | 46·6 | −0·4 | 45·2 | 46·3 | +1·1 | 47·1 | 47·6 | +0·5 |
| May ..... | 56·8 | 57·0 | +0·2 | 53·2 | 53·2 | 0·0 | 52·2 | 51·2 | −1·0 |
| June ..... | 56·1 | 55·9 | −0·5 | 62·9 | 62·5 | −0·4 | 56·3 | 55·2 | −1·1 |
| July ..... | 57·8 | 56·9 | −0·9 | 60·2 | 59·5 | −0·7 | 60·9 | 60·1 | −0·8 |
| August ..... | 60·5 | 59·5 | −1·0 | 65·4 | 65·5 | +0·1 | 62·1 | 61·9 | −0·2 |
| September ... | 58·5 | 57·8 | −0·7 | 56·4 | 56·2 | −0·2 | 59·5 | 60·3 | +0·8 |
| October ..... | 48·8 | 49·1 | +0·3 | 45·4 | 45·8 | +0·4 | 48·0 | 47·6 | −0·4 |
| November ... | 42·7 | 42·5 | −0·2 | 42·8 | 43·3 | +0·5 | 43·8 | 43·9 | +0·1 |
| December ... | 40·5 | 40·2 | −0·3 | 45·0 | 44·6 | −0·4 | 43·9 | 44·2 | +0·3 |

TABLE XIV. (Continued.)

| Month. | 1844. | | | 1845. | | | 1846. | | |
|---|---|---|---|---|---|---|---|---|---|
| | Mean temperature of the air. | | | Mean temperature of the air. | | | Mean temperature of the air. | | |
| | At Royal Observatory Greenwich. | At St. John's Wood. | In excess at St. John's Wood. | At Royal Observatory, Greenwich. | At St. John's Wood. | In excess at St. John's Wood. | At Royal Observatory, Greenwich. | At St. John's Wood. | In excess at St. John's Wood. |
| | ° | ° | ° | ° | ° | ° | ° | ° | ° |
| January ..... | 39·1 | 36·9 | −2·2 | 38·3 | 38·7 | +0·4 | 43·7 | 43·1 | −0·6 |
| February ... | 35·2 | 35·7 | +0·5 | 32·7 | 32·9 | +0·2 | 43·9 | 43·7 | −0·2 |
| March..... | 41·5 | 41·6 | +0·1 | 35·2 | 35·3 | +0·1 | 43·3 | 44·0 | +0·7 |
| April ..... | 51·7 | 52·2 | +0·5 | 46·3 | 47·5 | +1·2 | 47·1 | 46·8 | −0·3 |
| May ..... | 52·9 | 52·5 | −0·4 | 49·4 | 49·2 | −0·2 | 54·6 | 55·6 | +1·0 |
| June ..... | 60·7 | 59·9 | −0·8 | 60·7 | 60·6 | −0·1 | 65·3 | 65·2 | −0·1 |
| July ..... | 61·4 | 61·0 | −0·4 | 59·8 | 59·4 | −0·4 | 64·5 | 63·6 | −0·9 |
| August ..... | 57·7 | 57·4 | −0·3 | 57·3 | 57·6 | +0·3 | 63·2 | 62·5 | −0·7 |
| September ... | 56·9 | 57·4 | +0·5 | 53·6 | 53·8 | +0·2 | 60·1 | 60·1 | 0·0 |
| October ..... | 49·5 | 49·2 | −0·3 | 50·2 | 50·1 | −0·1 | 50·5 | 49·9 | −0·6 |
| November ... | 44·0 | 43·3 | −0·7 | 45·8 | 45·3 | −0·5 | 46·0 | 44·9 | −1·1 |
| December ... | 33·0 | 33·8 | +0·8 | 41·7 | 40·5 | −1·2 | 32·9 | 32·7 | −0·2 |

The observations at St. John's Wood consisted of one observation of the maximum thermometer and of one observation of the minimum thermometer, daily, as well as three observations at different times every day of other thermometers. They were made by GEORGE LEACH, Esq., to whom I am indebted for these results. The mean values for the month were obtained by the application of corrections from my tables. By examining the column of differences, no certain difference exists between the temperatures of the air at Greenwich and at St. John's Wood.

TABLE XV.—Mean monthly temperature of the Air at Fleet Street, London, as determined from observations taken by Mr. W. SIMMS, optician.

| Year. | January. | Feb. | March. | April. | May. | June. | July. | August. | Sept. | Oct. | Nov. | Dec. |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | ° | ° | ° | ° | ° | ° | ° | ° | ° | ° | ° | ° |
| 1838. | ..... | ..... | ..... | ..... | ..... | ..... | ..... | ..... | ..... | 52·6 | 42·3 | 39·9 |
| 1839. | 38·5 | 40·4 | 40·4 | 41·2 | 50·8 | 61·2 | 61·5 | 62·0 | 57·1 | 51·1 | 43·6 | 41·3 |
| 1840. | 41·4 | 38·9 | 39·8 | 52·3 | 55·5 | 58·9 | 59·4 | 65·1 | 54·8 | 48·9 | 45·8 | 36·6 |
| 1841. | 35·0 | 36·2 | | | | | | | | | | |
| 1842. | ..... | ..... | ..... | ..... | ..... | ..... | ..... | ..... | ..... | ..... | ..... | 47·6 |
| 1843. | 42·6 | 37·8 | 43·6 | 46·2 | 49·4 | 53·4 | 58·4 | 62·1 | ..... | 47·3 | 45·9 | 47·1 |
| 1844. | 43·6 | 35·8 | 43·5 | 49·3 | 50·0 | 58·2 | 60·8 | 56·8 | 57·5 | 50·4 | 44·8 | 36·7 |
| 1845. | 41·8 | 35·2 | 37·0 | 46·0 | 46·9 | 55·6 | 58·6 | 56·2 | 54·3 | 51·2 | 47·8 | 44·3 |
| 1846. | 46·1 | 45·4 | 47·8 | 45·9 | 53·9 | 62·3 | | | | | | |
| 1848. | 35·9 | 44·3 | 43·0 | 47·9 | 57·9 | 55·9 | 63·4 | 57·4 | 58·0 | 52·1 | 44·1 | 45·0 |

These observations were taken with good instruments, and believed to be taken with every care: Mr. SIMMS very kindly lent me the original observations, from which I have deduced the above values. By comparison with the simultaneous observations taken at Greenwich, it seems that the temperature at Fleet Street upon the whole year is 0°·7 higher than at Greenwich.

**Table XVI.**—Comparison of the temperature of the Air at Somerset House, and at the Royal Observatory, Greenwich, and deduction of the numbers in every month, necessary to be applied to reduce the mean values at one place to those at the other.

| Year. | January. | | | February. | | | March. | | |
|---|---|---|---|---|---|---|---|---|---|
| | Mean reading of the thermometer in air | | | Mean reading of the thermometer in air | | | Mean reading of the thermometer in air | | |
| | At the Royal Observatory. | At Somerset House. | Higher at Somerset House. | At the Royal Observatory. | At Somerset House. | Higher at Somerset House. | At the Royal Observatory. | At Somerset House. | Higher at Somerset House. |
| | ° | ° | ° | ° | ° | ° | ° | ° | ° |
| 1834. | 44·1 | 46·0 | 1·9 | 40·5 | 41·6 | 1·1 | 43·8 | 45·1 | 1·3 |
| 1835. | 37·7 | 39·6 | 1·9 | 41·0 | 42·6 | 1·6 | 41·2 | 42·1 | 0·9 |
| 1836. | 38·5 | 38·8 | 0·3 | 37·1 | 38·3 | 1·2 | 43·7 | 44·8 | 1·1 |
| 1837. | 38·3 | 38·8 | 0·5 | 41·2 | 41·7 | 0·5 | 36·0 | 36·9 | 0·9 |
| 1838. | 28·3 | 30·5 | 2·2 | 32·1 | 34·3 | 2·2 | 41·6 | 42·6 | 1·0 |
| 1839. | 36·6 | 38·8 | 2·2 | 39·6 | 40·5 | 0·9 | 38·4 | 40·1 | 1·7 |
| 1840. | 39·6 | 40·6 | 1·0 | 37·0 | 39·5 | 2·5 | 37·2 | 38·7 | 1·5 |
| 1841. | 33·6 | 36·1 | 2·5 | 35·3 | 36·6 | 1·3 | 46·2 | 47·9 | 1·7 |
| 1842. | 32·9 | 34·8 | 1·9 | 40·8 | 42·2 | 1·4 | 44·9 | 45·4 | 0·5 |
| 1843. | 39·9 | 41·3 | 1·4 | 36·0 | 37·5 | 1·5 | 42·9 | 43·6 | 0·7 |
| | April. | | | May. | | | June. | | |
| 1834. | 44·7 | 46·1 | 1·4 | 56·2 | 58·0 | 1·8 | 59·6 | 62·0 | 2·4 |
| 1835. | 46·1 | 47·5 | 1·4 | 52·3 | 54·0 | 1·7 | 58·7 | 60·9 | 2·2 |
| 1836. | 42·7 | 44·4 | 1·7 | 52·2 | 53·9 | 1·7 | 60·0 | 59·9 | −0·1 |
| 1837. | 39·6 | 40·2 | 0·6 | 48·6 | 48·9 | 0·3 | 60·9 | 59·0 | −1·9 |
| 1838. | 41·4 | 42·7 | 1·3 | 51·7 | 51·8 | 0·1 | 56·6 | 58·1 | 1·5 |
| 1839. | 40·4 | 42·0 | 1·6 | 50·0 | 51·0 | 1·0 | 59·5 | 59·6 | 0·1 |
| 1840. | 48·6 | 48·9 | 0·3 | 53·2 | 54·6 | 1·4 | 57·9 | 60·4 | 2·5 |
| 1841. | 47·0 | 47·4 | 0·4 | 56·8 | 57·9 | 1·1 | 56·4 | 57·2 | 0·8 |
| 1842. | 45·2 | 45·7 | 0·5 | 53·2 | 54·3 | 1·1 | 62·9 | 64·2 | 1·3 |
| 1843. | 47·1 | 48·6 | 1·5 | 52·2 | 52·8 | 0·6 | 56·3 | 56·4 | 0·1 |
| | July. | | | August. | | | September. | | |
| 1833. | 59·7 | 62·1 | 2·4 | 56·9 | 58·8 | 1·9 | 53·0 | 54·6 | 1·6 |
| 1834. | 64·0 | 65·1 | 1·1 | 61·5 | 63·6 | 2·1 | 57·0 | 59·4 | 2·4 |
| 1835. | 63·9 | 65·4 | 1·5 | 63·0 | 64·6 | 1·6 | 57·6 | 58·2 | 0·6 |
| 1836. | 62·8 | 63·9 | 1·1 | 59·8 | 60·2 | 0·4 | 53·7 | 54·5 | 0·8 |
| 1837. | ..... | ..... | ..... | 59·6 | 61·4 | 1·8 | 56·1 | 56·1 | 0·0 |
| 1838. | 61·0 | 61·5 | 0·5 | 60·0 | 60·9 | 0·9 | 55·7 | 55·5 | −0·2 |
| 1839. | 60·8 | 61·2 | 0·4 | 58·6 | 60·2 | 1·6 | 55·5 | 56·7 | 1·2 |
| 1840. | 59·3 | 59·0 | −0·3 | 63·0 | 63·4 | 0·4 | 52·5 | 55·2 | 2·7 |
| 1841. | 57·8 | 59·0 | 1·2 | 60·5 | 61·3 | 0·8 | 58·0 | 58·5 | 0·5 |
| 1842. | 60·2 | 61·5 | 1·3 | 65·4 | 66·6 | 1·2 | 56·4 | 57·5 | 1·1 |
| | October. | | | November. | | | December. | | |
| 1833. | 50·5 | 49·6 | −0·9 | 42·8 | 44·8 | 2·0 | 44·7 | 46·0 | 1·3 |
| 1834. | 51·1 | 51·8 | 0·7 | 43·9 | 45·4 | 1·5 | 40·6 | 42·4 | 1·8 |
| 1835. | 48·0 | 49·3 | 1·3 | 44·0 | 44·3 | 0·3 | 35·7 | 36·3 | 0·6 |
| 1836. | 47·9 | 48·7 | 0·8 | 41·9 | 42·8 | 0·9 | 39·6 | 41·0 | 1·4 |
| 1837. | 50·1 | 51·9 | 1·8 | 40·6 | 42·4 | 1·8 | 40·5 | 42·6 | 2·1 |
| 1838. | 49·7 | 51·3 | 1·6 | 40·9 | 42·1 | 1·2 | 38·4 | 40·0 | 1·6 |
| 1839. | 48·8 | 50·2 | 1·4 | 44·8 | 46·0 | 1·2 | 39·6 | 41·0 | 1·4 |
| 1840. | 45·7 | 48·1 | 2·4 | 44·0 | 44·7 | 0·7 | 32·3 | 34·7 | 2·4 |
| 1841. | 48·8 | 50·7 | 1·9 | 42·7 | 44·5 | 1·8 | 40·5 | 42·0 | 1·5 |
| 1842. | 45·4 | 47·2 | 1·8 | 42·8 | 44·2 | 1·4 | 45·0 | 45·3 | 0·3 |

By taking the means of the numbers in each column of differences, we find that the temperature of the air at the Apartments of the Royal Society was

| | |
|---|---|
| Higher than at the Royal Observatory, Greenwich, in January by . . | 1°·6 |
| Higher than at the Royal Observatory, Greenwich, in February by . | 1·4 |
| Higher than at the Royal Observatory, Greenwich, in March by . . | 1·1 |
| Higher than at the Royal Observatory, Greenwich, in April by . . . | 1·1 |
| Higher than at the Royal Observatory, Greenwich, in May by . . . | 1·1 |
| Higher than at the Royal Observatory, Greenwich, in June by . . . | 0·9 |
| Higher than at the Royal Observatory, Greenwich, in July by . . . | 1·0 |
| Higher than at the Royal Observatory, Greenwich, in August by . . | 1·3 |
| Higher than at the Royal Observatory, Greenwich, in September by . | 1·1 |
| Higher than at the Royal Observatory, Greenwich, in October by . . | 1·3 |
| Higher than at the Royal Observatory, Greenwich, in November by . | 1·3 |
| Higher than at the Royal Observatory, Greenwich, in December by . | 1·4 |

And upon the whole year the excess of temperature at Somerset House was 1°·2; and to reduce readings taken at Somerset House to those at Greenwich, it is necessary to subtract the preceding numbers from them; and it is necessary to increase the readings of the Royal Observatory by the above numbers to make them comparable with those taken at the Royal Society.

One part of these differences is owing to the difference of elevation, and which will amount to about 0°·3; the greater part of the remaining difference is most probably owing to the vicinity of the water of the Thames, whose temperature during the night hours, at all seasons of the year, is several degrees higher than that of the air (see remarks following Table XIII.).

The general result of the preceding investigations, with respect to the temperatures of London and the country is, that those parts of London situated near the river Thames, are somewhat warmer upon the whole year than the country, but that those parts of London which are situated at some distance from the river, do not enjoy higher temperatures than those due to their latitudes.

I proceed now to reduce the results at Somerset House to those of the Royal Observatory, Greenwich, by applying the numbers following the preceding Table to the numbers in Table I. of my former paper, and to those in Table X. till the year 1840. After this date the numbers are extracted from the several volumes of the Greenwich Meteorological Observations.

TABLE XVII.—Showing the mean temperature of each month at the Royal Observatory, Greenwich, as found from the numbers in Table I. of my former paper till the year 1840, and from the observations at Greenwich from the year 1841.

| Year. | January. | February. | March. | April. | May. | June. | July. | August. | September. | October. | November. | December. |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | ° | ° | ° | ° | ° | ° | ° | ° | ° | ° | ° | ° |
| 1771. | 29·9 | 33·4 | 34·7 | 38·7 | 54·5 | 54·0 | 59·5 | 58·4 | 52·0 | 47·2 | 40·9 | 41·4 |
| 1772. | 32·2 | 34·2 | 38·5 | 42·2 | 48·6 | 59·4 | 60·0 | 59·7 | 55·0 | 52·4 | 43·4 | 39·5 |
| 1773. | 36·9 | 34·9 | 40·9 | 44·2 | 47·5 | 55·6 | 58·5 | 60·9 | 53·8 | 48·2 | 39·2 | 38·2 |
| 1774. | 31·5 | 38·0 | 42·8 | 46·8 | 51·1 | 60·1 | 61·8 | 62·4 | 54·7 | 48·8 | 39·2 | 37·1 |
| 1775. | 40·4 | 41·9 | 41·7 | 49·7 | 54·1 | 62·6 | 63·0 | 60·8 | 58·4 | 48·2 | 40·2 | 39·3 |
| 1776. | 37·0 | 40·0 | 43·7 | 47·2 | 50·6 | 58·7 | 62·8 | 60·7 | 54·5 | 51·5 | 42·7 | 40·1 |
| 1777. | 35·9 | 35·8 | 44·6 | 44·0 | 52·3 | 56·3 | 60·5 | 62·4 | 58·1 | 51·3 | 43·7 | 35·8 |
| 1778. | 34·8 | 35·6 | 40·1 | 46·9 | 54·8 | 61·3 | 67·0 | 63·5 | 53·4 | 46·0 | 44·7 | 42·8 |
| 1779. | 34·8 | 45·3 | 47·0 | 50·7 | 54·7 | 58·0 | 64·9 | 63·9 | 60·7 | 51·9 | 41·9 | 40·2 |
| 1780. | 28·6 | 35·3 | 49·2 | 43·6 | 56·1 | 59·1 | 63·2 | 65·7 | 59·3 | 50·0 | 39·5 | 36·6 |
| 1781. | 36·2 | 40·3 | 42·6 | 46·1 | 53·1 | 62·5 | 65·3 | 63·0 | 56·8 | 48·5 | 41·7 | 41·0 |
| 1782. | 38·9 | 34·4 | 38·7 | 40·7 | 48·1 | 57·9 | 59·2 | 56·7 | 55·5 | 45·2 | 34·7 | 36·2 |
| 1783. | 36·9 | 39·2 | 37·7 | 47·9 | 48·3 | 58·4 | 65·7 | 60·7 | 54·6 | 49·0 | 42·5 | 35·0 |
| 1784. | 29·2 | 31·9 | 36·2 | 42·0 | 56·8 | 56·2 | 59·5 | 56·2 | 57·3 | 43·9 | 40·7 | 31·0 |
| 1785. | 36·1 | 30·4 | 33·9 | 46·2 | 52·5 | 59·4 | 62·2 | 57·5 | 56·8 | 46·9 | 40·2 | 35·2 |
| 1786. | 35·9 | 36·2 | 34·2 | 44·7 | 52·3 | 59·6 | 59·0 | 58·9 | 51·3 | 44·7 | 36·7 | 35·9 |
| 1787. | 36·7 | 39·5 | 42·8 | 44·4 | 51·3 | 57·8 | 61·4 | 61·1 | 54·4 | 48·6 | 39·6 | 39·6 |
| 1788. | 37·4 | 38·7 | 38·6 | 49·5 | 56·3 | 58·6 | 60·6 | 59·9 | 55·9 | 49·1 | 40·6 | 29·0 |
| 1789. | 33·4 | 39·9 | 34·4 | 44·1 | 53·2 | 54·8 | 58·8 | 60·2 | 54·6 | 46·8 | 38·7 | 41·6 |
| 1790. | 38·6 | 41·2 | 43·2 | 40·9 | 52·6 | 56·8 | 59·1 | 59·9 | 53·9 | 49·5 | 42·0 | 39·0 |
| 1791. | 39·8 | 38·8 | 42·1 | 48·8 | 49·4 | 57·6 | 59·5 | 61·4 | 56·8 | 46·6 | 41·3 | 34·8 |
| 1792. | 34·9 | 37·4 | 42·1 | 48·9 | 49·6 | 54·4 | 58·6 | 62·2 | 55·4 | 48·7 | 43·2 | 40·0 |
| 1793. | 35·3 | 39·7 | 39·3 | 42·4 | 50·7 | 55·4 | 64·9 | 59·0 | 52·8 | 51·9 | 42·9 | 41·0 |
| 1794. | 33·3 | 44·7 | 44·3 | 49·6 | 50·6 | 57·6 | 63·3 | 59·4 | 53·7 | 48·3 | 43·3 | 36·8 |
| 1795. | 32·9 | 34·1 | 38·6 | 45·1 | 51·9 | 53·7 | 58·9 | 60·8 | 60·8 | 53·4 | 40·7 | 44·8 |
| 1796. | 45·3 | 39·6 | 39·0 | 48·3 | 50·1 | 56·1 | 58·6 | 59·9 | 59·1 | 46·5 | 40·3 | 30·4 |
| 1797. | 35·4 | 35·6 | 37·9 | 44·7 | 51·3 | 54·8 | 63·3 | 59·0 | 54·6 | 47·0 | 41·4 | 41·2 |
| 1798. | 37·8 | 37·9 | 40·7 | 49·2 | 53·6 | 61·2 | 61·2 | 61·5 | 56·5 | 49·8 | 40·0 | 33·7 |
| 1799. | 33·3 | 36·4 | 37·2 | 41·5 | 49·5 | 55·6 | 59·8 | 57·5 | 54·3 | 47·3 | 42·9 | 32·8 |
| 1800. | 36·9 | 34·1 | 37·5 | 48·4 | 54·0 | 55·1 | 63·2 | 63·7 | 57·9 | 47·9 | 42·2 | 38·2 |
| 1801. | 39·5 | 38·5 | 44·1 | 45·4 | 53·6 | 58·4 | 60·5 | 62·5 | 58·7 | 50·9 | 40·2 | 36·1 |
| 1802. | 32·9 | 38·9 | 41·2 | 48·5 | 50·2 | 57·6 | 56·5 | 64·8 | 57·0 | 49·5 | 40·5 | 37·8 |
| 1803. | 33·4 | 36·3 | 42·3 | 47·8 | 50·1 | 56·2 | 63·7 | 61·7 | 52·4 | 48·9 | 41·9 | 43·3 |
| 1804. | 43·2 | 36·9 | 41·1 | 43·7 | 56·6 | 61·3 | 60·2 | 59·9 | 59·4 | 51·4 | 44·1 | 35·6 |
| 1805. | 34·5 | 38·7 | 42·0 | 45·3 | 49·6 | 54·5 | 59·1 | 61·7 | 59·3 | 47·4 | 39·9 | 39·5 |
| 1806. | 40·6 | 41·5 | 40·7 | 43·0 | 55·0 | 59·8 | 61·2 | 61·4 | 57·0 | 51·2 | 47·4 | 46·8 |
| 1807. | 36·7 | 40·0 | 37·0 | 45·4 | 55·0 | 57·7 | 63·5 | 63·7 | 53·1 | 53·0 | 38·7 | 36·6 |
| 1808. | 37·0 | 36·3 | 37·1 | 42·5 | 57·1 | 58·0 | 65·7 | 62·5 | 55·3 | 46·1 | 43·9 | 36·0 |
| 1809. | 35·4 | 44·1 | 42·6 | 41·1 | 55·7 | 57·5 | 59·6 | 58·9 | 56·1 | 49·6 | 39·5 | 41·0 |
| 1810. | 34·4 | 38·6 | 42·2 | 46·4 | 49·7 | 58·5 | 60·9 | 60·5 | 59·4 | 51·8 | 43·8 | 38·6 |
| 1811. | 32·8 | 40·1 | 43·4 | 48·7 | 56·2 | 57·6 | 61·0 | 58·5 | 57·9 | 55·5 | 45·2 | 38·6 |
| 1812. | 35·9 | 41·6 | 38·4 | 41·5 | 51·2 | 54·0 | 57·4 | 57·0 | 55·9 | 48·8 | 40·6 | 35·1 |
| 1813. | 34·4 | 41·6 | 43·1 | 43·8 | 52·3 | 55·3 | 58·9 | 58·3 | 54·5 | 47·3 | 40·2 | 36·6 |
| 1814. | 26·9 | 34·0 | 35·1 | 48·1 | 48·6 | 53·4 | 61·1 | 58·6 | 54·9 | 47·3 | 40·7 | 41·1 |
| 1815. | 31·9 | 41·2 | 45·0 | 46·6 | 54·7 | 58·0 | 59·9 | 60·4 | 62·3 | 51·4 | 38·9 | 37·0 |
| 1816. | 36·7 | 36·6 | 39·2 | 43·4 | 48·8 | 53·1 | 54·5 | 57·9 | 58·9 | 50·8 | 39·3 | 37·8 |
| 1817. | 39·2 | 42·6 | 41·6 | 43·9 | 47·9 | 59·1 | 57·7 | 55·4 | 55·5 | 45·0 | 46·9 | 37·1 |
| 1818. | 39·3 | 35·8 | 40·9 | 45·6 | 52·5 | 62·9 | 66·2 | 63·6 | 60·7 | 53·7 | 49·2 | 38·8 |
| 1819. | 40·1 | 40·0 | 44·0 | 48·2 | 54·2 | 56·4 | 61·7 | 63·8 | 58·1 | 47·5 | 49·8 | 37·0 |
| 1820. | 31·7 | 36·9 | 41·3 | 49·3 | 52·0 | 56·1 | 59·5 | 58·5 | 54·4 | 47·0 | 41·4 | 39·9 |
| 1821. | 37·5 | 36·0 | 42·8 | 50·4 | 49·4 | 54·1 | 57·7 | 61·7 | 59·6 | 50·3 | 47·6 | 44·3 |
| 1822. | 39·8 | 43·3 | 47·3 | 46·7 | 55·8 | 62·6 | 62·5 | 61·3 | 56·0 | 52·0 | 48·2 | 36·4 |
| 1823. | 31·8 | 38·1 | 39·8 | 42·8 | 54·6 | 55·4 | 59·1 | 59·8 | 55·4 | 47·6 | 43·0 | 39·9 |
| 1824. | 37·4 | 36·2 | 39·5 | 43·8 | 49·5 | 55·0 | 62·5 | 60·0 | 57·7 | 49·8 | 46·2 | 41·8 |
| 1825. | 38·4 | 38·1 | 38·5 | 48·7 | 53·6 | 58·9 | 65·2 | 61·8 | 59·9 | 50·8 | 41·2 | 40·6 |
| 1826. | 32·0 | 42·2 | 43·2 | 49·0 | 50·0 | 62·9 | 65·6 | 63·4 | 56·3 | 52·4 | 39·9 | 41·8 |
| 1827. | 33·4 | 31·6 | 43·1 | 46·8 | 52·7 | 57·6 | 63·5 | 59·0 | 56·9 | 51·8 | 41·5 | 44·1 |
| 1828. | 29·8 | 40·2 | 43·5 | 46·5 | 54·3 | 60·0 | 61·9 | 59·0 | 57·5 | 49·9 | 44·3 | 44·5 |
| 1829. | 31·7 | 38·4 | 39·0 | 43·7 | 54·5 | 59·0 | 60·1 | 57·7 | 53·2 | 47·5 | 39·3 | 34·9 |
| 1830. | 30·7 | 34·2 | 45·8 | 48·3 | 54·7 | 55·3 | 63·0 | 58·2 | 53·5 | 50·9 | 44·4 | 34·9 |
| 1831. | 34·4 | 41·2 | 43·9 | 48·1 | 59·8 | 59·4 | 64·3 | 63·3 | 56·4 | 55·0 | 44·3 | 42·0 |
| 1832. | 37·3 | 36·9 | 40·5 | 47·2 | 51·5 | 59·2 | 61·2 | 61·0 | 56·6 | 51·2 | 43·7 | 42·4 |
| 1833. | 34·5 | 42·4 | 37·6 | 45·2 | 59·4 | 59·8 | 61·1 | 57·5 | 53·5 | 48·3 | 43·5 | 44·6 |
| 1834. | 44·4 | 40·2 | 44·0 | 45·0 | 56·9 | 61·1 | 64·1 | 62·3 | 58·3 | 50·5 | 44·1 | 41·0 |
| 1835. | 38·0 | 41·2 | 41·0 | 46·4 | 52·9 | 60·0 | 64·4 | 63·3 | 57·1 | 48·0 | 43·0 | 34·9 |
| 1836. | 37·2 | 36·9 | 43·7 | 43·3 | 52·8 | 59·0 | 62·9 | 58·9 | 53·4 | 47·4 | 41·5 | 39·6 |
| 1837. | 37·2 | 40·3 | 35·8 | 39·1 | 47·8 | 58·1 | 61·3 | 60·1 | 55·0 | 50·6 | 41·1 | 41·2 |
| 1838. | 28·9 | 32·9 | 41·5 | 41·6 | 50·7 | 57·2 | 60·5 | 59·6 | 54·4 | 50·0 | 40·8 | 38·6 |
| 1839. | 37·2 | 39·1 | 39·0 | 40·9 | 49·9 | 58·7 | 60·2 | 58·9 | 55·6 | 48·9 | 44·7 | 39·6 |
| 1840. | 39·0 | 38·1 | 37·6 | 47·8 | 53·5 | 59·5 | 58·0 | 62·1 | 54·1 | 46·8 | 43·4 | 33·3 |
| 1841. | 33·6 | 35·3 | 46·2 | 47·0 | 56·8 | 56·4 | 57·8 | 60·5 | 58·1 | 48·8 | 42·7 | 40·5 |
| 1842. | 32·9 | 40·8 | 44·9 | 45·2 | 53·2 | 62·9 | 60·2 | 65·4 | 56·4 | 45·4 | 42·8 | 45·0 |
| 1843. | 39·9 | 36·0 | 42·9 | 47·1 | 52·2 | 56·3 | 60·9 | 62·1 | 59·5 | 48·0 | 43·8 | 43·9 |
| 1844. | 39·1 | 35·2 | 41·5 | 51·7 | 52·9 | 60·7 | 61·4 | 57·7 | 56·9 | 49·5 | 44·0 | 33·0 |
| 1845. | 38·3 | 32·7 | 35·2 | 46·3 | 49·4 | 60·7 | 59·8 | 57·3 | 53·6 | 50·2 | 45·8 | 41·7 |
| 1846. | 43·7 | 43·9 | 43·3 | 47·1 | 54·6 | 65·3 | 64·5 | 63·2 | 60·1 | 50·5 | 46·0 | 32·9 |
| 1847. | 35·1 | 35·4 | 41·0 | 45·3 | 56·4 | 58·0 | 65·4 | 62·1 | 54·3 | 52·9 | 46·9 | 42·8 |
| 1848. | 34·6 | 43·4 | 43·8 | 47·6 | 59·7 | 58·5 | 61·5 | 58·5 | 55·8 | 51·6 | 43·8 | 44·0 |
| 1849. | 40·1 | 43·2 | 42·5 | 43·2 | 54·0 | 57·9 | 62·1 | 62·9 | 58·8 | 51·1 | 44·1 | 39·1 |

By taking the means of the numbers in each column, we find that

| | |
|---|---|
| The mean temperature of January from all the observations is. . . | 35°·7 |
| The mean temperature of February from all the observations is . . | 38·2 |
| The mean temperature of March from all the observations is . . . | 40·9 |
| The mean temperature of April from all the observations is. . . . | 45·7 |
| The mean temperature of May from all the observations is . . . . | 52·6 |
| The mean temperature of June from all the observations is . . . . | 58·0 |
| The mean temperature of July from all the observations is . . . . | 61·3 |
| The mean temperature of August from all the observations is . . . | 60·5 |
| The mean temperature of September from all the observations is . . | 56·3 |
| The mean temperature of October from all the observations is . . | 49·3 |
| The mean temperature of November from all the observations is . . | 42·4 |
| The mean temperature of December from all the observations is . . | 38·8 |

And the mean of all the monthly results is 48°·3.

TABLE XVIII.—Showing the Highest and Lowest monthly mean temperature in every year from 1771 to 1849, with the amount of difference of temperature.

| Year. | Monthly mean temperature. | | Difference between the hottest and coldest months. | Month of temperature. | |
|---|---|---|---|---|---|
| | Highest. | Lowest. | | Highest. | Lowest. |
| | ° | ° | ° | | |
| 1771. | 59·5 | 29·9 | 29·6 | July. | January. |
| 1772. | 60·0 | 32·2 | 27·8 | July. | January. |
| 1773. | 60·9 | 34·9 | 26·0 | August. | February. |
| 1774. | 62·4 | 31·5 | 30·3 | August. | January. |
| 1775. | 63·0 | 39·3 | 23·7 | July. | December. |
| 1776. | 62·8 | 27·0 | 35·8 | July. | January. |
| 1777. | 62·4 | 33·9 | 28·5 | August. | January. |
| 1778. | 67·0 | 34·8 | 32·2 | July. | January. |
| 1779. | 64·9 | 34·8 | 30·1 | July. | January. |
| 1780. | 65·7 | 28·6 | 37·1 | August. | January. |
| 1781. | 65·3 | 36·2 | 29·1 | July. | January. |
| 1782. | 59·2 | 34·4 | 24·8 | July. | February. |
| 1783. | 65·7 | 35·0 | 30·7 | July. | December. |
| 1784. | 59·5 | 29·2 | 30·3 | July. | January. |
| 1785. | 62·2 | 30·4 | 31·8 | July. | February. |
| 1786. | 59·6 | 35·9 | 23·7 | June. | Jan. and Dec. |
| 1787. | 61·4 | 36·7 | 24·7 | July. | January. |
| 1788. | 60·6 | 29·0 | 31·6 | July. | December. |
| 1789. | 60·2 | 33·4 | 26·8 | August. | January. |
| 1790. | 59·9 | 38·6 | 21·3 | August. | January. |
| 1791. | 61·4 | 34·8 | 26·6 | August. | December. |
| 1792. | 62·2 | 34·9 | 27·3 | August. | January. |
| 1793. | 64·9 | 35·3 | 29·6 | July. | January. |
| 1794. | 65·3 | 33·3 | 32·0 | July. | January. |
| 1795. | 60·8 | 23·9 | 36·9 | Aug. and Sept. | January. |
| 1796. | 59·9 | 30·4 | 29·5 | August. | December. |
| 1797. | 63·3 | 35·4 | 27·9 | July. | January. |
| 1798. | 61·5 | 33·7 | 27·8 | August. | December. |
| 1799. | 59·8 | 32·8 | 27·0 | July. | December. |
| 1800. | 63·7 | 34·1 | 29·6 | August. | February. |
| 1801. | 62·5 | 36·1 | 26·4 | August. | December. |
| 1802. | 64·8 | 32·9 | 31·9 | August. | January. |
| 1803. | 63·7 | 33·4 | 30·3 | July. | January. |
| 1804. | 60·2 | 35·6 | 24·6 | July. | December. |
| 1805. | 61·7 | 34·5 | 27·2 | August. | January. |
| 1806. | 61·4 | 40·6 | 20·8 | August. | January. |
| 1807. | 63·7 | 36·6 | 27·1 | August. | December. |
| 1808. | 65·7 | 36·0 | 29·7 | July. | December. |
| 1809. | 59·6 | 35·4 | 24·2 | July. | January. |
| 1810. | 60·9 | 34·4 | 26·5 | July. | January. |

| Year. | Monthly mean temperature. | | Difference between the hottest and coldest months. | Month of temperature. | |
|---|---|---|---|---|---|
| | Highest. | Lowest. | | Highest. | Lowest. |
| | ° | ° | ° | | |
| 1811. | 61·0 | 32·8 | 28·2 | July. | January. |
| 1812. | 57·4 | 35·1 | 22·3 | July. | December. |
| 1813. | 58·9 | 34·4 | 24·5 | July. | January. |
| 1814. | 61·1 | 26·9 | 34·2 | July. | January. |
| 1815. | 62·3 | 31·9 | 30·4 | September. | January. |
| 1816. | 58·9 | 36·6 | 22·3 | September. | February. |
| 1817. | 59·1 | 37·1 | 22·0 | June. | December. |
| 1818. | 66·2 | 35·8 | 30·4 | July. | February. |
| 1819. | 63·8 | 37·0 | 26·8 | August. | December. |
| 1820. | 59·5 | 31·7 | 27·8 | July. | January. |
| 1821. | 61·7 | 36·0 | 25·7 | August. | February. |
| 1822. | 62·6 | 36·4 | 26·2 | June. | December. |
| 1823. | 59·8 | 31·8 | 28·0 | August. | January. |
| 1824. | 62·5 | 36·2 | 26·3 | July. | February. |
| 1825. | 65·2 | 38·1 | 27·1 | July. | February. |
| 1826. | 65·6 | 32·0 | 33·6 | July. | January. |
| 1827. | 63·5 | 31·6 | 31·9 | July. | February. |
| 1828. | 61·9 | 39·8 | 22·1 | July. | January. |
| 1829. | 60·1 | 31·7 | 28·4 | July. | January. |
| 1830. | 63·0 | 30·7 | 32·3 | July. | January. |
| 1831. | 64·3 | 34·4 | 29·9 | July. | January. |
| 1832. | 61·2 | 36·9 | 24·3 | July. | February. |
| 1833. | 61·1 | 34·5 | 26·6 | July. | January. |
| 1834. | 64·1 | 40·2 | 23·9 | July. | February. |
| 1835. | 64·4 | 34·9 | 29·5 | July. | December. |
| 1836. | 62·9 | 36·9 | 26·0 | July. | February. |
| 1837. | 61·3 | 35·8 | 25·5 | July. | March. |
| 1838. | 60·5 | 28·9 | 31·6 | July. | January. |
| 1839. | 60·2 | 37·2 | 23·0 | July. | January. |
| 1840. | 62·1 | 33·3 | 28·8 | August. | December. |
| 1841. | 60·5 | 33·6 | 26·9 | August. | January. |
| 1842. | 65·4 | 32·9 | 32·5 | August. | January. |
| 1843. | 62·1 | 36·0 | 26·1 | August. | February. |
| 1844. | 61·4 | 33·0 | 28·4 | July. | December. |
| 1845. | 60·7 | 32·7 | 28·0 | June. | February. |
| 1846. | 65·3 | 32·9 | 32·4 | June. | December. |
| 1847. | 65·4 | 35·1 | 30·3 | July. | January. |
| 1848. | 61·5 | 34·6 | 26·9 | July. | January. |
| 1849. | 62·9 | 39·1 | 23·8 | August. | December. |

The mean of all the differences between the hottest and coldest months in every year is 28°·5.

In the year 1790 the difference was 21°·3 only, and in the year 1780 it was as large as 37°·1, these numbers being respectively the smallest and largest within the period of seventy-nine years.

The coldest month in the year has occurred in January forty-three times, in February fifteen, in December twenty-one, and in March once; this unusual circumstance took place in the year 1837.

The hottest month in the year has taken place five times in June, forty-seven times in July, twenty-five times in August, and three times in September.

The following are the values of the extreme mean temperatures in every month:—

| | | |
|---|---|---|
| In January | 1795 the mean temperature was 23°·9, and in January | 1796 it was 45°·3. |
| In February | 1785 the mean temperature was 30°·4, and in February | 1794 it was 44°·7. |
| In March | 1785 the mean temperature was 33°·9, and in March | 1780 it was 49°·2. |
| In April | 1771 the mean temperature was 38°·7, and in April | 1844 it was 51°·7. |
| In May | 1773 the mean temperature was 47°·5, and in May | 1848 it was 59°·7. |
| In June | 1816 the mean temperature was 53°·1, and in June | 1846 it was 65°·3. |
| In July | 1816 the mean temperature was 54°·5, and in July | 1778 it was 67°·0. |
| In August | 1817 the mean temperature was 55°·4, and in August | 1780 it was 65°·7. |
| In September | 1786 the mean temperature was 51°·3, and in September | 1815 it was 62°·3. |
| In October | 1784 the mean temperature was 43°·9, and in October | 1811 and 1831 it was 55°·0. |
| In November | 1782 the mean temperature was 34°·7, and in November | 1822 it was 48°·2. |
| In December | 1788 the mean temperature was 29°·0, and in December | 1806 it was 46°·8. |

It is clear from these numbers that observations for a few years only can never be of great importance, when we consider that the difference of the monthly means of the winter months may be as large as 20°, and of the summer months of 11° or 12°.

By taking the means of the numbers in the Table in different groups of years the next Table is formed.

TABLE XIX.—Showing the mean temperature of the Air at the Royal Observatory, Greenwich, in every month in successive groups of years.

| Period. | Jan. | Feb. | March. | April. | May. | June. | July. | August. | Sept. | Oct. | Nov. | Dec. |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| From 1771 to 1779. | 33°·5 | 37°·7 | 41°·6 | 45°·6 | 52°·0 | 58°·4 | 62°·0 | 61°·2 | 55°·6 | 49°·5 | 41°·8 | 39°·4 |
| From 1780 to 1789. | 34·9 | 36·6 | 38·8 | 44·9 | 52·8 | 58·4 | 61·5 | 60·0 | 55·7 | 47·3 | 40·5 | 36·1 |
| From 1790 to 1799. | 35·8 | 38·5 | 40·4 | 45·9 | 50·9 | 56·3 | 60·9 | 60·1 | 55·8 | 48·9 | 41·8 | 37·5 |
| From 1800 to 1809. | 37·0 | 38·5 | 40·6 | 45·1 | 53·7 | 57·6 | 61·3 | 62·1 | 56·6 | 49·6 | 41·8 | 39·1 |
| From 1810 to 1819. | 35·2 | 39·2 | 41·3 | 45·6 | 51·6 | 56·8 | 59·9 | 59·4 | 57·8 | 49·9 | 42·4 | 37·8 |
| From 1820 to 1829. | 35·4 | 38·1 | 41·8 | 46·8 | 52·6 | 58·2 | 61·8 | 60·2 | 56·7 | 49·9 | 43·3 | 40·8 |
| From 1830 to 1839. | 36·0 | 38·5 | 41·3 | 44·5 | 52·9 | 58·8 | 62·3 | 60·3 | 55·4 | 50·1 | 43·1 | 39·9 |
| From 1840 to 1849. | 37·6 | 38·4 | 41·9 | 46·9 | 54·3 | 59·6 | 61·2 | 61·2 | 56·8 | 49·5 | 44·0 | 39·7 |

The next Table is formed by taking the difference between the mean temperature of each month, as found from all the years, and the mean temperature of the same month in every year.

TABLE XX.—Showing the excess of the monthly mean temperature at Greenwich, in every year, above the mean temperature of the month from all the years.

| Year. | January. | February. | March. | April. | May. | June. | July. | August. | September. | October. | November. | December. |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 1771. | − 5·8 | −4·8 | −6·2 | −7·0 | +1·9 | −4·0 | −1·8 | −2·1 | −4·3 | −2·1 | −1·5 | +2·6 |
| 1772. | − 3·5 | −4·0 | −2·4 | −3·5 | −4·0 | +1·4 | −1·3 | −0·8 | −1·3 | +3·1 | +1·0 | +0·7 |
| 1773. | + 1·2 | −3·3 | 0·0 | −1·5 | −5·1 | −2·4 | −2·8 | +0·4 | −2·5 | −1·1 | −3·2 | −0·6 |
| 1774. | − 4·2 | −0·2 | +1·9 | +1·1 | −1·5 | +2·1 | +0·5 | +1·9 | −1·6 | −0·5 | −3·2 | −1·7 |
| 1775. | + 4·7 | +3·7 | +0·8 | +4·0 | +1·5 | +4·6 | +1·7 | +0·3 | +2·1 | −1·1 | −2·2 | +0·5 |
| 1776. | − 8·7 | +1·8 | +2·8 | +1·5 | −2·0 | +0·7 | +1·5 | +0·2 | −1·8 | +2·2 | +0·3 | +1·3 |
| 1777. | − 1·8 | −2·4 | +3·7 | −1·7 | −0·3 | −1·7 | −0·6 | +1·9 | +1·8 | +2·0 | +1·3 | −3·0 |
| 1778. | − 0·9 | −2·6 | −0·8 | +1·2 | +2·2 | +3·3 | +5·7 | +3·0 | −2·9 | −3·3 | +2·3 | +4·0 |
| 1779. | − 0·9 | +7·1 | +6·1 | +5·0 | +2·1 | 0·0 | +3·6 | +3·4 | +4·4 | +2·6 | −0·5 | +1·4 |
| 1780. | − 7·1 | −2·9 | +8·3 | −2·1 | +3·5 | +1·1 | +1·9 | +5·2 | +3·0 | +0·7 | −2·9 | −2·2 |
| 1781. | + 0·5 | +2·1 | +1·7 | +0·4 | +0·5 | +4·5 | +4·0 | +2·5 | +0·5 | −0·8 | −0·7 | +2·2 |
| 1782. | + 3·2 | −3·8 | −2·2 | −5·0 | −4·5 | −0·1 | −2·1 | −3·8 | −0·8 | −4·1 | −7·7 | −2·6 |
| 1783. | + 1·2 | +1·0 | −3·2 | +2·2 | −4·3 | +0·4 | +4·4 | +0·2 | −1·7 | −0·3 | +0·1 | −3·8 |
| 1784. | − 6·5 | −6·3 | −4·7 | −3·7 | +4·2 | −1·8 | −1·8 | −4·3 | +1·0 | −5·4 | −1·7 | −7·8 |
| 1785. | + 0·4 | −7·8 | −7·0 | +0·5 | −0·1 | +1·4 | +0·9 | −3·0 | +0·5 | −2·4 | −2·2 | −3·6 |
| 1786. | + 0·2 | −2·0 | −6·7 | −1·0 | −0·3 | +1·6 | −2·3 | −1·6 | −5·0 | −4·6 | −5·7 | −2·9 |
| 1787. | + 1·0 | +1·3 | +1·9 | −1·3 | −1·3 | −0·2 | +0·1 | +0·6 | −1·9 | −0·7 | −2·8 | +0·8 |
| 1788. | + 1·7 | +0·5 | −2·3 | +3·8 | +3·7 | +0·6 | −0·7 | −0·6 | −0·4 | −0·2 | −1·8 | −9·8 |
| 1789. | − 2·3 | +1·7 | −6·5 | −1·6 | +0·6 | −3·2 | −2·5 | −0·3 | −1·7 | −2·5 | −3·7 | +2·8 |
| 1790. | + 2·9 | +3·0 | +2·3 | −4·8 | 0·0 | −1·2 | −2·2 | −0·6 | −2·4 | +0·2 | −0·4 | +0·2 |
| 1791. | + 4·1 | +0·6 | +1·2 | +3·1 | −3·2 | −0·4 | −1·8 | +0·9 | +0·5 | −2·7 | −1·1 | −4·0 |
| 1792. | − 0·8 | −0·8 | +1·2 | +3·2 | −3·0 | −3·6 | −2·7 | +1·7 | −0·9 | −0·6 | +0·8 | +1·2 |
| 1793. | − 0·4 | +1·5 | −1·6 | −3·3 | −1·9 | −2·6 | +3·6 | −1·5 | −3·5 | −2·6 | +0·5 | +2·2 |
| 1794. | − 2·4 | +6·5 | +3·4 | +3·9 | −2·0 | −0·4 | +4·0 | −1·1 | −2·6 | −1·0 | +0·9 | −2·0 |
| 1795. | −11·8 | −4·1 | −2·3 | −0·6 | −2·7 | +3·3 | −2·4 | +0·3 | +4·5 | +4·1 | −1·7 | +6·0 |
| 1796. | + 9·6 | +1·4 | −1·9 | +2·6 | −2·5 | −1·9 | −2·7 | −0·6 | +2·8 | −2·8 | −2·1 | −8·4 |
| 1797. | − 0·3 | −2·6 | −3·0 | −1·0 | −1·3 | −3·2 | +2·0 | −1·5 | −1·7 | −2·3 | −1·0 | +2·4 |
| 1798. | + 2·1 | −0·3 | −0·2 | +3·5 | +1·0 | +3·2 | −0·1 | +1·0 | +0·2 | +0·5 | −2·4 | −5·1 |
| 1799. | − 2·4 | −1·8 | −3·7 | −4·2 | −3·1 | −2·4 | −1·5 | −0·5 | −2·0 | −2·0 | +0·5 | −6·0 |
| 1800. | + 1·2 | −4·1 | −3·4 | +2·7 | +1·4 | −2·9 | +1·9 | +3·2 | +1·6 | −1·4 | −0·2 | −0·6 |
| 1801. | + 3·8 | +0·3 | +3·2 | −0·3 | +1·0 | +0·4 | −0·8 | +2·0 | +2·4 | +1·6 | −2·2 | −2·7 |
| 1802. | − 2·8 | +0·7 | +0·3 | +2·8 | −2·4 | −0·4 | −4·8 | +4·3 | +0·7 | +0·2 | −1·9 | −1·0 |
| 1803. | − 2·3 | −1·9 | +1·4 | +2·1 | −2·5 | −1·8 | +2·4 | +1·2 | −3·9 | −0·4 | −0·5 | +4·5 |
| 1804. | + 7·5 | −1·3 | +0·2 | −2·0 | +4·0 | +3·3 | −1·1 | −0·6 | +3·1 | +2·1 | +1·7 | −3·2 |
| 1805. | − 1·2 | +0·5 | +1·1 | −0·4 | −3·0 | −3·5 | −2·2 | +1·2 | +3·0 | −1·9 | −2·5 | +0·7 |
| 1806. | + 4·9 | +3·3 | −0·2 | −2·7 | +2·4 | +1·8 | −0·1 | +0·9 | +0·7 | +1·9 | +5·0 | +8·0 |
| 1807. | + 1·0 | +1·8 | −3·9 | −0·3 | +2·4 | −0·3 | +2·2 | +3·2 | −3·2 | +3·7 | −3·7 | −2·2 |
| 1808. | + 1·3 | −1·9 | −3·8 | −3·2 | +4·5 | 0·0 | +4·4 | +2·0 | −1·0 | −3·2 | +1·5 | −2·8 |
| 1809. | − 0·3 | +5·9 | +1·7 | −4·6 | +3·1 | −0·5 | −1·7 | −1·6 | −0·2 | +0·3 | −2·9 | +2·2 |
| 1810. | − 1·3 | +0·4 | +1·3 | +0·7 | −2·9 | +0·5 | −0·4 | 0·0 | +3·1 | +2·5 | +0·4 | −0·2 |
| 1811. | + 2·9 | +1·9 | +2·5 | +3·0 | +3·3 | −0·4 | −0·3 | −2·0 | +1·6 | +6·2 | +2·8 | −0·2 |
| 1812. | + 0·2 | +3·4 | +2·5 | −4·2 | +1·4 | −4·0 | −3·9 | −3·5 | −0·4 | −0·5 | −1·8 | −3·7 |
| 1813. | − 1·3 | +3·4 | +2·2 | −1·9 | −0·3 | −2·7 | −2·4 | −2·2 | −1·8 | −2·0 | −2·2 | −2·2 |
| 1814. | − 8·8 | −4·2 | −5·8 | +2·4 | −4·0 | −4·6 | −0·2 | −1·9 | −1·4 | −2·0 | −1·7 | +2·3 |
| 1815. | − 3·8 | +3·0 | +4·1 | +0·9 | +2·1 | 0·0 | −1·4 | −0·1 | +6·0 | +2·1 | −3·5 | −1·8 |
| 1816. | + 1·0 | −1·6 | −1·7 | −2·3 | −3·8 | −4·9 | −6·8 | −2·6 | +2·6 | +1·5 | −3·1 | −1·0 |
| 1817. | + 3·5 | +4·4 | +0·7 | −1·8 | −4·7 | +1·1 | −3·6 | −5·1 | −0·8 | −4·3 | +4·5 | −1·7 |
| 1818. | + 3·6 | −2·4 | 0·0 | −0·1 | −0·1 | +4·9 | +4·9 | +3·1 | +4·4 | +4·4 | +6·8 | 0·0 |
| 1819. | + 4·4 | +1·8 | +3·1 | +2·5 | +1·6 | −1·6 | +0·4 | +3·3 | +1·8 | −1·8 | −1·6 | −1·8 |
| 1820. | − 4·0 | −1·3 | +0·4 | +3·6 | −0·6 | −1·9 | −1·8 | −2·0 | −1·9 | −2·3 | −1·0 | +1·1 |
| 1821. | + 1·8 | −2·2 | +1·9 | +4·7 | −2·2 | −3·9 | −2·6 | +1·2 | +3·3 | +1·0 | −2·2 | +5·5 |
| 1822. | + 4·1 | +5·1 | +6·4 | +1·0 | +3·2 | +4·6 | +1·2 | +0·8 | −0·3 | +2·7 | +5·8 | −2·4 |
| 1823. | − 3·9 | −0·1 | −1·1 | −2·9 | +2·0 | −2·6 | −2·2 | −0·7 | −0·9 | −1·7 | +0·6 | +1·1 |
| 1824. | + 1·7 | −2·0 | −1·4 | −1·9 | −3·1 | −3·0 | +1·2 | −0·5 | +1·4 | +0·5 | +3·8 | +3·0 |
| 1825. | + 2·7 | −0·1 | −2·4 | +3·0 | +1·0 | +0·9 | +3·9 | +1·3 | +3·6 | +1·5 | −1·2 | +1·8 |
| 1826. | − 3·7 | +4·0 | +2·3 | +3·3 | −2·6 | +4·9 | +4·3 | +2·9 | 0·0 | +3·1 | −2·5 | +3·0 |
| 1827. | − 2·3 | −6·6 | +2·2 | +1·1 | +0·1 | −0·4 | +2·2 | −1·5 | +0·6 | +2·5 | −0·9 | +5·3 |
| 1828. | + 4·1 | +2·0 | +2·6 | +0·8 | +1·7 | +2·0 | +0·6 | −1·5 | +1·2 | +0·6 | +1·9 | +5·7 |
| 1829. | − 4·0 | +0·2 | +1·9 | −2·0 | +1·9 | +1·0 | −1·2 | −2·8 | −3·1 | −1·8 | −3·1 | −3·9 |
| 1830. | − 5·0 | −4·0 | +4·9 | +2·6 | +2·1 | −2·7 | +1·7 | −2·3 | −2·8 | +1·6 | +2·0 | −3·9 |
| 1831. | − 1·3 | +3·0 | +3·0 | +2·4 | +0·2 | +1·4 | +3·0 | +2·8 | +0·1 | +5·7 | +1·9 | +3·2 |
| 1832. | + 1·6 | −1·3 | −0·4 | +1·5 | −1·1 | +1·2 | −0·1 | +0·5 | +0·3 | +1·9 | +1·3 | +3·6 |
| 1833. | − 1·2 | +4·2 | −3·3 | −0·5 | +6·8 | +1·8 | −0·2 | −3·0 | −2·8 | −1·0 | +1·1 | +5·8 |
| 1834. | + 8·7 | +2·0 | +3·1 | −0·7 | +4·3 | +3·1 | +2·8 | +1·8 | +2·0 | +1·2 | +1·7 | +2·2 |
| 1835. | + 2·3 | +3·0 | +0·1 | +0·7 | +0·3 | +2·0 | +3·1 | +2·8 | +0·8 | −1·3 | +0·6 | −3·9 |
| 1836. | + 1·5 | −1·3 | +2·8 | −2·4 | +0·2 | +1·0 | +1·6 | −1·6 | −2·9 | −1·9 | −0·9 | +0·8 |
| 1837. | + 1·5 | +2·1 | −5·1 | −6·6 | −4·8 | +0·1 | 0·0 | −0·4 | −1·3 | +1·3 | −1·3 | +2·4 |
| 1838. | − 6·8 | −5·3 | +0·6 | +4·1 | −1·9 | −0·8 | −0·8 | −0·9 | −1·9 | +0·7 | −1·6 | −0·2 |
| 1839. | + 1·5 | +0·9 | −1·9 | −4·8 | −2·7 | +0·7 | −1·1 | −1·6 | −0·7 | −0·4 | +2·3 | +0·8 |
| 1840. | + 3·3 | −0·1 | −3·3 | +2·1 | +0·9 | +1·5 | −3·3 | +1·6 | −2·2 | −2·5 | +1·0 | −5·5 |
| 1841. | − 2·1 | −2·9 | +5·3 | +1·5 | +4·2 | −1·6 | −3·5 | 0·0 | +1·8 | −0·5 | +0·3 | +1·7 |
| 1842. | − 2·8 | +2·6 | +4·0 | −0·5 | +0·6 | +4·9 | −1·1 | +4·9 | +0·1 | −3·9 | +0·4 | +6·2 |
| 1843. | + 4·2 | −2·2 | +2·0 | +1·4 | −0·4 | −1·7 | −0·4 | +1·6 | +3·2 | −1·3 | +1·4 | +5·1 |
| 1844. | + 3·4 | −3·0 | +0·6 | +6·0 | +0·3 | +2·7 | +0·1 | −2·8 | +0·6 | +0·2 | +1·6 | −5·8 |
| 1845. | + 2·6 | −5·5 | −5·7 | +0·6 | −3·2 | +2·7 | −1·5 | −3·2 | −2·7 | +0·9 | +3·4 | +2·9 |
| 1846. | + 8·0 | +3·7 | +2·4 | +1·4 | +2·0 | +7·3 | +3·2 | +2·7 | +3·8 | +1·2 | +3·6 | −5·9 |
| 1847. | − 0·6 | −2·8 | +0·1 | −0·4 | +3·8 | 0·0 | +4·1 | +1·6 | −2·0 | −3·6 | +4·5 | +4·0 |
| 1848. | − 1·1 | +5·2 | +2·9 | −1·9 | +7·1 | +0·5 | +0·2 | −2·1 | −0·5 | +2·3 | +1·4 | −5·2 |
| 1849. | + 4·4 | +5·0 | +1·6 | −2·5 | +1·4 | −0·1 | +0·8 | +2·4 | +2·5 | +1·8 | +1·7 | +0·3 |

The sign − denotes that the temperature of that month was below the average, and the sign + denotes that it was above the average.

By taking the means of the numbers in each column without respect to sign, we find that the variability of temperature is greatest in the winter months; its mean value in January is 3°·1; in both February and March is 2°·6; in April is 2°·3; in May and June is 2°·0; in the months of August, September and October, whose temperatures are the steadiest, it is 1°·9; in November it is 2°·0, and in December it is 3°·1, as in January.

The numbers in the preceding Table very clearly show that causes exist at different times, which raise or depress the temperature, and which continue through long periods.

As in the distribution of the positive and negative signs in the space of seventy-nine years, we perceive a gradual increasing preponderance of the positive signs over the negative signs, it seems that the temperature of the climate during this period has increased.

As the mean results from so long a series of observations may be considered as true, having the advantage of being free from errors of observation and from those arising from imperfect instruments, we may really consider the numbers in the above Table as abnormal values; yet as it seems most desirable to have those at the beginning of the series confirmed by the description of each year, made without instrumental means, for this purpose, as well as for the comparison of the character of the climate at the beginning and at the end of the series, I have collected the following brief particulars of every year till that of 1800; after this time the general characters of the years are well known.

1771.—There were frequent and very sharp frosts till April 20. On February 12 the reading of the thermometer was as low as 4°; the month of May was warm; the summer was cool and dry; October was a wet and windy month, and the weather was mild to the end of the year. The severe weather of the beginning of the year caused a bad seed time, and the harvest was very late.

1772.—The beginning of the year was mild; from the middle of January frosts and great snows were frequent, and continued to the middle of March. The summer was very fine; the autumn was mild but wet, and there was no frost till December 22.

1773.—With the exception of the latter part of February, which was stormy and wet, there was much fine weather till the beginning of May; then many mornings were frosty, after which heavy rain fell frequently till June. The summer was fine; the autumn was wet. There were sharp frosts at the end of November and at the beginning of December.

1774.—The year began with severe frost, and for nearly two months the ground was frost-bound; occasionally there were great rains or snow; the weather was more moderate in April; the summer was cool with heavy rains. The autumnal months were wet, particularly in September. Some snow fell in November and beginning of December. This year was remarkably wet.

1775.—The weather was mild at the beginning of the year. The summer was dry

and hot; thunder-storms were frequent in autumn. The year was very fine, and grain was cheaper than it had been for many years past.

1776.—In January there fell a greater quantity of snow than had fallen for some years, and the frost was supposed to have been the most severe since 1740. The frost went away at the beginning of February, and the weather following was mild and wet; it became hot about the middle of April. May was cold and dry, with north winds; after this the weather was mostly fine till the end of December, when there was a sharp frost.

1777.—The year began with a sharp frost, and heavy falls of snow continued till towards the end of February; for a few days about the end of March the weather was unusually hot, the reading of the thermometer being nearly 70°; after this the weather was windy and cold till June. The latter part of the summer and autumn was fine. The year ended with frost and snow.

1778.—There were frost and snow at the beginning of the year; the beginning of April was fine. The summer was fine and hot, supposed at the time to have been as fine a summer as that of 1762, if not as fine as the summer of 1750. Frosty mornings began in September, but were less frequent afterwards. On the last day of this year there was a violent storm, supposed by some to have been as violent as that of 1703.

1779.—After the beginning of January there was no frost; the spring months were remarkably warm. In February wall fruit flowered; the middle of April was quite hot, as was the summer and autumn; about the middle of November there was a little frost, and again on December 22: there was much sickness this year.

1780.—This year began with a frost almost as severe as that in 1772; there was not much snow, and the weather continued severe till near the end of February. The month of March was warm; it was hot from July to September, and mostly mild till Christmas, when a frost set in. The year was sickly.

1781.—There was a little frost at the beginning of the year; the spring was mild, the summer was hot, and the ground was much burned. Autumn was fine and pleasant, and there were only a few frosty mornings during the remainder of the year.

1782.—The beginning of the year was mild, but in February it was frosty, and the remainder of the winter was severe; the spring was cold; nearly 12 inches of rain fell in April and May; the weather was fine in June, but bad afterwards; the autumn was cold; it was severe in November, and during the first half of December.

1783.—The spring was pleasant, with frosty mornings very constant till near April. A remarkable haze was prevalent all over Europe during the summer. The autumn was fine, and the weather was mostly mild till the last week in December, when a great fall of snow took place.

1784.—There was steady frost with snow till February 21, and till the end of March the mornings were frosty; and at the end of March there were cold winds with snow. This weather continued till the middle of April; and till the first week in May frosty mornings were frequent, and the remainder of May was exceedingly hot. There

were a few hot days in July, but the weather was precarious throughout the autumn; and in December the frost was as severe as it was in January.

1785.—The severe frost of the preceding month broke early in January, but on the last day of that month a second very severe frost set in and continued till the middle of March. This winter was most severe. The summer and part of autumn were showery; a heavy fall of snow took place at Christmas, with severe frost.

1786.—The frosts at the beginning of the year were of short duration. From the beginning of March there was a severe frost of a fortnight's duration, and cold E. and N.E. winds were prevalent with frosty mornings till the beginning of May. June and July were moderately fine; August was cold and showery; and from this time to the end of the year there was a great deal of rain.

1787.—The year began with open weather. April was cold with N. winds, and vegetation was stopped; during April and May frosty mornings were frequent, and there was a sharp frost on the morning of the 7th of June; it was a cold summer; the autumn was mild, and there was a heavy fall of snow and a week's frost at the end of the year.

1788.—January and February were mild, the latter month being wet; there was a fortnight's frost in March; there were several periods of hot weather in April, May and June. The summer was in general dry; autumn was fine; there was a gentle frost at the beginning of December, then an exceedingly severe frost set in with heavy falls of snow, which continued to the end of the year. This year was remarkable for abundance of fruits, &c.

1789.—Very heavy storms of wind and snow took place till the middle of January; and large rivers were frozen over; there was a great loss of fish in ponds from the severity of the cold. After the frost broke the weather was mild, but windy and wet. During March there were nearly constant N. winds, and heavy falls of snow were frequent with sharp frost. The summer was mostly wet; August was fine, after which it was again wet, and continued so to the end of the year, with scarcely any frost.

1790.—The weather was mild and open till April, when the first snow fell in the year, and the weather, during the beginning of this month, was the most severe during the winter. The summer was cool, cloudy and windy; autumn was fine and pleasant; December was stormy with very changeable weather.

1791.—Till January 6th there was frost; after this the weather was mild till towards the end of April; there were many frosty mornings with cold N.E. winds in May. The former part of the summer was cold; frosty mornings were frequent till the middle of June, the latter part of summer and autumn. During November and December there were frequent storms and falls of snow and frost.

1792.—There were frequent sharp frosts till March, with stormy and wet weather; the beginning of March was mild, after this there was a frost of a week's duration. The summer was wet and cold; the autumn was wet, and December was cloudy, with very little frost. This year was very wet.

1793.—January and February and beginning of March were mild; a frost set in at the end of March; there was a great fall of snow in the first week in April. The former part of the summer was cold, with frequent frosty mornings till June; July was wet; the autumn was fine, mild and calm, and there was no frost till the end of the year.

1794.—The year began with slight frost, which continued till the end of January; February was very mild; the spring was warm till May, which was cold; July was hot; the autumn was wet but mild, as was the first part of December, but the weather during the latter half of the month was severe with heavy snow.

1795.—The frost began about the middle of December 1794, was excessively severe in January, and continued till the end of March. There were very large falls of snow, and the consequent floods were so great that nearly all the bridges in England were injured. Some snow fell in April. The summer was cold, with frequent frosty mornings till June; there were some hot days in July, but it was generally cold; after this the weather was fine till autumn. In December much injury was done to shipping by the strong S. and S.W. winds; there was no frost.

1796.—January was remarkably warm, with occasional thunder-storms; there was no frost till March, and then of no long duration. The summer was cool; the autumn was fine with a few frosty mornings at the end of November; in December a severe frost set in, and the reading of the thermometer in many places on the 24th was below zero of Fahrenheit's scale.

1797.—During a few days in January the frost continued; after this, till the end of March, scarcely any rain fell, and the weather was fine with frequent frost. From April to September there were frequent heavy rains. The summer was cold; there was some warm weather in July; the autumn in general fine, and the weather continued open till the end of the year.

1798.—With the exception of a few slight frosts, which occasionally occurred till March, the weather was open and mild. The summer was fine, as was autumn and the beginning of December; after this a very severe frost set in, and the reading of the thermometer was as low as 5°.

1799.—The severe frost which set in about the middle of the preceding month continued to the middle of January, and again set in towards the end of the month with much snow, which continued during the first week in February; some snow fell in March, and the mornings were frosty till the end of the month. From April to the middle of November was wet; December was foggy; and after the 17th a severe frost set in with snow falling. The whole year was remarkably cloudy.

If we compare the character of the preceding years with the abnormal differences shown for the same years in Table XX., the agreement is most satisfactory, and leaves no doubt upon the correctness of the numbers at the beginning of this series. I do not think it necessary to describe the years from that of 1800, as most of them are well described by Luke Howard in his 'Climate of London.'

TABLE XXI.—Showing the mean temperature in quarterly periods, for the year, and the same for successive groups of years, at the Royal Observatory, Greenwich, from the year 1771 to 1849.

| Year. | January, February, March. | Group of years. | April, May, June. | Group of years. | July, August, September. | Group of years. | October, November, December. | Group of years. | For the year. | Group of years. |
|---|---|---|---|---|---|---|---|---|---|---|
| | ° | ° | ° | ° | ° | ° | ° | ° | ° | ° |
| 1771. | 32·7 | | 49·1 | | 56·6 | | 43·2 | | 45·4 | |
| 1772. | 35·0 | | 50·1 | | 58·2 | | 45·1 | | 47·1 | |
| 1773. | 37·6 | | 49·1 | | 57·7 | | 41·9 | | 46·6 | |
| 1774. | 37·4 | | 52·7 | | 58·9 | | 41·7 | | 47·7 | |
| 1775. | 41·3 | 37·6 | 53·5 | 52·0 | 60·7 | 59·6 | 42·6 | 43·6 | 50·0 | 48·2 |
| 1776. | 36·9 | | 52·2 | | 59·3 | | 44·8 | | 48·3 | |
| 1777. | 38·1 | | 50·9 | | 60·3 | | 43·6 | | 48·2 | |
| 1778. | 36·8 | | 54·3 | | 61·3 | | 44·5 | | 49·2 | |
| 1779. | 42·4 | | 54·5 | | 63·2 | | 44·7 | | 51·2 | |
| 1780. | 37·7 | | 52·9 | | 62·7 | | 42·0 | | 48·8 | |
| 1781. | 39·7 | | 53·9 | | 61·7 | | 43·7 | | 49·8 | |
| 1782. | 37·3 | | 48·9 | | 57·1 | | 38·7 | | 45·5 | |
| 1783. | 37·9 | | 51·5 | | 60·3 | | 42·2 | | 48·0 | |
| 1784. | 32·4 | 36·8 | 51·7 | 52·0 | 57·7 | 59·0 | 38·5 | 41·0 | 45·1 | 47·2 |
| 1785. | 33·5 | | 52·7 | | 58·8 | | 40·8 | | 46·5 | |
| 1786. | 35·4 | | 52·2 | | 56·4 | | 39·1 | | 45·8 | |
| 1787. | 39·7 | | 51·2 | | 59·0 | | 42·6 | | 48·1 | |
| 1788. | 38·2 | | 54·8 | | 58·8 | | 39·6 | | 47·9 | |
| 1789. | 35·9 | | 50·7 | | 57·9 | | 42·4 | | 46·7 | |
| 1790. | 41·0 | | 50·1 | | 57·6 | | 43·5 | | 48·1 | |
| 1791. | 40·2 | | 51·9 | | 59·2 | | 40·9 | | 48·1 | |
| 1792. | 38·1 | | 51·0 | | 58·7 | | 44·0 | | 48·0 | |
| 1793. | 38·1 | | 49·5 | | 58·9 | | 45·3 | | 47·9 | |
| 1794. | 40·8 | | 52·6 | | 59·5 | | 42·8 | | 48·9 | |
| 1795. | 32·2 | 38·3 | 50·2 | 51·1 | 60·2 | 58·9 | 46·3 | 42·7 | 47·2 | 47·8 |
| 1796. | 41·3 | | 51·5 | | 59·2 | | 39·1 | | 47·8 | |
| 1797. | 36·3 | | 50·3 | | 59·0 | | 43·2 | | 47·2 | |
| 1798. | 38·8 | | 54·7 | | 59·7 | | 41·2 | | 48·6 | |
| 1799. | 35·6 | | 48·9 | | 57·2 | | 41·0 | | 45·7 | |
| 1800. | 36·2 | | 52·5 | | 61·6 | | 42·8 | | 48·3 | |
| 1801. | 40·7 | | 52·5 | | 60·6 | | 42·4 | | 49·0 | |
| 1802. | 37·7 | | 52·1 | | 59·4 | | 42·6 | | 48·0 | |
| 1803. | 37·3 | | 51·4 | | 59·3 | | 44·7 | | 48·2 | |
| 1804. | 40·4 | | 53·9 | | 59·8 | | 43·7 | | 49·5 | |
| 1805. | 38·4 | 38·7 | 49·9 | 52·1 | 60·0 | 60·0 | 42·3 | 43·5 | 47·7 | 48·5 |
| 1806. | 40·9 | | 52·6 | | 59·9 | | 48·5 | | 50·5 | |
| 1807. | 37·9 | | 52·6 | | 60·1 | | 42·8 | | 48·3 | |
| 1808. | 36·8 | | 52·5 | | 61·2 | | 42·0 | | 48·1 | |
| 1809. | 40·7 | | 51·4 | | 58·2 | | 43·4 | | 48·0 | |
| 1810. | 38·4 | | 51·5 | | 60·3 | | 44·4 | | 48·7 | |
| 1811. | 38·8 | | 54·2 | | 59·1 | | 46·4 | | 49·6 | |
| 1812. | 38·6 | | 48·9 | | 56·8 | | 41·5 | | 46·5 | |
| 1813. | 39·7 | | 50·5 | | 57·2 | | 41·4 | | 47·2 | |
| 1814. | 32·0 | | 50·0 | | 58·2 | | 43·0 | | 45·8 | |
| 1815. | 39·4 | 38·5 | 53·1 | 51·3 | 60·9 | 59·1 | 42·4 | 43·3 | 49·0 | 48·1 |
| 1816. | 37·5 | | 48·4 | | 57·1 | | 42·6 | | 46·4 | |
| 1817. | 41·1 | | 50·3 | | 56·2 | | 43·0 | | 47·7 | |
| 1818. | 38·7 | | 53·7 | | 63·5 | | 47·2 | | 50·8 | |
| 1819. | 41·4 | | 52·9 | | 61·2 | | 41·8 | | 49·3 | |

FRANKLIN INSTITUTE LIBRARY

TABLE XXI. (Continued.)

| Year. | January, February, March. | Group of years. | April, May, June. | Group of years. | July, August, September. | Group of years. | October, November, December. | Group of years. | For the year. | Group of years. |
|---|---|---|---|---|---|---|---|---|---|---|
| | ° | | ° | | ° | | ° | | ° | |
| 1820. | 36·6 | | 52·5 | | 57·5 | | 42·8 | | 47·4 | |
| 1821. | 38·8 | | 51·3 | | 59·7 | | 47·4 | | 49·3 | |
| 1822. | 43·5 | | 55·0 | | 59·9 | | 45·5 | | 51·0 | |
| 1823. | 36·6 | | 50·9 | | 58·1 | | 43·5 | | 47·3 | |
| 1824. | 37·7 | | 49·4 | | 60·1 | | 45·9 | | 48·3 | |
| 1825. | 38·3 | 38·4 | 53·7 | 52·5 | 62·3 | 59·6 | 44·2 | 44·7 | 49·6 | 48·8 |
| 1826. | 39·1 | | 54·0 | | 61·8 | | 44·7 | | 49·9 | |
| 1827. | 36·0 | | 52·4 | | 59·8 | | 45·8 | | 48·5 | |
| 1828. | 41·2 | | 53·6 | | 59·5 | | 46·2 | | 50·1 | |
| 1829. | 36·4 | | 52·4 | | 57·0 | | 40·6 | | 46·6 | |
| 1830. | 36·9 | | 52·8 | | 58·2 | | 43·4 | | 47·8 | |
| 1831. | 39·8 | | 53·4 | | 61·3 | | 47·1 | | 50·4 | |
| 1832. | 38·2 | | 52·6 | | 59·6 | | 45·8 | | 49·1 | |
| 1833. | 38·2 | | 54·8 | | 57·4 | | 45·5 | | 49·0 | |
| 1834. | 42·9 | | 54·3 | | 61·6 | | 45·2 | | 51·0 | |
| 1835. | 40·1 | 38·6 | 53·1 | 52·1 | 61·6 | 59·3 | 42·0 | 44·4 | 49·2 | 48·6 |
| 1836. | 39·3 | | 51·7 | | 58·4 | | 42·8 | | 48·1 | |
| 1837. | 37·8 | | 48·3 | | 58·8 | | 44·3 | | 47·3 | |
| 1838. | 34·4 | | 49·8 | | 58·2 | | 43·1 | | 46·4 | |
| 1839. | 38·4 | | 49·8 | | 58·2 | | 44·4 | | 47·7 | |
| 1840. | 38·2 | | 53·6 | | 58·1 | | 41·2 | | 47·8 | |
| 1841. | 38·4 | | 53·5 | | 58·8 | | 44·0 | | 48·7 | |
| 1842. | 39·5 | | 53·8 | | 60·7 | | 44·4 | | 49·6 | |
| 1843. | 39·6 | | 51·9 | | 60·8 | | 45·2 | | 49·4 | |
| 1844. | 38·6 | | 55·1 | | 58·7 | | 42·2 | | 48·7 | |
| 1845. | 35·4 | 39·3 | 52·1 | 53·6 | 56·9 | 59·7 | 45·9 | 44·4 | 47·6 | 49·2 |
| 1846. | 43·6 | | 55·7 | | 62·6 | | 43·1 | | 51·3 | |
| 1847. | 37·2 | | 53·2 | | 60·6 | | 47·5 | | 49·6 | |
| 1848. | 40·6 | | 55·3 | | 58·6 | | 46·5 | | 50·2 | |
| 1849. | 41·9 | | 51·7 | | 61·3 | | 44·8 | | 49·9 | |

The mean temperature from all the observations

For the quarter ending March . 31 was 38°·3,

" June . 30 was 52°·1,

" September 30 was 59°·4,

" December 31 was 43°·4,

and for the year from all the observations was 48°·29.

By taking the difference between these numbers, and those contained in the preceding Table, the next Table is immediately formed.

TABLE XXII.—Showing the excess of the quarterly and yearly mean temperatures, in every year, and the same for groups of years, above the means from all the years.

| Year. | January, February, March. | Group of years. | April, May, June. | Group of years. | July, August, September. | Group of years. | October, November, December. | Group of years. | For the year. | Group of years. |
|---|---|---|---|---|---|---|---|---|---|---|
| | ° | ° | ° | ° | ° | ° | ° | ° | ° | ° |
| 1771. | −5·5 | | −3·0 | | −2·8 | | −0·2 | | −2·9 | |
| 1772. | −3·3 | | −2·0 | | −1·2 | | +1·7 | | −1·2 | |
| 1773. | −0·6 | | −3·0 | | −1·7 | | −1·5 | | −1·7 | |
| 1774. | −0·9 | | +0·6 | | −0·5 | | −1·7 | | −0·6 | |
| 1775. | +3·1 | −0·7 | +3·4 | −0·1 | +1·3 | +0·2 | −0·8 | −0·2 | +1·7 | −0·1 |
| 1776. | −1·4 | | +0·1 | | −0·1 | | +1·4 | | 0·0 | |
| 1777. | −0·1 | | −1·2 | | +0·9 | | +0·2 | | −0·1 | |
| 1778. | −1·5 | | +2·2 | | +1·9 | | +1·1 | | +0·9 | |
| 1779. | +4·2 | | +2·4 | | +3·8 | | +1·3 | | +2·9 | |
| 1780. | −0·6 | | +0·8 | | +3·3 | | −1·4 | | +0·5 | |
| 1781. | +1·5 | | +1·8 | | +2·3 | | +0·3 | | +1·5 | |
| 1782. | −1·0 | | −3·2 | | −2·3 | | −4·7 | | −2·8 | |
| 1783. | −0·3 | | +0·4 | | +0·9 | | −1·2 | | −0·3 | |
| 1784. | −5·9 | | −0·4 | | −1·7 | | −4·9 | | −3·2 | |
| 1785. | −4·7 | −1·5 | +0·8 | 0·0 | −0·6 | −0·4 | −2·6 | −2·4 | −1·4 | −1·1 |
| 1786. | −2·9 | | +0·1 | | −3·0 | | −4·3 | | −2·5 | |
| 1787. | +1·5 | | −0·9 | | −0·4 | | −0·8 | | −0·2 | |
| 1788. | 0·0 | | +2·7 | | −0·6 | | −3·8 | | −0·4 | |
| 1789. | −2·4 | | −1·4 | | −1·5 | | −1·0 | | −1·6 | |
| 1790. | +2·8 | | −2·0 | | −1·8 | | +0·1 | | −0·2 | |
| 1791. | +1·9 | | −0·2 | | −0·2 | | −2·5 | | −0·2 | |
| 1792. | −0·1 | | −1·1 | | −0·7 | | +0·6 | | −0·3 | |
| 1793. | −0·2 | | −2·6 | | −0·5 | | +1·9 | | −0·4 | |
| 1794. | +2·6 | | +0·5 | | +0·1 | | −0·6 | | +0·6 | |
| 1795. | −6·0 | 0·0 | −1·9 | −1·0 | +0·8 | −0·5 | +2·9 | −0·7 | −1·1 | −0·5 |
| 1796. | +3·1 | | −0·6 | | −0·2 | | −4·3 | | −0·5 | |
| 1797. | −2·0 | | −1·8 | | −0·4 | | −0·2 | | −1·1 | |
| 1798. | +0·5 | | +2·6 | | +0·3 | | −2·2 | | +0·3 | |
| 1799. | −2·6 | | −3·2 | | −2·2 | | −2·4 | | −2·6 | |
| 1800. | −2·0 | | +0·4 | | +2·2 | | −0·6 | | 0·0 | |
| 1801. | +2·4 | | +0·4 | | +1·2 | | −1·0 | | +0·7 | |
| 1802. | −0·5 | | 0·0 | | 0·0 | | −0·8 | | −0·3 | |
| 1803. | −1·0 | | −0·7 | | −0·1 | | +1·3 | | −0·1 | |
| 1804. | +2·2 | | +1·8 | | +0·4 | | +0·3 | | +1·2 | |
| 1805. | +0·1 | +0·4 | −2·2 | 0·0 | +0·6 | +0·6 | −1·1 | +0·1 | −0·6 | +0·3 |
| 1806. | +2·7 | | +0·5 | | +0·5 | | +5·1 | | +2·2 | |
| 1807. | −0·4 | | +0·5 | | +0·7 | | −0·6 | | 0·0 | |
| 1808. | −1·4 | | +0·4 | | +1·8 | | −1·4 | | −0·2 | |
| 1809. | +2·4 | | −0·7 | | −1·2 | | 0·0 | | −0·3 | |
| 1810. | +0·2 | | −0·6 | | +0·9 | | +1·0 | | +0·4 | |
| 1811. | +0·5 | | +2·1 | | −0·3 | | +3·0 | | +1·3 | |
| 1812. | +0·4 | | −3·2 | | −2·6 | | −1·9 | | −1·8 | |
| 1813. | +1·4 | | −1·6 | | −2·2 | | −2·0 | | −1·1 | |
| 1814. | −6·2 | | −2·1 | | −1·2 | | −0·4 | | −2·5 | |
| 1815. | +1·1 | +0·2 | +1·0 | −0·8 | +1·5 | −0·4 | −1·0 | −0·1 | +0·7 | −0·2 |
| 1816. | −0·7 | | −3·7 | | −2·3 | | −0·8 | | −1·9 | |
| 1817. | +2·8 | | −1·8 | | −3·2 | | −0·4 | | −0·6 | |
| 1818. | +0·5 | | +1·6 | | +4·1 | | +3·8 | | +2·5 | |
| 1819. | +3·1 | | +0·8 | | +1·8 | | −1·6 | | +1·0 | |

TABLE XXII. (Continued.)

| Year. | January, February, March. | Group of years. | April, May, June. | Group of years. | July, August, September. | Group of years. | October, November, December. | Group of years. | For the year. | Group of years. |
|---|---|---|---|---|---|---|---|---|---|---|
| | ° | ° | ° | ° | ° | ° | ° | ° | ° | ° |
| 1820. | −1·6 | | +0·4 | | −1·9 | | −0·6 | | −0·9 | |
| 1821. | +0·5 | | −0·8 | | +0·3 | | +4·0 | | +1·0 | |
| 1822. | +5·3 | | +2·9 | | +0·5 | | +2·1 | | +2·7 | |
| 1823. | −1·7 | | −1·2 | | −1·3 | | +0·1 | | −1·0 | |
| 1824. | −0·5 | | −2·7 | | +0·7 | | +2·5 | | 0·0 | |
| 1825. | 0·0 | +0·2 | +1·6 | +0·4 | +2·9 | +0·2 | +0·8 | +1·3 | +1·3 | +0·5 |
| 1826. | +0·9 | | +1·9 | | +2·4 | | +1·3 | | +1·6 | |
| 1827. | −2·3 | | +0·3 | | +0·4 | | +2·4 | | +0·2 | |
| 1828. | +3·0 | | +1·5 | | +0·1 | | +2·8 | | +1·8 | |
| 1829. | −1·9 | | +0·3 | | −2·4 | | −2·8 | | −1·7 | |
| 1830. | −1·3 | | +0·7 | | −1·2 | | 0·0 | | −0·5 | |
| 1831. | +1·5 | | +1·3 | | +1·9 | | +3·7 | | +2·1 | |
| 1832. | 0·0 | | +0·5 | | +0·2 | | +2·4 | | +0·8 | |
| 1833. | −0·1 | | +2·7 | | −2·0 | | +2·1 | | +0·7 | |
| 1834. | +4·7 | +0·4 | +2·2 | 0·0 | +2·2 | −0·1 | +1·8 | +1·0 | +2·7 | +0·3 |
| 1835. | +1·8 | | +1·0 | | +2·2 | | −1·4 | | +0·9 | |
| 1836. | +1·1 | | −0·4 | | −1·0 | | −0·6 | | −0·2 | |
| 1837. | −0·5 | | −3·8 | | −0·6 | | +0·9 | | −1·0 | |
| 1838. | −3·8 | | −2·3 | | −1·2 | | −0·3 | | −1·9 | |
| 1839. | +0·1 | | −2·3 | | −1·2 | | +1·0 | | −0·6 | |
| 1840. | 0·0 | | +1·5 | | −1·3 | | −2·2 | | −0·5 | |
| 1841. | +0·1 | | +1·4 | | −0·6 | | +0·6 | | +0·4 | |
| 1842. | +1·3 | | +1·7 | | +1·3 | | +1·0 | | +1·3 | |
| 1843. | +1·3 | | −0·2 | | +1·4 | | +1·8 | | +1·1 | |
| 1844. | +0·4 | +1·0 | +3·0 | +1·5 | −0·7 | +0·3 | −1·2 | +1·0 | +0·4 | +1·0 |
| 1845. | −2·9 | | 0·0 | | −2·5 | | +2·5 | | −0·7 | |
| 1846. | +5·4 | | +3·6 | | +3·2 | | −0·3 | | +3·0 | |
| 1847. | −1·1 | | +1·1 | | +1·2 | | +4·1 | | +1·3 | |
| 1848. | +2·3 | | +3·2 | | −0·8 | | +3·1 | | +1·9 | |
| 1849. | +3·6 | | −0·4 | | +1·9 | | +1·4 | | +1·6 | |

The sign — denotes that the temperature of that period was below the average, and the sign + denotes that it was above the average.

These numbers do not at all confirm the idea that a hot summer is either preceded or followed by a cold winter, or *vice versâ*; on the contrary, it would seem that any hot or cold period has been mostly accompanied by weather of the same character. The cold year of 1771 was followed by two cold years. The hot year of 1779 was preceded by one warm year and followed by two others. In 1780 the extreme cold of January was more than counterbalanced by the extreme heat of March. The cold year of 1782 was followed by a long series of cold years. The very cold year of 1799 was followed by a cold autumn and winter. The warm year of 1806 was preceded by a warm winter. The very cold year of 1814 (the last very cold year we have had) was preceded by a cold summer, autumn and winter. The hot year of 1818 was preceded by a moderate winter, and was followed by a warm one. The hot year of 1822 was preceded by a warm winter and was followed by a moderately cold one. The hot year of 1834 followed a very mild winter and was followed by another. The hot

year of 1846 was preceded by a warm winter and was followed by a moderate one. The warm year 1848 was both preceded and followed by warm periods.

The mean temperatures of the years 1771, 1782, 1784, 1786, 1799 and 1814, were all below 46°; the coldest was 1784, and its value was 45°·1.

The mean temperatures of the years 1779, 1818, 1822, 1834 and 1846, were all above 50°·5; the year of highest temperature was 1846, and its value was 51°·3.

Thus seventy-nine years, from 1771 to 1849 inclusive, gives a mean temperature of 48°·3, with a variation, between one year and another, from 45°·1 in 1784 to 51°·3 in 1846; the difference is 6°·2.

TABLE XXIII.—Showing the mean temperature of the Air in Spring, Summer, Autumn, Winter, and for the year from March, and the same for successive groups of years.

| Year. | Spring. | | Summer. | | Autumn. | | Winter. | | The year from March. | |
|---|---|---|---|---|---|---|---|---|---|---|
| | March, April, May. | Group of years. | June, July, August. | Group of years. | September, October, November. | Group of years. | December, January, February. | Group of years. | Whole year. | Group of years. |
| | ° | ° | ° | ° | ° | ° | ° | ° | ° | ° |
| 1771. | 42·6 | | 57·3 | | 46·7 | | 35·9 | | 45·6 | |
| 1772. | 43·1 | | 59·7 | | 50·3 | | 37·1 | | 47·5 | |
| 1773. | 44·2 | | 58·3 | | 47·1 | | 35·9 | | 46·4 | |
| 1774. | 46·9 | | 60·7 | | 47·6 | | 39·8 | | 48·7 | |
| 1775. | 48·5 | 46·4 | 62·1 | 60·5 | 48·9 | 49·0 | 35·4 | 36·9 | 48·8 | 48·2 |
| 1776. | 47·2 | | 60·7 | | 49·6 | | 36·6 | | 48·5 | |
| 1777. | 47·0 | | 59·7 | | 51·0 | | 35·4 | | 48·3 | |
| 1778. | 47·3 | | 63·9 | | 48·0 | | 41·0 | | 50·0 | |
| 1779. | 50·8 | | 62·3 | | 51·5 | | 34·7 | | 49·8 | |
| 1780. | 49·6 | | 62·7 | | 49·6 | | 37·7 | | 49·9 | |
| 1781. | 47·3 | | 63·6 | | 49·0 | | 38·1 | | 49·5 | |
| 1782. | 42·5 | | 57·9 | | 45·1 | | 37·4 | | 45·7 | |
| 1783. | 44·6 | | 61·6 | | 48·7 | | 32·0 | | 46·7 | |
| 1784. | 45·0 | 45·5 | 57·3 | 60·0 | 47·3 | 47·5 | 32·5 | 36·3 | 45·5 | 47·3 |
| 1785. | 44·2 | | 59·8 | | 48·0 | | 35·8 | | 46·9 | |
| 1786. | 43·7 | | 59·2 | | 44·2 | | 37·4 | | 46·1 | |
| 1787. | 46·2 | | 60·1 | | 47·5 | | 38·6 | | 48·1 | |
| 1788. | 48·1 | | 59·7 | | 48·5 | | 34·1 | | 47·6 | |
| 1789. | 43·9 | | 57·9 | | 46·7 | | 40·5 | | 47·3 | |
| 1790. | 45·6 | | 58·6 | | 48·5 | | 39·2 | | 48·0 | |
| 1791. | 46·8 | | 59·5 | | 48·2 | | 35·7 | | 47·6 | |
| 1792. | 46·9 | | 58·4 | | 49·1 | | 38·3 | | 48·2 | |
| 1793. | 44·1 | | 59·8 | | 49·2 | | 39·7 | | 48·2 | |
| 1794. | 48·2 | | 60·8 | | 48·4 | | 31·6 | | 47·2 | |
| 1795. | 45·2 | 45·8 | 57·8 | 59·1 | 51·6 | 48·8 | 43·2 | 37·0 | 49·5 | 47·7 |
| 1796. | 45·8 | | 58·2 | | 48·6 | | 33·8 | | 46·6 | |
| 1797. | 44·6 | | 59·0 | | 47·7 | | 39·0 | | 47·6 | |
| 1798. | 47·8 | | 61·3 | | 48·8 | | 34·5 | | 48·1 | |
| 1799. | 42·7 | | 57·6 | | 48·2 | | 34·6 | | 45·8 | |
| 1800. | 46·6 | | 60·7 | | 49·3 | | 38·7 | | 48·8 | |
| 1801. | 47·7 | | 60·5 | | 49·9 | | 36·0 | | 48·5 | |
| 1802. | 46·6 | | 59·6 | | 49·0 | | 35·8 | | 47·7 | |
| 1803. | 46·7 | | 60·5 | | 47·7 | | 41·1 | | 49·0 | |
| 1804. | 47·1 | 46·5 | 60·5 | 60·3 | 51·6 | 49·2 | 36·3 | 38·3 | 48·9 | 48·6 |
| 1805. | 45·6 | | 58·4 | | 48·9 | | 40·5 | | 48·4 | |
| 1806. | 46·2 | | 60·8 | | 51·9 | | 41·2 | | 50·0 | |
| 1807. | 45·8 | | 61·6 | | 48·3 | | 36·6 | | 48·1 | |
| 1808. | 45·6 | | 62·1 | | 48·4 | | 38·5 | | 48·7 | |
| 1809. | 46·5 | | 58·7 | | 48·4 | | 38·0 | | 47·9 | |

TABLE XXIII. (Continued.)

| Year. | Spring. | | Summer. | | Autumn. | | Winter. | | The year from March. | |
|---|---|---|---|---|---|---|---|---|---|---|
| | March, April, May. | Group of years. | June, July, August. | Group of years. | September, October, November. | Group of years. | December, January, February. | Group of years. | Whole year. | Group of years. |
| | ° | ° | ° | ° | ° | ° | ° | ° | ° | ° |
| 1810. | 46·1 | | 60·0 | | 51·3 | | 37·2 | | 48·6 | |
| 1811. | 49·4 | | 59·0 | | 52·9 | | 38·6 | | 50·0 | |
| 1812. | 43·7 | | 56·1 | | 48·4 | | 37·0 | | 46·3 | |
| 1813. | 46·4 | | 57·5 | | 47·3 | | 32·5 | | 45·9 | |
| 1814. | 43·9 | | 57·7 | | 47·6 | | 38·1 | | 46·8 | |
| 1815. | 48·8 | 46·1 | 59·4 | 58·6 | 50·9 | 50·0 | 36·8 | 37·2 | 49·0 | 48·0 |
| 1816. | 43·8 | | 55·2 | | 49·7 | | 39·9 | | 47·1 | |
| 1817. | 44·5 | | 57·4 | | 49·1 | | 37·4 | | 47·1 | |
| 1818. | 46·3 | | 64·2 | | 54·5 | | 39·6 | | 51·2 | |
| 1819. | 48·8 | | 60·6 | | 48·8 | | 35·2 | | 48·4 | |
| 1820. | 47·5 | | 58·0 | | 47·6 | | 37·8 | | 47·7 | |
| 1821. | 47·5 | | 57·8 | | 52·6 | | 42·5 | | 50·1 | |
| 1822. | 49·9 | | 62·1 | | 52·1 | | 35·4 | | 49·9 | |
| 1823. | 45·7 | | 58·0 | | 48·7 | | 37·8 | | 47·6 | |
| 1824. | 44·3 | | 59·2 | | 51·2 | | 39·4 | | 48·5 | |
| 1825. | 46·9 | 47·1 | 62·0 | 60·0 | 50·6 | 50·0 | 38·3 | 38·0 | 49·5 | 48·8 |
| 1826. | 47·4 | | 63·9 | | 49·5 | | 35·6 | | 49·1 | |
| 1827. | 47·5 | | 60·0 | | 50·1 | | 41·4 | | 49·8 | |
| 1828. | 48·1 | | 60·3 | | 50·6 | | 38·2 | | 49·3 | |
| 1829. | 45·7 | | 58·9 | | 46·7 | | 33·3 | | 46·2 | |
| 1830. | 49·6 | | 58·8 | | 49·6 | | 36·8 | | 48·7 | |
| 1831. | 48·3 | | 62·3 | | 51·9 | | 38·7 | | 50·3 | |
| 1832. | 46·4 | | 60·5 | | 50·5 | | 39·8 | | 49·3 | |
| 1833. | 47·4 | | 59·5 | | 48·4 | | 43·1 | | 49·6 | |
| 1834. | 48·6 | | 62·5 | | 51·0 | | 40·1 | | 50·5 | |
| 1835. | 46·8 | 46·3 | 62·6 | 60·5 | 49·4 | 49·5 | 36·3 | 38·5 | 48·8 | 48·7 |
| 1836. | 46·6 | | 60·3 | | 47·4 | | 39·0 | | 48·3 | |
| 1837. | 40·9 | | 59·8 | | 48·9 | | 34·3 | | 46·0 | |
| 1838. | 44·6 | | 59·1 | | 48·4 | | 38·3 | | 47·6 | |
| 1839. | 43·3 | | 59·3 | | 49·7 | | 38·9 | | 47·8 | |
| 1840. | 46·3 | | 59·9 | | 48·1 | | 34·1 | | 47·1 | |
| 1841. | 50·1 | | 58·2 | | 49·9 | | 38·1 | | 49·1 | |
| 1842. | 47·8 | | 62·8 | | 48·2 | | 40·3 | | 49·8 | |
| 1843. | 47·4 | | 59·8 | | 50·4 | | 39·4 | | 49·3 | |
| 1844. | 48·7 | | 59·9 | | 50·1 | | 34·7 | | 48·4 | |
| 1845. | 43·6 | 47·7 | 59·3 | 60·7 | 49·9 | 50·1 | 43·1 | 38·5 | 49·0 | 49·3 |
| 1846. | 48·3 | | 64·3 | | 52·2 | | 34·5 | | 49·8 | |
| 1847. | 47·6 | | 61·8 | | 51·4 | | 40·3 | | 50·2 | |
| 1848. | 50·3 | | 59·5 | | 50·4 | | 42·4 | | 50·7 | |
| 1849. | 46·6 | | 61·0 | | 51·3 | | 39·2 | | 49·5 | |

The mean temperature from all the results for Spring is . . . . . 46°·4

The mean temperature from all the results for Summer is . . . . . 60·0

The mean temperature from all the results for Autumn is . . . . . 49·3

The mean temperature from all the results for Winter is . . . . . 37·6

The mean temperature from all the results for the Year is . . . . . 48·3

The mean temperature of spring, from all the observations, is 46°·4.

The years distinguished by cold springs were 1771, 1772, 1782, 1786, 1789, 1799,

1812, 1814, 1816, 1837, 1839 and 1845, and the mean of their temperatures was 43°·1.

The coldest spring, during the whole period, was in the year 1837, and its mean temperature was 40°·9.

The years distinguished by hot springs were 1779, 1780, 1811, 1822, 1830, 1841 and 1848, and the mean of their temperatures was 50°·0.

The hottest spring, during the whole period, was 1779, and its mean temperature was 50°·8.

The mean temperature of summer, from all the observations, is 60°·0. The years distinguished by cold summers were 1771, 1784, 1799, 1812, 1813, 1814, 1816, 1817, and the mean of their temperatures was 56°·9.

The years distinguished by hot summers were 1778, 1779, 1780, 1781, 1818, 1826, 1831, 1834, 1835, 1842 and 1846, and the mean of their temperatures was 63°·2. The coldest summer within the period was that in the year 1816, and its mean temperature was 55°·2. The hottest summer within the period was that in the year 1846, and its mean temperature was 64°·3.

The mean temperature of autumn, from all the observations, is 49°·3. The years distinguished by cold autumns were 1771, 1782, 1786, 1789 and 1829, and the mean of their temperatures was 45°·9.

The years distinguished by hot autumns were 1779, 1795, 1804, 1806, 1811, 1818, 1821, 1822, 1831 and 1846, and the mean of their temperatures was 52°·3. The coldest autumn within the period was that in the year 1786, and its mean temperature was 44°·2. The hottest autumn within the period was that in the year 1718, and its mean temperature was 54°·5.

The mean temperature of winter, from all the observations, was 37°·6. The years distinguished by cold winters were 1783, 1784, 1794, 1796, 1813 and 1829; the mean of their temperatures was 32°·6.

The years distinguished by warm winters were 1778, 1795, 1803, 1806, 1821, 1827, 1833, 1845 and 1848, and the mean of their temperatures was 42°·1.

The coldest winter within the period was that in the year 1794, and its mean temperature was 31°·6.

The warmest winter within the period was that in the year 1795, and its mean value was 43°·2. The winters of the years 1833 and 1845 were remarkably warm, being both of the value of 43°·1.

By taking the difference between the mean temperature of each period from all the observations, and the mean temperature for the same period, in every year, the next Table is formed.

TABLE XXIV.—Showing the excess of the mean temperature, in every year, in Spring, Summer, Autumn, Winter, and the Year, above the mean temperature for each period from all the years, and the same for groups of years.

| Year. | Spring. | | Summer. | | Autumn. | | Winter. | | The year from March. | |
|---|---|---|---|---|---|---|---|---|---|---|
| | March, April, May. | Group of years. | June, July, August. | Group of years. | September, October, November. | Group of years. | December, January, February. | Group of years. | Whole year. | Group of years. |
| | ° | ° | ° | ° | ° | ° | ° | ° | ° | ° |
| 1771. | −3·8 | | −2·7 | | −2·6 | | −1·7 | | −2·7 | |
| 1772. | −3·3 | | −0·3 | | +1·0 | | −0·5 | | −0·8 | |
| 1773. | −2·2 | | −1·7 | | −2·1 | | −1·7 | | −1·9 | |
| 1774. | +0·5 | | +0·7 | | −1·7 | | +2·2 | | +0·4 | |
| 1775. | +2·1 | 0·0 | +2·1 | +0·5 | −0·3 | −0·3 | −2·2 | −0·7 | +0·5 | −0·1 |
| 1776. | +0·8 | | +0·7 | | +0·3 | | −1·0 | | +0·2 | |
| 1777. | +0·6 | | −0·3 | | +1·8 | | −2·2 | | 0·0 | |
| 1778. | +0·9 | | +3·9 | | −1·3 | | +3·4 | | +1·7 | |
| 1779. | +4·4 | | +2·3 | | +2·3 | | −2·9 | | +1·5 | |
| 1780. | +3·2 | | +2·7 | | +0·3 | | +0·1 | | +1·6 | |
| 1781. | +0·9 | | +3·6 | | −0·2 | | +0·5 | | +1·2 | |
| 1782. | −3·9 | | −2·1 | | −4·2 | | −0·2 | | −2·6 | |
| 1783. | −1·8 | | +1·6 | | −0·5 | | −5·6 | | −1·6 | |
| 1784. | −1·4 | | −2·7 | | −2·0 | | −5·1 | | −2·8 | |
| 1785. | −2·2 | −0·9 | −0·2 | 0·0 | −1·2 | −1·8 | −1·8 | −1·3 | −1·4 | −1·0 |
| 1786. | −2·7 | | −0·8 | | −5·1 | | −0·2 | | −2·2 | |
| 1787. | −0·2 | | +0·1 | | −1·7 | | +1·0 | | −0·2 | |
| 1788. | +1·7 | | −0·3 | | −0·8 | | −3·5 | | −0·7 | |
| 1789. | −2·5 | | −2·1 | | −2·5 | | +2·9 | | −1·0 | |
| 1790. | −0·8 | | −1·4 | | −0·8 | | +1·6 | | −0·3 | |
| 1791. | +0·4 | | −0·5 | | −1·0 | | −1·9 | | −0·7 | |
| 1792. | +0·5 | | −1·6 | | −0·2 | | +0·7 | | −0·1 | |
| 1793. | −2·3 | | −0·2 | | 0·0 | | +2·1 | | −0·1 | |
| 1794. | +1·8 | | +0·8 | | −0·9 | | −6·0 | | −1·1 | |
| 1795. | −1·2 | −0·6 | −2·2 | −0·9 | +2·4 | −0·4 | +5·6 | −0·6 | +1·2 | −0·6 |
| 1796. | −0·6 | | −1·8 | | −0·7 | | −3·8 | | −1·7 | |
| 1797. | −1·8 | | −1·0 | | −1·5 | | +1·4 | | −0·7 | |
| 1798. | +1·4 | | +1·3 | | −0·5 | | −3·1 | | −0·2 | |
| 1799. | −3·7 | | −2·4 | | −1·0 | | −3·0 | | −2·5 | |
| 1800. | +0·2 | | +0·7 | | +0·1 | | +1·1 | | +0·5 | |
| 1801. | +1·3 | | +0·5 | | +0·6 | | −1·6 | | +0·2 | |
| 1802. | +0·2 | | −0·4 | | −0·3 | | −1·8 | | −0·6 | |
| 1803. | +0·3 | | +0·5 | | −1·6 | | +3·5 | | +0·7 | |
| 1804. | +0·7 | | +0·5 | | +2·4 | | −1·3 | | +0·6 | |
| 1805. | −0·8 | +0·1 | −1·6 | +0·3 | −0·3 | −0·1 | +2·9 | +0·5 | +0·1 | +0·3 |
| 1806. | −0·2 | | +0·8 | | +2·6 | | +3·6 | | +1·7 | |
| 1807. | −0·6 | | +1·6 | | −0·9 | | −1·0 | | −0·2 | |
| 1808. | −0·8 | | +2·1 | | −0·9 | | +0·9 | | +0·4 | |
| 1809. | +0·1 | | −1·3 | | −0·8 | | +0·4 | | −0·4 | |
| 1810. | −0·3 | | 0·0 | | +2·1 | | −0·4 | | +0·3 | |
| 1811. | +3·0 | | −1·0 | | +3·6 | | +1·0 | | +1·7 | |
| 1812. | −2·7 | | −3·9 | | −0·8 | | −0·6 | | −2·0 | |
| 1813. | 0·0 | | −2·5 | | −2·0 | | −5·1 | | −2·4 | |
| 1814. | −2·5 | | −2·3 | | −1·6 | | +0·5 | | −1·5 | |
| 1815. | +2·4 | −0·3 | −0·6 | −1·4 | +1·6 | +0·8 | −0·8 | −0·4 | +0·7 | −0·3 |
| 1816. | −2·6 | | −4·8 | | +0·5 | | +2·3 | | −1·2 | |
| 1817. | −1·9 | | −2·6 | | −0·2 | | −0·2 | | −1·2 | |
| 1818. | −0·1 | | +4·2 | | +5·3 | | +2·0 | | +2·9 | |
| 1819. | +2·4 | | +0·6 | | −0·5 | | −2·4 | | +0·1 | |

TABLE XXIV. (Continued.)

| Year. | Spring. | | Summer. | | Autumn. | | Winter. | | The year from March. | |
|---|---|---|---|---|---|---|---|---|---|---|
| | March, April, May. | Group of years. | June, July, August. | Group of years. | September, October, November. | Group of years. | December, January, February. | Group of years. | Whole year. | Group of years. |
| | ° | ° | ° | ° | ° | ° | ° | ° | ° | ° |
| 1820. | +1·1 | | −2·0 | | −1·6 | | +0·2 | | −0·6 | |
| 1821. | +1·1 | | −2·2 | | +3·3 | | +4·9 | | +1·8 | |
| 1822. | +3·5 | | +2·1 | | +2·9 | | −2·2 | | +1·6 | |
| 1823. | −0·7 | | −2·0 | | −0·6 | | +0·2 | | −0·7 | |
| 1824. | −2·1 | | −0·8 | | +2·0 | | +1·8 | | +0·2 | |
| 1825. | +0·5 | +0·7 | +2·0 | 0·0 | +1·3 | −0·7 | +0·7 | +0·4 | +1·2 | +0·5 |
| 1826. | +1·0 | | +3·9 | | +0·3 | | −2·0 | | +0·8 | |
| 1827. | +1·1 | | 0·0 | | +0·8 | | +3·8 | | +1·5 | |
| 1828. | +1·7 | | +0·3 | | +1·4 | | +0·6 | | +1·0 | |
| 1829. | −0·7 | | −1·1 | | −2·6 | | −4·3 | | −2·1 | |
| 1830. | +3·2 | | −1·2 | | +0·4 | | −0·8 | | +0·4 | |
| 1831. | +1·9 | | +2·3 | | +2·6 | | +1·1 | | +2·0 | |
| 1832. | 0·0 | | +0·5 | | +1·3 | | +2·2 | | +1·0 | |
| 1833. | +1·0 | | −0·5 | | −0·9 | | +5·5 | | +1·3 | |
| 1834. | +2·2 | | +2·5 | | +1·8 | | +2·5 | | +2·2 | |
| 1835. | +0·4 | +0·1 | +2·6 | +0·5 | +0·1 | −0·2 | −1·3 | +0·9 | +0·5 | +0·4 |
| 1836. | +0·2 | | +0·3 | | −1·8 | | +1·4 | | 0·0 | |
| 1837. | −5·5 | | −0·2 | | −0·4 | | −3·3 | | −2·3 | |
| 1838. | −1·8 | | −0·9 | | −0·8 | | +0·7 | | −0·7 | |
| 1839. | −3·1 | | −0·7 | | +0·4 | | +1·2 | | −0·5 | |
| 1840. | −0·1 | | −0·1 | | −1·1 | | −3·5 | | −1·2 | |
| 1841. | +3·7 | | −1·8 | | +0·6 | | +0·5 | | +0·8 | |
| 1842. | +1·4 | | +2·8 | | −1·0 | | +2·7 | | +1·5 | |
| 1843. | +1·0 | | −0·2 | | +1·1 | | +1·8 | | +1·0 | |
| 1844. | +2·3 | | −0·1 | | +0·9 | | −2·9 | | +0·1 | |
| 1845. | −2·8 | +1·3 | −0·7 | +0·7 | +0·6 | +0·8 | +5·5 | +0·9 | +0·7 | +1·0 |
| 1846. | +1·9 | | +4·3 | | +3·0 | | −3·1 | | +1·5 | |
| 1847. | +1·2 | | +1·8 | | +2·1 | | +2·7 | | +1·9 | |
| 1848. | +3·9 | | −0·5 | | +1·2 | | +4·8 | | +2·4 | |
| 1849. | +0·2 | | +1·0 | | +2·0 | | +1·6 | | +1·2 | |

The sign − denotes that the temperature of that period was below the average, and the sign + denotes that it was above the average.

By taking the mean of the numbers for each period, without regard to gauge,

The mean variability in Spring is . . . 1·6°
The mean variability in Summer is . . . 1·5
The mean variability in Autumn is . . 1·4
The mean variability in Winter is . . . 2·2
The mean variability in the Year is . . . 1·1

All the following Tables are based upon the readings of self-registering thermometers, and exhibit the extreme readings at the Apartments of the Royal Society, and at the Royal Observatory, Greenwich. The first process in their formation was the copying from the Philosophical Transactions every reading of these thermometers, arranging all the minimum readings one under the other, and all the maximum readings similarly under each other, and then taking their monthly mean readings, or otherwise as was necessary to the construction of the Tables.

TABLE XXV.—Showing the monthly mean reading of the minimum temperature, and during the whole time that the maximum and minimum self-registering thermo- vember, at the Royal Observatory, Greenwich.

| Year. | January. | | February. | | March. | | April. | | May. | | June. | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | Mean of all the | | Mean of all the | | Mean of all the | | Mean of all the | | Mean of all the | | Mean of all the | |
| | Minimum readings. | Maximum readings. | Minimum readings. | Maximum readings. | Minimum readings. | Maximum readings. | Minimum readings. | Maximum readings. | Minimum readings. | Maximum readings. | Minimum readings. | Maximum readings. |
| | ° | ° | ° | ° | ° | ° | ° | ° | ° | ° | ° | ° |
| 1794. | 32·0 | 38·5 | 43·6 | 49·5 | 40·6 | 51·4 | 45·8 | 58·9 | 46·5 | 60·1 | 52·3 | 67·7 |
| 1795. | 23·0 | 29·7 | 32·8 | 39·0 | 35·6 | 45·3 | 42·4 | 53·3 | 46·3 | 62·1 | 50·9 | 63·3 |
| 1796. | 43·8 | 50·8 | 37·9 | 45·9 | 35·3 | 46·6 | 43·1 | 57·9 | 45·5 | 59·7 | 51·2 | 66·7 |
| 1797. | 34·7 | 40·0 | 38·9 | 42·9 | 34·3 | 45·7 | 41·0 | 53·7 | 45·7 | 62·0 | 49·2 | 65·9 |
| 1798. | 36·1 | 43·2 | 35·2 | 44·8 | 37·5 | 48·1 | 44·1 | 59·5 | 49·0 | 63·7 | 55·2 | 73·8 |
| 1799. | 32·1 | 38·5 | 33·8 | 42·9 | 35·0 | 44·0 | 39·1 | 49·1 | 45·5 | 59·0 | 50·5 | 65·7 |
| 1800. | 35·7 | 41·7 | 33·1 | 40·7 | 34·7 | 44·1 | 45·6 | 56·0 | 50·9 | 64·3 | 51·1 | 64·7 |
| 1801. | 37·1 | 45·0 | 36·8 | 43·9 | 41·1 | 50·7 | 39·8 | 55·8 | 47·2 | 63·3 | 52·7 | 68·9 |
| 1802. | 31·2 | 37·4 | 37·0 | 44·7 | 36·7 | 49·6 | 43·3 | 58·6 | 54·0 | 61·8 | 51·6 | 67·6 |
| 1803. | 33·1 | 37·5 | 34·6 | 42·0 | 38·8 | 50·3 | 43·9 | 57·3 | 46·7 | 59·4 | 52·3 | 65·5 |
| 1804. | 41·8 | 47·8 | 35·8 | 43·1 | 38·4 | 47·8 | 45·3 | 51·7 | 52·4 | 66·8 | 55·1 | 71·8 |
| 1805. | 33·6 | 38·9 | 36·5 | 44·9 | 38·4 | 49·4 | 41·4 | 54·6 | 45·0 | 59·6 | 50·2 | 65·3 |
| 1806. | 38·8 | 46·0 | 39·3 | 47·5 | 39·0 | 46·5 | 40·3 | 50·8 | 49·9 | 65·1 | 54·2 | 70·9 |
| 1807. | 35·5 | 42·8 | 37·4 | 46·2 | 34·0 | 44·6 | 44·7 | 55·8 | 51·1 | 64·2 | 52·5 | 68·2 |
| 1808. | 35·2 | 42·5 | 34·1 | 42·5 | 35·2 | 43·3 | 39·1 | 51·4 | 52·2 | 67·8 | 53·8 | 69·3 |
| 1809. | 33·8 | 40·3 | 41·8 | 50·0 | 39·6 | 49·9 | 38·0 | 49·7 | 50·2 | 65·2 | 53·3 | 68·2 |
| 1810. | 33·6 | 39·0 | 37·2 | 43·7 | 39·2 | 49·1 | 42·2 | 54·9 | 45·2 | 59·7 | 52·7 | 70·0 |
| 1820. | 30·5 | 37·9 | 35·3 | 43·0 | 37·2 | 50·3 | 44·9 | 59·5 | 48·3 | 62·7 | 52·5 | 66·2 |
| 1821. | 35·6 | 43·7 | 33·5 | 43·4 | 39·6 | 50·6 | 45·4 | 58·7 | 44·9 | 60·5 | 50·2 | 63·6 |
| 1822. | 35·8 | 46·0 | 40·5 | 50·7 | 44·0 | 55·5 | 43·9 | 55·3 | 52·6 | 65·0 | 58·3 | 73·6 |
| 1823. | ..... | ..... | ..... | ..... | ..... | ..... | ..... | ..... | 49·7 | 64·2 | 49·9 | 66·4 |
| 1824. | 36·6 | 41·7 | 37·7 | 43·8 | 37·3 | 45·7 | 40·7 | 51·6 | 46·5 | 58·5 | 51·1 | 64·6 |
| 1825. | 37·3 | 43·3 | 36·7 | 44·2 | 36·4 | 45·2 | 44·1 | 58·6 | 48·5 | 63·1 | 51·9 | 69·7 |
| 1826. | 29·8 | 37·3 | 40·4 | 47·9 | ..... | ..... | 44·6 | 58·8 | 46·3 | 60·8 | 56·4 | 74·6 |
| 1827. | 31·2 | 39·2 | 29·3 | 37·5 | 40·1 | 49·7 | 43·3 | 55·3 | 49·1 | 61·6 | 52·8 | 67·5 |
| 1828. | 37·5 | 45·0 | 38·4 | 45·2 | 40·0 | 51·0 | 43·1 | 55·0 | 50·0 | 64·2 | 55·9 | 70·2 |
| 1829. | 30·1 | 36·3 | 36·4 | 43·7 | 35·9 | 45·7 | 40·6 | 52·4 | 48·4 | 64·9 | 54·1 | 69·6 |
| 1830. | 29·3 | 35·0 | 30·9 | 40·5 | 41·5 | 53·9 | 44·1 | 57·9 | 50·0 | 64·8 | 52·0 | 65·2 |
| 1831. | 32·5 | 38·9 | 38·5 | 47·2 | 40·9 | 50·8 | 45·1 | 57·2 | 47·1 | 63·0 | 54·7 | 69·0 |
| 1832. | 34·5 | 40·8 | 34·7 | 42·6 | 36·9 | 47·7 | 42·0 | 56·4 | 46·3 | 61·6 | 55·2 | 69·5 |
| 1833. | 32·8 | 39·0 | 39·6 | 48·1 | 34·6 | 44·3 | 41·7 | 54·7 | 52·9 | 70·4 | 54·5 | 70·6 |
| 1834. | 42·5 | 49·0 | 36·7 | 46·6 | 40·4 | 51·3 | 40·3 | 54·4 | 50·5 | 67·7 | 55·0 | 73·5 |
| 1835. | 35·3 | 43·1 | 37·1 | 47·7 | 37·1 | 48·3 | 42·4 | 55·8 | 48·0 | 62·5 | 54·6 | 70·7 |
| 1836. | 34·5 | 43·8 | 34·0 | 42·3 | 40·2 | 50·5 | 40·5 | 51·3 | 44·7 | 60·6 | 55·2 | 69·1 |
| 1837. | 35·3 | 42·7 | 38·0 | 46·5 | 33·9 | 42·6 | 37·3 | 47·0 | 44·4 | 57·6 | 53·8 | 68·5 |
| 1838. | 27·1 | 34·4 | 31·2 | 38·4 | 38·1 | 49·2 | 39·2 | 50·9 | 45·8 | 61·3 | 53·6 | 68·6 |
| 1839. | 34·7 | 43·3 | 37·1 | 47·7 | 37·4 | 44·2 | 39·7 | 46·0 | 45·0 | 60·5 | 54·9 | 70·2 |
| 1840. | 36·9 | 43·5 | 36·5 | 42·4 | 35·9 | 41·7 | 43·3 | 53·5 | 49·6 | ..... | 55·5 | 71·2 |
| 1841. | 32·7 | 40·3 | 34·9 | 40·8 | 42·7 | 55·4 | 43·2 | 56·4 | 52·4 | 68·0 | 52·2 | 69·7 |
| 1842. | 32·0 | 38·1 | 38·4 | 46·4 | 41·6 | 51·5 | 41·1 | 53·8 | 48·8 | 64·9 | 58·3 | 76·6 |
| 1843. | 37·7 | 45·7 | 34·9 | 41·6 | 39·6 | 50·0 | 44·0 | 57·9 | 48·2 | 64·3 | 51·9 | 67·6 |
| | At the Royal Observatory, Greenwich. | | | | | | | | | | | |
| 1840. | ..... | ..... | ..... | ..... | ..... | ..... | ..... | ..... | ..... | ..... | ..... | ..... |
| 1841. | 29·4 | 39·5 | 31·6 | 40·7 | 38·7 | 56·2 | 39·9 | 58·4 | 48·4 | 69·7 | 48·2 | 67·0 |
| 1842. | 29·3 | 36·6 | 36·0 | 46·6 | 39·2 | 51·8 | 37·3 | 54·7 | 45·0 | 64·5 | 52·2 | 75·2 |
| 1843. | 35·4 | 44·7 | 31·9 | 40·2 | 37·5 | 50·5 | 40·7 | 57·9 | 45·5 | 63·3 | 49·0 | 67·0 |
| 1844. | 34·1 | 43·9 | 30·9 | 41·6 | 35·7 | 48·9 | 41·8 | 63·6 | 45·1 | 65·9 | 51·6 | 74·1 |
| 1845. | 34·3 | 43·3 | 27·9 | 38·4 | 30·8 | 42·4 | 39·3 | 57·5 | 42·7 | 59·6 | 52·2 | 72·5 |
| 1846. | 39·4 | 48·1 | 39·3 | 49·0 | 38·1 | 51·6 | 41·8 | 56·4 | 47·4 | 66·7 | 55·1 | 80·4 |
| 1847. | 31·5 | 40·1 | 30·5 | 41·5 | 34·3 | 50·1 | 38·8 | 55·4 | 47·5 | 68·0 | 49·7 | 69·4 |
| 1848. | 29·8 | 38·1 | 38·0 | 48·7 | 36·4 | 50·7 | 39·0 | 57·2 | 43·4 | 75·4 | 38·7 | 78·4 |
| 1849. | 35·7 | 45·2 | 36·5 | 49·4 | 36·3 | 50·1 | 36·5 | 52·5 | 46·7 | 63·8 | 48·5 | 69·1 |

the monthly mean reading of the maximum temperature of Air as observed daily, meters were in use at the Apartments of the Royal Society, and from 1840, No-

| Year. | July. | | August. | | September. | | October. | | November. | | December. | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | Mean of all the | | Mean of all the | | Mean of all the | | Mean of all the | | Mean of all the | | Mean of all the | |
| | Minimum readings. | Maximum readings. | Minimum readings. | Maximum readings. | Minimum readings. | Maximum readings. | Minimum readings. | Maximum readings. | Minimum readings. | Maximum readings. | Minimum readings. | Maximum readings. |
| | ° | ° | ° | ° | ° | ° | ° | ° | ° | ° | ° | ° |
| 1794. | 59·9 | 78·4 | 55·3 | 70·2 | 50·8 | 61·3 | 45·9 | 53·0 | 41·6 | 49·1 | 35·3 | 40·1 |
| 1795. | 53·0 | 66·1 | 56·6 | 71·7 | 55·6 | 70·4 | 51·0 | 60·3 | 38·2 | 46·9 | 43·2 | 48·9 |
| 1796. | 53·7 | 68·7 | 54·4 | 70·9 | 54·6 | 67·4 | 44·3 | 52·9 | 38·9 | 45·1 | 28·4 | 35·7 |
| 1797. | 56·5 | 75·8 | 53·8 | 70·9 | 50·4 | 63·5 | 44·3 | 53·3 | 38·8 | 48·0 | 38·7 | 46·3 |
| 1798. | 55·8 | 71·7 | 57·8 | 73·6 | 52·5 | 65·1 | 47·0 | 57·0 | 37·8 | 45·3 | 32·2 | 38·0 |
| 1799. | 55·6 | 69·1 | 53·4 | 67·7 | 49·9 | 63·0 | 45·0 | 54·7 | 41·1 | 48·0 | 32·3 | 36·3 |
| 1800. | 57·1 | 74·7 | 57·6 | 75·2 | 54·1 | 66·1 | 44·8 | 55·4 | 39·9 | 48·1 | 37·1 | 42·0 |
| 1801. | 55·1 | 70·9 | 57·4 | 73·4 | 55·3 | 67·0 | 47·7 | 57·7 | 38·5 | 45·8 | 34·3 | 41·5 |
| 1802. | 51·3 | 66·9 | 58·5 | 76·3 | 52·0 | 68·5 | 46·3 | 58·7 | 39·1 | 45·7 | 35·8 | 43·0 |
| 1803. | 58·4 | 70·7 | 56·5 | 72·6 | 46·9 | 63·8 | 46·3 | 56·2 | 39·7 | 47·7 | 40·2 | 45·4 |
| 1804. | 57·9 | 69·7 | 56·3 | 70·0 | 55·3 | 68·5 | 48·4 | 58·9 | 42·7 | 48·8 | 34·8 | 39·7 |
| 1805. | 55·1 | 69·1 | 58·0 | 72·0 | 54·9 | 68·6 | 45·0 | 53·9 | 37·6 | 45·6 | 37·5 | 44·3 |
| 1806. | 57·1 | 70·9 | 57·2 | 71·9 | 53·0 | 66·1 | 48·4 | 58·0 | 45·5 | 53·1 | 44·8 | 50·7 |
| 1807. | 59·0 | 74·3 | 60·0 | 73·7 | 48·7 | 61·4 | 50·2 | 60·2 | 36·9 | 45·0 | 34·7 | 41·4 |
| 1808. | 59·8 | 76·9 | 58·4 | 72·5 | 52·1 | 63·8 | 43·2 | 53·8 | 42·3 | 49·1 | 35·2 | 40·6 |
| 1809. | 55·6 | 69·4 | 59·5 | 69·4 | 53·0 | 64·6 | 47·2 | 56·3 | 37·5 | 45·1 | 38·8 | 45·3 |
| 1810. | 55·8 | 70·7 | 55·9 | 70·8 | 55·2 | 68·0 | 47·7 | 58·8 | | | | |
| 1820. | 56·3 | 68·8 | 55·7 | 69·8 | 49·7 | 64·1 | 44·2 | 55·5 | 39·8 | 48·1 | 38·5 | 45·3 |
| 1821. | 54·0 | 67·3 | 58·2 | 71·3 | 56·4 | 67·7 | 47·0 | 58·8 | 44·3 | 54·0 | 41·0 | 50·6 |
| 1822. | 59·3 | 70·6 | 58·7 | 69·9 | 53·2 | 64·1 | 50·3 | 58·6 | 47·1 | 54·1 | 34·5 | 41·3 |
| 1823. | 55·4 | 67·7 | 56·9 | 68·6 | 51·2 | 64·1 | 45·0 | 53·9 | 42·0 | 46·8 | 38·9 | 44·0 |
| 1824. | 57·4 | 72·1 | 56·9 | 69·1 | 54·9 | 65·1 | 47·5 | 56·3 | 43·2 | 51·4 | 39·6 | 46·3 |
| 1825. | 59·9 | 74·5 | 57·5 | 71·0 | 57·7 | 68·0 | 48·7 | 56·9 | 38·3 | 46·4 | 39·2 | 43·9 |
| 1826. | ..... | ..... | 61·2 | 73·6 | 54·3 | 63·3 | 50·3 | 59·4 | 38·3 | 45·5 | 40·8 | 45·7 |
| 1827. | 58·1 | 73·4 | 55·2 | 68·8 | 54·2 | 65·0 | 49·2 | 58·5 | 39·5 | 48·0 | 41·0 | 49·1 |
| 1828. | 58·3 | 71·5 | 55·9 | 68·6 | 54·2 | 66·4 | 46·2 | 57·0 | 41·8 | 49·9 | 42·6 | 49·2 |
| 1829. | 56·2 | 69·8 | 55·2 | 66·6 | 50·3 | 61·6 | 45·8 | 53·9 | 36·7 | 44·9 | 31·4 | 36·6 |
| 1830. | 58·1 | 73·0 | 53·9 | 68·5 | 50·1 | 62·0 | 47·0 | 58·4 | 41·9 | 49·7 | 32·2 | 39·4 |
| 1831. | 58·3 | 76·6 | 59·9 | 73·2 | 52·9 | 65·2 | 53·1 | 61·6 | 39·3 | 49·1 | 40·6 | 46·0 |
| 1832. | 56·1 | 71·2 | 56·8 | 71·3 | 51·8 | 66·2 | 48·4 | 57·9 | 41·9 | 49·0 | 39·0 | 47·0 |
| 1833. | 56·1 | 71·5 | 53·0 | 68·4 | 49·4 | 62·5 | 46·9 | 58·1 | 40·4 | 49·1 | 40·8 | 50·3 |
| 1834. | 59·3 | 74·7 | 57·9 | 72·8 | 54·1 | 67·3 | 46·2 | 58·2 | 41·4 | 49·4 | 38·1 | 45·6 |
| 1835. | 57·3 | 74·8 | 58·4 | 73·8 | 52·8 | 65·8 | 45·4 | 54·5 | 41·5 | 47·5 | 33·6 | 39·6 |
| 1836. | 57·1 | 71·9 | 54·5 | 68·9 | 50·3 | 61·2 | 45·3 | 53·5 | 38·7 | 47·6 | 38·0 | 44·4 |
| 1837. | 56·7 | 71·7 | 56·6 | 70·0 | 51·7 | 63·2 | 46·1 | 58·8 | 37·2 | 49·0 | 39·8 | 46·0 |
| 1838. | 56·0 | 70·8 | 56·4 | 69·0 | 51·5 | 62·6 | 47·0 | 57·4 | 39·9 | 46·8 | 37·5 | 43·5 |
| 1839. | 56·7 | 69·9 | 55·4 | 68·6 | 53·0 | 63·5 | 47·3 | 54·3 | 43·8 | 48·0 | 38·0 | 41·8 |
| 1840. | 54·9 | 69·8 | 57·9 | 72·7 | 50·0 | 63·3 | 43·2 | 54·8 | 40·8 | 50·7 | 31·5 | 38·8 |
| 1841. | 54·8 | 68·8 | 57·2 | 70·0 | 51·7 | 67·3 | 47·0 | 56·9 | 40·8 | 49·8 | 38·8 | 47·1 |
| 1842. | 55·5 | 73·5 | 60·8 | 76·0 | 53·5 | 65·6 | 42·9 | 53·4 | 41·5 | 49·0 | 41·9 | 50·5 |
| | At the Royal Observatory, Greenwich. | | | | | | | | | | | |
| 1840. | ..... | ..... | ..... | ..... | ..... | ..... | ..... | ..... | 35·7 | 46·7 | 27·1 | 36·1 |
| 1841. | 51·5 | 67·1 | 54·3 | 70·6 | 51·2 | 67·2 | 43·9 | 55·6 | 38·0 | 48·7 | 35·4 | 44·8 |
| 1842. | 52·1 | 71·2 | 56·3 | 78·1 | 49·8 | 64·3 | 39·3 | 53·4 | 39·0 | 48·1 | 40·2 | 49·4 |
| 1843. | 53·5 | 71·8 | 55·2 | 72·5 | 52·3 | 70·4 | 42·0 | 55·5 | 38·5 | 50·0 | 40·3 | 48·2 |
| 1844. | 54·1 | 72·8 | 50·3 | 67·9 | 50·2 | 67·5 | 44·4 | 56·7 | 39·6 | 48·1 | 30·4 | 36·8 |
| 1845. | 53·5 | 71·2 | 50·5 | 67·7 | 46·3 | 63·9 | 44·0 | 59·0 | 40·3 | 51·8 | 35·8 | 47·6 |
| 1846. | 56·5 | 77·9 | 56·6 | 74·4 | 51·4 | 71·9 | 44·5 | 58·7 | 40·0 | 50·3 | 37·9 | 37·2 |
| 1847. | 54·8 | 78·1 | 52·8 | 74·4 | 46·1 | 64·9 | 46·4 | 61·5 | 40·8 | 52·7 | 37·2 | 46·7 |
| 1848. | 51·2 | 73·7 | 50·4 | 68·9 | 45·9 | 66·8 | 43·8 | 59·2 | 36·1 | 50·5 | 37·3 | 48·9 |
| 1849. | 51·6 | 74·2 | 54·0 | 74·2 | 51·2 | 68·7 | 44·1 | 59·2 | 38·1 | 49·8 | 34·1 | 43·2 |

TABLE XXVI.—Showing the highest and lowest readings by the self-registering were in use at the Apartments of the Royal Society, and at the Royal Observatory,

| Year. | January. | | February. | | March. | | April. | | May. | | June. | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | Reading of the thermometers in the month. | | Reading of the thermometers in the month. | | Reading of the thermometers in the month. | | Reading of the thermometers in the month. | | Reading of the thermometers in the month. | | Reading of the thermometers in the month. | |
| | Lowest. | Highest. | Lowest. | Highest. | Lowest. | Highest. | Lowest. | Highest. | Lowest. | Highest. | Lowest. | Highest. |
| | ° | ° | ° | ° | ° | ° | ° | ° | ° | ° | ° | ° |
| 1794. | 22 | 51 | 35 | 56 | 34 | 56 | 38 | 73 | 40 | 71 | 46 | 79 |
| 1795. | 7 | 46 | 24 | 51 | 24 | 54·5 | 36 | 61 | 36 | 81·5 | 41 | 77·5 |
| 1796. | 36 | 56 | 30 | 56 | 26·5 | 60 | 36 | 70 | 39 | 65 | 45 | 80 |
| 1797. | 25 | 49 | 24·5 | 50 | 27·5 | 54 | 34 | 65 | 34 | 79 | 40 | 73 |
| 1798. | 28 | 53 | 24 | 54 | 30 | 58 | 30 | 69 | 43 | 76 | 47 | 86 |
| 1799. | 20 | 50 | 18 | 56 | 28 | 56 | 37 | 59 | 36 | 70 | 43 | 77 |
| 1800. | 18 | 51 | 25 | 53 | 23 | 57 | 38 | 62 | 40 | 75 | 43 | 75 |
| 1801. | 34 | 54 | 25 | 57 | 31 | 49 | 30 | 67 | 39 | 71 | 43 | 80 |
| 1802. | 15 | 48 | 29 | 56 | 27 | 65 | 33 | 68 | 31 | 76 | 40 | 78 |
| 1803. | 19 | 48 | 19 | 53 | 25 | 66 | 36 | 72 | 38 | 69 | 49 | 74 |
| 1804. | 27 | 55 | 25 | 51 | 28 | 62 | 34 | 71 | 44 | 73 | 47 | 87 |
| 1805. | 25 | 48 | 23 | 54 | 29 | 62 | 35 | 64 | 37 | 72 | 41 | 75 |
| 1806. | 28 | 55 | 30 | 56 | 26 | 56 | 31 | 64 | 43 | 75 | 46 | 83 |
| 1807. | 23 | 51 | 25 | 57 | 25 | 55 | 31 | 77 | 44 | 84 | 48 | 77 |
| 1808. | 18 | 53 | 18 | 53 | 26 | 54 | 37 | 64 | 42 | 82 | 48 | 76 |
| 1809. | 20 | 55 | 34 | 57 | 33 | 62 | 29 | 57 | 36 | 78 | 45 | 78 |
| 1810. | 14 | 51 | 18 | 54 | 28 | 59 | 31 | 69 | 34 | 67 | 45 | 78 |
| 1820. | 30 | 53 | 26 | 52 | 28 | 66 | 36 | 67 | 39 | 70 | 45 | 85 |
| 1821. | 25 | 52 | 25 | 61 | 31 | 58 | 36 | 72 | 37 | 70 | 43 | 73 |
| 1822. | 31 | 51 | 34 | 54 | 35 | 66 | 35 | 64 | 45 | 75 | 50 | 84 |
| 1823. | 24 | ..... | ..... | ..... | ..... | ..... | ..... | ..... | 40 | 75 | 43 | 74 |
| 1824. | 25 | 52·5 | 28 | 52 | 28 | 56 | 28 | 66·5 | 42 | 73 | 43 | 74 |
| 1825. | 30 | 54 | 26 | 51 | 28 | 53 | 34 | 66 | 40 | 71·5 | 42 | 81 |
| 1826. | 16 | 47 | 32 | 54 | ..... | ..... | ..... | ..... | 36·5 | 72·5 | 49·8 | 87·5 |
| 1827. | 16 | 48·8 | 19 | 52·5 | 31·2 | 57·6 | 32·8 | 73·5 | 37·8 | 69·8 | 46·3 | 74·5 |
| 1828. | 28 | 54·5 | 29 | 55·2 | 29·1 | 61·3 | 32·8 | 70·7 | 42·7 | 72·1 | 49·3 | 78·4 |
| 1829. | 19·5 | 45·7 | 23·2 | 50·8 | 26·8 | 58·6 | 30·7 | 59·3 | 44·3 | 70·6 | 41·1 | 77·8 |
| 1830. | 17·2 | 42·7 | 17·7 | 56·3 | 32·7 | 65·7 | 29·7 | 72·0 | 42·6 | 77·3 | 46·6 | 76·7 |
| 1831. | 24·3 | 48·5 | 26·7 | 59·5 | 31·7 | 59·4 | 35·3 | 65·2 | 33·8 | 72·6 | 48·6 | 75·7 |
| 1832. | 27·8 | 48·7 | 28·3 | 49·6 | 30·7 | 55·3 | 36·7 | 67·0 | 38·4 | 74·7 | 46·8 | 76·7 |
| 1833. | 27·3 | 46·6 | 32·4 | 55·2 | 27·8 | 54·2 | 34·0 | 62·4 | 43·4 | 81·4 | 46·6 | 80·8 |
| 1834. | 32·5 | 55·2 | 29·3 | 54·7 | 30·7 | 57·8 | 33·2 | 64·3 | 43·0 | 75·0 | 47·3 | 86·7 |
| 1835. | 25·0 | 49·7 | 27·9 | 53·2 | 32·7 | 54·2 | 30·0 | 66·2 | 41·7 | 72·8 | 44·6 | 83·6 |
| 1836. | 17·5 | 53·4 | 25·3 | 50·6 | 31·8 | 64·4 | 32·2 | 61·3 | 35·3 | 69·5 | 47·7 | 82·6 |
| 1837. | 24·0 | 50·7 | 30·0 | 54·0 | 26·7 | 49·0 | 28·0 | 59·2 | 35·5 | 68·6 | 43·2 | 75·8 |
| 1838. | 11·4 | 50·2 | 24·8 | 48·7 | 31·0 | 58·3 | 29·8 | 64·2 | 36·2 | 73·3 | 44·2 | 79·7 |
| 1839. | 23·7 | 51·8 | 26·8 | 51·3 | 26·0 | 53·2 | 30·5 | 58·7 | 33·7 | 72·2 | 45·6 | 85·0 |
| 1840. | 22·3 | 54·2 | 27·8 | 50·8 | 30·7 | 53·7 | 34·4 | 72·2 | 41·3 | ..... | 48·3 | 83·0 |
| 1841. | 14·9 | 52·8 | 21·6 | 52·2 | 35·0 | 64·2 | 36·7 | 72·4 | 45·3 | 79·4 | 45·3 | 87·0 |
| 1842. | 27·3 | 44·6 | 32·0 | 53·0 | 33·6 | 58·5 | 34·2 | 69·3 | 41·8 | 78·3 | 52·7 | 83·6 |
| 1843. | 29·8 | 57·7 | 23·8 | 53·0 | 30·5 | 61·0 | 33·0 | 66·0 | 40·3 | 73·4 | 47·3 | 79·7 |
| | At the Royal Observatory, Greenwich. | | | | | | | | | | | |
| 1840. | ..... | ..... | ..... | ..... | ..... | ..... | ..... | ..... | ..... | ..... | ..... | ..... |
| 1841. | 4·0 | 53·0 | 12·4 | 54·6 | 29·5 | 66·9 | 31·8 | 76·5 | 41·2 | 82·8 | 40·3 | 78·5 |
| 1842. | 23·2 | 46·8 | 26·4 | 53·2 | 29·9 | 60·5 | 28·0 | 73·7 | 36·4 | 74·7 | 44·7 | 87·4 |
| 1843. | 24·0 | 57·0 | 20·3 | 51·9 | 26·5 | 63·7 | 27·2 | 70·8 | 37·3 | 69·5 | 42·9 | 77·3 |
| 1844. | 18·8 | 53·7 | 20·0 | 50·4 | 24·1 | 60·2 | 33·4 | 74·9 | 33·9 | 77·4 | 43·4 | 87·6 |
| 1845. | 24·4 | 51·3 | 7·7 | 48·5 | 13·1 | 59·4 | 29·5 | 70·3 | 34·4 | 68·2 | 43·8 | 86·0 |
| 1846. | 29·4 | 55·3 | 26·9 | 62·3 | 26·5 | 58·0 | 33·3 | 63·0 | 38·3 | 84·3 | 49·4 | 91·1 |
| 1847. | 23·0 | 52·7 | 10·2 | 55·0 | 16·9 | 64·2 | 27·0 | 63·8 | 36·0 | 86·2 | 41·0 | 80·4 |
| 1848. | 15·8 | 50·4 | 29·2 | 55·0 | 27·3 | 71·5 | 29·7 | 75·0 | 33·5 | 83·0 | 38·7 | 78·4 |
| 1849. | 20·0 | 56·4 | 26·8 | 58·0 | 27·7 | 60·7 | 28·6 | 64·3 | 36·8 | 75·0 | 38·6 | 80·7 |

By comparing the readings of the two places for the years 1841, 1842 and 1843, it grees below those at the Apartments of the Royal Society. In January 1841 the the difference is wholly attributable to the effect of the comparative heated water of places at some distance from and those near the river. The maximum temperatures 1841 at Somerset House I think must be erroneous.

maximum and minimum thermometers in each month during the whole time they Greenwich, from the year 1841 to 1849.

| Year. | July. | | August. | | September. | | October. | | November. | | December. | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | Reading of the thermometers in the month. | | Reading of the thermometers in the month. | | Reading of the thermometers in the month. | | Reading of the thermometers in the month. | | Reading of the thermometers in the month. | | Reading of the thermometers in the month. | |
| | Lowest. | Highest. | Lowest. | Highest. | Lowest. | Highest. | Lowest. | Highest. | Lowest. | Highest. | Lowest. | Highest. |
| | ° | ° | ° | ° | ° | ° | ° | ° | ° | ° | ° | ° |
| 1794. | 54 | 84 | 48 | 78 | 37 | 68 | 35 | 63 | 30·5 | 57 | 25·5 | 54 |
| 1795. | 46 | 76 | 51 | 79 | 45 | 78 | 42 | 68 | 28 | 56 | 34 | 56 |
| 1796. | 44·5 | 77·5 | 48 | 80 | 45 | 79 | 30 | 59 | 29 | 57 | 4 | 51 |
| 1797. | 48 | 85 | 48 | 76 | 42 | 71 | 35 | 63 | 27 | 57 | 29 | 56 |
| 1798. | 51 | 78 | 52 | 83 | 44 | 76 | 32 | 64 | 25 | 60 | 11 | 50 |
| 1799. | 48 | 77 | 47 | 73 | 42 | 72 | 35 | 63 | 32 | 58 | 17 | 50 |
| 1800. | 50 | 81 | 49 | 89 | 41 | 77 | 35 | 66 | 30 | 59 | 29 | 51 |
| 1801. | 47 | 79 | 51 | 79 | 46 | 73 | 34 | 66 | 26 | 60 | 23 | 52 |
| 1802. | 45 | 71 | 50 | 82 | 40 | 75 | 33 | 75 | 30 | 53 | 29 | 50 |
| 1803. | 51 | 86 | 47 | 81 | 38 | 75 | 38 | 67 | 31 | 57 | 21 | 55 |
| 1804. | 49 | 80 | 49 | 81 | 45 | 81·5 | 38 | 68 | 34 | 59 | 19 | 51 |
| 1805. | 50 | 79 | 51 | 79 | 43 | 79 | 35 | 63 | 31 | 55 | 25 | 54 |
| 1806. | 52 | 81 | 51 | 80 | 44 | 73 | 35 | 65 | 36 | 60 | 39 | 57 |
| 1807. | 48 | 85 | 52 | 80 | 38 | 72 | 39 | 68 | 28 | 56 | 23 | 51 |
| 1808. | 50 | 90·5 | 51 | 80 | 39 | 71 | 35 | 63 | 31 | 56 | 19 | 53 |
| 1809. | 50 | 78 | 49 | 79 | 40 | 72 | 35 | 65 | 29 | 54 | 32 | 54 |
| 1810. | 51 | 78 | 50 | 80 | 48 | 83 | 30 | 68 | | | | |
| 1820. | 50 | 80 | 46 | 77 | 38 | 73 | 39 | 65 | 31 | 56 | 25 | 57 |
| 1821. | 46 | 74 | 50 | 77 | 46 | 75 | 41 | 68 | 34 | 63 | 36 | 58 |
| 1822. | 53 | 76 | 50 | 80 | 45 | 70 | 41 | 66 | 38 | 61 | 23 | 54 |
| 1823. | 49 | 74 | 49 | 78 | 40 | 73 | 37 | 62 | 29 | 55 | 29 | 53 |
| 1824. | 51 | 81 | 50·5 | 77 | 37 | 81 | 31 | 65 | 29 | 60 | 31 | 54 |
| 1825. | 51 | 89 | 53 | 84 | 47 | 77 | 33 | 68 | 29 | 58 | 28 | 53·5 |
| 1826. | ..... | ..... | 55 | 81·2 | 43·8 | 72·3 | 37·6 | 67·8 | 26·8 | 52·3 | 32·2 | 53 |
| 1827. | 51·8 | 81·1 | 48·3 | 80·2 | 47·7 | 70·0 | 36·4 | 67·7 | 23·8 | 55·8 | 30·8 | 54·8 |
| 1828. | 46·8 | 78·7 | 49·8 | 72·7 | 44·9 | 72·8 | 36·5 | 63·3 | 25·7 | 58·4 | 33·8 | 55·3 |
| 1829. | 48·7 | 74·7 | 46·7 | 76·5 | 42·4 | 66·7 | 33·3 | 61·4 | 26·8 | 52·7 | 18·2 | 46·0 |
| 1830. | 48·8 | 85·8 | 46·0 | 77·7 | 43·8 | 69·8 | 35·2 | 66·5 | 33·0 | 58·5 | 15·8 | 47·2 |
| 1831. | 52·3 | 80·8 | 54·4 | 79·7 | 46·5 | 72·2 | 40·3 | 68·2 | 28·7 | 57·2 | 29·8 | 55·6 |
| 1832. | 49·6 | 81·2 | 47·0 | 81·8 | 41·6 | 72·9 | 39·4 | 68·2 | 36·3 | 59·3 | 32·3 | 55·8 |
| 1833. | 47·3 | 80·5 | 48·2 | 75·3 | 41·0 | 67·2 | 38·3 | 62·3 | 31·6 | 59·7 | 32·9 | 55·6 |
| 1834. | 51·4 | 86·7 | 46·2 | 85·3 | 46·8 | 74·0 | 34·4 | 70·2 | 33·2 | 61·5 | 29·2 | 54·5 |
| 1835. | 50·6 | 84·2 | 51·8 | 80·6 | 46·4 | 76·3 | 35·4 | 62·6 | 34·0 | 55·5 | 21·0 | 51·6 |
| 1836. | 46·2 | 85·2 | 48·4 | 73·4 | 40·7 | 69·6 | 30·0 | 61·2 | 31·3 | 56·7 | 27·4 | 55·7 |
| 1837. | 47·5 | 79·6 | 48·5 | 78·8 | 44·4 | 69·7 | 35·4 | 68·5 | 28·0 | 56·4 | 31·7 | 55·3 |
| 1838. | 49·6 | 79·0 | 46·5 | 76·0 | 42·8 | 69·5 | 32·8 | 63·5 | 30·0 | 57·7 | 29·8 | 55·0 |
| 1839. | 48·6 | 80·3 | 45·4 | 78·6 | 45·0 | 70·0 | 37·3 | 63·5 | 33·8 | 55·3 | 32·0 | 54·6 |
| 1840. | 49·4 | 77·2 | 52·4 | 80·0 | 41·7 | 75·7 | 35·3 | 60·7 | 30·3 | 60·6 | 21·2 | 55·5 |
| 1841. | 49·8 | 80·3 | 50·0 | 77·5 | 42·8 | 74·6 | 37·2 | 64·3 | 28·2 | 58·6 | 29·9 | 53·8 |
| 1842. | 50·4 | 82·7 | 50·0 | 87·0 | 44·4 | 76·0 | 34·0 | 60·7 | 35·6 | 55·5 | 34·7 | 57·5 |
| | At the Royal Observatory, Greenwich. | | | | | | | | | | | |
| 1840. | ..... | ..... | ..... | ..... | ..... | ..... | ..... | ..... | 23·8 | 61·2 | 16·4 | 55·2 |
| 1841. | 44·3 | 76·0 | 45·5 | 79·6 | 36·6 | 79·6 | 32·2 | 64·6 | 22·2 | 58·3 | 24·3 | 53·9 |
| 1842. | 45·5 | 78·8 | 47·5 | 90·5 | 41·1 | 75·8 | 28·3 | 60·9 | 31·1 | 55·9 | 30·8 | 58·2 |
| 1843. | 44·6 | 89·8 | 47·2 | 82·8 | 34·9 | 79·9 | 29·5 | 70·4 | 27·4 | 57·5 | 25·6 | 54·7 |
| 1844. | 47·1 | 87·4 | 43·8 | 75·4 | 34·8 | 78·0 | 30·8 | 67·4 | 27·4 | 58·1 | 21·1 | 49·3 |
| 1845. | 44·6 | 83·3 | 43·2 | 77·8 | 33·4 | 73·5 | 31·4 | 67·6 | 29·1 | 59·6 | 28·0 | 55·5 |
| 1846. | 49·1 | 93·3 | 47·5 | 92·0 | 39·2 | 86·4 | 35·0 | 67·7 | 23·4 | 61·5 | 18·8 | 49·9 |
| 1847. | 45·4 | 89·0 | 42·0 | 87·3 | 32·0 | 72·5 | 33·0 | 73·2 | 24·5 | 66·3 | 25·0 | 59·5 |
| 1848. | 42·2 | 85·3 | 42·5 | 75·5 | 32·8 | 78·8 | 32·4 | 74·0 | 25·2 | 57·8 | 21·8 | 62·8 |
| 1849. | 47·0 | 84·1 | 42·4 | 82·5 | 42·7 | 79·0 | 31·5 | 69·7 | 23·5 | 61·7 | 18·8 | 56·3 |

will be seen that the minimum temperatures at the Observatory are usually some de- reading at the Observatory was as low as 4°, whilst that at Somerset House was 14°·9; the Thames, and this difference is always shown at those low temperatures between at the Observatory are usually the higher, but not always so; the maximum in June

TABLE XXVII.—Showing the extreme readings of the thermometer in every year that self-registering thermometers were used at the Royal Society's Apartments, and from the year 1840 to 1849 at the Royal Observatory, Greenwich.

| Year. | At the Apartments of the Royal Society. | | | | |
|---|---|---|---|---|---|
| | Highest reading of the thermometer. | Lowest reading of the thermometer. | Difference or range of reading in the year. | Month and day of Highest readings. | Month and day of Lowest readings. |
| 1794. | 84·0 | 22·0 | 62·0 | On July 13. | On January 10. |
| 1795. | 81·5 | 7·0 | 74·5 | On May 23. | On January 25. |
| 1796. | 80·0 | 4·0 | 76·4 | On June 26 and August 22. | On December 25. |
| 1797. | 85·0 | 24·5 | 60·5 | On July 14. | On February 28. |
| 1798. | 86·0 | 11·0 | 75·0 | On June 28. | On December 29. |
| 1799. | 77·0 | 17·0 | 60·0 | On June 10, 30, July 6 and 8. | On December 31. |
| 1800. | 89·0 | 18·0 | 71·0 | On August 2. | On January 1. |
| 1801. | 80·0 | 23·0 | 57·0 | On June 29. | On December 20. |
| 1802. | 82·0 | 15·0 | 67·0 | On August 30. | On January 16. |
| 1803. | 86·0 | 19·0 | 67·0 | On July 2. | On January 26 and February 11. |
| 1804. | 87·0 | 19·0 | 68·0 | On June 25. | On December 24. |
| 1805. | 79·0 | 23·0 | 56·0 | On July 4, August 12 and Sept. 18. | On February 2. |
| 1806. | 83·0 | 26·0 | 57·0 | On June 10. | On March 13. |
| 1807. | 85·0 | 23·0 | 62·0 | On July 22. | On January 15 and December 8. |
| 1808. | 93·5 | 18·0 | 75·5 | On July 13. | On January 22 and February 15. |
| 1809. | 79·0 | 20·0 | 59·0 | On August 17. | On January 18 and 19. |
| 1810. | 83·0 | 14·0 | 69·0 | On September 2. | On January 17. |
| 1820. | 85·0 | 20·0 | 65·0 | On June 27. | On January 5. |
| 1821. | 77·0 | 25·0 | 52·0 | On August 5, 6, 22, 24 and 25. | On January 2, 3 and February 27. |
| 1822. | 84·0 | 23·0 | 61·0 | On June 10. | On December 30. |
| 1823. | 78·0 | 24·0 | 49·0 | On August 13. | On January 15. |
| 1824. | 81·0 | 25·0 | 56·0 | On July 13, 14 and September 1. | On January 14. |
| 1825. | 89·0 | 26·0 | 63·0 | On July 19. | On February 5. |
| 1826. | 87·5 | 16·0 | 71·5 | On June 27. | On January 16. |
| 1827. | 81·1 | 16·0 | 65·1 | On July 29. | On January 3. |
| 1828. | 78·7 | 25·7 | 53·0 | On July 3. | On November 12. |
| 1829. | 77·8 | 18·2 | 59·6 | On June 3. | On December 28. |
| 1830. | 85·8 | 15·8 | 70·0 | On July 30. | On December 25. |
| 1831. | 80·8 | 24·3 | 56·5 | On July 29. | On January 8. |
| 1832. | 81·8 | 27·8 | 54·0 | On August 10. | On January 5. |
| 1833. | 81·4 | 27·3 | 54·1 | On May 15. | On January 23. |
| 1834. | 86·7 | 29·2 | 57·5 | On June 21 and July 17. | On December 24. |
| 1835. | 84·2 | 21·0 | 63·2 | On July 28. | On December 25. |
| 1836. | 85·2 | 17·5 | 67·7 | On July 4. | On January 2. |
| 1837. | 79·6 | 24·0 | 55·6 | On July 28. | On January 2. |
| 1838. | 79·7 | 11·4 | 68·3 | On June 24. | On January 16. |
| 1839. | 85·0 | 23·7 | 61·3 | On June 20. | On January 30. |
| 1840. | 83·0 | 21·2 | 61·8 | On June 1. | On December 18. |
| 1841. | 87·0 | 14·9 | 72·1 | On June 20. | On January 9. |
| 1842. | 87·0 | 27·3 | 59·7 | On August 11. | On January 24. |
| | At the Royal Observatory, Greenwich. | | | | |
| 1841. | 82·8 | 4·0 | 78·8 | On May 27. | On January 9. |
| 1842. | 90·5 | 23·2 | 67·3 | On August 10. | On January 23. |
| 1843. | 89·8 | 20·3 | 69·5 | On July 6. | On February 15. |
| 1844. | 87·6 | 18·8 | 68·6 | On June 25. | On January 3. |
| 1845. | 86·0 | 7·7 | 78·3 | On June 13. | On February 11. |
| 1846. | 93·3 | 18·8 | 74·5 | On July 5. | On December 14 and 30. |
| 1847. | 89·0 | 10·2 | 78·8 | On July 12. | On February 11. |
| 1848. | 85·3 | 15·8 | 69·5 | On July 14. | On January 28. |
| 1849. | 84·1 | 18·8 | 65·3 | On July 8. | On December 29. |

From the particulars in this Table, it seems that the highest reading of the thermometer within the year has occurred three times in May, seventeen times in June, twenty-four times in July, ten times in August, and three times in September.

The lowest reading of the thermometer in the year has occurred twenty-eight times in January, nine times in February, once in March, once in November, and fourteen times in December.

TABLE XXVIII.—Showing the highest and lowest temperature during the period in each month.

| Month. | At the Apartments of the Royal Society. | | | | | At the Royal Observatory, Greenwich. | | | | |
|---|---|---|---|---|---|---|---|---|---|---|
| | The lowest reading of the thermometer. | The highest reading of the thermometer. | Difference of readings. | Mean of all the | | The lowest reading of the thermometer. | The highest reading of the thermometer. | Difference of readings. | Mean of all the | |
| | | | | Lowest readings. | Highest readings. | | | | Lowest readings. | Highest readings. |
| | ° | ° | ° | ° | ° | ° | ° | ° | ° | ° |
| January ... | 7·0 | 57·7 | 50·7 | 22·6 | 51·0 | 4·0 | 57·0 | 53·0 | 20·2 | 52·9 |
| February... | 17·7 | 61·0 | 43·3 | 26·1 | 53·7 | 7·7 | 62·3 | 54·6 | 19·9 | 54·3 |
| March..... | 23·0 | 66·0 | 43·0 | 29·2 | 58·5 | 13·1 | 71·5 | 58·4 | 24·6 | 62·7 |
| April ..... | 27·0 | 77·0 | 50·0 | 32·8 | 66·5 | 27·0 | 76·5 | 49·5 | 29·8 | 70·3 |
| May ..... | 31·0 | 84·0 | 53·0 | 39·3 | 73·8 | 33·5 | 86·2 | 52·7 | 36·4 | 77·9 |
| June ..... | 40·0 | 87·5 | 47·5 | 45·5 | 79·5 | 38·6 | 87·6 | 49·0 | 42·5 | 83·0 |
| July..... | 44·5 | 93·5 | 49·0 | 49·3 | 80·5 | 42·2 | 93·3 | 51·1 | 45·5 | 85·2 |
| August ... | 45·4 | 89·0 | 43·6 | 49·4 | 79·3 | 42·0 | 92·0 | 50·0 | 44·5 | 82·6 |
| September | 37·0 | 83·0 | 46·0 | 42·9 | 73·6 | 32·0 | 86·4 | 54·4 | 36·3 | 78·2 |
| October ... | 30·0 | 75·0 | 45·0 | 35·5 | 65·2 | 28·3 | 74·0 | 45·7 | 31·4 | 68·4 |
| November | 23·8 | 63·0 | 39·2 | 30·4 | 57·4 | 22·2 | 66·3 | 44·1 | 26·0 | 59·6 |
| December | 4·0 | 58·0 | 54·0 | 25·9 | 53·6 | 16·4 | 62·8 | 46·4 | 23·5 | 55·5 |

The lowest reading, as observed at the Apartments of the Royal Society, was 4°; it occurred in the night of December 24, 1796 (at this time the reading in the environs of London was—6°). The highest reading was 89°; the difference of these readings is 85°.

The lowest reading, as observed at the Royal Observatory within the years 1841 to 1849, was 4°, and the highest was 93°·3; the difference of these readings is 89°·3.

TABLE XXIX.—Showing the extreme range of the thermometer in every month during the time self-registering instruments were in use at the Apartments of the Royal Society, and at the Royal Observatory, Greenwich, from 1840.

| Year. | At the Apartments of the Royal Society. Extreme range of readings of the thermometer in each month. | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | January. | February. | March. | April. | May. | June. | July. | August. | September. | October. | November. | December. |
| 1794. | 29° | 21° | 22° | 35° | 31° | 33° | 30° | 30° | 31° | 28° | 26°·5 | 28°·5 |
| 1795. | 39 | 27 | 30·5 | 25 | 45·5 | 36·5 | 30 | 28 | 33 | 26 | 28 | 22 |
| 1796. | 20 | 26 | 33·5 | 34 | 26 | 35 | 33 | 32 | 34 | 29 | 28 | 47 |
| 1797. | 24 | 25·5 | 26·5 | 31 | 45 | 33 | 37 | 28 | 29 | 28 | 30 | 27 |
| 1798. | 25 | 30 | 28 | 39 | 33 | 39 | 27 | 31 | 32 | 32 | 35 | 39 |
| 1799. | 30 | 38 | 28 | 32 | 34 | 34 | 29 | 26 | 30 | 28 | 26 | 33 |
| 1800. | 33 | 28 | 34 | 24 | 35 | 32 | 31 | 40 | 36 | 31 | 29 | 22 |
| 1801. | 30 | 32 | 28 | 37 | 32 | 37 | 32 | 28 | 27 | 32 | 34 | 29 |
| 1802. | 33 | 27 | 38 | 35 | 45 | 38 | 26 | 32 | 35 | 42 | 23 | 21 |
| 1803. | 29 | 34 | 41 | 36 | 31 | 25 | 35 | 34 | 37 | 29 | 26 | 34 |
| 1804. | 28 | 26 | 34 | 37 | 29 | 40 | 31 | 32 | 36·5 | 30 | 25 | 32 |
| 1805. | 23 | 31 | 33 | 29 | 35 | 34 | 29 | 28 | 36 | 28 | 24 | 29 |
| 1806. | 27 | 26 | 30 | 33 | 32 | 37 | 29 | 29 | 29 | 30 | 24 | 18 |
| 1807. | 28 | 32 | 30 | 46 | 40 | 29 | 37 | 28 | 34 | 29 | 28 | 28 |
| 1808. | 35 | 35 | 28 | 37 | 40 | 28 | 43·5 | 29 | 32 | 28 | 25 | 34 |
| 1809. | 35 | 23 | 29 | 28 | 42 | 33 | 28 | 30 | 32 | 30 | 25 | 22 |
| 1810. | 37 | 36 | 31 | 38 | 33 | 33 | 27 | 30 | 35 | 38 | | |
| 1820. | 33 | 26 | 38 | 31 | 31 | 40 | 30 | 31 | 35 | 26 | 25 | 32 |
| 1821. | 27 | 36 | 27 | 36 | 33 | 30 | 28 | 27 | 29 | 27 | 29 | 22 |
| 1822. | 20 | 20 | 31 | 29 | 30 | 34 | 23 | 30 | 25 | 25 | 23 | 31 |
| 1823. | ..... | ..... | ..... | ..... | 35 | 31 | 25 | 29·0 | 33 | 25 | 26 | 24 |
| 1824. | 27·5 | 24 | 28 | 38·5 | 31 | 31 | 30 | 26·5 | 44 | 34 | 31 | 23 |
| 1825. | 24 | 25 | 25 | 32 | 31·5 | 39 | 38 | 31·0 | 30 | 35 | 29 | 25·5 |
| 1826. | 31 | 22 | ..... | ..... | 36 | 37·7 | ..... | 26·2 | 28·5 | 30·2 | 25·5 | 20·8 |
| 1827. | 32·8 | 33·5 | 26·4 | 40·7 | 32 | 28·2 | 29·3 | 31·9 | 22·3 | 31·3 | 32·0 | 24·0 |
| 1828. | 26·5 | 26·2 | 32·2 | 37·9 | 29·4 | 29·1 | 31·9 | 22·9 | 27·9 | 26·8 | 32·7 | 21·5 |
| 1829. | 26·2 | 27·6 | 31·8 | 28·6 | 26·3 | 36·7 | 26·0 | 29·8 | 24·3 | 28·1 | 25·9 | 27·8 |
| 1830. | 25·5 | 38·6 | 33·0 | 42·3 | 34·7 | 30·1 | 37·0 | 31·7 | 26·0 | 31·3 | 25·5 | 31·4 |
| 1831. | 24·2 | 32·8 | 27·7 | 29·9 | 38·8 | 27·1 | 28·5 | 25·3 | 25·7 | 27·9 | 28·5 | 25·8 |
| 1832. | 20·9 | 21·3 | 24·6 | 30·3 | 36·3 | 29·9 | 31·6 | 34·8 | 31·3 | 28·8 | 23·0 | 23·5 |
| 1833. | 19·3 | 22·8 | 26·4 | 28·4 | 38·0 | 34·2 | 33·2 | 27·1 | 26·2 | 24·0 | 28·1 | 22·7 |
| 1834. | 22·7 | 25·4 | 27·1 | 31·1 | 32·0 | 39·4 | 35·3 | 39·1 | 27·2 | 35·8 | 28·3 | 25·3 |
| 1835. | 24·7 | 25·3 | 21·5 | 36·2 | 31·1 | 39·0 | 33·6 | 28·8 | 29·9 | 27·2 | 20·6 | 30·6 |
| 1836. | 35·9 | 25·3 | 32·6 | 29·1 | 34·2 | 34·9 | 39·0 | 25·0 | 28·9 | 31·2 | 25·4 | 28·3 |
| 1837. | 26·7 | 24·0 | 22·3 | 31·2 | 33·1 | 32·6 | 32·1 | 30·3 | 25·3 | 33·1 | 28·4 | 23·6 |
| 1838. | 38·8 | 23·9 | 27·3 | 34·4 | 37·1 | 35·5 | 29·4 | 29·5 | 26·7 | 30·7 | 27·7 | 25·2 |
| 1839. | 28·1 | 24·5 | 27·2 | 28·2 | 38·5 | 39·4 | 31·7 | 33·2 | 25·0 | 26·2 | 21·5 | 22·6 |
| 1840. | 31·9 | 23·0 | 23·0 | 37·8 | ..... | 34·7 | 27·8 | 27·6 | 34·0 | 25·4 | 30·3 | 34·3 |
| 1841. | 37·9 | 30·6 | 29·2 | 35·7 | 34·1 | 41·7 | 30·5 | 27·5 | 31·8 | 27·1 | 30·4 | 25·9 |
| 1842. | 17·3 | 21·0 | 24·9 | 35·1 | 36·5 | 30·9 | 32·3 | 37·0 | 31·6 | 26·7 | 19·9 | 22·8 |
| 1843. | 27·9 | 29·2 | 30·5 | 33·0 | 33·1 | 32·4 | | | | | | |
| | At the Royal Observatory, Greenwich. | | | | | | | | | | | |
| 1840. | ..... | ..... | ..... | ..... | ..... | ..... | ..... | ..... | ..... | ..... | 37·4 | 38·8 |
| 1841. | 49·0 | 42·2 | 37·4 | 44·7 | 41·6 | 38·2 | 31·7 | 34·1 | 43·0 | 32·4 | 36·1 | 29·6 |
| 1842. | 23·6 | 26·8 | 30·6 | 45·7 | 38·3 | 42·7 | 33·3 | 43·0 | 34·7 | 32·6 | 24·8 | 27·4 |
| 1843. | 33·0 | 31·6 | 37·2 | 43·6 | 32·2 | 34·4 | 45·2 | 35·6 | 45·9 | 41·9 | 30·1 | 29·1 |
| 1844. | 34·9 | 30·4 | 36·1 | 41·5 | 43·5 | 44·2 | 40·3 | 32·6 | 43·2 | 36·6 | 30·7 | 28·2 |
| 1845. | 26·9 | 40·8 | 46·3 | 40·8 | 33·8 | 42·2 | 38·7 | 34·6 | 40·1 | 36·2 | 30·5 | 27·5 |
| 1846. | 25·9 | 35·4 | 31·5 | 29·7 | 46·0 | 41·7 | 44·2 | 44·5 | 47·2 | 32·7 | 38·1 | 31·1 |
| 1847. | 29·7 | 44·8 | 47·3 | 36·8 | 50·2 | 39·4 | 43·6 | 45·3 | 40·5 | 40·2 | 41·8 | 34·5 |
| 1848. | 34·6 | 25·8 | 44·2 | 45·3 | 49·5 | 39·7 | 43·1 | 33·0 | 46·0 | 41·6 | 32·6 | 41·0 |
| 1849. | 36·4 | 31·2 | 33·0 | 35·7 | 38·2 | 42·1 | 37·1 | 40·1 | 36·3 | 38·2 | 38·2 | 35·9 |

TABLE XXX.—Showing the mean daily range of temperature in each month.

| Year. | At the Apartments of the Royal Society. The average daily range of temperature. | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | January. | February. | March. | April. | May. | June. | July. | August. | September. | October. | November. | December. |
| 1794. | 6·5 | 5·9 | 10·8 | 13·1 | 13·6 | 15·4 | 16·5 | 14·9 | 10·5 | 9·1 | 7·5 | 4·8 |
| 1795. | 6·7 | 6·2 | 9·7 | 10·9 | 15·8 | 12·4 | 13·1 | 15·1 | 14·8 | 9·3 | 8·7 | 5·7 |
| 1796. | 7·0 | 8·0 | 11·3 | 14·8 | 14·2 | 15·5 | 15·0 | 16·5 | 12·8 | 8·6 | 6·2 | 7·3 |
| 1797. | 5·3 | 4·0 | 11·4 | 12·7 | 16·3 | 16·7 | 19·3 | 16·2 | 13·1 | 9·0 | 9·2 | 7·6 |
| 1798. | 7·1 | 9·6 | 10·6 | 15·4 | 14·7 | 17·6 | 15·9 | 15·8 | 12·6 | 10·0 | 7·5 | 5·8 |
| 1799. | 6·4 | 9·1 | 9·0 | 10·0 | 13·5 | 15·2 | 13·5 | 14·3 | 13·1 | 9·7 | 6·9 | 4·0 |
| 1800. | 6·0 | 7·6 | 9·4 | 10·4 | 13·4 | 13·6 | 17·6 | 17·6 | 12·0 | 10·6 | 8·2 | 4·9 |
| 1801. | 7·9 | 7·1 | 9·6 | 16·0 | 16·1 | 16·2 | 15·8 | 16·0 | 11·7 | 10·0 | 7·3 | 7·2 |
| 1802. | 6·2 | 7·7 | 12·9 | 15·3 | 7·8 | 16·0 | 15·6 | 17·8 | 16·5 | 12·4 | 6·6 | 7·2 |
| 1803. | 4·4 | 7·4 | 11·5 | 13·4 | 12·7 | 13·2 | 12·3 | 16·1 | 16·9 | 9·9 | 8·0 | 5·2 |
| 1804. | 6·0 | 7·3 | 9·4 | 6·4 | 14·4 | 16·7 | 11·8 | 13·7 | 13·2 | 10·5 | 6·1 | 4·9 |
| 1805. | 5·3 | 8·4 | 11·0 | 13·2 | 14·6 | 15·1 | 14·0 | 14·0 | 13·7 | 8·9 | 8·0 | 6·8 |
| 1806. | 7·2 | 8·2 | 7·5 | 10·5 | 15·2 | 16·7 | 13·8 | 14·7 | 13·1 | 9·6 | 7·6 | 5·9 |
| 1807. | 7·3 | 8·8 | 10·6 | 11·1 | 13·1 | 15·7 | 15·3 | 13·7 | 12·7 | 10·0 | 8·1 | 6·7 |
| 1808. | 7·3 | 8·4 | 8·1 | 12·3 | 15·5 | 14·5 | 17·1 | 14·1 | 11·7 | 10·6 | 6·8 | 5·4 |
| 1809. | 6·5 | 8·2 | 10·3 | 11·7 | 15·0 | 15·9 | 13·8 | 9·9 | 11·6 | 9·1 | 7·6 | 6·5 |
| 1810. | 5·4 | 6·5 | 9·9 | 12·7 | 14·5 | 17·3 | 14·9 | 14·9 | 12·8 | 11·1 | ..... | |
| 1820. | 7·4 | 7·7 | 13·1 | 14·6 | 14·4 | 13·7 | 12·5 | 14·1 | 14·4 | 11·3 | 8·3 | 6·8 |
| 1821. | 8·1 | 9·9 | 11·0 | 13·3 | 15·6 | 13·4 | 13·3 | 13·1 | 11·3 | 11·8 | 9·7 | 9·6 |
| 1822. | 10·2 | 10·2 | 11·5 | 11·4 | 12·4 | 15·3 | 11·3 | 11·2 | 10·9 | 8·3 | 7·0 | 6·8 |
| 1823. | ..... | ..... | ..... | ..... | 14·5 | 16·5 | 12·3 | 11·7 | 12·9 | 8·9 | 4·8 | 5·1 |
| 1824. | 5·1 | 6·1 | 8·4 | 10·9 | 12·0 | 13·5 | 14·7 | 12·2 | 10·2 | 8·8 | 8·2 | 6·7 |
| 1825. | 6·0 | 7·5 | 8·8 | 14·5 | 14·6 | 17·8 | 14·6 | 13·5 | 10·3 | 8·2 | 8·1 | 4·7 |
| 1826. | 7·5 | 7·5 | ..... | 14·2 | 14·5 | 18·2 | ..... | 12·4 | 11·0 | 9·1 | 7·2 | 4·9 |
| 1827. | 8·0 | 8·2 | 9·6 | 12·0 | 12·5 | 14·7 | 15·3 | 13·6 | 10·8 | 9·3 | 8·5 | 8·1 |
| 1828. | 7·5 | 6·8 | 11·0 | 11·9 | 14·2 | 14·3 | 13·2 | 12·7 | 12·2 | 10·8 | 8·1 | 6·6 |
| 1829. | 6·2 | 7·3 | 9·8 | 11·8 | 16·5 | 15·5 | 13·6 | 11·4 | 11·3 | 8·1 | 8·2 | 5·2 |
| 1830. | 5·7 | 9·6 | 12·4 | 13·8 | 14·8 | 13·2 | 14·9 | 14·6 | 11·9 | 11·4 | 7·8 | 7·2 |
| 1831. | 6·4 | 8·7 | 9·9 | 12·1 | 15·9 | 14·3 | 18·3 | 13·3 | 12·3 | 8·5 | 9·8 | 5·4 |
| 1832. | 6·3 | 7·9 | 10·8 | 14·4 | 15·3 | 14·3 | 15·1 | 14·5 | 14·4 | 9·5 | 7·1 | 8·0 |
| 1833. | 6·2 | 8·5 | 9·7 | 13·0 | 17·5 | 16·1 | 15·4 | 15·4 | 13·1 | 11·2 | 8·7 | 9·5 |
| 1834. | 6·5 | 9·9 | 10·9 | 14·1 | 17·2 | 17·5 | 15·4 | 14·9 | 13·2 | 12·0 | 8·0 | 7·5 |
| 1835. | 7·8 | 10·6 | 11·1 | 13·4 | 14·5 | 16·1 | 17·5 | 15·4 | 13·0 | 9·1 | 6·0 | 6·0 |
| 1836. | 9·3 | 8·3 | 10·3 | 10·8 | 15·9 | 13·7 | 14·8 | 14·4 | 10·9 | 8·2 | 8·9 | 6·4 |
| 1837. | 7·4 | 8·5 | 8·7 | 9·7 | 13·2 | 14·7 | 15·0 | 13·4 | 11·5 | 12·7 | 11·8 | 6·8 |
| 1838. | 7·3 | 7·2 | 11·1 | 11·7 | 15·5 | 15·0 | 14·8 | 12·6 | 11·1 | 10·4 | 7·9 | 6·0 |
| 1839. | 8·6 | 10·6 | 6·8 | 6·3 | 15·5 | 15·3 | 13·2 | 13·2 | 10·5 | 7·0 | 4·2 | 3·8 |
| 1840. | 6·6 | 5·9 | 5·8 | 10·2 | ..... | 15·7 | 14·9 | 14·8 | 13·3 | 11·6 | 9·9 | 7·3 |
| 1841. | 7·6 | 5·9 | 12·7 | 13·2 | 15·6 | 17·5 | 14·0 | 12·8 | 15·6 | 9·9 | 9·0 | 8·3 |
| 1842. | 6·1 | 8·0 | 9·9 | 12·7 | 16·1 | 18·3 | 18·0 | 15·2 | 12·1 | 10·5 | 7·5 | 8·6 |
| 1843. | 8·0 | 6·7 | 10·4 | 13·9 | 16·1 | 15·7 | | | | | | |
| | At the Royal Observatory, Greenwich. | | | | | | | | | | | |
| 1840. | ..... | ..... | ..... | ..... | ..... | ..... | ..... | ..... | ..... | ..... | 11·0 | 9·0 |
| 1841. | 11·1 | 9·1 | 17·5 | 16·5 | 21·3 | 18·8 | 15·6 | 16·3 | 16·0 | 11·7 | 10·7 | 9·4 |
| 1842. | 6·4 | 10·4 | 10·9 | 16·1 | 16·7 | 22·2 | 17·7 | 20·3 | 12·8 | 13·2 | 7·9 | 8·2 |
| 1843. | 7·9 | 7·5 | 12·4 | 15·4 | 14·7 | 15·2 | 15·6 | 16·4 | 17·4 | 12·8 | 10·2 | 6·6 |
| 1844. | 8·7 | 10·5 | 12·1 | 21·0 | 18·6 | 19·9 | 16·2 | 15·4 | 15·3 | 12·4 | 7·4 | 5·4 |
| 1845. | 6·4 | 8·7 | 11·1 | 16·8 | 14·2 | 18·2 | 14·9 | 14·8 | 15·6 | 13·3 | 10·9 | 9·9 |
| 1846. | 7·7 | 8·3 | 12·7 | 13·1 | 16·6 | 22·5 | 17·5 | 15·5 | 18·0 | 10·4 | 8·0 | 10·3 |
| 1847. | 8·8 | 11·6 | 16·0 | 18·3 | 21·2 | 19·4 | 23·3 | 21·0 | 18·7 | 14·0 | 11·4 | 9·7 |
| 1848. | 8·3 | 10·7 | 14·3 | 16·7 | 30·5 | 17·7 | 22·5 | 18·5 | 20·9 | 16·5 | 15·7 | 12·7 |
| 1849. | 10·8 | 12·9 | 13·8 | 16·0 | 16·3 | 20·6 | 22·6 | 20·2 | 17·5 | 15·1 | 11·7 | 9·1 |

TABLE XXXI.—Showing the mean monthly minimum temperature by night, the mean monthly maximum temperature by day, the mean daily and monthly range of temperature, at the Apartments of the Royal Society, and at the Royal Observatory, Greenwich, together with the increase of temperature month by month, by night and by day.

| Month. | Mean of all the minimum readings, or of the lowest temperature by night at the | | Higher mean minimum reading at the Royal Society. | Mean of all the maximum readings, or of the highest temperature by day at the | | Lower mean maximum reading at the Royal Society. | The mean daily range of temperature at the | | Less daily range at the Royal Society. | The mean monthly range of temperature at the | | Less monthly range at the Royal Society. | Monthly increase in the mean | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | Royal Society. | Royal Observatory. | | Royal Society. | Royal Observatory. | | Royal Society. | Royal Observatory. | | Royal Society. | Royal Observatory. | | Temperature of the air. | Of the lowest temperature by night | | Of the highest temperature by day | |
| | | | | | | | | | | | | | | At the Royal Society. | At the Royal Observatory. | At the Royal Society. | At the Royal Observatory. |
| December ... | ° ..... | ° ..... | ° ..... | ° ..... | ° ..... | ° ..... | ° ..... | ° ..... | ° ..... | ° ..... | ° ..... | ° ..... | ° | ° | ° | ° | ° |
| January ..... | 34·4 | 33·1 | 1·3 | 46·2 | 42·2 | −3·0 | 6·8 | 8·5 | 1·7 | 28·4 | 32·7 | 4·3 | −3·1 | −3·1 | −1·5 | −2·7 | −1·6 |
| February..... | 36·4 | 33·6 | 2·8 | 44·3 | 44·0 | −0·3 | 7·9 | 9·9 | 2·0 | 27·6 | 34·3 | 6·7 | +2·5 | +2·0 | +0·5 | +3·1 | +1·8 |
| March..... | 37·8 | 36·3 | 1·5 | 48·2 | 50·3 | 2·1 | 10·2 | 13·4 | 3·2 | 29·3 | 38·2 | 8·9 | +2·7 | +1·4 | +2·7 | +3·6 | +6·3 |
| April ..... | 42·5 | 39·2 | 3·3 | 54·7 | 56·8 | 2·1 | 12·3 | 16·7 | 4·4 | 33·7 | 40·5 | 6·8 | +4·8 | +4·7 | +2·9 | +7·0 | +6·5 |
| May ..... | 48·3 | 45·7 | 2·6 | 63·1 | 66·3 | 3·5 | 14·8 | 18·9 | 4·1 | 34·8 | 41·5 | 6·7 | +6·9 | +5·8 | +6·5 | +8·2 | +8·4 |
| June ..... | 53·1 | 49·5 | 3·6 | 68·6 | 72·6 | 4·0 | 15·5 | 19·4 | 3·9 | 34·0 | 40·5 | 6·5 | +5·4 | +4·8 | +3·6 | +5·5 | +7·4 |
| July ..... | 56·6 | 53·2 | 3·4 | 71·4 | 73·1 | 1·7 | 14·9 | 18·4 | 3·5 | 31·2 | 39·7 | 8·5 | +3·3 | +3·5 | +3·7 | +2·8 | +0·5 |
| August ..... | 56·9 | 53·4 | 3·5 | 70·8 | 72·1 | 1·3 | 14·1 | 17·6 | 3·5 | 29·9 | 38·1 | 8·2 | −0·8 | 0·0 | +0·2 | −0·6 | −1·0 |
| September... | 52·6 | 49·4 | 3·2 | 65·1 | 67·3 | 2·2 | 12·5 | 17·0 | 4·5 | 30·7 | 41·8 | 11·1 | −4·2 | −4·0 | −4·0 | −5·7 | −4·6 |
| October ..... | 46·8 | 43·6 | 3·2 | 56·7 | 57·6 | 0·9 | 9·9 | 13·3 | 3·4 | 29·5 | 36·9 | 7·4 | −7·0 | −5·8 | −5·8 | −8·4 | −9·7 |
| November ... | 40·4 | 38·6 | 1·8 | 48·2 | 49·7 | 1·5 | 8·0 | 10·5 | 2·5 | 27·0 | 34·0 | 7·0 | −6·9 | −6·4 | −4·9 | −8·5 | −7·9 |
| December ... | 37·5 | 34·6 | 2·9 | 43·9 | 44·0 | 0·1 | 6·4 | 9·0 | 2·6 | 27·1 | 32·3 | 5·2 | −3·6 | −2·9 | −4·1 | −4·3 | −5·7 |

The successive differences shown here between the results at the Apartments of the Royal Society and at the Royal Observatory, are harmonious with the differences exhibited in Table XIII. and following remarks, between the temperatures of the water of the Thames and those of the air at Greenwich, but of less amount, and they indicate the great influence the presence of a tidal river has upon the meteorological elements of the district through which it passes.

The subjects of this paper are the determination of mean numerical values, and the establishment of the laws of periodic variation from the long series of observations which were taken under the direction of this Society, combined with that still being made at Greenwich. I have not attempted to deduce any rules for non-periodic variations.

It is most fortunate that through all reports this series of observations continued unbroken for so many years, and that it did not cease till that at Greenwich had been in operation for two or three years.

The number of observations treated of in this paper exceeds 200,000, spread nearly equally over seventy-nine years, and the results generally are important additions to science. I consider the determination of the mean temperature at Greenwich as a real addition; it is probably the best determination of this element of any spot on the globe, and it will help to an accurate knowledge of the mean temperature of its surface.

I may however here remark, that none of the mean results in this paper could have been calculated if observations at equal intervals had not been taken throughout the twenty-four hours and continued for a few years. The observations at Greenwich have supplied this want. It was upon them, taken for five years, I based my determinations of curve of hourly mean temperature, and by this means have made all the observations available.

As it is difficult to have instruments read more frequently than twice or thrice in a day, yet, to make these available, it is necessary that the laws of diurnal changes of temperature be known; and where such is not the case, an effort should be made in all countries to have a series of hourly or bi-hourly observations made for a few years, so as to be able to deduce useful results. Such series of frequent observations need not be made near each other, as it is found that the observations made over a considerable extent of country are subject to the same general laws.

# XXX. *On the Dynamical Stability and on the Oscillations of Floating Bodies.*

*By the Rev.* Henry Moseley, *M.A., F.R.S.,*
*Corresponding Member of the Institute of France.*

Received January 24,—Read June 13, 1850.

If a body be made, by the action of certain disturbing forces, to pass from one position of equilibrium into another, and if in each of the intermediate positions these forces are in excess of the forces opposed to its motion, it is obvious that, by reason of this excess, the motion will be continually accelerated, and that the body will reach its second position with a certain finite velocity, whose effect (measured under the form of *vis viva*) will be to carry it beyond that position. This however passed, the case will be reversed, the resistances will be in excess of the moving forces, and the body's velocity being continually diminished and eventually destroyed, it will, after resting for an instant, again return towards the position of equilibrium through which it had passed. It will not however finally rest in this position until it has completed other oscillations about it. Now the amplitude of the first oscillation of the body beyond the position in which it is finally to rest, being its greatest amplitude of oscillation, involves practically an important condition of its stability; for it may be an amplitude sufficient to carry the body into its next adjacent position of equilibrium, which being, of necessity, a position of unstable equilibrium, the motion will be yet further continued and the body overturned. Different bodies requiring moreover different amounts of work to be done upon them to produce in all the same amplitude of oscillation, that is (relatively to that amplitude) the most stable which requires the greatest amount of work to be so done upon it. It is this condition of stability, dependent upon dynamical considerations, to which, in the following paper, the name of dynamical stability is given.

I cannot find that the question has before been considered in this point of view, but only in that which determines whether any given position be one of stable, unstable or mixed equilibrium; or which determines what pressure is necessary to retain the body at any given inclination from such a position.

1. To the discussion of the conditions of the dynamical stability of a body the principle of *vis viva* readily lends itself. That principle*, when translated into a language which the labours of M. Poncelet have made familiar to the uses of practical science, may be stated as follows:—

* See Poisson, Mécanique, chap. ix. Art. 565; Poncelet, Mécanique Industrielle, *passim*; Mechanical Principles of Engineering by the author of this paper, Art. 129.

"When, being acted upon by given forces, a body or system of bodies has been moved from a state of rest, the difference between the aggregate *work* of those forces whose tendencies are *in* the directions in which their points of application have been moved, and that of the forces whose tendencies are in the opposite direction, is equal to one-half the *vis viva* of the system."

Thus, if $\Sigma u_1$ be taken to represent the aggregate work of the forces by which a body has been displaced from a position in which it was at rest, and $\Sigma u_2$ the aggregate work (during this displacement) of the other forces applied to it; and if the terms which compose $\Sigma u_1$ and $\Sigma u_2$ be understood to be taken positively or negatively, according as the tendencies of the corresponding forces are in the directions in which their points of application have been made to move or in the opposite directions; then representing the aggregate *vis viva* of the body by $\frac{1}{g}\Sigma wv^2$

$$\Sigma u_1+\Sigma u_2=\frac{1}{2g}\Sigma wv^2, \quad \ldots\ldots\ldots\ldots\ldots\ldots \quad (1.)$$

Now $\Sigma u_2$ representing the aggregate work of those forces which acted upon the body in the position from which it has been moved, may be supposed to be known; $\Sigma u_1$ may therefore be determined in terms of the *vis viva*, or conversely.

2. In the extreme position into which the body is made to oscillate and from which it begins to return, it, for an instant, *rests*. In this position, therefore, its *vis viva* disappears, and we have

$$\Sigma u_1+\Sigma u_2=0. \quad \ldots\ldots\ldots\ldots\ldots\ldots \quad (2.)$$

This equation, in which $\Sigma u_1$ and $\Sigma u_2$ are functions of the impressed forces and of the inclination, determines the extreme position into which the body is made to roll by the action of given disturbing forces; or, conversely, it determines the forces by which it may be made to roll into a given extreme position.

3. The position in which it will finally *rest* is determined by the *maximum* value of $\Sigma u_1+\Sigma u_2$ in equation 1; for, by a well-known property, the *vis viva* of a system* attains a maximum value when it passes through a position of stable, and a minimum, when it passes through a position of unstable equilibrium. The extreme position into which the body oscillates is therefore essentially different from that in which it will finally rest.

4. Different bodies, requiring different amounts of work to be done upon them to bring them to the same given inclination, *that* is (relatively to that inclination) the most stable, which requires the greatest amount of work to be so done upon it, or in respect to which $\Sigma u_1$ is the greatest. If, instead of all being brought to the same given inclination, each is brought into a position of unstable equilibrium, the corresponding value of $\Sigma u_1$ represents the amount of work which must be done upon it to *overthrow* it, and may be considered to measure its *absolute*, as the former value

* Poisson, Mécanique, Art. 571.

measures its *relative* dynamical stability*. The absolute dynamical stability of a body thus measured I propose to represent by the symbol U, and its relative dynamical stability, as to the inclination $\theta$, by $U(\theta)$.

The measure of the absolute dynamical stability of a body is the maximum value of its relative stability, or U the maximum of $U(\theta)$; for whilst the body is made to incline from its position of stable equilibrium, it continually tends to return to it until it passes through a position of unstable equilibrium, when it tends to recede from it; the aggregate amount of work necessary to produce this inclination must therefore continually increase until it passes through that position and afterwards diminish.

5. The work opposed by the weight of a body to any change in its position is measured by the product of the vertical elevation of its centre of gravity by its weight†. Representing therefore by W the weight of the body, and by $\Delta H$ the vertical displacement of its centre of gravity when it is made to incline through an angle $\theta$, and observing that the displacement of this point is in a direction opposite to that in which the force applied to it acts, we have $\Sigma u_2 = -W.\Delta H$, and by equation 2,

$$U(\theta) - W.\Delta H = 0. \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (3.)$$

If therefore no other force than its weight be opposed to a body's being overthrown, its absolute dynamical stability, when resting on a rigid surface, is measured by *the product of its weight by the height through which its centre of gravity must be raised to bring it from a stable into an unstable position of equilibrium.*

6. *The Dynamical Stability of Floating Bodies.*—The action of gusts of wind upon a ship or of blows of the sea being measured in their effects upon it by their work, that vessel is the most stable under the influence of these, or will roll and pitch the least (other things being the same), which requires the greatest amount of work to be done upon it to bring it to a given inclination; or, in respect to which the relative dynamical stability $U(\theta)$ is the greatest for a given value of $\theta$. In another sense, that ship may be said to be the most stable which would require the greatest amount of work to be done upon it to bring it into a position from which it would not again right itself, or whose absolute dynamical stability U is the greatest. Subject to the one condition, the ship will *roll* the least, and subject to the other, it will be the least likely to roll *over*.

Thus the theory of dynamical stability involves a question of naval construction, and it is principally with reference to this question that I have entered on the discussion of it.

* It is obvious that the absolute dynamical stability of a body may be greater than that of another, whilst its stability, relatively to a given inclination, is less; *less* work being required to incline it than the other at that angle, but more, entirely to overthrow it.

† Poncelet, Mécanique Industrielle, 2me partie, Art. 50; Moseley, Mechanical Principles of Engineering, Art. 60.

7. Let a body be conceived to float, acted upon by no other forces than its weight W, and the upward pressure of the water (equal to its weight); which forces may be conceived to be applied respectively to the centre of gravity of the body and to the centre of gravity of the displaced fluid; and let it be supposed to be subjected to the action of a third force whose direction is parallel to the surface of the fluid. Let $\Delta H_1$ represent the vertical displacement of the centre of gravity of the body thereby produced*, and $\Delta H_2$ that of the centre of gravity of its immersed part. Let moreover the volume of the immersed part be conceived to remain unaltered† whilst the body is in the act of displacement. If each centre of gravity be assumed to ascend, the work of the weight of the body will be represented by $-W.\Delta H_1$, and that of the upward pressure of the fluid by $+W.\Delta H_2$, the negative sign being taken in the former case, because the force acts in a direction opposite to that in which the point of application is moved, and the positive sign in the latter, because it acts in the same direction, so that the aggregate work $\Sigma u_2$ (see equation 1.) of the forces which constituted the equilibrium of the body in the state from which it has been disturbed is represented by

$$-W.\Delta H_1+W.\Delta H_2.$$

If the centre of gravity of the body or of the displaced fluid *descends* (a property which will be found to characterize a large class of vessels), $\Delta H_1$ in the one case, and $\Delta H_2$ in the other, must be taken with the negative sign, since the weight of the body will be applied in the same direction, and the pressure of the fluid in an opposite direction to that in which their respective points of application are moved. Moreover, the system put in motion includes, with the floating body, the particles of the fluid displaced by it as it changes its position, so that if the weight of any element of the floating body be represented by $w_1$, and of the fluid by $w_2$, and if their velocities be $v_1$ and $v_2$, the whole *vis viva* is represented by

$$\frac{1}{g}\Sigma w_1 v_1^2+\frac{1}{g}\Sigma w_2 v_2^2,$$

and we have by equation 1,

$$U(\theta)-W(\Delta H_1-\Delta H_2)=\frac{1}{2g}\Sigma w_1 v_1^2+\frac{1}{2g}\Sigma w_2 v_2^2. \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (4.)$$

In the extreme position into which the body is made to roll and in which $\Sigma w_1 v_1^2=0$,

$$U(\theta)=W.(\Delta H_1-\Delta H_2)+\frac{1}{2g}\Sigma w_2 v_2^2, \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (5.)$$

* When a floating body is so made to incline from any one position into any other as that the volume of fluid displaced by it may in the one position be equal to that in the other, its centre of gravity is also vertically displaced; for if this be not the case, the perpendicular distance of the centre of gravity of the body from its plane of flotation must remain unchanged, and the form of that portion of its surface, which is subject to immersion, must be *determined geometrically* by this condition; but by the supposition the form of the body is undetermined. It is remarkable what currency has been given to the error, that whilst a vessel is rolling or pitching its centre of gravity remains at rest. I should not otherwise have thought this note necessary.

† It will be shown that this supposition is only approximately true.

or if the inertia of the displaced fluid be neglected,

$$U(\theta)=W.(\Delta H_1-\Delta H_2). \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (6.)$$

*Whence it follows that the work necessary to incline a floating body through any given angle is equal to that necessary to raise it bodily through a height equal to the difference of the vertical displacements of its centre of gravity and of that of its immersed part, so that other things being the same, that ship is the most stable the product of whose weight by this difference is the greatest.*

In the case in which the centre of gravity of the displaced fluid descends, the *sum* of the displacements is to be taken instead of the difference.

8. This conclusion is nevertheless in error in the following respects:—

1st. It supposes that throughout the motion the weight of the displaced fluid remains equal to that of the floating body, which equality cannot accurately have been preserved by reason of the inertia of the body and of the displaced fluid*.

From this cause there cannot but result small vertical oscillations of the body about those positions which, whilst it is in the act of inclining, correspond to this equality, which oscillations are independent of its principal oscillation.

2ndly. It involves the hypothesis of absolute rigidity in the floating body, so that the motion of every part and its *vis viva* may cease at *once* when the principal oscillation terminates. The frame of a ship and its masts are however elastic, and by reason of this elasticity there cannot but result oscillations, which are independent of, and may not synchronize with, the principal oscillation of the ship as she rolls, so that the *vis viva* of every part cannot be assumed to cease and determine at one and the same instant, as it has been supposed to do.

3rdly. No account has been taken of the work expended in communicating *motion* to the displaced fluid, measured by half its *vis viva* and represented by the term $\frac{1}{2g}\Sigma w_s v_s^2$ in equation 5.

9. From a careful consideration of these causes of error, I was led to conclude that they would not affect that practical application of the formula which I had principally in view in investigating it, especially as in certain respects they tended to neutralize one another. The question appeared however of sufficient importance to be subjected to the test of experiment, and on my application, the Lords Commissioners of the Admiralty were pleased to direct that such experiments should be made in Her Majesty's Dockyard at Portsmouth, and Mr. FINCHAM, the eminent

* The motion of the centre of gravity of the body being the same as though all the disturbing forces were applied directly to it, it follows, that no elevation of this point is caused in the beginning of the motion, by the application of a horizontal disturbing force, or by a horizontal displacement of the weight of the body, which, if it be a ship, may be effected by moving its ballast. The motion of rotation thereby produced takes place therefore, in the first instance, about the centre of gravity, but it cannot so take place without destroying the equality of the weight of the displaced fluid to that of the body. From this inequality there results a vertical motion of the centre of gravity, and another axis of rotation.

Master Shipwright of that dockyard, and Mr. Rawson were kind enough to undertake them.

The details of these experiments accompany my paper; they extend beyond the object originally contemplated by me; and whether regard be had to the practical importance of the question under discussion, the great care and labour bestowed upon them, or the many expedients by which these gentlemen have succeeded in giving to them a degree of accuracy hitherto, I believe, unknown in experiments of this kind, they claim to rank as authentic and valuable contributions to the science of naval construction.

10. That it might be determined experimentally whether the work which must be done upon a floating body to incline it through a given angle be that represented by equation 6, it was necessary to do upon such a body an amount of work which could be measured; and it was further necessary to ascertain what were the elevations of the centres of gravity of the body and of its immersed part thus produced, and then to see whether the amonnt of work done upon the body equaled the difference of these elevations multiplied by its weight.

To effect this, I proposed that a vessel should be constructed of a simple geometrical form, such that the place of the centre of gravity of its immersed part might readily be determined in every position into which it might be inclined, that of its plane of flotation being supposed to be known; and that a mast should be fixed to it, and a long yard to this mast, and that when the body floated in a vertical position a weight suspended from one extremity of the yard should suddenly be allowed to act upon it causing it to roll over; that the position into which it thus rolled should be ascertained, together with the corresponding elevations of its centre of gravity and the centre of gravity of its immersed part, and the vertical descent of the weight suspended from the extremity of its arm. The product of this vertical descent by the weight suspended from the arm ought then, by the formula, to be found nearly equal to the difference of the elevations of the two centres of gravity multiplied by the weight of the body; and this was the test to which I proposed that the formula should be subjected, having in view its adoption by practical men as a principle of naval construction.

To give to the deflecting weight that *instantaneous* action on the extremity of the arm which was necessary to the accuracy of the experiment, a string was in the first place to be affixed to it and attached to a point vertically above, in the ceiling. When the deflecting weight was first applied this string would sustain its pressure, but this might be thrown at once upon the extremity of the arm by cutting it. A transverse section of the vessel, with its mast and arm, was to be plotted on a large scale on a board, and the extreme position into which the vessel rolled being by some means observed, the water-line corresponding to this position was to be drawn. The position of the yard, in respect to the surface of the water in that position, would then be known, and the vertical descent of the deflecting weight could be measured, and also the vertical ascent of the centre of gravity of the immersed part or displacement.

To determine the position of the centre of gravity of the vessel, it was to be allowed to rest in an inclined position under the action of the deflecting weight; and the water-line corresponding to this position being drawn on the board, the corresponding position of the deflecting weight and of the centre of gravity of the immersion were thence to be determined. The determination of the position of the vertical passing through the centre of gravity of the body would thus become an elementary question of statics; and the intersection of this line, with that about which the section was symmetrical, would mark the position of the centre of gravity. This determination might be verified by a second similar experiment with a different deflecting weight.

These suggestions have received a great development at the hands of Mr. Rawson, and he has adopted many new and ingenious expedients in carrying them out. Among these, that by which the position of the water-line was determined in the extreme position into which the vessel rolls, appears to me specially worthy of observation. A strip of wood was fastened at right angles to that extremity of the yard to which the deflecting weight was attached, of sufficient length to dip into the water when the vessel rolled, on this slip of wood, and also on the side of the vessel nearest to it, a strip of glazed paper was fixed. The highest points at which these strips of paper were wetted in the rolling of the vessel, were obviously points in the water-line in its extreme position, and being plotted upon the board, a line drawn through them determined that position with a degree of accuracy which left nothing to be desired.

11. Two forms of vessels were used (see Plate XLVII. figs. 1 and 2); one of them had a triangular and the other a semicircular section. The following Table contains the general results of the experiments, of which the particulars are detailed in the Appendix:—

| Form of the model experimented on. | No. of experiment. | Weight of model and loading. | Disturbing weight. | Dynamical stability, as determined by experiment. | Dynamical stability calculated from the formula $U(f) = W\Delta(H_1 - H_2)$. | Extreme inclination into which the vessel rolled, as determined by experiment. | Extreme inclination into which the vessel should roll, as determined by calculation from the formula $U(f) = W\Delta(H_1 - H_2)$*. | Inclination in which the vessel finally rested when subjected to the action of the disturbing weight. | Ratio of the volume of the displaced fluid in the extreme position into which the vessel rolled to that in the position in which it originally rested. |
|---|---|---|---|---|---|---|---|---|---|
| | | lbs. | lbs. | | | ° ′ | ° ′ | ° ′ | |
| Triangular model. | 1. | 33·8626 | ·5485 | ·5161 | ·5361 | 23 30 | ..... | 12 30 | ·8961 |
| | 2. | 36·8590 | ·3450 | ·4887 | ·4951 | 15 30 | ..... | 8 0 | ·98114 |
| | 3. | 37·3563 | ·5377 | 1·1724 | 1·4503 | 24 0 | ..... | 13 0 | ·88512 |
| | 4. | 38·2911 | ·5739 | 1·2673 | 1·8460 | 25 0 | ..... | 13 30 | ·9330 |
| Circular model. | 1. | 197·18 | 2·8225 | 7·3761 | 7·394 | 26 0 | 24 20 | 13 0 | |
| | 2. | 197·18 | 1·9570 | 3·2486 | 3·122 | 17 0 | 16 22 | 9 0 | |
| | 3. | 255·43 | 1·9570 | 1·7727 | 1·7667 | 10 0 | 10 0 | 4 30 | |

In the experiments with the smaller triangular model the differences between the

* The inclinations are calculated by the formula (9.).

results and those given by the formula are much greater than in the experiments with the heavier cylindrical vessel.

In explanation of this difference, it will be observed, *first*, that the conditions of the experiment with the cylindrical model more nearly approach to those which are assumed in the formula than those with the other; the disturbance of the water in the change of the position of the former being less, and therefore the work expended upon the inertia of the water, of which the formula takes no account, less in the one case than the other; and, *secondly*, that the weight of the model being greater, this inertia bears a less proportion to the amount of work required for inclining it than in the other case.

The effect of this inertia adding itself to the buoyancy of the fluid, cannot but be to lift the vessel out of the water and to cause the displacement to be less at the termination of each rolling oscillation than at its commencement*. This variation in volume of the displacement was apparent in all the experiments. Its amount was measured and is recorded in the last column of the Table; its tendency is to produce in the body vertical oscillations, which are so far independent of its rolling motion that they will not probably synchronize with it. The body displacing, when rolling, less fluid than it would at rest, the effect of the weight used in the experiments to incline it is thereby increased, and thus is explained the fact (apparent in the eighth and ninth columns of the Table) that the inclination by experiment is somewhat greater than the formula would make it.

12. *The dynamical stability of a vessel whose athwart sections (where they are subject to immersion and emersion) are circular, having their centres in a common axis.*

Let EDF, Plate XLVIII. fig. 3 or 4, be an athwart section of such a vessel, the parts of whose periphery ES and FR, subject to immersion and emersion, are parts of the same circular arc ETF, whose centre is C. Let $G_1$ represent the projection of the centre of gravity of the vessel on this section, and $G_2$ that of the centre of gravity of the space whose section is SDRT, supposing it filled with water. This space lies wholly within the vessel in fig. 3 and without it in fig. 4. Let

$h_1 = CG_1$, $h_2 = CG_2$.

$W_1$ = weight of vessel.

$W_2$ = weight of water occupying, or which would occupy, the space whose section is STRD.

$\theta$ = the inclination from the vertical.

Since in the act of the inclination of the vessel the whole volume of the displaced fluid remains constant, and also that volume of which STRD is the section†, it follows that the volume of that portion of which the circular area PSRQ is the section

* This result connects itself with the well-known fact of the rise of a vessel out of the water when propelled rapidly, which is so great in the case of fast track-boats, as considerably to reduce the resistance upon them.

† It will be observed that the space STRD is supposed always to be under water.

remains also constant, and that the water-line PQ, which is the chord of that area, remains at the same distance from C, so that the point C neither ascends nor descends. Now the forces which constituted the equilibrium of the vessel in its vertical position were its weight and that of the fluid it displaced. Since the point C is not vertically displaced, the work of the former force, as the body inclines through the angle $\theta$, is represented by $-W_1h_1$ vers $\theta$. The work of the latter is equal to that of the upward pressure of the water which would occupy the space of which the circular area PTQ is the section *increased*, in the case represented in fig. 3, by that of the water which would occupy STRD; and *diminished* by it in the case represented in fig. 4.

But since the space, of which the circular area PTQ is the section, remains similar and equal to itself, its centre of gravity remains always at the same distance from the centre C, and therefore neither ascends nor descends. Whence it follows that the work of the water which would occupy this space is *zero*; so that the work of the *whole* displaced fluid is equal to that of the *part* of it which occupies the space STRD, taken in the case represented in fig. 3 with the positive, and in that represented in fig. 4 with the negative sign. It is represented therefore generally by the formula $\pm W_2h_2$ vers $\theta$. On the whole, therefore, the work $\Sigma u_2$ (see Art. 1.) of those forces, which in the vertical position of the body constituted its equilibrium, is represented by the formula

$$\Sigma u_2 = -W_1h_1 \text{ vers } \theta \pm W_2h_2 \text{ vers } \theta.$$

Representing therefore the dynamical stability $\Sigma u_1$ by $U(\theta)$, we have by equation (2.)

$$U(\theta) = (W_1h_1 \mp W_2h_2) \text{ vers } \theta, \quad \ldots\ldots\ldots\ldots \quad (7.)$$

in which expression the sign $\mp$ is to be taken according as the circular area ATB lies wholly within the area ADB, as in fig. 3, or partly without it, as in fig. 4. Other things being the same, the latter is therefore a more stable form than the former.

13. The work of the upward pressure of the water upon the vessel represented in fig. 4 being a negative quantity, $-W_2h_2$ vers $\theta$, it follows that the point of application of the pressure must be moved in a direction opposite to that in which the pressure acts; but the pressure acts upwards, therefore its point of application, *i. e.* the centre of gravity of the displaced fluid, *descends*. This property may be considered to distinguish *mechanically* the class of vessels whose type is fig. 3, from that class whose type is fig. 4; as the property of including wholly or only partly, within the area of any of their athwart sections, the corresponding circular area ETF, distinguishes them geometrically.

14. To obtain from the formula 7 an expression adapted to the experiments with the circular model, Plate XLVII. fig. 2, let

$$OM = b, \ MQ = c, \text{ Disturbing weight } = w.$$

Now it may readily be shown that the vertical descent of the point Q, when the vessel is made to incline through the angle $\theta$, is represented by

$$b \text{ vers } \theta + c \sin \theta.$$

Therefore the work done upon the vessel by the disturbing weight in the act of this inclination is represented by

$$w(b \text{ vers } \theta + c \sin \theta),$$

which expression ought, therefore, neglecting the inertia of the fluid, to equal that (equation 7.) which represents $U(\theta)$, or

$$w(b \text{ vers } \theta + c \sin \theta) = (W_1 h_1 \mp W_2 h_2) \text{ vers } \theta,$$

whence we obtain

$$\tan \tfrac{1}{2}\theta = \frac{wc}{W_1 h_1 \mp W_2 h_2 - wb} \quad \ldots \quad (8.)$$

In the vessel experimented upon, $W_2 = 0$,

$$\therefore \tan \tfrac{1}{2}\theta = \frac{wc}{W_1 h_1 - wb}, \quad \ldots \quad (9.)$$

which is the formula used in calculating the eighth column of the Table, p. 615.

15. *The dynamical stability of a vessel of any given form subjected to a rolling or pitching motion.*

Conceive the vessel, after having completed an oscillation in any given direction, —being then about to return towards its vertical position—to be for an instant at rest, and let RS (fig. 5) represent the intersection of its plane of flotation *then*, and PQ of its flotation when in its vertical position, with a section CAD of the vessel perpendicular to the mutual intersection O of these planes. The section CAD will then be a vertical section of the vessel.

Let G be the projection upon it of the vessel's centre of gravity when in its vertical position.

H, that of the centre of gravity of the fluid displaced by the vessel in the vertical position.

*g*, that of the fluid displaced by the portion of the vessel of which QOS is a section.

*h*, that of the fluid which would be displaced by the portion, of which POR is a section, if it were immersed.

GM, HN, *gm*, *hn*, KL perpendiculars upon the plane RS.

$W$ = weight of vessel or of displaced fluid.

$w$ = weight of water displaced by either of the equal portions of the vessel of which POR and QOS are sections.

$H_1$ = depth of centre of gravity of vessel in vertical position.

$H_2$ = depth of centre of gravity of displaced water in vertical position.

$\Delta H_1$ = elevation of centre of gravity of vessel.

$\Delta H_2$ = elevation of centre of gravity of displaced water.

$\theta$ = inclination of planes PQ and RS.

$\eta$ = inclination of line O in which planes PQ and RS intersect, to that line about which the plane PQ is symmetrical.

$\zeta$ = inclination to horizon of line about which the plane PQ is symmetrical.

$x$ = distance of section CAD, measured along the line whose projection is O, from the point where that line intersects the midship section.

$y = O\beta$.

$y_1 = PQ$.

$y_2 = RS$.

$z = hn + mg$.

$\lambda = KL$.

I = moment of inertia of plane PQ about axis O.

A and B = moments of inertia of PQ about its principal axes.

$\mu$ = weight of a cubic unit of water.

Suppose the water actually *displaced* by the vessel to be, on the contrary, *contained* by it; and conceive that which occupies the space QOS to pass into the space POR, the whole becoming solid. Let $\Delta H_2$ represent the corresponding elevation of the centre of gravity of the whole contained fluid. Then will $\Delta H_2 + \Delta H_3$ represent the total elevation of the centre of gravity of this fluid as it passes from the position it occupied when the vessel was vertical into the position PAQ. But this elevation is obviously the same as though the fluid had assumed the solid state in the vertical position of the body, and the latter had revolved with it, in that state, into its present position. It is therefore represented by KH − NH*;

$$\therefore \Delta H_2 + \Delta H_3 = KH - NH \text{ and } \Delta H_3 = KH - NH - \Delta H_2.$$

Since, moreover, by the elevation of the fluid in QOS, whose weight is $w$, into the space OPR, and of its centre of gravity through $(gm + hn)$, the centre of gravity of mass of fluid of which it forms a part, and whose weight is W, is raised through the space $\Delta H_3$; it follows, by a well-known property of the centre of gravity of a system†, that

$$W.\Delta H_3 = w(gm + hn);$$

$$\therefore W(KH - NH - \Delta H_3) = w(gm + hn).$$

But

$$NH = KH \cos\theta - KL = H_2 \cos\theta - \lambda;$$

$$\therefore KH - NH = H_2 \operatorname{vers}\theta + \lambda,$$

and

$$mg + nh = z;$$

$$\therefore W(H_2 \operatorname{vers}\theta + \lambda - \Delta H_3) = wz;$$

$$\therefore W.\Delta H_3 = W(H_2 \operatorname{vers}\theta + \lambda) - wz. \quad \ldots\ldots\ldots\ldots \quad (10.)$$

* The line joining the centres of gravity of the vessel and its immersed part, in its vertical position, is parallel to the plane CAD, for it is perpendicular to the plane PQ, to whose intersection with the plane RS the plane CAD is perpendicular; $\therefore$ GK = $H_1$ and HK = $H_2$.

† Poncelet, Mécanique Industrielle, 2me partie, Art. 50, or Moseley's Mechanical Principles of Engineering, Art. 59.

Also $$\Delta H_1 = KG - MG = H_1 - (H_1 \cos\theta - \lambda) = H_1 \operatorname{vers}\theta + \lambda;$$

$$\therefore W(\Delta H_1 \mp \Delta H_2) = W(H_1 \mp H_2) \operatorname{vers}\theta + wz \text{ *};$$

$$\therefore \text{(equation 6.) } U(\theta, \eta) = W(H_1 \mp H_1) \operatorname{vers}\theta + wz; \quad . \quad . \quad . \quad . \quad (11.)$$

the sign $\mp$ being taken according as the vessel is of the class represented in fig. 3, in which the centre of gravity of the displaced fluid ascends, or of that represented in fig. 4, in which it descends.

If $\alpha\beta$ be a vertical prismatic element of the space QOS, whose base is $dx\,dy\cos\theta$, and height $y\sin\theta$, then will $w.\overline{mg}$ be represented, in respect to that element, by $\mu y \sin\theta . dx\,dy\cos\theta . \frac{1}{2} y \sin\theta$, or by $\frac{1}{2}\mu \sin^2\theta \cos\theta\, y^3 dx\,dy$; and $wz$ will be represented, in respect to the whole space of which $Pr\sigma Q$ is the section, by

$$\frac{1}{2}\mu \sin^2\theta \cos\theta \iint y^3 dx\,dy,$$

or by $$\frac{1}{2}\mu \sin^2\theta \cos\theta . I.$$

If therefore we represent by $\varphi$ the value of $wz$, in respect to the spaces of which the mixtilinear areas $PR\rho$ and $QS\sigma$ are the sections, we have

$$wz = \frac{1}{2}\mu I \sin^2\theta \cos\theta + \varphi.$$

But the axis O, about which the moment of inertia of the plane PQ is I, is inclined to the principal axes of that plane at the angles $\eta$ and $\frac{\pi}{2} - \eta$, about which principal axes the moments of inertia are A and B; and it has been shown by M. Dupin† that when $\theta$ is small the line in which the planes PQ or RS intersect passes through the centre of gravity of each;

$$\therefore \quad I = A\cos^2\eta + B\sin^2\eta;$$

therefore by equation (11.),

$$U(\theta, \eta) = W(H_1 \mp H_2) \operatorname{vers}\theta + \frac{1}{2}\mu(A\cos^2\eta + B\sin^2\eta)\sin^2\theta\cos\theta + \varphi. \quad . \quad . \quad . \quad (12.)$$

If $\theta$ be so small that the spaces $Pr R$ and $Q\sigma S$ are evanescent in comparison with $PO\rho$ and $QO\sigma$, then, assuming $\varphi = 0$ and $\cos\theta = 1$,

$$U(\theta, \eta) = W(H_1 \mp H_2) \operatorname{vers}\theta + \frac{1}{2}\mu(A\cos^2\eta + B\sin^2\eta)\sin^2\theta, \quad . \quad . \quad . \quad . \quad . \quad . \quad (13.)$$

which may be put under the form

$$U(\theta, \eta) = \left\{ W(H_1 \mp H_2) + \mu(A\cos^2\eta + B\sin^2\eta) \right\} \operatorname{vers}\theta.$$

Again, since

$$\sin\zeta = \sin\theta \sin\eta, \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (14.)$$

* The sign $\mp$ is here taken to include the case in which the centre of gravity of the displaced fluid descends. See Art. 7.

† Sur la Stabilité des Corps Flottants, p. 32.

and $(A\cos^2\eta+B\sin^2\eta)\sin^2\theta=\{A+(B-A)\sin^2\eta\}\sin^2\theta$,

$\therefore$ $(A\cos^2\eta+B\sin^2\eta)\sin^2\theta=A\sin^2\theta+(B-A)\sin^2\zeta$;

$\therefore$ by equation 13,

$$U(\theta,\zeta)=W(H_1\mp H_2)\operatorname{vers}\theta+\frac{1}{2}\mu\{A\sin^2\theta+(B-A)\sin^2\zeta\}, \quad . \quad . \quad . \quad . \quad (15.)$$

*by which formula the dynamical stability of the ship is represented, both as it regards a pitching and a rolling motion.*

If in equation 13 $\eta=\frac{\pi}{2}$, the line in which the plane PQ (parallel to the deck of the ship) intersects its plane of flotation is at right angles to the length of the ship, and we have, since in this case $\theta=\zeta$ (see equation 14.),

$$U(\zeta)=W(H_1\mp H_2)\operatorname{vers}\zeta+\frac{1}{2}\mu B\sin^2\zeta, \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (16.)$$

which expression represents the dynamical stability, in regard to a pitching motion alone, as the equation

$$*U(\theta)=W(H_1\mp H_2)\operatorname{vers}\theta+\frac{1}{2}\mu A\sin^2\theta \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (17.)$$

represents it in regard to a rolling motion alone.

16. If a *given* quantity of work represented by $U(\theta)$ be supposed to be done upon the vessel, the angle $\theta$ through which it is thus made to roll may be determined by solving equation 17 with respect to $\sin\frac{\theta}{2}$. We thus obtain

$$\sin^2\frac{\theta}{2}=\frac{W(H_1\mp H_2)+\mu A-\sqrt{\{W(H_1\mp H_2)+\mu A\}^2-2\mu A.U(\theta)}}{2\mu A} \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (18.)$$

17. If PR and QS be conceived to be straight lines, so that POR and QOS are triangles, then $w.z$, taken in respect to an element included between the section CAD, and another parallel to it and distant by the small space $dx$, is represented by

$$\frac{1}{4}\mu y_1y_2\sin\theta dx(mg+nh);$$

or, since $mg+nh=\frac{1}{8}y_1\sin\theta$,

by $\frac{1}{12}\mu\sin^2\theta y_1^2y_2dx$;

$$\therefore \quad wz=\frac{1}{12}\mu\sin^2\theta\int y_1^2y_2dx,$$

and, equation 11

$$U(\theta,\zeta)=W(H_1\mp H_2)\operatorname{vers}\theta+\frac{1}{12}\mu\sin^2\theta\int y_1^2y_2dx, \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (19.)$$

which formula may be considered an approximate measure of the stability of the vessel under all circumstances.

* This formula may be verified experimentally by a method similar to that applied to equation 6. See Art. 10.

If, as in the case of the experiments of Messrs. Fincham and Rawson, the vessel be prismatic and the direction of the disturbance perpendicular to its axis,

$$y = \text{constant} = a, \text{ and } z = \frac{1}{3} a \sin \theta;$$

$$\therefore \quad wx = \frac{1}{3} aw \sin \theta, \text{ and}$$

$$U(\theta) = W(H_1 \mp H_2) \text{ vers } \theta + \frac{1}{3} aw \sin \theta.$$

Mr. Rawson has obligingly undertaken the verification of this formula by comparing it with his experiments on the cylindrical model. The following is the result:—

| No. of experiment. | W. | w. | $H_1$. | $H_2$. | $\ell$. | U($\ell$) by formula. | U($\ell$) by experiment. |
|---|---|---|---|---|---|---|---|
| | lbs. | lbs. | | | ° | | |
| 3 | 255·43 | 17·294 | 3·903 | 4·800 | 9 | 1·760 | 1·766 |
| 4 | 255·43 | 46·84 | 4·02 | 4·82 | 26 | 13·478 | 13·5015 |
| 5 | 197·18 | 37·98 | 0·80 | 3·80 | 26 | 6·807 | 7·3761 |

18. *A rigid surface on which the vessel may be supposed to rest whilst in the act of pitching and rolling.*

If we imagine the position of the centre of gravity of a vessel afloat to be continually changed by altering the positions of some of its contained weights without altering the weight of the whole, so as to cause the vessel to incline into an infinite number of different positions displacing, in each, the same volume of water, then will the different planes of flotation, corresponding to these different positions, envelope a curved surface, called the surface of the planes of flotation (*surface des flotaisons*), whose properties have been discussed at length by M. Dupin in his excellent memoir, Sur la Stabilité des Corps Flottants, which forms part of his Applications de Géométrie*. So far as the properties of this surface concern the conditions of the vessel's *equilibrium*, they have been exhausted in that memoir, but the following property, which has reference rather to the conditions of its dynamical stability than its equilibrium, is not stated by M. Dupin:—

*If we conceive the surface of the planes of flotation to become a rigid surface, and also the surface of the fluid to become a rigid plane without friction, so that the former surface may rest upon the latter and roll and slide upon it, the other parts of the vessel being imagined to be so far immaterial as not to interfere with this motion, but not so as to take away their weight or to interfere with the application of the upward pressure of the fluid to them, then will the motion of the vessel, when resting by this curved surface upon this rigid but perfectly smooth horizontal plane, be the same as it was when, acted upon by the same forces, it rolled and pitched in the fluid.*

In this general case of the motion of a body resting by a curved surface upon a horizontal plane, that motion may be, and generally will be, of a complicated cha-

* Bachelier, Paris, 1822.

racter, including a sliding motion upon the plane, and simultaneous motions round two axes passing through the point of contact of the surface with the planes and corresponding with the rolling and pitching motion of a ship. It being however possible to determine these motions by the known laws of dynamics, when the form of the surface of the planes of flotation is known, the complete solution of the question is involved in the determination of the latter surface.

The following property*, proved by M. DUPIN in the memoir before referred to (p. 32), effects this determination:—

"The intersection of any two planes of flotation, infinitely near to each other, passes through the centre of gravity of the area intercepted upon either of these planes by the external surface of the vessel."

If, therefore, any plane of flotation be taken, and the centre of gravity of the area here spoken of be determined with reference to that plane of flotation, then that point will be one in the curved surface in question, called the surface of the planes of flotation, and by this means any number of such points may be found and the surface determined.

19. *The axis about which a vessel rolls may be determined, the direction in which it is rolling being given.*

If, after the vessel has been inclined through any angle, it be left to itself, the only forces acting upon it (the inertia of the fluid being neglected) will be its weight and the upward pressure of the fluid it displaces; the motion of its centre of gravity will therefore, by a well-known principle of mechanics, be wholly in the same vertical line.

Let HK (fig. 6) represent this vertical line, PQ the surface of the fluid, and *a*M*b* the surface of the planes of flotation. As the centre of gravity G traverses the vertical HK, this surface will partly roll and partly slide by its point of contact M on the plane PQ.

If we suppose, therefore, PRQ to be a section of the vessel through the point M, and perpendicular to the axis about which it is rolling, and if we draw a vertical line MO through the point M, and through G a horizontal line GO parallel to the plane PRQ, then the position of the axis will be determined by a line perpendicular to these, whose projection on the plane PRQ is O.

For since the motion of the point G is in the vertical line HK, the axis about which the body is revolving passes through GO, which is perpendicular to HK; and since the point M of the vessel traverses the line PQ, the axis passes also through MO which is perpendicular to PQ; and GO is drawn parallel to, and MO *in* the plane PRQ, which, by supposition, is perpendicular to the axis, therefore the axis is perpendicular to GO and MO.

If HK be in the plane PRQ, which is the case whenever the motion is exclusively one of rolling or one of pitching, the point O is determined by the intersection of GO and MO.

20. *The time of the rolling through a small angle of a vessel whose athwart sections*

* This property appears to have been first given by EULER.

*are (in respect to the parts subject to immersion and emersion) circular, and have their centres in the same longitudinal axis.*

Let EDF (fig. 3 or fig. 4) represent the midship section of such a vessel, in which section let the centre of gravity $G_1$ be supposed to be situated, and let HK be the vertical line traversed by $G_1$ as the vessel rolls. Imagine it to have been inclined from its vertical position through a given angle $\theta_1$ and the forces which so inclined it then to have ceased to act upon it, so as to have allowed it to roll freely back again towards its position of equilibrium until it had attained the inclination OCD to the vertical, which suppose to be represented by $\theta$.

Referring to equation 1., let it be observed that in this case $\Sigma u_2=0$, so that the motion is determined by the condition

$$\Sigma u_1=\frac{1}{2g}\Sigma w v^2. \qquad \text{(20.)}$$

But the forces which have displaced it from the position in which it was, for an instant, at rest are its weight and the upward pressure of the water; and the work of these, $U(\theta_1)-U(\theta)$, done between the inclinations $\theta$ and $\theta_1$ when the vessel was in the act of receding from the vertical, was shown to be represented by $(W_1h_1\mp W_2h_2)$ (vers $\theta$— vers $\theta_1$) by Art. 12 (adopting the same notation as in that article); therefore the work, between the same inclinations, when the motion is in the opposite direction, is represented by the same expression with the sign changed;

$$\therefore \quad \Sigma u_1=(W_1h_1\mp W_2h_2)(\text{vers}\,\theta_1-\text{vers}\,\theta),$$

and since the axis about which the vessel is revolving is perpendicular to the plane EDF, and passes through the point O (Art. 19.), if $W_1k_1$ represent its moment of inertia about an axis perpendicular to the plane EDF, and passing through its centre of gravity $G_1$,

$$\Sigma w v^2=W_1(k^2+\overline{OG_1}^2)\left(\frac{d\theta}{dt}\right)^2.$$

Substituting in equation 20 and writing for $OG_1$ its value $h_1\sin\theta$, we have

$$(W_1h_1\mp W_2h_2)(\text{vers}\,\theta_1-\text{vers}\,\theta)=\frac{W_1}{2g}(k^2+h_1^2\sin^2\theta)\left(\frac{d\theta}{dt}\right)^2;$$

$$\therefore\ t(\theta_1)=\frac{-1}{\sqrt{2gh_1\left(1\mp\frac{W_2h_2}{W_1h_1}\right)}}\int_{+\theta_1}^{-\theta_1}\sqrt{\frac{k^2+h_1^2\sin^2\theta}{\text{vers}\theta_1-\text{vers}\,\theta}}\,d\theta. \qquad \text{(21.)}$$

$$t(\theta_1)=\frac{1}{\sqrt{2gh_1\left(1\mp\frac{W_2h_2}{W_1h_1}\right)}}\int_{-\theta_1}^{+\theta_1}\sqrt{\frac{k^2+4h_1^2\sin^2\frac{1}{2}\theta\cos^2\frac{1}{2}\theta}{2\left(\sin^2\frac{1}{2}\theta_1-\sin^2\frac{1}{2}\theta\right)}}\,d\theta$$

$$=\frac{1}{\sqrt{gh_1\left(1\mp\frac{W_2h_2}{W_1h_1}\right)}}\int_{-\theta_1}^{+\theta_1}\sqrt{\frac{k^2\sec^2\frac{1}{2}\theta+4h_1^2\sin^2\frac{1}{2}\theta}{\sin^2\frac{1}{2}\theta_1-\sin^2\frac{1}{2}\theta}}\cdot\cos\tfrac{1}{2}\theta\,d\tfrac{1}{2}\theta,$$

or assuming $\theta$ to be so small that the fourth and all higher powers of $\sin\frac{1}{2}\theta$ may be neglected, and observing that, this being the case,

$$\sqrt{k^2\sec^2\tfrac{1}{2}\theta+4h_1^2\sin^2\tfrac{1}{2}\theta}=\sqrt{k^2\left(1+\sin^2\tfrac{1}{2}\theta\right)+4h_1^2\sin^2\tfrac{1}{2}\theta}$$

$$=k\sqrt{1+\frac{4h_1^2+k^2}{k^2}\sin^2\tfrac{1}{2}\theta}=k\left\{1+\frac{4h_1^2+k^2}{2k^2}\sin^2\tfrac{1}{2}\theta\right\}$$

$$t(\theta_1)=\frac{k}{\sqrt{gh_1\left(1\mp\frac{W_2h_2}{W_1h_1}\right)}}\int_{-\theta_1}^{+\theta_1}\frac{1+\frac{4h_1^2+k^2}{2k^2}\sin^2\frac{1}{2}\theta}{\sqrt{\sin^2\frac{1}{2}\theta_1-\sin^2\frac{1}{2}\theta}}d\sin\tfrac{1}{2}\theta.$$

But
$$\int_{-\theta_1}^{+\theta_1}\frac{d\sin\frac{1}{2}\theta}{\sqrt{\sin^2\frac{1}{2}\theta_1-\sin^2\frac{1}{2}\theta}}=\pi,$$

and
$$\int_{-\theta_1}^{+\theta_1}\frac{\sin^2\frac{1}{2}\theta\,d\sin\frac{1}{2}\theta}{\sqrt{\sin^2\frac{1}{2}\theta_1-\sin^2\frac{1}{2}\theta}}=\frac{1}{2}\pi\sin^2\tfrac{1}{2}\theta_1,$$

$$\therefore\quad t(\theta_1)=\frac{\pi k}{\sqrt{gh_1\left(1\mp\frac{W_2h_2}{W_1h_1}\right)}}\left\{1+\frac{4h_1^2+k^2}{4k^2}\sin^2\tfrac{1}{2}\theta_1\right\}.\qquad(22.)$$

The sign $\mp$ being taken according as the centre of gravity of the displaced fluid ascends or descends.

21. *The time of a vessel's rolling or pitching through a small angle, its form and dimensions being any whatever.*

Let EDF (figs. 3 or 4) represent the midship section of such a vessel, supposed to be rolling about an axis whose projection is O; and let C represent the centre of the circle of curvature of the surface of its planes of flotation (Art. 18.) at the point M where that surface is touched by the plane PQ, being above the load water-line AB in fig. 3, and beneath it in fig. 4. Let the radius of curvature CM be represented by $\varrho$; then adopting the same notation as in the last article, and observing that the axis O about which the vessel is turning is perpendicular to EDF, we shall find its moment of inertia to be represented by

$$W_1\{k^2+(H_1\mp\varrho)^2\sin^2\theta\}\left(\frac{d\theta}{dt}\right)^2,$$

where $H_1$ represents the depth of the centre of gravity in the vertical position of the vessel.

Also, by equation 17, reasoning as in Art. 20,

$$\Sigma u_1=U(\theta_1)-U(\theta)=W_1(H_1\mp H_2)(\cos\theta-\cos\theta_1)+\tfrac{1}{2}\mu A(\cos^2\theta-\cos^2\theta_1),$$



FRANKLIN INSTITUTE

$\therefore$ by equation 20,

$$W_1(H_1 \mp H_2)(\cos\theta - \cos\theta_1) + \frac{1}{2}\mu A(\cos^2\theta - \cos^2\theta_1) = \frac{W_1}{2g}\left\{k^2 + (H_1 \mp \varrho)^2 \sin^2\theta\right\}\left(\frac{d\theta}{dt}\right)^2$$

$$\therefore\ t(\theta_1) = \frac{1}{\sqrt{2g}} \int_{-\theta_1}^{+\theta_1} \sqrt{\frac{k^2 + (H_1 \mp \varrho)^2 \sin^2\theta}{(H_1 \mp H_2)(\cos\theta - \cos\theta_1) + \frac{1}{2}\frac{\mu A}{W_1}(\cos^2\theta - \cos^2\theta_1)}}\, d\theta$$

$$t(\theta_1) = \frac{1}{\sqrt{2g}} \int_{-\theta_1}^{+\theta_1} \sqrt{\frac{k^2 + (H_1 \mp \varrho)^2 \sin^2\theta}{\left\{H_1 \mp H_2 + \frac{1}{2}\frac{\mu A}{W_1}(\cos\theta + \cos\theta_1)\right\}\left\{\cos\theta - \cos\theta_1\right\}}}\, d\theta.$$

Assuming $\theta$ and $\theta_1$ to be so small that $\cos\theta + \cos\theta_1 = 2$, and observing that

$$\cos\theta - \cos\theta_1 = \operatorname{vers}\theta_1 - \operatorname{vers}\theta,$$

$$t(\theta_1) = \frac{1}{\sqrt{2g\left\{H_1 \mp H_2 + \frac{\mu A}{W_1}\right\}}} \int_{-\theta_1}^{+\theta_1} \sqrt{\frac{k^2 + (H_1 \mp \varrho)^2 \sin^2\theta}{\operatorname{vers}\theta_1 - \operatorname{vers}\theta}}\, .\, d\theta.$$

Supposing, moreover, $\varrho$ to remain constant between the limits $-\theta_1$ and $+\theta_1$, and integrating as in Art. 20, equation 21,

$$t(\theta_1) = \frac{\pi k}{\sqrt{g\left(H_1 \mp H_2 + \frac{\mu A}{W_1}\right)}}\left\{1 + \frac{4(H_1 \mp \varrho)^2 + k^2}{4k^2} \sin^2\frac{1}{2}\theta_1\right\} \quad \ldots\ldots \quad (23.)$$

where $\varrho$ is to be taken with the sign $\mp$ according as the surface of the planes of flotation is above or below the load-water line, and $H_2$, according as the centre of gravity of the displaced fluid ascends or descends.

Since the value of $\sin^2\frac{1}{2}\theta_1$ is exceedingly small, the oscillations are nearly tautochronous, and the period of each is nearly represented by the formula

$$t(\theta_1) = \frac{\pi k}{\sqrt{g\left(H_1 \mp H_2 + \frac{\mu A}{W_1}\right)}} \quad \ldots\ldots\ldots\ldots \quad (24.)$$

The following method is given by M. Dupin for determining the value of $\varrho$*:—

"If the periphery of the plane of flotation be imagined to be loaded at every point with a weight represented by the tangent of the inclination of the sides of the vessel at that point to the vertical, then will the moments of inertia of that curve, so loaded, about its two principal axes, when divided by the area of the plane of flotation, represent the radii of greatest and least curvature of the envelope of the planes of flotation."

If $\varrho$ be taken to represent the radius of greatest curvature, the formula 25 will represent the time of the vessel's rolling; if the radius of least curvature (B being also substituted for A), it will represent the time of pitching.

* Applications de Géométrie, p. 47.

22. *Experiments made by Messrs.* FINCHAM *and* RAWSON *with the cylindrical model* (Plate XLVII. fig. 2) *to verify the formula* 22, *which represents the time of the rolling of a vessel of that form.*

The following ingenious expedient for determining the time of the oscillations of a floating body was suggested by Mr. FINCHAM and found fully to answer the purpose.

The motion of the vessel, when floating in the tank, was limited to a rolling motion by means of upright guides (A, B, Plate XLIX.), receiving between them the extremities of a longitudinal axis fixed in the vessel so as nearly to pass through the centre of gravity. A frame, PKL, resting on two parallel rails, was made to traverse uniformly by means of clockwork, M, in the direction of this axis produced, that is, in the direction of the length of the model, and at right angles to the direction in which it rolled. This frame carried a cylindrical piece of wood, PL, having its axis in the direction of the motion of the frame, and its surface so curved that an arm, HI, fixed to the model parallel to its length and projecting beyond its extremity, should, as it



rolled, sweep parallel to the surface of the cylinder. A pencil was fixed at the extremity of this arm and pressed lightly by a spring upon the surface of the cylinder, which was covered by a piece of paper. The frame which carried this cylinder advancing in the direction of its axis, and the vessel at the same time rolling so as to sweep the arm over its surface perpendicular to that direction, a zigzag line was, by the combination of the two motions, described, as represented in the diagram on the preceding page, of which each two consecutive loops mark the beginning and end of the same oscillation, and the distance AM between them, measured in the direction in which the frame moved, shows the space traversed by it in the time occupied by that oscillation. This space being known from the experiment, and the rate at which the frame travels uniformly being also known, the time occupied in the oscillation may be determined*.

At a certain point the amplitudes of the oscillations will be observed suddenly to increase. This is due to the return of the wave created by the vessel in the act of rolling and reflected by the sides of the tank†.

Before the times of oscillation could be calculated by the formula (22.) to compare them with those determined by experiment, it was necessary that the moment of inertia $W,k^2$ of the floating body should be ascertained. To ascertain it by calculation would have been a difficult task, involving in some respects an uncertain result; it was sought therefore by experiment.

With this view a knife-edge was fixed at each extremity of the cylinder, so as accurately to coincide with its axis prolonged. The vessel taken out of the water was then made to rest by means of these knife-edges on two hard steel plates, accurately adjusted to the same level, and in this position it was allowed to oscillate, the times of its oscillations being determined as before. It then became possible to determine the moment of inertia from the following well-known formula—

$$t=\pi\sqrt{\frac{k^2+h^2}{gh}}\left\{1+\left(\frac{1}{2}\right)^2\sin^2\frac{\theta}{2}+\left(\frac{1.3}{2.4}\right)^2\sin^4\frac{\theta}{2}+\ldots.\right\}. \quad . \quad . \quad . \quad . \quad . \quad . \quad (25.)$$

Two series of experiments were made, the model vessel being loaded in the one series so as to weigh 197·18 lbs. gross, and in the other so as to weigh 255·43 lbs. Having obtained from the above formula a mean value of $k$ in respect to each of

* The apparatus, and the method of experimenting with it, are more fully described in the Appendix. It will be observed that in the diagram the amplitudes of the successive oscillations are shown to have diminished, up to a certain point. This diminution was found in a great number of experiments to take place with remarkable uniformity. The uniform diminution of the amplitude of oscillation as the body comes to rest, is of course due to the absorption of the *vis viva* of the rolling body by the water which it puts in motion, to the friction of the water which adheres to it on the rest of the water, to the resistance of the air, and to the friction and abrasion of the parts of the rolling body itself in the act of rolling. Mr. Rawson has made some experiments on this subject, the results of which he communicated to the British Association for the Advancement of Science.

† The precision with which the instant of the return of this wave and its progress are indicated, seems to show this method of experimenting to be well-suited to determining the velocities of waves.

these series of experiments, Mr. RAWSON verified these mean values by calculating from them the times of oscillation by the following equivalent formula:—

$$t=\sqrt{\frac{k^2+h^2}{gh}}\cdot \mathrm{F}c\frac{\pi}{2},$$

which I had previously communicated to him, in which $\mathrm{F}c\frac{\pi}{2}$ represents that complete elliptic function of the first order whose modulus is $c$. The results of these experiments and calculations are given in the following Table:—

| Gross weight of model. | Amplitude of oscillation on either side of vertical. | Time of oscillation by experiment. | Value of $\sqrt{k^2+h^2}$ by formula $\frac{\sqrt{ag}\cdot t}{\pi(1+f')}$ (see Appendix). | Mean value of $k$ deduced from the preceding column. | Time of oscillation calculated from the formula $t=2\sqrt{\frac{k^2+h^2}{gh}}\cdot \mathrm{F}\left(c\frac{\pi}{2}\right)$ with the preceding value of $k$, verifying that value. |
|---|---|---|---|---|---|
| lbs. | ° ′ | ″ | in. | in. | ″ |
| 197·18 | 5 0 | ·8190 | 11·983 | ..... | ·8348 |
| | 7 30 | ·8905 | 12·562 | 10·465 | ·8352 |
| | 10 0 | ·7930 | 11·554 | ..... | ·8359 |
| 255·43 | 2 30 | ·7280 | 11·070 | ..... | ·7280 |
| | 5 0 | ·6500 | 10·451 | 9·3294 | ·6500 |
| | 7 30 | ·7800 | 11·784 | | |
| | 10 0 | ·6760 | 11·706 | | |

Table of the times of the oscillation in water of a model vessel as determined,—1st, by the experiments of Messrs. FINCHAM and RAWSON; and 2ndly, by the formula (22.),

$$t=\frac{\pi k}{\sqrt{gh_1\left(1\mp\frac{W_2h_2}{W_1h_1}\right)}}\left\{1+\frac{4h_1^2+k^2}{4k^2}\sin^2\frac{1}{2}\theta_1\right\},$$

| Constants of formula. | Angle of oscillation $\theta_1$. | Time of oscillation in seconds by formula. | Time of oscillation in seconds by experiment. |
|---|---|---|---|
| Weight of model = 197·18 lbs. $W_2=0$ | ° 5 | ·75637 | ·798 |
| $k=10·465$ in. | 10 | ·75840 | ·798 |
| $h_1=4·9$ in. | 15 | ·76172 | ·840* |
| $t=·75668\left\{1+·46924\sin^2\frac{1}{2}\theta_1\right\}$ | 20 | ·76641 | ·784 |
| Weight of model = 255·43 lbs. $W_2=0$ | 5 | ·61094 | ·658 |
| $k=9·3294$ in. | 10 | ·61289 | ·665 |
| $h_1=5·97$ in. | 15 | ·61471 | ·616 |
| $t=·61033\left\{1+·56021\sin^2\frac{1}{2}\theta_1\right\}$ | 20 | ·64811 | ·602 |

23. *General considerations applicable to the stability of floating bodies.*

An exceedingly small pressure is sufficient to move a floating body from its position of stable equilibrium. As the inclination becomes greater the pressure must be increased until it attains, in a given position, its maximum value. Now if instead of this variable and continually increasing pressure we conceive a constant one to

* This experiment was faulty.

have been applied, less than the maximum one spoken of above, but considerably greater than that necessary to produce the initial motion, it is not difficult to see that this lesser pressure, by reason of its continued action on the body, may be sufficient to carry it *through* the position in which it would have required the *maximum* pressure to have *held* it; for in all the positions in which this pressure exceeded that necessary to move the body, the excess of its work over that of the resistance is accumulated under the form of *vis viva*, and in all those in which it fell short of that pressure, the work thus accumulated comes to its aid, and carries the body forward*.

24. To move a body from a given position into any other, it is not necessary that the work of the forces whence this change of position results should continue to be done upon it during the whole period of such change. They may be in the nature of pressures whose action ceases when they have communicated the *vis viva* necessary to continue the motion until the second position is attained, as in the case of the impact of one body on another, or of a gust of wind acting on a floating body, or of a blow of the sea.

In all these cases the excess of the work of the disturbing forces over that of the

* As an illustration of this principle, let us take the analogous case of a cylindrical body (fig. 7)—whose radius CD is represented by $a$—rolling on a horizontal plane, and to simplify the investigation let us suppose the force P, which causes it to roll, to be applied horizontally to the axis $c$. Let the weight of the cylinder be represented by W, and suppose it to be so loaded that the distance of its centre of gravity from its axis may be CG($=c$). Let the cylinder be made to roll through an angle ($\theta$) from the position in which it would rest, and in which CG is vertical. The work done upon it by P, whilst it thus rolls, is represented by $Pa\theta$, and the work opposed to its rolling by the weight of the cylinder, is $Wc$ vers $\theta$,

$$Pa\theta - Wc \text{ vers } \theta$$

is therefore the excess of the work of the forces whose tendency is in the direction of the motion over the work of those whose tendency is in the opposite direction. This excess represents one-half the *vis viva*, and in the extreme position into which the cylinder rolls and from which it begins to roll back, this vanishes, so that in this position

$$Pa\theta - Wc \text{ vers } \theta = 0.$$

If this position be the inverted position of the body $\theta = \pi$, and

$$P = \frac{2Wc}{\pi a}.$$

Now let us suppose that P, instead of being a constant pressure, had been made so to vary that in every position into which the body rolled it was only just sufficient to make it roll *slowly* out of that position. The maximum pressure P′, applied under these circumstances, would have been that corresponding to the position in which CG is horizontal, and would have been represented by the formula

$$P' = \frac{Wc}{a},$$

whence it follows that

$$P = \frac{2}{\pi} P' = \cdot 6366\, P';$$

so that the pressure, which, being continually applied the same in amount, would be sufficient to overturn the body, is less than two-thirds of that which must be exerted in its position of maximum effort, the lesser but constant pressure accumulating in its previous position, an excess of work which is sufficient to carry the body through and far beyond that position in which it would have required the greater pressure to have held it.

resistances accumulates, so as to be represented at any time by half the *vis viva* of the body, and it is the work accumulated under this form and in this amount, which, when the operation of the disturbing forces is withdrawn, carries the body forwards.

25. If, in the case of an oscillatory motion, the force which causes that motion be intermittent, and if the periods of this intermission so coincide with those of the body's oscillation that the force is withdrawn when any oscillation in its direction is completed, and renewed when the next oscillation in *that direction* begins, it is evident that the *vis viva* created by it in all such successive oscillations will be accumulated, and the amplitudes of the oscillations rendered, in succession, greater than one another, so that by the intermittent action of a small force which so synchronizes with the oscillations of the body on which it is made to act, a great inclination of its position from that of its equilibrium may eventually result*. This might for instance be produced, in respect to a floating body, by the action of gusts of wind or blows of the waves, repeated at stated intervals.

If the periods at which the intermittent work is done upon the body, instead of synchronizing with the commencement of each oscillation and thus favouring the motion, had so occurred as to oppose it at stated intervals (which may or may not synchronize with the body's own oscillations), it is evident that a complicated motion dependent on these several conditions will result, in which the oscillations will be repeated in cycles.

* As an illustration of this, let us suppose that in case of the cylinder (fig. 7), the motive force, instead of being applied horizontally to the axis, is a weight $w$ applied to the point D on its surface when the cylinder was inclined at the angle $\theta$ to its position of stable equilibrium; and that when the point D had, by the rolling of the cylinder, been made to descend until it again touched the plane, the weight $w$ was withdrawn, the cylinder completing its oscillation on the other side of the vertical by reason of the *vis viva* thus communicated to it.

On its return it will oscillate (the resistance being neglected) through the same angle, on the side of the vertical from which it started, as it completed on the opposite side. Let the weight $w$ be then placed again on the point D, and taken off a second time when this point comes in contact with the plane; and so continually, a rocking motion of increasing amplitude being produced by the alternate placing and withdrawal of the weight until at last the position of CG is reversed and the cylinder is overturned.

Let $\theta_1, \theta_2, \theta_3 \ldots \theta_n$ be the angles on either side of the vertical through which, in its successive oscillations, the cylinder is made to roll, then shall we obviously have the following relations:—

$$(Wc+wa)\operatorname{vers}\theta = Wc\operatorname{vers}\theta_1,$$
$$(Wc+wa)\operatorname{vers}\theta_1 = Wc\operatorname{vers}\theta_2,$$
$$\&c. \quad = \quad \&c.$$
$$(Wc+wa)\operatorname{vers}\theta_{n-1} = Wc\operatorname{vers}\theta_n.$$

Multiplying these equations together,

$$(Wc+wa)^n \operatorname{vers}\theta = (Wc)^n \operatorname{vers}\theta_n.$$

But $\theta_n = \pi$, $\therefore$ $\operatorname{vers}\theta_n = 2$ and $\operatorname{vers}\theta = 2\sin^2\frac{1}{2}\theta$,

$$\therefore (Wc+wa)^n \sin^2\frac{1}{2}\theta = (Wc)^n,$$

and

$$w = \frac{Wc}{a}\left\{\left(\operatorname{cosec}\frac{1}{2}\theta\right)^{\frac{2}{n}} - 1\right\}.$$

26. If, when the work of any disturbing force begins to be done upon a floating body, it be already acted upon by some other force, which has caused it to incline from the position in which it would otherwise rest through some given angle $\alpha$, as in the case of a squall or a heavy sea striking a ship already inclined by the action of a steady wind upon her beam; representing by $\theta$ the additional inclination given to it by the action of the disturbing force, whose work, in giving it this inclination, is represented by $u(\theta)$, and representing the work done through this same angle $\theta$ by the forces originally impressed, and still acting, upon it by $U(\theta)$, we have

$$Wc\{\text{vers}\,(\alpha+\theta)-\text{vers}\,\alpha\}=U(\theta)+u(\theta).$$

Differentiating and transposing,

$$\delta\theta=\{\delta U(\theta)+\delta u(\theta)\}\frac{1}{Wc\sin(\alpha+\theta)}.$$

The small additional angle $\delta\theta$ through which the body is made to roll by the application to it of a given small additional amount of work,

$$\delta U(\theta)+\delta u(\theta),$$

varies therefore inversely as the sine of the inclination, and is greatest in the position nearest to the vertical position; or, in other words, the body sustains in an inclined position a less change of that position by the application of a given disturbing force than it does in a vertical position. It yields most readily to the action of any disturbing force in its vertical position, and the further it is made to deviate from this position (within certain limits and under certain conditions), the more resolutely does it oppose any further deviation. This explains the liability of a ship to rolling when sailing before the wind, and her stiffness in the water when close hauled.

*Conclusions applicable to Ship-building.*

27. To make an alteration in the angle through which a ship rolls, it is necessary to elevate or to depress her weights. In the former case she will roll through a greater, and in the latter through a less angle. It does not alter the amplitude of rolling to move the weights horizontally, but only the time of rolling, provided the trim of the ship remain unaltered; for this does not alter the position of the centre of gravity of the ship or of the displaced fluid, and it is upon these that the stability of the ship depends (Art. 7 and equation 18.).

28. When a ship's motion is only a rolling motion, or about an axis parallel to her length, the position of that axis is, at any instant, determined by the intersection of a horizontal line through her centre of gravity, and a vertical line through the centre of gravity of her plane of flotation at that instant (Art. 19).

29. A ship should be so constructed that the centre of gravity of that plane of flotation, whose boundary is the load water-line, may be vertically above the centre of gravity of the ship. If this be not the case, the pressure of the additional water displaced by any vertical oscillation of the ship, acting obviously at the centre of gravity

of that plane and not in the same vertical with the centre of gravity of the ship, will cause, in addition to that vertical oscillation, a pitching or a rolling motion.

30. All the planes of flotation of the ship, when it is made to roll through small angles from its vertical position, should have their centres of gravity in the midship section (supposed to be that which contains the centre of gravity of the ship), and the centre of gravity of the displaced fluid should also always remain in this plane; for if that be not the case, it is obvious, from Art. 28, that the axis about which the vessel rolls cannot be parallel to its length, so that every rolling must be accompanied also by a pitching motion.

31. The angle through which a ship rolls under the action of a gust of wind, is essentially different from that at which it would be held inclined by the steady action of the same force of the wind, so that when the inclination which a given pressure would give to the ship, if applied to the centre of effort of the wind on the sails, is calculated (as is customary) by the formula known as that of Atwood, it is erroneous to conclude that the vessel, if subjected suddenly to that force of the wind, would incline only through that angle.

The experiments of Messrs. Fincham and Rawson, of which the results are stated in the Table, p. 615, show that it will roll through nearly double that angle, confirming, in this respect, the deductions of theory (Art. 2).

Neither can calculations, made by means of the theorem of Atwood, as to the respective pressures which would hold different ships inclined at the same given angle, be considered as determining with certainty their *relative* stabilities in respect to rolling; for the amplitude of each oscillation depends upon the stiffness of the vessel, not only in respect to that given inclination, but upon its stiffness at every other inclination which it must have passed through to reach that angle, and at every inclination which by reason of its acquired momentum it may pass through afterwards. The same observation is applicable to the effect of disturbances in the water-line and to blows of the waves.

32. All the causes which produce the rolling motion of a ship, whether they be gusts of wind, disturbances of the water-line, or blows of the waves, are measured in their effect upon it under the form of *work* (travail), so that according as a ship requires a greater or a less amount of work to be done upon her to cause her to roll through a given angle, there is a greater or less probability that, when at sea, she will roll through so great an angle as that. The angle through which the ship will be made to roll under the action of a given amount of *work*, is measured (Art. 7) by the product of her weight, by the difference or the sum of the vertical displacements of her centre of gravity, and the centre of gravity of her immersed part whilst she is in the act of rolling through that angle; the difference being taken or the sum according as these centres of gravity both ascend, or as the one ascends and the other descends; or in other words, it is *the work necessary to raise the vessel bodily through the difference or the sum of these vertical displacements.*

33. If therefore some existing vessel were fixed upon whose qualities in respect to rolling were well known, and if it were determined by calculation from this theorem what amount of work must be done upon that vessel to make it roll through some *given angle*; and this amount of work being so determined in respect to that existing ship, if, before all other ships of the same class were built, it were determined by a similar calculation, made from the drawings of those ships, whether a greater or a less amount of work would be necessary to make *them* roll through the same angle, then it would be known whether *these* ships would, under the like circumstances, roll more or less than *that* ship, and the forms proposed to be given them might be adopted or might be altered accordingly.

I conceive that by this means, if duly applied, great certainty might be given to the construction of ships in respect to rolling, and of course to pitching, for the same principles which apply to the one apply also to the other, with no other difference than in the direction in which the inclination is supposed to take place.

34. The force of the winds and waves, to the action of which a vessel is liable, may be supposed to vary as the surface she opposes to them, that is, to the area of her sails and the superficial dimensions of her hull. In vessels geometrically similar these vary as the squares of any of their similar linear dimensions, their lengths for instance. On the other hand, the weights of such vessels, supposed to be similarly loaded, varying as the cubes of their lengths; and the depths of their centres of gravity, and of the centres of gravity of their immersed parts, varying as their lengths; their dynamical stabilities, with reference to a given inclination, vary as the fourth powers of their lengths. Since, then, in reference to vessels thus geometrically similar, the disturbing forces, to the action of which they are subject, vary as the squares of their lengths and their stabilities as the fourth powers, it follows that their actual steadiness in the water will vary as the *squares* of their lengths, the greater vessel being more steady than the less in this proportion.

35. The expedients which I have pointed out for so designing a ship as to satisfy the conditions of easy rolling and pitching, suppose a knowledge of the exact position of the centre of gravity of the ship and of the centre of gravity of her displacement. The determination of these however is no new question; a knowledge of them has always been considered necessary to the skilful building of a ship, and the methods given for that purpose in books on ship-building are sufficiently accurate for the purpose, if the data are to be relied upon; and if not, nothing is required but the labour to determine these data.

36. That form of vessel in which the surfaces subject to immersion and emersion, when intersected by planes perpendicular to the vessel's length, *have circular* sections, having their centres in a common axis, is, *cæteris paribus*, eminently a *stable form*; because in a vessel of such a form (Art. 12.) the centre of gravity of the portion of the displaced fluid which is included within the solid of revolution (ATB figs. 3, 4) formed by all these circular sections, does not in the act of rolling *rise*.

If it be not practicable to give to the vessel, throughout its whole length, a form subject to these conditions, this is practicable with regard to the midship section, which is the governing section.

37. Of vessels having this general form, those are, *cæteris paribus*, the most stable in which the circular area, when completed, includes entirely the corresponding section of the ship (as shown in fig. 4), because, in respect to these ships, the centre of gravity of the displaced fluid *descends* as the ship rolls (Art. 13.); and when this is the case, the work necessary to incline the ship through any given angle (which measures its dynamical stability) is equal to that necessary to raise it bodily through a height equal to the *sum* of the vertical displacements which its centre of gravity, and the centre of gravity of the displaced fluid, suffer in that inclination, whilst in the opposite case, represented in fig. 3, it is equal to the work necessary to raise it through the *difference* of those heights*.

Of the class of vessels represented in fig. 4, the stability of those is the greatest, other things being the same, in respect to which the space STD between the circumference of the circular area and the hull of the vessel is the greatest.

38. It is not necessary to these results, taken in a general sense, that the sections of the vessels should be accurately circular as to their parts subject to immersion and emersion. If on the midship section of a ship a circle can be described, having its centre in the vertical axis of the section so as nearly to coincide with the parts of the periphery subject to immersion and emersion, then the ship may be distinguished as to whether it belongs to the class in which the centre of gravity of the immersion ascends or descends, by observing whether this circular area is wholly or only partly included within the section. The midship sections of Her Majesty's ships Vanguard, Bellerophon and Canopus present illustrations of this principle. They are represented in figs. 8, 9, 10. It will be observed, that if a circular area be struck on each section according to the conditions stated above, that area will in the Bellerophon and Canopus entirely include the corresponding sections of the hulls of the two ships, a wider space intervening between the two areas in the Canopus than the Bellerophon. Other things being the same, the former ought therefore to be the more stable ship. In the Vanguard the circular section does not wholly include that of the hull. This should therefore be the least stable ship of the three. These conclusions are, I believe, in accordance with the known qualities of the ships. If there be any ship whose midship section resembles that represented in fig. 3, the centre of gravity of its displacement will ascend in the act of rolling, and, *cæteris paribus*, it cannot but be an unstable ship.

* The hull may be so shaped as to cause the centre of gravity of the vessel to descend in the act of rolling. In this case $\Delta H_1$, equation 6, must be taken negatively. If the centre of gravity of the immersed part ascends, $U(\delta)$ will in this case be negative, and the position will be one of unstable equilibrium. If the centre of gravity of the immersion descends, $\Delta H_2$, in equation 6, must be taken positively; and if it exceeds $\Delta H_1$, the equilibrium will be stable.

In all these comparisons it has been supposed that the ships do not otherwise differ as it regards their stability, than in their approximation to the typical forms represented in figs. 3 and 4. It has been supposed therefore (see equation 17) that the depths of their centres of gravity and of the centres of gravity of the fluid they displace in a vertical position are the same, and that the moments of inertia of their planes of flotation are equal. This cannot be the case; and it is impossible to know to what extent this error in the hypothesis may in any particular case affect the measure of the dynamical stability, except by calculating it by formula 17. The problem is far too complicated to render the application of any general principle—except with this precaution—safe. It is not—in this respect as in others—more practicable to dispense with the resources of mathematical reasoning and of calculation, in building the ship, than, after she is built, in sailing her.

39. It is a deduction of theory (equation 24.), and is confirmed by experiment, that, within the ordinary limits of rolling, the *Time* of a vessel's rolling is independent of the angle through which it rolls, being dependent only upon the form of the vessel, its weight, the position of its centre of gravity, and its moment of inertia about an axis passing through that point (see equation 24); so that every different vessel, when loaded in a given manner, has *a time of rolling proper and peculiar to it*, and which may be said to *characterize* it. And the same is true of the time of pitching.

40. This time of the oscillations of the ship may have such a relation to the times of oscillation of the waves* as to cause the blows of the sea to be received by the ship at those instants when they will produce the greatest effect on the amplitude of her oscillations (Art. 25.), and thus a little sea may, under certain circumstances, produce very heavy rolling.

If there be not this relation between successive oscillations of the ship and of the waves, then there will be, during a certain number of oscillations, an antagonism of the two, until the times of the one class of oscillations have so gained upon those of the other as to bring about an interference. The vessel will then probably be comparatively at rest. Then will follow a series of oscillations of the waves and the ship, which will in various degrees concur to produce heavy rolling, until it reaches a maximum, when the same cycle of changes will be gone through again†.

41. The straining of the ship in the act of rolling, is dependent upon the time of its oscillations. This straining takes place in every part of it, but more particularly (by reason of their elasticity) in the masts. When the rolling begins, the higher parts of the masts, by reason of their inertia, remain behind the lower portions, and the masts bend; as the rolling proceeds they receive an independent motion

* If the ship be under sail, the rate at which she sails and the distances of the waves from one another, measured in the direction in which she sails, are also among the conditions on which her rolling depends.

† This cyclical antagonism and concurrence of the independent oscillations of the waves and the ship will interfere, to a certain extent, with the tautochronism of the ship's oscillations.

from their elasticity, influenced, besides this cause, by their weight and length, and this motion assumes the form of an independent oscillation, affecting more or less the oscillatory motion of the vessel itself.

If, at the instant when the ship would otherwise begin to roll back, the elasticity of its masts is in the act of carrying them forwards, there will be a violent strain of the ship, which would not take place in a ship so constructed or so loaded as to create that synchronism of the independent oscillations of the vessel and its masts, which is implied in the fact that she does not strain herself in rolling.

42. The properties of different ships with regard to the strain they suffer in rolling, and whether, in respect to the seas which are of most frequent occurrence, they roll easily or heavily, are probably well known, so that it would be possible to fix upon some ship of each class which might in this respect serve as a standard with which other ships of that class might be compared. The time of oscillation proper and peculiar to this ship might also be ascertained by experiment. It would then become possible to build and load all other ships of that class so as to oscillate in the same time as that ship, and thereby ensure, supposing them to be masted in the same way, very nearly the same qualities in regard to the strain they suffer in rolling.

The form of the ship so constructed need not however in any respect resemble that of the standard ship; all that is required is, that—in respect to the dimensions of its parts and the distribution of its weights when loaded—it should satisfy the conditions implied in assigning a given value to $t(\theta_1)$ in equation 24. In all other respects full latitude is allowed to the builder*.

43. I have shown (Art. 19.) that the axis about which the ship may at any instant be conceived to roll is perpendicular to two straight lines, one of which is drawn horizontally from the vessel's centre of gravity parallel to the direction in which it is rolling, and the other vertically through the centre of gravity of its plane of flotation at that instant.

Its *vis viva*, when rolling or pitching, is therefore greater as its weights are placed at a greater distance from this axis, and less as they are nearer to it.

Whence it follows as a general principle (equation 24.), that the ship is made to roll more slowly by moving its weights to a greater distance from this axis, as when the yards are run up; and more quickly by bringing them nearer to it, as when the guns are run back in a heavy sea to diminish the strain on the ship's timbers.

44. The form under which $H_2$ enters equation 24, shows that the greater the depth of the centre of gravity of the ship's displacement the more slowly (other things being the same) will she roll, provided that she be a ship of that class of which fig. 3 is the type, in which this quantity (*i. e.* the depth of the centre of gravity of the displacement) diminishes as the vessel rolls; but that if, on the contrary, she belongs to

* Taking a ship, whose form may indeed (within certain assignable limits) be any whatever, it is in his power, guided by that equation, so to *load* it as that it shall oscillate in the same time with any other ship whose form may be in all respects different.

the class of which fig. 4 is the type, the centre of gravity of whose displacement descends in the act of rolling, she will roll the faster as this centre of gravity is seated deeper in her hull.

45. It may be received as a general rule that (other things being the same) vessels of the class fig. 4 roll more quickly than those of the class fig. 3, but do not roll so far. So that unless some special provision be made for that end, stability in rolling may not, and will not probably be obtained except at the expense of quick rolling.

46. The form under which A enters equation 24, shows that breadth of beam is not *of itself* conducive to slow rolling, and that it can only tend to it indirectly, by carrying the ship's weights further from the axis about which it rolls, and thereby augmenting the quantity $k$, which represents in the formula the moment of inertia of the ship, and is the ruling element of the time. The form under which $W_1$ enters the equation shows heavy loading to be conducive to slow rolling.

47. It would be unsafe however to be guided in the construction of a ship by any one of these considerations taken separately from the rest, for there is scarcely any element of the discussion which can be changed without bringing about a change in an opposite direction in some other.

What will be the total result of any proposed change, and by what means the whole object sought by it is to be accomplished, can only be determined by that complete mathematical discussion of the question in all its elements, the principles of which it has been the object of this paper to develope, and which the formulæ contained in it afford a means of applying.

*December* 1, 1849.

## APPENDIX.

*Experiments on the Dynamical Stability and the Oscillations of Floating Bodies. By* JOHN FINCHAM, *Esq., Master Shipwright in Her Majesty's Dockyard, Portsmouth, and* ROBERT RAWSON, *Esq.*

Experiments necessary to verify the formula 6,

$$U(\theta)=W(\Delta H_1-\Delta H_2),$$

which represents the work done in deflecting a floating body through an angle such that the height through which the centre of gravity of the floating body is raised shall be $\Delta H_1$; and the height through which the centre of gravity of displacement is raised, shall be $\Delta H_2$.

For this purpose two models were made, such that their sections were uniform throughout the whole length of the model: the section of one was a triangle, and of the other a circle (see figs. 1, 2).

If the reader will refer to Art. 10 for a general description of the apparatus, the following explanation of the drawing fig. 1 will be sufficient to show how the experi-

ments have been conducted. It represents a section of the model; TK is the yard by means of which the deflecting weight hanging at Q, deflects the model from the upright position. AC is water-line in the upright position, and BD that in the extreme position into which it rolls; EF that in the position in which it finally rests.

In the first place, the model is adjusted by means of moveable weights, until the water-line AC is parallel to the upper side, LN, of the model; and then a string, SK, is fixed at S and K, so that when the deflecting weight is placed at Q no effect is produced by the deflecting weight on the model until the string SK is cut (RS is a fixed beam independent of the model).

When the string SK is cut there is an extreme deflection where the water-line becomes BD, and a permanent deflection where the water-line becomes EF.

These lines are determined in the following manner: PX is a thin graduated scale, fixed at P at right angles to the arm of the lever TK, and having a strip of prepared paper fixed upon its surface, which shows distinctly, by the depth to which it is wetted when the vessel rolls, a point in the extreme position of the water-line. Two other points in this position of the water-line are determined by means of scales similarly applied to L and N.

When any two of these three points are observed, a section of the model being drawn of the half-size on a drawing-board, we could set off upon it the distances $Pp$, $Ll$, $Nn$, and thus draw in the water-line BD. There is no occasion to use prepared paper to show the water-lines, excepting in the ultimate deflection.

The paper which we used, and which answered the purpose admirably, was nothing more than common writing-paper rubbed over with a little colouring, in order to take off from the surface of the paper any oily matter which might prevent the water's making a distinct mark upon it.

This means was adopted as the best means, after several other expedients had been tried with partial success.

The centre of gravity G was determined by observing the permanent water-line EF in a number of deflections by means of various deflecting weights. The position of this water-line, for any given deflecting weight, being set out on the drawing, we were enabled, knowing the weight of the vessel, to determine the position of the centre of gravity, by well-known principles of statics, with no other aid than that of the scale and compasses. Suffice it to say, that great care was taken to get this point.

The points H and $h$, which are the centres of gravity of the part immersed in the vertical position of the vessel and in the position into which it rolls, were determined from the known property of the centre of gravity of a triangle in fig. 1, and from the common formula for determining the centre of gravity of the segment of circle in fig. 2.

The drawings were made to half size from the following Table, which was filled up during the time the experiments were in operation: this circumstance enabled us obtain all the data required for our computations with extreme exactness.

## Cylindrical Model.

| Model at rest, without the deflecting weight. | | | Model at rest, with the deflecting weight. | | | Model at ultimate deflection, with deflecting weight. | | | Weight of the model and deflecting weight. | | Distance from centre of model to P and Q. | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| L. | Lz. | Nz. | Po. | Lq. | Nr. | Pp. | Ll. | Nn. | Deflecting weight. | Weight of model. | P. | Q. | |
| | | | | | | | | | lbs. Av. | lbs. Av. | ft. in. | ft. in. | |
| | $8\frac{1}{16}$ | $8\frac{1}{16}$ | ... | 6 | $10\frac{1}{2}$ | $31\frac{1}{16}$ | $4\frac{3}{16}$ | ... | 1·957 | 197·18 | 3 $6\frac{1}{2}$ | 5 $4\frac{1}{2}$ | (2.) |
| | 8 | $8\frac{1}{2}$ | ... | 6 | $10\frac{1}{2}$ | $31\frac{3}{16}$ | $4\frac{1}{2}$ | ... | ..... | ..... | 3 $6\frac{1}{2}$ | 5 $4\frac{1}{2}$ | |
| | | | | $6\frac{1}{2}$ | $9\frac{1}{2}$ | ..... | ... | ... | ..... | ..... | 3 $6\frac{1}{2}$ | 4 $0\frac{1}{2}$ | |
| | 6 | $6\frac{1}{2}$ | ... | $4\frac{3}{4}$ | $7\frac{1}{16}$ | $34\frac{3}{16}$ | $3\frac{1}{2}$ | ... | 1·957 | 255·43 | 3 $6\frac{1}{2}$ | 5 $4\frac{1}{2}$ | (3.) |
| | | | | $5\frac{1}{2}$ | 7 | ..... | ... | ... | ..... | ..... | 3 $6\frac{1}{2}$ | 4 $0\frac{1}{2}$ | |
| | 6 | $6\frac{1}{16}$ | 31 | $2\frac{1}{4}$ | $9\frac{7}{16}$ | $20\frac{1}{2}$ | $0\frac{1}{2}$ | ... | 5·0285 | 255·43 | 3 $6\frac{1}{2}$ | 5 $4\frac{1}{2}$ | (4.) |
| | | | $33\frac{1}{2}$ | $3\frac{7}{16}$ | $8\frac{7}{16}$ | 21 | ... | ... | ..... | ..... | 3 $6\frac{1}{2}$ | 4 $0\frac{1}{2}$ | |
| | $8\frac{1}{2}$ | $8\frac{1}{2}$ | 34 | 5 | $11\frac{7}{16}$ | $24\frac{1}{16}$ | $2\frac{3}{16}$ | ... | 2·8225 | 197·18 | 3 $6\frac{1}{2}$ | 5 $4\frac{1}{2}$ | (5.) |
| | | | $36\frac{1}{2}$ | $5\frac{1}{2}$ | $10\frac{7}{16}$ | ... | ... | ... | ..... | ..... | 3 $6\frac{1}{2}$ | 4 $0\frac{1}{2}$ | |

The position of the water-line corresponding to the extreme position into which the model rolled being thus determined in every experiment, the corresponding displacement was also known. In fig. 1, this displacement having a triangular section *eMf*, its centre of gravity *h* could readily be determined by construction. In fig. 2, the displacement having a circular section, its centre of gravity *h* could be determined by known rules. Drawing a perpendicular *hc* from *h* upon BD, this line measures the depth of the centre of gravity of the immersion in the extreme position into which the vessel rolls, and H*a* measures it in the vertical position; therefore the difference of these lines measures its elevation in the act of rolling. In like manner the perpendicular G*ó* measures the depth of the centre of gravity of the *model* when the water-line was BD, and G*a* was its depth in the vertical position, therefore the difference of these lines is its elevation in the act of rolling.

Thus the elevations of the centre of gravity of the model and of the centre of gravity of the displaced fluid, in the act of rolling, are found, and its weight being known, the work which must have been done upon it to cause it thus to roll may be determined according to equation 6.

But the work actually done upon it by the deflecting weight may, in like manner, be determined; for if a perpendicular Q*o* be drawn from Q on BD, the length of this line will be the height of Q when the water-line was BD, and Q*m* was its height in the vertical position, therefore the difference of these lines is the space through which the deflecting weight has descended vertically; and the product of this distance of the deflecting weight gives the work actually done by it upon the rolling body. This amount of work ought, by the theory, to be the same with that found as above from equation 6; and the comparison of results thus obtained, by theory and experiment, constitutes a verification of the formula, and is given in the Table, p. 615.

A single example will show the way in which the calculations were made.

In the triangular model, Experiment 1, the following dimensions were measured in inches:—

$$Ga=1{\cdot}75,\quad Gb=1{\cdot}05,\quad Ha=2{\cdot}75$$
$$hc=2{\cdot}24,\quad Qm=15{\cdot}2,\quad Qo=3{\cdot}9$$

$\therefore$ elevation of centre of gravity of model, in feet $=\frac{1{\cdot}75-1{\cdot}05}{12}=\Delta H_1$

elevation of centre of gravity of displaced fluid, in feet $=\frac{2{\cdot}75-2{\cdot}24}{12}=\Delta H_2$

weight of model in lbs. . . . . $=33{\cdot}8626=W.$

$\therefore$ by equation 6, $U(\theta)=\left\{\frac{(1{\cdot}75-1{\cdot}05)-(2{\cdot}75-2{\cdot}24)}{12}\right\}\times 33{\cdot}8626={\cdot}5361.$

Also vertical descent of deflecting weight, in feet $=\frac{15{\cdot}2-3{\cdot}9}{12}$,

deflecting weight Q in lbs. $={\cdot}5485$;

$\therefore$ by experiment $U(\theta)=\left\{\frac{15{\cdot}2-3{\cdot}9}{12}\right\}\times{\cdot}5485={\cdot}5165.$

The computations on both these models, made in accordance with formula 6, agree with the experiments.

All the experiments show what we conceive to be important, that the same moment of force which is necessary to maintain a vessel in a position $\theta$ at rest, will deflect the vessel through nearly twice $\theta$ when made to act upon a vessel which is not deflected. Atwood's statistical stability therefore appears to us to be of little use, so far as the rolling of the vessel is concerned.

### *Experiments on the Time of Oscillation.*

To find the moment of inertia of a cylindrical model, whose radius is 13·5 inches, weight 197·18 lbs. avoirdupois, round an axis passing through the axis of the cylinder.




ABC is a vertical section of the cylinder passing through its centre of gravity G.

It is required to find the moment of inertia of the cylindrical model, about an axis passing through O, the centre of the cylinder at right angles to the section ABC.

For this purpose the model was made to oscillate out of the water, upon knife-edges passing through O and parallel to the sides of the cylinder. Several experiments were carefully made, and the times of oscillations were observed through the amplitude of 5°, $7\frac{1}{2}$° and 10°. The apparatus by means of which the times were observed, enables us to measure the times of oscillation to an exactness of ·013 of a second, or in round numbers to the one-hundredth part of a second of time.

If T= time of oscillation of a simple pendulum,
$2\theta$= angle of amplitude of oscillation,
$r$= length of pendulum,
$g$= 32·19084 feet,
$\pi$= 3·1415927, &c. &c.,
we have

$$T=\pi\sqrt{\frac{r}{g}}\left\{1+\left(\frac{1}{2}\right)^2\left(\frac{\text{vers}\,\theta}{2}\right)+\left(\frac{1.3}{2.4}\right)^2\left(\frac{\text{vers}\,\theta}{2}\right)^2+\left(\frac{1.3.5}{2.4.6}\right)^2\left(\frac{\text{vers}\,\theta}{2}\right)^3+\&c.^*\right\}.$$

Put R= radius of oscillation of a compound pendulum.

Then the time of oscillation of the compound pendulum will be the same as in the case of the simple pendulum, if we put R instead of $r$ in the above formula.

$$T=\pi\sqrt{\frac{R}{g}}\left\{1+\left(\frac{1}{2}\right)^2\left(\frac{\text{versin}\,\theta}{2}\right)+\left(\frac{1.3}{2.4}\right)^2\left(\frac{\text{versin}\,\theta}{2}\right)^2+\left(\frac{1.3.5}{2.4.6}\right)^2\left(\frac{\text{versin}\,\theta}{2}\right)^3\&c.\right\}. \quad . \quad . \quad (26.)$$

We may here observe that

$$R=\frac{k^2+h^2}{h},$$

where $k$= the radius of gyration about the centre of gravity, $h$= the distance from the centre of suspension to the centre of gravity of the model.

Since

$$\frac{\text{versin}\,\theta}{2}=\frac{1-\cos\theta}{2}=\sin\frac{\theta}{2},$$

we shall have

$$T=\pi\sqrt{\frac{k^2+h^2}{gh}}\left\{1+\left(\frac{1}{2}\right)^2\sin\frac{\theta}{2}+\left(\frac{1.3}{2.4}\right)^2\sin^4\frac{\theta}{2}+\left(\frac{1.3.5}{2.4.6}\right)^2\sin^6\frac{\theta}{2}+\&c.\right\}. \quad . \quad . \quad (27.)$$

If we put

$$f(\theta)=\left(\frac{1}{2}\right)^2\sin^2\frac{\theta}{2}\left\{1+\left(\frac{3}{4}\right)^2\sin^2\frac{\theta}{2}+\left(\frac{3.5}{4.6}\right)^2\sin^4\frac{\theta}{2}+\&c.\,\&c.\right\}, \quad . \quad . \quad . \quad . \quad . \quad (28.)$$

equation (4.) will become

$$T=\pi\sqrt{\frac{k^2+h^2}{gh}}\{1+f(\theta)\}.$$

From which equation we obtain

$$\sqrt{k^2+h^2}=\frac{\sqrt{gs}}{\pi\{1+f(\theta)\}}\times T. \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (29.)$$

If $T_1$, $T_2$, $T_3$ be the time of the first, second and third oscillations during the time that $\theta$ and $s$ remain constant, we shall have

$$n\sqrt{k^2+h^2}=\frac{\sqrt{gs}}{\pi\{1+f(\theta)\}}\left\{T_1+T_2+T_3+\&c.\text{ to }n\text{ terms}\right\},$$

$$\therefore\ \sqrt{k^2+h_2}=\frac{\sqrt{gs}}{n\pi\{1+f(\theta)\}}\left\{T_1+T_2+T_3\,\&c.\text{ to }n\text{ terms}\right\}. \quad . \quad . \quad . \quad . \quad . \quad . \quad (30.)$$

* See Poisson's Traité de Mécanique, p. 348.

For very small angles of amplitude $f(\theta)$ is very small, and may be entirely neglected, showing that for small angles the oscillations are independent of the angles.

The value of $\sqrt{k^2+h^2}$ was in the first place calculated in respect to *one* of the quantities $T_1$, $T_2$, &c., then in respect to *two*, and so on, to *four*. The mean of these four values being then taken in respect to each experiment, a final mean was taken in regard to all the experiments. The data and the results are stated in the following Table as it regards the value of $\sqrt{k^2+h^2}$, and the rest in the first Table, p. 629. The times of oscillation, as calculated by formula (22.) and as determined by experiment, are stated in the second Table on that page.

| | Angle of oscillation $\theta$. | $1+f\theta$. | Value of $\sqrt{k^2+h^2}$ calculated in inches from time of | | | | Mean value of $\sqrt{k^2+h^2}$ in each experiment. | Mean value of $\sqrt{k^2+h^2}$ in all the experiments. |
|---|---|---|---|---|---|---|---|---|
| | | | One oscillation. | Two oscillations. | Three oscillations. | Four oscillations. | | |
| W=197·18 lbs..... | ° ′ 5 | 1·0004762 | 11·336 | 11·780 | 12·356 | 12·461 | 11·983 | 12·033 |
| | 7 30 | 1·0010723 | 12·318 | 12·200 | 12·828 | 12·903 | 12·562 | |
| $h$=4·9 inches ..... | 10 | 1·0019072 | 12·003 | 11·620 | 11·620 | 11·870 | 11·550 | |
| W=255·43 lbs..... | 2 30 | 1·0000235 | 11·128 | 10·731 | 11·194 | 11·227 | 11·07 | 11·076 |
| | 5 | 1·0004762 | 9·429 | 10·328 | 10·924 | 11·123 | 10·451 | |
| $h$=5·97 inches ..... | 7 30 | 1·0010723 | 11·910 | 11·315 | 11·976 | 11·935 | 11·784 | |
| | 10 | 1·0019072 | 10·332 | 10·818 | 11·446 | 11·414 | 11·000 | |

# XXXI. *Electro-Physiological Researches. On Induced Contraction.—Ninth Series.*

*By Signor* Carlo Matteucci, *Professor in the University of Pisa, &c. &c.*
*Communicated by* W. R. Grove, *Esq., F.R.S.*

Received May 13,—Read June 20, 1850.

It is not without considerable regret that I am compelled to depart from my established rule of never publishing any facts relating to electro-physiology without having previously endeavoured to connect them with those already discovered, and without having succeeded in reproducing them in such a constant and unvarying manner as to remove the slightest doubt of their truth. The announcement, however, just made to the Académie des Sciences by M. du Bois Raymond of a work "*On the Law of Muscular Current, and on the Modification which that law undergoes by the effect of Contraction,*" obliges me, though unwillingly, to transmit to the Royal Society the continuation of my researches on induced contraction, confining myself, for the present, to some fundamental experiments, made a long time since, for the publication of which I should have wished to await a more favourable moment.

In the Third and Fifth Series of my Electro-physiological Researches*, I studied, with all possible care, and in its minute details, the fact of induced contraction, in order to deduce the law of this phenomenon, and from thence to be led to the discovery of its cause. In the Fifth Series, principally, I was led to conclude, that, according to all the analogies, and without being in opposition to the experiments, induced contraction might be considered to be the effect of an electric discharge which takes place during the act of muscular contraction.

In a memoir published in the Annales de Physique et de Chimie, Octobre 1847, after having given an exposition of the laws of the electrical discharge of fish, and demonstrated all the analogies existing between this function and muscular contraction, I declared still more explicitly, that experiment leads to the admission that in muscular contraction there is a phenomenon analogous to that of the discharge of the Leyden phial, and which was the cause of induced contraction. Nevertheless it has been my wish that this conclusion, which I have always studiously announced with extreme reserve, should be demonstrated by direct experiment, and this object I have vainly endeavoured to attain in making use of the galvanometer.

In the memoirs above cited, are to be found a description of all the efforts made to this purpose; by forming piles with muscular elements of the frog and making these elements contract, I endeavoured, but always without satisfactory result, to obtain

* Philosophical Transactions, Part II. 1845, 1847.

from the galvanometer signs of electrical phenomena produced by the act of contraction. The variations produced in the conductibility of the circuit, by the convulsive movements of the muscles of the frogs, which alter the points of contact between the elements of the pile, the agitation of the liquid into which the platina plates of the galvanometer are plunged, are constant and inevitable causes of the production of an electric current, which involves a constant uncertainty as to the effects which may depend on contraction. These same causes of error exist in the experiment made by M. DU BOIS REYMOND on voluntary contraction of a man's arm; I have tried a great number of experiments, following his method, increasing the number of elements which contract at the same time, without ever succeeding in obtaining an evident and constant development of electricity by muscular contraction. In the researches for the discovery of this development, I have not failed to employ, with all proper care, the galvanoscopic frog. Operating on a circle of thirty and forty individuals, who all contracted the same arm at the same time, and although the galvanoscopic frog, the nerve of which formed part of the circuit (being in contact with the two outermost fingers of this pile of men), was extremely sensitive, yet never did we obtain the slightest sign of a current from voluntary contraction. Yet the circuit, though composed of a great number of individuals, was always a sufficiently good conductor for the transmission of a current of some muscular elements, capable of producing contraction in the galvanoscopic frog.

Since, therefore, the galvanometer employed in my first experiments on induced contraction, and by means of which M. DU BOIS REYMOND thinks that he has discovered the development of electricity in voluntary muscular contraction, never has with me led to any other but uncertain and very doubtful results, since by the aid of the galvanoscopic frog, used as a substitute for the galvanometer, I have *never obtained the slightest signs* of an electric current in the voluntary contraction of the muscles of the arms, I was authorized in concluding that the development of electricity by muscular contraction still remained to be demonstrated by experiment, and that the phenomenon of induced contraction was still that which led most directly to this result.

I will now give some new experiments on induced contraction, of incontestable evidence and certainty, and which undoubtedly lend an increasing probability to the conclusion that induced contraction is due to an electric discharge, and that muscular contraction is accompanied by a development of electricity.

Exp. 1. I prepare a frog in the usual manner, and I lay on the muscles of its thighs, legs, and on the articulations of its claws, the nerves of highly sensitive galvanoscopic frogs: on provoking the contraction of the muscles of the first frog by irritating its lumbar nerves, the galvanoscopic frogs contract, and when these first contractions are very violent, induced contraction may be seen to take place on contact even with the extremities of the limb of the entire* frog. The signs of in-

* I apply the word entire to the frog fastened on the glass tubes: see figs. 1 and 3.

duced contraction are always obtained stronger and more durably on the muscles of the thigh and leg, than on the other parts of the frog.

Exp. 2. Induced contraction is very evident at the moment when the muscle itself, on which is laid the nerve of the galvanoscopic frog, is divided. This experiment is perfectly analogous to that which is made by cutting, in different directions, a very small piece of the organ of the torpedo, upon which a nerve of the galvanoscopic frog has been placed.

Exp. 3. Induced contraction is produced in the same manner, and with equal intensity, whatever may be the direction in which the nerve of the galvanoscopic frog is extended, in respect to the muscular fibres.

Exp. 4. If we interpose between the nerve of the galvanoscopic frog and the surface of the thigh of the entire frog several layers of wet paper, we cease to obtain induced contraction: if there is only a layer or two of very thin paper, induced contraction continues to be produced.

Exp. 5. We dispose a prepared frog, as in Plate L. fig. 1; *a c* and *b d* are two glass tubes covered with varnish, upon which the frog is fixed by means of Indian rubber rings, *e* and *f*; *g* and *h* are two bits of linen, or of thick paper moistened with salt water. If we touch separately the point *g* or the point *h* with the nerve of the galvanoscopic frog, there is no sign of induced contraction; but if the nerve of the galvanoscopic frog be disposed as in fig. 1, so that the nerve touches at the same time the points *g* and *h*, we have immediate contraction in the galvanoscopic frog, exciting contractions in the muscles of the entire frog. This takes place in whatever manner the contractions are provoked, whether by wounding or cutting the spinal marrow, or in passing an electric current from a small pair of zinc and platina along the lumbar nerves.

Exp. 6. If, while making the preceding experiment, a communication be established between the two legs of the frog, by placing a wetted cotton wick over the points *t s* or *p* and *q*, or over all the intervening points, the contractions of the galvanoscopic frog cease instantly, although the members of the entire frog are in contraction: we have only to remove the cotton wick and the phenomenon reappears. These alternatives are constant, and are always reproduced in the same manner.

Exp. 7. The results of the preceding experiments are obtained whether the legs of the entire frog are brought into contact or whether they are kept separate. We see from this the advantage of the arrangement adopted in these experiments in order to avoid placing the frog on a plane, which would soon become moistened and serve as a conductor.

Exp. 8. By means of a solution of the extract of nux vomica, I produce a state of nervous superexcitation in the frogs. While in this condition these animals are subject at intervals to violent contractions, which may also be excited by the slightest contact. I place a frog in this condition on the apparatus, fig. 1. The galvanoscopic frog rarely gives signs of contraction, while the entire frog contracts violently. *One*

*of the lumbar nerves ought now to be cut*; this being done, we are certain to obtain contractions in the galvanoscopic frog, at each contraction of the entire frog; these contractions cease if the two legs are brought into communication with the wetted cotton, as in the preceding experiment.

Exp. 9. I take a half frog, and instead of the other half, I employ a wick of cotton, *v*, *r* (fig. 2), one end of which touches the upper part of the leg or thigh, and the other the nerve of the galvanoscopic frog, *g p n*. The other extremity of this nerve rests on the lower part of the leg of the half frog, a thick stratum of wetted paper (*o*) being placed between the nerve and the leg. Every time that the half frog contracts the galvanoscopic frog contracts also; the latter ceases to contract if one removes the upper end (*v*) of the cotton wick from its contact with the upper part of the leg. It ought to be observed, that in this arrangement of the experiment we obtain the contraction of the galvanoscopic frog at the instant that we place the nerve in this sort of circuit.

This experiment has been tried with equal success operating on the limb of a living rabbit.

Exp. 10. Instead of one galvanoscopic frog I dispose two, as in fig. 3, and by irritating first one lumbar nerve and then the other, I produce contractions in each limb separately. During the first moments the two galvanoscopic frogs, *c* and *d*, contract, whichever may be the limb of the entire frog which contracts. Afterwards, when the galvanoscopic frogs begin to be less sensitive, we are sure to obtain contractions in the galvanoscopic frog, *d*, only when the limb *a* contracts, and the contraction in the galvanoscopic frog *c*, when it is the limb *b* which contracts. We obtain the same result by employing the arrangement adopted in fig. 2, representing the non-contracting limb by the wet cotton wick, disposed in the manner already described. Thus, if instead of having the nerve, *g p*, disposed as in fig. 2, we reverse the position of the nerve of the galvanoscopic frog in such a manner as to touch the cotton wick with its upper part, and the point, *o*, superposed on the limb with its lower part, either no contraction at all is obtained, or it soon ceases.

Exp. 11. I cut the thigh of a frog, above and below, so as to form a piece, *a b* (fig. 4), similar to a portion of a cylinder the two circular bases of which are the interior surfaces of muscle. The nerve of the galvanoscopic frog, *g p*, is disposed on the surface of this cylinder so as to be exactly parallel with the two bases. If we irritate the point *c* there are signs of induced contraction.

It is impossible for me to confine myself to the simple description of these experiments without deducing from them some conclusions, the most evident of which appear to me to be the following:—

1. The cause of induced contraction, according to all analogies, is the same as that which produces contraction of the galvanoscopic frog in the *sixth* and *following* experiments.

2. The cause of these contractions is evidently an electrical phenomenon developed

in the act of contraction, and which consists in a different state of electricity in the different points of the contracted limb.

3. This electrical phenomenon, like the contraction which produces it, lasts only for an instant.

4. These electric states, developed by contraction, tend to produce electrical currents which circulate in opposite directions across a conducting arch interposed between the two limbs, which contract at the same time.

5. The tenth experiment proves the existence of these currents and their directions; here we should remember that the galvanoscopic frog is more sensitive to the passage of the current when that current traverses the nerve in the direction of its ramification. Thus the contraction of the galvanoscopic frog, *d* (fig. 3), during the contraction of the limb, *a*, proves the existence of the electrical current, which goes from *a* towards *d*. The contraction of the galvanoscopic frog, *c*, during the contraction of the limb, *b*, proves, in the same manner, the existence of an electrical current going from *b* towards *c*.

Whatever the theory of these phenomena may be, it is certain that they demonstrate the production of an electrical *disequilibrium* in the act of muscular contraction.

In the experiments which have been described, this electro-physiological phenomenon may consist in a species of discharge, propagated in muscles in the direction of the ramification of the nerves. Is the cause of this discharge a phenomenon analogous to that of electrical fish, or does it consist in a change in the natural conditions of the muscular current, produced by contraction? In the present state of science it is impossible for us to answer this question. According to all the analogies, and according to our present experimental knowledge, we lean to the former of these two explanations; but we wait the light of new experiments to proceed safely further in this difficult field of science.

*Pisa, April* 1, 1850.

## XXXII. *Contributions to the Chemistry of the Urine.*—Paper IV.

### *On so-called Chylous Urine.*

*By* Henry Bence Jones, *M.D., M.A.Cantab., F.R.S., Physician to St. George's Hospital.*

Received January 21,—Read March 14, 1850.

URINE white from the suspension of a quantity of fatty matter in it, has been called chylous urine, and the albumen and fibrin which escape from the blood with the fat have been considered to belong to the chyle and not to the blood.

An opportunity of observing a case of this disease having occurred to me, I was led to make the following experiments. The conclusions therefrom are,—

1st. That the fat on which the white colour of the urine depends does indeed appear in the urine after the chyle is absorbed, but the albumen, fibrin, blood-globules and alkaline salts, may be found in the urine previous to any food being taken, and these substances can be made to appear in, or disappear from the urine according as the circulation is hurried by motion or quieted by rest.

2nd. That the disease consists in some slight alteration in the structure of the kidney, by which, when the circulation is most active, one or more of the constituents of the blood passing through the filter escape from the vessels into the urine.

The supposition that the disease consists in an accumulation of fat in the blood which is thrown out by the kidneys carrying with it albumen, fibrin, blood-globules and salts, is altogether disproved, both by actual analysis of the blood itself, and by the frequent occurrence of a large jelly-like coagulum in the urine, when no white fatty matter can be seen to be present.

For an account of the patient and for the treatment and its ultimate effect in stopping the escape of the white water, which he had passed more or less frequently for nine months previous to my seeing him, I must refer to the Medico-Chirurgical Transactions for 1850.

On the 19th of October he came to me, having taken food last at 11 A.M. The water passed at 2 P.M. solidified like blanc mange in ten minutes. It contained, when passed from the bladder, some clots ready-formed. It was very feebly acid to test-paper. Thrown on a filter, a very small quantity of reddish streaked fibrin remained on it. The filtered fluid, at 60° Fahr., had a specific gravity =1015. It coagulated by heat and acid. In appearance it was quite milky, but became clear when agitated with a considerable excess of ether. Some perfectly healthy blood-globules were seen with the microscope, and the granules of fat were so small as scarcely to be resolvable by a high power.

574·0 grs. of urine evaporated *in vacuo* over sulphuric acid.

Residue . . . . . =25·5 grs.
=44·42 grs. per 1000 grs. of urine.

Burnt. The ash = 4·60 grs. = 8·01 grs. per 1000 grs. of urine.

1015·4 grs. of urine precipitated with more than twice their bulk of alcohol.

Albumen and fat =22·75 grs. =22·40 grs. per 1000 grs. of urine.

Treated with ether. Residue soluble in ether.
=8·5 grs. fat= 8·37 grs. per 1000 grs. of urine.

Albumen . . . . . =14·03 grs. per 1000 grs. of urine.

574 grs. treated with absolute alcohol after evaporation to dryness.

Alcohol filtered when cold.

Residue . . . =9·02 grs. =15·70 grs. per 1000 grs. of urine.

Burnt ash . . =1·40 gr. = 2·44 grs. per 1000 grs. of urine.

Urea and extractive . . . =13·26 grs. per 1000 grs. of urine.

Hence

| | | |
|---|---|---|
| Total residue . | = | 44·42 grs. per 1000 grs. urine. Specific gravity =1015. |
| Total ash . . | = | 8·01 grs. |
| Albumen . . | = | 14·03 grs. |
| Fat . . . . | = | 8·37 grs. |
| Urea, &c. . . | = | 13·26 grs. |
| Loss . . . | = | ·75 gr. |
| Water . . . | = | 955·58 grs. |
| | | 1000·00 grs. |

In order to watch the variations in the appearance of the urine at different hours of the day, it was each time passed into a bottle, marked with the hour at which it was made for five successive days.

First day. Water passed at

7 A.M. thrown away. Breakfast a pint of coffee; a quarter of a pint of milk. Bread, with little butter or sugar.

8h 10m A.M., just before breakfast. Quantity one ounce, clear. Acid with pink deposit of urate of ammonia gave no precipitate with heat and nitric acid. Remained acid three days.

10 A.M. Reddish colour, milky throughout. Six ounces alkaline, in three days.

12h 20m. Milky, thick throughout. Six ounces, alkaline; contained some clots of fibrin.

1h 25m P.M. More thick. White with rather reddish clots, two ounces, alkaline, made just before dinner, which consisted of mutton chop, boiled rice, onion with bread.

2h 20m P.M. White, with more blood, six ounces, alkaline.

6 P.M. More white, with deposit of blood, eight ounces, alkaline; smelt strongly

of onions; passed just before tea; three quarters of a pint of cocoa with milk and bread.

10 P.M. Very white, milky, with some blood. Twelve ounces, alkaline.

Second day. Water passed at

7 A.M. Lost.

8h 30m A.M. Nearly clear; a little blood and very slight coagulum. An ounce and a half, acid; passed just before breakfast. Pint of boiled milk with sago, bread, and a little butter.

9h 30m A.M. Very slightly opalescent, with a delicate transparent coagulum filling the lower half of the bottle, containing some streaks of blood. The clear liquid coagulated strongly with heat and acid. An ounce and a half in quantity, alkaline.

11h 30m A.M. Milky, with a little blood, alkaline.

1h 15m P.M. Milky, with more blood; six ounces more alkaline; made just before dinner, which consisted of a mutton chop, broccoli and bread.

3 P.M. Milky; about eight ounces, alkaline.

5 P.M. Milky; eight ounces, feebly acid; passed just before tea; three quarters of a pint of milk and sago, bread, very little butter.

8 P.M. Milky; eight ounces, feebly acid.

10h 30m P.M. Milky; eight ounces, slightly more acid.

Third day. Water passed at

6 A.M. Opalescent yellow, did not clear with heat; gave the slightest trace of albumen with heat and acid; about eight ounces, slightly acid.

7h 30m A.M. Clear when passed; cloudy about twelve from urate of ammonia; about one ounce passed immediately after getting out of bed; gave a more distinct trace of albumen, contained a few blood-globules; slightly acid.

8h 30m A.M. The whole of the urine in the bottle consisted of coagulum of a yellow opalescent colour, not at all milky; a few drops of liquid only could be poured from it, and this was excessively albuminous; the quantity made was nearly two ounces, alkaline to test-paper, passed just *before* breakfast, which consisted of a pint of boiled milk and sago, bread, and a little butter.

9h 30m A.M. More opalescent; slightly milky, with a tinge of blood; the bottle was full of coagulum from which a drachm or two of liquid could be poured; about five ounces; alkaline highly.

12h 30m A.M. Milky; eight ounces, neutral.

1h 15m P.M. Milky; two ounces, neutral; passed just before dinner; steak, roast onion and bread.

4h 45m P.M. Milky; five ounces, neutral.

5h 30m P.M. Milky; five ounces, alkaline just before tea; three quarters of a pint of coffee, bread, with little butter.

9h 30m P.M. Milky; eight ounces, neutral.

10h 30m P.M. Milky; four ounces, feebly acid.

Fourth day. Water passed at

6 A.M. Clear, six ounces, strongly acid; the slightest trace of albumen with heat and acid.

7h 15m A.M. Clear; half an ounce, very strongly acid. Passed immediately on getting out of bed for the day; the slightest trace of albumen with heat and acid. This and a little of the urine passed at six, had specific gravity 1027, 513·5 grs. precipitate with alcohol =0·40 gr. =0·8 gr. per 1000 grs. of urine.

9h 50m A.M. Slightly opalescent, solid, yellow, coagulum; three ounces, alkaline. Passed just *before* breakfast. Pint of boiled milk with sago and bread, with but little butter or sugar. When filtered a bloody coagulum remained on the filter. The clear liquid left at rest deposited a layer of blood-globules. Specific gravity =1015·6, gave a nearly solid coagulum with heat and acid. 507·8 grs. precipitated by alcohol =7·20 grs. =14·1 grs. per 1000 grs. of urine.

11 A.M. Chylous with clots and pink coagulum; six ounces, alkaline, filtered; bloody coagulum was left on the filter. Milky fluid on standing deposited a layer of blood-globules. Specific gravity =1013·4, 506·7 grs. precipitated by alcohol =7·35 grs.=14·5 grs. per 1000 grs. of urine.

1h 35m P.M. Very milky; eight ounces, with little blood; neutral. Passed just before dinner; mutton chop with broccoli and bread.

3h 40m P.M. Very milky; eight ounces, very little blood; neutral.

5h 40m P.M. Very milky; one and a half ounce; blood doubtful; feebly acid; passed just before tea; three quarters of a pint of coffee, half a pint of milk with bread, but little butter or sugar.

7h 40m P.M. Very milky; four and a half ounces; little blood; neutral.

10 P.M. Very milky; five ounces; little blood; very feebly acid.

Fifth day. Water passed at

6 A.M. Slightly milky; yellowish; eight ounces; strongly acid. Specific gravity =1017. No blood; contained a very minute trace of albumen; did not clear with heat.

8h 15m A.M. Slightly cloudy; no blood; no coagulum; one and a half ounce, acid. Specific gravity =1020·7. Contained a considerable quantity of albumen, though he had nothing to eat and remained in bed.

9h 30m A.M. Almost quite clear; three quarters of an ounce, acid. Passed just before breakfast, which consisted of a pint of boiled milk, sago, bread, with a little butter. Apparently rather less albumen. Specific gravity =1022.

11h 20m A.M. Yellowish milky. Three ounces made just before he got up for the day; very feebly acid. Contained a considerable quantity of albumen; more than the two preceding specimens. No spontaneous coagulation. Did not clear by heat. Specific gravity =1019·4.

1 P.M. Milky; coagulated spontaneously; four ounces, neutral; passed just before dinner; mutton chop, onion with bread.

4h 50m P.M. Milky; neutral; six ounces just before tea; three quarters of a pint of milk boiled, bread with butter.

8 P.M. Milky; five ounces; neutral.

10 P.M. Milky; three ounces; feebly acid.

Sixth day. Water passed at

6h 35m A.M. Yellow milky; more than opalescent; six ounces, strongly acid. Specific gravity 1026·6. Passed on getting up. 513·3 grs. precipitated by alcohol = 1·85 gr. = 3·6 grs. per 1000 grs. of urine.

8h 10m A.M. More milky, with large pinkish coagula; two ounces, alkaline. Specific gravity 1016·4. 508·2 grs. precipitated by alcohol = 8·40 grs. = 16·5 grs. per 1000 grs. of urine.

9 A.M. Pink coagulum filling an ounce bottle, alkaline; passed just before breakfast; a pint of boiled milk, sago, with a little butter.

11h 30m A.M. Very milky, with large coagula.

From these observations, and more particularly from the 3rd, 4th and 6th days, it is evident that the fibrin and albumen appear in the urine when no fat is perceptible, and previous to breakfast being taken, thus:—

The 3rd day, 8h 30m A.M., the urine passed before breakfast, after he had been up an hour, was highly albuminous, and a nearly solid coagulum filled the bottle.

The 4th day, 7h 15m A.M., on first getting up the urine contained the slightest trace of albumen. The specific gravity = 1027. The precipitate by alcohol = 0·8 gr. per 1000 grs. of urine.

The 4th day, 9h 50m A.M., just before breakfast the urine formed a solid coagulum, and contained a visible deposit of blood. Specific gravity = 1015·6. The precipitate by alcohol = 14·1 grs. per 1000 grs. of urine.

The 4th day, 11 A.M., the urine was chylous.

The 6th day, 6h 35m A.M., on first getting up, the specific gravity = 1026·6. The precipitate by alcohol = 3·6 grs. per 1000 grs. of urine.

The 6th day, 8h 10m A.M., before breakfast the urine coagulated spontaneously. Specific gravity = 1016·4. The precipitate by alcohol = 16·5 per 1000 grs. of urine.

Further experiments on the influence of rest and motion in lessening or increasing the albumen in the urine, previous to breakfast, were then made.

*On the Influence of Rest and Motion in Lessening or Increasing the Albumen in the Urine previous to and after Food was taken.*

Seventh day. Last food was taken at 5h 15m P.M. yesterday. He laid in bed this morning till 9h 30m A.M.

Urine passed at

10 P.M. Last night, milky; eight ounces.

6h 40m A.M. Yellow, slightly milky; six ounces, acid; contained a little albumen.

8h 10m A.M. Clear, healthy looking urine, made just before breakfast (boiled milk, a pint of sago, bread, with a little butter). The quantity, one and a half ounce.

Specific gravity =1021·3. Gave no coagulum with heat and acid. 510·65 grs. precipitated by alcohol. Precipitate =0·30 gr.=0·6 gr. per 1000 grs. of urine.

9h 30m A.M. Opalescent, no spontaneous coagulation. Two and a half ounces passed when he got up. Specific gravity =1019·0. Gave a considerable precipitate with heat and acid. 509·5 grs. precipitated by alcohol. Precipitate =1·40 gr. =2·7 grs. per 1000 grs. of urine.

12h 30m A.M. Milky; spontaneously coagulating.

Eighth, being the next day. Last food between 5 and 6 P.M. yesterday. Up this morning at 6 A.M. Urine passed at 10 P.M., last night, was chylous.

2 A.M. Yellow milky; three ounces, acid. Slightly coagulating with heat and acid.

6h A.M. Quite clear; healthy-looking. Two ounces; acid. Contained no trace of albumen. Specific gravity =1026·4. 513·2 grs. precipitated by alcohol. Precipitate =0·85 gr. =1·65 gr. per 1000 grs. of urine.

7h 30m A.M. Opalescent; one and a half ounce; feebly acid; gave a large precipitate with nitric acid and heat; contained multitudes of healthy blood-globules; no casts. On long standing gave a small bloody coagulum, which fell to the bottom of the bottle. Specific gravity =1018·8. 509·4 grs. precipitated by alcohol. Precipitate =06·5 gr.=11·9 grs. per 1000 grs. of urine.

9 A.M. Opalescent; by 12 o'clock became a solid jelly; two ounces, alkaline. Passed just before breakfast, which consisted of a pint of milk and sago, with bread and little butter.

11h 30m A.M. Coagulated spontaneously to a strong, unclear, slightly milky jelly. About three ounces, alkaline, passed in my room. Says that he thinks he can tell when the urine will be most thick and bloody by the pain, pressure and dragging, with heat in the loins.

Ninth, being the next day. Last food at 6 P.M. the day previous; staid in bed today until 9h 30m A.M.

Urine passed at

3 A.M. Cloudy, opalescent; five ounces.

6h 30m A.M. Clear healthy water; an ounce and a half, highly acid. No precipitate with heat and acid.

8h 40m A.M. Clear, one ounce; contained the smallest trace of albumen. Specific gravity =1024·2. He did not sleep from 6h 30m, but he remained in bed. This water was passed just before breakfast, which consisted of a pint of boiled milk and sago, bread, with a little butter. 512·1 grs. precipitated by alcohol. Precipitate =0·85 gr. =1·61 gr. per 1000 grs. of urine.

9h 30m A.M. Still clear, an ounce and a half in quantity, made on first getting up. Gave the most minute trace of albumen. Specific gravity =1022·2. Very slightly acid. 511·1 grs. precipitated by alcohol. Precipitate =0·60 gr. =1·1 gr. per 1000 grs. of urine.

10h 30m A.M. Very milky, alkaline.

Tenth day. After animal food had formed the greatest part of his diet for ten days; he remained this day in bed until after breakfast.

Urine passed at

8h 20m A.M. Clear; no trace of albumen; acid. Specific gravity =1023·4 grs. passed before breakfast. 511·7 grs. precipitated by alcohol. Precipitate =0·40 gr. =0·78 gr. per 1000 grs. of urine.

Eleventh day. The following morning; up early.

Urine passed at

8h 10m A.M. Cloudy; contained some blood-globules, but no trace of fibrinous casts; acid. Specific gravity =1022·6; passed before breakfast. Gave a considerable precipitate with heat and acid. 511·3 grs. precipitated by alcohol. Precipitate =9·40 grs. =18·38 grs. per 1000 grs. of urine.

The following table shows these results clearly:—

| | | Specific gravity. | Precipitate by alcohol. |
|---|---|---|---|
| **Seventh day. Remained in bed late.** | | | |
| 8h 10m A.M. In bed. | Urine passed before breakfast, clear | =1021·3 | = 0·6 gr. per 1000 grs. of urine. |
| 9h 30m A.M. In bed. | Urine passed after breakfast, opalescent | =1019·0 | = 2·7 |
| **Eighth day. Up early.** | | | |
| 6 A.M. On getting up. | Urine passed before breakfast, clear | =1026·4 | = 1·6 |
| 7h 30m A.M. Up. | Urine passed before breakfast, opalescent | =1018·8 | =11·9 |
| **Ninth day. Remained in bed late.** | | | |
| 8h 40m A.M. In bed. | Urine passed before breakfast, clear | =1024·2 | = 1·6 |
| 9h 30m A.M. On getting up. | Urine passed after breakfast, clear | =1022·2 | = 1·1 |
| **Tenth day. Remained in bed.** | | | |
| 8h 20m A.M. | Urine passed before breakfast, clear | =1023·4 | = 0·78 |
| **Eleventh day. Up early.** | | | |
| 8h 10m A.M. | Urine passed before breakfast, cloudy | =1022·6 | =18·38 |
| Healthy urine free from albumen, precipitated by alcohol in excess | | =1020·2 | = 2·15 |
| Second experiment | | =1021·2 | = 3·48 |

The precipitate chiefly consisted of sulphates and a little phosphate of lime, and no uric acid.

These experiments show most clearly the influence of rest and the effect of rising, (and even of waking) in causing the albumen to appear in the urine. The comparison of the 8th day with the 7th or 9th, and the great difference between the 11th and 10th days is quite conclusive. In other experiments I frequently determined before-hand whether the urine before breakfast should be albuminous or not, by directing the patient to get up and move about early or to keep very quiet in bed. And by keeping in bed all the day the urine throughout the whole day was very slightly albuminous.

It appeared to me to be very desirable to see whether the blood was milky. Mr. Wilson, of Tavistock Street, through whose kindness the patient came to me, bled him for me. The veins were filled with blood rather longer than usual before the opening was made; the blood came in a tolerable stream. The dinner, at 1h 30m P.M., consisted of a mutton chop with vegetables and bread. The blood was taken at 4h 30m P.M. into a thin wide mouth bottle. It was left to stand fourteen hours. There was no appearance of buff or cupping. The serum was opalescent, but not at all milky; and when agitated with ether it did not become clear, and the quantity of fat dissolved in the ether was very small.

Blood . . . =1216·2 grs.

(1.) Serum poured off= 288·5 grs. Residue on evaporation= 26·9 grs.
Hence water . . =261·6 grs.

(2.) Clot washed with distilled water until colourless.
Fibrin dried, *in vacuo* . . . =3·20 grs.
=2·63 grs. per 1000 grs. of blood.

(3.) Blood-globules, *plus* residue of serum, *minus* fibrin. . . . . } =924·3 grs.
Evaporated to dryness . . . . . =261·8 grs.
Hence water . . . . . =662·5 grs.
contain by (1.) . . . . . 68·1 grs. of solids of serum.

Therefore blood-globules=261·8−68·1=193·7 grs.=159·3 grs. per 1000 grs. of blood.
Total solids of serum = 68·1+26·9= 95·0 grs.= 78·1 grs. per 1000 grs. of blood.

(4.) Dried blood-globules, and serum, in the proportion of one-quarter serum to three-quarters globules, were treated with ether frequently: 99·7 grs. gave 0·25 gr., soluble in ether =2·6 grs. of fat per 1000 grs. of dry residue.

Hence in 1000 parts of blood—

| | |
|---|---|
| Fibrin . . . . . | 2·63 |
| Blood-globules . . . . . | 159·3 |
| Solids of serum . . . . . | 78·1 |
| Total solid residue . . . . . | 240·03 |
| Water . . . . . | 759·97 |
| Fat . . . . . | 0·62 |

The urine made the same day on which he was bled was also examined.

That passed at

6h 30m A.M. Clear.

8 A.M. Slightly cloudy. Then got up and had breakfast on arrow-root.

10 A.M. A solid and pinkish-white coagulum formed in the urine spontaneously.

1h 30m P.M. Milky, with some blood and spontaneous coagula. Six ounces passed just before dinner, which consisted of a mutton chop, with vegetables and bread.

4 P.M. Milky; five ounces.

4h 30m P.M. Milky; one ounce, mixed afterwards with 4 o'clock water. It contained a very little blood. He was bled immediately afterwards. Four ounces of this urine were evaporated to dryness, treated with boiling water, filtered, tested with sulphate of copper and liquor potassæ; gave no evidence of sugar.

6 P.M. Very milky urine, with blood-globules and coagula. Specific gravity =1018; neutral to test-paper; about two ounces, made before tea.

509·0 grs. evaporated, *in vacuo*, over sulphuric acid—

Residue . . . . =28·95 grs.
=56·87 grs. per 1000 grs. of urine.
Ash=5·50 . . . =10·80 grs. per 1000 grs. of urine.

509·0 grs., precipitated by an excess of alcohol—

Albumen and fat=10·90 grs. . . . =22·41 grs. per 1000 grs. of urine.
Ether dissolved = 3·8 grs. . . . = 7·46 grs. per 1000 grs. of urine.
Therefore albumen . . . . . =13·95 grs. per 1000 grs. of urine.

509·0 grs., evaporated to dryness, treated with absolute alcohol, filtered when cold—

Residue=12·85 grs. . . . =25·24 grs. per 1000 grs. of urine.
Ash = 0·60 gr. . . . . = 1·18 gr. per 1000 grs. of urine.
Therefore urea and extractive =24·06 grs. per 1000 grs. of urine.

Hence—

Total dry residue = 56·87 grs. per 1000 grs. of urine. Specific gravity =1018.

| | |
|---|---|
| Total ash . . . | = 10·80 |
| Albumen . . . | = 13·95 |
| Fat . . . . . | = 7·46 |
| Urea, &c. . . . | = 24·06 |
| Loss . . . . . | = ·60 |
| Water . . . . | =943·13 |
| | 1000·00 grs. |

The conclusions from these experiments are:—

1st. That so-called chylous urine may contain fat, albumen, fibrin and healthy blood-globules.

2ndly. That although the fat passes off in the urine after food is taken, yet the albumen and fibrin and blood-globules are thrown out before any food has been taken. During perfect rest the albumen ceases to be excreted, and it does not appear in quantity in the urine even after food is taken, provided there is perfect rest. A short time after rising early the urine may coagulate spontaneously, although no fat is present in perceptible quantity, and this may happen previous to any food.

3rdly. Though the urine made just before and a short time after bleeding was as milky as it usually was at that period of the day, yet the serum of the blood was not milky. It did not contain a larger quantity of fat than healthy blood does. In other

respects, excepting in the diminution of the solids in the serum, the analysis of the blood corresponds with that of a case of cerebral congestion given by ANDRAL.

| | Cerebral congestion. | So-called chylous urine. |
|---|---|---|
| Fibrin . . . . . | 2·7 | 2·63 |
| Globules . . . . . | 152·3 | 159·3 |
| Solids of serum . . . | 105·0 | 78·1 |
| Water . . . . . | 740·0 | 759·97 |

The general results are—

1st. That the most important changes in the urine take place independently of the influence of digestion.

2ndly. That the urine in one respect only resembles chyle, and that is in containing, after digestion, a large quantity of fat in a very fine state of division; but the excess of fat in the urine is not caused by any excess of fat in the blood, for no excess of fat was found there.

3rdly. It appears that some change is produced in the kidney by which fibrin, albumen, globules and salts are allowed to pass out whenever the circulation through the kidney is increased: if, at the same time, fat is present in the blood, it escapes also into the urine.

That this change of structure is not visible to the naked eye on *post mortem* examination of the kidneys, Dr. PROUT long since demonstrated; and in a case of this disease, which was in St. George's Hospital, and was examined at Plymouth, no disease of the kidney was observed. From the total absence of fibrinous casts of the tubes from this urine, it is not improbable that by the microscope a difference may be detected in the structure of the mammary processes rather than in that of the cortical part of the kidney.

# XXXIII. *Contributions to the Chemistry of the Urine.*—Paper III.

## Part IV. *On the Variations of the Sulphates and Phosphates in Disease.*

*By* Henry Bence Jones, *M.D., M.A.Cantab., F.R.S., Physician to St. George's Hospital.*

Received April 19,—Read June 13, 1850.

THE object of the following experiments was to determine whether the sulphates in the urine were increased or diminished in any class of diseases. The total amount of phosphates in the urine in the same diseases was at the same time made the subject of experiment, partly to see whether the deductions made in a paper published in the Philosophical Transactions for 1846 would be confirmed, and partly to determine whether the same disease produced the same or a different effect on the phosphates as on the sulphates; whether, in diseases in which the phosphates were increased the sulphates would be also increased in the same proportion; and whether, in those diseases in which the phosphates were diminished, the sulphates also would be found to be below the average amount.

Most of the following experiments were made on the urine first passed in the morning before food. When this could not be obtained, the afternoon or night urine was taken. Almost all the cases were in St. George's Hospital, and therefore under nearly the same circumstances as regards exercise. The diet usually varied with the state of the patient.

In two papers in the Philosophical Transactions for 1845 and 1849, I have shown that in the healthy state on full diet the total amount of sulphates and phosphates in the urine varies as regards sulphates—

| | Spec. grav. |
|---|---|
| After food from 11·85 grs. of sulphate of baryta per 1000 grs. of urine . | 1033·9 |
| Before food to 7·93 grs. of sulphate of baryta per 1000 grs. of urine . . | 1026·5 |

As regards the total phosphates—

| | |
|---|---|
| After food from 7·22 grs. of phosphate of lime per 1000 grs. of urine . . | 1030·0 |
| Before food to 7·96 grs. of phosphate of lime per 1000 grs. of urine . . | 1027·9 |

In the following paper I shall give the amount of the sulphates and the total amount of the phosphates in the urine:—

1. In acute and chronic diseases in which the muscular structures are chiefly affected.

2. In some functional diseases of the brain, as delirium tremens and some other forms of delirium.

3. In acute inflammatory disease of the nervous structures.

4. In chronic diseases of the nervous structures.

5. In *acute* diseases in which neither the nervous nor the muscular structures are chiefly affected.

6. In *chronic* diseases in which neither the muscular nor nervous structures are chiefly affected.

TABLE I.—On the amount of Sulphates and the total amount of Earthy and Alkaline Phosphates in those diseases in which the muscular structures are chiefly affected.

| | Sulphate of baryta per 1000 grs. of urine. | Specific gravity. | Total phosphates per 1000 grs. of urine. |
|---|---|---|---|
| Case 1. Acute chorea after salts. | | | |
| 5th day | 25·09 | 1032·3 | 0·68 |
| 5th day | 21·73 | 1035·2 | |
| 8th day | 7·28 | 1030·0 | 7·34 |
| 9th day | 2·56 | 1013·1 | 4·70 |
| Case 2. Acute chorea. Boy, æt. 8. | | | |
| 6th day | 11·25 | 1030·6 | 3·29 |
| 7th day | 10·66 | 1031·8 | 2·52 |
| 8th day | 11·15 | 1031·2 | 2·54 |
| 10th day | 7·39 | 1028·4 | 3·50 |
| 11th day | 3·92 | 1018·6 | 1·57 |
| 102nd day | 8·01 | 1030·6 | |
| Case 3. Acute chorea. Girl, æt. 22. | | | |
| 3rd day | 19·88 | 1036·0 | |
| 5th day | 15·86 | 1033·8 | |
| 6th day | 13·80 | 1028·4 | 6·51 |
| 7th day | 9·36 | 1026·8 | |
| 8th day | 6·08 | 1025·4 | |
| 13th day | 4·72 | 1016·4 | |
| Case 4. Chronic chorea | 1·86 | 1008·2 | |
| Case 5. Chronic chorea | 3·49 | 1014·7 | 1·61 |
| | 1·91 | 1014·3 | 1·12 |
| | 2·66 | 1013·0 | 4·05 |
| Case 6. Chronic tetanus | 1·58 | 1009·9 | 2·47 |
| | 2·95 | 1015·5 | 2·75 |

Hence in three cases of acute chorea the most remarkable increase was observed in the amount of sulphates in the urine. That this did not arise from the small quantity of urine passed is evident from the small amount of the total phosphates in the urine. Moreover the actual quantity passed, when it could be determined by measure, was found occasionally to be above thirty ounces in twenty-four hours. It is worthy of notice that the amount of urea was also very greatly increased in these cases; so much so, that on the addition of nitric acid to the urine without any evaporation, nitrate of urea immediately crystallized out.

A very small quantity of food was taken by these patients, whilst the muscular action was most severe; and the contrast between the amount of sulphates when they were recovering and taking full diet, and the amount when they took little food, but were in a state of violent muscular action, is very remarkable.

The general conclusion is, that in acute chorea the amount of sulphates in the urine is increased, whilst the phosphates are in some cases as remarkably diminished.

**Table II.—On the amount of Sulphates and the total amount of Earthy and Alkaline Phosphates in some functional diseases of the brain, as delirium tremens and some other forms of delirium.**

| | Sulphate of baryta per 1000 grs. of urine. | Specific gravity. | Total phosphates. |
|---|---|---|---|
| Case 1. Delirium tremens. | | | |
| 6th day | 5·74 | 1017·9 | |
| 6th night. Death. | | | |
| Case 2. Delirium tremens. | | | |
| 5th day | 13·34 | 1018·0 | |
| Case 3. Delirium tremens. | | | |
| 3rd day | 10·60 | 1023·94 | 5·29 |
| Case 4. Delirium tremens. | | | |
| 10th day | 17·31 | 1024·74 | 0·87 |
| Case 5. Delirium tremens. Chloroform. | | | |
| 8th day | 8·51 | 1026·8 | |
| Case 6. Delirium tremens. | | | |
| 5th day | 20·77 | 1037·8 | 2·14 |
| 5th night | 37·07 pink. | 1041·2 | 5·95 |
| 6th died. | | | |
| Case 7. Delirium tremens. | | | |
| Uncertain day | 2·96 | 1013·2 | 1·18 |
| Uncertain day | 7·83 | 1021·6 | 7·24 |
| Uncertain day | 8·61 | 1022·0 | 7·43 |
| Case 8. Delirium tremens. | | | |
| 13th day | 13·10 | 1037·4 | 9·83 |
| 14th day | 12·95 | 1034·6 | 8·89 |
| Case 9. Traumatic delirium tremens. | | | |
| 3rd day | ..... | 1014·8 | 1·97 |
| 5th day | 8·45 | 1028·0 | 3·11 |
| 6th day | 8·77 | 1026·2 | 6·23 |
| Case 10. Poisoned by laudanum, with delirium and excitement. | | | |
| 2nd day | 7·83 | 1026·8 | 7·53 |
| 3rd day | 6·78 | 1023·0 | 1·11 |
| Re-admitted again poisoned. | | | |
| 1st day | 6·35 | 1029·2 | 8·88 |
| 2nd day | 6·38 | 1024·0 | 8·24 |
| 3rd day | 15·89 | 1028·0 | 4·22 |
| 4th day | 13·01 | 1026·0 | 4·81 |
| 6th day | 7·55 | 1025·0 | 4·42 |
| 7th day | 8·22 | 1026·3 | 5·88 |
| Case 11. Delirium, with phthisis. | | | |
| 4th day | 10·84 | 1027·34 | 1·44 |
| 4th night | 6·97 | 1024·2 | 0·72 |
| 7th day | 4·45 | 1018·3 | 1·51 |

In the 2nd, 3rd, 4th, 6th and 8th cases of delirium tremens the sulphates were found to be above the average. In the 6th case the sulphates are in the greatest quantity ever observed in health or disease. Sulphate of magnesia had also been taken by this patient, so that the amount of sulphates is partly owing to the medicine; but that this is not the sole or chief cause of the increase is proved by the fact that many of the patients with other diseases took the same quantity of sulphate of magnesia, but the sulphates in the urine were never increased to the same amount.

The phosphates, in seven out of the nine cases of delirium tremens, were below the average. The same fact was stated in my previous paper, but from the diminution

of the phosphates in acute chorea, it becomes doubtful how far this result is owing to the action of alcohol in the system.

Further experiments are required; meanwhile excessive abstinence from food must be admitted as a cause of the diminution of the phosphates in the urine, provided there is no inflammatory action of the nervous structures.

In a case of restless excitement leading to self-destruction, the sulphates in the urine were found to be increased, and the same thing was also observed with a diminution of the phosphates in a case of delirium and phthisis.

In the 6th and 10th cases urea was found to be in great excess when the sulphates were increased. In the other cases the excess of urea was not looked for.

TABLE III.—On the amount of Sulphates and the total amount of Earthy and Alkaline Phosphates in acute inflammatory diseases of the nervous structures.

| | Sulphate of baryta per 1000 grs. of urine. | Specific gravity. | Total phosphates. |
|---|---|---|---|
| Case 1. Inflammation of the brain. | | | |
| 20th day | 7·67 | 1031·8 | |
| Case 2. Inflammation of the brain. | | | |
| 12th day | 3·96 | 1018·7 | 5·14 |
| 13th day | 11·23 | 1027·26 | 11·13 |
| 14th day | 2·91 | 1013·1 | 6·06 |
| 16th day | 7·34<br>7·69 | 1027·0 | 10·75<br>11·04 |
| 16th night. Died. | | | |
| Case 3. Subacute hydrocephalus. | | | |
| 15th day | 8·83 | 1030·0 | 9·41 |
| 16th day | 10·69 | 1029·0 | 8·45 |
| 22nd day | 8·83 | 1029·8 | 10·19 |
| 26th day | 9·46 | 1031·4 | 9·01 |
| 28th day. Died. | | | |
| Case 4. Acute after chronic disease. | | | |
| Uncertain | 3·54 | 1024·9 | 0·91 |
| | 9·39 | 1026·0 | 9·31 |
| Died. | | | |
| Case 5. Head symptoms, with tubercles in cerebellum and lungs. | | | |
| 15th day | 9·88 | 1031·6 | 8·72 |
| 15th night | 10·07 | 1032·2 | 8·91 |
| 16th day | 6·69 | 1016·4 | 4·72 |
| 16th night | 8·25 | 1018·2 | 5·69 |
| 18th day. Died. | | | |
| Case 6. Inflammation of the lungs, with tubercles and violent head symptoms. | | | |
| 4th day | 8·55 | 1027·85 | 7·19 |
| 6th day | 7·81 | 1026·1 | 6·43 |
| 8th day | 11·63 | 1031·4 | 9·30 |
| 9th day | 10·13 | 1026·2 | 7·99 |
| 9th night. Died. | | | |
| Case 7. Injury, with head symptoms not violent. | | | |
| 2nd day | 7·34 | 1026·8 | 5·20 |
| 4th day | 9·66 | 1028·6 | 7·52 |
| 5th day | 13·74 | 1028·6 | 7·91 |
| 32nd day | 2·11 | 1011·66 | 1·52 |
| Case 8. Injury of the head, slight. | | | |
| 7th day | 6·59 | 1022·9 | 8·93 |

TABLE III. (continued.)

| | Sulphate of baryta per 1000 grs. of urine. | Specific gravity. | Total phosphates. |
|---|---|---|---|
| Case 9. Fractured spine. | | | |
| 5th day | 3·75 | 1014·2 | 3·15 |
| 6th day | 12·23 | 1030·2 | 10·68 |
| 7th day | 9·91 | 1028·8 | 10·10 |
| 7th night. Died. | | | |
| Case 10. Fractured spine. | | | |
| 4th day | 14·57 | 1029·2 | 9·26 |
| 5th day | 15·54 | 1029·2 | 8·16 |
| 6th day | 13·00 | 1030·2 | 7·96 |
| 7th day | 6·65 | 1021·6 | 4·30 |
| 8th day | 8·80 | 1022·0 | 6·67 |
| 9th day | 2·18 | 1007·3 | 1·58 |
| 10th day | 2·37 | 1010·8 | 2·57 |
| Died. | | | |
| Case 11. Fractured spine. | | | |
| 1st day | 5·59 | 1012·0 | 4·15 |
| 1st night. Died. | | | |
| Case 12. Fractured spine. | | | |
| 1st day | 5·90 | 1019·4 | 2·47 |
| 2nd day | 6·45 | 1025·3 | 4·31 |
| 2nd night | 3·37 | 1012·4 | 1·40 |
| 3rd day | 5·87 | 1023·0 | 1·09 |
| 3rd night | 10·32 | 1027·0 | 3·11 |
| 4th day | 6·65 | 1022·6 | 5·77 |
| 4th night | 7·61 | 1024·1 | 4·90 |
| 5th day | 13·03 | 1027·8 | 4·08 |
| 6th day. Died. | | | |

In the first eight cases of inflammatory action in the brain, there is an increase in the amount of sulphates as well as in the total amount of phosphates in the urine. In the second and third cases this increase is most apparent. In the previous paper the phosphates in the urine were shown to be decidedly increased in inflammation of the brain, and from these experiments it is evident that the sulphates are increased also.

From the amount of albumen in the nervous structures, it is certain that the amount of sulphur present therein is but little if at all less than the amount of phosphorus which it contains.

TABLE IV.—On the amount of Sulphates and the total amount of Phosphates, Earthy and Alkaline, in some slight and chronic diseases of the nervous or neighbouring structures.

| | Sulphate of baryta per 1000 grs. urine. | Specific gravity. | Total phosphates. |
|---|---|---|---|
| Case 1. Pain in the head. After salts. | | | |
| 40th day | 9·98 | 1026·2 | |
| Case 2. Hemiplegia. | | | |
| 7th day | 5·13 | 1021·6 | 5·22 |
| 21st day | 2·60 | 1017·0 | 1·51 |
| Case 3. Scalp wound. After salts. | | | |
| 6th day | 8·34 | 1023·7 | 4·63 |
| 8th day | 4·84 | 1018·7 | 3·77 |
| Case 4. Fracture of the skull. After salts | 11·97 | 1019·1 | 6·08 |
| Case 5. Recent paraplegia | 7·24 | 1021·6 | 4·50 |

In these diseases no increase of sulphates was observed, except after sulphate of magnesia had been taken as a medicine. The quantity taken was usually two drachms; yet the amount in the urine never reached to what it was when there was excessive action of the muscular or nervous structures.

TABLE V.—On the amount of Sulphates and the total amount of Earthy and Alkaline Phosphates in acute diseases, in which neither the nervous nor muscular structures are chiefly affected.

| | Sulphate of baryta per 1000 grs. of urine. | Specific gravity. | Total phosphates. |
|---|---|---|---|
| Case 1. Petechial fever. | | | |
| 5th day | 5·65 | 1014·6 | 2·62 |
| 6th day | 3·79 | 1012·9 | 2·01 |
| 9th day | 1·30 | 1010·0 | 0·73 |
| 13th day | 0·93 | 1011·5 | 2·61 |
| 18th day | 5·25 | 1016·2 | 0·73 |
| 19th day | 10·06 | 1027·4 | 4·80 |
| 20th day | 1·12 | 1010·94 | 2·10 |
| 22nd day | 2·58 | 1020·80 | 2·68 |
| 55th day. Recovered. | | | |
| Case 2. The same patient with ague and | | | |
| 28th day | 5·71 | 1021·6 | 5·13 |
| 33rd day | 4·86 | 1015·6 | 1·41 |
| afterwards with petechial fever. | | | |
| 5th day | 5·39 | 1027·0 | 4·32 |
| 8th day | 6·56 | 1026·2 | 4·32 |
| 16th day | 3·19 | 1014·2 | 3·09 |
| 21st day. Recovered. | | | |
| Case 3. Scarlet fever. | | | |
| 3rd day | 8·27 | 1032·2 | 6·33 |
| 10th day | 2·01 | 1012·0 | 2·90 |
| 19th day | 4·14 | 1022·1 | 5·42 |
| Case 4. Inflammation of the lungs. | | | |
| 7th day | 6·21 | 1019·7 | 6·41 |
| 8th day | 5·91 | 1021·5 | 6·98 |
| 9th day | 6·59 | 1021·5 | 4·24 |
| 10th day | 6·96 | 1025·4 | 6·96 |
| 11th day | 8·13 | 1025·5 | 4·23 |
| 13th day | 8·02 | 1027·1 | 2·86 |
| 16th day | 4·16 | 1018·0 | 3·77 |
| Case 5. Petechial fever. | | | |
| 16th day | 3·05 | 1013·7 | 4·08 |
| Case 6. Petechial fever. | | | |
| 10th day | 3·35 | 1013·2 | 2·90 |
| 11th day | 4·04 | 1013·7 | 3·94 |
| 14th day | 3·73 | 1016·8 | 7·08 |
| Case 7. Inflammation of the lungs and membranes of the brain. | | | |
| 7th day | 4·05 | 1012·5 | 2·86 |
| Case 8. Acute rheumatism. After sulphur. | | | |
| 9th day | 11·75 | 1031·10 | |
| Case 9. Acute rheumatism. | | | |
| 11th day | 6·96 | 1025·7 | 5·59 |
| Case 10. Acute rheumatism. After salts. | | | |
| 5th day | 11·89 | 1026·0 | 9·84 |
| 7th day. After salts | 10·78 | 1029·1 | 5·53 |
| 20th day | 6·94 | 1021·8 | 5·97 |
| Case 11. Acute rheumatism. | | | |
| 8th day | 7·17 | 1023·2 | 5·60 |
| 17th day | 5·68 | 1027·5 | 6·26 |

In these acute diseases, except after sulphate of magnesia, the amount of sulphates was not found above the average. The amount both of phosphates and sulphates appeared not to be influenced by these diseases.

TABLE VI.—On the amount of Sulphates and the total amount of Earthy and Alkaline Phosphates in Chronic Diseases, in which neither the nervous nor muscular structures are chiefly affected.

| | Sulphate of baryta per 1000 grs. of urine. | Specific gravity. | Total phosphates. |
|---|---|---|---|
| Case 1. Exostosis | 1·75 | 1016·6 | |
| Case 2. Exostosis | 7·09 | 1023·4 | 6·03 |
| Case 3. Exostosis | 9·08 | 1026·4 | 11·58 |
| Case 4. Diabetes | 7·45 | 1025·2 | 3·94 |
| Case 5. Diabetes | 4·21 | 1030·2 | 0·91 |
| Case 6. Diuresis. Albumen | 0·49 | 1003·6 | 1·09 |
| | 0·89 | 1005·36 | 1·49 |
| Case 7. Obstruction of the œsophagus. Albumen | 1·38 | 1012·2 | 4·70 |
| Case 8. Aneurism of aorta? | 6·03 | 1017·8 | 2·39 |
| Case 9. Obstruction of the bowels. Sulphate of magnesia. 8th day | 22·55 | 1024·3 | 3·51 |
| 9th. Died. | | | |
| Case 10. Excessive oxalate of lime | 7·89 | 1025·5 | 6·14 |
| Case 11. Indigestion. Alkaline from fixed alkali | 3·26 | 1024·7 | 3·65 |
| Case 12. Chronic rheumatism. After sulphur | 5·85 | 1011·82 | 4·86 |
| Case 13. Chronic rheumatism | 7·93 | 1023·44 | |
| Case 14. Chronic gout. Vichy water | 10·04 | 1025·8 | 5·26 |

In these chronic diseases nothing remarkable was observed as to the amount of sulphates or phosphates, excepting in case 3 of exostosis, in which the amount of sulphates and of phosphates was above the average.

In case 9, of total obstruction of the bowels, sulphate of magnesia was given frequently during the day in small doses: nothing passed through the intestine. The whole of the sulphate was absorbed, and hence the great increase in the sulphates in the urine.

In a patient, case 14, who was taking Vichy water, the sulphates were observed to be slightly above the average.

The conclusions I have drawn may be thus enumerated:—

Table I. In three cases of acute chorea the most remarkable increase was observed in the amount of sulphates in the urine. In the same cases the quantity of urea was very much increased. The quantity of urine made in twenty-four hours was not excessively diminished, and the total amount of earthy and alkaline phosphates was below the average amount.

The general conclusion was, that in acute chorea the amount of sulphates in the urine is increased, whilst sometimes the phosphates are as remarkably diminished.

Table II. In delirium tremens and in other delirium a remarkable increase in the amount of sulphates in the urine was frequently observed, and the total phosphates were in the same cases occasionally remarkably diminished; and the resemblance to

the state of chorea was still closer, inasmuch as occasionally a very great excess of urea was found in these cases also.

Table III. In acute inflammatory diseases of the nervous structures, during the most febrile symptoms, an increase was observed in the amount of sulphates in the urine, and the total amount of earthy and alkaline phosphates in these diseases appeared to be increased in the same proportion as the sulphates were increased.

Table IV. In some slight and chronic diseases of the nervous structures, no increase in the amount of sulphates in the urine was observed, excepting when sulphate of magnesia had been taken as a medicine.

Table V. In acute diseases, in which neither the nervous nor the muscular structures were chiefly affected, no increase in the sulphates or phosphates was observed, except after sulphate of magnesia.

Table VI. In chronic diseases, in which neither the nervous nor the muscular structures were chiefly affected, no decided increase in the sulphates or phosphates in the urine was observed, except after sulphate of magnesia. One case of exostosis may be regarded as a doubtful exception to this statement.

The general conclusions are—

1. That in acute chorea, in which the muscles are in excessive action, the sulphates and urea in the urine are greatly increased.

2. That in delirium tremens the same state of urine is frequently met with; that in these diseases the phosphates are not at all increased.

3. That in acute inflammation of the nervous structures, sulphates and phosphates are both increased in the urine.

4. That in chronic diseases of the brain, and that in other acute inflammations and diseases and in other chronic diseases, no increase in the total amount of sulphates is observed, excepting when sulphate of magnesia is taken as a medicine.

The result of this investigation is that—

Muscular action increases the sulphates in the urine without increasing the phosphates; whilst

Inflammation of the brain increases both the sulphates and phosphates in the urine.

## XXXIV. *Second Appendix to a paper on the Variations of the Acidity of the Urine in the state of Health.*

*By* Henry Bence Jones, *M.D., M.A., Cantab., F.R.S., Physician to St. George's Hospital.*

Received June 6,—Read June 20, 1850.

### *On the Influence of Tartrate of Ammonia and of Carbonate of Ammonia on the Acidity of the Urine.*

In a previous paper and appendix on the acidity of the urine, published in the Philosophical Transactions for 1849, I have shown the effect of different diets, of sulphuric acid, of tartaric acid, of caustic potash and of tartrate of potash on the acidity of the urine; in this Appendix I purpose tracing the effect of tartrate of ammonia and of carbonate of ammonia.

III. (*e.*) The effect of tartrate of potash having been so remarkable, it was thought, that by observing the effect of tartrate of ammonia, some conclusion might most rapidly and decidedly be obtained, as to the comparative effect of fixed and volatile alkalies on the acidity of the urine.

Mr. Morson prepared for me some beautifully crystalline tartrate of ammonia: one portion was dried by pressure on blotting paper; another portion was dried in a water bath. When dissolved in water no acid reaction was perceptible.

(36.) The first day for comparison no tartrate of ammonia was taken. Breakfast at $8^h\ 40^m$ A.M. Dinner at $6^h$ P.M. On mixed diet.

| | h | m | Spec. gr. | Acidity per 1000 grs. of urine. | Appearance. |
|---|---|---|---|---|---|
| Water passed at | 7 | 25 A.M. | was thrown away. | | |
| Water passed at | 8 | 40 | 1015·3 | + 4·93 measures. | Clear. |
| Water passed at | 9 | 45 | 1021·7 | − 2·93 | Clear. |
| Water passed at | 10 | 50 | 1018·5 | − 7·85 | Clear. |
| Water passed at | 1 | 0 P.M. | 1025·8 | +10·72 | Thick from urates. |
| Water passed at | 3 | 25 | 1024·2 | +19·52 | Thick from urates. |
| Water passed at | 6 | 0 | 1023·5 | +26·38 | Clear. |
| Water passed at | 8 | 15 | 1029·4 | +25·26 | Thick from urates. |
| Water passed at | 10 | 15 | 1031·7 | +15·50 | Thick from urates. |
| Water passed at | 7 | 10 A.M. | 1022·3 | +10·76 | Clear. |

(37.) For the following days tartrate of ammonia was taken. The first day two drachms of imperfectly dry tartrate of ammonia were taken, in two ounces of distilled water, at a few minutes after one o'clock P.M.

| | | | | | |
|---|---|---|---|---|---|
| Water passed at | 8 | 35 A.M. | 1025·1 | +13·65 measures. | Thick appearance from urates. |
| Water passed at | 10 | 5 | 1023·9 | +11·72 | Thick from urates. |
| Water passed at | 11 | 30 | 1027·2 | − 7·78 | Clear. |

| | h m | Spec. gr. | Acidity per 1000 grs. of urine. | Appearance. |
|---|---|---|---|---|
| Water passed at | 1 5 P.M. | 1027·0 | + 5·84 measures. | Thick from urates. |
| Water passed at | 2 10 | 1025·2 | +11·70 | Thick from urates. |
| Water passed at | 2 50 | 1025·6 | +18·52 | Thick from urates. |
| Water passed at | 4 30 | 1025·9 | +20·47 | Cloudy. |
| Water passed at | 6 30 | 1024·6 | +18·54 | Clear. |
| Water passed at | 11 45 | 1031·0 | +12·62 | Thick from urates. |
| Water passed at | 6 55 A.M. | 1021·1 | +16·64 | Clear. |

(38.) The following day 180 grains of tartrate of ammonia, dried at 100, were taken soon after twelve o'clock; and at three o'clock 108 grains more were taken. In all then, 288 grains. Breakfast at $8^h\ 24^m$ A.M. Dinner at $6^h\ 30^m$ P.M. The salt caused severe griping pain of the bowels, which lasted until the night, but the bowels were not relaxed.

| | | | | |
|---|---|---|---|---|
| Water passed at | 8 24 A.M. | 1026·0 | +17·54 measures. | Thick from urates. |
| Water passed at | 10 10 | 1027·0 | +13·63 | Thick from urates. |
| Water passed at | 12 5 | 1027·4 | +11·68 | Thick from urates. |
| Water passed at | 1 0 P.M. | 1024·8 | +17·56 | Thick from urates. |
| Water passed at | 3 0 | 1027·4 | +23·36 | Thick from urates. |
| Water passed at | 5 0 | 1025·5 | +25·35 | Clear. |
| Water passed at | 6 20 | 1026·0 | +27·29 | Clear. |
| Water passed at | 11 15 | 1029·2 | +15·54 | Thick from urates. |
| Water passed at | 6 40 A.M. | 1022·9 | +17·59 | Clear. |

(39.) The following day a single dose of tartrate of ammonia was taken. At twelve o'clock 177 grains of imperfectly dry tartrate of ammonia were taken. Breakfast at $8^h\ 10^m$ A.M. Dinner at $6^h\ 30^m$ P.M. as before.

| | | | | |
|---|---|---|---|---|
| Water passed at | 8 10 A.M. | 1027·0 | +19·47 measures. | Thick from urates. |
| Water passed at | 9 45 | 1024·8 | +17·56 | Thick from urates. |
| Water passed at | 12 0 | 1026·9 | +14·60 | Thick from urates. |
| Water passed at | 1 30 P.M. | 1026·0 | +16·57 | Thick from urates. |
| Water passed at | 3 20 | 1027·3 | +25·30 | Thick from urates. |
| Water passed at | 4 50 | 1027·9 | +27·24 | Thick from urates. |
| Water passed at | 6 30 | 1027·7 | +28·21 | Thick from urates. |
| Water passed at | 11 40 | 1027·2 | − 8·75 | Clear. |
| Water passed at | 7 0 A.M. | 1017·5 | +17·69 | Thick from urates. |

The medicine caused slight uneasiness of the bowels, which lasted until the evening.

(40.) The following day no tartrate of ammonia was taken. Breakfast at $8^h\ 30^m$ A.M. Dinner at $6^h\ 50^m$ P.M., as before.

| | | | | |
|---|---|---|---|---|
| Water passed at | 8 30 A.M. | 1024·8 | +21·46 measures. | Thick from urates. |
| Water passed at | 10 10 | 1020·6 | +11·75 | Thick from urates. |
| Water passed at | 11 20 | 1023·0 | 0 | Clear. |
| Water passed at | 1 0 P.M. | 1027·0 | + 5·84 | Thick from urates. |
| Water passed at | 2 30 | 1027·1 | +14·60 | Thick from urates. |
| Water passed at | 5 5 | 1025·0 | +26·34 | Cloudy from urates. |
| Water passed at | 6 50 | 1026·6 | +29·22 | Clear. |
| Water passed at | 11 0 | 1032·1 | + 8·72 | Thick from urates. |

| | Spec. gr. | Acidity per 1000 grs. of urine. | Appearance. |
|---|---|---|---|
| Water passed at 6 45 A.M. | 1016·7 | +15·73 measures. | Clear. |
| Water passed at 8 30 | 1026·8 | +23·37 | Thick from urates. |
| Water passed at 9 45 | 1027·2 | +15·56 | Thick from urates. |
| Water passed at 10 40 | 1025·0 | + 5·85 | Thick from urates. |
| Water passed at 12 0 | 1026·2 | − 3·89 | Clear. |
| Water passed at 1 30 P.M. | 1026·5 | +11·69 | Thick from urates. |

It follows from these experiments, which are best seen in Plate LI., that the influence of tartrate of ammonia in lessening the acidity of the urine is not perceptible.

By comparing this Plate with Plate XXIII. 1849, the remarkable difference between the action of volatile alkali and fixed alkali is very apparent. When two drachms of tartrate of potash were taken, the effect was perceptible in thirty-five minutes. When three drachms of tartrate of ammonia were taken, no diminution of the acidity of the urine was observed.

In three days, one ounce, one drachm, two scruples and five grains of tartrate of ammonia were taken without any apparent effect in diminishing the acidity of the urine.

III. (*f*.) The effect of carbonate of ammonia on the acidity of the urine was then examined; and for this purpose Mr. Morson gave me some of the so-called sesquicarbonate of pharmacy. Each dose was reduced to powder immediately before it was taken, in distilled water.

(41.) The first day for comparison no carbonate of ammonia was taken. Breakfast at $8^h\ 20^m$ A.M. Dinner at $6^h\ 40^m$ P.M. As before.

| | Spec. gr. | Acidity per 1000 grs. of urine. | Appearance. |
|---|---|---|---|
| Water passed at 8 20 A.M. | 1028·4 | lost. | Thick from urates. |
| Water passed at 11 5 | 1025·2 | + 4·87 measures. | Cloudy. |
| Water passed at 12 50 | 1024·4 | + 6·83 | Clear. |
| Water passed at 3 5 P.M. | 1026·0 | +16·57 | Clear. |
| Water passed at 5 15 | 1016·7 | +18·68 | Clear. |
| Water passed at 6 40 | 1023·6 | +25·40 | Clear. |
| Water passed at 11 5 | 1031·4 | 0 | Clear. |
| Water passed at 6 55 A.M. | 1021·1 | +12·73 | Clear. |

(42.) The following day. Breakfast at $8^h\ 15^m$ A.M. Dinner at $6^h\ 50^m$ P.M., as before. Eighteen grains of carbonate of ammonia were taken at $12^h\ 50^m$.

| | | | |
|---|---|---|---|
| Water passed at 8 15 A.M. | 1021·7 | +15·66 measures. | Clear. |
| Water passed at 9 50 | 1012·6 | + 7·90 | Clear. |
| Water passed at 11 35 | 1020·3 | 0 | Clear. |
| Water passed at 12 50 | 1022·5 | +11·63 | Clear. |
| Water passed at 3 0 P.M. | 1022·1 | +17·61 | Clear. |
| Water passed at 4 30 | 1021·1 | +20·56 | Clear. |
| Water passed at 6 50 | 1023·7 | +24·42 | Clear. |
| Water passed at 11 0 | 1031·1 | +19·39 | Thick from urates. |
| Water passed at 6 50 A.M. | 1023·4 | +15·63 | Clear. |

(43.) The following day. Breakfast at $8^h\ 12^m$ A.M. Dinner at $6^h\ 35^m$ P.M. Twenty

grains of carbonate of ammonia were taken at $1^m$ P.M.; and the same quantity at $3^h\ 30^m$ P.M.

| | h m | Spec. gr. | Acidity per 1000 grs. of urine. | Appearance. |
|---|---|---|---|---|
| Water passed at | 8 12 A.M. | 1024·6 | +22·49 measures. | Clear. |
| Water passed at | 9 45 | 1021·0 | +16·65 | Thick from urates. |
| Water passed at | 11 0 | 1025·0 | +11·70 | Thick from urates. |
| Water passed at | 1 0 P.M. | 1027·5 | +15·57 | Thick from urates. |
| Water passed at | 2 35 | 1029·6 | +21·36 | Thick from urates. |
| Water passed at | 4 25 | 1027·2 | +29·20 | Thick from urates. |
| Water passed at | 6 35 | 1026·2 | +29·23 | Clear. |
| Water passed at | 9 25 | 1033·4 | +27·09 | Thick from urates. |
| Water passed at | 11 25 | 1029·3 | + 2·91 | Clear. |
| Water passed at | 6 50 A.M. | 1026·4 | +29·23 | Clear. |

(44.) The following day. Breakfast at $8^h\ 10^m$ A.M. Dinner at $6^h\ 40^m$ P.M., as before. Twenty grains of carbonate of ammonia at $11^h\ 15^m$ A.M. The same quantity at $12^h\ 45^m$ noon. Repeated at $2^h\ 15^m$ P.M.; and again repeated at $4^h$ P.M. In all, eighty grains of carbonate of ammonia in the day.

| | | | | |
|---|---|---|---|---|
| Water passed at | 8 10 A.M. | 1030·6 | +32·99 measures. | Thick from urates. |
| Water passed at | 9 45 | 1025·1 | +22·34 | Thick from urates. |
| Water passed at | 11 15 | 1027·4 | +13·62 | Thick from urates. |
| Water passed at | 12 45 | 1029·0 | +19·43 | Thick from urates. |
| Water passed at | 2 15 P.M. | 1028·4 | +24·31 | Thick from urates. |
| Water passed at | 4 0 | 1026·2 | +27·28 | Clear. |
| Water passed at | 6 40 | 1027·7 | +30·16 | Clear. |
| Water passed at | 10 45 | 1031·1 | +29·09 | Thick from urates. |
| Water passed at | 6 10 A.M. | 1022·6 | +25·42 | Clear. |

(45.) The following day. Breakfast at $8^h\ 15^m$ A.M. Dinner at $6^h\ 45^m$ P.M., as before. For comparison no carbonate of ammonia was taken.

| | | | | |
|---|---|---|---|---|
| Water passed at | 8 15 A.M. | 1023·6 | +26·37 measures. | Clear. |
| Water passed at | 10 0 | 1023·5 | +23·44 | Thick from urates. |
| Water passed at | 12 45 | 1027·2 | +21·41 | Thick from urates. |
| Water passed at | 3 20 P.M. | 1029·0 | +34·02 | Thick from urates. |
| Water passed at | 5 35 | 1028·3 | +35·00 | Clear. |
| Water passed at | 6 45 | 1030·8 | +36·86 | Thick from urates. |
| Water passed at | 9 20 | 1032·9 | +37·75 | Thick from urates. |
| Water passed at | 11 45 | 1031·4 | + 7·75 | Cloudy. |
| Water passed at | 7 25 A.M. | 1029·8 | +22·33 | Thick from urates. |

(46.) Breakfast at $8^h\ 30^m$ A.M.

| | | | | |
|---|---|---|---|---|
| Water passed at | 8 30 | 1028·6 | +27·22 | Thick from urates. |
| Water passed at | 9 35 | 1025·4 | +17·55 | Clear. |
| Water passed at | 11 0 | 1027·7 | + 8·75 | Clear. |
| Water passed at | 1 0 P.M. | 1030·3 | +17·47 | Thick from urates. |
| Water passed at | 3 0 | 1029·3 | +25·26 | Thick from urates. |
| Water passed at | 5 45 | 1029·0 | +27·21 | Thick from urates. |

The result of these experiments is very evident in Plate LII.

It follows therefrom, that carbonate of ammonia, taken in large doses, does not diminish the acidity of the urine. On the contrary, the third day (experiment 44.), when most carbonate of ammonia was taken, the acidity was higher than it had been any previous day. By experiment (45.) it appears that the acidity of the urine was still high on the following day. The effect of the eighty grains of carbonate of ammonia was very evident twenty-four hours after it was taken.

The comparison between Plate XXII. Philosophical Transactions, 1849, representing the acidity when tartaric acid was taken, and this Plate, which shows the effect of carbonate of ammonia, is worthy of observation. The urine was more acid when carbonate of ammonia was taken than when tartaric acid was taken. It is possible that there was some difference in the irritability of the stomach when the two series of observations were made. But the gradual increase of the acidity, as the quantity of carbonate of ammonia taken was increased, shows that the difference of the state of the stomach was not the cause of the state of the acidity of the urine. When no carbonate of ammonia was taken, the acidity of the urine, after food was taken, was diminished to a greater degree than it was when the volatile alkali was taken.

The comparison between Plate XXI. Philosophical Transactions, 1849, which represents the acidity of the urine when liquor potassæ was taken, and this Plate, which shows the acidity when carbonate of ammonia was taken, is also very interesting, as it establishes the important difference of the effect of volatile and fixed alkali on the acidity of the urine.

That 138 grains of carbonate of ammonia, taken in three consecutive days, should not diminish the acidity of the urine is very remarkable. It is still more worthy of attention that it actually increases the acidity. It appeared very desirable to test these facts by further experiments.

(47.) The experiment with large doses of carbonate of ammonia was therefore repeated. For comparison, the day previous to that on which the carbonate of ammonia was taken, the variations in the acidity of the urine were determined. Breakfast at $8^h\ 30^m$ A.M. Dinner at 7 P.M.

| | h m | Spec. gr. | Acidity per 1000 grs. of urine. | Appearance. |
|---|---|---|---|---|
| Water passed at | 7 20 A.M. | thrown away. | | |
| Water passed at | 8 30 | 1028·8 | +19·44 measures. | Thick from urates. |
| Water passed at | 9 40 | 1026·0 | +14·62 | Thick from urates. |
| Water passed at | 10 35 | 1025·2 | + 5·85 | Clear. |
| Water passed at | 11 55 | 1027·6 | −14·59 | Cloudy from phosphates. |
| Water passed at | 1 0 P.M. | 1027·9 | +12·64 | Cloudy from urates. |
| Water passed at | 2 55 | 1026·8 | +18·50 | Thick from urates. |
| Water passed at | 5 10 | 1025·4 | +24·38 | Thick from urates. |
| Water passed at | 7 0 | 1027·9 | +31·13 | Thick from urates. |
| Water passed at | 11 0 | 1031·8 | + 7·75 | Thick from urates. |
| Water passed at | 6 45 A.M. | 1024·7 | + 9·76 | Clear. |

(48.) The following day. Breakfast at $8^h\ 15^m$ A.M. Dinner at 7 P.M. Twenty

grains of carbonate of ammonia were taken at $11^h\ 40^m$ A.M. The same quantity at $1^h\ 15^m$ P.M. It was repeated at $2^h\ 25^m$, and again repeated at $3^h\ 55^m$. In all, eighty grains dissolved in about eight ounces of distilled water.

| | h m | Spec. gr. | Acidity per 1000 grs. of urine. | Appearance. |
|---|---|---|---|---|
| Water passed at | 8 15 A.M. | 1026·2 | +17·54 measures. | Clear. |
| Water passed at | 9 30 | 1025·0 | +12·68 | Thick from urates. |
| Water passed at | 10 25 | 1023·8 | + 6·83 | Clear. |
| Water passed at | 11 40 | 1027·0 | + 2·92 | Clear. |
| Water passed at | 1 15 P.M. | 1026·7 | +11·69 | Clear. |
| Water passed at | 2 25 | 1027·3 | +19·47 | Thick from urates. |
| Water passed at | 3 55 | 1023·9 | +23·44 | Clear. |
| Water passed at | 5 30 | 1022·8 | +25·42 | Clear. |
| Water passed at | 7 0 | 1025·2 | +29·26 | Clear. |
| Water passed at | 10 55 | 1028·9 | + 3·94 | Clear. |
| Water passed at | 5 10 A.M. | 1024·6 | + 2·94 | Clear. |

Plate LIII. gives the means of comparing the acidity of the urine on these days. Here also it is evident that the acidity is not so much diminished after food when carbonate of ammonia is taken, but the increase in the acidity after the volatile alkali is taken is not so evident as in the previous Plate LII.: this probably arose from the very considerable increase in the quantity of water made on the day the carbonate of ammonia was last taken. The volatile alkali acted as a diuretic. This is seen by the lower specific gravity of the urine the second day. The actual quantity of water passed was one-third more than it was on the previous day.

Still this experiment shows that eighty grains of carbonate of ammonia do not lessen the acidity of the urine.

(49.) The following day no carbonate of ammonia was taken. Breakfast at $8^h\ 20^m$ A.M. Dinner at $7^h\ 15^m$ P.M. An increased quantity of urine was secreted during this day also.

| | h m | Spec. gr. | Acidity per 1000 grs. of urine. | Appearance. |
|---|---|---|---|---|
| Water passed at | 8 20 A.M. | 1017·2 | +13·76 | Clear. |
| Water passed at | 9 30 | 1014·5 | + 8·87 | Clear. |
| Water passed at | 10 15 | 1014·5 | + 7·88 | Clear. |
| Water passed at | 11 25 | 1021·3 | +12·72 | Clear. |
| Water passed at | 1 10 P.M. | 1023·8 | +17·58 | Clear. |
| Water passed at | 2 30 | 1023·5 | +20·51 | Clear. |
| Water passed at | 3 50 | 1021·5 | +19·58 | Clear. |
| Water passed at | 5 20 | 1022·2 | +21·42 | Clear. |
| Water passed at | 7 15 | 1025·9 | +23·39 | Clear. |
| Water passed at | 10 30 | 1028·3 | 0 | Clear. |
| Water passed at | 6 25 A.M. | 1026·4 | +11·69 | Clear. |

(50.) The next day eighty grains of carbonate of ammonia were taken in divided doses: twenty grains at $11^h\ 45^m$ A.M.; the same quantity at $1^h\ 15^m$ P.M., at $2^h\ 30^m$ P.M., and at $3^h\ 45^m$ P.M. Breakfast was at $8^h\ 20^m$ A.M., and dinner at $7^h\ 30^m$ P.M.

The quantity of urine was much less than on the two previous days.

| | h | m | | Spec. gr. | Acidity per 1000 grs. of urine. | Appearance. |
|---|---|---|---|---|---|---|
| Water passed at | 8 | 20 | A.M. | 1026·5 | +18·50 measures. | Thick from urates. |
| Water passed at | 9 | 30 | | 1025·6 | +14·62 | Thick from urates. |
| Water passed at | 10 | 35 | | 1028·4 | + 7·78 | Thick from urates. |
| Water passed at | 11 | 45 | | 1029·3 | 0 | Clear. |
| Water passed at | 1 | 15 | P.M. | 1027·9 | +14·59 | Thick from urates. |
| Water passed at | 2 | 30 | | 1027·4 | +21·41 | Clear. |
| Water passed at | 3 | 45 | | 1026·7 | +26·29 | Clear. |
| Water passed at | 5 | 20 | | 1026·9 | +28·24 | Clear. |
| Water passed at | 7 | 30 | | 1028·7 | +32·08 | Clear. |
| Water passed at | 11 | 15 | | 1029·7 | +17·48 | Clear. |
| Water passed at | 6 | 55 | A.M. | 1028·4 | +19·44 | Thick from urates. |

Here again there is decided evidence of an increase in the acidity of the urine after a large dose of carbonate of ammonia. There was no diuretic action, but during the night a most profuse and unusual perspiration took place. The following morning no carbonate of ammonia was taken.

(51.) Breakfast was at $8^h\ 35^m$ A.M. Dinner at $6^h\ 15^m$ P.M. The same as on the previous days.

| | | | | | |
|---|---|---|---|---|---|
| Water passed at | 8 | 35 | A.M. | 1026·7 | +22·40 | Thick from urates. |
| Water passed at | 9 | 40 | | 1026·2 | +13·64 | Thick from urates. |
| Water passed at | 11 | 0 | | 1027·4 | + 8·76 | Thick from urates. |
| Water passed at | 1 | 0 | P.M. | 1030·6 | +11·64 | Thick from urates. |
| Water passed at | 3 | 0 | | 1028·9 | +21·38 | Thick from urates. |
| Water passed at | 6 | 15 | | 1030·8 | +29·10 | Thick from urates. |
| Water passed at | 10 | 30 | | 1033·3 | +13·55 | Thick from urates. |
| Water passed at | 2 | 0 | A.M. | 1030·3 | + 8·73 | Thick from urates. |
| Water passed at | 7 | 20 | | 1028·8 | +18·47 | Thick from urates. |
| Water passed at | 8 | 20 | | 1029·8 | +20·39 | Thick from urates. |

Perhaps the acidity did not rise higher on account of the perspiration, which must have removed much acid from the system. The effect of the carbonate of ammonia may be traced in a smaller fall than usual in the acidity after breakfast and dinner.

These experiments, well seen in Plate LII., then tend to the confirmation of the results previously obtained:—first, that there is a very great difference between the effects of volatile and fixed alkalies on the acidity of the urine; secondly, that carbonate of ammonia, in large doses, does not diminish the acidity of the urine; thirdly, that carbonate of ammonia, in large doses, actually increases the acidity of the urine; and this was evident, not only in the acidity not falling so low as it did after food when no carbonate of ammonia was taken, but in an actual rise before food to a higher degree than was reached when no carbonate of ammonia was administered.

The conclusions from these experiments with tartrate and carbonate of ammonia may be shortly stated thus—

(*e.*) That tartrate of ammonia in large doses produces no effect on the alkalescence of the urine. It differs entirely in this respect from tartrate of potash.

(*f.*) That carbonate of ammonia in large doses increases the acidity of the urine.

I hope to determine the cause of this in a future paper on the variations of the nitrates in the urine.

# XXXV. *An Experimental Inquiry into the Strength of Wrought-Iron Plates and their Riveted Joints as applied to Ship-building and Vessels exposed to severe strains.*

*By* WILLIAM FAIRBAIRN, *Esq.*

*Communicated by the Rev.* HENRY MOSELEY, *F.R.S.*

Received April 25,—Read June 13, 1850.

THE experiments herein recorded were instituted early in the spring of 1838, and before the close of the following winter most of them had been completed; owing however to a long series of professional engagements they have stood over (with the exception of some additions made in the following year) to the present time. The object of the inquiry was twofold—first, to ascertain by direct experiment the strength of wrought-iron plates and their riveted joints in their application as materials for ship-building; and secondly, to determine their relative value when used as a substitute for wood. On these two points it cannot be expected that our knowledge should be far advanced, as a very few years have elapsed since it was asserted that iron, from its high specific gravity, was not calculated for such a purpose, and that the greatest risk was likely to be incurred in attempting to construct vessels of what was then considered a doubtful material. Time has however proved the fallacy of these views, and I hope, in the following experiments, to show that the iron ship, when properly constructed, is not only more buoyant, but safer, and more durable than vessels built of the strongest English oak.

At the commencement of the experiments I felt desirous of conducting them upon a scale of such magnitude as would supply sound practical data, and at the same time establish a series of results calculated to ensure confidence as well as economy in the use of the material. My views were ably carried out by Mr. HODGKINSON, who conducted the experiments under my direction, and from whom I received valuable assistance.

In conducting the investigation I found it necessary to divide the subject into four distinct parts:—

1st. The strength of plates when torn asunder by a direct tensile strain in the direction of the fibre, and when torn asunder across it.

2ndly. On the strength of the joints of plates when united by rivets as compared with the plates themselves.

3rdly. On the resistance of plates to the force of compression, whether applied by a dead weight or by impact.

And lastly. On the strength and value of wrought-iron frames and ribs as applied to ships and other vessels*.

## PART I.

At the commencement of iron ship-building, in which I took an active part, the absence of acknowledged facts relative to the strength and varied conditions under which the material was applied, was the principal reason which induced me to enter upon this inquiry. I have extended the investigation into the best methods of riveting, and the proportional strength of rivets, joints, &c., as compared with the plates and the uses for which they are intended. The latter is a practical and highly important inquiry, as great difference of opinion exists amongst engineers and others, as to the form, strength and proportions of rivets, and the joints of which they form an essential part. I therefore considered an experimental investigation much wanted, not only on account of its important practical bearing, but what was probably of equal value, in order to remove existing discrepancies and to establish a sounder principle of construction founded upon the unerring basis of experiment. From these considerations I bestowed increased attention upon the inquiry, and endeavoured to render it practically useful. Before detailing the experiments, it may be necessary to describe the apparatus by which the results were obtained.

The annexed drawings, Plate LIV., represent a side and end view of the apparatus used in the experiments. The large lever A was made of malleable iron and was fixed to the lower cross beam B (fig. 1) by a strong bolt O, which passed through it at B. At the top end of this bolt a preparation was made to receive the end of the lever, and by means of the screw-nut at *a*, the lever A was raised or lowered to suit the length of the plates to be experimented upon. Upon the top side of the beam, and under the gable wall of a building five stories high, were placed two cast-iron columns, D, D, which retained the beam B in its place and prevented it from rising when the lever was heavily loaded during the experiment. The frame E guided the end of the lever and the weight W, and close to the fulcrum were placed two wooden standards,

* Several important facts and improvements in the construction of iron ships have been ascertained since my experiments were made, but I apprehend none of them have tended in the least degree to diminish their value. Nor have they, to the best of my knowledge, been superseded by others of a more elaborate or more decisive character. It is true, that a series of interesting and important experiments have been made at the instance of the Admiralty on the effect of shot upon the sides of iron ships. At some of these experiments I had the honour to be present, and witnessed some curious and unexpected results.

The first series was conducted at the Arsenal, Woolwich, and subsequently others were made at Portsmouth. Both were important as respects the effect of shot upon wrought-iron plates, with enlarged and diminished charges of powder and at different velocities, but discouraging as regards the use of iron in the construction of ships of war. These experiments, however interesting in themselves, do not appear to be conclusive; and it is to be hoped that the apparent danger, indicated by the experiments, may yet be overcome, and the superiority as well as the greater security of the iron ship fully established.

F F, on which were fixed the cast-iron saddles receiving the cross bar G, from which the plates to be experimented upon were suspended. These plates were nearly all of the same form as shown at H, and were made narrower in the middle to ensure fracture in that part; the ends, as at *b*, *b*, had plates riveted to them on both sides, in order to strengthen them at those parts when attached to the bolts and shackle under strain.

The specimens thus prepared were suspended by the cross bolts *i*, *i*, and resting upon the standards were torn asunder by weights suspended from the large beam, as exhibited in the Plate.

In addition to the large weight W, a strong scale was attached to the extreme end of the lever at I, for the purpose of increasing the weights when required in the larger description of experiments, and by the application of a pair of blocks and the windlass K, the load was removed, and the changes produced upon the plates were by these means carefully determined.

The following data respecting the weight W, lever, shackle, &c., are taken from the actual weights from which the calculations are made:—

| | lbs. |
|---|---|
| W. The weight with its carriage . . . . . | 2552 |
| A. The weight of the beam . . . . . | 1070 |
| 2 A. The weight of the beam . . . . . | 2140 |
| 3 A. The weight of the beam . . . . . | 3210 |
| K. Shackle . . . . . | 24 |
| 4 K. Shackle . . . . . | 96 |
| 6 K. Shackle . . . . . | 144 |

*Experiments to ascertain the Strength of Plates, &c.*

In the following experiments all the plates were of uniform thickness, and of the form exhibited in fig. 2 in the column of remarks; the ends had plates riveted to them on both sides to render them inflexible; they had holes, 0, 0, bored through them perpendicular to the plate, in order to connect it by bolts, with the apparatus for tearing it asunder in the part A B, which was made narrower than the rest. The centres of the holes 0, 0 were in a direct line through the middle between A and B*.

TABLE I. Strength of Plates.—Low Moor Yorkshire Iron.

| No. of exp. | Description of plate and dimensions in the middle. | Weight laid on in lbs. | Reduced dimensions in middle of plate through weights laid on. | Breaking weight in lbs. | Mean breaking weight in lbs. | Remarks. |
|---|---|---|---|---|---|---|
| | Drawn in the direction of the fibre. | | | | | Fig. 2. Plan and section of the plates, the line AB being that of the fracture. |
| 1. | Area of section in middle | 24,043 | 1·96×·21 | | | |
| | 2·00×·22=·44 in. | 25,531 | 1·89×·19 | 25,531 | | |
| 2. | ..... | 23,571 | Reduced. | | | |
| | | 24,747 | 1·93×·18 | 24,747 | 25,400, or 25·77 tons per square inch. | |
| 3. | ..... | 25,923 | 1·94×·18 | 25,923 | | |
| | | | | | | All the plates were laminated as if formed of three or more plates, the external ones being thinner than the internal ones†. In the last experiment there was a disunion between the lamina which admitted the point of a penknife. |
| | Same iron drawn across the fibre. | | | | | |
| 4. | Area of section | 23,179 | Altered. | | | |
| | 2·00×·22=·44 in. | 24,355 | 1·99×·215 | | | |
| | | 25,923 | ..... | | | |
| | | 27,099 | 2·2×·19 | 27,099 | 27,099, or 27·49 tons per square inch. | This, it will be seen, did not break at the narrowest place. |

TABLE II. Strength of Plates.—Low Moor Yorkshire Iron.

| No. of exp. | Description of plate and dimensions in the middle. | Weight laid on in lbs. | Reduced dimensions in middle of plate through weights laid on. | Breaking weight in lbs. | Mean breaking weight in lbs. | Remarks. |
|---|---|---|---|---|---|---|
| | Same iron as in Table I., drawn across the fibre. | | | | | The form and size of specimen as before, fig. 2. |
| 5. | Area of section | | | | | In these experiments it was observed, as in No. 4. in the preceding Table, that the plate did not break at the narrowest part, a circumstance the more anomalous, as there did not appear to be anything in the apparatus to cause it. |
| | 2·00×·22=·44 in. | 24,355 | Stretching. | | | |
| | | 26,315 | 21·5 ×·20 | 26,315 | | |
| 6. | ..... | 23,571 | 2·25×·20 | 23,571 | 25,662, or 26·037 tons per square inch. | |
| | Same iron, thicker plates, drawn in direction of fibre. | | | | | |
| 7. | Area of section | | | | | |
| | 2·00×·26=·52 in. | 27,099 | Thickness ·25 | 27,099 | ..... | Very uniform in texture. |
| | ..... | 25,923 | 1·96×·24 | 25,923 | 26,511, or 22·76 tons per square inch. | The fracture of this specimen showed a great want of regularity; about one-third of the area had the appearance of steel. All the other plates appeared to be uniform, but laminated, as mentioned before. |

* For the appearance of the fractures see Plate LV.

† Nearly the whole of the plates manufactured in this country are laminated, owing to the manner in which the shingles are formed, by piling a number of flat bars one upon another, which are made larger or smaller according as the plate may be required heavier or lighter.

The results obtained from the Low Moor plates in the preceding Tables give fair indications of their strength. It will be observed, on comparing the mean of the breaking weights in this case with the experiments of Brown and Telford, that there is a very slight difference between the strength of plates and bar iron.

Taking the results of Captain Brown, we have in eight experiments on Swedish, Welsh and Russian iron, 25 tons as a mean of the breaking weight when reduced to an inch square.

In Mr. Telford's experiments on Swedish, Welsh, Staffordshire and faggoted iron, the mean breaking weight obtained from nine different bars was 29¼ tons to the square inch. The comparison will then be—

| | |
|---|---|
| Captain Brown's experiments, 25 tons to the square inch . . . . | Mean 26·41 tons. |
| Minord and Desames' experiments, 25 tons to the square inch . . | |
| Mr. Telford's experiments, 29¼ tons to the square inch . . . . | |
| Yorkshire plates' experiments, 24½ tons to the square inch. | |

Making the strength of plates to that of bars as 24·5 : 26·4, being a comparatively small difference in their respective powers to resist a tensile force.

Table III. Strength of Plates.—Derbyshire Iron.

| No. of exp. | Description of plate and dimensions in the middle. | Weight laid on in lbs. | Reduced dimensions in middle of plate through weights laid on. | Breaking weight in lbs. | Mean breaking weight in lbs. | Remarks. |
|---|---|---|---|---|---|---|
| 9. | Drawn in the direction of the fibre. Area of section 2·00×·28in. Mean 2·00×2·85=·57 | 21,219<br>28,667 | Stretched.<br>2·00×·27 | 28,667 | | Form of specimen the same as shown in Table I. fig. 2. |
| 10. | 2·00×·29in. | 21,219<br>22,789<br>26,707 | Sinking.<br>Sinking.<br>2·15×·27 | 26,707 | 27,687, or 21·68 tons per square inch. | There was a stripe resembling steel across the fracture near one side. |
| 11. | Plates drawn across the fibre. Area of section 2·00×·28=·56 in. | 22,395<br>23,179 | Stretching.<br>Thickness ·27 | 23,179 | ..... | In the broken surface there seemed to be a stratum of steel, the rest was laminated but imperfectly. |
| 12. | 2·00×·28=·56 in. | 24,747 | 2·00×·28 | 24,747 | 23,963, or 18·65 tons per square inch. | Short streaks of steel in fractured surface. |

If we compare the results in the Derbyshire plates with those in the preceding Tables, we have in the mean of four experiments a ratio of 20·165 : 24·850, or 5 to 6 nearly.

Again, by comparing the same plates with the mean strength of bars reduced to an inch square, the difference will be as 20 to 26, being an excess of 6 tons in favour of the bars.

TABLE IV. Strength of Plates.—Shropshire Iron.

| No. of exp. | Description of plate and dimensions in the middle. | Weight laid on in lbs. | Reduced dimensions in middle of plate through weights laid on. | Breaking weight in lbs. | Mean breaking weight in lbs. | Remarks. |
|---|---|---|---|---|---|---|
| | Drawn in the direction of the fibre. | | | | | Form of specimen the same as shown in Table I. fig. 2. |
| 13. | Area of section 2·00×·265=·53 in. | ..... | ..... | 28,275 | | In the first experiment the fracture showed an iron very uniform, except a few bright spots like steel. |
| 14. | ..... | ..... | ..... | 25,923 | 27,099, or 22·826 tons per square inch. | Experiment 2. Appearance of fracture as before, but a crack up the middle showed that the plate was formed of two plates of equal thickness, not well united. |
| | Plates of the same iron drawn across the fibre. | | | | | |
| 15. | 2·00×·265=·53 in. | ..... | ..... | 26,315 | 26,119, or 22 tons per square inch. | Fracture as before, with a laminated diversion, as in last experiment. |
| 16. | ..... | ..... | ..... | 25,923 | | |

The Shropshire iron gives better indications of strength than those obtained from the Derbyshire plates; the mean breaking weights in the last Table being 22·41 tons. From the Yorkshire plates we have a mean breaking weight of 24·85 tons, exhibiting a difference of 2½ tons in favour of the Yorkshire iron, and 2 tons or about $\frac{1}{10}$th greater than the Derbyshire.

TABLE V. Strength of Plates.—Staffordshire Iron.

| No. of exp. | Description of plate and dimensions in the middle. | Weight laid on in lbs. | Reduced dimensions in middle of plate through weights laid on. | Breaking weight in lbs. | Mean breaking weight in lbs. | Remarks. |
|---|---|---|---|---|---|---|
| | Drawn in the direction of the fibre. | | | | | Form of specimen the same as before, fig. 2. |
| 17. | 2·00×·26=·52 in. | ..... | ..... | 23,571 | 22,787, or 19·563 tons per square inch. | Fracture dark grey colour, very similar to that from the four preceding plates. |
| 18. | ..... | ..... | ..... | 22,003 | | It had however a few specks of bright matter in it, and was without any laminated appearance. |
| | Plates of the same iron drawn across the fibre. | | | | | Irregular in texture, air-bubbles in fractured surface, with bright crystallized matter like steel. |
| 19. | Area of section 2·00×·265=·53 in. | ..... | ..... | 24,335 | 24,943, or 21·01 tons per square inch. | This iron has much of the same irregularity as the Derbyshire iron. |
| 20. | ..... | 23,571 | The thickness ·26 | 25,531 | | Surface of fracture showed the iron to be very irregular, one-half being bright matter like steel. |

On comparing the strengths of the different irons, it appears that the Derbyshire and Staffordshire plates are nearly equal, the former indicating 20·165 tons as the mean of the breaking weight per square inch, and the latter, as in the preceding Table, 20·28 tons per square inch. The same comparison further applies to the above and those made on the Derbyshire plates in Table III.

Taking therefore the results as derived from these experiments, it will be observed, that in every instance little or no difference appears to exist in the resisting powers of plates, whether drawn in the direction of the fibre or across it. This fact is clearly established by the following comparison, which evidently shows, that in whatever direction the plates are torn asunder, their strength is nearly the same.

| | Mean breaking weight in the direction of the fibre, in tons per square inch. | Mean breaking weight across the fibre, in tons per square inch. |
|---|---|---|
| Yorkshire plates..... | 25·770 | 27·490 |
| Yorkshire plates..... | 22·760 | 26·037 |
| Derbyshire plates ..... | 21·680 | 18·650 |
| Shropshire plates ..... | 22·826 | 22·000 |
| Staffordshire plates ..... | 19·563 | 21·010 |
| Mean..... | 22·519 | 23·037 |

Or as 22·5 : 23·0, equal to about $\frac{1}{45}$ in favour of those torn across the fibre*.

From the above it is satisfactory to know, so far as regards uniformity in the strength of plates, that the liability to rupture is as great when drawn in one direction as in the other; and it is not improbable that the same property would be exhibited, and the same resistance maintained, if the plates were drawn in any particular direction obliquely across their fibrous or laminated structure.

In order however to establish the relative powers of resistance in plates of rolled iron, I have endeavoured to tabulate the results, as derived from the preceding experiments, in such form as will indicate their respective values, and place them in comparison with each other, and also with those made on bars by Telford and Brown. The comparisons are made from the Yorkshire plates, as producing the best results; and conceiving them to be a fair average of the strength of rolled iron, I have selected them as the standard of comparison.

Comparative results of rolled iron as derived from experiment, the Yorkshire plates being unity.

| Names of Iron. | No. of experiments. | Mean breaking weight in tons per square inch. | Mean breaking weight in tons per square inch. | Ratio of the strength of plates drawn in the direction of the fibre, and across it. Also of rolled and faggoted bars drawn in the direction of the fibre. |
|---|---|---|---|---|
| Yorkshire plates..... | 8 | 25·514 | ..... | |
| Derbyshire plates ..... | 4 | ..... | 20·160 | 1 : 0·7882 |
| Shropshire plates ..... | 4 | ..... | 22·413 | 1 : 0·8789 |
| Staffordshire plates ..... | 4 | ..... | 20·264 | 1 : 0·7946 |
| Mean..... | ..... | 25·514 | 20·945 | 1 : 0·8209 |
| From Mr. Telford and Captain Brown's experiments on bars ..... | ..... | ..... | 26·41 | 1 : 1·0351 |

* In some experiments by Navier upon the strengths of plates of wrought iron, both in the direction of the fibre and perpendicular to it, he found them as 40·8 to 36·4. The new methods of piling the rough bars before rolling may however account for the difference, and in a great measure determines the strength of the plate. In this country the process of piling is by equal layers of flat bars at right angles to each other, which produces great uniformity of strength and texture in the manufacture. At other places there is sometimes a difference in the mode of piling, which varies the texture of the plate, and also the strength of the layers are greater in one direction than another.

Here it will be observed that the difference between the strength of the Low Moor plates in their resistance to a tensile strain, when compared with bar iron, is inconsiderable; but taking the mean of the other irons, viz. the Derbyshire, Shropshire and Staffordshire, there is a falling off in the strength of about 21 per cent., the ratio being in favour of bar iron as 1·035 : ·8209.

In treating of the strength of iron, it may be useful to compare the foregoing experiments on the tensile strength of plates with those of a similar description on timber. On this subject I feel the more desirous of establishing a comparison, as the two kinds of material are now applied to similar purposes, such as ship-building and other constructions, and the question becomes every day more important as to which of the two materials is the best. There is every reason to believe that the advocates of improvement would arrange themselves on the side of iron, and those for the "wooden walls" would be equally zealous on that of timber. This is however a question which time and experience alone can determine, and conceiving that our knowledge of the properties of iron, as a material for ship-building, is far from perfect, we may safely leave its final decision to the evidence of experimental research, and a more extended application of its practical results.

When we attempt a comparison of the value of one material, in its application to a specific purpose, with that of another material similarly applied, the comparison is only correct when the two materials are placed in juxtaposition, or when they are contrasted under the same circumstances as to the trials and tests to which they are respectively subjected. Now in this comparison I am fortunate in having before me the able experiments of Musschenbrock, Buffon, and those of a more recent date on direct cohesion by Professor Barlow of Woolwich. I have selected from the experiments of the latter those which appear to approach most nearly to the present inquiry; and impressed with the conviction of their having been carefully conducted and being from English timber, I attach the greatest value to them.

According to Musschenbrock's, the strengths of direct cohesion per square inch of the following kinds of timber are as follows:—

| | lbs. | | lbs. |
|---|---|---|---|
| Locust-tree | 20,100 | Pomegranate | 9750 |
| Locust-tree | 18,500 | Lemon | 9250 |
| Beech and oak | 17,300 | Tamarind | 8750 |
| Orange | 15,500 | Fir | 8330 |
| Alder | 13,900 | Walnut | 8130 |
| Elm | 13,200 | Pitch pine | 7630 |
| Mulberry | 12,500 | Quince | 6750 |
| Willow | 12,500 | Cyprus | 6000 |
| Ash | 12,500 | Poplar | 5500 |
| Plum | 11,800 | Cedar | 4880 |
| Elder | 10,000 | | |

From Barlow the strengths are,—

| | lbs. | | lbs. |
|---|---|---|---|
| Box | 20,000 | Beech | 11,500 |
| Ash | 17,000 | Oak | 10,000 |
| Teak | 15,000 | Pear | 9800 |
| Fir | 12,000 | Mahogany | 8000 |

Mr. Barlow, in adverting to the experiments of Musschenbrock, observes, that some of them differ considerably from his own, a circumstance probably not difficult to account for, as the different degrees of dryness have a great effect upon the strength of timber*.

Dr. Robison, in speaking of the experiments of Musschenbrock, states, that we may presume they were carefully made and faithfully narrated, but they were made on such small specimens, that the unavoidable natural inequalities of growth or texture produced irregularities in the results which have too great a proportion to the whole quantities observed. It is for the same reason that I give preference to Mr. Barlow's results, as he observes, "that the experiments from which they are drawn were made with every possible care the delicacy of the operation would admit." Assuming therefore that Barlow is correct, and taking the mean strength of iron plates, as given in the preceding Tables, at 49,656 lbs. to the square inch, or calling it 50,000 lbs., and the resistance of the direct cohesion of different kinds of timber as given by Mr. Barlow, the following ratio of strengths will be obtained:—

| | Timber lbs. | : | Iron. lbs. | Ratio, taking timber as unity. |
|---|---|---|---|---|
| Ash | 17,000 | : | 50,000, | or as 1 : 2·94 |
| Teak | 15,000 | : | 50,000, | or as 1 : 3·33 |
| Fir | 12,000 | : | 50,000, | or as 1 : 4·16 |
| Beech | 11,500 | : | 50,000, | or as 1 : 4·34 |
| Oak | 10,000 | : | 50,000, | or as 1 : 5·00 |

Hence it appears that the direct cohesion of iron plates is five times greater than oak; or in other words, their powers of resistance to a force applied to tear them asunder is as 5 to 1, making an iron plate $\frac{1}{2}$ inch thick equal to an oak plank of $2\frac{1}{2}$ inches thick. In the teak wood and fir specimens, which exhibit greater resisting powers, nearly the same rule will apply, and thinner planks, as regards the tensile strength, would answer the purpose. This is a circumstance which may be applicable to teak wood, but unfavourable to fir when viewed as a building material exposed to a great variety of strains, or when used for sheathing and similar purposes in the art of ship-building. The teak wood being timber of greater density and of

* It has been shown by Mr. Hodgkinson, that timber, when wet, will be crushed by a force less than one-half of what would take to crush it when dry. It therefore follows that much depends upon the samples selected and the way in which the timber has been seasoned.

higher specific gravity, is better calculated to resist shocks than a tough fibrous substance of a soft and spongy nature, such as fir.

On this subject it should however be noticed, that whatever material is used for covering the ribs of vessels, it should be strong and elastic, in order to resist not only the force of direct tension, but that of lateral and compressed action. In a ship at sea these forces are strikingly exemplified, and that under circumstances embarrassing as well to the practical builder as the man of science.

*Remarks on the foregoing experiments.*

Having determined the strength of iron plates when drawn in the direction of the fibre as well as across it, and having compared the results with experiments of a similar character on timber, it may be useful to offer a few general observations on the question now under consideration.

Dr. Robinson, in his article on the strength of materials*, when discussing the nature of a stretching force applied to materials, observes, "that in pulling a body asunder the force of cohesion is directly opposed with very little modification of its action; that all parts are equally stretched, and the strain in every transverse section is the same in every part of that section." From this it would appear, that a body of a homogeneous texture will have the cohesion of its parts equal, and since every part is equally stretched, it follows that the particles will be drawn to equal distances, and the forces thus exerted must be equal. Now if this were true, the application of an external force to a body might be increased to such an extent as not only to separate the parts furthest asunder, but ultimately to destroy the cohesion of all the particles *at once*, a circumstance under which instantaneous rupture would follow as a result. These views are however not borne out by facts, as the experiments of Mr. Hodgkinson on iron wire show that the same iron may be torn asunder many times in succession without impairing its strength†; and some recent experiments at the Royal Dockyard, Woolwich, clearly show, that an iron bar may be stretched until its transverse section is considerably reduced and ultimately broken without injury to its tensile strength. Nay, more, the same iron (so elongated), when again submitted to experiment, exhibited increased strength, and continued to increase, under certain limitations, beyond the bearing powers of the same bar in its original form‡. That all the parts of a body "subjected to a tensile strain are equally stretched" is therefore questionable. Bodies vary considerably in their powers of resistance, and exhibit peculiar properties of cohesion under the influence of forces calculated to tear them asunder. Fibrous substances, for instance, such as ropes and some kinds of timber having their fibres twisted, are enabled to resist tension under the influence of considerable elongation without impairing their ultimate strength.

* Encyclopædia Britannica.

† Manchester Memoirs, vol. v.

‡ I am indebted to Mr. Thomas Loyd of the Admiralty for a series of interesting results on this subject. See Appendix.

Many of the fibres are stretched, but only to the extent of bringing the others to bear upon the load, which done, their united force constitutes the maximum of resistance to a tensile strain.

Other bodies of less ductility and more of a crystalline structure, such as cast iron, stone, glass, &c., seem to be subject to the same law. In these cases it seldom happens that the whole of the particles are brought into action at once, as much depends upon the conditions of the body, the unequal state of tension of its parts, and the strain which some of the particles must sustain before the others receive their due portion of the load. Should the non-resisting particles be within the limits of elongation of the other particles, the body will then have attained its maximum power of resistance; but in the event of rupture to any of the resisting particles, the cohesive force of the body is thereby reduced, and that to the extent of the injury sustained by the fractured parts.

"There are however," as Dr. ROBINSON truly observes, "immense varieties in the structure and composition of bodies which lead to important facts, and prove that the absolute cohesion of all bodies, whatever be their texture, is proportional to the areas of their sections." Undoubtedly this is the case in bodies having an uniform texture with straight fibres, and hence it follows that the absolute strength of a body, resisting a tensile strain, will be as the area of its section.

The peculiar nature of the material combining a crystalline as well as a fibrous structure has led to these observations. In some instances the specimens experimented upon exhibited an almost distinct fibrous texture, and in others a clearly developed crystalline structure*. At other times some of the specimens were of a mixed kind, with the crystalline and fibrous forms united; the fracture having a laminated appearance, with the crystalline parts closely bound on each side by layers of the fibrous structure. These varieties are probably produced in the manufacture, and may be easily effected either by the mode of "piling" the layers of bars which form the plate, or from the unequal temperature of the parts as they pass through the rolls. But whichever way they are produced, it is evident, from the experiments, that the fractures gave, in most cases, indications of an unequal and varied texture.

In the foregoing experiments, and also in those which follow, great attention was paid to the appearance of the fracture, in order to ascertain the structure of the plate, and to determine how far it could be depended upon in its application to the varied purposes for which it was intended.

These appearances are all shown in the drawings appended to the experiments, and to which I beg to refer.

* See the fractured parts of the different specimens, Plate LV.

## PART II.

*On the Strength of Iron Plates united by Rivets, and the best mode of Riveting.*

The extensive and almost innumerable uses to which iron is applied, constitute one of the most important features in the improvements of civilized life. It contributes to the domestic comforts and commercial greatness of the country, and from its cheapness, strength and power of being moulded, rolled and forged into almost every shape, it is not only the strongest, but in many respects the most eligible material for the construction of vessels exposed to severe strain. Large vessels composed of iron plates, such as steam-boilers, cisterns, ships, &c., cannot however be formed upon the anvil or the rolling-mill. They are constructed of many pieces, and these pieces have to be joined together in such a manner as to ensure the requisite strength and effect all the requirements of sound construction. This operation is called riveting, and although practically understood, it has not, to my knowledge, on any previous occasion, received that attention which the importance of the subject demands.

Up to the present time* nothing of consequence has been done to improve or enhance the value of this process. We possess no facts or experiments calculated to establish principles sufficient to guide our operations in effecting constructions of this kind, on which the lives of the public as well as the property of individuals depend. In fact, such has been our ignorance of the relative strength of plates and their riveted joints, that until the commencement of the present inquiry the subject was considered of scarcely sufficient importance to merit attention. Even now, it is by many assumed that a well-riveted joint is stronger than the plate itself, and a number of persons, judging from appearances alone, concur in that opinion. Now this is a great mistake, and although the double thickness of the joint indicates increased strength, it is nevertheless much weaker than the solid plate, a circumstance of some importance, as we hope to show in the following experiments.

It would probably be superfluous to offer any lengthened description of the principle upon which wrought-iron plates are united together; riveting is so familiar to every person in this country, that it might appear a work of supererogation to attempt it; and, assuming that the usual method of riveting by hammers to be generally known, we shall proceed to describe another method by machinery which effects the same object in considerably less time and at less cost, and completes the union of the plates with much greater perfection than could possibly be done by the hand. In hand-riveting it will be observed, that the tightness of the joint and the soundness of the work depends upon the skill and also upon the will of the workman, or those who undertake to form the joint and close the rivets. In the machine-riveting neither the will nor the hand of man has anything to do with it, the machine closes the joint and forms the rivet with an unerring precision, and in no instance can imperfect work be accomplished so long as the rivets are heated to the extent compressible by the machine.

* 1838, when these observations were written.

This property of unvarying soundness in the work, constitutes the superiority of the machine over the hand-riveting. The machine produces much sounder work, as the time occupied in the hand process allows the rivet to cool, and thus by destroying its ductility, the rivet is imperfectly closed, and hence follow the defects of leaky rivets and imperfect joints. It is evident that an instrument, such as the riveting-machine, having sufficient force to compress the rivet at once, or within an almost infinitely short period of time, must obviate, if not entirely remedy, these evils, as the force of compression being nearly instantaneous, the heads on both sides cannot be formed until the body of the rivet is squeezed tight into the hole; and in every case (even where the holes are not exactly straight) the compressed rivets are never loose, but fill the holes with the same degree of tightness as if placed directly opposite to each other. If, for example, we take a circular boiler, such as represented at A*, Plate LVI. fig. 3, and having all the perforations made and the plates attached to each other by temporary bolts and suspended over the machine in the position as shown at A, and having brought the holes in a line with the die marked *i*, *k*, the machine then is set to work, and by means of the cam or excentric raising the pulley of the elbow-joint C, the die *k* is advanced against the fixed die *i* in the wrought-iron stem, and the rivet is compressed into the required form with an increasing force as the die advances which gives the "nip," or greatest pressure, at the required time, namely, at the closing of the rivet.

From this description it will appear that a very limited portion of time is occupied in the process, and as twelve rivets can be inserted and finished by the machine in a minute, it follows, from the rapidity of the operation and the absence of hammering, that the ductility of the rivets is retained, and their subsequent contraction upon the plate renders the joint perfectly tight and the rivets sound in every respect. Under all the circumstances the machine-riveting is preferable to that executed by the hammer; it saves much time and labour, and that in proportion of 12 to 1, when compared to a long series of impacts applied by the hammer.

Having described the process of uniting wrought-iron plates by rivets, it may be of some importance to know the value of joints thus formed as regards their strength when compared with the plates themselves. To attain this object, and satisfactorily to determine their powers of resistance to a tensile strain, a great variety of joints were made, and having prepared the different specimens with the utmost care and attention, they were submitted to the test of experiment as follows:—

* The plan represents the machine in the act of riveting the corners of a square cistern or a locomotive fire-box.

## Table VI. Strength of riveted Plates.—Yorkshire Iron*.

| No. of exp. | Description of plates and mode of riveting. | Weight laid on in lbs. | Changes produced by weights. | Breaking weight in lbs. | Form of specimen and mode of fracture. | Remarks. |
|---|---|---|---|---|---|---|
| 21. | Plates 22 inches thick, overlap joints, two rivets half-inch diameter, lap 1½ inch, AB = 3 inches, riveted by the patent machine. | ..... | ..... | 20,011 } Mean 20,127 | Fig. 4.   | Torn across at the rivet-holes. |
| 22. | Same as last, area 44 in. | ..... | ..... | 18,667 | | Rivet-holes torn out. |
| 23. | ..... | ..... | ..... | 21,703 | | Rivet-holes torn out. |
| 24. | Plates as before, riveted by the hammer, the rivets half-inch diameter, being of the usual length, but rather shorter than those used for the machine. | 14,839 | ..... | 16,115 } Mean 16,107 | Specimen same as before, fig. 4. | Rivet-heads broke off and the plate torn across them in consequence. |
| 25. | ..... | 15,343 | Plates bent. | 16,099 | ..... | Rivet-heads cracked across and rivet-holes torn out. |
| 26. | Plates same as before and riveted by the hammer, with half-inch rivets, the rivets being a little longer and 2 inches lap ..... | 14,839 | Plates bent nearly into a direct line with straining force. | 17,833 } Mean 18,982 | Specimen same as before, fig. 4. | Here the rivets were the same length as the machine rivets, experiments 1, 2, 3, and were worked with great care on both sides. Both rivet-heads broken and the plate torn across them. |
| 27. | ..... | 14,839 | ..... | 20,131 | ..... | Torn across at rivet-holes, and one rivet-head split. |
| 28. | Plates same as before, lap 2 inches, and the rivets the same as in the last experiment, but riveted by the machine ..... | 14,839 | Plates bent into a direct line by the straining force. | 19,123 } Mean 19,147 | Specimen same as before, fig. 4. | Both rivets cracked across, metal torn across the rivet-holes. |
| 29. | ..... | 18,667 | Joint apparently sound. | 19,171 | ..... | Torn across at the rivet-holes, both rivets slightly cracked near the head. |

The plates used in the foregoing experiments are of Yorkshire iron, the same as those employed in Tables I. and II. The specimens were prepared in the same manner and of the same thickness, but 1 inch wider at the joint. This was done in order to retain sufficient metal round the rivet-holes, making the breadth of the plate the same after the rivet-holes were punched out as that of the plates torn asunder in the preceding experiments. In all these experiments only two half-inch rivets were used in the breadth of the plate. The lap was however increased, after the three first experiments, from 1½ to 2 inches, to give greater strength in the longitudinal line of the plate and to prevent the metal tearing in that direction. This precaution was

* The nature and appearance of the fractures of all the irons and their riveted joints are shown in Plate LVII.

found necessary, as the metal gave indications of weakness in consequence of the lap being rather narrow. Another reason for enlarging the lap was a desire at the commencement to begin with the least possible quantity, and by direct experiment to ascertain the maximum distance which the plates should overlap each other in the joints, and to determine the strongest and best form of uniting them. To these points every attention was given, for the purpose of collecting the facts on which are founded the tabulated results on that part of the subject which treats of the comparative dimensions of rivets and extent of the lap in reference to the thickness of the plates. In this department of the inquiry will be found the depth of lap, diameter and length of rivets, and the distances of holes for nearly every description of joint; also the thickness of the plate, with a column of strengths as deduced from the experiments.

If we examine the nature of the fracture in the foregoing experiments, it will be found that the machine-riveting is superior to that done by the hammer; the mean of the three first experiments being to the mean of the fourth and fifth as 5 : 4. In the eighth and ninth the strengths are nearly the same.

On comparing the strength of plates with their riveted joints, it will be necessary to examine the sectional areas taken in a line through the rivet-holes with the section of the plates themselves. It is perfectly obvious, that in perforating a line of holes along the edge of a plate, we must reduce its strength; and it is also clear, that the plate so perforated, will be to the plate itself nearly, as the areas of their respective sections, with a small deduction for the irregularities of the pressure of the rivets upon the plate; or in other words, the joint will be reduced in strength somewhat more than the ratio of its section, through that line, to the solid section of the plate. For example, suppose two plates, each 2 feet wide and three-eighths of an inch thick, to be riveted together with ten $\frac{3}{4}$-inch rivets. It is evident that out of 2 feet, the length of the joint, the strength of the plates is reduced by perforation to the extent of $7\frac{1}{2}$ inches; and here the strength of the plates will be to that of the joint as 9 : 6·187, which is nearly the same as the respective areas of the solid plate, and that through the rivet-holes, namely, as 24 : 16·5. From these facts it is evident that the rivets cannot add to the strength of the plates, their object being to keep the two surfaces of the lap in contact, and being headed on both sides, the plates are brought into very close union by the contraction or cooling of the rivets after they are closed. It may be said that the pressure or adhesion of the two surfaces of the plates would add to the strength; but this is not found to be the case, to any great extent, as in almost every instance the experiments indicate the resistance to be in the ratio of their sectional areas, or nearly so.

If we take the ultimate strength of the Yorkshire plates in Tables I. and II., it will be found that the mean breaking weight of eight specimens, each with a sectional area of ·46 inch, is 26,168, and the strength of the single joint*, of the same description of plates with an area of ·44 inch, is 18,591; this reduced gives the ratio of the

* I use the term single joint to distinguish it from the double riveted joint, which will be treated of hereafter.

strength as 25,030 : 18,591, or as 1 : ·742, the comparative strength of a single riveted plate of equal area through the line of the rivets. It will be observed that in this comparison the areas of the sections are nearly equal, and consequently there is a difference in strength between the solid part of the plate and that part where the perforations have been made of 32 per cent. The difference is considerable, but it probably arises from the narrowness of the specimen and the lateral strain induced by the position of the rivet, and the bending upwards of the end of the plates. From these facts I would infer that single riveting is weaker, and probably the loss of strength in this description of joint, including loss caused by the rivet-holes, is not less, under ordinary circumstances, than 40 per cent.

TABLE VII. Strength of riveted Plates.

| No. of exp. | Description of plates and mode of riveting. | Weight laid on in lbs. | Changes produced by weight. | Breaking weight in lbs. | Form of specimen and mode of fracture. | Remarks. |
|---|---|---|---|---|---|---|
| 30. | Plates ·22 inches thick, with three rivets, each $\frac{3}{4}$ inch diameter, AB 3 inches, lap $1\frac{1}{4}$ inch, area through rivet-holes ·4125 ..... | 14,839 | Bent into a straight line. | 16,603 | Fig. 5.   | The plates were sound, but two of the rivets were cut directly across. Rivets too weak. |
| 31. | Plates the same as before, overlap joints differing from the last in having three rivets $\frac{1}{4}$ inch diameter, forming an isosceles triangle, AB 3 inches ... | 18,667 | Joint apparently sound. | 22,699 | Fig. 6.   | With the first weight the plates became bent, so as to be in a direct line with the straining force. |
| | | 20,683 | Single rivet slightly opened. | | | |
| | | 22,027 | The other two rivets quite tight. | | | |
| 32. | Same as before ..... | 18,667 | Separation at end of plate, single rivet slightly opened. | Mean 23,035 | | Tore across the two rivet-holes, in the direction AB. |
| | | 22,027 | ..... | | | With 22,027 lbs. the single rivet seemed somewhat opened, but the other two seemed quite close. |
| | | 23,035 | Slightly drawn at the rivets ..... | 23,371 | | Plate torn across at the single rivet and one of the double ones. Rivets sound in this and the preceding experiment. |

In the first experiment the rivets (two in number) were evidently too weak, which caused them to shear directly across as if cut by a pair of scissors. In the next experiment the rivets were increased in number and size, which gave an excess of strength to the retaining power of the rivets and caused the plate to tear. If we take the mean of the experiments as respects the area of the rivets to that of the plates,

we find two half-inch rivets about the proportion, or the area of the rivets in the last experiments should have been ·4 inches, which is nearly equal to the area of the plate through the rivet-holes*.

TABLE VIII. Strength of riveted Plates.

| No. of exp. | Description of plates and mode of riveting. | Weight laid on in lbs. | Changes produced by weight. | Breaking weight in lbs. | Form of specimen and mode of fracture. | Remarks. |
|---|---|---|---|---|---|---|
| 33. | Plates same as before, ·22 inch thick, but wider, AB being 3½ inches, with three rivets ½ inch diameter, all in a line; lap 1¼ in. | 18,667 | Ends of plate much separated by bending. | 19,675 | Fig. 7.   | Though the ends of the plates were much separated, the light of a candle could not be seen through the line of the rivets. Plate torn across the rivet-holes. |
| 34. | Thicker plates ·26 in. thick, in other respects the same as in experiments 31, 32, Table VII.; lap 3 inches; rivets ½ inch diameter | 18,667 | Ends of plate separated, joints apparently good. | | Fig. 8.   | Tore across the two rivet-holes. |
| | | 22,699 | One plate much bent; joint apparently good. | 23,707 | Mean 25,387 | |
| 35. | Plates the same as the last..... | 21,019 | One end separated so far as to exhibit the single rivet. | 27,067 | | Tore across the two rivet-holes, where the breadth was 3½ inches. |

Here the section of the rivets is to that of the plates, through the line of the rivets, in the ratio of ·58 to ·44; had they been equal, it is probable that fracture would have taken place as soon by the rivets shearing as through the plates.

During the whole of the experiments on single riveted joints, it was observed that the ends of the plates under strain curled upwards on each side, and produced a diagonal strain upon the plates, which materially reduced the strength of the joint, as shown at *a* fig. 7.

This position gave an oblique direction to the forces, and caused the plate to break in some degree transversely through the rivet-holes. In order to obviate this defect, and prevent as much as possible a transverse strain upon the plates through the

* Subsequent experiments made for ascertaining the strength of rivets (*vide* experiments on the strength of rivets for the Britannia and Conway Tubular Bridges) fully corroborate these views, namely, that riveted joints exposed to a tensile strain are directly, or nearly so, as their respective areas, or in other words, the collective areas of the rivets are equal to the sectional area of the plate taken through the line of the rivets.

points in contact, the lap was increased and a third rivet introduced to keep down the ends of the plates.

The sketches in the 31st experiment, Table VII., and those in the 34th and 35th experiment, Table VIII., represent the form of joint, and the methods adopted for securing the plates in the direct line of the strain.

On comparing the breaking weights, it will be seen that the increased lap, with a rivet to keep down and retain the ends of the plates, gives a considerable accession of strength, and exhibits several important facts in connection with the construction of vessels exposed to severe pressure. But this becomes more apparent in the forthcoming experiments on the double-riveted joints.

TABLE IX. Strength of riveted Plates.

| No. of exp. | Description of plates and mode of riveting. | Weight laid on in lbs. | Changes produced by weight. | Breaking weight in lbs. | Form of specimen and mode of fracture. | Remarks. |
|---|---|---|---|---|---|---|
| 36. | Double-riveted plates ·22 inch thick; overlap joints riveted with five rivets of ¾ inch diameter each; lap 2 inches; AB = 3 inches in breadth ... | 16,115 | Plates bent in a right line between the points of tension. | | Fig. 9.   | Torn right across at the three rivet-holes, all the rivets being sound after fracture. |
| 37. | Plates the same as before, except that AB = 2⅞ inches in breadth ..... | 21,715 | Little or no alteration. | 24,043 } Mean 22,531 | | |
| | | 18,667 | Plates bent into right line, as before. | 21,019 } | | Broke as before; rivets all sound. |

In these experiments, as in those in the preceding Table, the area of the rivets is in excess, and hence follows rupture through the plates.

TABLE X. Strength of riveted Plates, &c.

| No. of exp. | Description of plates and mode of riveting. | Weight laid on in lbs. | Changes produced by weight. | Breaking weight in lbs. | Form of specimen and mode of fracture. | Remarks. |
|---|---|---|---|---|---|---|
| 38. | "Jump Joints." Plates the same as before, both riveted to an extra plate of the same thickness laid on one side of them; lap of extra plate over each end 2 inches; each plate riveted by five rivets ¾ inch diameter; AB = 3¼ inches. | 14,839 | Bent into straight line. | | Fig. 10.   | Tore across the rivet-holes. |
| | | 19,637 | All sound. | | | Rivets sound after fracture. |
| | | 21,691 | Rivets sound; plates much bent. | 23,371 } Mean 23,707 | | |
| 39. | Same as above..... | 18,667 | Bent nearly into a straight line. | | | |
| | | 22,699 | Rivets sound; joint apparently good. | 24,043 } | | Tore across as before; one rivet-head crooked. |

The same observations will apply to these experiments as to the last; the area of the rivets is in excess of that of the plates.

The system of double riveting exhibits several remarkable properties as regards strength, and the plates appear to retain their position under strain much better than single-riveted joints. These circumstances have induced a comparison of the results of the preceding experiments with those contained in Tables VII., VIII., IX. and X. The experiments in Tables VII. and VIII. give indications of increased strength by a slight enlargement of the lap and the introduction of a single rivet to keep down the end of the plate. In those experiments it was found that the additional rivet gave an increase of 26 per cent. over those obtained from the single rivets; a circumstance which suggested a further extension of the experiments, accompanied with a minute investigation of the parts, in order to ascertain their relative strengths, and the strongest form of joint.

The mean breaking weights of equal sections of single-riveted joints, as given in Table VI. and taken from nine experiments, are respectively as follows:—

| lbs. | |
|---|---|
| 20,127 | |
| 16,107 | |
| 18,982 | Mean . . 18,590 |
| 19,147 | |

giving a mean of 18,590 lbs. for the strength of single-riveted joints. Now in the second and third experiments, Table VII., with the rivets inserted in the shape of an isosceles triangle (which in fact is double riveting), and of equal sections to the specimens in Table VI., the mean breaking weight is 23,035, which gives an excess of 4445, or a ratio of 10 : 8 in favour of the experiments recorded in Table VII.

In the experiments (Table X.), the area of the section, taken through the line of the rivet-holes, is ·44 inch, or precisely equal to the section of the specimens experimented upon in Table VI., in which the mean breaking weight is 18,590 lbs. In these experiments the breaking weight is 23,707 lbs., which is rather more than that in Table IX., where the material had a smaller section, but having its dimensions exactly corresponding with the proportions given above. It therefore follows that in plates jointed with single rivets, the ratio of the strength of the single rivets is to that of the double-riveted joints as 8 to 10, the latter being one-fourth stronger.

It has been ascertained that it required a weight of 23,707 lbs. to tear asunder double-riveted plates, $3\frac{1}{8}$ inches wide and ·22 inches thick, with a flush joint, having a plate on the back and held together by five $\frac{3}{4}$-inch rivets on each side; the quantity of metal between the holes, in a direct line across the plate, being $·2 \times ·22 = ·44$ inch, which is the same transverse section as those operated upon in the first Table.

Now if we take the mean breaking weights of the riveted joints in Tables X. and VI. and compare them with the section of the plate itself as given in Table I., the areas being the same, we have for the tensile strength of plates—

| | Section of iron torn asunder. | lbs. |
|---|---|---|
| In Table I., solid plate . . . . . | ·44 | 25,400 |
| In Table X., double-riveted joints . . . . | ·44 | 23,707 |
| In Table VI., single-riveted joints . . . . | ·44 | 18,590 |

Assuming therefore the strength of the plates to be 1000, we have—

| | |
|---|---|
| For the strength of plates of equal sections . . . . . | 1000 |
| For the double-riveted joints . . . . . | 933 |
| For the single-riveted joints . . . . . | 731 |

We may safely assume these ratios as the comparative values of jointed plates of equal sections when acted upon by a force calculated to tear them asunder.

The correct value of the plates, computed from a sectional area taken through the rivet-holes, will therefore be to their riveted joints as 100, 93 and 73, or in round numbers as 10, 9 and 7.

In addition to a loss of nearly one-tenth in the double-riveted joints, and three-tenths in the single ones, it will be observed that the strength of the plates is still further reduced by the quantity of iron punched out for the rivets.

TABLE XI. Single riveted Plates.

| No. of exp. | Description of plates and mode of riveting. | Weight laid on in lbs. | Changes produced by weight. | Breaking weight in lbs. | Form of specimen and mode of fracture. | Remarks. |
|---|---|---|---|---|---|---|
| 40. | Plates same as before, ·22 inch thick, with overlap joint and double rivets; countersunk on one side; AB = 3½ inches; five rivets, each ⅝ diameter. ..... | 19,675 | Plates bent in a right line; doubtful whether the joint would hold water ..... | 23,707 | Fig. 11.   | By the word countersunk is understood a conical recess on one side of the plate to receive the head of the rivet, in order that it might not project beyond the surface of the plate.<br>Tore across the three rivet-holes. |
| 41. | Plates the same strength, but different from the last in having only ⅝-inch rivets all in a line; AB = 3½ ins. | 14,839 | Plates bent into a right line with the fixing..... | 16,351 | | In an unsuccessful experiment made before this upon plates precisely the same, and riveted in the same manner, they were torn across the rivet-holes in attempting to lay on 18,667 lbs.<br>Plates tore across the rivet-holes. |
| 42. | Same as last, except in not having the rivet-holes countersunk; lap 1½ inch; AB = 3½ inches ..... | 14,839 | Joint sound..... | 16,351 | | All the rivets on one side were cut in two in the middle, and the plates left sound. |

The results in the two last experiments, in the above Table, are identical as to strength. In the first, with the countersunk rivets, the plates were torn asunder, and in the latter the rivets appear the weakest, owing to the increased sectional area of the plates, which in the preceding experiment was reduced by countersinking the rivets.

In both experiments it will be observed that the strengths of the rivets are proportional to the strengths of the plates, their powers of resistance being equal, or nearly so. In forty-one experiments the sectional area of the rivets was to that of the plates as ·340 to ·347, that is, the sections were nearly equal; and in forty-two experiments as ·34 to ·44, which accounts for the nature of the fracture in both cases.

## Table XII. Strength of riveted Plates.

| No. of exp. | Description of plates and mode of riveting. | Weight laid on in lbs. | Changes produced by weight. | Breaking weight in lbs. | Form of specimen and mode of fracture. | Remarks. |
|---|---|---|---|---|---|---|
| 43. | Plates the same as before, their edges brought into contact, and each plate riveted by three rivets $\frac{3}{4}$ of an inch diameter, to a plate on each side of the joint, each external plate being half the thickness of the internal, or a little thicker; AB = $3\frac{1}{2}$ ins. | 19,879 | Sound; no alteration. | | Fig. 12. | Both side plates were torn across, and two of the rivets cut off. The sum of the thickness of the side plates was ·24 inch, the middle plates being ·22 inch thick. |
| | | 24,715 | ..... | 25,723 | | The middle plates were left sound. |
| 44. | Plate same as last ... | ..... | ..... | 21,255 | Mean 23,539 | Second experiment broken as before, the two outside plates torn off; all the rest sound. |
| 45. | Same as the last experiment, having thicker plates outside, each being ·15 inch thick. | 23,371 | Joint good ..... | 24,715 | Fig. 12 *a*. | Middle plate torn straight across the rivet-holes. All the rivets and both plates left sound. |
| 46. | Differing from the last only in having five rivets to each plate in double rows instead of three rivets $\frac{3}{4}$ diameter; AB = $3\frac{1}{2}$ inches ... | 23,371 | Joint sound..... | ..... | | Both outside plates torn across at the three rivets. |
| | | 25,387 | ..... | 26,059 | | |
| 47. | Same as the last ..... | 23,371 | Joint sound..... | | | Outer plate sound; torn across the two rivet-holes. |
| | | 24,715 | Slightly altered; joint good ..... | 27,403 | Mean 26,731 | Rivets sound; inner plate only torn. |

When the comparative merits of plates and their riveted joints were under consideration, it appeared desirable to repeat several of the experiments, particularly those which seemed to throw light upon their relative powers of resistance. I considered these experiments to be of importance, as they increased our knowledge, as respects the strength of the material, and also its properties in combination.

In ship-building these objects are of some value, as any reduction in the powers or parts of a vessel by imperfect construction, or misapplied material, might lead to serious error and even great risk to the safety of the ship.

Since the first use of iron for these objects, it has been the practice to countersink the heads of the rivets in order to present a smooth surface for the passage of the vessel through the water. This practice is in general use at my works at Millwall, and I believe the same methods are pursued at the establishment of Messrs. John Laird and Co., and others in different parts of the country. The introduction of this system of riveting caused a further extension of the experiments, in order to elucidate the various forms of joints given in the preceding Tables, and further to investigate the strength of the joint with a plate riveted on each side, which appears to be the strongest and best calculated to resist a tensile strain. This description of joint is seldom used in ship-building, but in order to render the experiments as perfect as

possible, it will be necessary to consider it in this paper with others of equal importance and probably of more general use.

The system of countersinking the rivets is only used when smooth surfaces are required; under other circumstances their introduction would not be desirable, as they do not add to the strength of the joint, but to a certain extent reduce it. This reduction is not observable in the experiments, but the simple fact of sinking the head of the rivet into the plate and cutting out a greater portion of metal, must of necessity lessen its strength, and render it weaker than the plain joint with raised heads. This must appear evident from the fact of the sectional area of the plate being diminished, and the consequent reduction of the heads of the rivets, which in this state are less able to sustain the effects of an oblique or transverse strain.

It is, however, satisfactory to observe that countersinking the heads of the rivets does not seriously injure the joint in its powers of resistance to a direct tensile force; but the rivets are liable to start when exposed to collisions or a strong impinging force, such as the sides of ships are frequently doomed to encounter.

On referring to experiments (Table XI.), the same results as to strength are obtained with the countersunk rivets as those with rounded heads; they are rather under the mean of the former experiments, but not more than is easily accounted for by the reduced section of the countersunk plates.

The joint with plates, riveted on each side, is seldom used, a circumstance which probably arises from its greater complexity of form and the danger which a treble thickness of plate would be subject to if used in boilers or vessels exposed to the action of intense heat. It is also inadmissible in ship-building, as the smooth surface requires to be maintained, and the greatest care observed in the formation of the outer sheathing to lessen the resistance of every part of the hull immersed in the water. In other respects the double-riveted plate is a strong joint, and in every case, where great strength is required, it may be used with perfect safety.

It will be unnecessary to go through a further comparison of the experiments, as sufficient data have already been furnished to enable us to calculate the force per square inch, and to resolve the whole into a general summary exhibiting the relative strengths—1st, of the plates; 2ndly, of the single- and double-riveted joints; and lastly, the ratio of the strengths as deduced from the whole series of experiments.

General summary of Results as obtained from the foregoing Experiments.

| | Cohesive strength of plates. Breaking weight in lbs. per square inch. | Strength of single-riveted joints of equal section to the plates, taken through the line of rivets. Breaking weight in lbs. per square inch. | Strength of double-riveted joints of equal section to the plates, taken through the line of rivets. Breaking weight in lbs. per square inch. |
|---|---|---|---|
| | 57,724 | 45,743 | 52,352 |
| | 61,579 | 36,606 | 48,821 |
| | 58,322 | 43,141 | 58,286 |
| | 50,983 | 43,515 | 54,594 |
| | 51,130 | 40,249 | 53,879 |
| | 49,281 | 44,715 | 53,879 |
| | 43,805 | 37,161 | |
| | 47,062 | | |
| Mean ... | 52,486 | 41,590 | 53,635 |

The relative strengths will therefore be,—

For the plate . . . . . 1000

Double-riveted joint . . . . . 1021

Single-riveted joint . . . . . 791

From the above, it will be seen that the single-riveted joints have lost one-fifth of the actual strength of the plates, whilst the double-riveted have retained their resisting powers unimpaired. These are important and convincing proofs of the superior value of the double joint, and in all cases where strength is required this description of joint should never be omitted.

On referring to the experiments contained in the separate tables, there will be found a striking coincidence in the facts tending to establish the principle of double riveting as superior in every respect to the general practice now in use of the single rivets. It appears, when plates are riveted in this manner, that the strength of the joints is to the strength of the plates of equal sections of metal as the numbers,—

1000 : 1021 and 791*.

In a former analysis it was 1000 : 933 and 731,

which gives us a mean of 1000 : 977 and 761

which in practice we may safely assume as the correct value of each. Exclusive of this difference, we must however deduct 30 per cent. for the loss of metal actually punched out for the reception of the rivets, and the absolute strength of the plates will then be, to that of the riveted joints, as the numbers 100, 68 and 46. In some cases, where the rivets are wider apart, the loss sustained is however not so great;

* The cause of the increase of strength in the double-riveted plates may be attributed to the riveted specimens being made from the best iron, whereas the mean strength of the plates is taken from all the irons experimented upon, some of inferior quality, which will account for the high value of the double-riveted joint. In ordinary cases and in practice it will therefore be safer to take the mean of the whole, viz.—

Strength of plates..... 100

Strength of double-riveting..... 97

And of single-riveting ..... 76

but in boilers and similar vessels, where the rivets require to be close to each other, the edges of the plates are weakened to that extent. In this estimate we must however take into consideration the circumstances under which the results were obtained, as only two or three rivets came within the reach of experiment: and again, looking at the increase of strength which might be gained by having a greater number of rivets in combination, and the adhesion of the two surfaces of the plates in contact, which in the compressed rivets by machine is considerable, we may fairly assume the following relative strengths as the value of plates with their riveted joints:—

| | |
|---|---|
| Taking the strength of the plate at . . . . . | 100 |
| The strength of the double-riveted joint would then be . . | 70 |
| And the strength of the single-riveted joint . . . . . | 56 |

These proportions may therefore in practice be safely taken as nearly the standard value of joints, such as used in vessels where they are required to be steam- or water-tight, and subjected to pressure varying from 10 to 100 lbs. upon the square inch.

Since the above was written, I have ascertained, on a recent visit to Bristol, that the large steam-ship* now building there is double-riveted, the plates being three-fourths of an inch thick over the bottom and bilge, and five-eighths thick up to the water-line. These plates are joined together with double rivets of 1 inch diameter, and inserted at distances of 3 inches apart. The proportions appear to be good; and conceiving the workmanship to be equally so, I should infer that this fine vessel would fairly establish the principle, that iron, in all the ramifications of ship-building, is an article of paramount importance to the war as well as to the mercantile navy.

In the pursuit of the foregoing inquiry, I was naturally led to the consideration of the best proportions and best forms of riveting plates together. I investigated this subject with great care, and from my own personal knowledge and that of others, I have collected a number of practical facts, such as long experience alone could furnish. From these data I have been enabled to complete the following Table, which for practical use I have found highly valuable in proportioning the distances and strength of rivets in joints requiring to be steam- or water-tight.

Table exhibiting the strongest forms and best proportions of riveted joints as deduced from the experiments and actual practice.

| Thickness of plates in inches. | Diameter of rivets in inches. | Length of rivets from the head in inches. | Distance of rivets from centre to centre in inches. | Quantity of lap in single joints in inches. | Quantity of lap in double-riveted joints in inches. |
|---|---|---|---|---|---|
| ·19=$\frac{3}{16}$ | ·38 | ·88 | 1·25 | 1·25 | |
| ·25=$\frac{4}{16}$ | ·50 | 1·13 | 1·50 } 6 | 1·50 } 6 | |
| ·31=$\frac{5}{16}$ | ·63 } 2 | 1·38 | 1·63 } 5 | 1·88 | |
| ·38=$\frac{6}{16}$ | ·75 | 1·63 } 4·5 | 1·75 | 2·00 } 5·5 | For the double-riveted joint, add two-thirds of the depth of the single lap. |
| ·50=$\frac{8}{16}$ | ·81 | 2·25 | 2·00 | 2·25 | |
| ·63=$\frac{10}{16}$ | ·94 } 1·5 | 2·75 | 2·50 } 4 | 2·75 } 4·5 | |
| ·75=$\frac{12}{16}$ | 1·13 | 3·25 | 3·00 | 3·25 | |

* The Great Britain steam-ship.

The figures 2, 1·5, 4·5, 6, 5, &c. in the preceding Table are multipliers for the diameter, length and distance of rivets, also for the quantity of lap allowed for the single and double joints. These multipliers may be considered as proportionals of the thicknesses of the plates to the diameter, length, distance of rivets, &c. For example, suppose we take three-eighth plates and required the proportionate parts of the strongest form of joint, it will be—

·375 × 2 = ·750 diameter of rivet, $\frac{3}{4}$ inch.
·375 × 4½ = 1·688 length of rivet, $1\frac{3}{4}$ inch.
·375 × 5 = 1·875 distance between rivets, $1\frac{3}{4}$ inch.
·375 × 5½ = 2·063 quantity of lap, 2 inches.
·375 × 5½ = 3·438 quantity of lap for double joints, $3\frac{1}{2}$ inches.

·75, 1·68, 1·87, 2·06 and 3·43 are therefore the proportionate quantities necessary to form the strongest steam- or water-tight joints on plates three-eighths of an inch thick.

In the preceding pages I have endeavoured to investigate almost every circumstance having a practical bearing on the question of the strength of rolled plates, and the best methods of uniting them together. In conclusion, I would venture a few remarks on the value and judicious use of this material, in its adaptation to ship-building, and other purposes to which it may be successfully applied. It is not my intention to enter into the question as to whether wood or iron be the preferable material, as a number of circumstances, such as cost, durability, &c., must be considered in order to form a correct decision.

I would however observe, that in ship-building alone, it appears from the facts already recorded, that iron is very superior in its powers of resistance to strain; it is highly ductile in its character, and easily moulded into any required form without impairing its strength. It is also stronger in combination than timber, arising from the nature of the construction, and the materials composing the iron ship become a homogeneous mass when united together, forming as it were a solid, without joints, and presenting as a whole the most formidable powers of resistance*. These are some of the properties which appear to distinguish iron from other materials, and which give it an ascendency of combined action, which cannot be obtained in the union of timber however ingeniously contrived. It moreover possesses the property of lightness along with strength; in fact, its buoyancy, strength and durability constitute the elements of its utility in the innumerable cases to which it may be applied. In ship-building it possesses other advantages over timber. Its hull is free from the

* Since the above was written we have had many examples of the enormous strength of iron ships, and amongst others we may instance an iron vessel which took the ground with nearly one-half of her length at the stern hanging over a shelf for a whole tide; another, the Vanguard iron steamer, which for several hours (under the action of a heavy surf) was beating upon sharp shelving rocks without going to pieces; and lastly, the Great Britain steam-ship, which was stranded in Dundrum Bay, and resisted the force of the winter storms for many months.

risk of fire; and in case of shipwreck, either on rocks or sand-banks, it will resist the heaviest sea, endure the severest concussion, and with proper attention to the construction, it may be the means of saving the lives of all on board. It moreover has the advantage of bulkheads, which, made perfectly water-tight, not only strengthen the vessel, but give greater security to it, and by a judicious arrangement in the divisions will float the ship under the adverse circumstance of a leak occurring in any one of the compartments. These are the qualities and powers of the iron ship; and I trust the present research into the strength and proportions of the material of which it is composed, will not only give increased confidence in its security, but will lead to an extension of its application in every branch of marine and mechanical architecture.

## PART III.

*Resistance of Wrought-iron Plates to Pressure by a Blunt Instrument at right angles to the surface of the Plate.*

Irrespective of the experiments made to determine the strength of wrought-iron plates and the relative strength of the joints by which they are united, the investigation would be incomplete if we omitted another inquiry of equal importance, namely, the resistance offered by plates to a crushing force, such as exhibited in the injuries received by vessels when stranded on rocks or taking the ground in harbours where the surfaces are uneven.

Almost every person connected with nautical affairs is acquainted with the nature of the injuries received by timber-built vessels when placed in circumstances affecting their stability, or when resting on hard and unequal ground, such as frequently occurs in tidal harbours at low water. Such a position is attended with danger under every circumstance; and in order to determine the relative values of the two materials, wood and iron, it was considered desirable to institute a similar class of experiments on both, and thus to afford the means of comparison between them. English oak, as the strongest and best material used for the construction of first class vessels, was selected for this purpose, and the results obtained from both are given, under circumstances as nearly similar as the nature of the experiment would admit. They are as follows.

In each of the experiments the plate was fastened upon a frame of cast iron, 1 foot square inside and 1 foot 6 inches outside, its breadth being 3 inches and thickness half an inch. The sides of the plates, when hot, were twisted round the frame, to which they were firmly bolted. The contraction, by cooling, caused it to be very tight, and the force to burst it was applied in the centre. This was done in order that the force might in some degree resemble that from a stone or other body with a blunt end pressing against the side or bottom of a vessel: a bolt of iron, terminating in a hemisphere 3 inches in diameter, had thus its rounded end pressed perpendicularly to the plate in the middle. The results are given in the following Tables.

TABLE XIII. Experiments to determine the Resistance of Plates of Wrought Iron to a force tending to burst them.

| No. of exp. | Description of plates. | Weight laid on in lbs. | Permanent indentation of plate. | Remarks. |
|---|---|---|---|---|
| | | | inch. | |
| 1. | Plate of the best Staffordshire iron ¼ inch thick. | 8,617 | ·3 | Plate not cracked. |
| | | 9,893 | ·35 | Plate not cracked. |
| | | 11,169 | ·5 | Crack on convex side 8 inches long. |
| | | 12,445 | ·6 | Crack on convex side 9 inches long; not opened on concave side. |
| | | 13,789 | ·7 | Hole through the plate about 1½ inch long, and ½ inch wide. |
| 2. | Plate of the same iron and the same thickness. | 9,893 | ·25 | Double crack on convex side 1 inch long. |
| | | 11,169 | ·34 | Double crack increased. |
| | | 12,445 | ·4 | |
| | | 13,789 | ·47 | |
| | | 16,477 | ·6 | Form of crack on convex side (⅛ inch wide). |
| | | 17,821 | ·65 | Not cracked through. |
| | | 19,769 | ..... | Cracked through. |
| 3. | Plate of the same iron ½ inch thick. | 18,523 | ..... | No crack. |
| | | 21,075 | ·33 | Incipient crack on convex side. |
| | | 22,787 | ·45 | Crack above-mentioned 4 inches long, forming a cross. |
| | | 25,923 | ·60 | Crack above, 6 inches long. |
| | | 29,059 | ·75 | Crack above, ½ inch wide. |
| | | 32,195 | ·80 | |
| | | 35,331 | ·97 | |
| | | 36,899 | 1·10 | No crack on concave side. |
| | | 37,519 | ..... | Plate cracked through. |
| 4. | Plate same as the last. | 21,219 | ..... | No crack. |
| | | 21,983 | ·35 | Slight crack on convex side. |
| | | 27,706 | ·47 | Form of crack on convex side. |
| | | 31,796 | ·7 | Form of crack increased. |
| | | 33,431 | ·75 | |
| | | 35,066 | ·83 | Form of crack 4 inches deep. |
| | | 36,701 | ·97 | Not cracked through. |
| | | 37,928 | ..... | Cracked through. |

In Plate LVIII. figs. 13 and 14, will be found representations of the fractures of the plates experimented upon in this Table.

From the above we obtain the strength of plates to resist rupture from pressure from a blunt body, or a ball 3 inches diameter.

| | lbs. | Mean. |
|---|---|---|
| In experiment 1, a plate one-fourth of an inch thick was burst by | 13,789 | 16,779 |
| In experiment 2, a plate one-fourth of an inch thick was burst by | 19,769 | |
| In experiment 3, a plate half an inch thick was burst by . . . | 37,519 | 37,723 |
| In experiment 4, a plate half an inch thick was burst by . . . | 37,928 | |

Here the strengths are as the depths, a half-inch plate requiring double the weight to produce fracture that had previously burst the quarter of an inch plate. In the succeeding experiments on oak timber, the powers of resistance follow the ratio of the squares of the depth, so that a wrought-iron plate of only one-quarter of an inch thick is able to resist a force equal to that required in the rupture of a 3-inch plank.

The experiments were made upon good English oak, of different thicknesses, and of the same width as the iron plates. The specimens were laid upon solid planks, 12 inches asunder, and by the same apparatus the rounded end of the 3-inch pin was forced through them as follows:—

Resistance of planks of timber to the entrance of a ball, 3 inches diameter, the planks being laid upon props 12 inches asunder; the object of the experiments being to burst them by pressing a pin, terminated by a hemispherical end, 3 inches diameter, through the centre of the plank, as was done with the plates of iron.

TABLE XIV.

| No. of exp. | Description of plank. | Weight laid on. | Remarks. |
|---|---|---|---|
| 1. | English oak, very dry and good, 11¼ inches broad, and 2¼ inches deep. | lbs. 16,115 17,235 | Indentation from hemisphere ⅛ inch deep; wood otherwise uninjured. Hole through the middle, 3 inches diameter nearly broke out, all the rest remaining sound. |
| 2. | English oak, rather green, 8 inches broad, 3 inches deep. | 18,941 | It bore 18,941 lbs. about ten minutes, and then exploded with violence, dividing into three parts, the middle one on which the pin rested being about an inch thick at the top, and ¼ an inch at the bottom. With a ton less weight there was a crack under the plank in the centre, and an indentation by the pin ⅛ inch deep on the upper side. Sap was driven out from the ends on the side nearest to the heart. |
| 3. | English oak plank, and dimensions same as in last experiment. | 12,445 16,925 | Sap driven out as in last experiment; plank without crack; indentation by the pressure about ⅛ inch. The plank split with bearing the pressure about ten minutes. |
| 4. | English oak from same plank as in experiment 2 and 3; breadth 8 inches, depth 1½ inch. | 4,532 | The plank broke by splitting. |
| 5. | English oak from same plank and same size as in the last experiment. | 4,280 | Broke by splitting diagonally. |

Taking the results of the four last experiments, which were on pieces from the same plank, we obtain—

| | lbs. | Mean. |
|---|---|---|
| Strength from planks 3 inches thick . . . . | 18,941 | 17,933 |
| Strength from planks 3 inches thick . . . . | 16,925 | |
| Strength from planks 1½ inch thick . . . . | 4,532 | 4,406 |
| Strength from planks 1½ inch thick . . . . | 4,280 | |

Here the strength to resist crushing follows the ratio of the square of the depth, as is found to be the case in the transverse fracture of rectangular bodies of constant breadth and span.

If we compare the foregoing results with the experiments performed by Mr. HODGKINSON on timber, it will be found that the strength of dry English oak to resist a crushing force is 4·24 tons to the square inch, whereas wrought iron, according to RONDELET, requires a pressure of about 31 tons per square inch, and with this weight it is reduced about one-sixteenth of its length. The resistance of wrought iron to a crushing force is therefore about seven and a quarter times greater than that of oak: and according to the experiments in the preceding Table, it appears that the resistance of wrought-iron plates to a force calculated to burst them, follows a different law to that of oak, the resistance of the former being directly as the depth and of the latter as the square of the depth. Reasoning from these facts, it may be interesting to know that in the use of timber, such as the oak sheathing of ships, the strength to ex-

ternal pressure increases in the ratio of the squares of its thickness; and, where great strength is required, it will be necessary, in the construction of vessels, to consider the nature of the service and the required thickness of the planks.

The same remarks will apply to vessels constructed of iron, computed from the formula deduced from the experiments. In a table of experimental results by Mr. Hodgkinson we have the mean force per square inch required for crushing timber of different kinds; and assuming Rondelet's experiments, which give 70,000 lbs. as the resistance per square inch of wrought iron, to be correct, we then have as the ratio of their respective powers of resistance as follows:—

Table XV.

| Specific gravities. | Description of timber used. | Resistance per square inch. | Resistance of wrought iron per square inch. | Ratio, the wood representing unity. |
|---|---|---|---|---|
| | | lbs. | lbs. | |
| 7·700 | Wrought iron ..... | ..... | 70,000 | |
| 0·560 | Yellow pine..... | 5375 | 70,000 | 1 : 13·02 |
| 0·540 | Cedar ..... | 5674 | 70,000 | 1 : 12·33 |
| 0·580 | Red deal ..... | 5748 | 70,000 | 1 : 12·16 |
| 0·640 | Birch ..... | 6402 | 70,000 | 1 : 10·93 |
| 0·660 | Sycamore..... | 7082 | 70,000 | 1 : 9·88 |
| 0·753 | Spanish mahogany ... | 8198 | 70,000 | 1 : 8·53 |
| 0·780 | Ash ..... | 8683 | 70,000 | 1 : 8·06 |
| 0·700 | Dry English oak ..... | 9509 | 70,000 | 1 : 7·36 |
| 0·980 | Box ..... | 9771 | 70,000 | 1 : 7·16 |

In addition to the relative resisting forces of the different kinds of timber above enumerated, will be found the specific gravities of each, which enables the reader to determine the comparative weights as well as strength of the different kinds of wood.

## PART IV.

In the preceding researches I have endeavoured to determine the value of iron chiefly in reference to its application for the purposes of ship-building. It now only remains to determine the best form and condition of another part of the structure, namely, the frames and ribs of vessels, also composed of iron. Some of the forms experimented upon indicate weakness, but certain modifications which have since been introduced, have given increased support to the bilge and sides of the ship, and greater powers of resistance to the outer sheathing. The beam shown at fig. 19, Plate LVIII., is probably one of the strongest and most suitable for the support of the decks, but it is inadmissible as a frame for receiving the exterior sheathing plates. These frames are generally formed of a plate with angle-irons along the edges on both sides, of which the annexed sketch are sections. *a*, *a*, &c. represents a portion of the outside plates; *b*, *b* the angle-iron frames or ribs, which vary from 18 to 24 inches asunder, according to the position in the direction

Fig. 15.



of the length of the ship; *c*, *c*, angle-iron of the same strength is riveted along the edge of each rib for the purpose of stiffening the sides of the ship and giving increased resistance to those parts, also to receive interior plates, some of which, in large vessels, are riveted diagonally to the interior angle-irons *c*, *c*, &c., forming stringers and braces from the kelsons round the bilge to the upper decks.

Other kinds of frames might be used with double angle-iron, as shown at *d*, *d*, &c. in the annexed sketch, but they are more expensive, and from the increased complexity of construction, the extra strength obtained does not compensate for the difference of cost. Altogether, the frames recorded in fig. 15 have come into general use as the most effective and easy of construction. Those experimented upon were of different kinds, as shown in Plate LVIII. fig. 17, 18, &c., and in sections given in the Tables, and from which the following results were obtained:—

Fig. 16.




TABLE XVI. Experiments to ascertain the strengths of uniform wrought-iron beams of different forms to support the sides and other parts of vessels, the beams having their ends placed upon props and being loaded in the middle.

| No. of exp. | Description and form of the beam. | Weight laid on middle. | Deflections with these weights. | Breaking weight of the beam of 7 feet between the supports. | Weight of the beam of 7 feet 6 inches long. | Oak beams. Side of square of oak beams of equal strength with the iron one. | Oak beams. Weight of such beams of 7 feet 6 inches long and specific gravity 900. | Remarks. |
|---|---|---|---|---|---|---|---|---|
| | | lbs. | | lbs. | lbs. | inches. | lbs. | |
| 1. | Beam formed from two 2½ angle-irons, riveted together with rivets 6 inches asunder, and a plate a ¼ inch thick riveted to the back, with rivets 4 inches asunder. Distance between the supports 7 feet, and whole length 7 feet 6 inches, its weight being 109 lbs. Dimensions of section. Thickness. AB = 5 inches. CD = 2·6 inches. *aa* = ·5 inch. *bb* = ·56 inch. *cc* = ·64 inch. *ee* = ·25 inch. The part C was downwards during the experiment, the weight being laid upon the part D. | | | 3355 | 109 | 3·6324 | 38·65 | The weight 3355 lbs. was laid on at once, and the beam almost immediately sunk with it; a weight something less would have done it. |
| 2. | The beam last used, cut in two; distance between supports 2 feet 3 inches; vertical rib downwards, that it might be stretched as before; weight of 3 feet 9 inches = 54 lbs. | 4,039<br>5,383<br>6,055<br>6,727<br>7,399<br>7,735 sunk | ·18<br>·30<br>·43<br>·64<br>·88<br>..... | 2486 | 109 | 3·287 | 31·80 | With 7735 lbs. it sunk, by stretching and tearing at a rivet-hole. |
| 3. | The other half of the beam (exp. 1.) cut in two. Distance between the supports 2 feet 3 inches; weight of 3 feet 9 inches = 55 lbs.; vertical rib upwards thus, ⊥ that fracture might take place by the compression of that rib. | 4,039<br>5,383<br>6,055<br>6,727<br>7,399<br>8,071<br>8,743<br>9,415<br>10,087<br>10,423<br>10,759 sunk | ·17<br>·23<br>·26<br>·34<br>·47<br>·63<br>·85<br>1·10<br>1·95<br>2·90<br>..... | 3458 | 109 | 3·6692 | 39·44 | With 10,759 lbs. it sunk; the vertical rib becoming twisted. |

All the beams experimented upon in the foregoing Table are shown in view and in section, Plate LVIII. figs. 17 and 18. In the first experiment the beam was 7 feet between the supports, but having yielded to the first weight, 3355 lbs., laid on, it was subsequently cut in two, as shown in the drawings above referred to. In experiment 2, it will be observed that a frame of this form is weak, arising from the deficiency of material on the lower side of the rib formed by angle-iron, which, yielding to a tensile strain, becomes elongated in the act of bending, and would thus deflect through a considerable space before actual fracture took place. Reversing the other part of the beam with the broad flange downwards it carried more weight, but ultimately sunk under a load of 10,759 lbs., being in the ratio of 10 : 7 in favour of the beam with the rib upwards.

These experiments, when reduced to 7 feet between the supports, gave nearly the same proportion, viz. nearly as 34 : 24. They are however all weak, arising almost exclusively from want of material on the top edge of the ribs, and a due proportion in the construction of the beam.

TABLE XVII. Experiments on Wrought-iron Beams (continued).

| No. of exp. | Description and form of the beam. | Weight laid on middle. | Deflections with these weights. | Breaking weight of the beam of 7 feet between the supports. | Weight of the beam of 7 feet 6 inches long. | Oak beams. Side of square of oak beams of equal strength with the iron one. | Oak beams. Weight of such beams of 7 feet 6 inches long and specific gravity 900. | Remarks. |
|---|---|---|---|---|---|---|---|---|
| | | lbs. | | lbs. | lbs. | inches. | lbs. | |
| 4. | Beam differing from that in exp. 1 only in being of greater strength, this beam being formed of two 3-inch angle-irons, riveted as before to a plate a ¼-inch thick. Distance between the supports 7 feet; weight of the beam 7 feet 6 inches long, 167½ lbs.; vertical rib downwards ⊤. | 3,355 | ·40 | | | | | After bearing the weight 7399 lbs. a short time the beam became cracked at a rivet-hole and sunk. From the experiments of BUFTON upon green oak, the side of a square beam of equal strength would be 4·558 inches, and its weight 708 lbs. |
| | | 4,711 | ·62 | | | | | |
| | | 5,383 | ·82 | | | | | |
| | | 5,719 | ·98 | | | | | |
| | | 6,055 | 1·12 | | | | | |
| | | 6,391 | 1·30 | | | | | |
| | | 6,727 | 1·87 | | | | | |
| | | ..... | 1·92 | | | | | |
| | | 7,063 | 2·29 | | | | | |
| | | 7,399 | 3·25 | 7399 | 167·5 | 4·7281 | 65·49 | |
| 5. | Half the beam used in exp. 4, now 3 feet 9 inches long, and weighing 82½ lbs. Distance between supports 3 feet 6 inches; vertical rib downwards. | 4,039 | 0·85 | | | | | |
| | | 7,399 | 0·25 | | | | | |
| | | 10,759 | 0·43 | | | | | |
| | | 11,431 | 0·53 | | | | | |
| | | 12,103 | 0·65 | | | | | |
| | | 12,439 | broke at a rivet-hole. | 6219 | 1675 | 4·462 | | |
| 6. | The other half of the beam in exp. 4, weighing 85 lbs.; length 3 feet 6 inches. Distance between the supports 2 feet 3 inches; rib upwards ⊥. | 8,304 | 0·12 | | | | | |
| | | 12,392 | 0·24 | | | | | |
| | | 16,480 | 0·75 | | | | | |
| | | 18,115 | sunk, the vertical rib being twisted. | 5823 | 1675 | 4·3653 | 55·83 | |

The whole of the experiments herein recorded are of the same description as the last, with the exception of the beam being composed of thicker angle-iron, and consequently rendered much stiffer and stronger than those first experimented upon. This increased stiffness reversed the resisting powers of the beam, when taken at a 7-feet

span, in the ratio of 6 : 5 in favour of the first position with the rib downwards. For plans and sections of these beams see Plate LVIII. fig. 18.

TABLE XVIII. Experiments on Wrought-iron Beams (continued).

| No. of exp. | Description and form of the beam. | Weight laid on middle. | Deflections with these weights. | Breaking weight of the beam of 7 feet between the supports. | Weight of the beam of 7 feet 6 inches long. | Oak beams. Side of square of oak beams of equal strength with the iron one. | Oak beams. Weight of such beams of 7 feet 6 inches long and specific gravity 900. | Remarks. |
|---|---|---|---|---|---|---|---|---|
| | | lbs. | | lbs. | lbs. | inches. | lbs. | |
| 7. | Solid wrought-iron beam, 4 feet 2 inches long, weighing 23 lbs., placed upon props 4 feet asunder; vertical rib upwards. Form and dimension of section.  Thickness at a = ·24 b = ·29 c = ·41 d = ·36 AB = 2·50 CD = 2·85 | 1394<br>1932<br>2470<br>2739<br>3008 | ·135<br>·24<br>·59<br>·90<br>1·35 | 1790 | 41·4 | 2·9461 | 25·43 | With 3008 lbs. the elasticity was entirely destroyed, and a like additional weight would have destroyed the form of the beam. |
| 8. | Same beam rendered straight, and turned with its rib downwards ⊤. | 1394<br>1932<br>2470<br>2739<br>3008<br>3142 | ·17<br>·25<br>·66<br>1·22<br>2·20<br>sunk | 1870 | 41·4 | 2·9894 | 26·18 | |
| 9. | Solid beam, same form as before; length 5 feet ⅝ inch; weight 25½ lbs. Distance between supports 4 feet; rib upwards thus. See fig. to experiment 7. Thickness at a = ·23 b = ·30 c = ·40 d = ·33 AB = 2·05 CD = 2·95 | 1394<br>1932<br>1526<br>2201<br>2335<br>in a few minutes | ·30<br>·86<br>1·19<br>1·59<br>2·04<br>2·13 | 1334 | 37·6 | 2·671 | 20·90 | After bearing the weight, 2335 lbs., it had taken a permanent set, or flexure = 1·71 inch, and would have sunk more if it had not been unloaded. |
| 10. | Same beam rendered straight and turned upside down thus ⊤. Distance between supports 4 feet. | 1394<br>1932<br>2201<br>2335<br>in a minute<br>2469 | ·27<br>·51<br>1·01<br>1·57<br>1·60<br>2·50<br>..... | 1411 | 37·6 | 2·7215 | 21·70 | After bearing 2469 lbs. it was unloaded, as a little additional weight would have destroyed its form. |

The experiments in this Table were made on solid ⊤ iron, and indicate nearly the same proportions, as respects their strength, as the beams composed of a plate and double angle-iron riveted together. The whole of these beams appear to be defective in form, and are therefore not calculated to sustain a severe transverse strain. To attain the section of greatest strength, it is probable a different form would be required, as well as a different proportion of the parts, such as in the annexed figure with a double flange*.

* Since the experiments herein recorded were made, others have been instituted on some deck-beams by Mr. KENNEDY of Messrs. BURY, CURTIS and KENNEDY, Liverpool, the particulars of which are inserted in the Appendix.

## Table XIX. Experiments on Wrought-iron Beams (continued).

| No. of exp. | Description and form of the beam. | Weight laid on middle. | Deflections with these weights. | Breaking weight of the beam of 7 feet between the supports. | Weight of the beam of 7 feet 6 inches long. | Oak beams. Side of square of oak beams of equal strength with the iron one. | Oak beams. Weight of such beams of 7 feet 6 inches long and specific gravity 900. | Remarks. |
|---|---|---|---|---|---|---|---|---|
| | | lbs. | | lbs. | lbs. | inches. | lbs. | |
| 11. | Beam of wrought iron, formed of two bars (nearly equal), whose section is riveted together; length of the beam 4 feet 2 inches; its weight 44 lbs. 5 oz. Distance between the supports 4 feet. Dimensions of section. AB = 2·86 inches. Mean thickness of AB = ·33 inch. EF = 3·70 inches. | 4,195 | 0·75 | | | | | |
| | | 7,465 | 0·148 | | | | | |
| | | 10,735 | 0·22 | | | | | |
| | | 10,735 laid on again. | ..... | ..... | ..... | ..... | ..... | After bearing the weight 10,735 lbs., the beam had taken a set = ·06. Pieces of wood were driven tightly in between the ribs AB, CD, at each side of the beam in *the middle*, to prevent the load laid on it there from deranging its form. |
| | | 14,005 | 0·24 broke | 8336 | 79·76 | 4·9199 | 70·91 | The beam broke by the bottom rib being torn asunder, preceded by one of the bars cracking at a rivet-hole. |

The above is probably the strongest form of beam, if duly proportioned, by adapting the material to a balance of the two opposing forces of extension and compression.

## Table XX. Experiments on Wrought-iron Beams (continued).

| No. of exp. | Description and form of the beam. | Weight laid on middle. | Deflections with these weights. | Breaking weight of the beam of 7 feet between the supports. | Weight of the beam of 7 feet 6 inches long. | Oak beams. Side of square of oak beams of equal strength with the iron one. | Oak beams. Weight of such beams of 7 feet 6 inches long and specific gravity 900. | Remarks. |
|---|---|---|---|---|---|---|---|---|
| | | lbs. | | lbs. | lbs. | inches. | lbs. | |
| 12. | Beam of wrought iron composed of an uniform vertical rib (7 inches deep and 7 feet 6 inches long) with two 2-inch angle-irons riveted to both top and bottom of the rib; rivets 4 inches asunder; weight of beam 161½ lbs. Distance between the supports 7 feet. Dimensions of section. CD = 7 inches. AB = 4·5 inches. EF = 4·5 inches. Mean thickness of AB = ·28 inch. EF = ·30 inch. Plate GH = ·25. | 4,216 | ·10 | | | | | |
| | | 8,304 | ·18 | | | | | |
| | | 16,480 | ·25 | | | | | |
| | | 18,667 | ·36 | | | | | |
| | | 22,027 | ·52 | | | | | |
| | | in five minutes | ·54 | 24,379 | 161½ | 7·0358 | 145·03 | |
| | | 24,379 | sunk | ..... | ..... | ..... | ..... | With the weight 24,379 lbs. the top ribs of the beam became twisted. |
| 13. | Same beam rendered straight and uniform; experiment 12 repeated. | 16,115 | ·29 | | | | | |
| | | 18,355 | ·36 | | | | | |
| | | 19,475 | ·42 | | | | | |
| | | 20,595 | ·51 | | | | | |
| | | 21,715 | sunk | 21,715 | 161½ | 6·7695 | 134·26 | The beam was heated by the smiths, and when reduced to its original form, it was allowed to cool gradually. With 21,715 lbs. it became bent, towards the wall, in a direction in which it was slightly drawn by the lever; ribs not twisted as before. It bore the weight a minute or two before giving way. |

This experiment shows the superior quality of wrought-iron beams in giving timely notice before fracture; it further exhibits weakness on the top sides of the beams, a circumstance requiring great attention in their construction, which in some recent experiments, instituted for attaining the section of greatest strength, have been strikingly developed*.

In the preceding experiments, we have endeavoured to compare the strengths, as well as the weights of the beams or frames which form the ribs of ships. As regards the strengths with equal weights, it is in favour of oak; but the circumstance of the fastenings by rivets in the sheathing being so much superior to those of timber, the iron ship-builder is enabled to dispense with one-half the number of frames, and consequently a great reduction of weight is effected and more strength obtained in the vessel as a whole, than could possibly be accomplished in the timber-built ship, however ingenious the construction or the arrangement and distribution of the material. The very act of caulking the joints of a wooden vessel has a tendency to loosen the fastenings, whereas, in the iron ship, there are no actual joints, for the whole being bound together *en masse*, the same, or nearly the same, strength is obtained as if the whole ship were composed of solid plates and ribs.

The best sectional form of beams for the decks of ships is probably that exhibited in Table XX., which, along with the box beam of the annexed form for supporting the shafts and paddle-boxes of steamers, is that generally used in the construction of vessels of this description. Other forms have been adopted, particularly those suggested by Mr. KENNEDY of Liverpool, alluded to in the Appendix.

Having carefully investigated the different properties of wrought iron in its varied forms of construction, and conceiving that the results obtained from the experiments may be useful in a variety of circumstances connected with the useful arts, I have endeavoured to collect them in the abstract, in order that the practical builder and engineer may the more readily ascertain the comparative value of the different forms of beams, the properties of the material, and their adaptation to any particular construction in which he may be engaged. Should further information be required, we must then refer to the experiments, in which will be found the facts more in detail, and which are probably better calculated to satisfy the inquiring mind and to effect that conviction essential to success.

I have not attempted any inquiry into the laws of oxidation, the adhesion of barnacles and marine vegetation, and the means necessary to prevent such evils. This is a subject which does not come within the province of the present inquiry, and more properly belongs to that of the chemist. I would however briefly notice, that in the whole of my experience I have had little to complain of from the effects of oxidation, as that destructive process, as regards iron, appears to be greatly mitigated, if not almost suspended, by constant use, and under the influence of vibratory action the operation appears to be rendered nugatory, if it does not entirely cease, and that

* See my work on the Construction of the Britannia and Conway Tubular Bridges.

under circumstances exceedingly difficult to explain. This is an investigation not unworthy the attention of some of our best chemists, to whom the causes may be known, but which are at present, as far as I know, unaccounted for. For example, I may mention that an iron ship, if kept constantly in use, or nearly so, will last for a number of years exposed to all the changes of weather and temperature without any sensible appearance of decay. The same may be said of iron rails, over which are passing daily such enormous weights, and at such velocities as almost to neutralize the action of the elements. All these are striking examples of the durability of wrought iron, which may be considered as an important element of its security, and a recommendation for its extended application. There is another circumstance in connection with this subject to which it may be necessary in this place to advert, and that is the effect which a long continuance in salt water has upon the hull of an iron ship. It is well known that a long immersion of cast iron in the sea will convert it into plumbago, and that a similar process with malleable iron, from its contact with the saline particles of the ocean, produces oxidation; and in case the immersions were long continued, the effects of this destructive process might endanger the safety of the ship. As yet we have not had sufficient evidence of its effects to enable us to come to any definite conclusion, but it is not improbable that an occasional visit to harbours of fresh water may mitigate, if it does not entirely neutralize, the injurious effects which the material is likely to sustain. With these observations, which I offer with diffidence, I now beg to direct attention to the abstracts as deduced from the experiments.

*Abstract of Results as obtained from the experiments.*

In Part I. of this inquiry we have endeavoured to show that 50,000 lbs. per square inch is the mean breaking weight of iron plates, whether torn asunder in the direction of the fibre or across it; and we have also shown that the tensile strength of different kinds of timber drawn in the direction of the fibre varies in a given ratio to that of iron: the timber in this comparison being represented by unity, we have the following ratio of strength:—

| | Timber : | Iron. |
|---|---|---|
| Ash as . . . . . | 1 : | 2·94 |
| Teak as . . . . . | 1 : | 3·33 |
| Fir as . . . . . | 1 : | 4·16 |
| Beech as . . . . . | 1 : | 4·34 |
| Oak as . . . . . | 1 : | 5·00 |

These, for practical purposes, may be taken as a fair measure of the strength of the different woods as compared with that of iron plates.

It has been shown that wrought-iron plates, when riveted together, lose a considerable portion of their strength, as may be seen by the experiments in Part IV., where the plates, by their union with each other, lose by the ordinary process of riveting 44 per cent., and by the best mode of riveting 30 per cent. This should not however

create serious alarm, as the loss of strength is almost entirely obviated by the new process of riveting used in the bottom of the Britannia and Conway Tubular Bridges*; and it should also be observed that in timber the same injuries are sustained by splicing or any other method of forming the joints as are here exhibited in the riveting of iron plates. The two processes, that of riveting (according to the method used in the experiments) and splicing, when intended to resist a tensile strain, must therefore be considered analogous, and the comparison under such circumstances will nearly follow the same law as regards a diminution of strength.

In this section of the inquiry the results obtained from the experiments indicate a loss in the joints as compared with the solid plate, as the numbers 100, 70 and 56, viz.—

| | |
|---|---|
| For the solid plate . . . . . | 100 |
| For the double-riveted joint . . . . . | 70 |
| For the single-riveted joint . . . . . | 56 |

which numbers may be considered as a fair average value of the strengths of the different parts of vessels constructed in this manner.

Part V. exhibits the strength of plates to resist vertical pressure from a blunt instrument, which was forced through them for the purpose of ascertaining their comparative powers of resistance with oak timber, placed under circumstances precisely similar and subjected to the same force. The results are interesting, as the iron plates appear to follow a different law in their resistance to pressure to that of oak, the strength being as the depth or thickness of the plates in the first case, and as the squares of the depth in the second. The resistances are therefore in the ratio of 1 : 12, the iron being 12 times stronger than oak.

In Part IV. we have some curious facts illustrative of the necessity and value of experimental research. In the earlier experiments of the inquiry it is evident, that angle and T iron beams or frames are not the best, as regards form, to resist a transverse strain. In every case they are weak, and although exceedingly useful, and in fact indispensable for many purposes of construction, they are nevertheless not calculated to resist strain in the form of beams or girders. These defects I have endeavoured to obviate by the introduction of beams with double flanges formed of a body plate and riveted angle-irons at the top and bottom. All these latter constructions may however be left with safety to the practical engineer†.

The strengths of nearly the whole of these beams have been mathematically investigated by Mr. Tate, to whose friendship and analytical research I am indebted for the annexed mathematical inquiry into the different forms of the wrought-iron beams which have been experimented upon. To the mathematician this part of the subject will be the more interesting, as the utmost care has been observed in the measurements

* See my process of chain-riveting as exhibited in the lower sides of the Britannia and Conway Tubular Bridges, where the injuries above enumerated are entirely obviated.

† For a more elaborate inquiry into the strengths of wrought-iron beams, see my work on the Britannia and Conway Bridges.

and exact proportions of the parts, in order to obtain the necessary formula for calculating the strength of beams and frames of this description.

## FORMULÆ RELATIVE TO THE BEAMS IN THE FOREGOING EXPERIMENTS.

### *Beams with a Single Flanch.*




Let ABF be a section of a beam having a single flanch AB*kh*, the material being symmetrically distributed with respect to the vertical line EF. Let *hacd* and DFC be parallel to AB; *cr* and *kd*C parallel to EF. Put EB=EA=$e$, CB=DA=$e_1$, $ac$=Fr=$t$, B$k$=A$g$=$t_1$, E$a$=B$d$=$t_2$, F$e$=F$n$=$t_3$, area section AB$cenhg$=A, and the distance of the centre of gravity of this section from the edge $ne$=X.

### *To find the Position of the Neutral Axis.*

Assuming the material to be perfectly elastic, the neutral axis will be in the centre of gravity of the section. Hence we have, by calculating the moments with respect to the line DC,

$$\mathrm{A}\times\mathrm{X}=ee_1^2-(e_1-t_3)^3(e-t)-\frac{1}{3}(e_1-t_3)^3(t-t_3)-(e-t)(t_2-t_1)\left(e_1-\frac{2}{3}t_3-\frac{1}{3}t_1\right),$$

$$\therefore\ \mathrm{X}=\frac{3ee_1^2-(e_1-t_3)^2(3e-2t-t_3)-(e-t)(t_2-t_1)(3e_1-2t_3-t_1)}{3\mathrm{A}}, \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (1.)$$

which expresses the distance of the neutral axis from the edge $ne$, where

$$\mathrm{A}=(t+t_3)(e_1-t_2)+(t_1+t_3)(e-t)+2tt_3 \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (2.)$$

### *To find the Moments of Rupture.*

Let I = the moment of inertia of the section about the neutral axis.

$\mathrm{I}_1$= the moment of inertia of the section about DC.

W= the breaking weight of the beam.

$l$= the distance between the supports.

S= the force per square inch of the material opposed to extension or compression, as the case may be, at the thin edge of the beam.

Taking DC as the axis,—

$\mathrm{I}_1$= moment inertia ABCD − 2 moment inertia $r$C$dc$ − 2 moment inertia $erc$ − 2 moment inertia $cdk$.

Now, moment inertia ABCD=$\frac{2}{3}ee_1^3$,

2 moment inertia $r$C$dc$=$\frac{2}{3}(e-t)(e_1-t_3)^3$,

2 moment inertia $erc$=$\frac{1}{6}(t-t_3)(e_1-t_3)^3$,

2 moment inertia $cdk$=$\frac{1}{6}(e-t)\{(e_1-t_1)^3-3(e_1-t_3)^3+(e_1-t_1)(e_1-t_3)(2e_1-t_1-t_3)\}$.

Substituting these values and reducing, we find

$$I_1=\frac{1}{6}[4ee_1^3-(e_1-t_2)^3(e-t_2)-(e-t)(e_1-t_1)\{(e_1-t_1)^2+(e_1-t_2)(2e_1-t_1-t_2)\}]. \quad . \quad (3.)$$

Also (Moseley's Engineering, p. 82) we have

$$I=I_1-AX^2. \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (4.)$$

Moreover, by the formula of rupture,

$$\frac{Wl}{4}=\frac{SI}{X},$$

$$\therefore \quad S=\frac{WlX}{4I} \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (5.)$$

Taking the data of Table XVI., we have

$$e=2{\cdot}5,\ e_1=2{\cdot}6,\ t=\cdot32,\ t_1=\cdot35,\ t_2=\cdot25,\ t_3=\cdot42\ ;$$

therefore, by equation (2.),

$$A=(\cdot32+\cdot25)(2{\cdot}6-\cdot42)+(\cdot35+\cdot42)(2{\cdot}5-\cdot32)+2\times\cdot32\times\cdot42=3{\cdot}19.$$

By equation (1.),

$$X=\{3\times2{\cdot}5\times2{\cdot}6^2-(2{\cdot}6-\cdot42)^3(7{\cdot}5-\cdot64-\cdot25)-(2{\cdot}5-\cdot32)$$
$$\times(\cdot42-\cdot35)(7{\cdot}8-\cdot84-\cdot35)\}\div3\times3{\cdot}19=1{\cdot}91,$$

which is the distance of the neutral axis from the edge *ne* of the beam.

By equation (3.),

$$I_1=\frac{1}{6}[4\times2{\cdot}5\times2{\cdot}6^3-(2{\cdot}6-\cdot42)^3(2{\cdot}5-\cdot25)-(2{\cdot}5-\cdot32)(2{\cdot}6-\cdot35)$$
$$\times\{(2{\cdot}6-\cdot35)^2+(2{\cdot}6-\cdot42)(5{\cdot}2-\cdot35-\cdot42)\}]=13{\cdot}375.$$

By equation (4.),

$$I=13{\cdot}375-3{\cdot}19\times1{\cdot}91^2=1{\cdot}738.$$

By equation (5.),

$$S=Wl\times\frac{1{\cdot}91}{4\times1{\cdot}738}\text{ lbs.}=Wl\times\frac{1{\cdot}91}{15568}\text{ tons.}$$

In experiment 1, $W=3409$, $l=7\times12=84$,

$$\therefore \quad S=\frac{3409\times84\times1{\cdot}91}{15568}=35\text{ tons.}$$

Let $X_1=$ the distance of the neutral axis from the edges AB, and $S_1=$ the force per square inch opposed to extension or compression, as the case may be, at the edge AB, then

$$X_1=2{\cdot}6-1{\cdot}91=\cdot69,$$

and

$$S_1=\frac{X_1}{X}.S=\frac{\cdot69\times35}{1{\cdot}91}=12{\cdot}6\text{ tons.}$$

In experiment 2, $W=7735+18=7753$, and $l=27$,

$$\therefore \quad S=\frac{7753\times27\times1{\cdot}91}{15568}=25{\cdot}6\text{ tons,}$$

and

$$S_1=\frac{\cdot69\times25{\cdot}6}{1{\cdot}91}=9{\cdot}3\text{ tons.}$$

In experiment 3, $W=10759+18=10777$, $l=27$,

$$\therefore\ S=\frac{10777\times 27\times 1{\cdot}91}{15568}=35 \text{ tons},$$

and $S_1=12{\cdot}6$ tons.

Taking the data of Table XVIII., experiments 7 and 8,

$$e=1{\cdot}425,\ e_1=2{\cdot}5,\ t={\cdot}2,\ t_1={\cdot}36,\ t_2={\cdot}4,\ t_3={\cdot}12.$$

Hence we find from equation (2.), $A=1{\cdot}762$; from equation (1.), $X=1{\cdot}86$, and $\therefore\ X_1=2{\cdot}5-1{\cdot}86={\cdot}64$; from equation (3.), $I_1=6{\cdot}943$; and from equations (4.) and (5.), $S=Wl\times{\cdot}00021$ tons.

In experiment 7, $W=3008+11=3019$, $l=48$,

$$\therefore\ S=3019\times 48\times{\cdot}00021=30{\cdot}4 \text{ tons},$$

and

$$S_1=\frac{{\cdot}64\times 30{\cdot}4}{1{\cdot}86}=10{\cdot}4 \text{ tons}.$$

In experiment 8, $W=3142\times 11=3153$, $l=48$,

$$\therefore\ S=3153\times 48\times{\cdot}00021=31{\cdot}7 \text{ tons},$$

and

$$S_1=\frac{{\cdot}64\times 31{\cdot}7}{1{\cdot}86}=10{\cdot}9 \text{ tons}.$$

*Observations.*—The value of S determined from experiment 1, is the resistance of the material to extension, whereas the value of S determined from experiment 3, is the resistance to compression. Hence it appears, that in beams of this form and *thickness of plates* the resistance to extension is equal to that of compression. The same observation applies to the values of S determined from experiments 7 and 8; and the same law also holds true for experiments 9 and 10.

These calculations further show, that the material in these beams is not properly distributed, for while the thin side of the beam is about to undergo rupture, the broad side has not attained one-half of the tension or compression, as the case may be, which it is capable of sustaining.

It will also be observed, that the resistance of the material at the thin side, as indicated by these calculations, is greater than what it would be under ordinary circumstances, viz. about 25 tons per square inch. This apparent discrepancy may be explained as follows:—as a beam of wrought iron approaches the limit of tension it undergoes an accelerated rate of elongation, even while the cohesion of the material remains unimpaired*. Now this unusual extension of the particles in the lower laminæ (in a beam having a single flanch placed upwards) allows a succession of particles in the higher laminæ to come into full tensile strain, so that the particles at the lower edge of the beam apparently attain a tensile strain greater than they would have under ordinary circumstances. And it may be presumed, that a similar law obtains in reference to the compression of wrought-iron beams. Hence it follows, that all calculations which assume the tensile or compressive forces, in beams of this form, at the edges of the beam equal to what they are under ordinary circumstances, must lead to erroneous results.

* See remarks on experiment 2, p. 720.

It may be further worthy of remark, that experiments 2 and 3, 8 and 7, show that when the flanches of the beams are placed upwards the deflections are considerably greater than what they are when the flanches are placed downwards; thus in experiments 2 and 3, we have

| Weight on the beams. | Deflections when the flanch is upwards. | Deflections when the flanch is downwards. |
|---|---|---|
| lbs. | inch. | inch. |
| 6055 | ·43 | ·26 |
| 6727 | ·68 | ·34 |
| 7399 | ·88 | ·47 |
| and in experiments 8 and 7, | | |
| 2470 | ·66 | ·59 |
| 2739 | 1·22 | ·90 |
| 3008 | 2·20 | 1·35 |

*Beams with a Double Flanch.*

Let ABFE be a section of a beam having two flanches AB*ba* and EF*fe* formed by angle-irons riveted to a vertical plate CD, the material being symmetrically distributed with respect to the vertical line CD. Let O be the neutral axis, and KVG a line passing through the centre V of the vertical line CD parallel to AB or EF. Put A= the area of the section of the material, $A_1$= area ABFE or 2 area ABGK, $A_2$=2 area *mjsi*, $A_3$=2 area *jgb*G, $a_2$=2 area *mjqv*, $a_3$=2 area *jwf*G, $D_1$=GB=GF, $D_2$=*sj*, $D_3$=*b*G, $d_2$=*jq*, $d_3$=*f*G, X=OV, $I_1$= moment of inertia about KG, I= moment of inertia about O, W= the breaking upon the centre of the beam, *l*= the distance of the supports, S, $S_1$= the resistance of the material per square inch at the edges EF and AB respectively.




*To find the Neutral Axis.*

Taking KG as the axis of moments,

$$A \times X = \tfrac{1}{2}(A_2D_2 + A_3D_3 - a_2d_2 - a_3d_3),$$

$$\therefore \quad X = \frac{A_2D_2 + A_3D_3 - a_2d_2 - a_3d_3}{2A} \quad \ldots\ldots\ldots\ldots (6.)$$

where

$$A = A_1 - A_2 - A_3 - a_2 - a_3 \quad \ldots\ldots\ldots\ldots (7.)$$

*To find the Moments of Rupture, &c.*

Taking the moments of inertia with respect to the line KG,

$I_1$= moment inertia ABFE − 2 moment inertia space *bgsiqf*

$$= \tfrac{1}{3}(A_1D_1^2 - A_2D_2^2 - A_3D_3^2 - a_2d_2^2 - a_3d_3^2) \quad \ldots\ldots\ldots\ldots (8.),$$

$$I=I_1-AX^3 \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (9.)$$

$$S=\frac{Wl(D_1-X)}{4I} \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (10.)$$

and $$W=\frac{4SI}{l(D_1-X)}. \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (11.)$$

If $a_2=A_2,\ a_3=A_3,$

then $X=0,\ I_1=I,$

and $$I=\frac{1}{3}\left\{A_1D_1^3-2A_2D_2^3-2A_3D_3^3\right\},$$

$$\therefore\ S=\frac{WlD_1}{4I}$$

$$=\frac{3WlD_1}{4\{A_1D_1^3-2A_2D_2^3-2A_3D_3^3\}} \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (12.)$$

and $$W=\frac{4S(A_1D_1^3-2A_2D_2^3-2A_3D_3^3)}{3lD_1}, \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (13.)$$

which expresses the breaking weight when S is given.

Let $D_1'$, $D_2'$, ..., $A'$, $A_1'$, ... &c. be the corresponding dimensions of a beam in all respects similar, and let $r$ be the ratio of the linear dimensions, then

$D_1'=rD_1$, &c., $A'=r^2A_1$, &c., $A_2'D_2'=r^3A_2D_2$, &c., $A_1'D_1'^2=r^4A_1D_1^3$, &c.

By equation (6.),

$$X'=\frac{A_2'D_2'+A_3'D_3'-a_2'd_2'-a_3'd_3'}{2A'}$$

$$=\frac{r^3A_2D_2+r^3A_3D_3-r^2a_2d_2-r^2a_3d_3}{2r^2A}$$

$$=r\times\frac{A_2D_2-A_3D_3-a_2d_2-a_3d_3}{2A}$$

$$=r\times X.$$

By equation (8.),

$$I_1'=\frac{1}{3}\left\{A_1'D_1'^3-A_2'D_2'^3-A_3'D_3'^3-a_2'd_2'^3-a_3'd_3'^3\right\}$$

$$=r^4\times\frac{1}{3}\left\{A_1D_1^3-A_2D_2^3-A_3D_3^3-a_2d_2^3-a_3d_3^3\right\}$$

$$=r^4\times I_1.$$

By equation (11.),

$$W'=\frac{4SI'}{l'(D_1'-X')}$$

$$=\frac{4S\times r^4I}{rl(rD_1-rX)}$$

$$=r^3\times\frac{4SI}{l(D_1-X)}$$

$$=r^3\times W \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (14.)$$

That is, THE BREAKING WEIGHTS IN SIMILAR BEAMS ARE TO EACH OTHER AS THE SQUARES OF THEIR LIKE LINEAR DIMENSIONS.

The method of demonstration here used in establishing this important theorem may be applied to any other form of beam.

When the sections of the beams are similar, but the distance between the supports any quantity $l_1$, then we have

$$W' = \frac{l'}{l_1} . r^3 W. \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (15.)$$

Suppose W in equation (11.) to be determined by experiment, then we are at liberty to assume

$$W = \frac{A d C}{l},$$

where $d$ is the depth of the beam, and C a constant determined by the assumed relation.

From equation (14.), $W' = r^3 W$

$$= r^3 . \frac{A d C}{l}$$

$$= \frac{r^3 A . rd . C}{rl}$$

$$= \frac{A' d' C}{l'} . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (16.)$$

That is, THE BREAKING WEIGHTS IN BEAMS ARE FOUND BY MULTIPLYING TOGETHER THE AREA OF THE SECTION, THE DEPTH, AND A CONSTANT DETERMINED FROM EXPERIMENT ON BEAMS OF THE PARTICULAR FORM, AND DIVIDING THIS PRODUCT BY THE DISTANCE BETWEEN THE SUPPORTS.

The value of $l'$ in this formula is not restricted to the condition of similarity.

In experiment 12,

$D_1 = 3{\cdot}5, D_2 = 1{\cdot}375, D_3 = 3{\cdot}22, d_2 = 1{\cdot}375, d_3 = 3{\cdot}2, W = 24380 + 80 = 24460, l = 84,$

$A_1 = 4{\cdot}5 \times 7 = 31{\cdot}5, A_2 = 1{\cdot}375 \times {\cdot}28 \times 2 = {\cdot}7, A_3 = 3{\cdot}22 \times 1{\cdot}845 \times 2 = 11{\cdot}8818,$

$a_2 = 1{\cdot}375 \times {\cdot}3 \times 2 = {\cdot}75, a_3 = 3{\cdot}2 \times 1{\cdot}825 \times 2 = 11{\cdot}68,$

$A = A_1 - A_2 - A_3 - a_2 - a_3 = 32{\cdot}5 - 25{\cdot}01 = 6{\cdot}48,$

$\therefore$ by equation (6.), $X = {\cdot}0611.$

By equation (8.), $I_1 = 46{\cdot}782.$

By equation (9.), $I = 46{\cdot}782 - 6{\cdot}48 \times {\cdot}0611^3 = 46{\cdot}758.$

By equation (10.),

$$S = \frac{24460 \times 84 (3{\cdot}5 - {\cdot}0611)}{4 \times 46{\cdot}758 \times 2240} = 17 \text{ tons nearly,}$$

and $S_1 = 17\frac{1}{2}$ tons nearly.

In experiment 13, $W = 21715 + 80 = 21800$ nearly,

and

$$S_1 = \frac{21800 \times 84 (3{\cdot}5 + {\cdot}0611)}{4 \times 46{\cdot}7854 \times 2240} = 15{\cdot}5 \text{ tons,}$$

$$S = \frac{21800 \times 84 (3{\cdot}5 - {\cdot}0611)}{4 \times 46{\cdot}7854 \times 2240} = 15 \text{ tons.}$$

The values of S and $S_1$, as determined by these calculations, being less for the beam in experiment 13 than they are for the beam in experiment 12, it follows that the latter has a better distribution of the material than the former. And at the same time the difference of the value of these constants is so small as to lead us to infer that the form of the beam in experiment 12 approaches to that of maximum strength with a given quantity of material. The sectional areas of the top and bottom flanches are to each other as 28 : 30 or 14 : 15, which is very nearly a ratio of equality.

## APPENDIX.

Experiments by Thomas Loyd, Esq., Inspector of Machinery, to ascertain the effect of a tensile strain upon bars of wrought iron under varied conditions. Twenty pieces of $1\frac{3}{4}$ S C ⏢ bar iron, each 10 feet long, were cut out of the middle of twenty rods of iron. These 10-feet lengths were cut into two parts of 5 feet each, and marked with the same letter. A, B, C, &c. were first broken so as to get the average breaking strain. $A^2_2$, $B^2_2$, $C^2_2$ were subjected to the constant action of three-fourths of the breaking weight for five minutes. The load was then taken off, and they were afterwards broken. It will be seen that the breaking strain was about the same as before, thus proving that the previous strain had not weakened them.

Experiment 1.

| First. | | | | Second. | | | |
|---|---|---|---|---|---|---|---|
| Mark on the bars. | Dimensions of the bars. | Breaking weight in tons. | Ultimate elongation of bar in inches. | Mark on the bars. | Dimensions of the bars. | Breaking weight in tons. | Ultimate elongation of bars in inches with 25 tons. |
| A. | 1·37 | 33·75 | 9·12 | A 2. | ..... | 33·75 | 1·56 |
| B. | 1·37 | 30·00 | 9·12 | B 2. | ..... | 33·00 | 1·61 |
| C. | 1·37 | 33·25 | 9·75 | C 2. | ..... | 33·25 | 1·56 |
| D. | 1·37 | 32·75 | 9·22 | D 2. | ..... | 32·25 | 1·75 |
| E. | 1·37 | 32·50 | 9·22 | E 2. | ..... | 32·50 | 1·75 |
| F. | 1·37 | 33·25 | 10·50 | F 2. | ..... | 33·00 | 1·56 |
| G. | 1·37 | 32·75 | 8·50 | G 2. | ..... | 33·00 | 1·61 |
| H. | 1·37 | 33·25 | 10·61 | H 2. | ..... | 33·50 | 1·50 |
| I. | 1·37 | 33·50 | 8·37 | I 2. | ..... | 32·75 | 1·67 |
| J. | 1·37 | 33·50 | 9·22 | J 2. | ..... | 33·25 | 1·67 |
| K. | 1·37 | 32·25 | 8·00 | K 2. | ..... | 32·50 | 1·86 |
| L. | 1·37 | 32·25 | 7·50 | L 2. | ..... | 31·50 | 2·00 |
| M. | 1·37 | 30·25 | 9·12 | M 2. | ..... | 32·75 | Broke mark 1·75 in s. c. |
| N. | 1·37 | 34·25 | 9·22 | N 2. | ..... | 34·00 | 1·12 |
| O. | 1·37 | 31·75 | 7·61 | O 2. | ..... | 32·50 | 1·75 |
| P. | 1·37 | 29·75 | 10·00 | P 2. | ..... | 31·00 | 1·75 |
| Q. | 1·37 | 33·50 | 9·22 | Q 2. | ..... | 33·75 | 1·50 |
| R. | 1·37 | 33·75 | 9·75 | R 2. | ..... | 33·75 | 1·56 |
| S. | 1·37 | 33·00 | 9·12 | S 2. | ..... | 33·25 | 1·12 |
| T. | 1·37 | 32·25 | 8·75 | T 2. | ..... | 31·00 | 2·18 |
| Mean ... | ..... | 32·87 | 9·09 | | ..... | 32·81 | 1·64 |

In the first columns of the experiments it will be observed that the force required to break the bars was 32·37 tons, with a mean stretch of 9 inches upon twenty bars. In the second column the mean of the elongations, with a strain of 25 tons, was only 1·6 inch, whereas the ultimate breaking strain was 32·8 tons, evidently showing an increase instead of a diminution of strength from the previous strain of 25 tons, to which the bars had been respectively subjected.

Experiments made in the testing-machine of Woolwich Dockyard to ascertain the effect upon iron-bolt staves or iron bars to a tensile strain. The following results show the strains required for each of four successive breakages of the same pieces of iron as in the first experiment, $1\frac{3}{8}$ths of an inch diameter S C ⁂.

Experiment 2.

| Distinguishing mark. | First breakage. | | Second breakage. | | Third breakage. | | Fourth breakage. | | Reduced from 1·37 to |
|---|---|---|---|---|---|---|---|---|---|
| | Tons. | Stretch in 54 inches. | Tons. | Stretch in 36 inches. | Tons. | Stretch in 24 inches. | Tons. | Stretch in 15 inches. | |
| | | in. | | in. | | in. | | in. | in. |
| A. | 33·75 | 9·125 | 35·5 | 2·00 | | | | | |
| C. | 33·75 | 9·250 | 35·25 | ·25 | 37·00 | 1·00 | 38·75 | ..... | 1·25 |
| E. | 32·5 | 9·250 | 34·75 | 1·25 | | | | | |
| F. | 33·25 | 10·500 | 35·50 | 1·12 | 37·25 | ·62 | ·40 | ..... | 1·18 |
| G. | 32·75 | 8·500 | 35·00 | 1·25 | 37·5 | ..... | ·41 | ..... | 1·25 |
| H. | 33·75 | 10·625 | 36·25 | 1·87 | | | | | |
| I. | 33·50 | 8·375 | 34·50 | ·62 | 36·5 | 1·50 | | | |
| J. | 33·50 | 9·250 | 36·00 | ·25 | 36·75 | 1·120 | 41·75 | ..... | 1·25 |
| L. | 32·25 | Defective | 36·50 | 1·5 | 37·75 | ..... | 41·00 | ·31 | 1·25 |
| M. | 30·25 | Defective | 36·50 | ·62 | 37·75 | ·06 | 38·50 | ·06 | 1·25 |
| Mean ..... | 32·92 | ..... | 35·57 | ..... | 37·21 | ..... | 40·16 | ..... | 1·24 |
| Mean per square inch..... | 23·94 | ..... | 25·86 | ..... | 27·06 | ..... | 29·20 | ..... | ·90 |

The results of the above experiments are highly interesting, as they not only confirm those previously made, but they indicate a progressive increase of strength, notwithstanding the reduced sectional area of the bars. These interesting facts are of considerable value, as they show that a severe tensile strain is not injurious to the bearing powers of wrought iron even when repeated to the extent of four times. In practice it may not be prudent to test bars and chains to their utmost limit of resistance; it is however satisfactory to know that in cases of emergency those limits may be approached without incurring serious risk of injury to the ultimate strength of the material.

It is further important to observe, that the elongations are not in proportion to the forces of extension; thus in the bar F, experiment 2, the elongation of a bar 54 inches long with 33·25 tons, is 10·5 inches, giving an elongation per unit of weight and length $=\frac{10{\cdot}5}{33{\cdot}25 \times 54}={\cdot}0058$; whereas an additional weight of 2·25 tons produces an

elongation of 1·25 inch in 36 inches length of bar, giving an elongation per unit of weight and length $=\frac{1\cdot25}{2\cdot25\times36}=\cdot0154$; that is, the elongation in this latter case is about three times that in the former.

Experiments made to ascertain whether a shorter bar of iron is stronger than a longer one of the same kind and size, $1\frac{3}{8}$ths of an inch diameter, SC.

## Experiment 3.

| Length between the nippers 10 feet. | | | | | | |
|---|---|---|---|---|---|---|
| Distinguishing mark. | Stretch in 10 feet. | Breaking strain. | Mean. | Reduced at fracture. | To elsewhere. | Remarks. |
| | in. | tons. | tons. | in. | in. | |
| 1. | 26·00 | 33·00 | | 1 | 1·25 | |
| 2. | 26·75 | 31·75 | | ..... | 1·18 | |
| 3. | 26·25 | 32·25 | 32·21 | ..... | 1·25 | Mean of elongation 26 inches. |
| 4. | 23·00 | 32·00 | | ..... | ..... | |
| 5. | 27·50 | 32·25 | | B. | B. | |
| 6. | 26·75 | 32·00 | | 1·06 | ..... | |

## Experiment 4.

| Length between the nippers 42 inches. | | | | | | |
|---|---|---|---|---|---|---|
| Distinguishing mark. | Stretch in 42 inches. | Breaking strain. | Mean. | Reduced at fracture. | To elsewhere. | Remarks. |
| | in. | tons. | tons. | in. | in. | |
| B. | 9·50 | 32·50 | | 1·06 | 1·25 | |
| B. | 9·37 | 33·00 | | B. | ..... | |
| B. | 10·25 | 31·75 | 32·125 | 1 | B. | Mean of elongation 9·8 inches. |
| B. | 10·37 | 31·50 | | ..... | B. | |
| B. | 8·62 | 32·00 | | 1·06 | F. | |
| B. | 8·87 | 32·00 | | F. | F. | |

## Experiment 5.

| Length between the nippers 36 inches. | | | | | | |
|---|---|---|---|---|---|---|
| Distinguishing mark. | Stretch in 36 inches. | Breaking strain. | Mean. | Reduced at fracture. | To elsewhere. | Remarks. |
| | in. | tons. | tons. | in. | in. | |
| A. | 8·50 | 32·25 | | 1·06 | 1·25 | |
| A. | 8·75 | 32·25 | | 1 | B. | |
| A. | 9·00 | 31·25 | 32·25 | F. | B. | Mean of elongation 8·8 inches. |
| A. | 9·12 | 31·50 | | ..... | ..... | |
| A. | 9·37 | 33·50 | | B. | B. | |
| A. | 8·87 | 33·25 | | B. | B. | |

## Experiment 6.

Length between the nippers 24 inches.

| Distinguishing mark. | Stretch in 2 feet. | Breaking strain. | Mean. | Reduced at fracture. | To elsewhere. | Remarks. |
|---|---|---|---|---|---|---|
| | in. | tons. | tons. | in. | in. | |
| C 1. | 6·00 | 31·75 | | 1 | 1·25 | |
| C 2. | 6·62 | 31·50 | | 1·06 B. | F. | |
| C 3. | 6·12 | 32·50 | 32·00 | 1 | | Mean of elongation 6·2 inches. |
| C 4. | 6·12 | 31·75 | | 1 | | |
| C. | 6·00 | 32·25 | | 1 | | |
| C. | 6·37 | 32·25 | | ..... | B. | |

## Experiment 7.

Length between the nippers 10 inches.

| Distinguishing mark. | Stretch in 10 inches. | Breaking strain. | Mean. | Reduced at fracture. | To elsewhere. | Remarks. |
|---|---|---|---|---|---|---|
| | in. | tons. | tons. | in. | in. | |
| A. | 4·00 | 32·25 | | 1·06 | 1·25 | |
| A. | 3·87 | 32·50 | | | | |
| A. | 4·62 | 30·50 | | B. | B. | |
| A. | 4·75 | 31·50 | 32·29 | 1 | 1·18 | Mean of elongation 4·2 inches. |
| A. | 4·00 | 33·25 | | ..... | 1·25 | |
| A. | 4·12 | 33·75 | | | | |

## Abstract of the foregoing.

| Length between the nippers. | Breaking strain in tons. | Mean elongation in inches. |
|---|---|---|
| in. | | |
| 120 | 32·21 | 26 |
| 42 | 32·125 | 9·8 |
| 36 | 32·35 | 8·8 |
| 24 | 32·00 | 6·2 |
| 10 | 32·29 | 4·2 |

As these experiments were made upon the same description of iron, it may be fairly inferred that the length of a bar does not in any way affect its strength.

## Reduction of the preceding Table.

| Length of bar. | Elongation. | Elongation per unit of length. |
|---|---|---|
| in. | | |
| 120 | 26 | ·216 |
| 42 | 9·8 | ·233 |
| 36 | 8·8 | ·244 |
| 24 | 6·2 | ·258 |
| 10 | 4·2 | ·420 |

Here it appears that the rate of elongation of bars of wrought iron increases with the decrease of their length; thus while a bar of 120 inches has an elongation of ·216 inch per unit of its length, a bar of 10 inches has an elongation of ·42 inch per unit of its length, or nearly double what it is in the former case. The relation between the length of and its maximum elongation per unit, may be approximately expressed by the following formula, viz.—

$$l = \cdot 18 + \frac{2 \cdot 5}{L},$$

where L represents the length of the bar, and $l$ the elongation per unit of length of the bar.

These results are of some value, as they exhibit the ductility of wrought iron at a low temperature, and also the greatly increased strength which it exhibits with a reduced section under severe strain.

On some future occasion we may refer to this subject in order to show the bearing powers of wrought iron when compared with its elongated transverse section when reduced by forces sufficient to ensure fracture.

The following experiments were made to determine the transverse strength of beams, recommended by Mr. KENNEDY of Liverpool, for supporting the decks of iron ships.

### Experiment 8.—October 10, 1845.

On a malleable iron beam, of the annexed sectional form, 11 feet 7 inches long, and 11 feet between the supports.

Dimensions at $a$ = 1·000 in. × 2½ in.
Dimensions at $b$ = ·325 in. × 7 in.
Dimensions at $c$ = ·380 in. × 4 in.
Weight of beam = 227 lbs.
Weight of shackle = 885 lbs.

| Weight in lbs. | Deflection in inches. | Deflection load removed. | Remarks. |
|---|---|---|---|
| 885 | ·04 | | |
| 2,581 | ·12 | | |
| 4,317 | ·20 | | |
| 6,050 | ·26 | | |
| 7,743 | ·35 | | |
| 9,493 | ·46 | | |
| 11,253 | ·60 | ·09 | |
| 12,955 | ..... | ..... | With this weight the beam became distorted, and continuing the weight for some time, the deflection kept increasing until it bent laterally so as to be no longer able to sustain the load. |
| Ultimate deflection = ·69. | | | |

Experiment 9.—October 10, 1845.

On a malleable iron beam, of the annexed sectional form (see fig. 66), 10 feet 8 inches long, and 10 feet between the supports.

Dimensions at $a$=1·000 in.×2$\frac{3}{4}$ in.
Dimensions at $b$= ·350 in.×8 in.
Dimensions at $c$= ·440 in.×4·30 in.
Weight of beam=247 lbs.
Weight of shackle=885 lbs.

| Weight in lbs. | Deflection in inches. | Deflection load removed. | Remarks. |
|---|---|---|---|
| 885 | | | |
| 2,631 | ·04 | | |
| 4,358 | ·12 | | |
| 6,098 | ·15 | | |
| 7,827 | ·19 | | |
| 9,585 | ·21 | | |
| 11,278 | ·26 | | |
| 12,980 | ·30 | ·03 | |
| 14,693 | ·35 | ·03 | |
| 16,373 | ·45 | ·09 | |
| 18,115 | ·68 | ·26 | |
| 18,962 | ..... | ..... | With this weight the beam was distorted and the experiment discontinued. |
| Ultimate deflection=·71. | | | |

In both these experiments the beams yielded to lateral deflection, showing certain defects of form arising from want of lateral strength and breadth in the top and bottom flanges.

Experiment 10.—October 10, 1845.

Malleable iron beam of the same form as the last, 10 feet 7 inches long and 10 feet between the supports.

Thickness, $a$ = 1·000 in. × 2·75 in.
Thickness, $b$ = ·380 in. × 8 in.
Thickness, $c$ = ·420 in. × 4·30 in.
Weight of beam = 276 lbs.

| Weight in lbs. | Deflection in inches. | Deflection load removed. | Remarks. |
|---|---|---|---|
| 885 | ·020 | | |
| 2,606 | ·050 | | |
| 4,364 | ·090 | | |
| 6,105 | ·100 | | |
| 7,835 | ·140 | | |
| 9,559 | ·165 | ·03 | |
| 11,257 | ·195 | ·03 | |
| 12,999 | ·220 | ·04 | |
| 14,728 | ·250 | | |
| 16,407 | ·250 | | |
| 18,108 | ·290 | | |
| 19,839 | ·370 | | |
| 21,553 | ·475 | ..... | With 21,553 lbs. the deflection increased in four minutes ·025; in the next four minutes ·10; and in four minutes more it had sunk to ·34. |
| 22,387 | ·590 | | |
| 23,046 | ..... | ..... | Bent laterally upwards of 2·65 inches, when the experiment was discontinued. |
| Ultimate deflection = ·6. | | | |

In these experiments it will be necessary to remark, that they were made with the narrow flange uppermost; a position rather favourable to the strength than otherwise, on account of the increased area of the top flange, which is equal to 2·75 inches; and the bottom flange is only 1·8 inch, a circumstance (deduced from subsequent experiments) favourable to the resisting powers of a wrought-iron beam.

*Manchester, April* 10, 1850.

# XXXVI. *On the Mutual Relations of the Vital and Physical Forces* *.

*By* William B. Carpenter, *M.D., F.R.S., F.G.S.,*
*Examiner in Physiology and Comparative Anatomy in the University of London.*

Received June 20,—Read June 20, 1850.

## I. *Introductory Remarks.*

THE degree to which the phenomena of Life are dependent upon Physical agencies, has been a subject of inquiry and speculation among scientific investigators of almost every school. That many of the actions taking place in the living body are conformable to the laws of mechanics, has been hastily assumed as justifying the conclusion that *all* its actions are mechanical; and hence arose the *iatro-mathematical* doctrines, which obtained considerable currency among the physicians and physiologists of the seventeenth century †. In like manner, the fact that many of the

* The author thinks it due to himself to state, that the inquiry whose results are embodied in this paper has been occupying his attention for some years; in proof of which he may cite the following passage from a review of Prof. Matteucci's "Lectures on the Physical Phenomena of Living Beings," contributed by him to the "British and Foreign Medico-Chirurgical Review" for Jan. 1848 (p. 235):—"There can be no doubt that the present tendency of scientific investigation is to show a much more intimate relation than has been commonly supposed to exist between *vital* and *physical* agencies; and to prove that, whilst the former are of a nature altogether peculiar, they are yet dependent upon conditions supplied by the latter. And the more closely these phenomena are investigated, the more intimate and uniform does that dependence appear; so that we seem to have the general conclusion almost forced upon us, that the *vital* forces of various kinds bear the same relation to the several *physical* forces of the inorganic world, that they bear to each other; the great and essential modification or transformation being effected by their passage, so to speak, through the germ of the organic structure, somewhat after the same fashion that heat becomes electricity when passed through certain mixtures of metals." Of the paper communicated by Dr. Fowler to the British Association at its last meeting (September 1849) under the title—"If Vitality be a Force having Correlations with the Forces, Chemical Affinities, Motion, Heat, Light, Electricity, Magnetism, Gravity, so ably shown by Professor Grove to be modifications of one and the same Force?"—he has no more knowledge than that which he has obtained from the short abstract of it in the Report of that meeting, published since the greater part of his own paper had been written; and whilst it is evident from that abstract that Dr. Fowler has been pursuing the same line of investigation with himself, and with somewhat of the same results, he has not thought this a sufficient reason for keeping back his own communication from the Royal Society. For he thinks it will appear, from the extract he has cited, that he may fairly claim priority in the enunciation of the *idea*; and he ventures to believe that the systematic working out of that idea, which he has attempted in this paper, will give it a claim to the consideration of physicists and physiologists, such as it scarcely derives from the treatment which it has received from Dr. Fowler—so far, at least, as the author can judge from the abstract referred to. (See the *Supplementary Note*, p. 757.)

† "The body," says Dr. Bostock (History of Medicine, p. 165), "was regarded simply as a machine composed of a certain system of tubes; and calculations were made of their diameter, of the friction of the fluids in

changes of composition which take place within living bodies are analogous to those occurring externally to them, was assumed by another party as the foundation of the hypothesis that *all* the phenomena of life are of the nature of Chemical actions; and of that hypothesis the *iatro-chemical* doctrines which superseded the system of Galen, and which held their ground under various modifications for several centuries, were the natural expressions *. The insufficiency of either of these hypotheses, or of both of them combined, to explain the phenomena of life, gave origin to a third, which was undoubtedly more correct in its fundamental conception than either of its predecessors had been; the position assumed being, that the phenomena of each living body proceed from a *vital* agency, or *anima*, peculiar to each organized structure, and having nothing in common with chemical or mechanical principles †. The sect of the Vitalists, however, did not steer clear of the exclusiveness which had been the great fault of the chemists and physicists; but, in looking at every action of the living body as the immediate result of vital agency, claimed for that agency much that is clearly attributable to the operation of chemical and physical forces.

Among modern Physiologists there is a distinct recognition of the fact, that many of the phenomena of living bodies may be placed in the same category with those of inanimate matter, and that such are not otherwise affected by vital agency than as this prepares or modifies the conditions under which they occur. But there is also a distinct recognition of the fact, that living bodies present a large class of phenomena which are altogether peculiar to them, and which can only be attributed to agencies of which the inorganic world is altogether independent; and hence has arisen the notion of *vital agency* as the foundation of Physiological science, just as the notion of *affinity* is the foundation of Chemistry, and that of *mutual attraction* of General Physics. And putting aside all hypothetical considerations with regard to the abstract nature of that agency, Physiologists have been aiming to determine the laws

passing along them, of the size of the particles and the pores, the amount of retardation arising from friction and other mechanical causes, while the doctrines of derivation, revulsion, lentor, obstruction, and resolution, with others of an analogous kind, all founded upon mechanical principles, were the almost universal language of both physicians and physiologists towards the close of the seventeenth century."

* "The leading principle of the chemists," says Dr. Bostock (*op. cit.* p. 138), "was, that the living body is subject to the same chemical laws with inanimate matter, and that all the phenomena of vitality may be explained by the operation of these laws." The chemical physicians of the seventeenth century held "that the operations of the living body are all guided by chemical actions, of which one of the most important and the most universal is fermentation. The states of health and disease were supposed to be ultimately referable to certain fermentations, which took place in the blood or other fluids; while these fluids themselves were the result of specific fermentations, by which they were elaborated from the elements of which the body is composed" (*op. cit.* p. 157).

† "We are told," says Dr. Bostock (*op. cit.* p. 175), "that the *anima* superintends and directs every part of the animal economy from its first formation; that it prevents or repairs injuries, counteracts the effects of morbid causes, or tends to remove them when actually present, yet that we are unconscious of its existence; and that, while it manifests every attribute of reason and design, it is devoid of these qualities, and is, in fact, a necessary and unintelligent agent."

of its operation; following the same mode of inquiry for this purpose, as that which has been found successful in other departments of scientific investigation. In doing this, it has been necessary for them to *isolate*, as much as possible, those phenomena which may be regarded as Chemical or Physical, from those which must be distinguished as Vital; in order that, by the collocation and comparison of the latter, their mutual relations may be discovered. Still, after making every possible allowance for the operation of chemical and physical agencies, in the *direct* production of the changes of composition, mechanical movements, &c. which connect living beings (so to speak) with the universe around them, it is impossible for the discriminating inquirer not to see, that the influence of these agencies is *indirectly* exerted, to a yet greater extent, in the production or modification of purely vital phenomena. Thus, to take a very simple case, it cannot be for a moment doubted that heat and light exert an influence upon the vegetable germ, which is essential to its growth and development into the perfect plant, and to the performance of all the actions of the latter, whether these have reference to the extension of its own fabric, to the formation of organic compounds from the materials supplied by the inorganic world, or to the production of the germs of new individuals which are in like manner to go through the same series of phases. Hence light and heat have been designated as "vital stimuli;" the current idea being, that their agency upon the vegetable germ excites or awakens the forces which were dormant in it; and that, by enabling it thus to assimilate the new materials supplied by the inorganic world, and to give to these the structure of organized bodies, they contribute to develope the latent powers of these materials, which in their turn exhibit vital properties as they are made to form part of organized structures. Such, at least, is the doctrine of those who have most clearly expressed themselves upon the relation of the "vital stimuli" to the "vital properties" of organized bodies; and the author has not been able to find in physiological writings, any indication of a more intimate relationship between the physical forces and vital phenomena, than that just stated,—save on the part of those who have vaguely identified Heat or Electricity with the "vital principle," with about the same amount of philosophical discrimination as that which was exercised by the iatro-chemists and iatro-mathematicians of the sixteenth and seventeenth centuries.

The views of physical philosophers have been directed of late almost exclusively to the *dynamical* aspect of the inorganic universe; that is to say, its phenomena have been studied as the manifestations of certain *forces*; and each department of science takes cognizance of one or more of these, its *general* laws being nothing else than expressions of the modes and conditions of their operation, so far as known to the scientific investigator. That among all these forces there are very intimate mutual relations, is a conviction which has been gradually increasing in strength in the minds of philosophical inquirers during the whole of the present century; in consequence of the extraordinary development which the sciences of Chemistry, Electricity, Mag-

netism, Optics, and Thermotics, have undergone during that period, and of the accumulation of facts which more or less distinctly indicate the existence of such relations to those who know how to read them aright. Amongst those who have laboured most successfully in this line of inquiry, Prof. Faraday stands pre-eminent; but the author is not aware that any other attempt has been made to *formularize* the entire series of these mutual relations, than that which has been put forth by Prof. Grove in his short treatise 'On the Correlation of Physical Forces;' in which he seeks to establish "that the various imponderable agencies, or the affections of matter which constitute the main objects of experimental physics, viz. heat, light, electricity, magnetism, chemical affinity, and motion, are all correlative or have a reciprocal dependence:—that neither, taken abstractedly, can be said to be the essential or proximate cause of the others, but that either may, as a force, produce or be convertible into the other; thus heat may mediately or immediately produce electricity, electricity may produce heat, and so of the rest" (p. 8).

That the same view might be probably applied to the mutual relations of some of the Vital forces, did not escape Prof. Grove's sagacity, as will appear from the following passage near the conclusion of his essay:—"I believe that the same principles and mode of reasoning might be applied to the organic, as well as the inorganic world, and that muscular force, animal and vegetable heat, &c., might, and at some time will, be shown to have similar definite correlations; but I have purposely avoided this subject, as pertaining to a department of science to which I have not devoted my attention" (p. 49). The forces here alluded to by Prof. Grove, however, —those of muscular *motion* and *heat*,—are really *physical* in their manifestations, though generated in living bodies; the purely *vital* operations of growth, development, and reproduction are not even named by him; and not the slightest hint is given by him of the existence of any such relation between the Vital and Physical forces, as it is the chief object of this paper to establish.

Believing, as the author himself does, that all *force* which does not emanate from the will of created sentient beings, directly and immediately proceeds from the Will of the Omnipotent and Omnipresent Creator (which is evidently the idea entertained by Locke*),—and looking therefore at what we are accustomed to call the physical forces, as so many *modi operandi* of one and the same agency, the creative and sustaining will of the Deity,—he does not feel the validity of the objections which have been raised by some to whose opinions on philosophical questions he attaches great weight, against the idea of the absolute metamorphosis or conversion of forces. In deference to those opinions, however, he would here say *in limine* that his present object is to show, that *the same relation* (in whatever way defined) exists among the several vital forces, whose operation may be traced in living bodies, as exists among the physical; and that the vital and physical forces are themselves connected by a similar relationship. And as a mode of expressing that relationship

* Human Understanding, Book II. Chap. xxi. *On Power*, § 4.

without any hypothetical assumption, he would state his idea of the "correlation" of two forces, A and B, to be this;—that A, operating upon a certain form of matter, ceases to manifest itself, but that B is developed in its stead; and that, *vice versâ*, B, operating upon some other form of matter, ceases to manifest itself, but that A is reproduced in its stead. The idea of correlation also involves that of *a certain definite ratio* or equivalent between the two forces thus mutually interchangeable; so that the measure of force B, which is excited by a certain exertion of force A, shall, in its turn, give rise to the same measure of force A as that originally in operation. Thus, when an electric current is set in motion (to use the common phraseology) by galvanic action, the amount of chemical decomposition which it will effect bears a precise correspondence (*cæteris paribus*) with the amount of zinc which has undergone oxidation; chemical action thus exciting electricity, which in its turn reproduces the original equivalent of chemical action. In like manner, when water at 212° is converted into steam, the heat which it receives is no longer manifested *as* heat, but mechanical force is developed in its stead, and this in a certain definite ratio; as soon, however, as the steam, losing its elasticity by condensation, returns to the condition of water, the original equivalent of heat is again developed, its mechanical force being no longer manifested.

Whether we regard it as most consonant to our ideas of the nature of force, to consider the one force, in any such case, as itself becoming *latent*, whilst it excites an equivalent measure of a force of another kind which was previously *dormant*,—or whether we consider that the one force is actually *converted* into the other, and that there is really no such condition as dormant or latent force,—the fact of the mutual relationship, and the definite character of that relationship, remains the same; and it is upon this, rather than upon any hypothetical representation of it, that the author wishes chiefly to insist. Although, therefore, the terms "conversion" and "metamorphosis" will be occasionally employed in the present paper, as the most convenient modes of expressing the author's meaning, he is desirous that it should be understood that he does not desire to imply anything else than the existence of the relationship just defined.

One more preliminary remark is necessary, upon a point on which Prof. Grove has not thought it requisite strongly to dwell; namely, the necessity for a certain *material substratum* as the medium of the change in question. Thus, to take a familiar case, the correlation of Electricity and Magnetism is indicated by the development of magnetic attractions and repulsions in iron, when a current of electricity is made to circulate around it. In like manner, the correlation between Heat and Electricity is shown in the disturbance of electric equilibrium, which ensues on the application of heat to bars of certain dissimilar metals (especially bismuth and antimony) in contact with each other. The iron, in the first case, is the necessary medium for the development of the magnetic force by electricity; as the bars of dissimilar metals are in the second, for the development of the electric force by heat. So, again, in the

(so-called) magnetization of light by Prof. FARADAY, it seems necessary that the magnetic force should act through some material substratum, in order to produce any effect upon the luminous ray; the intensity of the effect varying according to the medium employed.—This consideration will be found of great importance hereafter, when the mutual relations of the Physical and Vital forces are brought under discussion.

## II. *Mutual Relations of the Vital Forces.*

Our clearest idea of the agencies essentially concerned in the production of vital phenomena, is derived from the study of the history of the development of any single organism; and it will be convenient to take that of the Plant in the first instance, as presenting us with these phenomena in their least complex assemblage.

The germ of a Cryptogamic plant, when set free from its parent, is a minute particle, apparently homogeneous in its character, but probably *a cell* in the earliest stage of development.—I. The first change which we witness, is its *growth* or enlargement; and this, when analysed, is found to involve several distinct operations. 1. The germ, under the influence of light, decomposes carbonic acid, and unites its carbon with the elements of water; at the same time decomposing ammonia, and uniting its azote with oxygen, hydrogen and carbon derived from the sources just named; thus forming *organic compounds*, such as no operation of ordinary chemistry has yet been able to imitate. 2. These organic compounds, at first in the condition of crude amylaceous and albuminous substances, need to be rendered *plastic* or organizable, by the process of assimilation, before they are fit to be applied to the extension of the living structure. 3. The organization of this plastic material then takes place, by which its materials are withdrawn from the fluid, and incorporated with the solid texture; and in this process they become fully possessed of the properties of the fabric of which they form part. 4. At the same time, a further process of organic transformation may generate other compounds, which occupy the cavity of the cell, and which are not destined to undergo organization, but are *secreted* or set apart for some ulterior purpose. In these, as in the organic compounds first generated, it is probable that the elements are arranged according to the laws of chemical affinity, although no agency but that of a living organized body has yet been found capable of bringing about their combination in these modes.

Thus we have in operation, in the simple *growth* of a vegetable cell, a force closely allied to chemical affinity, but so far different that it can only be exerted through a living organism; a force of assimilation or vital transformation; and a force of organization and complete vitalization. In speaking of them as distinct forces, it is only meant to affirm that their manifestations are diverse; for it cannot but be observed that they are all mutually dependent, and that they form part of a continuous series of phenomena which have but one ostensible cause,—the action of light and heat upon a living cell,—and but one destiny, the growth of that cell.

II. The *multiplication* of the cell, by spontaneous division or fission, is a process intimately connected with its growth, and takes place under precisely the same influences. It is by this kind of multiplication, that the simpler forms of vegetation are chiefly extended; and that the "germinal mass" is produced in the higher, the component cells of which, resembling each other in all their ostensible characters, seem to be nothing else than repetitions of that in which they all originated.

III. But from this homogeneous germinal mass, a complex and heterogeneous fabric is gradually evolved, of which the several parts or organs present wide diversities in structure and endowments. In this process of evolution or *development* (which obviously differs essentially both from growth and multiplication) it is usual to regard two separate agencies as in operation; namely, *Morphological Transformation*, which is concerned in the evolution of the several organs of which the entire body is composed; and *Histological Transformation*, the operation of which is limited to the component tissues of which these several organs are made up. It appears to the author, however, that, strictly speaking, there is but one such force; the form as well as the composition of each organ being determined by the *development* of particular tissues, and by their *multiplication* in one direction rather than another; he would therefore consider that the transformation of the simple primordial cells into other forms of tissue is the only indication of a distinct force which is manifested in the development of the fabric. Its assumption of its complete and perfect structure, is the result of that perfect harmony and balancing of the several forces of *growth*, *multiplication*, and *transformation*, which indicates, in the most distinct and unmistakeable manner, the controlling and sustaining action of an intelligent mind, acting in accordance with a determinate plan*.

In the life of the fully-developed organism, we have still to trace the persistence of the same phenomena; for this is entirely made up of the vital manifestations of its component parts; and these, in the plant, are either cells of various forms, or are tubes formed by the coalescence of cells, which minister simply to the conveyance of liquids. The vegetable physiologist has long been familiar with the fact, that all the operations of the most truly *vital* nature are performed in *cells*, which have not departed in any considerable degree from their primitive type. These operations do not essentially differ in the most elaborate vegetable structure, from those which are performed in the simplest plants, and in the earliest stage of development of the more complex; the chief difference being, that the products of the actions of individual cells

* The term "*germ-force*" has been employed by Mr. Paget (Lectures on Repair and Reproduction) to designate the power which each germ possesses "to develope itself into the perfection of an appropriate specific form." The author has elsewhere shown (Brit. and For. Med.-Chir. Review, Oct. 1849, p. 413) that this term cannot be logically understood as anything else than "a comprehensive expression of all the individual forces which are separately concerned in the evolution, maintenance, and reparation of a living being." And so far from regarding the whole force which produces the evolution as being possessed by, or as residing in, the germ, it will be the author's object to prove that it is of *external* origin.

are employed for other purposes in the economy, instead of being appropriated by the cells alone. Thus the cells of the spongioles absorb the water, and those of the green surfaces obtain the carbon (from the carbonic acid of the atmosphere), which are required for the nutrition of the entire fabric; and it is especially in the cells of the leaves that those assimilating processes are performed, whereby the plastic fluid is prepared, at the expense of which the organization of new tissue may take place elsewhere, or from which the cells in remote portions of the fabric may draw the materials of their peculiar secretion. So, again, we find that the process of multiplication of cells is limited to certain parts in which the actions of growth are most actively going on; and that a large proportion of the solid fabric is composed of structures which have ceased to take any active share in the performance of the vital functions, and which retain their integrity simply because they are not exposed to influences that would occasion their decomposition.

Everywhere it is to be noticed, that if the condition of the tissues is such as to cause it to be changed by the play of the ordinary chemical affinities, it can only retain its normal character so long as it is performing vital actions; and when these cease, it either undergoes decay (which is the case with the softer tissues), or it becomes transformed into a substance which resists decay, as is seen in the conversion of "sap-wood" into "heart-wood" by the filling-up of the woody tubes with sclerogen, resinous secretions, &c., which have little tendency to decomposition. And it will be observed, too, that the combined influence of warmth, air, and moisture, which favours the rapid decay of dead tissue, is that which most promotes the growth of the living plant. Further, the more rapid and energetic are the processes of growth, the sooner (generally speaking) are they succeeded by decomposing changes; this is seen especially in the Fungi, whose growth is more speedy, and whose degeneration is more immediately consequent upon the completion of their term of life, than that of any other tribe of plants; and it is seen also in cases in which the leaves have been forced into extraordinary activity by an excess of heat and light, their death and exuviation being thus induced at a comparatively early period. Conversely, if the vital operations be retarded by the withdrawal of the external agencies on which they are dependent, we find that the life of the structure is proportionally prolonged, and the decomposing changes are retarded accordingly; this is seen in the well-known fact, that a bouquet of flowers may be made to preserve its appearance of freshness for some time longer when kept in a dark room than it would do if exposed to light. These facts, and many others which might be cited, indicate that every integral part of the living fabric possesses within itself a capacity of being so acted on by external agencies, that the very forces which would tend to decompose and destroy it if it were dead, only excite it to vital activity if it be alive; but that this capacity lasts no longer than the completion of its own term of growth, every individual cell being destined to pass through a certain series of changes, the completion of which leaves it at the mercy of the physical and chemical agencies to which it may

happen to be subjected; and the duration of its life being inversely proportional to the rapidity with which these operations are performed.

In addition to the phenomena included under the general term of growth or development, we have to study those which constitute the proper *generative* process. This appears to consist, as the author has elsewhere shown*, in the reunion of the contents of two of the cells which had been previously separated by the process of fission. In the simplest tribes of plants, it would seem as if *all* the cells thus springing from the same primordial source, were capable of performing the generative act by "conjugation;" but this capability, like other endowments, is limited in the higher plants to particular groups of cells, which are developed in organs distinct from those concerned in the acts of nutrition, and are obviously set apart from the first for the performance of the act of generation alone.

Various kinds of *motion*, again, are performed by the agency of the vegetable structure, although these are less remarkable than they are in animals. From the extended researches of Prof. SCHLEIDEN it appears probable that within *every* cell, at some stage of its formation, a circulation of fluid takes place†, which is sustained by agencies that cannot be regarded as mechanical, and that are intimately connected with the formative processes; varying in its rate with the general activity of those processes, and only ceasing with their cessation. Wherever a cytoblast exists, the currents radiate from it and return to it again; in other cases (as the Chara) they are observed to extend over the whole lining of the cell-wall; in both cases being connected with the part that shows the greatest vital activity. The *zoospores* of various inferior Algæ are covered with *cilia*, by the vibration of which these bodies are carried through the water, and deposited at a distance from their parent. These zoospores are minute cells, formed within certain cells of the parent fabric, and liberated by their rupture. So, again, the spiral filaments long since observed in the Characeæ, the Hepaticæ, and in Mosses, and more recently discovered in the Fucaceæ and in Ferns, have a peculiar independent movement, which seems obviously destined to diffuse them, and thus to bring them into contact with the germ-cells which they are to fertilize. Each of these spiral filaments is developed within a distinct cell. And lastly, in certain plants, both of high and low organization, sensible movements are occasionally to be witnessed, which are immediately due to changes of form in their component cells; these changes of form being sometimes spontaneous, that is, occurring as a part of the regular series of the vital operations of those cells, and not directly excited by any external influences, as we see in the rhythmical movements of the *Oscillatoriæ*; and being sometimes consequent upon mechanical or other irritations applied to the cells which exhibit them, as in the case of the closure of the fly-trap of the *Dionæa*, but not being at all the less dependent upon the vital endowments of those cells, which cease to exhibit them when their vital activity is diminished. The folding of the leaves of the *Mimosa pudica* appears to take place

* Brit. and For. Med.-Chir. Review, Oct. 1849, p. 346. † Principles of Scientific Botany, p. 95.

spontaneously in some cases, and to be an excited phenomenon in others, thus combining the characters of both classes of movement, and showing their dependence on similar properties of the contractile cells.

Further, in many of the higher plants, and also in animals, we witness movements of fluid through a capillary network, which must be wholly or in part due to the vital relations of the fluid and the tissues through which it is carried; no physical agency being capable of entirely accounting for these movements, and some of them taking place under circumstances, which, as in the case of the rotation within the cells of the Chara, &c., seem to exclude the idea of such agency. Thus the *cyclosis* of Schultz (a recent observation upon which, apparently free from all fallacy, has been recorded by Prof. Balfour, 'Manual of Botany,' p. 128), whether or not an universal phenomenon, seems unquestionably to present the spectacle of a rapid capillary circulation, not maintained by any *vis a tergo*, but depending upon forces connected with the vital endowments of the parts through which it takes place. The movement of nutritive fluid in the canals excavated in the tissues of many of the lower Animals, in like manner, seems to be but little dependent on mechanical propulsion, and to be chiefly maintained by some power originating in the living tissues. And even the capillary circulation of the highest animals, in which the regular flow is sustained by the propulsive power of the heart, exhibits certain residual phenomena,—such as local accelerations and stagnations,—which cannot be attributed to changes in the rate or power of the heart's contractions, and indicate the existence of influences arising out of the vital relations of the nutritious fluids to the tissues through which its movement takes place;—this movement being most active when the formative actions of the part are being most energetically performed, and exhibiting a retardation as soon as any influence depresses them*.

The forces concerned in the growth, development, and movements of Animals appear to be essentially the same with those whose existence has thus been traced in plants. The animal, however, deriving its nutriment from organic compounds previously elaborated, does not perform that preliminary operation, which is so remarkably intermediate between chemical and vital agency, viz. the production of ternary and quaternary compounds, of complex atomic constitution, by the union of their elements. But in animals we find an additional power, termed Nervous Agency, nothing analogous to which exists in plants; this power, related on the one hand to the conscious mind, to which it communicates impressions derived from the external world, is also related, in a very remarkable manner, to the vital endowments of the organism in general, as will be presently seen, and particularly to the contractile tissues; the most perfect form of which (the striated muscular fibre) is usually called into action through its instrumentality, in obedience to mental impulses.

* That such is the case, must be admitted, the author believes, by all Physiologists and Pathologists who study the phenomena of the capillary circulation, whether or not they be disposed to admit the validity of the hypothesis of "vital attractions and repulsions" which has been offered by Prof. Alison as an explanation of this order of phenomena.

In order to meet the more varied requirements of the Animal organism, a much larger proportion of its tissues undergoes various transformations, so as to depart more or less widely from the original cellular type, than we find to be the case in the plant; still it is no less true in the animal than in the plant—as proved by the researches of SCHWANN, extended and confirmed as they have been in this particular by the researches of all subsequent histologists—*that all the tissues possessing distinctly vital endowments*, originate, directly or indirectly, in the transformation of cells.* And further, it may be stated, that *all the most active vital operations,* in the Animal as in the Vegetable organism, *are performed by tissues which retain their original cellular constitution with little or no change*†.

The several modifications of vital force which have now been enumerated will be found, when closely examined, to have a very intimate mutual relationship, however dissimilar may be the phenomena they produce. In the first place they are all exerted, even in the most highly organized living being, through a common instrumentality, the simple cell. Secondly, the entire assemblage of cells making up the totality of any organism, have all a common parentage; being linearly descended from the single primordial cell in which the organism originated. Thirdly, they are manifested in connection with each other, in those single-celled organisms, which are the lowest members of the two kingdoms respectively, and in which there is no separation or specialization of function.—Hence we may express them collectively under the general term of *Cell-force*; and seem entitled to affirm that each is a particular *modus operandi* of the same force as that which is concerned in cell-formation‡.

* It may now be considered as a well-established fact, that the *simple fibrous tissues* may originate in a structureless blastema, and may be produced by its fibrillation, without passing through the intermediate condition of cells. But these tissues cannot be regarded as possessing any truly *vital* endowments; their properties being simply physical, and their uses in the economy merely mechanical.

† This general proposition was first advanced by the author in regard to the operations in which organic life consists (and which are common, therefore, to plants and animals), in his "Report on the Origin and Functions of Cells" in the Brit. and For. Med. Review for January 1843. The subsequent discovery of the cellular composition of the ultimate fibrilla of striated muscular fibre, by himself and Prof. SHARPEY contemporaneously, and the accumulation of various facts relative to the existence of cells or cell-nuclei at the peripheral extremities of the afferent nerves, as well as in the central organs, seem to justify the assertion that unmetamorphosed cells are the active agents in the production of Muscular and Nervous force; in the former case effecting contraction by their change of form, and in the latter developing nerve-force, which is transmitted along the fibres as its conductors.

‡ The author is particularly desirous that he should be understood as implying by the term "cell-force," *not* that the force is produced or generated *by* the cell, but that the growth of the cell is the most general objective manifestation of that force, and that the cell affords the ordinary instrumental condition for its exertion, though there can be no doubt that the force may be exerted in many cases in which cell-development does not take place. The use which he would make of the term is just that which is commonly made of the term "Engine-power;" every one knowing that the steam-engine possesses no power itself, but that it is simply the instrument most commonly employed, because the most convenient and advantageous yet devised, for the application of the expansive force of steam, generated by the application of heat, to the production of mechanical motion.

This inference derives a remarkable confirmation from a series of facts, which indicate that when that *specialization* of function takes place, which has been mentioned as a characteristic of the higher organisms, the cells which become the instruments of some one particular kind of operation seem to lose their other endowments,—as if the expenditure of the vital force of each cell upon any one purpose, unfitted it for any other agency. Thus the *assimilating* cells (whether floating in the nutrient fluids, or included in the absorbent glandulæ), whose function it is to convert the raw material supplied by the food into organizable *plasma*, exercise little or no purely chemical transformation; they do not undergo change of form; they do not exert any mechanical or nervous power; and they do not reproduce their kind. So, again, the cells which are specially endowed with the power of *multiplication*, seem to possess no other special vital endowment; simply receiving the nutriment which has been prepared for them by other agencies, and applying it to the production of new cells, which, if themselves possessed of more special endowments, do not reproduce themselves. Of this we see an example in the first development of the embryonic structure, the cells of which rapidly multiply by the process of fission, up to the time at which histological transformations commence, and then this multiplication almost or entirely ceases; so that (as in the case of the insect, whose larva is an embryonic mass of very rapid production, composed almost entirely of cells destined to undergo histological change during the metamorphosis) the perfect structure *may* be even smaller than that from which it is developed. In the formation of new parts which make their appearance at a subsequent time, the same rule generally holds good, viz. that their foundation is laid in a mass of cells which rapidly multiply up to a certain point without histological transformation, and then undergo histological transformation with little further multiplication. But the most striking illustrations of this principle are perhaps to be derived from those cases, in which a continual production of cells possessed of some special endowment goes on during adult life. Thus it is necessary for every act of *secretion*, that a new formation of secreting cells should take place within the ultimate follicles of glands. These ultimate follicles are really to be regarded (as shown by Prof. Goodsir*) in the light of parent-cells, which produce the true secreting cells in proportion as the materials of their growth are supplied by the blood. Now *these parent-cells themselves possess no secreting power, their vital force being entirely expended in the production of the true secreting cells.* On the other hand, *the true secreting cells possess no reproductive power, but die and are cast off when they have reached their maturity; as if their whole vital force were expended in the secreting process*, which is itself nothing else than a portion of the act of growth. This will be found, the author believes, to be the type of a large order of facts, of which some others will be presently noticed. Again, the cells which are endowed with the special *reproductive* power, exercised in the true act of generation, seem to possess no other endowment; they do not exercise chemical transformation, nor do they undergo

* Anatomical and Pathological Observations, No. V.

histological change, nor do they multiply after the ordinary fashion. But here, again, we find that these cells are produced within others, whose whole endowment seems that of multiplication; the *sperm-cells* being generated in vast numbers within follicles or parent-cells, which have themselves no power of producing spermatic filaments; and each *germ-cell*, also, being a secondary product of the parent-cell of the ovule,—the other cells to which it gives origin (those which fill the embryo-sac in the vegetable ovule, and which form the vitellus of the animal unimpregnated ovum) being of very inferior character and transient duration. That a relation of reciprocity exists between the forces concerned in the growth, development, and maintenance of the individual organism, and those which are employed in the generative act,—so that an excessive expenditure of either diminishes the amount of vital force which is applicable to the other,—is an idea so familiar to physiologists, that the author need not here dwell upon it, further than to point out how completely it coincides with, and illustrates, the view for which he is contending.

When we look, moreover, at the tissues which have been developed from the original cells by histological transformation, we find that in proportion as they lose the cellular character, they for the most part cease to perform any strictly vital operation; as if the act of transformation had expended their vital power. We seem to see this in the development of tubes from cells, alike in the plant and in the animal, the tubes thenceforth serving merely for the conveyance of liquids; and in the development of the simple fibrous tissues of animals, the endowments of these fibres being purely physical, and what vital force they may retain serving merely to enable them to resist chemical change. When we look at the cells concerned in the production of *mechanical movement*, we find the same principle holding good in a most remarkable manner, these cells being apparently incapable of performing any other function. Thus the cells which constitute the fibrillæ of striated muscular fibre exercise no power of chemical transformation, they undergo no histological change, and they appear to be entirely destitute of the power of multiplication; the expenditure of their vital force in the act of muscular contraction involves their death and disintegration; and their renewal appears to be accomplished by a production of new cells by the continued agency of the parent-cell (or sarcolemma), which, itself possessing no contractile power, seems to hold the same relation to the contractile cells of the fibrillæ, that the parent-cells or follicles of glands hold to the true secreting cells occupying their interior. Again, the ciliary action, when the special endowment of a particular set of cells—as those lining the excretory ducts of the glands, respiratory organs, &c. of higher animals—appears to be in like manner incompatible with any other action, but to be the sole manifestation of the vital force of these cells. For the *ciliated epithelium is never a secreting epithelium*; so that in tracing the one form into the other, there seems to be such a marked transition in function (the mode of production and the general conditions of development being essentially the same) as clearly indicates that the ciliary action and the secreting agency, although very

dissimilar in themselves, are both to be looked upon as modes of operation of the same vital force as that which is exerted in the production of the cell. And this view derives remarkable confirmation from the fact, that in the history of the "zoospores" of the Algæ we have two distinct periods, one of ciliary action, and the other of growth and multiplication; *so long as the ciliary action continues, which is provided for their dispersion, no further vital change seems to take place in them; but so soon as this ceases and they become stationary, they begin to exercise chemico-vital transformations, and to grow and multiply as cells.*

These views in regard to the mutual relationship of the different kinds of vital force, are strikingly confirmed by the phenomena of *Nervous Agency*. There can be no reasonable doubt that the production of nerve-force in the central organs is dependent upon the development of the peculiar cells constituting the ganglionic or vesicular substance; and, as already remarked, the progress of physiological inquiry seems to justify the belief (long since entertained and expressed by the author) that either cells or cell-nuclei are the agents in the origination of nerve-force at the peripheral extremities of the nerve-fibres *. The nerve-force thus generated is not merely expended in arousing mental activity on the one hand, or in exciting muscular contraction on the other, but has an intimate relationship (there can be no doubt) with all the other manifestations of vital force which the animal organism exhibits. So intimate is this relationship, so obvious is the controlling and regulating action of the nervous system over the operations of nutrition, secretion, &c., especially in the higher animals, that many physiologists have regarded these actions as necessarily *dependent* upon the exertion of nervous force. On the other hand, it has been urged with great plausibility by Prof. Alison and others, that since the functions of organic life in Animals are performed under the same essential conditions as those of Plants, and since the acts of formation, secretion, &c. are effected by the very same agency in animals as in plants,—namely, by cell-growth,—there is no valid reason for regarding them as dependent upon nervous agency; although it must be freely admitted that they are greatly affected by that agency, being not merely accelerated and retarded through its influence, but also altered in kind. The view here advocated will, it is believed, afford a definite scientific expression for all the phenomena which bear upon this question. For, just as electricity developed by chemical change may operate (by its correlation with chemical affinity) in producing other chemical changes

* There can be little doubt that such is the function of the cells of the retina, which are shown, by the history of the development of the eye, actually to originate in the optic ganglion. The same appears to be the fact in regard to the cells in relation with the peripheric expansion of the auditory nerve, which originate in the auditory ganglion. (See Mr. H. Gray's paper "On the Development of the Retina and Optic Nerve, and of the Membranous Labyrinth and Auditory Nerve," at p. 189 of the present volume of the Philosophical Transactions.) And it seems probable from the researches of Kölliker (Annales des Sciences Naturelles. Ser. III. Zool. tom. vi. p. 102), that the plexuses which appear to constitute the ultimate distribution of the sensory nerves in the skin, are really composed of nerve-cells, which have sent out very slender prolongations to inosculate with each other.

elsewhere,—*so may nerve-force, which has its origin in cell-formation, excite or modify the process of cell-formation in other parts, and thus influence all the vital manifestations of the several tissues, whatever may be their own individual characters.* And this expression will also be found available for the well-known influence of mental conditions upon the properties of the various tissues and secretions, since this influence can only be exerted through the medium of nervous agency. Further, it not only appears that a simple withdrawal or disturbance of the nervous force supplied to particular organs occasions a retardation or perversion of their vital operations; but there also seems evidence that an influence of *an opposite kind* may be transmitted through the nervous system, which is positively and directly antagonistic to the vital powers of the several tissues and organs;—such, at least, appears to be the only mode of accounting for the extraordinary effect of a *shock*, mechanical or mental, in at once and completely destroying the contractility of the heart, and in immediately bringing to a stand the vital operations of other parts; and it harmonizes well with the fact that, in hemiplegia, the "palsy-stroke" transmitted from the brain along the spinal cord almost invariably affects the leg less injuriously than the arm, and for a shorter duration, recovery first taking place in the leg, even when it has been at first paralysed as completely as the arm. If the nervous force be regarded as a *polar* force (as suggested by Messrs. Todd and Bowman, 'Physiological Anatomy,' vol. i. p. 237 *et seq.*), analogous in its mode of transmission to electricity or galvanism, it is not difficult to understand that the *reversal* of the usual direction of its action may produce the effects in question, regard being had to the opposite effects shown by Prof. Matteucci to be produced upon nervous excitability by the *direct* and the *inverse* electric currents *.

It is hoped that the foregoing considerations (in support of which many others might be adduced †) will have served to establish the general proposition, that so close a mutual relation exists between all the vital forces, that they may be legitimately regarded as *modes* of one and the same force. The most general and characteristic of the manifestations of this force, which serves to unite and connect all the rest, is that which is concerned in *cell-formation*; and to this act, many of the other agencies appear to be essentially related. Thus the tissue of a muscle is constructed solely with a view to its manifestation of contractile power; whilst the development of nervous matter has reference entirely to the peculiar operations in which it is to be concerned. We find only one kind of tissue serving for the generation and transmission of nervous power; this alone affording the *material substratum* through which the vital force can manifest itself as nervous agency. And so, in like manner, it can scarcely be doubted that the contractile tissues, the assimilating cells,

* Lectures on the Physical Phenomena of Living Beings, translated by Dr. Pereira, p. 262.

† The dynamical relations of the nerve-force to mental agency, on the one hand, and to the several vital forces on the other, constitute a field of inquiry of vast extent and profound interest. To this inquiry the author purposes to apply himself, should the views enunciated in this paper be accepted as true, or even probable, by those most competent to judge of their merits.

the secreting cells, &c., have their own respective peculiarities of structure or composition, whereby they are severally enabled to serve as the material substrata, through which the vital force is exerted in the production of the various phenomena of life.

### III. *Relations of the Vital and Physical Forces.*

Having thus endeavoured to develope the fundamental relations which subsist between all strictly Vital phenomena, by showing that a "correlation" may be traced among the several forces to whose agency they are attributable, it is the author's purpose to inquire, whether any similar relation can be shown to exist between the *vital* and the *physical* forces.

In the conduct of this inquiry, it will be advantageous to take, as our starting-point, a case in which the existence of such a correlation appears particularly obvious; that, namely, of Nervous Force, the strong *analogy* of which to *Electricity* is admitted by all who do not believe in the *identity* of these two agents. The disproof of their identity will be found, the author believes, in the numerous experiments of Prof. Matteucci and others, who have failed to procure any manifestations of a change in the electric state of nerves, through whose agency muscular contractions were being most vigorously excited; and in the well-known fact, that the conduction of nervous force is prevented by pressure on the nerve-trunk, or by other disorganizing changes, which do not impair its power of conducting electricity. All the facts which have been adduced in support of the *identity* of these two forces will be found readily explicable on the idea of their "correlation" or mutual convertibility;—electricity, when acting through nerve-fibres, developing nervous force; and nerve-force, when operating upon a certain special form of apparatus, developing electricity. This view the author purposes now to unfold in more detail; adducing in support of it facts which are so well known to physiologists and electricians, that there can be no occasion to do more than cite them.

1. If an electric current be made to traverse the trunk of a *motor* nerve for a short distance only, it will produce contraction of the muscles which are supplied from its branches. It was formerly supposed that the contraction was excited by the immediate action of the electricity upon the muscles; but it has been clearly proved that the electric current need not proceed to them, its passage along the trunk for a very short distance being sufficient to develope the nervous force in its branches.

2. In like manner, if the electric current be passed for a short distance only along a *sensory* nerve, it will excite in the sensorium the peculiar sensations ordinarily produced by impressions conveyed through that nerve; that is to say, the ordinary tactile sensations, if the current be transmitted along a nerve of common sensation; or those of sight, hearing, smell, or taste, if the current be transmitted along the optic, auditory, olfactive, or gustative nerves. And thus, as remarked by Müller, we may, by proper management, be made conscious at one and the same time of pricking sensations, of flashes of light, of a phosphoric odour, and of a peculiar taste;

all excited by a peculiar cause, the transmission of an electric current along the sensory nerves, through which these modes of consciousness are respectively excited.

This production of muscular contraction on the one hand, and of various forms of sensation on the other, by the transmission of an electric current through a nerve-trunk, along a short distance only, appear to indicate that it is to the nervous force called into activity by the electric, and not to the electric force itself, that the phenomena are immediately due; and so strong an analogy presents itself between this development of nerve-force in a nerve, and the development of the magnetic force in a piece of iron, as the immediate and direct result of a certain application of the electric current, that, whatever may be the view taken of the relation of the magnetic force to the electric, the relation of the nervous force to the electric can scarcely but be placed in the same category. It is no objection to this view to say, that the nervous force can only be excited in the nerve of a living animal, or in that of an animal recently killed. In all instances of conversion of force, as already noticed, some form of matter is required as the medium of the metamorphosis; and a slight change in the condition of that matter may have a very considerable effect in modifying the process of conversion. Thus, it is by causing an electric current to circulate around a bar of iron, that we most readily develope the magnetic force; but the molecular condition of that iron, whether hard or soft, crystalline or fibrous, has an important influence upon the result. Now we know that the normal condition of the nerve-fibre can only be kept up by the continual performance of the changes which constitute nutrition; so that if these changes be interrupted, its molecular condition speedily undergoes alteration. Hence, the fact that the electric force can no longer call forth the manifestations of nervous force, when a short time has elapsed after the suspension of the nutritive processes by the stoppage of the circulation, is in no way inconsistent with the idea here advocated of the intimate relation between the two.

In order to complete the idea of "correlation," however, it must be shown that the nervous force may be the means of developing electricity; and it seems the only feasible method of accounting for the results of the experiments of Davy, Faraday, Matteucci, and others, upon the Electric Fishes, to look upon the development of electricity as the result of the action of their nervous force upon the peculiar organic apparatus to which its production is attributed. For the electric power has been ascertained to be entirely dependent upon the connection of that apparatus with the nervous centres, by nerve-trunks of large size, whose branches are distributed with extraordinary minuteness through the ultimate subdivisions of the electric organs; if these nerves be wholly divided, the electric discharge can no longer be called forth in the usual mode; if they be partially divided, the electric power is proportionably weakened; if the "electric lobe" of the encephalon be destroyed, removed, or injured, the electric power is annihilated or weakened, in precise accordance with the degree of damage inflicted; whilst, on the other hand, if the "electric lobe" be

mechanically irritated, or if the nerves proceeding from it be excited to action, even after their separation from the central organ, electric manifestations are obtained, the intensity of which is proportional to the excitement of nervous power thus effected. Various other phenomena recorded by Matteucci make it evident, that the amount of electric force generated by the electrical apparatus is in precise accordance with the amount of nervous force which is transmitted to it*.

Thus it appears that whilst electricity excites nervous force through the instrumentality of the nervous structure, nervous force excites electricity through the instrumentality of the electrical apparatus; and the case seems to be one which points directly to the existence of the *same kind of relation* between nervous force and electricity, as exists between electricity and magnetism, heat, chemical affinity, &c., whatever may be the form in which we think it best to express our notion of that relation. No one, the author believes, who has once adopted the idea of "correlation" as subsisting among the physical forces, can look at the peculiar connections to which he has adverted, as existing between the nervous and electrical forces, without perceiving how completely it is applicable to them. And he cannot but think that some such idea must have been present to the mind of Prof. Matteucci, although he has not met with any distinct expression of it in his writings†.

But Electricity is not the only physical force possessing this peculiar relation to the nervous force.

Our sensations of heat and cold are entirely dependent upon the power which *Heat* possesses of exciting nerve-force in the sensory nerves. Further, if heat be applied to a motor nerve in its course, it will call forth muscular contractions; and if applied to a sensory nerve, it will occasion sensations, both common and special; precisely after the manner of electricity. Conversely, there are phenomena well known to physiologists, which have not yet been explained upon the purely chemical doctrine of calorification, and for which it does not seem possible that any such explanation can account. Several of these phenomena appear to point to the nervous force as a direct agent in the production of heat; the amount of caloric thus generated being

* The question whether a disturbance of electric equilibrium occurs during the contraction of a muscle, and whether this is to be looked upon as the direct result of the operation of the nervous force, or is consequent upon the molecular changes taking place in the muscle under the influence of that force, must be regarded as at present *sub judice*. If the former prove to be the case, we have another instance of the direct production of electricity by nervous force; if the latter, the same metamorphosis would seem to take place through the intermediate condition of muscular force.

† [Since this paper was written, the author has had the satisfaction of learning, from the perusal of Prof. Matteucci's Eighth Series of "Electro-Physiological Researches," that he has formally adopted the doctrine of the correlation between the nervous and electrical forces, which the author had himself put forth, nearly two years before, in a review of Prof. Matteucci's "Lectures." (See Brit. and For. Med.-Chir. Review, Jan. 1848, p. 232.) In addition to the proofs adduced above, Prof. Matteucci has furnished a new series, arising out of the action of an electric current transmitted through a *muscle*, on the *nerves* which ramify through it. (See p. 296 of the present volume of the Philosophical Transactions.)—Nov. 20th, 1850.]

proportional to the expenditure of that force.—Thus a "correlation" is distinctly indicated between Nervous force and Heat.

Precisely the same may be said of *Chemical Affinity*; for the application of various reagents to the nerve-trunks may be made to call into action their peculiar endowments, whether these be motor or sensory; whilst, on the other hand, there is ample evidence that the chemical properties of secretions may be greatly changed under the direct influence of nervous force.

The power of *Light* to excite the nervous force is clearly indicated by the influence of this agent upon the optic nerve, whose peculiar force is excited by the impression of light upon its peripheral extremities; conversely, there are certain phenomena of animal luminosity, especially among the *Annelida*, which do not appear to be directly referable to chemical change, but which seem to be rather dependent upon a direct exertion of nervous power; vivid scintillations (resembling the luminous effects of an electric discharge through a glass tube spotted with tin-foil) being excited by any irritation applied to the nervous system of these animals*.

The relation of *Motion* to the nervous force is too striking to be passed by. The peculiar vital endowments of a nerve may be called into active exercise, as well by pinching or pricking it, as by electrical or chemical stimuli; thus by pressure on a nerve of common sensation, pain is excited; by pressure on a motor nerve, muscular contraction; by pressure upon the eyeball, sensations of light and colours may be produced in complete darkness; pressure applied to the meatus of the ear, so as to affect the auditory nerve, will give rise to a ringing sound; and by quickly but lightly striking the surface of the tongue, near its tip, with the finger, a distinct taste, sometimes acid, sometimes saline, is produced†. Conversely, the nervous force appears convertible into motion through the medium of the Muscular apparatus, just as it excites electricity through the instrumentality of the electric organs of Fishes. That the motor force thus generated is always proportional, *cæteris paribus*, to the

* This is the conclusion at which the author arrived some years since, from observations which he made at Tenby on a small Annelide (probably a species of *Syllis*), in which the luminous discharges are seen with extraordinary brilliancy, when the animal is subjected to irritation, as by slightly pinching or pricking it, or by the movement of the water around it. The same conclusion was contemporaneously arrived at by M. de Quatrefages, from observations made on the Annelida of the coast of France. "En étudiant, à l'aide du microscope, de petites Annélides transparents, M. de Quatrefages est arrivé à découvrir un rapport curieux entre certains phénomènes de phosphorescence animale, et l'influence de l'agent qui détermine la contraction musculaire, et qui, à plusieurs égards, semble tant d'analogie avec l'électricité. Il est probable que la lumière plus ou moins vive, que répandent un grand nombre d'animaux inférieurs, ne dépend pas toujours de la même cause; que tantôt c'est un phénomène qui accompagne la décomposition des matières organiques, et que d'autres fois c'est le résultat de la sécrétion d'un liquide particulier; mais il est probable que, dans un grand nombre de cas, la cause de la phosphorescence est entièrement physique, *et se lie, comme la contraction musculaire, à l'influence nerveuse.*"—Rapport sur une Série de Mémoires de M. A. de Quatrefages, relatifs à l'organisation des Animaux sans Vertèbres des Côtes de la Manche, par M. Milne-Edwards (Annales des Sciences Naturelles, Troisième Série, tom. i. p. 23).

† See Dr. Baly's Translation of Müller's Physiology, p. 1062.

degree of nervous power exerted, will be (the author believes) disputed by no physiologist; it is most remarkably illustrated in the extraordinary force developed under the influence of emotional excitement, which often calls forth a much greater measure of muscular power than the will can command.

Of the relations between *Magnetism* and the nervous force, the author thinks it preferable to say nothing more at present, than that various indications appear to him to be afforded, by recent investigations, of the existence of a direct and influential connection*.

The relation thus pointed out between Nervous agency and the various Physical forces, is the more remarkable, when it is considered that the nervous power must be regarded as the *highest* of all the forms of vital force, both in its relations to mental action, and in its dominant power over organic processes of every kind. Considering how closely, as already pointed out, it is correlated to the forces concerned in muscular and ciliary movement †, in nutrition and secretion, in development and reproduction, it cannot be thought improbable that what is true of it should be true of them also; and that a relation of mutual convertibility should exist between these and one or more of the physical forces. Such relations the author believes to exist; and he now proceeds to adduce facts which appear to him adequate to support that belief.

The *muscular* force may be called forth, as is well known, by electricity directly applied to the muscle itself; by heat, cold, and chemical agents; and by mechanical irritation. These agencies, however, do not appear so directly concerned in the production of the motor power, as in occasioning that metamorphosis of living organized tissue into chemical compounds, whereon the development of the muscular force seems to be immediately dependent. It is now universally admitted that the disintegration of a certain amount of muscular tissue, and the new arrangement of its components in combination with oxygen supplied by the blood, is necessary for the development of its contractile force; and the considerations adduced by Prof. Liebig render it highly probable, that the muscular contraction may be regarded as proceeding from the expenditure or metamorphosis of the cell-force, which ceases to exist as a *vital* power, in giving rise to *mechanical* agency. The amount of muscular force developed appears to bear an exact correspondence with the amount of urea formed by the metamorphosis of the muscular tissue; and this metamorphosis involves the cessation of its existence as a living structure, and consequently the annihilation of the vital

* Whatever scientific value we might have otherwise been disposed to attach to the researches of Baron von Reichenbach on "Magnetism, Crystallization, &c. in their relations to Vital Force," they seem to derive some additional claims on our attention from the discoveries of Prof. Faraday in regard to the universal operation of the magnetic force, and its relations to light and to the polar force of crystals,—discoveries which, be it observed, had not been made when the phenomena observed by Baron von Reichenbach were first made public.

† In man and the higher animals, the ciliary movement does not appear to be in any degree controllable by nervous agency; but there can scarcely be a doubt that in the *Rotifera* it is thus governed.

forces which that structure possessed. We are, then, to regard the nervous, electrical, and other stimuli, under whose influence the muscular force is called forth, less as the immediate sources of that force, than as furnishing the conditions under which the vital force acting through the muscle is converted into the mechanical force developed in its contraction.

We do not yet know enough of the conditions under which *ciliary movement* takes place, to enable us to affirm that the production of mechanical motion through its means is in like manner the result of an expenditure of vital force; but the considerations formerly adduced in regard to the relation of ciliary action to other vital manifestations, together with the remarkable similarity between the influence of strychnia, opium, electric discharges, &c. upon the ciliary movement and upon muscular contractility, leave little room for doubt that what is true of the muscular force is true also of ciliary motion, and that it, too, is to be regarded as directly depending upon a conversion of vital force into mechanical motion. The continuance of motion in the cilia appears to be intimately related to changes taking place in the cells on which they are borne; and its persistence after the detachment of these cells from the remainder of the body, like the persistence in the contractility of muscular fibre which has been completely isolated from all its connections, proves that we must look to forces existing in them, and not to influences derived from any other source, for the maintenance of this curious operation.

Passing from these particular manifestations of vital force, which so remarkably indicate its relations to physical agencies, to those which, being concerned in the development and growth of organized structures, seem to have less in common with them, we shall fix our attention on the fundamental fact, that these Organizing forces (as we may conveniently designate them) are so completely dependent upon the continual agency of *Heat* (and in some cases of Light also), that they may be considered as the manifestations of the action of heat upon organized fabrics.

The necessity for this agency may be seen at every period of the life of organized beings of all kinds. In the lower tribes of animals, and in the entire vegetable kingdom, we trace this dependence in *the precise relation between the vital activity of each individual, and the amount of heat which it receives from external sources.* Every species is adapted to flourish within a certain range of temperature; and that amount of heat which is most effective in sustaining the life of one species, may be injurious or even fatal to another. But within the range which is compatible with the manifestation of its vital powers, we find that the relation is most constant between the temperature and the organizing force exhibited by each species. It is scarcely necessary to accumulate facts in support of a position so generally admitted; but the author particularly wishes to direct attention to the definiteness and exactness of this relation, and may instance the following facts as examples.

1. According to Boussingault, the same annual plant, in arriving at its full development, and going through all the processes of flowering and maturation of its

seed, *everywhere receives the same amount of solar light and heat*, whether it be grown at the equator or in the temperate zone; its *rate of growth being in a precisely inverse ratio to the amount it receives in any given time.* Hence it appears that the organizing force of Plants bears a relation of equivalence to the Heat and Light which act upon them.

2. This has been separately demonstrated with regard to the special influence of Light, in producing the decomposition of carbonic acid and the formation of chlorophyll, &c.; the amount of carbon fixed by plants being *cæteris paribus* in accordance with the amount of illumination they receive. The influence of Light, it may be remarked, seems to be exerted only in this peculiar process of vital chemistry; whilst that of Heat is exercised in *all* the other operations in which growth consists; and hence it is that Animals are comparatively little dependent upon light, their food being prepared for them by the agency of the vegetable kingdom.

3. The rate of "rotation" of the fluid within the cells of *Chara*, &c., and the rate of "cyclosis" in the latex-vessels of *Ficus elastica*, &c., appear to be in precise relation (within certain definite limits) with the temperature to which these organisms are subjected; the movement of the fluids being accelerated by warmth, and retarded or checked by cold*.

4. In cold-blooded Animals, the same relation may be seen, between the activity of the organizing processes, and the amount of Heat to which they are subjected. The production of larvæ from the eggs of Insects, like the germination of the seeds of plants, may be accelerated or retarded at pleasure, simply by the regulation of the temperature; and the time required for the last metamorphosis is precisely in the inverse ratio to the heat supplied; so that, as in the maturation of the plant, each individual of the same species receives the same amount of heat, whether the intensity of its action be greater or less. Further, it has been remarked by Mr. Paget†, that the processes of *development* seem to require a higher degree of Vital force than those of simple *growth*; and it harmonizes admirably with the doctrine here contended for, that there appears to be a necessity for a higher temperature for developmental operations, than for those of simple increase. Thus in the economy of the Social Bees, as shown by Mr. Newport, there is a special provision for generating heat during the last few hours of the metamorphosis, in which the tissues and organs of the imago are being completed; and in the Viper and some other ovo-viviparous Reptiles, there seems to be an unusual calorifying power, for the purpose of promoting the development of the embryo. So, again, it has been found by Dr. Edwards and Mr. Higginbottom that the metamorphosis of Batrachia requires a larger amount of light and heat than

* It would almost seem as if some anti-vital influence, resembling that of "shock" in animals, could be exerted by mechanical injury on plants. When a portion of the leaf of *Vallisneria* is detached for the exhibition of the movement of "rotation" in its cells, the movement generally ceases for some little time; the application of warmth will usually re-excite it; and it may then continue for several hours or even days.

† Lectures on Repair and Reproduction.

suffices for their growth in the larva state, being retarded or even prevented by the want of a due amount of these agencies (see p. 753); and it has been also shown by Mr. Higginbottom that the *development* of new limbs in the Triton, to replace those which have been lost, cannot take place at a lower temperature than about 60°, although the processes of *growth* go on under a much less degree of heat*. The general propositions enunciated by Prof. Milne-Edwards†, in regard to the geographical distribution of the Crustacea, indicate the existence of this relation in the most decided manner. They are, briefly, as follows:—I. The varieties of form and organization (which may be regarded as so many varied manifestations of the organizing force) increase as we pass from the Polar Seas towards the equator, the number of species thus augmenting greatly as we go southwards. II. The differences of form and organization are not only more numerous and more characteristic in the warm than in the cold regions of the globe; they are also more important. III. Not only are those Crustacea which are most elevated in the scale deficient in the polar regions, but their relative number decreases rapidly as we pass from the equator towards the pole. IV. The average size of the Crustacea of tropical regions is considerably greater than that of the tribes inhabiting temperate or frigid climes. V. It is where the temperature is most elevated, that the peculiarities of structure which characterize the several groups are most strongly manifested. And VI., there is a remarkable coincidence between the temperature of different regions, and the prevalence of certain forms of Crustacea.—It is interesting to observe, that the want of a high temperature is no obstacle to the growth and multiplication of individuals of a comparatively small size and low grade of organization; the Arctic and Antarctic seas being as numerously peopled with such, as the tropical ocean is with higher forms. But the preceding statements point to a direct and definite relation between Heat and the Organizing force, as manifested in this group of animals. A comparison of the facts relating to the geographical distribution of other classes of cold-blooded animals would probably justify the same conclusions. There can be no doubt of their general applicability to the Vegetable kingdom.

5. The influence of temperature upon the general vital activity of cold-blooded animals is no less remarkable. The facts determined by the experiments of Dr. W. F. Edwards‡ lead to this general conclusion;—that the *rate of life* of Batrachia and Fishes, of which the activity of their respiratory process is the exponent, varies directly (within certain limits) as the temperature of the surrounding medium; so that the *duration of life*, when these animals are deprived of air, either partially or completely, or are placed in any other circumstances unfavourable to its sustenance, varies inversely with the external temperature. Thus when frogs were confined in a limited quantity of water, and were not allowed to come to the surface to breathe, it

* Proceedings of the Royal Society, March 18, 1847.

† Histoire des Crustacés, tom. iii. p. 555 *et seq.*

‡ On the Influence of Physical Agents on Life, *passim*

was found that they died in from 12 to 32 minutes, when its temperature was 90°; in from 35 to 90 minutes, when its temperature was 72°; in from 350 to 375 minutes, when its temperature was 50°; and from 367 to 498 minutes, when it was cooled down to the freezing-point. The prolongation of life at the lower temperatures was not due to torpidity, for the animals performed the functions of voluntary motion and enjoyed the use of their senses; but it was occasioned by the diminished activity of *all* their functions, and their consequent less demand for air. On the other hand, the elevation of temperature increases the demand for air, and occasions speedier death when it is withheld, chiefly by producing a vast acceleration in the rate at which all the operations, both of animal and organic life, take place.

6. Although the warm-blooded animals are in great degree removed, by the independent calorifying power which they possess, from the influence of external temperature, yet it is very easily shown that their vital activity is no less under the direct and immediate influence of heat, than is that of cold-blooded animals. In fact, it would seem to be for the sake of keeping up their vital energy to a certain high and uniform rate, that they are endowed with the heat-generating power; and if this power be not exercised, and the body be cooled down, its vital activity is reduced, and at last extinguished. From the experiments of Chossat* it appears that Birds and Mammals cannot (except in the case of the hybernating species) be cooled down more than 30° below their natural standard, without the entire suspension of their animal and organic functions. This depression of temperature consequent upon prolonged starvation, was found to take place as soon as all the fat and other disposable materials in the body had been burned off. But so soon as animals thus reduced to a moribund condition were subjected to external heat, which artificially raised the temperature of their bodies, their sensibility and muscular power were renewed; they flew about the room, and took food when it was presented to them; and their secretions were restored. If this artificial assistance was prolonged, until the digested aliment was prepared in sufficient amount to maintain the combustive process, they recovered; but if it was withdrawn too soon, they died.—The hybernating species of Mammalia differ from the rest essentially in this, that the lowering of the temperature of their bodies does not destroy their vitality, but merely suspends their activity, so that they are reduced for a time to a condition in all respects comparable to that of cold-blooded animals but little removed above absolute torpidity; and in this condition, all that has been said respecting the influence of external temperature upon the rate of life of cold-blooded animals, applies to them also.

The vast mass of facts, of which the foregoing are examples, appears to the author to justify the conclusion, that Heat is something more than a *stimulus* capable of arousing a dormant vital force; but, on the other hand, they by no means justify the assumption that heat and the "vital principle" are identical. That Heat, acting upon or through an Organized structure, then manifests itself as Vital force,—or that heat

* Expériences sur l'Inanition.

and vital force are "correlated,"—seems to be the expression of their mutual dependence, which is most in accordance with all our knowledge of the influence of heat upon organized beings; whilst conversely (as will be shown hereafter) it accords with the fact of the restoration to the inorganic world—under some form or other—of all the *force* thus withdrawn from it.

It may serve, however, to bring this idea into contrast with the notions usually entertained, and to illustrate its application more fully, if it be considered in its relation to the Development of any highly organized being from its primordial germ-cell. According to the doctrine current among some physiologists, the whole "organizing force," "nisus formativus," or "bildungstrieb," which is to be exerted in the development of the complete structure, *lies dormant in this single cell*, the germ (it has been affirmed) being "potentially" the entire organism. And thus all the organizing force required to build up an oak or a palm, an elephant or a whale, is concentrated in a minute particle only discernible by microscopic aid.

As a refuge from this doctrine, which seems almost too absurd ever to have gained believers, other physiologists (among whom the author formerly ranked himself) have affirmed that *vital force must exist in a dormant condition in all matter capable of becoming organized*; that the germ-cell, in drawing to itself organizable materials, and in incorporating these into the living structure, does nothing else than evoke into activity their latent powers; and thus that, with every act of growth and cell-multiplication, new vital force is called into operation, whereby the process is continually maintained. This proposition, it may be safely asserted, does not involve any manifest absurdity. It attributes to oxygen, hydrogen, carbon, and nitrogen, properties which they were not previously supposed to possess; but no one could logically deny to these elements the possession of dormant vital powers, whilst they held that a dormant magnetic power might be attributed to iron. In the one case, as in the other (it may be affirmed), a certain combination of conditions is needed to call the property into exercise; and the living cell, combining the elementary substances into the pabulum of its growth, and then applying this to its own nutrition, calls their latent vital properties into activity,—just as (it has been argued) an electric current, made to circulate around a piece of iron, developes the latent magnetic force of that metal.

The views of Prof. Grove, however, strike at the root of the notion of *latent force* of any description whatever; all force once generated being, in his estimation, perpetually *active* under one form or other; and its supposed "latency" being a hypothetical condition, the idea of which is quite unnecessary when the force which has ceased to manifest itself is recognized under some other form. Thus, in his view, when iron is rendered magnetic by an electric current, the development of the magnetic force is rather to be looked on as the result of the conversion of the electric, by the instrumentality of the iron, than as a case of the excitation of one force previously

dormant, by another which is expended in thus evoking it. Such an analogy should rather lead the physiologist to look for some extraneous source of the organizing force; and to suspect that when organizable materials are applied to the extension of a living structure, and are caused to manifest vital forces, *some agency external to the organism is the moving spring of the whole series of operations.* And thus, according to the view here advocated, the vital force which causes the primordial cell of the germ first to multiply itself, and then to develope itself into a complex and extensive organism, was not either originally locked up in that single cell, nor was it latent in the materials which are progressively assimilated by itself and its descendants; but is directly and immediately supplied by the Heat which is constantly operating upon it, and which is transformed into vital force by its passage through the organized fabric that manifests it. The facts already cited, which show how completely dependent the process of germ-development, both in plants and animals, is upon the constant agency of heat, and how precisely its rate may be regulated by the measure of that force supplied to it, appear to the author to be so much better accounted for upon this view than upon either of the others, that he ventures to think that they demonstrate it almost as fully as the nature of physiological evidence will admit.

Having thus contrasted the doctrine for which he is contending, with those which are current among physiologists, the author thinks it well to point out that he no more regards heat as the "vital principle," or as itself identical with the "vital force," than it is identical with electricity or with chemical affinity. Nor does he in the least recognize the possibility, that any action of heat upon the inorganic elements can of itself develope an organized structure of even the simplest kind. The pre-existence of a living organism, through which *alone* can heat be converted into vital force, is as necessary upon this theory, as it is upon any of those currently received amongst physiologists. And it is the *speciality* of the material substratum thus furnishing the medium or instrument of the metamorphosis, which in his opinion establishes, and must ever maintain, a well-marked boundary-line between the Physical and the Vital forces. Starting with the abstract notion of Force, as emanating at once from the Divine Will, we might say that this force, operating through inorganic matter, manifests itself in electricity, magnetism, light, heat, chemical affinity, and mechanical motion; but that, when directed through organized structures, it effects the operations of growth, development, chemico-vital transformation, and the like; and is further metamorphosed, through the instrumentality of the structures thus generated, into nervous agency and muscular power. If we *only* knew of heat as it acts upon the organized creation, the peculiarities of its operation upon inorganic matters would seem as strange to the physiologist, as the effects here attributed to it may appear to those who are only accustomed to contemplate the physical phenomena to which it gives rise.

The variety of organic forms called forth by the agency of heat, which may be regarded as the products of its operation upon living germs, does not present any

real obstacle to the reception of this doctrine; since in *any* hypothesis which assumes a common force as operative in the living kingdoms of nature, it is necessary to admit that this force is modified in its action by the properties of the germ, just as that the general force of chemical affinity manifests itself differently in the reactions of each elementary and composite substance. And just as the chemist seeks to determine the laws of chemical affinity by observation and experiment, so does the philosophic physiologist aim to discover the general plan on which the vital force is exerted, in the production of the wonderful series of organized structures which have successively presented themselves on this globe.

In speaking of Heat as the physical agent especially concerned in the development of living organisms, and in the maintenance of their activity, the author would by no means leave out of view the other physical forces, *all* of which, if correlated to each other, as well as to the vital forces, must be capable of exerting an important influence on these processes. He has merely selected Heat, as the one whose operation is most extensive and most easily demonstrated; and every fact which indicates that other physical agencies are also in operation, will (of course) only add weight to his argument. To the universally-admitted agency of *Light*, in directly exciting one (at least) of the most important processes of vegetable growth, reference has already been made. But there is evidence that light has an influence upon certain processes of *development*, which cannot be accounted for by its agency in the fixation of carbon from the atmosphere, and in the production of organic compounds. One of the most remarkable examples of this agency is furnished by the experiments of Mirbel upon the *gemmæ* of *Marchantia polymorpha*. He found, after repeated trials, that during the development of these little discs, stomata are formed on the side exposed to the light, whilst root-fibres grow from the lower surface; and that it is a matter of indifference *which* side of the disc is at first turned upwards, since each has the power of developing stomata, or roots, according to the influence it receives*. The experiments of Dr. W. F. Edwards indicate that a decided influence is exerted by light upon the metamorphosis of the Batrachia; since, according to his statements, when tadpoles, *arrived at nearly their full growth*, were secluded from the influence of light, but were supplied with aërated water and food, *they continued to increase as tadpoles* (so as to attain an extraordinary size, doubling or even trebling their usual full weight) without undergoing any metamorphosis †. The influence of light upon the

* Nouvelles Annales du Muséum, tom. i.

† On the Influence of Physical Agents on Life, p. 53.—The results of the recent experiments of Mr. Higginbottom appear to negative those obtained by Dr. Edwards, and to show that metamorphosis is only retarded by privation of light, when accompanied by reduction of temperature. But the remarkable fact above quoted from Dr. Edwards's statements, to which Mr. Higginbottom has recorded nothing parallel, shows that there was some difference in the conditions of the two sets of experiments, which should prevent us from setting aside those statements, made (as they are) by a most trustworthy observer, until they shall have been more fully disproved.

minute Entomostracous Crustacea is well known. Their development is greatly retarded by the want of it; and the exuviation of their shells, which normally takes place at short intervals when they have attained their complete form and size (apparently for the purpose of freeing them from the minute plants with which their surface becomes clothed), is much less frequently performed*. With these facts before us, we can scarcely refrain from suspecting that the deprivation of light may be the cause of the atrophy of the visual organs in certain animals which pass their whole lives in complete seclusion from its influence. This condition, which has been long known to exist in the common Mole, and also in the *Proteus anguineus*, and which has also been discovered in the *Amblyopsis spelæus*, a fish inhabiting the waters of the Great Cave of Kentucky, has recently been detected in a considerable number of species of Insects discovered in the very caverns of the Tyrol whose waters afford a *habitat* to the Proteus†. It may be supposed that the non-development of eyes in all these animals is a part of their original constitution, and is to be looked upon as an example of the adaptation of their organisms to the peculiar conditions of their existence; and such a view cannot at present be positively disproved. But the actual dependence of the nutrition of the visual organs, or (at least) of the nervous apparatus which forms the essential part of them, upon the continued agency of light, appears from the well-known fact, that if, by the complete opacity of the cornea, light is entirely prevented from entering the eye, the retina and the optic nerve become atrophied, and in time altogether lose their characteristic structure; thus clearly indicating the direct influence of light in keeping up those nutritive actions, by which the integrity of that structure is normally maintained.

That *Electricity*, also, has an important influence on the operations concerned in the development and maintenance of organized structures, can scarcely be doubted by any one who duly considers the proofs of the disturbance of the electric equilibrium in those parts of vegetable as well as animal bodies which are in a state of greatest functional activity, afforded by the observations and experiments of Prof. Matteucci and others. At present, however, it would be premature to make any positive statement as to its *modus operandi*; although it would certainly appear most probable that it is more directly related to the chemico-vital changes of composition which take place in the living body, than to the operations of cell-growth, multiplication, and development, properly so called.

If the views advocated in this communication be correct, it follows that not merely are the *materials*, withdrawn from the inorganic world by vital agencies, given back to it again by the disintegration of the living structures of which they have formed

* See Dr. Baird's "Natural History of the Entomostracous Crustacea" (published by the Ray Society), p. 192.

† Specimen *Faunæ Subterraneæ*, Bidrag til den underjordiske Fauna, ved J. C. Schiödte: Kjöbenhavn, 1849.

a part, but all the *forces*, which are operative in producing the phenomena of life, are in the first place derived from the inorganic universe, and are finally restored to it again. The author thinks it not difficult to show that such is actually the case; the very same antagonism existing, in respect to the relation of the Vegetable and Animal kingdoms respectively, to the *forces* of the universe, as exists in regard to their *material components*. Plants, it will be recollected, form those organic compounds at the expense of which animal life (as well as their own) is sustained, by the decomposition of carbonic acid, water, and ammonia; and the *light*, by whose agency alone these compounds can be generated, may be considered as metamorphosed into the *chemico-vital affinity* by which their components are held together. The *heat* which plants receive, acting through their organized structures as *vital force*, serves to augment these structures to an almost unlimited extent, and thus to supply new instruments for the agency of light and for the production of organic compounds. The whole *nisus* of vegetable life may be considered as manifested in this production; and in effecting it, each organism is not only drawing *material*, but *force*, from the universe around it. Supposing that no animals existed to consume these organic compounds, they would be all restored to the inorganic condition by spontaneous decay, which would reproduce carbonic acid, water, and ammonia, from which they were generated. In this decay, however slow, the same amount of Heat would be given off, as in more rapid processes of combustion; and the faint luminosity which has been perceived in some vegetable substances in a state of eremacausis, makes it probable that the same is true of Light. And though the process of decay may be prevented or modified, so that the whole or a part of the materials of vegetable structures are disposed of in other ways, yet whenever they return to the condition from which they were at first withdrawn, they not only give back to the inorganic world the materials out of which they were formed, but the light and heat to which their production was due. Thus in making use of the stores of Coal which have been prepared for his wants by the luxuriant flora of past ages, man is not only restoring to the atmosphere the carbonic acid, the water, and the ammonia which it must have contained in the carboniferous period, but is artificially reproducing the Light and Heat which were then expended in the operations of vegetable growth. That the relative proportion of the light and heat thus restored, should be the same as that which they originally bore to each other, is by no means necessary; since each (according to Prof. Grove's views) is convertible into the other*. In the few cases in which *motion* is affected by the vital force of plants, this may be considered as restoring to the inorganic universe a certain measure of the force which they have derived from it, in the form of light and heat.

But the organic compounds which the agency of Light and Heat upon the Vege-

* [In the second edition of his Essay on the "Correlation of the Physical Forces," just published, Prof. Grove advances the opinion (p. 59) that when Light is "absorbed" (to use the ordinary phraseology), that is, when it ceases to manifest itself *as* light, it is usually converted into Heat.—Nov. 20, 1850.]

table structures has produced, are destined for a much higher purpose than that of being merely given back to the inorganic universe by eremacausis or combustion. In serving as the food of Animals, they not merely become the materials of their structures, but are rendered subservient to the production of the nervous and muscular forces. The animal, like the plant, receives *heat* from external sources; and this is expended, in the form of vital force, not merely in the building-up of the organism from its germ, but also in its subsequent maintenance. For, as was first definitely stated by Prof. Liebig, the vital force, which is applied in Plants to the extension of the structure, is appropriated in Animals to the development of muscular and nervous power; and this development, depending as it does upon a continual disintegration of the tissues which are its instruments, requires as continual a reconstruction of them. The organizing force required for this reconstruction or maintenance, appears, like that employed in the original operations of development, to be supplied by Heat; and it is a confirmation of this view, that we should find a provision (in those classes of animals which are constructed for the greatest development of nervo-muscular power) for the maintenance of a constantly high temperature, by the combustion of a portion of the organic compounds supplied to them as food.—Of the amount of *light* which is appropriated by Animals, we have no means of forming an estimate; but from the limited nature of its action on their economy, it probably bears an insignificant proportion to that which is applied to the purposes of vegetable nutrition. Thus, then, the forces on which the animal is essentially dependent, are the *affinities* which hold together the elements of its food, and which are embodiments (so to speak) of the light and heat by whose agency they were combined; the *heat*, which it derives in part from the physical universe, and in part from the combustion of some of its alimentary materials; and the small amount of *light* required by them, which is supplied from external sources alone. These forces may be considered as in a state of *continual restoration* during the whole life of animals, in the heat, light, and electricity, and still more in the motion, which they develope; and, after their death, in the production of heat and light during the processes of decay. During animal life there is a continual restoration to the inorganic world of carbonic acid, water, and ammonia; and the amount thus given up by the animal organism bears an exact proportion, on the one hand, to the amount of heat and motion which are generated by it, and on the other to the amount of organic compounds consumed as food. So that, on the whole there is strong reason to believe that *the entire amount of force of all kinds* (as of materials) *received by an animal during a given period, is given back by it during that period*, his condition at the end of the term being the same as at the beginning. And all that has been expended in the building up of the organism, is given back by its decay after death.

In bringing this communication to a close, the author would remark, that he has not sought in it to increase the knowledge of existing *facts*, so much as to develope new

*relations* between those already known. He has preferred, in fact, rather to build upon the foundation afforded by the generally admitted facts of Physiological science*, than to go in search of phenomena, his account of which might be questioned by those indisposed to admit his leading ideas. If those ideas be correct, they will be found, he believes, to afford a precision to Physiological doctrines which they have never before possessed; and to open out a vast number of new lines of inquiry, which promise an ample harvest of results, not only valuable in a scientific view, but likely to be fertile in applications to various departments of the therapeutic art. At any rate, it is very important that Physiological science should be considered under the same *dynamic* aspect, as that under which the Physical sciences are now viewed by the most enlightened philosophers; and he trusts that the present attempt may thus aid in its advancement, even if it should answer no higher purpose.

---

*Supplementary Note.*—[Since the foregoing paper was written, the author's attention has been drawn to the fact, that Mr. NEWPORT had been led, in the year 1845—"by the close relation shown by Dr. FARADAY to subsist between light and electricity, and by MATTEUCCI between electricity and nervous power, and by the known dependence of most of the functions of the body on the latter,"—"to consider light as the primary source of all vital and instinctive power, the degrees and variations of which, he suggested, may, perhaps, be referred to modifications of this influence on the special organization of each animal body." (See "Athenæum" for Dec. 6, 1845.) These views were embodied in a paper "On the Natural History of *Meloë*," presented to the Linnæan Society, and printed in the 20th volume of its Transactions. But as the passages in which they had been enunciated were omitted by the desire of the Council of that Society, no other public record of them exists than that just cited.—Nov. 20, 1850.]

* [To his mode of stating some of these facts, the author is aware that exceptions may be taken; but he trusts that it may be perceived that his argument is a *cumulative* one, and that his conclusions rest upon a large number of *independent* probabilities. Consequently, even if *some* of his data should be found questionable, it does not follow that the validity of his general doctrine is disproved.—Nov. 20, 1850.]

## XXXVII. *On the Condition of certain Elements at the moment of Chemical Change.*

*By* Benjamin Collins Brodie, *Esq.*, *F.R.S.*

Received June 6,—Read June 20, 1850.

THE experimental inquiry which I now lay before the Society is so intimately connected with certain theoretical considerations, in which it took its rise, and which are necessary to its right comprehension, that I am unwilling to separate them. These considerations alone can explain why it appeared to me desirable to devote much time and labour to the determination of a simple analytical problem, which it has been open for the last thirty years to any chemist to undertake, but which, although doubtless connected with some of the most curious and obscure phenomena of chemical science, no one has thought it worth his while to enter upon. The reason of this may have been, that from other points of view this inquiry seemed of little importance, or, which is also probable, the question may have been, at various times, partially investigated, and the answer to it thought to be other than what it truly is, because approached from a wrong side. I shall therefore lay before the Society theory as well as experiment; for the theory is necessary to render the experiment intelligible, although this latter, in so far as it is true, has an independent value, and may be explained by others in some totally different manner.

The difference which chemists draw between the chemical elements and all other bodies, is far greater and indeed of altogether another kind to that which exists between any two compound substances. Other bodies are composed and decomposed; but applied to the elements, these words are altogether inappropriate; when the element is formed there is no chemical synthesis, and when it passes from the free to the combined state, there is no chemical decomposition. This difference the atomic theory expresses by assigning to the two classes of bodies a different molecular constitution. The element it considers as consisting of single and isolated atoms, and all other bodies as systems more or less complex of combined particles. This fundamental difference of conception is well given in the following passage from Berzelius*:—"Les atomes d'un même corps élémentaire ne possèdent aucune force de combinaison mutuelle; ils n'adhèrent ensemble qu'en vertu de la force d'agrégation. Plus deux corps élémentaires se ressemblent quant à leurs propriétés chimiques, moins ils tendent à s'unir, et le nouveau corps qui resulte de leur combinaison, a tant d'analogies avec ses éléments constituants, qu'il diffère peu d'un mélange mécanique. Plus, au contraire, les corps élémentaires diffèrent de propriétés chimiques, plus la

* Berzelius, Traité de Chimie, Paris, 1845, vol. i. p. 25.

force de combinaison qu'ils exercent les uns sur les autres est grande et plus aussi les propriétés de leurs composés diffèrent de celles de leurs éléments. C'est là un problème dont je ne pourrais entreprendre la solution qu'en traitant de l'influence de l'électricité sur la matière."

This view, although the received doctrine, has not passed quite unquestioned. Ampère invented a molecular theory, which led him to conclusions inconsistent with it. For reasons not of a chemical nature only, but which had reference principally to the propagation of light and sound and to other physical phenomena, he had arrived at the idea that in every chemical substance there were what may be called three forms of matter, the indivisible atom, the molecule or system of atoms, and the particle or system of molecules. He conceived, moreover, that every gas contained in the same space an equal number of these molecules. From this it was a necessary inference, that in that contraction which takes place when oxygen and hydrogen combine to form water, a division must take place of the elemental molecule. He considered that the oxygen divided, half a molecule of oxygen combining with each molecule of hydrogen*. On this view therefore the atoms, even of the elements, formed what was in a certain sense a compound group. The discovery of isomeric forms of hydrocarbon in different states of condensation, and of other similar facts, gave rise to new ideas as to the possible differences of bodies, and explanations similar to that by which the differences between certain isomeric organic bodies have been accounted for came to be applied to the case of the elemental bodies themselves, Thus the allotropy of sulphur has been explained by assuming it, in its various forms, to be the same substance in different states of condensation, in which case the difference between these forms might be expressed by giving to them the different chemical formulæ of S, $S_2$, $S_3$. Those physical relations however of density and specific heat, which might give a true scientific value to such speculations, and prove that these substances were really thus connected, have not yet been made out to exist; nor indeed has any fact been discovered which places such a notion beyond a conjecture. Graham again, to explain the mode in which the metals conduct electricity in the voltaic circuit, assigns to these bodies what he terms a sali-molecular structure, and regards them as consisting of two atoms of a chlorous or acid combined with one atom of a zincous or basile element, "the three atoms of the molecule being of one metal and of the same nature†." The latest work in this direction is a paper of M. Laurent, in which he has attempted, among other things, to account for the differences in the different classes of salts of the same metal in which, hitherto, different oxides of a different degree of saturation have been supposed to exist, by assuming them to contain different molecules or atomic groups of the metal; and he has shown how, on this idea, our classification of chemical substances may be much simplified; on this

* Annales de Chimie, vol. lviii. p. 434. See also Gerhardt, Comptes Rendus des Travaux de Chimie, 1847, p. 90, note.

† See Graham's Chemistry, Ed. 1842, pp. 226 and 541.

view it is necessary to suppose that the present elemental atoms are susceptible of a yet further division*.

These ideas, however philosophical and suggestive, are yet, it must be allowed, very hypothetical. The proof of the compound nature of a chemical substance is of a very simple kind. It lies in the fact, that it has been made by the composition of certain parts, or broken up into those parts, or at least in some phenomena which are supposed to be the evidence of this. Indeed the rational formula of a chemical substance is but a memorandum of its reactions, and a particular mode of expressing the law of the synthesis and analysis of the body, apart from which it has but little meaning. The true nature therefore and chemical formula of the elemental bodies, as of all other substances, is to be discovered by the study of the series of chemical changes in which they are formed, and by the phenomena which they present when they pass into the combined condition. There are even well-known facts of great importance in this point of view, some unexplained, and some, I conceive, misinterpreted.

The point which I shall seek to establish is this,—that at the moment of chemical change a chemical difference exists between the particles of which certain elemental bodies consist, perfectly the same in kind to that which exists between the particles of compound substances under similar circumstances, and on which the phenomena of combination and decomposition depend. That a peculiar chemical relation exists between two particles which combine, is generally admitted and expressed by the term affinity. The electro-chemical theory has defined more exactly in what this affinity consists, and states that the two particles are to one another in a positive and negative electric relation. But I do not know that it has ever been pointed out that this chemical relation—this affinity between the particles of a substance—is an essential condition of the decomposition as well as of the composition of the body. As I am about to infer a chemical difference between the particles of the element from the fact of their chemical separation, I must say a few words upon this point, and I shall simplify the whole question by stating briefly the mode in which I consider chemical change to be effected. I may do this sufficiently for my present purpose in the following propositions:—

1. That when two particles chemically combine, a certain chemical relation exists between them which is expressed by the terms positive and negative. The chemical difference of the particles I term the difference between their conditions in this respect.

2. That when chemical combination takes place between the particles of which any two or more substances consist, a chemical difference exists between the particles of each substance, so that the particles of the same substance are to one another in a positive and negative relation.

3. That the chemical relation between any two particles of these substances is

* Comptes Rendus des Travaux de Chimie, August 1849.

determined by the chemical relation of all the other particles with which they are for the time being associated. Substances, the particles of which are to one another in this peculiar chemical relation, I term chemically polar.

The electro-chemical theory was developed before even the true laws of the propagation of electricity had been discovered, and in the above propositions I have but transferred to chemical change some of the more exact ideas as to the nature of electric action which have since arisen; and we may transfer the ideas and mode of thought without making any hypothesis as to the mutual relation of the phenomena. This is not the place to enter fully on this question, and I shall confine myself to the application of these principles to explain certain phenomena of change in compound substances, to which I shall presently show the parallel in the case of the element. These phenomena are those which go under the name of the "phenomena of the nascent state."

Silver cannot be oxidized by the direct action of oxygen on the metal, but oxide of silver is readily formed by boiling the chloride of this metal with potash. The particles of oxygen and silver have therefore acquired by this association with the chlorine and potassium a chemical relation or affinity which at other times they have not. This is the fact. The rational conception of the fact is given in the expression

$$\underbrace{\overset{+}{\mathrm{Ag}}\,\overset{-}{\mathrm{Cl}}\,\overset{+}{\mathrm{K}}\overset{-}{\mathrm{O}}}=\mathrm{AgO}+\mathrm{K\,Cl},$$

in which I have indicated the polar relation of the substances. The chemical relation therefore between the oxygen and silver is essentially dependent on the chemical relation between the oxygen and potassium, in the same way as a negative and positive electricity are related to each other. The same is true of the relation between any other two particles of the system. Hence chemical decomposition is an essential condition of chemical combination; so that when we see one of these events we may infer the other.

On the other hand, where this polar division of the substance cannot take place, there is no chemical action, or at any rate it takes place with greater difficulty; thus anhydrous sulphuric acid may (as has been shown by Millon) be distilled off carbonate of potash without alteration, and generally the so-called anhydrous acids have none of the combining properties of the hydrates to which they correspond. The reason of this being, that when these bodies combine they do not decompose, and that it is by the very fact alone of the decomposition of the substance that the combining power is developed in the particles of which they consist, so that in the chemical change which is thus represented—

$$\underbrace{\overset{+}{\mathrm{H}}\mathrm{SO_4}\,\overset{+}{\mathrm{K}}\overset{-}{\mathrm{O}}}=\mathrm{HO}+\mathrm{SO_4K},$$

the two combinations which take place are not two combinations accidentally simul-

taneous, but correlative and mutually dependent phenomena which we cannot separate.

In the case of double decomposition, each of the four substances which enter into the change is combined, but it does not appear that this state of combination is necessary to the action. It can take place also, and in the same manner, when the combining substances are only in contact with each other, and not in combination, provided always that there is the right chemical difference between them, which however is essential. Thus, for example, when iodine and phosphorus decompose water (in the usual mode of the formation of hydriodic acid), the chemical relation between the iodine and phosphorus is an essential condition of the action. The same remark applies to the decomposition of water between nitric oxide and chlorine, which can be effected by neither body separately; so that the changes which take place in these experiments are not simply due to the fact that the chlorine or iodine stand in one relation to water, or to the elements of water, and the nitric oxide or phosphorus in another, and that thus the water breaks up, being acted upon by two opposite forces; but that there is also, and must be, a certain chemical difference between the chlorine and nitric oxide and between the iodine and phosphorus, which is as essential and important a condition to the propagation of the action as their relation to the water itself, and indeed without which they could not have this relation. I am not aware that this remark has before been made, nor do I think it likely that it should have been made, but upon the view which I have given, of which it is a consequence.

Facts corresponding to these cases of composition are to be observed, as might be expected, in the decomposition of bodies, for if decomposition be the condition of combination, so of course must combination be the condition of decomposition. FARADAY long since showed that dry carbonate of lime withstands the highest temperatures and is not to be decomposed by heat, but that when a little steam is thrown upon the heated carbonate, decomposition takes place with facility. Why is this? but that the water is the medium for the transference of the polar action which can now take place with the division of the masses: thus—

$$\underbrace{\overset{+}{\mathrm{Ca}}\,\overset{-}{\mathrm{CO_3}}\,\overset{+}{\mathrm{H}}\overset{-}{\mathrm{O}}}=\mathrm{CaO}+\mathrm{CO_3H}.$$

I might mention many other examples of the same class.

On the view which I have here given of the nature of chemical change, the very existence of the elemental bodies was a strange and unaccountable anomaly. I have regarded the molecular structure of bodies but as an expression of the law of their synthesis and analysis, and this law again as a result of the peculiar nature of chemical force. It was therefore truly difficult to conceive how an element in the sense of BERZELIUS was formed. The formation of this "uncombined particle" was a fact quite different to the formation of a compound substance, and yet it seemed as unreasonable to suppose that the laws of chemical action should vary in different

materials, as that the laws of motion should be different in different bodies. I therefore considered attentively what we really knew of the laws of chemical change in these bodies. Examples occurred to me, both of the chemical division and chemical synthesis of the elements, by which various phenomena hitherto obscure might be explained. The experiments of the first class prove that a division of the elemental bodies which is known to occur in certain cases of chemical change, is truly a chemical and not simply a mechanical division of these substances. This is shown by the fact that the particles of the element thus separated show the peculiar combining properties of "nascent bodies." It is not necessary to my argument that the precise view which I have given of the nature of this "nascent state" should be admitted; provided only it be allowed, that these properties depend upon the fact that the particle is issuing from a state of combination, which is generally allowed.

1. No theory of chemical change has given rise to more discussion among chemists, than the usual mode of the formation of sulphuric acid by the mutual action of sulphurous acid, nitric oxide, air and water. On this question there are some six recognized theories. The problem is simply this: Why, when the oxygen is made a part of this system of particles, does it possess oxidizing properties which otherwise it has not? On the view I have stated the cause is plain. When nitric oxide acts chemically upon oxygen, the gas is thrown into a polar condition; the result of which is to give to other particles of the mass a combining power, in a direction the reverse of that in which the oxygen combines with the nitric oxide; the change being in all respects analogous to the decomposition of water by the joint action of nitric oxide and chlorine*; thus—

$$\underbrace{\overset{+}{N}O_2\,O\overset{-}{O}\,\overset{+}{S}O_2}=NO_3+SO_3.$$

The best of the other explanations of this fact is, in my opinion, that of Péligot†, who considers the formation of the sulphuric acid to be the result of the successive formation and decomposition of nitric acid. This, however, does but shift the difficulty to another point; for why does nitric acid oxidize sulphurous acid? In truth, in this case, a perfectly similar polarization takes place within the acid itself—

$$(NO_5=)\underbrace{\overset{+}{N}O_3\,\overset{-}{O}\,O\,\overset{+}{S}O_2}=NO_4+SO_3.$$

* In the following experiments I am compelled to call by the same name three very different things—the isolated element, the particles of the element at the moment of their chemical separation or synthesis, and the combined element; and I wish to observe, that when I state that there is a chemical difference between the particles of the element, I mean simply the particles of which the element consists. The chemical nature of these particles is a further question.

† Annales de Chimie, 3rd Series, vol. xii. p. 266. Péligot states that nitric oxide always forms hyponitric acid and no nitrous acid, in contact with atmospheric air; but it by no means follows, even if this be the substance formed with atmospheric air alone, that the same substance is formed in the presence of sulphurous acid; indeed, on the view I have given, a difference in the reaction would rather be anticipated.

For the formation of the hyponitric acid from the nitric acid is just as much the formation of a new chemical substance as if it were made by the direct action of oxygen upon nitric oxide, and is attended with a similar division of the oxygen. But this stage of the formation of nitric acid is useless, and not necessary to the conception of the change; for there are other perfectly parallel cases which do not admit of such an explanation.

2. I will take the formation of chloro-sulphuric acid, in the remarkable experiment by which Regnault prepared this body*. Olefiant gas, as usually prepared from alcohol and sulphuric acid, contains a large quantity of sulphurous acid; when chlorine is brought in contact with this mixture of gases, two substances are formed, chloro-sulphuric acid, $SO_2Cl$, and the Dutchman's liquid, $C_4H_4Cl_2$. Upon sulphurous acid alone (in the circumstances under which the experiment is made) chlorine has no action whatever, nor, according to Regnault, upon olefiant gas, when both gases are dry, and only in diffused daylight. The formation, therefore, of this body is due to the polar division of the chlorine, just as the formation of sulphuric acid to the polar division of the oxygen; the olefiant gas being to the chlorine in the same relation as the nitric oxide to the oxygen in the other experiments, so that we may conceive the change to take place thus—

$$\underbrace{\overset{+}{C_2}H_2\overset{-}{Cl}\overset{+}{Cl}\overset{-}{SO_2}} = C_2H_2Cl + ClSO_2.$$

This example is not open to those objections which, from the formation of the oxides of nitrogen, might be raised to the other instance, for here the combinations mutually determine each other. With water, the chloro-sulphuric acid decomposes with the formation of sulphuric and hydrochloric acids; but through this experiment we can distinctly trace back the cause of the formation of the sulphuric acid, in this, as in the more usual mode of its formation, to the polarization of the element; and on considering attentively the mode of the formation of chemical substances, it may be seen that the formation of a large class of compounds, among which are the oxides of chlorine and iodine, is ever preceded by a similar fact.

3. It is well known that when a mixture of hydrogen and any oxide of nitrogen† is passed over heated spongy platinum, the oxide of nitrogen is decomposed and ammonia and water formed. Were the hydrogen a compound substance, it would be thought that the simultaneous formation of these substances was sufficiently explained, by saying that it was a case of double decomposition, and it is indeed the same phenomenon; thus—

$$\underbrace{\overset{+}{N}\overset{-}{O_3}\overset{+}{H_3}\overset{-}{H_3}} = 3HO + NH_3,$$

the hydrogen being "*nascent*" from itself.

* Annales de Chimie, 2nd Series, lxix. p. 170, and lxxi. p. 445.

† See Kuhlmann, Liebig's Annalen, vol. xxix. p. 286.

4. We know from the researches of H. Rose, that in a neutral solution of the bichloride of mercury, the mercury is precipitated on zinc in the form of a black powder, but on the addition of an acid the metal becomes bright and the zinc is amalgamated*. The addition of bichloride of mercury also instantly stops the most violent evolution of hydrogen from the action of hydrochloric acid upon zinc, with the formation of the same amalgam. These curious experiments, which certainly caused much surprise in Rose, become intelligible from the considerations which I have mentioned. The combination of zinc with mercury is a combination in a different direction to that of the zinc with chlorine, hence the latter determines and causes the first; thus—

$$\underbrace{\overset{+}{H}\,\overset{-}{Cl}\,\overset{+}{Zn}\,\overset{-}{Zn}\,\overset{+}{Hg}\,\overset{-}{Cl}}=H\,Cl+Zn\,Hg+Zn\,Cl.$$

5. A very beautiful illustration of the way in which one chemical combination determines another, is seen in another experiment with the same metal. Zinc, it is known, decomposes slowly, with evolution of hydrogen, a strong and boiling solution of caustic potash; but when into the solution a few crystals of nitre or nitrite of potash are thrown, the zinc is rapidly dissolved with the evolution of ammonia. The reason of this I consider to be, that the polar division of the zinc now takes place with the greatest facility, the zinc being oxidized in two directions; the zinc decomposes the water, by which a polarity is given to the hydrogen, which causes it to combine with the nitrogen of the nitric acid to form ammonia, by which combination the other particles of the nitric acid become in their turn polar and oxidize again the zinc; the action, as it were, proceeding from and returning back again to that element. The change, for example, may be represented thus:—

$$\underbrace{\overset{+}{H_3}\,\overset{-}{O_3}\,\overset{+}{Zn_3}\,\overset{-}{Zn_3}\,\overset{+}{O_3}\,\overset{-}{N}}=NH_3+6ZnO.$$

6. To the preceding experiments I will only add the phenomena of substitution, which, viewed in relation to them, assume a new form. The division of the chlorine which takes place in substitution is a very similar fact to that distribution of the element which takes place in the formation of chloro-sulphuric acid (which I have before cited), and admits of a similar explanation. The problem is, why, with even the smallest quantity of chlorine, does a portion of the chlorine ever combine with the organic body? Why is the hydrogen never simply removed? The solution is, that one of these two changes determines the other, precisely as the combination with olefiant gas determines the combination with sulphurous acid. Nor do I see what intelligible distinction is to be drawn between the action of chlorine on the organic body and that of hydrogen on nitric oxide, or between either of these two cases and that of water itself on chloro-sulphuric acid. The organic body behaves as though it were a simple compound of hydrogen on the one hand, and the remaining ele-

* Liebig's Annalen, vol. lxiv. 283.

ments of the system on the other, and this, during the action and under the influence of the chlorine, it may truly be.

If it be true that in the preceding experiments this polar division of the element takes place, (a division, at any rate, in many points analogous to the decomposition of the compound body when no elemental substance is isolated, but the particles are transferred from one system to another,) it cannot but be, that in the *formation* of the element the correlative fact is to be observed, and that the element itself is made by the synthesis of polar particles. This is indicated by theory, and although the more usual mode of forming these elemental bodies is not such as to bring to light the true nature of this synthesis, there are other, although as yet rarer, instances of the formation of these bodies, which not only are not opposed to this view, but prove it.

1. When an acid is added to a perfectly pure solution of an alkaline iodide, such as may readily be procured by precipitating any iodate it contains by baryta water and filtering, the solution remains perfectly clear. Neither, when an acid is added to a pure solution of iodate of potash, is there any alteration, but on mixing these solutions an abundant precipitate of iodine is formed. It is said that the iodate and iodide of zinc, without acid, undergo a similar decomposition. It is very plain that these changes are simple cases of what is called double decomposition. The hydriodic and iodic acids decompose one another, and it is my opinion that in the change

$$IO_6H+5HI=6HO+6I,$$

whatever be that combining relation which subsists between the oxygen and hydrogen, that same relation must also be between the particles of the iodine itself. What is commonly called the affinity of hydrogen for oxygen is not sufficient to account for this change, for hydrogen alone will not decompose the iodic acid, unless it be in the nascent condition. When hydrochloric acid is the decomposing body, chloride of iodine is formed, when hydriodic acid, the iodine itself. Are we not to admit that these two substances are formed according to the same law? To this synthesis of the iodine, the division of the element which takes place at the formation of the hydriodic and iodic acids, is the correlative fact, to explain which we must assume the same polar difference between its particles (see page 765).

2. In the course of his researches on the hypophosphites, Wurz discovered a very singular substance, the hydruret of copper*. This substance is formed by the action of hypophosphorous acid upon copper salts. It readily decomposes, so that it is not easy to determine its constitution, but his analyses very closely corresponded with the formula $Cu_2H$. That this is truly the formula of the substance, may be inferred with yet more certainty than from the analyses, from the following curious reaction.

* Berzelius attempted to throw some doubt upon the existence of this body, but the correctness of the facts, as stated by Wurz, is guaranteed, not only by the well-known skill and ability of this chemist, but also by the fact that Poggendorff had succeeded in procuring a hydruret of copper by the electrolysis of the sulphate of this metal.

In contact with strong hydrochloric acid hydrogen is evolved, and the protochloride of copper, $Cu_2Cl$, formed. Both substances are decomposed, and Wurz satisfied himself, and gives the experiments, which show that the volume of the hydrogen evolved was the double of that due to the simple decomposition of the substance. I will add the remark which he makes on this experiment:—"On sait que l'acide chlorhydrique n'attaque le cuivre qu'avec une extrême difficulté, et la presence de l'hydrogène, loin de favoriser la réaction, devrait, d'après les lois de l'affinité, y ajouter un nouvel obstacle. La décomposition de l'hydrure de cuivre par l'acide chlorhydrique paraît donc s'effectuer en vertu d'une action de contact*."

This fact, the conception of which offers these theoretical difficulties, becomes perfectly intelligible, and indeed might have been predicted from the principles I have laid down. The decomposition is perfectly similar to that of the suboxide of copper under analogous circumstances, arises from the same cause, and may be expressed thus—

$$\underbrace{\overset{+}{Cu_2}\,\overset{-}{H}\,\overset{+}{H}\overset{-}{Cl}} = Cu_2Cl + H_2.$$

This experiment enables us to see clearly the cause of a class of decompositions very analogous to it, and which have presented similar theoretical difficulties†. An alloy of platinum and silver will dissolve in nitric acid, which will not act upon the platinum alone; acids will, in like manner, dissolve the alloy of copper and zinc‡, which on the copper alone have no action. Now the hydruret of copper is itself, in its chemical relations, an alloy, and the action of the acid on the alloy of copper and zinc is a fact very analogous to the action of the hydrochloric acid upon this body, and the explanation of this fact involves similar phenomena; thus—

$$\underbrace{\overset{+}{H}\,\overset{-}{Cl}\,\overset{+}{Zn}\,\overset{-}{Cu}\,\overset{+}{Cl}\,\overset{-}{H}} = Cl\,Zn + Cu\,Cl + H_2,$$

the polar composition of the hydrogen being essential to the comprehension of the experiment. A further confirmation of this view is found in the decomposition by water of the remarkable bodies discovered by Frankland§, to which he has given the names of zinc-methyl and zinc-ethyl. The theoretical analogy of these bodies to the hydrogen compounds of the metal is perfect, and with water they give a precisely similar reaction to that of the hydruret of copper with hydrochloric acid. Zinc-ethyl, for example, breaks up thus—

$$\underbrace{\overset{+}{Zn}\,\overset{-}{C_4H_5}\,\overset{+}{H}\overset{-}{O}} = C_4H_5\,H + ZnO,$$

in which decomposition the hydrogen and the hydrocarbon (which is the analogue of

* Annales de Chimie, 3rd Series, vol. xi. 251.

† These facts have been cited by Liebig with another view. Liebig's Annalen, vol. xxx. p. 262.

‡ Gmelin's Handbuch, vol. iii. p. 448.

§ Journal of the Chemical Society, January 1850.

hydrogen) are to one another in the same polar relation, and fulfill the same part in the change as the two equivalents of the hydrogen itself in the decomposition of the hydruret.

3. When a solution of bichromate of potash is poured into a strong and acid solution of the peroxide of barium in hydrochloric or nitric acid, a violent effervescence and escape of oxygen takes place; apart, these solutions are perfectly stable; bring them together, they are both decomposed; the chromic acid passes into chloride of chrome, the peroxide of hydrogen into water, and the oxygen formed is due to the simultaneous decomposition of both bodies, thus—

$$3ClH+2Cr\,O_3+3HO_2=Cr_2\,Cl_3+6HO+3O_2.$$

I certainly regard the oxygen itself, in this experiment, as the true reducing agent, and I believe that the chromic acid is decomposed by the oxygen of the peroxide of hydrogen, according to the same law of decomposition, and for the very same reason, as it would be by hydrogen itself if a piece of zinc were thrown into the acid solution, this reason being the polarity of the particle induced by chemical change. In this experiment is brought before us, in a very forcible manner, the very slight difference which truly separates the phenomena of oxidation and reduction, which are usually regarded as so distinct. In speaking of the formation of sulphuric acid, I have said that the oxidation of sulphurous acid by nitric acid is to be attributed to a polar condition of the oxygen liberated from the nitric acid, which polar condition is induced by the formation of hyponitric acid within the system of which it forms a part. Now the formation of water in the peroxide of hydrogen is a fact precisely similar to the formation of the hyponitric acid in the nitric acid, and it might reasonably be anticipated that this oxygen would have a similar oxidizing power. This is in truth the case; for when the temperature is low, the solutions dilute, and the experiment carefully managed, no gas is given off, but a deep blue solution is formed, containing perhaps, as stated by Barreswil*, who first examined this reaction, a higher oxide of chrome. This solution however rapidly decomposes, oxygen is evolved, the blue colour disappears, and the final result is the same as if the compound had never been formed. When manganate of potash, peroxide of manganese and various other substances are substituted for the chromate of potash in this experiment, a similar decomposition takes place, but without any signs of the intermediate stage of oxidation. Under other circumstances the oxidation and reduction may be separated. Thus, when peroxide of barium is thrown into an acid solution of the prussiate of potash, the prussiate is oxidized and the red prussiate is formed. When, on the other hand, the same experiment is made with the alkaline or neutral solution of the red prussiate, oxygen gas is given off in abundance from the peroxide of barium as well as from the red prussiate, and the latter passes into prussiate. On adding to this solution an acid solution of perchloride of iron, care being taken that

* Annales de Chimie, vol. xx. p. 364.



FRANKLIN INSTITUTE

the whole of the peroxide of barium is decomposed, prussian blue is produced in abundance. In this experiment one atom of oxygen is first added, and this atom is then removed by the contact of another atom under suitable circumstances. I infer therefore from these experiments, not that the oxidation is a necessary antecedent to the disoxidation, but that the spontaneous decomposition of the oxidized body and the reduction of the chromic acid, where no oxidation takes place, and the oxidation of the body, are due to one and the same cause, namely, to the mutual attraction of the elemental particles. When, for example, arsenious acid is oxidized by the action of chlorine, I consider that the oxygen is oxidized as well as the arsenic. We are led to the same conclusions by various well-known experiments; in the case, for example, of the decomposition of the nitrate of ammonia on boiling, when this compound breaks up into water and nitrogen, thus—

$$\underbrace{\overset{+}{N}O_4\overset{-}{H}_4\overset{+}{N}\overset{-}{}}=4HO+N_2;$$

while from no point of view is it very logical to draw a distinction between two facts so very similar as the formation of the water and the nitrogen, it is proved, by the experiments I have cited, that the mutual attraction of the particles of the nitrogen is a most important condition of the change.

The transition from these cases of spontaneous decomposition to other instances, in which no one of the substances usually called compound is formed, but the elements alone are liberated, is obvious; and I cannot but think that these phenomena, viewed as the last of a series of chemical changes, proceeding from the simplest case of double decomposition to the curious experiments I have just cited, each successive link of which is bound to the preceding by the closest analogies, reasonably admit of a very different interpretation to that which we should put upon them when regarded out of this connection. It is hard to draw a distinction between the decomposition of the chloride of nitrogen and of the nitrite of ammonia. From quite independent considerations, the conclusion is forced upon us, that the mutual attraction of the particles of chlorine and of nitrogen plays a most important part in other cases of chemical change. Why may we not admit that in this case the decomposition is determined solely by these relations? The heat which attends upon this and other similar decompositions is, on the electro-chemical theory, as confessed by its greatest supporters, an inexplicable enigma. Heat is the constant sign of combination, but here it asserts is only decomposition, so that theory and fact are plainly at issue. On the other hand, admitting that in this experiment the formation of the elements is a true chemical synthesis, the evolution of heat is accounted for; and as the elements, chlorine and nitrogen, are far more permanent forms of matter, and less readily altered by chemical action than the chloride of nitrogen, so it is reasonable to believe that the particles of which they are composed are in a far more intimate state of combination. The transition from these experiments to the most ordinary cases of the formation of

the element is obvious, it being plain that the reduction of oxide of silver* into oxygen gas and the metal, differs only from the spontaneous decomposition of the chloride of nitrogen in the temperature at which it takes place.

In the preceding statement, I have used the word polar to express that alternate difference of the condition of the particles by which I conceive chemical action to be propagated. It is no objection to the use of this word that it is undefined, and that I have not pointed out in what this difference consists. It may be a real difference, which we can use for purposes of thought and inquiry, and yet an unknown difference, to which we cannot at present assign a true value. A more serious objection lies in the way in which this word has been misused, and the false associations which, in some minds, are connected with it. It is, however, not difficult for those who must ultimately fix the meaning of this term, to draw the distinctions necessary to its right application; and as I myself have found the word very useful, and also found that through the associations which are rightly connected with it, it conveyed to some persons, whose opinion was well worth considering, an idea which could not otherwise have been so simply given, I have here used it. At the same time let me observe, that that to which I wish to direct the attention of chemists, is to a new analogy between certain chemical changes and to the correlation of phenomena which have not before been grouped together, and, provided that analogy and relation be recognized, the word by which it is expressed is of less importance†. I now proceed to an experimental inquiry which originated in the considerations I have here given.

The discoverer of the peroxide of hydrogen, Thénard, observed certain singular and remarkable properties of this compound, of a kind altogether new and calculated to fix the interest and attention of chemists. To prepare the peroxide of hydrogen, according to his directions, is a process so troublesome and tedious, that it may have deterred chemists from the further and full investigation of these phenomena. It is at any rate to Thénard alone that we owe whatever knowledge we possess of this singular body. Since his investigation, which dates from the year

* In certain cases we can trace the very mode in which this decomposition by heat takes place. Thus in the decomposition of chlorate of potash by heat, the true way in which this substance is decomposed is, as discovered by Serullas, the decomposition of one particle by the next. The chlorate is first oxidized to perchlorate, and this perchlorate, as shown by Millon, again reduced to chlorate with evolution of oxygen. Thus the action proceeds by a continual oxidation and reduction of the substance, the phenomena being very similar to the oxidation of the chromic acid by the peroxide of hydrogen and the spontaneous decomposition of the compound formed. By mixing the chlorate of potash with oxide of copper, the formation of the perchlorate is entirely prevented, and the action converted into one of spontaneous decomposition.

† The idea of polarity has been applied to the explanation of chemical phenomena by other chemists as well as myself. I may refer especially to Löwig's Introduction to his Organic Chemistry (vol. i. p. 1. Edition 1845). Graham also has given, in the last edition of his Treatise on Chemistry, a chapter on Chemical Polarity. It would be out of place to enter here on any criticism of their views or comparison of them with my own, but I give the reference for those who may be desirous to see the way in which others have treated this subject.

1818, no new fact of the slightest importance has been added to its history. The properties however of which I speak, can all be observed with the solution of the peroxide of barium, in hydrochloric or acetic acid, which can be readily prepared. The properties of this solution are different according as it is alkaline or acid. The alkaline solution is of an unstable nature; even at ordinary temperatures it continually loses oxygen, and on heating undergoes rapid decomposition. The acid solution is more permanent, may be long kept without sensible alteration, and may even be heated to the boiling-point with no evident evolution of gas. Either solution, however, is violently decomposed when certain substances (among which finely divided carbon or platinum are very effective) are thrown into it. In these cases the peroxide is decomposed, while the carbon and platinum remain, as far as we know, unaltered. There are however other bodies which cause this decomposition with perhaps greater energy, and themselves undergo a chemical change of the most surprising nature; these bodies are all those metallic oxides which can readily be reduced,—the oxides of gold, and silver and mercury, and the peroxides of lead, manganese, nickel and other similar substances. These bodies decompose the solution, as does platinum or carbon, while the substances themselves also, during the decomposition, lose oxygen, and are reduced either to a metal or to a lower degree of oxidation. The solution, whether acid or alkaline, is ever decomposed by these bodies; but the facility with which the substance itself is reduced, and in some cases whether this reduction takes place at all, depends upon the neutral or acid condition of the solution, and varies with the particular substance taken in a way on which it is not now necessary to dwell. The decomposition caused by platinum and carbon, however strange, is not quite without parallel. But the simultaneous reduction of the peroxide of hydrogen and the oxide of silver is a solitary fact, by the side of which chemists have been able to place scarcely an analogous much less a similar instance. Yet eminent chemists have offered an explanation of these phenomena, and if these are adequate, further inquiry is unnecessary. I shall not criticise the absolute or the relative value of these explanations; but they add so much to the interest of the question, so clearly show the difficulties under which chemical theory has laboured in dealing with these facts, and also, as I believe, how inadequate it has proved to meet them, that I shall briefly mention the most remarkable.

The following quotation gives the impression made by these facts upon Thénard, who first discovered them:—

"Quelle est la cause des phénomènes que nous venons d'exposer? Voilà maintenant ce qu'il s'agit de rechercher. Pour cela qu'il nous soit permis de rappeler ceux que présentent l'oxide d'argent et l'argent avec le nitrate oxigéné neutre du potasse. L'argent très divisé dégage rapidement l'oxigène de ce sel; il ne s'altère point, et le nitrate oxigéné devient nitrate neutre.

"L'oxide d'argent dégage plus rapidement encore que l'argent l'oxigène du nitrate oxigéné; lui-même est décomposé, il se réduit, l'argent se précipite tout entier, et l'on

ne retrouve dans la liqueur que du nitrate neutre de potasse ordinaire. Or, dans ces décompositions, *l'action chimique est évidemment nulle*; il faut donc les attribuer à une cause physique; mais elles ne dépendent ni de la chaleur, ni de la lumière; d'ou il suit qu'elles sont probablement dues à l'électricité. Je chercherai à m'en assurer d'une manière positive; je chercherai aussi à savoir si la cause, quelle qu'elle soit, ne pourrait point être produite par le contact de deux liquides, et même de deux gaz. De là, découlera peut-être l'explication d'un grand nombre de phénomènes*."

An idea as to the possible cause of these phenomena was thrown out, some years back, by another distinguished French chemist, Dumas, which, although but an incidental observation and unaccompanied with any experimental research, has a special interest as giving the scientific conception of these facts from the electro-chemical point of view, from which this chemist then regarded them.

"La répulsion que les molécules de même signe exercent l'une sur l'autre, répulsion qui nous a servi à expliquer plus haut les effets qu'on observe dans la formation des composés multiples, va nous servir maintenant à expliquer aussi ceux que l'on observe entre deux corps qui contiennent un excès de molécules semblables. Ces corps tendent à se décomposer mutuellement par suite de cette action répulsive.

"En effet c'est ainsi qu'on peut se rendre compte de l'action des acides sur beaucoup de peroxides qui perdent sur leur influence une partie de leur oxygène, c'est ainsi qu'on peut concevoir l'action si bigarre et si remarquable de l'eau oxygenée sur certains oxides. Ce composé perd par le contact de l'oxide d'argent, par exemple, la moitié de son oxigène repasse à l'état d'eau, *chasse* l'oxigène de l'oxide et le ramène à l'état métallique. Quant on envisage ce simple fait avec les anciennes idées de l'affinité, il est inintelligible, tandis qu'avec les idées électriques il pouvait en quelque sorte être prévu†."

Another view has been put forward by Liebig. These experiments with the peroxide of hydrogen he places by the side of the fermentation and decay of organic bodies, of which chemical changes he thus gives the cause‡:—"The cause," says he, "is the power which a body possesses in the act of decomposition or composition to elicit the same action in a body in contact with it, or to render it capable of undergoing the same change which itself experiences. Thus the decomposition of the ferment decomposes also the sugar, and the decomposition of the peroxide of hydrogen decomposes the metallic oxide." The simultaneous decomposition of the two substances is the fact. That it is the very chemical change itself in the one instance which determines the chemical change in the other; this relation Liebig has pointed out. But why and how, consistently with what we otherwise know of the nature of chemical action, and the mode of its transference and propagation, this can be the

* Annales de Chimie, 2nd Series, vol. ix. p. 98?

† Dumas, Chimie Appliquée aux Arts, vol. i. Introduction, p. 64.

‡ Liebig's Annalen. vol. xxx. pp. 280, 262 and 279.

case, is a problem which remained to us, and which, in the case of one at least of these experiments, it was my hope to solve.

Hitherto, in the breaking up of the oxide of silver and the peroxide of hydrogen, no chemical fact has been recognised but the simultaneous decomposition of two chemical substances. This is that fact for which it has been so difficult to account. Were it, for example, a hydride of silver which was thus decomposed and water formed and not simply oxygen, the experiment would have attracted no attention. On the view I have given, the formation of the oxygen itself is as truly a chemical synthesis as the formation of water, and may be substituted for it in a chemical change. This supplies an explanation of these facts at once adequate and simple; the oxide of silver in this experiment being reduced by the oxygen of the peroxide of hydrogen, just as in other cases it might be by hydrogen; the formation of the silver from the particles of which it is composed being the corresponding fact in the decomposition of the oxide of silver to the formation of water in the peroxide, so that we may represent the change thus:—

$$\underbrace{\overset{+}{H}\overset{-}{O}\overset{+}{O}\overset{-}{O}\overset{+}{Ag_{\frac{1}{2}}}}\ \overset{-}{Ag_{\frac{1}{2}}} = HO + O_2 + Ag.$$

No one can be more sensible than I am of the wide interval which exists between such a mode of representing a chemical change and an ascertained fact. The very form in which I have just expressed the decomposition involves an important assumption, an assumption indeed on which, in my opinion, the whole question rests. If it be true that these bodies are thus decomposed in definite and equivalent proportions, and that the simultaneous decomposition of the bodies proceeds according to this law, it is impossible to deny the chemical relation of these changes and the mutual chemical action of the substances; and, on the other hand, if the formation of this oxygen is to be regarded as a true chemical synthesis, this synthesis must follow the universal law of the formation of chemical substances, and the masses must combine in definite and equivalent proportions. It is only the apparent absence of this relation between the decomposing bodies which removes fermentation from ordinary chemical changes, and causes its chemical nature to be denied; and in that parallel which Liebig draws between these decompositions and fermentation, it is tacitly assumed that in this case also, as well as in the case of fermentation, no such relation exists. The following words of Liebig, from the paper I have already referred to, clearly show this point:—"A certain quantity of ferment is required to cause fermentation in a portion of sugar; its action however is *no action of mass*, but is entirely limited to its presence up to that moment when the last atom of sugar is decomposed. It is therefore no peculiar body, no substance or matter which effects decomposition, but these are the carriers of an activity* which extends itself over the sphere of the decomposing body."

* "Träger einer Thätigkeit." Liebig's Annalen, vol. xxx. p. 279.

It was therefore the quantitative relation of the decomposing substances which seemed to me the essential point to be determined, and which experiment alone could decide; for it was quite possible (and indeed had been taken for granted) that the action varied according to some other law. It might have none of the characters of a chemical change; it might, for example, vary directly with the acting masses, or with the temperature alone, or be a function, so to say, of so many variables that the true law of action would be altogether hidden.

*Preparation of the Peroxide of Barium.*

The baryta used in the following experiments was prepared by the ignition of the pure nitrate in a crucible of fine white earthenware. This was protected externally by a common earthenware crucible, and the space between the two filled up with crucible dust. The nitrate was thrown gradually into the crucible, one portion being thoroughly decomposed before the addition of the next. Baryta, as commonly prepared, contains large quantities of peroxide, as may readily be ascertained by dissolving in hydrochloric acid and adding bichromate of potash to the solution; and a very long and strong ignition is necessary to drive off the last portion of oxygen. The purest baryta is not porous, but perfectly compact, very heavy, and of the crystalline grain of fine marble. The baryta thus prepared contains traces only of matter from the crucible, the adhering particles of which are to be carefully broken off, and hardly any impurities, but a little water, and a very little carbonic acid. If an ordinary Hessian crucible be used for its preparation, as was the case with the baryta used in some of the earlier of my experiments, the baryta will be very impure.

To prepare the peroxide, oxygen was passed over the baryta, broken into pieces of the size of a small pea and placed in a combustion-tube, which was heated in an ordinary charcoal trough. The oxygen was made from peroxide of manganese and carefully freed from carbonic acid, and dried before entering the tube. The gas was contained in a gas-holder so as to regulate the current, and was passed over the peroxide, after all absorption had ceased, until the tube was cool. The temperature necessary for the absorption is a low red heat, which is not to be exceeded, as a portion of oxygen is given off at a higher temperature. The operation may be distinctly followed through the tube, the baryta glowing when the stream of gas comes in contact with it. The absorption is both rapid and complete; and I have repeatedly made the experiment of attaching to the end of the tube, where the oxygen not absorbed would pass out, a small tube dipping into mercury, and have found that the experiment can readily be so regulated that a considerable stream of gas will enter at one end of the tube and not a bubble pass out at the other; and indeed the absorption was often so rapid that the gas was absorbed faster than it entered, and the mercury rose several inches in the tube; the whole oxygen therefore is absorbed.

The peroxide presents after the experiment a mass of uniform texture and appearance, and is very white, the baryta itself being of a darker colour. A little of the

powdered substance, moistened with water on the back of the hand, gives no sensible heat. The peroxide was carefully freed from any adhering glass, or pieces in which the absorption was incomplete, from which it may be distinguished by the colour, and was preserved in stoppered bottles over sulphuric acid; a precaution which was desirable, as the preparations had to be preserved for a long time without any alteration in the per-centage of oxygen.

The peroxide of barium thus obtained is a perfectly stable body. When dry, it is only a very intense heat which can drive off its oxygen. It is nearly insoluble in water, the filtered solution giving no gas with oxide of silver, which would be the case if any substance were dissolved; and when preserved from the action of the carbonic acid of the air, it may be long kept even in water without any sensible evolution of gas. When the powdered substance is even boiled with water, no gas is given off; and after long boiling, on examining the dried residue, I have found that the effect of boiling has actually been to increase the per-centage of oxygen, the baryta, of which a certain quantity is always present, being dissolved. These facts are contrary to the usual statements*, and probably this stability only belongs to a very pure substance, for a small quantity of the oxides of iron or of manganese would alter these reactions.

The peculiar experiments of the reduction of the metallic oxides, as stated by Thénard and other chemists, are referred to the peroxide of hydrogen; and it is on the peculiar instability of this body that the explanation of Liebig of these phenomena rests, the spontaneous decomposition of the peroxide being considered as antecedent to and necessary to set up the action in the other substances. I was however anxious to see whether the peroxides of metals themselves would not produce similar effects; and on placing the peroxide of potassium (the mass which is produced by the action of potassium on melted nitre) in contact with moist chloride of silver in water, I found that the chloride was reduced, just as it might be by zinc, and oxygen evolved; and the same takes place with the iodide, bromide, cyanide, nitrate and oxide of silver and with other metallic combinations. Water alone, as is well known, decomposes the peroxide of potassium; this body therefore was in a similar unstable state to that supposed in the peroxide of hydrogen; but on extending my experiments to the peroxide of barium itself, I found that all the reductions which could be made with the peroxide of hydrogen, took place with this body also with the greatest facility. Finely-divided platinum, silver or carbon, decompose it, but far less rapidly than those substances which are themselves also decomposed. I will not here discuss the general chemical reactions of this peroxide, but defer their consideration until I can treat with advantage, in a more exact manner, of the general theory of this action.

The facts I have just mentioned gave a direction to my experiments, and instead of the peroxide of hydrogen, the preparation and preservation of which involved many difficulties, and with which it was inconvenient to work, I determined to use, in the experiments I proposed, the peroxide of barium itself.

* See Barium superoxyd, Handwörterbuch der Chemie, vol. i. p. 667.

Before the study of these decompositions was possible, it was necessary to have some ready and accurate method of determining the amount of oxygen in the various preparations of the peroxide, which could never be obtained absolutely pure and corresponding to a theoretical formula, and of which I cannot indeed find that any satisfactory analysis has yet been made.

After various experiments I selected two methods, which combined the advantage of great facility of execution with perfect agreement in their results. One of these methods depends on the chemical change which takes place when the peroxide of barium is brought in contact with an acid solution of chromic acid, when, as I have before mentioned, both the peroxide and the chromic acid are decomposed with evolution of gas. Supposing this to be a definite and constant reaction, we have, it is evident, in the evolved gas, a measure of the oxygen in the peroxide, from which, if the reaction were known, the latter might be calculated. For this, however, it was necessary first to discover the nature of the decomposition. The other method depends on the decomposition of the acid solution of the peroxide by finely-divided platinum or carbon, in which case the oxygen evolved is plainly half the total oxygen in the peroxide itself. For the determination of the oxygen in the preparation of a small quantity of the peroxide, it was quite practicable to weigh the baryta before and after the absorption of the gas; and although this plan could not be applied to those larger quantities of the substance which it was desirable to prepare at once, yet, as there could be no doubt as to the general accuracy of the determination if the experiment were conducted with care, I availed myself of it for determining the reaction in question with chromic acid, and for a general control over the methods. The baryta was placed in a platinum tube about 8 inches long and half an inch wide, and the whole experiment conducted precisely in the manner already described in the preparation of the peroxide. The tube was first weighed empty, the ends being closed with dry corks, again with the baryta, and again after the experiment. The peroxide was then rapidly pounded and used for the other determinations. A glass tube cannot be used for this experiment, as the glass is always slightly acted upon, where in contact with the baryta, which, although of little consequence in an experiment on a large scale, as causing an impurity in the peroxide, yet gives rise to a discrepancy between the amount of oxygen calculated from the absorption and the percentage of oxygen deduced from the other experiments.

Two experiments, conducted in this manner, gave the following results:—

A. 12·581 grms. of baryta increased in weight 0·952 grm., corresponding to an increase in weight of 7·53 on 100 parts.

B. 15·180 grms. of baryta increased in weight 1·111 grm., corresponding to an increase in weight of 7·318 on 100 parts.

Hence the two preparations of peroxide of barium contained respectively—

Preparation A, 7·03 per cent.; preparation B, 6·81 per cent. of oxygen in addition to the oxygen of the baryta.

The experiment with the acid solution of chromic acid was made thus:—a weighed quantity of the peroxide was mixed with a very large excess of powdered bichromate of potash in a small flask, such as is often used for the determination of carbonic acid, provided, that is, with a drying tube (in this case filled with small pieces of caustic potash) and a small tube reaching to the bottom of the flask, through which a little air might be drawn after the conclusion of the experiment. Strong hydrochloric acid was contained in the usual small tube, and the whole experiment, in short, conducted precisely as a carbonic acid determination. It is essential to the accuracy of the experiment that care should be taken to have present a great excess of bichromate (at least three or four times the weight of the peroxide taken), an excess of acid, and also to have fresh potash in the drying tube, as there is a considerable rush of gas, and a little carbonic acid or water might otherwise pass through the tube. The peroxide, however, in a good preparation contains a mere trace of carbonate; and I have made the experiment of passing the gas from the potash tube through baryta water, and have found that no carbonic acid escaped the apparatus, with a far more violent evolution of gas than need take place in the experiment.

I. 2·1015 grms. of the preparation A. gave a loss of 0·243 grm., corresponding to a loss of 11·56 on 100 parts of the substance taken.

II. 2·1265 grms. of the preparation A. gave a loss of 0·252 grm., corresponding to a loss of 11·85 on 100 parts of the substance.

III. 2·2127 grms. of the preparation B. gave a loss of 0·268 grm. corresponding to a loss of 12·11 on 100 parts of the substance.

IV. 2·0975 grms. of the preparation B. gave a loss of 0·259 grm., corresponding to a loss of 12·34 on 100 parts of the substance.

V. 2·0395 grms. of the preparation B. gave a loss of 0·243 grm., corresponding to a loss of 11·91 on 100 parts of the substance.

From these experiments it results that in this reaction the chromic acid loses three and the peroxide four equivalents of oxygen, that is, that the total loss is to the loss from the peroxide as 7 : 4. For calculating on this hypothesis the amount of oxygen in the two preparations, we find for the preparation A. from experiments I. and II. respectively, 6·60 and 6·67 per cent. of oxygen, and for the preparation B. from experiments III., IV. and V., 6·91, 7·05 and 6·80 per cent. of oxygen, which are the numbers given in the other experiments. The reaction would therefore be represented thus—

$$2CrO_3 + 4BaO_2 = Cr_2O_3 + O_7 + 4BaO.$$

This method has the advantage of giving a considerable loss of oxygen with a small quantity only of the substance; and the perfect agreement with one another of numerous experiments made in this way, led me to place in it the greatest confidence. Facts, however, afterwards came to my knowledge, which proved that this action was not so absolutely uniform as had at first appeared; and although under the circumstances, and with the precautions (especially as to the relative quantities of the sub-

stances) which I have mentioned, the entire agreement of the experiments proves that the action is that which I have here given, yet this threw a certain doubt upon it, and it is only in some of my first experiments that I have used this plan of determining the oxygen uncontrolled by the following.

The determinations with platinum were made in a little apparatus of a very simple construction, which, as I shall elsewhere have occasion to mention it, I will call a bulb apparatus.

A is a small flask in which the weighed substance, together with a small portion of finely-divided platinum (prepared from platinum black by ignition) or of animal charcoal, which is equally effective, is placed. B is a glass bulb holding about two fluid ounces, which, before the experiment, is filled with dilute hydrochloric or acetic acid, and is closed by a well-ground stopper. C is a drying tube of potash. After weighing the apparatus, the stopper is loosened and the acid allowed to flow into the interior. The evolution of gas takes place immediately, but goes much slower than in the experiments with chromic acid. After eighteen or twenty hours the apparatus is again weighed, when the action may be considered terminated. It is, however, of course, to be weighed again until it ceases to lose weight. During the experiment a second potash tube, or a small tube dipping into a vessel of lime, is to be attached to the first, to prevent any increase of weight by absorption of moisture from the atmosphere. The following experiments were made in this manner:—

I. 2·389 grms. of the preparation A. gave a loss of 0·162 grm.
II. 2·437 grms. of the same gave a loss of 0·162 grm.

These experiments correspond to a loss per cent. of

| I. | II. |
|---|---|
| 6·78 | 6·64 |

III. 2·615 grms. of preparation B. gave a loss of 0·175 grm.
IV. 2·785 grms. of the same gave a loss of 0·184 grm.

These experiments correspond to a loss per cent. of

| III. | IV. |
|---|---|
| 6·63 | 6·60 |

These determinations entirely agree with each other; and the per-centage of oxygen in the substance is probably in fact (as is given by this experiment) a little less than that calculated from the amount of oxygen taken up, as in pulverizing it it is not possible to prevent the absorption of a little water by the baryta present, which must diminish the per-centage of oxygen. There is no violent rush of gas during the

experiment, nor is any variation of the action to be feared. I consider therefore this method to be as accurate as can be desired.

*Experiments with Metallic Oxides.*

The method of weighing the loss of oxygen, which succeeds very well for determining the amount of oxygen given off in the preceding experiments, cannot be employed with advantage for determining the amount given off by a metallic oxide in contact with the peroxide of barium. The evolution of gas is not rapid, continuing, at ordinary temperatures, sometimes for several days before all action ceases, during which time the apparatus is liable to alter in weight; and also more water is required to dissolve the baryta than can be introduced into the bulb of the apparatus, or conveniently and accurately be weighed. In these experiments, therefore, I determined indirectly the amount of oxygen given off by ascertaining the amount of metal reduced.

The form of the experiment was very simple. The weighed peroxide was intimately mixed in a flask with the metallic oxide, and a certain portion of water, about twelve ounces, poured upon the mixture. In the following experiments, those at the temperature of the air were placed in a cellar where the temperature was uniform, so that they might be comparable with one another, and the action was allowed to continue until all evolution of gas had ceased. In the experiments at 100° and at other temperatures, the water was first brought to the temperature required, then poured on the mixed substances and the mixture kept at the same temperature, either boiling or in a water-bath, during the action. In the experiments with oxide of silver, to determine the silver reduced, the residue, after the evolution of the gas had ceased, was treated with very dilute hydrochloric acid, with which it was allowed to remain in contact at least twelve hours. All oxide was thus converted into chloride. The fluid was now filtered from the residue and the hydrochloric acid washed out, the bulk of the solid substance being still kept in the flask in which the experiment was made. From this residue, consisting of chloride of silver and metallic silver, the silver was extracted by boiling with nitric acid, the substance on the filter being added to the rest and the filter also treated with acid. The solution was diluted and the silver dissolved, which was in fact the silver reduced, estimated as chloride. It is plain, that whether the oxide were reduced to metal or to a lower degree of oxidation, this silver must still be a correct measure of the oxygen lost. This method of determining the loss of oxygen I followed in all the experiments with silver compounds.

My first experiments were made before I had ascertained all the points necessary for the careful preparation of the peroxide, and the preparations used for these contained considerably less per-centage of oxygen than that which I afterwards readily procured, and contained also impurities from which the other preparations were free; in these experiments also the oxygen was determined only with bichromate of potash and hydrochloric acid. These circumstances in no way affect their general

result. But as the conclusions which they indicated were afterwards brought out and confirmed by experiments not open to these objections, it would be superfluous to give in their case also the numerical details of the determinations. As however they threw much light on the general nature of the inquiry, I cannot omit some account of them.

In the Tables which follow, I have arranged the chief results of these experiments.

The column A. contains the amount of oxygen $=a$ in 100 parts of the peroxide of barium employed, as given by the determination with bichromate of potash. The column B. contains the relative loss of oxygen from the metallic oxide; the loss, that is, calculated on 100 parts of the peroxide of barium. This loss $=\psi$. The column C. contains the ratio of the quantity of oxygen in the peroxide of barium to the loss from the metallic oxide; the ratio, that is, of $a:\psi$ and the calculated value of $\psi$. In the column D. I have given the approximate ratio of the oxygen in the amount of peroxide of barium taken, to that in the oxide of silver or peroxide of lead taken in each experiment. The first Table contains the experiments made at 100° C. The first six experiments were made with oxide of silver, the rest with peroxide of lead. In the case of the peroxide of lead, the amount of oxygen lost by the peroxide was determined by extracting the residue after the experiment with very dilute nitric acid, which, leaving the peroxide, dissolves the oxide formed. The lead thus dissolved was estimated as sulphide.

Experiments at 100° C.

| | A. | B. | C. | | D. |
|---|---|---|---|---|---|
| 1. | 4·03 | 1·65 | 5 : 2 | 1·61 | 3 : 2 |
| 2. | | 1·64 | | | |
| 3. | 4·18 | 1·95 | 2 : 1 | 2·09 | 3 : 2 |
| 4. | | 2·08 | | | 1 : 1 |
| 5. | 5·85 | 3·08 | 2 : 1 | 2·92 | AgO not weighed. |
| 6. | | 2·99 | | | |
| 7. | 4·32 | 1·85 | 5 : 2 | 1·72 | 5 : 4 |
| 8. | | 1·71 | | | 1 : 1 |
| 9. | 6·10 | 3·31 | 7 : 4 | 3·48 | $PbO_2$ not weighed. |
| 10. | | 3·37 | | | |

Classifying these ten experiments with reference to the ratios given in the third column, we find that they may be arranged thus:—

5 : 2, four experiments.
4 : 2, four experiments.
$3\frac{1}{2}$ : 2, two experiments.

In the next Table the experiments were made below 100°; where the temperature is not given they were at the temperature of the air. The two last experiments were made with the peroxide of lead, the rest with the oxide of silver.

Experiments below 100°.

| | A. | B. | C. | | D. |
|---|---|---|---|---|---|
| 1. | 4·18 | 2·35 T. 38° to 42°. | 7 : 4 | 2·38 | 3 : 1 |
| 2. | | 2·53 | | | |
| 3. | | 2·51 T. 24° to 26°. | 5 : 3 | 2·50 | 5 : 2 |
| 4. | | 2·81 | 3 : 2 | 2·78 | 3 : 1 |
| 5. | 4·32 | 2·93 T. 16°. | 3 : 2 | | |
| 6. | | 3·00 | | 2·88 | About 1 : 1 in the four experiments. |
| 7. | | *2·96 T. 0° upwards. | 3 : 2 | | |
| 8. | | 2·77 | | | |
| 9. | 4·47 | 3·25 | 4 : 3 | 3·35 | AgO not weighed. |
| 10. | | 3·30 | | | |
| 11. | 6·10 | 4·21 | 3 : 2 | 4·06 | $PbO_2$ not weighed. |
| 12. | | 3·93 | | | |

The experiments in this Table, arranged in the order of ratios, as those at the higher temperature, give the following series:—

$3\frac{1}{2}$ : 2, one experiment.
5 : 3, two experiments.
3 : 2, seven experiments.
4 : 3, two experiments.

These experiments placed beyond doubt, that, under similar circumstances of temperature and mass, the loss of oxygen from the metallic oxide stood in a certain fixed relation to the quantity of the peroxide of barium employed. They showed also (speaking generally) that this loss varied inversely with the temperature, but yet it appeared that within certain limits (II. experiments 5, 6, 7, 8) the temperature might be very considerably altered without affecting the action. This was also the case, to a certain extent at any rate, with the mass; for a perfect agreement was found between experiments where the quantity of oxide of silver taken was considerably varied or even accidental. At the same time it was to be observed, that in determining these ratios a great deal would depend on the limits allowed for the error of analysis; and it was a question of great importance, and yet by no means easy to decide, whether they were absolutely such as I have here assumed them to be; that is to say, whether the difference between two nearly identical experiments was to be attributed to the error of analysis or to a real, though small, difference in the action. I determined therefore to make a more extended series of experiments, in which I might ob-

* The water in these two experiments was cooled down in ice before it was poured on the substances; at this low temperature no gas was given off. The action was allowed gradually to proceed as the temperature rose in the air.

serve the effect of varying the mass, at a constant temperature, and with the same preparation of the peroxide.

The great accuracy of the silver determination and the comparative facility of determining by it the loss of oxygen from the compounds of this metal, caused me to confine to them my attention. Indeed it was plain from experiments I had made with the oxide of mercury, as well as with peroxide of lead, that the general nature of the changes in question was, with any one of these substances, the same.

The following experiments were made with the chloride and the oxide of silver at 100°, and at the temperature of the air: I had already found how very greatly at the lower temperature this circumstance might be varied without alteration of the action; and in this case the experiments are arranged without any special reference to the slight variations of the temperature of the air. The peroxide taken is the same for each series; the general form of the experiments was precisely as already described.

*Oxygen determinations.*

The determinations of the oxygen in the different preparations of the peroxide of barium employed, gave the following results:—

I. Peroxide P.

I.—(1.) 2·8970 grms. of a peroxide (P) gave with hydrochloric acid and bichromate of potash, a total loss of 0·425 grm. of oxygen, corresponding to a loss of 14·67 per cent. on the peroxide.

(2.) 2·9215 grms. of the same substance gave, in a similar experiment, a total loss of 0·427 grm. of oxygen, corresponding to a loss of 14·61 per cent.

The oxygen in 100 parts of the peroxide, calculated from the above experiments, is,—

| I. | II. |
|---|---|
| 8·38 | 8·36. |

(3.) 2·823 grms. of the same peroxide in an experiment with platinum and acetic acid, gave a loss of 0·235 grm., corresponding to a loss of 8·32 per cent. oxygen.

The mean of these three experiments gives 8·35 as the per-centage of oxygen in the substance.

II. Peroxide Q.

II.—(1.) 2·9565 grms. of a peroxide (Q) gave with hydrochloric acid and bichromate of potash, a total loss of 0·457 grm. of oxygen, corresponding to a loss of 15·45 per cent.

(2.) 2·9555 grms. of the same gave in a similar experiment, a total loss of 0·450 grm. of oxygen, corresponding to a loss of 15·22 per cent.

(3.) 2·955 grms. of the same gave with nitric acid and bichromate of potash, a total loss of 0·453 grm. of oxygen, corresponding to a loss of 15·32 per cent.

The oxygen in 100 parts of the peroxide, calculated from the above experiments, is,—

| I. | II. | III. | Mean. |
|---|---|---|---|
| 8·82 | 8·69 | 8·75 | 8·75 |

(1.) 2·6355 grms. of the peroxide gave with platinum and acetic acid, a total loss of 0·227 grm. of oxygen.

(2.) 2·9474 grms. of the same gave with platinum and acetic acid, a total loss of 0·257 grm. of oxygen.

(3.) 2·847 grms. of the same gave with platinum and hydrochloric acid, a total loss of 0·241 grm. of oxygen.

(4.) 2·9815 grms. of the same gave, in a similar experiment, a total loss of 0·254 grm. of oxygen.

These determinations correspond to a loss of oxygen per cent. of—

| I. | II. | III. | IV. | Mean. |
|---|---|---|---|---|
| 8·65 | 8·71 | 8·46 | 8·51 | 8·58 |

### III. Peroxide O.

III.—(1.) 2·4875 grms. of a peroxide (O) gave with platinum and hydrochloric acid, a loss of 0·191 grm. of oxygen.

(2.) 2·515 grms. of the same, in a similar experiment, lost 0·191 grm. of oxygen.

(3.) 2·7296 grms. of the same, in a similar experiment, lost 0·204 grm. of oxygen.

These determinations correspond to a loss of oxygen per cent. of—

| I. | II. | III. | Mean. |
|---|---|---|---|
| 7·67 | 7·59 | 7·47 | 7·57 |

### *Experiments with Chloride of Silver at* 100° C.

The following experiments were made with the peroxide P and chloride of silver at 100° C. The chloride of silver was in the finely-divided state in which it is produced by precipitating nitrate of silver with chloride of sodium. The precipitate with hydrochloric acid cannot so readily be mixed with the peroxide. The chloride of silver was dried either at 100° or at a gentle heat over a lamp; it was, when dried, in the state of a fine powder.

The following Table contains the details of the experiments:—

TABLE I.—A.

| | Peroxide of barium P. | Chloride of silver taken. | Chloride of silver obtained. | Equivalent of oxygen. |
|---|---|---|---|---|
| | grms. | grms. | grms. | grms. |
| 1. | 3·0115 | 0·527 | 0·280 | 0·0155 |
| 2. | 3·014 | 1·003 | 0·3945 | 0·0219 |
| 3. | 3·0865 | 1·404 | 0·5633 | 0·0312 |
| 4. | 3·0455 | 2·057 | 0·8085 | 0·0449 |
| 5. | 3·0036 | 4·011 | 1·019 | 0·0566 |
| 6. | 3·0206 | 5·963 | 1·0573 | 0·0587 |
| 7. | 3·0295 | 7·983 | 1·1815 | 0·0656 |
| 8. | 2·958 | 9·235 | 1·087 | 0·0605 |
| 9. | 2·967 | 11·139 | 1·170 | 0·0652 |
| 10. | 3·0465 | 11·064 | 1·3105 | 0·0728 |
| 11. | 3·0375 | 15·960 | 1·3515 | 0·0739 |
| 12. | 3·0695 | 19·920 | 1·3425 | 0·0745 |
| 13. | 3·0125 | 8·059 | 1·4795 | 0·0822 |

In the second Table, B, which follows, the oxygen equivalent to the reduced silver is compared with the oxygen in the peroxide; the peroxide being taken as 100, and the oxygen therefore as 8·34. In the third Table, the oxygen in the peroxide is taken as the unit. The third and fourth columns in both cases contain the assumed and calculated ratio of the oxygen lost by the peroxide to that equivalent to the reduced silver. I have assumed as this ratio the simplest ratio which agrees with the experiments, as a convenient and sufficiently accurate expression of the loss.

TABLE I.—B.

| | Oxygen in the peroxide of barium P = $a$. | Oxygen equivalent to the chloride of silver reduced = $\psi$. | Ratio, $a : \psi$. | Calculated ratio. |
|---|---|---|---|---|
| 1. | | 0·51 | | |
| 2. | | 0·72 | | |
| 3. | | 1·01 | | |
| 4. | | 1·47 | | |
| 5. | | 1·88 | 9 : 2 | 1·85 |
| 6. | | 1·94 | | |
| 7. | 8·34 | 2·18 | | |
| 8. | | 2·04 | 4 : 1 | 2·08 |
| 9. | | 2·19 | | |
| 10. | | 2·42 | | |
| 11. | | 2·47 | 7 : 2 | 2·38 |
| 12. | | 2·42 | | |
| 13. | | 2·73 | 3 : 1 | 2·78 |

TABLE I.—C*.

| | Oxygen in the peroxide of barium = $a$. | Oxygen equivalent to the chloride of silver reduced = $\psi$. | Ratio, $a : \psi$. | Calculated ratio. |
|---|---|---|---|---|
| 1. | | 6·11 | | |
| 2. | | 8·63 | | |
| 3. | | 12·11 | | |
| 4. | | 17·62 | | |
| 5. | | 22·54 | 9 : 2 | 22·22 |
| 6. | | 23·26 | | |
| 7. | 100 | 26·13 | | |
| 8. | | 24·46 | 4 : 1 | 25·0 |
| 9. | | 26·25 | | |
| 10. | | 29·01 | | |
| 11. | | 29·61 | 7 : 2 | 28·57 |
| 12. | | 29·01 | | |
| 13. | | 32·73 | 3 : 1 | 33·33 |

* In these Tables the experiments are arranged in all cases according to the nature of the actions, and not with reference to the quantities taken of the decomposed bodies. But for the sake of a ready general compa-

100 parts of this peroxide require 149·7 parts of chloride of silver to one equivalent of the oxygen it contains. Hence 3 grms. of the peroxide require 4·491 grms. of the chloride for the same proportion.

In the first four experiments, in which comparatively small quantities of chloride of silver, at most not half an equivalent, were taken, the loss increases nearly with the mass of the chloride, and bears therefore no constant ratio to the loss from the peroxide. In all these four experiments the chloride has been reduced nearly in the same proportion, but yet between the first and second experiment there is a difference which is not found between the other three, as may be seen from the following comparison of the chloride of silver taken with the chloride found.

| Exp. | Chloride of silver taken. | Chloride of silver found. |
|---|---|---|
| 1. | 100 | 53·1 |
| 2. | 100 | 39·3 |
| 3. | 100 | 40·1 |
| 4. | 100 | 39·3 |

It appears from this comparison that in the three last of these experiments exactly two-fifths of the chloride taken are reduced, and we may regard this limit of reduction as the circumstance which here determines the action. The gradual increase of loss, with the mass, does not continue, or the increase becomes very small, for one and three equivalents of chloride give very nearly the same amount of reduced silver, equivalent to exactly one-fourth of the oxygen in the peroxide. There is also a constant ratio of loss, which appears likewise to be connected with the increase of mass where the ratio is as 7 : 2, and there is one exception to the order of the series where the loss does not stand in the same general relation to the mass, which may be observed in the other experiments. In this, however, the same simplicity of ratio prevails, and it is evidently a term of the series; the ratio of the loss being as 3 : 1. It is worthy of observation, that the turning-point of the action where the loss ceases to increase with the mass, lies at any rate near to that point where the decomposing bodies are taken in equal equivalent proportions.

My experiments had led me to suspect that some circumstance connected with the particular preparation of the peroxide employed materially influenced the results. This circumstance might be the proportion of free baryta in the peroxide, which was not quite the same in different preparations, or it might be some peculiarity in the molecular condition of the peroxide itself due to some other cause; I repeated therefore the experiments made with one peroxide with another preparation, and arranged these experiments apart.

The following experiments were made also with chloride of silver at 100°, but with the peroxide Q containing 8·58 per cent. of oxygen. The Tables are of the same nature as before.

rison of these quantities, nearly the same quantity of the peroxide, 3 grms., was, with some few exceptions, always employed. The experiments, as will be seen, do not call for any more exact comparison than can thus at a glance be made.

TABLE II.—A.

| | Peroxide of barium Q. | Chloride of silver taken. | Chloride of silver obtained. | Equivalent of oxygen. |
|---|---|---|---|---|
| 1. | 3·9065 grms. | 4·0015 grms. | 0·5305 grms. | 0·0295 grms. |
| 2. | 2·971 | 5·003 | 0·709 | 0·03952 |
| 3. | 2·9995 | 8·0015 | 0·732 | 0·0408 |
| 4. | 3·0145 | 8·0745 | 0·9845 | 0·0548 |
| 5. | 2·962 | 10·129 | 0·968 | 0·05396 |
| 6. | 3·001 | 11·9955 | 1·003 | 0·05591 |
| 7. | 2·985 | 14·936 | 1·126 | 0·0627 |
| 8. | 2·9545 | 12·0175 | 1·2245 | 0·06826 |
| 9. | 2·9965 | 16·0165 | 1·3205 | 0·07361 |

TABLE II.—B.

| | Oxygen in the peroxide of barium Q = a. | Oxygen equivalent to the chloride of silver reduced = ψ. | Ratio, a : ψ. | Calculated ratio. |
|---|---|---|---|---|
| 1. | | 0·96 | 9 : 1 | 0·95 |
| 2. | | 1·33 | 6 : 1 | 1·43 |
| 3. | | 1·36 | | |
| 4. | | 1·81 | | |
| 5. | 8·58 | 1·82 | 9 : 2 | 1·90 |
| 6. | | 1·86 | | |
| 7. | | 2·10 | 4 : 1 | 2·14 |
| 8. | | 2·31 | 7 : 2 | 2·45 |
| 9. | | 2·45 | | |

TABLE II.—C.

| | Oxygen in the peroxide of barium Q = a. | Oxygen equivalent to the chloride of silver reduced = ψ. | Ratio, a : ψ. | Calculated ratio. |
|---|---|---|---|---|
| 1. | | 11·18 | 9 : 1 | 11·11 |
| 2. | | 15·3 | 6 : 1 | 16·6 |
| 3. | | 15·8 | | |
| 4. | | 21·0 | | |
| 5. | 100 | 21·2 | 9 : 2 | 22·22 |
| 6. | | 21·6 | | |
| 7. | | 24·4 | 4 : 1 | 25·00 |
| 8. | | 26·9 | 7 : 2 | 28·57 |
| 9. | | 28·5 | | |

3 grms. of this peroxide require 4 grms. of chloride of silver as equivalent to the oxygen it contains. Thus the experiments from 1 to 6 in this series, were made with a proportion of the chloride, on the whole greater than the experiments 5 to 9 on the first Table. Yet a great diminution is to be observed in the loss of oxygen; in experi-

ment 1 only 13·2 parts out of 100 of the chloride are reduced. And here the ratio 9 : 2 occupies the place of the ratio 4 : 1 or 8 : 2 on the other series. But the limiting ratio of 7 : 2 is in both series the same, and on the whole a certain increase of loss, although not a gradual increase, is to be observed with the increase of the chloride taken. These experiments confirm the fact, that under similar circumstances the different preparations of the peroxide have a different reducing power.

*Experiments with Chloride of Silver at the temperature of the air.*

The next experiments were made also with the chloride of silver, but at a lower temperature, the temperature of the air. I had already found how very much at this low temperature the temperature might be varied without alteration of the action, and in this case the experiments are arranged without any special reference to the variation of the temperature. The peroxide in the first series was the same as that taken in the last experiments, namely, the peroxide Q containing 8·58 per cent. of oxygen.

TABLE III.—A.

| | Peroxide of barium Q. | Chloride of silver taken. | Chloride of silver obtained. | Equivalent of oxygen. |
|---|---|---|---|---|
| 1. | 3·034 grms. | 4·0125 grms. | 1·366 grms. | 0·076 grms. |
| 2. | 2·9942 | 4·988 | 1·480 | 0·0825 |
| 3. | 3·0275 | 6·1315 | 1·545 | 0·08613 |
| 4. | 2·994 | 8·0905 | 1·9415 | 0·10823 |
| 5. | 2·9742 | 10·016 | 2·043 | 0·1138 |
| 6. | 2·9532 | 14·916 | 2·019 | 0·1125 |
| 7. | 3·014 | 9·9915 | 2·336 | 0·1302 |
| 8. | 2·9915 | 12·9075 | 2·3125 | 0·1289 |
| 9. | 2·0132 | 14·916 | 1·5485 | 0·0863 |

TABLE III.—B.

| | Oxygen in the peroxide of barium Q = $a$. | Oxygen equivalent to the chloride of silver reduced = $\psi$. | Ratio, $a : \psi$. | Calculated ratio. |
|---|---|---|---|---|
| 1. | 8·58 | 2·50 | 7 : 2 | 2·48 |
| 2. | | 2·75 | 3 : 1 | 2·86 |
| 3. | | 2·84 | | |
| 4. | | 3·61 | 7 : 3 | 3·67 |
| 5. | | 3·82 | 9 : 4 | 3·81 |
| 6. | | 3·80 | | |
| 7. | | 4·31 | | |
| 8. | | 4·30 | 2 : 1 | 4·29 |
| 9. | | 4·28 | | |

TABLE III.—C.

| | Oxygen in the peroxide of barium Q = $a$. | Oxygen equivalent to the chloride of silver reduced = $\psi$. | Ratio, $a : \psi$. | Calculated ratio. |
|---|---|---|---|---|
| 1. | 100 | 29·13 | 7 : 2 | 28·57 |
| 2. | | 32·05 | 3 : 1 | 33·33 |
| 3. | | 33·10 | | |
| 4. | | 42·07 | 7 : 3 | 42·85 |
| 5. | | 44·52 | 9 : 4 | 44·44 |
| 6. | | 44·28 | | |
| 7. | | 50·23 | 2 : 1 | 50·0 |
| 8. | | 50·11 | | |
| 9. | | 49·88 | | |

The point to be observed in these experiments is the great increase of reduction at the lower temperature. The comparative experiments in this and the last series, show that from corresponding quantities of the chloride, as nearly as possible twice the amount of silver is reduced; and these experiments, it is worthy of remark, take up the action exactly at the point where the other series terminates, so that the expression of the relative loss forms a continuation of the series of ratios commencing with 7 : 2 and terminating with 2 : 1.

The following are a few experiments made with the peroxide P, containing 8·34 per cent. of oxygen.

TABLE IV.—A.

| | Peroxide of barium Q. | Chloride of silver taken. | Chloride of silver obtained. | Equivalent of oxygen. |
|---|---|---|---|---|
| 1. | 3·020 grms. | 1·012 grms. | 0·5715 grms. | 0·03175 grms. |
| 2. | 3·032 | 2·009 | 0·765 | 0·0426 |
| 3. | 3·0256 | 3·895 | 1·484 | 0·08244 |
| 4. | 3·0005 | 8·879 | 1·733 | 0·0962 |
| 5. | 3·0046 | 6·11 | 1·9495 | 0·1083 |
| 6. | 3·05 | 11·983 | 2·065 | 0·1147 |

TABLE IV.—B.

| | Oxygen in the peroxide of barium P = $a$. | Oxygen equivalent to the chloride of silver reduced = $\psi$. | Ratio, $a : \psi$. | Calculated ratio. |
|---|---|---|---|---|
| 1. | 8·34 | 1·04 | 8 : 1 | 1·04 |
| 2. | | 1·40 | 6 : 1 | 1·39 |
| 3. | | 2·72 | 3 : 1 | 2·78 |
| 4. | | 3·26 | 5 : 2 | 3·33 |
| 5. | | 3·60 | 9 : 4 | 3·70 |
| 6. | | 3·72 | | |

TABLE IV.—C.

| | Oxygen in the peroxide of barium P = $a$. | Oxygen equivalent to the chloride of silver reduced = $\psi$. | Ratio, $a : \psi$. | Calculated ratio. |
|---|---|---|---|---|
| 1. | 100 | 12·47 | 8 : 1 | 12·5 |
| 2. | | 16·06 | 6 : 1 | 16·66 |
| 3. | | 32·61 | 3 : 1 | 33·33 |
| 4. | | 39·08 | 5 : 2 | 40·0 |
| 5. | | 43·16 | 9 : 4 | 44·44 |
| 6. | | 44·60 | | |

The experiments with this peroxide give about the same range of action as with the last. On the whole, however, the loss here, as at 100° with the same substance, is rather less, but the difference is not so apparent.

*Experiments with the Oxide of Silver at* 100° C.

The following are experiments with the oxide of silver at 100° C. The oxide was prepared either by precipitation with baryta water or with a pure potash. It contained no chloride but some carbonate, and was dried at 100°. The peroxide employed was the peroxide P, containing 8·34 per cent. of oxygen; 3·63 grms. of the oxide of silver are equivalent to 3 grms. of the peroxide.

TABLE V.—A.

| | Peroxide of barium P. | Oxide of silver. | Chloride of silver found. | Equivalent of oxygen. |
|---|---|---|---|---|
| 1. | 3·0225 grms. | 0·855 grms. | 0·625 grms. | 0·0347 grms. |
| 2. | 3·0295 | 1·525 | 0·8353 | 0·0463 |
| 3. | 2·9807 | 1·205 | 0·9784 | 0·0543 |
| 4. | 3·006 | 1·832 | 1·165 | 0·0647 |
| 5. | 3·0107 | 2·235 | 1·369 | 0·0760 |
| 6. | 2·997 | 2·920 | 1·5565 | 0·0864 |
| 7. | 2·982 | 4·692 | 1·492 | 0·0831 |
| 8. | 3·007 | 4·890 | 1·510 | 0·0841 |
| 9. | 3·0185 | 6·182 | 1·483 | 0·08238 |
| 10. | 3·601 | 6·266 | 1·874 | 0·1041 |
| 11. | 2·986 | 6·4675 | 1·503 | 0·0837 |
| 12. | 3·067 | 9·339 | 1·6345 | 0·0908 |
| 13. | 3·019 | 11·051 | 1·7325 | 0·09625 |
| 14. | 3·0485 | 7·810 | 1·7785 | 0·0988 |
| 15. | 2·983 | 4·932 | 1·84 | 0·1025 |
| 16. | 3·616 | 15·675 | 2·395 | 0·133 |
| 17. | 2·9725 | 9·5345 | 2·001 | 0·1115 |
| 18. | 3·0075 | 12·2035 | 2·2365 | 0·1248 |

TABLE V.—B.

| | Oxygen in the peroxide of barium P = a. | Oxygen of the oxide of silver reduced = ψ. | Ratio, a : ψ. | Calculated ratio. |
|---|---|---|---|---|
| 1. | | 1·14 | | |
| 2. | | 1·52 | 5 : 1 | 1·67 |
| 3. | | 1·82 | | |
| 4. | | 2·15 | 4 : 1 | 2·08 |
| 5. | | 2·52 | 7 : 2 | 2·38 |
| 6. | | 2·88 | | |
| 7. | | 2·78 | | |
| 8. | | 2·79 | | |
| 9. | 8·34 | 2·72 | 3 : 1 | 2·78 |
| 10. | | 2·88 | | |
| 11. | | 2·80 | | |
| 12. | | 2·96 | | |
| 13. | | 3·18 | | |
| 14. | | 3·24 | 5 : 2 | 3·33 |
| 15. | | 3·43 | | |
| 16. | | 3·67 | 9 : 4 | 3·70 |
| 17. | | 3·75 | | |
| 18. | | 4·14 | 2 : 1 | 4·17 |

TABLE V.—C.

| | Oxygen in the peroxide of barium P = a. | Oxygen of the oxide of silver reduced = ψ. | Ratio, a : ψ. | Calculated ratio. |
|---|---|---|---|---|
| 1. | | 13·66 | | |
| 2. | | 18·22 | 5 : 1 | 20·0 |
| 3. | | 21·82 | | |
| 4. | | 25·77 | 4 : 1 | 25·0 |
| 5. | | 30·21 | 7 : 2 | 28·57 |
| 6. | | 34·53 | | |
| 7. | | 33·33 | | |
| 8. | | 33·45 | | |
| 9. | | 32·61 | 3 : 1 | 33·33 |
| 10. | | 34·53 | | |
| 11. | 100 | 33·57 | | |
| 12. | | 35·49 | | |
| 13. | | 38·12 | | |
| 14. | | 38·84 | 5 : 2 | 40·00 |
| 15. | | 41·12 | | |
| 16. | | 44·00 | 9 : 4 | 44·44 |
| 17. | | 44·84 | | |
| 18. | | 49·63 | 2 : 1 | 50·00 |

These experiments give the same results as those made with the chloride of silver at the lower temperature, and comprise as these a series of ratios beginning with 7 : 2 and ending with 2 : 1. The experiments with the smaller quantities of oxide show

also the same kind of progressive increase of loss, as already observed with the chloride; the increase however is not so constant. In experiments 4 and 5 exactly half the oxide is reduced; the ratio of the oxygen in the oxide of silver taken, to the oxygen from the oxide reduced, being in the two experiments as 100 : 51·2 and 100 : 49·31; the presence however of carbonate of silver in the oxide renders this fact less certain than the similar fact observed in the case of the chloride of silver (Table I.).

I repeated these experiments with another preparation of the peroxide, the peroxide O, containing 7·57 per cent. of oxygen; 3·12 grms. of oxide of silver are equivalent to 3 grms. of this peroxide.

TABLE VI.—A.

| | Peroxide of barium O. | Oxide of silver. | Chloride of silver obtained. | Equivalent of oxygen. |
|---|---|---|---|---|
| 1. | 3·0666 grms. | 2·737 grms. | 1·692 grms. | 0·094 grms. |
| 2. | 3·006 | 3·659 | 1·7146 | 0·0952 |
| 3. | 3·098 | 4·801 | 1·7335 | 0·0963 |
| 4. | 3·007 | 5·426 | 2·0735 | 0·1151 |
| 5. | 3·0806 | 11·592 | 2·5123 | 0·1395 |

TABLE VI.—B.

| | Oxygen in the peroxide of barium O = $a$. | Oxygen of the oxide of silver reduced = $\psi$. | Ratio, $a : \psi$. | Calculated ratio. |
|---|---|---|---|---|
| 1. | 7·57 | 3·09 | | |
| 2. | | 3·16 | 5 : 2 | 3·02 |
| 3. | | 3·10 | | |
| 4. | | 3·85 | 2 : 1 | 37·8 |
| 5. | | 4·52 | 5 : 3 | 4·74 |

TABLE VI.—C.

| | Oxygen in the peroxide of barium O = $a$. | Oxygen of the oxide of silver reduced = $\psi$. | Ratio, $a : \psi$. | Calculated ratio. |
|---|---|---|---|---|
| 1. | 100 | 40·81 | | |
| 2. | | 40·74 | 5 : 2 | 40·00 |
| 3. | | 40·95 | | |
| 4. | | 50·59 | 2 : 1 | 50·00 |
| 5. | | 59·70 | 7 : 3 | 60·00 |

The experiments 1, 2, 3 here correspond to the experiments 6, 7, 8, 9 in Table V.; they give however a considerably greater loss, the ratio being 5 : 2 instead of 3 : 1. This difference, it is probable, extends also to the higher terms in the series, for we

have here a ratio 5 : 3, which is a greater loss than any in the other series of experiments. It is worthy of remark, that the loss per cent. on the peroxide is nearly the same in the two, which might lead us to think that this loss stood in some fixed ratio to the baryta of the substance, with the whole of which the oxygen of the peroxide may be considered to be in combination. This however is doubtless but a coincidence, as the experiments with chloride of silver, made with different preparations of the peroxide, where similar differences exist, do not show this relation.

*Experiments with the Oxide of Silver at the temperature of the air.*

The following experiments were made with the peroxide P (containing 8·34 per cent. of oxygen) and oxide of silver at the temperature of the air.

TABLE VII.—A.

| | Peroxide of barium P. | Oxide of silver. | Chloride of silver found. | Equivalent of oxygen. |
|---|---|---|---|---|
| 1. | 2·999 grms. | 0·824 grms. | 0·528 grms. | 0·2293 grms. |
| 2. | 3·004 | 1·604 | 0·9135 | 0·05075 |
| 3. | 3·017 | 3·123 | 1·3915 | 0·0773 |
| 4. | 3·022 | 3·994 | 1·6815 | 0·0934 |
| 5. | 3·039 | 6·313 | 1·990 | 0·1105 |
| 6. | 3·04 | 7·788 | 2·057 | 0·1142 |
| 7. | 3·029 | 9·400 | 2·041 | 0·1133 |
| 8. | 2·9417 | 2·964 | 2·2055 | 0·1225 |
| 9. | 3·059 | 15·720 | 2·3785 | 0·132 |
| 10. | 15·925 | 26·522 | 13·677 | 0·759 |
| 11. | 3·478 | 9·405 | 2·965 | 0·1647 |
| 12. | 3·021 | 7·6195 | 3·222 | 0·1796 |

TABLE VII.—B.

| | Oxygen in the peroxide of barium P = $a$. | Oxygen of the oxide of silver reduced = $\psi$. | Ratio, $a : \psi$. | Calculated ratio. |
|---|---|---|---|---|
| 1. | | 0·97 | | |
| 2. | | 1·68 | | |
| 3. | | 2·56 | 7 : 2 | 2·38 |
| 4. | | 3·10 | 5 : 2 | 3·33 |
| 5. | | 3·63 | | |
| 6. | 8·34 | 3·75 | 9 : 4 | 3·70 |
| 7. | | 3·74 | | |
| 8. | | 4·16 | | |
| 9. | | 4·31 | 2 : 1 | 4·17 |
| 10. | | 4·76 | | |
| 11. | | 4·70 | 7 : 4 | 4·76 |
| 12. | | 5·94 | 7 : 5 | 5·95 |

TABLE VII.—C.

| | Oxygen in the peroxide of barium P = $a$. | Oxygen of the oxide of silver reduced = $\psi$. | Ratio, $a : \psi$. | Calculated ratio. |
|---|---|---|---|---|
| 1. | 100 | 11·63 | | |
| 2. | | 20·14 | | |
| 3. | | 30·69 | 7 : 2 | 28·57 |
| 4. | | 37·17 | 5 : 2 | 40·0 |
| 5. | | 43·52 | | |
| 6. | | 44·96 | 9 : 4 | 44·44 |
| 7. | | 44·84 | | |
| 8. | | 49·88 | 2 : 1 | 50·00 |
| 9. | | 51·67 | | |
| 10. | | 57·07 | 7 : 4 | 57·1 |
| 11. | | 56·35 | | |
| 12. | | 71·22 | 7 : 5 | 71·42 |

When small quantities of the oxide of silver are taken, the loss is not very different from that at the higher temperature, as is also the case in the experiments with the chloride; but after a certain point the actions diverge, and the total general result gives an entirely different range of action in the two series. In all cases, after a certain point, the mass ceases to have a determinate influence on the action; and here this influence would seem soon to be entirely lost, for after the first two or three experiments, no relation whatever can be traced between the relative masses of the substances and the proportion of reduced silver. At the same time, even these experiments, which we may regard as accidental, arrange themselves in a certain order, and give on the whole higher numbers in the series of ratios than any yet obtained. This series may be extended yet further; thus two experiments with peroxide O, at the temperature of the air, gave—

TABLE VIII.—A.

| | Peroxide of barium O. | Oxide of silver. | Chloride found. | Equivalent of oxygen. |
|---|---|---|---|---|
| 1. | 2·926 grms. | 5·186 grms. | 2·8557 grms. | 0·1586 grm. |
| 2. | 3·06 | 5·064 | 3·0402 | 0·1689 |

TABLE VIII.—B.

| | Oxygen in the peroxide of barium O = $a$. | Oxygen of the oxide of silver reduced = $\psi$. | Ratio, $a : \psi$. | Calculated ratio. |
|---|---|---|---|---|
| 1. | 7·57 | 5·42 | 7 : 5 | 5·40 |
| 2. | | 5·51 | | |

TABLE VIII.—C.

| | Oxygen in the peroxide of barium O = $a$. | Oxygen of the oxide of silver reduced = $\psi$. | Ratio, $a : \psi$. | Calculated ratio. |
|---|---|---|---|---|
| 1. | 100 | 71·59 | 7 : 5 | 71·42 |
| 2. | | 72·78 | | |

These experiments, although made with but small quantities of the oxide, give a loss as great as any made with the other preparation.

Two experiments with the peroxide Q, at the same temperature, gave a yet greater loss.

TABLE IX.—A.

| | Peroxide of barium Q. | Oxide of silver. | Chloride of silver found. | Equivalent of oxygen. |
|---|---|---|---|---|
| 1. | 2·985 grms. | 7·878 grms. | 3·843 grms. | 0·2142 grm. |
| 2. | 2·9544 | 7·9215 | 3·801 | 0·2119 |

TABLE IX.—B.

| | Oxygen in the peroxide of barium Q = $a$. | Oxygen of the oxide of silver reduced = $\psi$. | Ratio, $a : \psi$. | Calculated ratio. |
|---|---|---|---|---|
| 1. | 8·58 | 7·17 | 6 : 5 | 7·15 |
| 2. | | 7·17 | | |

TABLE IX.—C.

| | Oxygen in the peroxide of barium Q = $a$. | Oxygen of the oxide of silver reduced = $\psi$. | Ratio, $a : \psi$. | Calculated ratio. |
|---|---|---|---|---|
| 1. | 100 | 83·56 | 6 : 5 | 83·33 |
| 2. | | 83·56 | | |

This is the greatest amount of loss which I have yet obtained in these experiments with silver compounds, which has never quite equaled the oxygen in the peroxide.

The specific difference in the amount of reduction of the chloride and of the oxide of silver under otherwise similar circumstances with the same preparation of the peroxide, that is, at the same temperature, depends doubtless on the difference in the chemical nature of the substances. It was an interesting matter of inquiry whether this difference would be found with other silver compounds: I have not yet extended my experiments in this direction so far as the importance of the question demands, but the following results show both the identity and the difference which may exist in the reaction.

The following experiments were made at 100° C. with carbonate of silver and with

the peroxide Q, which was used also in the experiments with the chloride (Table II.). Two equivalents of the carbonate were taken to one of the peroxide.

TABLE X.—A.

| | Peroxide of barium Q. | Carbonate of silver. | Chloride of silver found. | Equivalent of oxygen. |
|---|---|---|---|---|
| 1. | 3·025 grms. | 9·2055 grms. | 1·339 grm. | 0·0746 grm. |
| 2. | 3·03 | 9·2085 | 1·490 | 0·0830 |

TABLE X.—B.

| | Oxygen in the peroxide of barium Q = $a$. | Oxygen of the carbonate of silver reduced = $\psi$. | Ratio, $a : \psi$. | Calculated ratio. |
|---|---|---|---|---|
| 1. | 8·58 | 2·46 | 7 : 2 | 2·45 |
| 2. | | 2·73 | 3 : 1 | 2·86 |

TABLE X.—C.

| | Oxygen in the peroxide of barium Q = $a$. | Oxygen of the carbonate of silver reduced = $\psi$. | Ratio, $a : \psi$. | Calculated ratio. |
|---|---|---|---|---|
| 1. | 100 | 28·67 | 7 : 2 | 28·57 |
| 2. | | 31·81 | 3 : 1 | 33·3 |

Two other experiments were made with the same substance at a lower temperature, 17° C.

TABLE XI.—A.

| | Peroxide of barium Q. | Carbonate of silver. | Chloride of silver found. | Equivalent of oxygen. |
|---|---|---|---|---|
| 1. | 2·926 grms. | 9·2075 grms. | 1·714 grm. | 0·95556 grm. |
| 2. | 3·012 | 9·1525 | 1·938 | 0·108 |

TABLE XI.—B.

| | Oxygen in the peroxide of barium Q = $a$. | Oxygen of the carbonate of silver reduced = $\psi$. | Ratio, $a : \psi$. | Calculated ratio. |
|---|---|---|---|---|
| 1. | 8·58 | 3·26 | 5 : 2 | 3·43 |
| 2. | | 3·58 | | |

TABLE XI.—C.

| | Oxygen in the peroxide of barium Q = $a$. | Oxygen of the carbonate of silver reduced = $\psi$. | Ratio, $a : \psi$. | Calculated ratio. |
|---|---|---|---|---|
| 1. | 100 | 37·99 | 5 : 2 | 40 |
| 2. | | 41·72 | | |

These two experiments were made in the small bulb-apparatus used for the oxygen determinations, and thus the total loss of oxygen was estimated as well as the reduced silver. The action proceeds more rapidly than in the experiments with the chloride and oxide, so as to render it probable that a more accurate result might in this manner be obtained with the carbonate than with those substances. In the first experiment the total loss was 12·19 per cent.; in the second, 11·91 per cent. The sum of the oxygen in the peroxide and that due to the silver reduced, as given by the determinations, is in the first experiment 11·84 per cent.; in the second, 12·16 per cent.; which so agree with the other numbers as to show that no oxygen is retained by the substances.

On turning to those experiments with the chloride of silver at 100° C. and at the lower temperature, with which these experiments are comparable (Tables I. and II.), it will be seen that the reduction is nearly the same with the two substances.

With sulphate of silver the result was very different. The two following experiments were made with pure crystallized sulphate of silver and the peroxide Q, at 100° C. In the first experiment one equivalent, in the second two equivalents of the sulphate were taken.

TABLE XII.—A.

| | Peroxide of barium Q. | Sulphate of silver. | Chloride of silver found. | Equivalent of oxygen. |
|---|---|---|---|---|
| 1. | 2·969 grms. | 5·449 grms. | 0·118 grm. | 0·00657 grm. |
| 2. | 3·005 | 10·805 | 0·542 | 0·03021 |

TABLE XII.—B.

| | Oxygen in the peroxide of barium Q = $a$. | Oxygen of the sulphate of silver reduced = $\psi$. | Ratio, $a : \psi$. | Calculated ratio. |
|---|---|---|---|---|
| 1. | 8·58 | 0·221 | 40 : 1 | 0·21 |
| 2. | | 1·00 | 9 : 1 | 0·95 |

TABLE XII.—C.

| | Oxygen in the peroxide of barium Q = $a$. | Oxygen of the sulphate of silver reduced = $\psi$. | Ratio, $a : \psi$. | Calculated ratio. |
|---|---|---|---|---|
| 1. | 100 | 2·57 | 40 : 1 | 2·5 |
| 2. | | 11·66 | 9 : 1 | 11·1 |

The amount of reduction is here so small that the action of the sulphate of silver is very nearly the same as the so-called contact action of platinum. I have already pointed out that the action of very small quantities of the chloride and of the oxide of silver is also of the same nature. In the case of these different chemical substances, therefore, it approaches the same limit, although according to a different law.

I have now brought this investigation to that point at which for the present I shall leave it. I would willingly have attempted to render these tables of experiments more complete, had it not appeared to me that there were certain defects in the method of experimenting which rendered this course unadvisable. One most important question is, whether the series of ratios by which I have expressed the relative loss of oxygen from the two substances is truly an intermittent or a continuous series, that is to say, whether there are or are not certain points where this ratio is constant although the proportions of the masses are varied. That there is with each chemical substance at least one such point, namely, a certain limit of reduction beyond which a great increase of the mass of the substance to be reduced does not alter the action, may, I think, be asserted with confidence, and without in any way implying that all the ratios which these experiments have brought to light are of this nature; yet it is difficult to account for the great coincidence of experiments made with very different proportions of the substances, without admitting a tendency of the action to fall into certain ratios rather than into others. Indeed the experiments appear to me to indicate both that for certain intervals the loss of oxygen truly does vary directly with the mass of the substance reduced, and that in certain other points the mass may be varied and the loss yet be constant. In these experiments, however, I could never secure that perfect agreement between two experiments made under exactly similar circumstances, by which alone I could hope to answer a question demanding such exactness. One principal reason of the anomalies which the experiments occasionally exhibit is doubtless, that by simply mixing the substances, even where the same quantities are taken in two experiments, the same conditions of mass are yet not realized: I therefore turned my attention to other methods of experimenting, by which it is my hope to answer this question in a more exact and satisfactory manner. My experiments are not yet complete, but I may mention, that by operating with solutions, I have obviated this difficulty. Lastly, let me thus sum up the general results of these experiments. First, the amount of oxygen lost by the substance reduced is, under circumstances otherwise similar, in a definite and constant ratio to the quantity of the peroxide of barium employed. Secondly, this loss is greater as the mass of the substance reduced is increased, and diminishes as the temperature at which the reduction takes place is raised. It varies also with the preparation of the peroxide. Thirdly, in each series of experiments there is a certain definite limit of reduction beyond which at any rate a very great increase of the mass of the substance reduced causes no increase of the loss of oxygen*. Lastly, in reference to that chemical question from which this inquiry proceeded, namely, how much oxygen is lost by the substance reduced in proportion to the loss of oxygen from the peroxide of barium, it is to be observed, that however much the circumstances are varied, there are yet two limiting

* It appears from other experiments which I have made, that with each chemical substance there is a specific limit of reduction of this kind; thus, for example, in the experiment with chromic acid (p. 779), the only reason of the constant reaction there obtained, is that by taking a very great excess of the bichromate of potash,

ratios between which the whole action is comprised, either of which may be almost indefinitely approached. These are the limit of least reduction, in which the ratio of the loss from the peroxide of barium to that from the metallic oxide is infinite, or as 1 : 0; and the limit of greatest reduction, which is the ratio of equality, in which the two substances would lose an equal amount of oxygen. This limit also, in no one experiment with any silver compound, have I ever exceeded or reached. The first limit is that in which the action would be a pure reduction by contact, such as takes place when platinum or carbon are the substances which cause the decomposition. The other would be a purely chemical action, such as may be seen in an experiment to which I will now proceed, and which, although perhaps not at first sight as striking as the reduction of the metallic oxides, is, philosophically considered, quite as remarkable, being indeed the same experiment, but detached from circumstances which give in the other case the apparent differences to the reaction.

*Action of Iodine on the Peroxide of Barium.*

It occurred to me, that if it were for the reasons I have stated, that the iodide and chloride of silver decompose the peroxide of barium with the evolution of the oxygen it contains, iodine and chlorine should produce a similar effect. Indeed this was a very critical and important experiment; for we know the action of chlorine and iodine on baryta; and on the view which is usually taken of this decomposition and of other analogous changes, namely, that the iodine takes away the barium from the oxygen because of its superior affinity for the metal, and that the oxygen which is thus liberated combines with the iodine because it is in a nascent condition, and thus converts it into iodous or iodic acid; by acting on iodine with the peroxide of barium, we ought to have just twice as much iodic acid formed as in the other case; nor was there any apparent reason why the oxygen from the peroxide of barium should not oxidize as well as the oxygen from the baryta. The same iodine, the same barium, and the same oxygen are supposed to be present; and if the iodine acted at all on the peroxide, the oxygen would still be nascent. Considered however from that theoretical point of view which I have given in the early part of this paper, there was no reason to expect this result. I have there suggested (p. 767), that in the action of iodine upon baryta, the combination of iodine and oxygen takes place solely on account of the polar relation in which the particles are placed under the peculiar circumstances of the action. Each particle in the change being alternately positive and negative, thus :—

$$\underbrace{{}^{+}\mathrm{I}\,{}^{-}\mathrm{I}\,{}^{+}\mathrm{Ba}\,{}^{-}\mathrm{O}} = \mathrm{IBa} + \mathrm{IO}.$$

I at once determined the action to a limit which it could not exceed. When small quantities of the bichromate are employed the result is entirely different, and a very small quantity of the bichromate decomposes a very great excess of the peroxide. The reaction which I have given (p. 769) is to a certain extent hypothetical, it is the limit of greatest reduction.

When phosphorus and iodine are used instead of iodine in this experiment, no essential change has taken place in the causes which determine the combining condition of the particles, but a particle of phosphorus now stands in the same relation to the baryta as the particle of iodine in the other experiment, thus:—

$$\underbrace{\overset{+}{P}\ \overset{-}{I}\ \overset{+}{Ba}\ \overset{-}{O}} = IBa + PO.$$

Now if thus intercalating the particle of phosphorus transfers the action from the iodine to the phosphorus, so also intercalating a particle of oxygen might transfer the action from the iodine to the oxygen itself, which would now be the truly oxidized body, provided of course that the particle of oxygen thus intercalated were a body which stood to the other particles with which it was in contact, in the same chemical relation as the iodine and phosphorus in the other changes; nor do I see that this substitution of the oxygen for the iodine is more truly extraordinary than the substitution of the iodine for the phosphorus. Indeed, if we inquire into the causes of chemical change, the two would depend essentially upon one and the same fact, namely, a chemical difference between the particles of the element. In the one case we have the chemical division of the element, in the other the chemical synthesis to explain; and to give a philosophical account of either fact we must assume alike the existence of a chemical difference between its particles. Now, when we substitute peroxide of barium for baryta in the iodine experiment, this very intercalation of the oxygen has been effected, and the conditions of the change been fulfilled, the polar cycle being completed, thus:—

$$\underbrace{\overset{-}{I}\ \overset{+}{Ba}\ \overset{-}{O}\ \overset{+}{O}} = IBa + O_2.$$

In fact, when water is poured upon a mixture of peroxide of barium and iodine, a violent evolution of gas occurs, and the same when chlorine is led into water containing the peroxide, or when the peroxide is thrown into a solution of hypochlorite of lime in acetic acid.

This experiment with iodine is so important, that I shall give at full length the determinations of the quantity of gas evolved in this reaction. The experiment was made in the small bulb-apparatus already described, p. 779.

The weighed peroxide and weighed iodine were mixed in the flask, the bulb being filled with distilled water; the apparatus was weighed, and the water then allowed to descend on the mixture. The loss on again weighing the apparatus is the oxygen evolved. The same precautions are to be taken in the experiment as in the oxygen determination.

The peroxide used in the following experiments was the peroxide Q, containing 8·58 per cent. of oxygen; 100 parts of this peroxide require 138 parts of iodine as one equivalent to the oxygen it contains. The first of the following Tables contains

the quantities of the substances taken and the loss; in the second the comparison is made between this loss and the oxygen of the peroxide.

TABLE XIII.—A.

| | Peroxide of barium Q. | Iodine. | Loss of oxygen. |
|---|---|---|---|
| 1. | 1·094 grms. | 30·242 grms. | 0·187 grm. |
| 2. | 0·973 | 16·082 | 0·164 |
| 3. | 0·843 | 11·633 | 0·140 |
| 4. | 1·409 | 15·5485 | 0·238 |
| 5. | 1·845 | 17·8225 | 0·315 |
| 6. | 2·0675 | 17·130 | 0·358 |
| 7. | 0·7995 | 5·5325 | 0·140 |
| 8. | 1·9364 | 10·6495 | 0·331 |
| 9. | 1·2405 | 5·277 | 0·212 |
| 10. | 1·275 | 3·517 | 0·215 |

TABLE XIII.—B.

| | Oxygen in the peroxide Q. | Loss of oxygen. | Oxygen in the peroxide. | Loss of oxygen. |
|---|---|---|---|---|
| 1. | | 17·09 | | 199·1 |
| 2. | | 16·85 | | 196·3 |
| 3. | | 16·60 | | 193·4 |
| 4. | | 16·89 | | 196·8 |
| 5. | | 17·06 | | 198·8 |
| 6. | 8·58 | 17·31 | 100 | 201·7 |
| 7. | | 17·51 | | 204·0 |
| 8. | | 17·09 | | 199·1 |
| 9. | | 17·08 | | 199·0 |
| 10. | | 16·86 | | 196·5 |

The mean of these experiments gives the ratio of the oxygen in the peroxide compared with the loss, as 8·58 : 17·03, or as 100 : 198·4. They clearly prove that the reaction is as I have stated. The quantity of iodine taken varies from 2 to 20 equivalents. The number of these experiments may appear superfluous, but there were some circumstances connected with the reaction when a smaller quantity of iodine was employed, which caused me particularly to inquire whether any excess of iodine would alter its nature. It is plain that this cannot be done. I have also ascertained the fact, that with a perfectly pure peroxide an equivalent of iodine always decomposes exactly an equivalent of the peroxide, so that if an excess of the peroxide be taken it remains undecomposed. In this important point this reaction differs from the other experiments I have given, in which very small quantities of the substance decompose the *whole* of the peroxide present. With iodine this will not take place.

The decomposition of the chloride of silver by the peroxide of barium is a true link between these experiments with iodine and the reduction of the metallic oxides. In whatever rational form we may express these facts, the facts themselves are the same. We cannot *see* the mode in which the action is effected, nor for the present argument is it at all important whether we consider, as we reasonably may, that the

change takes place* by the decomposition of water, and that the oxygen which is formed is the result of the combination of the element of the water with the element of the peroxide, or whether we consider the iodine to be transferred directly to the barium, and the whole of the oxygen to come from the peroxide itself. Whatever theory accounts for this reaction, the same theory, I will venture to assert, will explain the decomposition of the metallic oxides. It remains only to show why it is that this decomposition with iodine comes before us as a chemical reaction of the simplest nature, and that in the other experiments the decomposition is apparently so variable. The reason I believe to be this, that in these latter experiments the peroxide is simultaneously decomposed in two ways, between which we must discriminate, by the action of contact and by the chemical action of the oxide or chloride. The decomposition by platinum is a pure contact action, in which the peroxide loses only one equivalent of oxygen. The decomposition with iodine is a pure chemical action, in which two equivalents of oxygen are given off. The action with metallic oxides is an action compounded of these two, and therefore it is that the loss, as I have already pointed out, ever lies between these two limits. There are two causes by either or by both of which this decomposition may be effected; the one, the metallic silver or other substance which is the result of the reduction; the other, the very oxide or chloride or peroxide itself which is reduced. Certain oxides which are not themselves reduced, can unquestionably act in this manner; and it is highly probable therefore that those which are reduced, and which belong to the same class of bodies, have the same property. On this view therefore the law of the formation of the oxygen is ever one and the same, and so far as relates to the chemical action of the peroxide of barium on the metallic oxide this is ever definite. The fact therefore which is expressed by the series of ratios is by no means any different forms of combination of the particles of the oxygen with each other, but simply the way in which the decomposition of the peroxide of barium is distributed between these different modes of action, and the relative velocity with which these two modes of decomposition take place. If, for example, the ratio of the loss of oxygen from the peroxide of barium to that from the metallic oxide, be as 4 : 1, three parts of the peroxide of barium will have been decomposed by the contact and one by the chemical action; if the ratio be as 2 : 1, the decomposition will have taken place in equal proportions between the two. All the phenomena are perfectly consistent with this view. As a fact, we know that the contact action proceeds far more rapidly at a high than at a low temperature; we need not therefore be surprised if the relative velocity of this to the chemical action

* I have made the experiment of heating the dry peroxide with oxide of silver until the latter was reduced, but the loss of oxygen was only that of the silver. It is however remarkable, that when it is heated in a similar manner with chloride of silver, the chloride is reduced and the two equivalents of oxygen of the peroxide evolved. This decomposition takes place also with baryta, but not with lime; and I cannot but suspect that it is connected with the peculiar property of baryta of taking up a second equivalent of oxygen which does not belong to lime. It is moreover extremely difficult to prepare a baryta quite free from peroxide and water, so as to make a truly comparative experiment.

increases with the temperature. By increasing the mass of the oxide or chloride, on the other hand, the velocity of the chemical action is relatively increased; in this case therefore we have a great reduction. Again, a substance in a fine state of division is decomposed more rapidly than one which is dense and compact; here, therefore, and in other similar differences, is the cause of the different results given by different preparations of the peroxide*.

By the words *contact* and *chemical*, I mean to express no theory, and am indeed drawing but a momentary distinction between facts, for I cannot believe that the one of these portions of oxygen is formed according to one law and the other in a different manner, that the one fact is a chemical synthesis and the other not. The only difference between them I believe to be, that in the case of the action I have called chemical, the peroxide of barium decomposes peroxide of lead, or oxide of silver, or the like; and in the contact action one particle of peroxide of barium decomposes another particle of the same substance, the platinum, silver oxide or other body causing that chemical relation between the particles which renders the decomposition possible. The important question as to the nature of that definite relation which these experiments indicate between the contact action and the chemical action, I reserve for future inquiry.

I have made various experiments to ascertain whether the same kind of reduction could be effected by means of other metallic peroxides, such, for example, as the peroxide of lead or manganese, as with the peroxide of barium and potassium, but without success. I believe this to admit of a very rational explanation, and that this reducing power is a result of the peculiar chemical nature of the alkaline metals and their compounds; in short, of what is usually termed their powerful chemical affinities and position on the electro-chemical scale, to which indeed we may distinctly trace it. This relation may be expressed in various ways, but which mean essentially one and the same thing. If, for example, in the last experiment we express the change which takes place thus—

$$\underbrace{\overset{+}{\mathrm{Ba}}\,\overset{-}{\mathrm{O}}\,\overset{+}{\mathrm{O}}\,\overset{-}{\mathrm{O}}\,\overset{+}{\mathrm{H}}\,\overset{-}{\mathrm{I}}} = \mathrm{BaI} + \mathrm{O_2} + \mathrm{HO},$$

it follows, from the view I have given of the mutual relation of these particles, and the interdependence of these chemical changes, that we cannot substitute for the barium a metal which stands in a different chemical relation to the particles between which it is placed without altering the relation of all the other particles of the system, so that if the chemical difference on which combination depends does not exist between the metal and the iodine, neither can it exist between the particles of the oxygen. In this way the fact, at first sight very anomalous, admits of a very simple explanation,

* I by no means wish to exclude from these a real chemical difference in their nature, which the behaviour of certain analogous bodies leads me to suspect.

that the peroxide of barium, the less reducible peroxide, is that which under these circumstances is thus readily decomposed.

Lastly, let me observe, that I have limited my assertions as to the nature of the elemental bodies, to the statement, that, under certain conditions, there exists a chemical difference between the particles of which they consist. On the chemical nature of these particles I have offered no opinion. The apparent and obvious inference from the experiments is doubtless that the elements form a peculiar group of chemical substances, consisting of similar particles or atoms in a state of combination, as other bodies consist of dissimilar. Of this view, in the early part of this paper, I have already spoken; it is the hypothesis of Ampère. Many theoretical difficulties however meet us, when we come logically and consistently to carry out this idea to the explanation of chemical phenomena, especially to the phenomena of direct combination and to the simplest cases of chemical decomposition; and it by no means follows that, although the apparent, it is the rational and philosophical interpretation of the experiments. Besides this view and that of Berzelius, there is yet a third hypothesis which we may form as to the constitution of these elements, namely, that they consist of yet other and further elements. On this view, the real fact which lay hid under these phenomena, might be the synthesis of the oxygen from the ultimate and further elements of which the oxygen consisted. In the present state of our knowledge it is useless to dilate on this idea; but on the assumption that the elemental bodies are in this sense compound, we may, I believe, account for all these experiments without ever assuming a chemical difference between two similar particles; and it appears to me perfectly possible, that in such a constitution of the elemental bodies, these experiments, together with the phenomena of allotropy, may find their ultimate solution.

## XXXVIII. *Supplementary Observations on the Diffusion of Liquids.*

*By* Thomas Graham, *F.R.S., F.C.S.*

Received May 2,—Read June 20, 1850.

The experiments of my former paper furnished strong grounds for believing that isomorphous salts possess a similar diffusibility. All the salts of potash and ammonia, which were compared, appeared to be equi-diffusive; so also were the salts of certain magnesian bases. A single preliminary observation on the nitrates of lead and baryta, however, opposed the general conclusion, and demanded further inquiry. It is scarcely necessary to say that any new means of recognizing the existence of the isomorphous relation between different substances, must prove highly valuable. Let us inquire therefore how far liquid diffusion is available for that purpose.

The salts were still diffused from weak solutions, that is from solutions containing from 1 to 8 per cent. of salt; but now a measure of the solution, equal to 100 grs. of water, was made to contain 1 grain of the salt, to form what is called the 1 per cent. solution; instead of 1 grain of salt being added to 100 grs. of water, as before, without reference to the condensation which generally occurs. The quantities 1, 2, 4 and 8 per cent. thus indicate the parts of salt present in a constant volume of liquid,—as 10, 20, 40 and 80 grs. of the salt in 1000 water grain-measures of the solution. The same phials for the solution and jars for the external water-atmosphere continued to be used, and the manipulations were similar. It is believed, however, that the temperature of the liquids was maintained more uniform in the new experiments than the old, partly by the better regulation of the temperature of the apartment, and partly by placing the jars close together upon a table with upright ledges, and covering the whole over with sheets of paper during the continuance of an experiment. The mass of fluid in 80 or 100 jars, which were employed at once and placed together, made the small oscillations of temperature, which might still occur, slow and less injurious.

The investigation is also extended to several new substances, such as hydrocyanic acid, acetic acid, sulphurous acid, alcohol, ammonia and salts of organic bases, without reference to isomorphous relations. It is very necessary to have data which are minute and accurate respecting the diffusion of a considerable variety of substances. This it is my present object to endeavour to supply, leaving speculative deductions in general respecting the nature and laws of liquid diffusion for a future occasion.

The density of all the solutions was observed at a constant temperature, namely, 60° Fahr.

1. *Hydrochloric Acid.*

The period of diffusion arbitrarily chosen for this acid was five days. The diffusate, or quantity of acid diffused, was determined by precipitating the liquid of the external reservoirs with nitrate of silver, and weighing the chloride of silver formed. In the 1 and 2 per cent. solutions, the liquids of two jars were generally mixed and precipitated together.

(1.) Hydrochloric acid, 0·99 per cent.; density 1·0043. Diffused at 53°·5, in six cells, 7·52, 7·52, 7·42; mean 7·49 grs. for two cells. Calculated for 1 per cent., 7·56 grs. at 53°·5 for two cells, or 7·41 grs. at 51°, when corrected for that temperature.

(2.) Hydrochloric acid, 1·92 per cent.; density 1·009. Diffused at 51°, in eight cells, 14·71, 14·05, 14·54, 14·47; mean 14·44 grs. for two cells. Calculated for 2 per cent., 15·04 grs. at 51° for two cells.

(3.) Hydrochloric acid, 1·993 per cent.; density 1·0094. Diffused at 62°·8, in six cells, two experiments on one-sixth part of the mixed jars gave 8·203, 8·198; mean 8·20 grs. for one cell, or 16·40 grs. for two cells. Calculated for 2 per cent., 16·46 grs. at 62°·8 for two cells.

(4.) Hydrochloric acid, 3·90 per cent.; density 1·0190. Diffused at 51°, in eight cells, 29·18, 30·70, 30·70, 29·26; mean 29·96 grs. for two cells. Calculated for 4 per cent., 30·72 grs. at 51° for two cells.

(5.) Hydrochloric acid, 7·90 per cent.; density 1·0380. Diffused at 51°, in four cells, 32·71, 33·64, 33·64, 33·74; mean 33·43 grs. for one cell. Calculated for 8 per cent., 33·84 grs. at 51° for one cell.

Comparing the diffusibilities of the 2 per cent. solutions (2 and 3) at 51° and 62°·8, an increase is observed from 15·04 to 16·40 grs., or from 100 to 109·1, which gives an increase of 0·77 per cent. for 1°. This method of estimating the effect of temperature is not exact, as the times only in which an equal diffusion at the different temperatures takes place are truly comparable. We may deduce from it, however, the effect of the small difference of temperature of 2°·5 of the 1 per cent. solution from the others, as has been done, without sensible error. The diffusates at the same temperature would then be as follows:—

Diffusion of Hydrochloric Acid in five days at 51° Fahr.; two cells.

| | Grs. | Ratio. |
|---|---|---|
| From 1 per cent. solution . . . . . | 7·41 | 0·97 |
| From 2 per cent. solution . . . . . | 15·04 | 2·00 |
| From 4 per cent. solution . . . . . | 30·72 | 4·08 |
| From 8 per cent. solution . . . . . | 67·68 | 9·00 |

The increasing diffusibility with the larger proportions of acid here observed is unusual, at least in the degree exhibited by the 8 per cent. solution. Other substances, as will be immediately observed of nitric acid, appear to lose proportionally in diffusibility as their solutions are concentrated.

Hydrochloric acid belongs to the most diffusive class of substances known; it appears to exceed hydrate of potash at 53°·5, as 7·56 to 6·12, or as 100 to 80·9*.

The rapidity with which hydrochloric acid diffuses, and the facility with which that substance may be estimated, induced me to examine the progression with which its diffusion takes place with increasing times in a minute manner. The 2 per cent. solution was diffused for times increasing by six hours, from twelve hours or 0·5 day to 4·75 days, six cells being diffused for every period. Instead of determining the acid diffused separately in each jar or pair of jars, the contents of the six jars of each experiment were mixed together, and a definite proportion of the liquid precipitated by nitrate of silver, so as to obtain at once the mean result. Another observation for 5·75 days is added, although made at a sensibly higher temperature.

Diffusion of Hydrochloric Acid, 2 per cent. solution; one cell.

| Time. | Temperature. | Diffusate in grains. | Differences. |
|---|---|---|---|
| days. | ° | | |
| 0·5 | 53·75 | 0·909 | |
| 0·75 | 53·75 | 1·312 | ·403 |
| 1 | 53·75 | 1·766 | ·454 |
| 1·25 | 53·75 | 2·353 | ·587 |
| 1·5 | 53·75 | 2·596 | ·243 |
| 1·75 | 53·58 | 3·178 | ·582 |
| 2 | 53·58 | 3·410 | ·232 |
| 2·25 | 53·42 | 3·967 | ·557 |
| 2·5 | 53·58 | 4·339 | ·372 |
| 2·75 | 53·50 | 4·618 | ·279 |
| 3 | 53·50 | 4·969 | ·351 |
| 3·25 | 53·50 | 5·304 | ·335 |
| 3·5 | 54·85 | 5·857 | ·553 |
| 3·75 | 54·85 | 6·254 | ·397 |
| 4 | 54·85 | 6·407 | ·153 |
| 4·25 | 54·85 | 6·795 | ·388 |
| 4·5 | 54·71 | 7·034 | ·239 |
| 4·75 | 54·71 | 7·473 | ·339 |
| 5·75 | 56·46 | 8·363 | |

The differences are evidently affected by accidental errors of observation. The diffusion at 3·5 days is also increased by a rise of temperature of more than 1° in that and the following experiments. The diffusion always increases with the time, but less rapidly, according to a gradually diminishing progression.

### 2. *Hydriodic Acid, Hydrobromic Acid and Bromine.*

*Hydriodic Acid.*—Time of diffusion five days, as for hydrochloric acid. The acid diffused was estimated from the iodide of silver which it gave when precipitated by nitrate of silver.

Hydriodic acid, 1·98 per cent.; density 1·0142. Diffused at 53°·5, in eight cells, 14·90, 15·67, 15·25, 15·27; mean 15·27 grs. for two cells. Calculated for 2 per cent., 15·42 grs. at 53°·5 for two cells, or 15·11 grs. at 51°.

* Philosophical Transactions, 1850, p. 39.

These experiments indicate a similarity of diffusion between the two isomorphous substances, hydrochloric and hydriodic acids.

Diffusion from 2 per cent. solutions at 51° Fahr.

| | | |
|---|---|---|
| Hydrochloric acid . . . . . | 15·04 | 100 |
| Hydriodic acid . . . . . | 15·11 | 100·46 |

*Hydrobromic Acid.*—Time of diffusion five days. The diffusate was estimated from the bromide of silver.

(1.) Hydrobromic acid, 1·556 per cent.; density 1·0112. Diffused at 59°·7, in eight cells. The whole diffusates mixed together gave by analysis a mean of 12·90 grs. of hydrobromic acid in two cells; calculated for 2 per cent., 16·58 grs. in two cells, at 59°·7.

(2.) The experiment was repeated at 59°·8, with a solution containing 1·578 per cent. of hydrobromic acid, of density 1·0116, with five diffusion phials not employed above. The mean diffusate for a pair of cells was 13·05 grs. of hydrobromic acid; that is, 16·53 grs. for a 2 per cent. solution, which is as nearly as possible the result of the preceding series of experiments.

(3.) Another solution containing exactly 2 per cent. of hydrochloric acid was diffused for comparison in eight cells, in the same circumstances of time and temperature as (1.); its density was 1·0104.

Diffusate from 2 per cent. solutions at 59°·7 Fahr.

| | | |
|---|---|---|
| Hydrochloric acid . . . . . | 16·55 | 100 |
| Hydrobromic acid . . . . . | 16·58 | 100·18 |

Hydrobromic acid appears therefore to coincide in diffusibility with hydrochloric acid at this temperature. It may be remarked that these three acids, hydrochloric, hydrobromic and hydriodic, do not exhibit the same correspondence in another physical property, namely, the densities of their aqueous solutions containing the same proportion of acid. The densities of 2 per cent. solutions of hydrochloric and hydriodic acids appear to be respectively 1·0104 and 1·0143, at 60° Fahr., and that of hydrobromic acid will obviously be an intermediate number. The same acids are also known to differ considerably in the boiling-points of solutions containing the same proportion of acid. A considerable diversity of physical properties appears here to be compatible with equal diffusibility in substances which are isomorphous.

*Bromine.*—Pure water readily dissolves more than 1 per cent. of this substance. The solution prepared, however, contained only 0·864 per cent. of bromine, as was ascertained by treating it with sulphurous acid and afterwards precipitating by nitrate of silver. Its density was 1·0070. It was evident, from the slow appearance of the brown colour in the exterior cell, that bromine diffuses less rapidly than hydrobromic acid.

The diffusion-time of bromine was made ten days, or double the time of hydrobromic acid. Two cells contained together a diffusate of 5·80 grs. of bromine; another two cells a diffusate of 5·88 grs.; mean 5·84 grs. at 60°·1 Fahr.; or 6·76 grs. for a 1 per cent. solution. Doubling the last result we have 13·52 grs. for a 2 per cent. solution, which is still considerably under the diffusate of hydrobromic acid (16·58 grs.) in half the time.

### 3. *Hydrocyanic Acid.*

Time of diffusion five days. The acid diffused was estimated from the cyanide of silver which it gave with nitrate of silver.

Hydrocyanic acid, 1·766 per cent., made up to a density of 1·0142 with sulphate of potash. Diffused at 64°·2, in six cells, 11·40, 11·86, 11·80; mean 11·68 grs. for two cells. Calculated for 2 per cent., 13·23 grs. at 64°·2 in two cells, or about 13·10 grs. at 62°·8, assuming this acid to be affected in the same way by temperature as hydrochloric acid.

Hydrocyanic acid here appears less diffusive than hydrochloric acid, at the same temperature 62°·8, as 13·10 to 16·40, or as 79·6 to 100, and not to belong therefore to the same class of diffusive substances.

### 4. *Nitric Acid.*

Time of diffusion five days. The quantity of this acid diffused was always determined with great exactness by neutralization by means of a normal solution of carbonate of soda.

1. Nitrate of water ($HO.NO_5$), 1 per cent.; density 1·0052. Diffused at 50°·8, in eight cells, 6·77, 6·77, 7·26, 6·97; mean 6·94 grs. of nitrate of water in two cells at 50°·8, and 6·99 grs. by estimate at 51°·2.

2. Nitrate of water, 1 per cent.; density 1·0052. Diffused at 53°·5, in six cells, 7·32, 7·32, 7·20; mean 7·28 grs. in two cells.

3. Nitrate of water, 1·92 per cent.; density 1·0112. Diffused at 51°·2, in eight cells, 14·34, 14·24, 14·10, 13·96; mean 14·16 grs. in two cells. Calculated for 2 per cent., 14·74 grs. at 51°·2 in two cells.

4. Nitrate of water, 2 per cent.; density 1·0106. Diffused at 63°·2, in eight cells, 16·97, 16·64, 16·81, 16·64; mean 16·76 grs. in two cells.

5. Nitrate of water, 3·88 per cent.; density 1·0209. Diffused at 51°·2, in eight cells, 27·76, 28·34, 27·90, 27·62; mean 27·90 grs. in two cells. Calculated for 4 per cent., 28·76 grs. at 51°·2 in two cells.

6. Nitrate of water, 7·96 per cent.; density 1·0432. Diffused at 51°·2, in four cells, 29·17, 29·17, 29·17, 27·76; mean 28·82 grs. in one cell. Calculated for 8 per cent., 28·96 grs. at 51°·2 in one cell.

For the difference of temperature between 51°·2 and 63°·2, the diffusion rises, in the 2 per cent. solution, from 14·74 to 16·76 grs., or from 100 to 113·7; which gives an increase of 1·142 per cent. for one degree of temperature.

The diffusion of the different proportions of this acid at one temperature is as follows:—

Diffusion of Nitrate of Water in five days at 51°·2; two cells.

| | Grs. | Ratio. |
|---|---|---|
| From 1 per cent. solution . . . . . | 6·99 | 0·95 |
| From 2 per cent. solution . . . . . | 14·74 | 2 |
| From 4 per cent. solution . . . . . | 28·76 | 3·90 |
| From 8 per cent. solution . . . . . | 57·92 | 7·86 |

The 2 per cent. solution is taken as the standard of comparison for the ratios, instead of the 1 per cent. solution, from the greater accuracy with which the diffusion of the former can be observed.

The usual approach to equality of diffusion, between chlorides and nitrates, is observable in hydrochloric and nitric acids, at least in the 1 and 2 per cent. solutions.

Diffusion from 1 per cent. solution at 53°·5.

| | | |
|---|---|---|
| Hydrochloric acid . . . . . | 7·56 | 100 |
| Nitrate of water . . . . . | 7·28 | 96·3 |

Diffusion from 2 per cent. solution.

| | | |
|---|---|---|
| Hydrochloric acid at 51° . . . . | 15·04 | 100 |
| Nitrate of water at 51°·2 . . . . | 14·74 | 98·0 |

The 2 per cent. solutions of both acids were also diffused at higher temperatures.

Diffusion from 2 per cent solution.

| | | |
|---|---|---|
| Hydrochloric acid at 62°·8 . . . | 16·46 | 100 |
| Nitrate of water at 63°·2 . . . . | 16·76 | 101·8 |

Here the diffusibility of the two acids is as nearly as possible equal.

Diffusion from 4 per cent. solution.

| | | |
|---|---|---|
| Hydrochloric acid at 51° . . . . | 30·72 | 100 |
| Nitrate of water at 51°·2 . . . . | 28·76 | 93·7 |

Diffusion from 8 per cent. solution.

| | | |
|---|---|---|
| Hydrochloric acid at 51° . . . . | 67·68 | 100 |
| Nitrate of water at 51°·2 . . . . | 57·92 | 85·3 |

The wide divergence between these two acids, in the 8 per cent. solution, is produced by the remarkably increased diffusion of hydrochloric acid in that high proportion.

### 5. *Sulphuric Acid.*

That time of diffusion arbitrarily chosen for this acid was ten days. The diffusate of this acid was determined in the same manner as that of nitric acid.

1. Sulphate of water ($HO.SO_3$), 0·993 per cent.; density 1·0065. Diffused at 51°·7, in eight cells, 8·87, 8·87, 8·87, 8·69; mean 8·82 grs. of sulphate of water for two cells. Calculated for 1 per cent., 8·91 grs. at 51°·7 for two cells, and 8·69 grs. at 49°·7.

2. Sulphate of water, 1·89 per cent.; density 1·0130. Diffused at 49°·7, in eight cells, 16·13, 16·16, 15·58, 16·03; mean 15·98 grs. for two cells. Calculated for 2 per cent., 16·91 grs. at 49°·7 for two cells.

3. Sulphate of water, 2 per cent.; density 1·0133. Diffused at 63°·5, in eight cells, 19·80, 20·05, 19·67, 19·41; mean 19·73 grs. for two cells.

4. Sulphate of water, 3·87 per cent.; density 1·0261. Diffused at 49°·7, in eight cells, 32·72, 32·72, 33·06, 32·58; mean 32·77 grs. for two cells. Calculated for 4 per cent., 33·89 grs. at 49°·7 for two cells.

5. Sulphate of water, 7·90 per cent.; density 1·0513. Diffused at 49°·7, in four cells, 34·08, 34·76, 33·74, 33·63; mean 34·05 grs. for one cell. Calculated for 8 per cent., 34·48 grs. at 49°·7 for one cell.

In the 2 per cent. solution the diffusion rises, with the difference of temperature between 49°·7 and 63°·5, from 16·91 to 19·73 grs., or from 100 to 116·68. This is an increase of 1·209 per cent. for one degree of temperature.

The diffusion of the different proportions of sulphuric acid is as follows:—

Diffusion of Sulphate of Water in ten days at 49°·7; two cells.

| | Grs. | Ratio. |
|---|---|---|
| From 1 per cent. solution . . . . . | 8·69 | 1·03 |
| From 2 per cent. solution . . . . . | 16·91 | 2 |
| From 4 per cent. solution . . . . . | 33·89 | 4·01 |
| From 8 per cent. solution . . . . . | 68·96 | 8·16 |

The diffusibility of different strengths of this acid appears to be pretty uniform, but with a slight tendency to increase in the higher proportions, like hydrochloric acid.

Sulphuric acid is greatly inferior in velocity of diffusion to hydrochloric acid, but still appears to possess considerably more than half the diffusibility of the latter.

### 6. *Chromic Acid.*

Time of diffusion ten days. The diffusates from four cells of the 2 per cent. solution were mixed together, and the quantity of chromic acid diffused for two cells reduced by means of hydrochloric acid and alcohol, and weighed as oxide of chromium.

1·762 per cent. of anhydrous chromic acid, density 1·01404, diffused at 67°·3, gave 19·78 grs. of chromic acid in two cells. Calculated for 2 per cent., 22·43 grs. of chromic acid, in two cells, at 67°·3. The diffusion of sulphuric acid at 63°·5, was 19·73 grs., which would give about 21 grs. of that acid at 67°·3.

### 7. *Acetic Acid.*

Time of diffusion ten days. This acid cannot be determined accurately by the acidimetrical method, owing to the acetates of potash and soda being essentially alkaline to test-paper, like the carbonates of the same bases, although neutral in composition. The weight of carbonate of baryta dissolved by the acid was had recourse to.

1. Acetate of water ($HO.C_4H_3O_3$), 2 per cent.; density 1·0030. Diffused at 48°·8, in eight cells, 12·62, 10·94, 11·10, 11·39 grs. of acetate of water; mean 11·51 grs. for two cells.

2. Acetate of water, 4 per cent.; density 1·0060. Diffused at 48°·8, in eight cells, 22·12, 21·71, 21·59, 22·67; mean 22·02 grs. for two cells.

3. Acetate of water, 8 per cent.; density 1·0117. Diffused at 48°·8, in four cells, 21·19, 20·13, 21·84, 20·44; mean 20·90 grs. for one cell. The diffusion of the different proportions of acetic acid is as follows:—

Diffusion of Acetate of Water in ten days at 48°·8; two cells.

| | Grs. | Ratio. |
|---|---|---|
| From 2 per cent. solution . . . . . | 11·31 | 2 |
| From 4 per cent. solution . . . . . | 22·02 | 3·83 |
| From 8 per cent. solution . . . . . | 41·80 | 7·26 |

The diffusibility diminishes with the larger proportions of acid. This acid appears to be considerably less diffusive than sulphuric acid. I was led to over-estimate the diffusion of acetic acid in a preliminary observation of my former paper, by trusting to the acidimetrical method of determination. Hydrochloric acid appears to diffuse about two and a half times more rapidly than acetate of water, at the same temperature.

### 8. *Sulphurous Acid.*

The time of diffusion chosen for this acid was ten days, for comparison with sulphuric acid. The usual number of eight cells of the 1 and 2 per cent. solutions were diffused, and four cells of the 4 and 8 per cent. solutions. The whole diffusates of each proportion were then mixed together, and the proportional quantity of liquid representing two cells in the 1 and 2 per cent. solutions, and 1 cell in the 4 and 8, was converted into sulphuric acid by a slight excess of bromine, and determined from the sulphate of baryta.

1. 0·982 per cent. of sulphurous acid, density 1·0056, diffused at 68°·1, gave 7·94 grs. in two cells. Calculated for 1 per cent., 8·09 grs. of sulphurous acid in two cells at 68°·1.

2. 1·965 per cent. of sulphurous acid, density 1·01055, diffused at 68°·1, gave 16·66 grs. for two cells. Calculated for 2 per cent., 16·96 grs. of sulphurous acid in two cells at 68°·1.

3. 3·93 per cent. of sulphurous acid, density 1·01991, diffused at 68°·1, gave

16·21 grs. for one cell. Calculated for 4 per cent., 16·50 grs. of sulphurous acid in one cell at 68°·1.

4. 7·86 per cent. of sulphurous acid, density 1·0384, diffused at 68°·1, gave 32·60 grs. for one cell. Calculated for 8 per cent., 33·19 grs. of sulphurous acid in one cell at 68°·1.

Diffusion of Sulphurous Acid in ten days at 68°·1; two cells.

| | Grs. | Ratio. |
|---|---|---|
| From 1 per cent. solution . . . | 8·09 | 0·954 |
| From 2 per cent. solution . . . | 16·96 | 2 |
| From 4 per cent. solution . . . | 33·00 | 3·891 |
| From 8 per cent. solution . . . | 66·38 | 7·827 |

This substance appears to be less diffusive than sulphuric acid at the same temperature; the diffusion of sulphurous acid at 68°·1 considerably resembles that of sulphuric acid at 49°·7 (p. 811).

9. *Ammonia.*

The time of diffusion chosen was 4·041 days, or that of hydrate of potash with chloride of sodium at seven days. The usual number of eight cells of the 1 and 2 per cent. solutions were diffused, and four cells of the 4 and 8 per cent. solutions. The whole diffusates of each proportion were then mixed together, and the quantity of ammonia diffused for two cells determined by an alkalimetrical experiment, which was always repeated twice. It was necessary for diffusion to have the ammoniacal solution made denser than water, which was effected by the addition of common salt.

1. 1·005 per cent. of ammonia, density made up to 1·00352 with chloride of sodium, diffused at 63°·4, gave 4·96 grs. for two cells; calculated for 1 per cent., 4·93 grs. of ammonia in two cells at 63°·4.

2. 2·01 per cent. of ammonia, density made up to 1·00617 with chloride of sodium, diffused at 63°·4, gave 9·64 grs. for two cells; calculated for 2 per cent., 9·59 grs. of ammonia in two cells at 63°·4.

3. 4·02 per cent. of ammonia, density made up to 1·01141 with chloride of sodium, diffused at 63°·4, gave 9·91 grs. for one cell; calculated for 4 per cent., 9·86 grs. of ammonia, in one cell, at 63°·4.

4. 8·04 per cent. of ammonia, density made up to 1·0215 with chloride of sodium, diffused at 63°·4, gave 20·71 grs. for one cell; calculated for 8 per cent., 20·61 grs. of ammonia in one cell at 63°·4.

Diffusion of Ammonia in 4·04 days at 63°·4; two cells.

| | Grs. | Ratio. |
|---|---|---|
| From 1 per cent. solution . . . | 4·93 | 1·029 |
| From 2 per cent. solution . . . | 9·59 | 2 |
| From 4 per cent. solution . . . | 19·72 | 4·117 |
| From 8 per cent. solution . . . | 41·22 | 8·605 |

Ammonia appears to have a diffusibility approaching to that of hydrate of potash. It appears somewhat less diffusive than hydrocyanic acid at the same temperature, in the proportion of 12 to 13 nearly; or to possess about three-fourths of the diffusibility of hydrochloric acid.

10. *Alcohol.*

Time of diffusion ten days. The quantity of alcohol diffused was determined by careful distillation.

1. Alcohol, 2 per cent.; density made up to 1·0237 with chloride of sodium. Diffused at 40°·7, in eight cells, 17·80, 16·70; mean 17·25 grs. for four cells, or 8·62 grs. for two cells.

2. Alcohol, 4 per cent.; density made up to 1·0203 with chloride of sodium. Diffused at 48°·7, in eight cells, 34·30, 30·20; mean 32·25 grs. for four cells, or 16·12 grs. for two cells.

3. Alcohol, 8 per cent.; density made up to 1·0154 with chloride of sodium. Diffused at 48°·7, in four cells, 30·80, 40·2; mean 35·50 grs. for two cells, or 17·75 grs. for one cell.

The results accord less closely with each other than usual, owing, I believe, chiefly to the difficulties of manipulation when the density of the liquid placed in the phials to be diffused approaches so nearly to that of water. This is more particularly true of the 8 per cent. solution.

Diffusion of Alcohol in ten days at 48°·7; two cells.

| | |
|---|---|
| From 2 per cent. solution . . . . . | 8·62 |
| From 4 per cent. solution . . . . . | 16·12 |
| From 8 per cent. solution . . . . . | 35·50 |

It would be unsafe to draw any conclusion as to the proportionality of the diffusion of alcohol to the strength of the solution from these experiments.

Alcohol does not appear to belong to the same class of diffusive substances as acetic acid, which might be expected from their similarity of composition, but possesses a considerably lower diffusibility.

Diffusion from 2 per cent. solutions in ten days.

| | | |
|---|---|---|
| Acetate of water at 48°·8 . . . | 11·51 | 100 |
| Alcohol at 48°·7 . . . . . | 8·62 | 74·9 |

The diffusion of alcohol approaches to one-half of that of sulphate of water at nearly the same temperature, p. 811.

Alcohol may be substituted for water to dissolve certain salts, and also as an atmosphere into which these salts may diffuse. From experiments which have been commenced on this subject, it appears that the diffusion of hydrate of potash, iodide of potassium, chloride of calcium and others is about four times slower into alcohol of density 0·840 than into water. The salts likewise often exhibit the same rela-

tions in their diffusibility in alcohol, as in water, with some singular exceptions, such as chloride of mercury.

### 11. *Nitrate of Baryta.*

Time of diffusion 11·43 days*. The salt diffused was precipitated by sulphuric acid, and calculated from the weight of the sulphate of baryta formed.

1. Nitrate of baryta, 1 per cent.; density 1·0083. Diffused at 51°·5, in eight cells, 6·71, 6·71, 6·84, 6·68; mean 6·73 grs. for two cells.

2. Nitrate of baryta, 0·993 per cent.; density 1·00886. Diffused at 64°·1, in eight cells, 7·64, 7·70, 7·74, 7·61; mean 7·67 grs. for two cells. Calculated for 1 per cent., 7·72 grs. for two cells.

3. Nitrate of baryta, 2 per cent; density 1·01686. Diffused at 64°·1, in eight cells, 15·63, 14·81, 14·41, 15·32; mean 15·04 grs. for two cells.

4. Nitrate of baryta, 4 per cent.; density 1·03319. Diffused at 64°·1, in four cells, 15·36, 14·78, 14·79, 14·30; mean 14·80 grs. for one cell.

5. Nitrate of baryta, 8 per cent; density 1·06556. Diffused at 64°·1, in four cells, 26·46, 26·77, 28·63, 27·13; mean 27·25 grs. for one cell.

The diffusion from the 1 per cent. solution increases by a rise of temperature from 51°·5 to 64°·1, from 6·73 grs. to 7·72, or from 100 to 114·7, which is an increase of 1·17 per cent for 1°.

Diffusion of Nitrate of Baryta in 11·43 days at 64°·1; two cells.

| | Grs. | Ratio. |
|---|---|---|
| From 1 per cent. solution . . . | 7·72 | 1·026 |
| From 2 per cent. solution . . . | 15·04 | 2 |
| From 4 per cent. solution . . . | 29·60 | 3·936 |
| From 8 per cent. solution . . . | 54·50 | 7·247 |

### 12. *Nitrate of Strontia.*

Time of diffusion 11·43 days. Of anhydrous nitrate of strontia 0·82 per cent.; density 1·0063. Diffused at 51°·5, in eight cells, 5·59, 5·62, 5·44, 5·69; mean 5·59 grs. for two cells; calculated for 1 per cent., 6·79 grs. at 51°·5 for two cells.

The diffusion of nitrate of strontia almost coincides with that of the isomorphous nitrate of baryta at the same temperature.

Diffusion from 1 per cent. solutions at 51°·5 in 11·43 days.

| | | |
|---|---|---|
| Nitrate of baryta . . . . . | 6·73 | 100 |
| Nitrate of strontia . . . . . | 6·79 | 100·89 |

* This time is to that of sulphate of magnesia (16·166 days) as the square root of 8 is to the square of 16; but does not appear to express the true relation between these salts.

### 13. *Nitrate of Lime.*

Time of diffusion 11·43 days. The diffusate was evaporated to dryness with an excess of sulphuric acid, and the nitrate of lime, which is always supposed anhydrous, was estimated from the sulphate of lime produced.

1. Nitrate of lime, 1·17 per cent; density 1·0088. Diffused at 51°·5, in eight cells, 7·39, 7·76, 7·69, 7·80; mean 7·66 grs. for two cells; calculated for 1 per cent., 6·54 grs. at 51°·5 for two cells.

2. Nitrate of lime, 0·985 per cent.; density 1·00802. Diffused at 64°·1, in eight cells, 7·47, 7·38, 7·63, 7·72; mean 7·55 grs. for two cells; calculated for 1 per cent., 7·66 grs. at 64°·1 for two cells.

3. Nitrate of lime, 1·97 per cent.; density 1·01508. Diffused at 64°·1, in eight cells, 15·04, 14·74, 14·55, 14·83; mean 14·79 grs. for two cells; calculated for 2 per cent., 15·01 grs. at 64°·1 for two cells.

4. Nitrate of lime, 3·94 per cent.; density 1·0296. Diffused at 64°·1, in four cells, 14·30, 15·29, 13·79, 13·93; mean 14·33 grs. for one cell; calculated for 4 per cent., 14·52 grs. at 64°·1 for one cell.

5. Nitrate of lime, 7·88 per cent.; density 1·0582. Diffused at 64°·1, in four cells, 27·95, 27·10, 26·80, 26·73; mean 27·14 grs. for one cell; calculated for 8 per cent., 27·55 grs. at 64°·1 for one cell.

By a rise of temperature from 51°·5 to 64°·1, the diffusion of the 1 per cent. solution increases from 6·54 to 7·66 grs., or from 100 to 117·1; which is an increase of 1·357 per cent. for 1°.

Diffusion of Nitrate of Lime in 11·43 days at 64°·1; two cells.

| | Grs. | Ratio. |
|---|---|---|
| From 1 per cent. solution . . . | 7·66 | 1·021 |
| From 2 per cent. solution . . . | 15·01 | 2 |
| From 4 per cent. solution . . . | 29·04 | 3·872 |
| From 8 per cent. solution . . . | 55·10 | 7·334 |

The results throughout for this salt are almost identical with those of nitrate of baryta (p. 815), although these two salts differ greatly in solubility, and in one being a hydrated, and the other an anhydrous salt.

### 14. *Acetate of Lead.*

Diffused for 16·166 days; the time chosen before for sulphate of magnesia, with seven days for chloride of sodium. The solution contained 0·965 per cent. of anhydrous salt, with the density 1·0080. As this solution of acetate of lead was found to be precipitated by pure water, about 2 per cent. of strong acetic acid was introduced into the solution, and the same acid was added in a less proportion to the water jars. The salt of lead diffused was afterwards determined by means of sulphuric acid. Diffused in eight cells, at 53°·1, 7·45, 7·29, 7·46 and 8·07 grs.; mean 7·56; or 7·84 for 1 per cent. in two cells.

15. *Acetate of Baryta.*

Diffused for 16·166 days. The solution contained 0·977 per cent. of anhydrous salt, with the density 1·0073. The same addition of acetic acid was made to it as to the preceding acetate of lead, in order that the circumstances of diffusion might be similar for both salts. The salt diffused was estimated also in the form of sulphate.

Diffused at 53°·5, in eight cells, 7·30, 7·38, 7·40 and 7·21 grs. in two cells; mean 7·33; or 7·50 for 1 per cent. in two cells.

Diffusion of 1 per cent. solutions in 16·166 days; two cells.

| | | |
|---|---|---|
| Acetate of baryta at 53°·5 . . . . | 7·50 | 100 |
| Acetate of lead at 53°·1 . . . . . | 7·84 | 104·53 |

Here, of two isomorphous salts, that of greatest atomic weight sensibly exceeds the other in diffusibility.

16. *Chloride of Barium.*

Time of diffusion 11·43 days. The diffused salt was weighed as sulphate of baryta.

1. Chloride of barium, 0·99 per cent. Diffused at 50°·9, in eight cells, 7·91, 7·27, 7·42, 7·12; mean 7·43 grs. of chloride of barium for two cells; calculated for 1 per cent., 7·50 grs. at 50°·9 for two cells.

The diffusion of this salt being manifestly more rapid than that of the chloride of calcium, a shorter time was tried, which is to seven days, the time of chloride of sodium, as the square root of 3 to the square root of 4·5. Time of diffusion 8·57 days.

2. Chloride of barium, 1·01 per cent.; density 1·0095. Diffused at 63°, in eight cells, 6·46, 6·44, 6·41, 6·27; mean 6·39 grs. for two cells; calculated for 1 per cent., 6·32 grs. at 63° for two cells.

3. Chloride of barium, 2·02 per cent.; density 1·0183. Diffused at 63°, in eight cells, 11·98, 12·03, 12·75, 12·03; mean 12·20 grs. for two cells; calculated for 2 per cent., 12·07 grs. at 63° for two cells.

4. Chloride of barium, 4·04 per cent.; density 1·0359. Diffused at 63°, in four cells, 12·43, 12·30, 11·87, 11·86; mean 12·10 grs. for one cell; calculated for 4 per cent., 11·98 grs. at 63° for one cell.

5. Chloride of barium, 8·08 per cent.; density 1·0712. Diffused at 63°, in four cells, 23·17, 23·05, 22·98, 23·62; mean 23·20 grs. for one cell; calculated for 8 per cent., 22·96 grs. at 63° for one cell.

Diffusion of Chloride of Barium in 8·57 days at 63°; two cells.

| | Grs. | Ratio. |
|---|---|---|
| From 1 per cent. solution . . . | 6·32 | 1·047 |
| From 2 per cent. solution . . . | 12·07 | 2 |
| From 4 per cent. solution . . . | 23·96 | 3·970 |
| From 8 per cent. solution . . . | 45·92 | 7·608 |

17. *Chloride of Strontium.*

First time of diffusion 11·43 days. The diffused salt was weighed as sulphate of strontia.

1. Chloride of strontium, 0·803 per cent.; density 1·0076. Diffused at 51°, in eight cells, 6·36, 6·06, 5·93, 5·73; mean 6·02 grs. of chloride of strontium for two cells; calculated for 1 per cent., 7·52 grs. at 51° for two cells.

Second time of diffusion 8·57 days.

2. Chloride of strontium, 1 per cent.; density 1·00936. Diffused at 63°, in eight cells, 6·10, 6·17, 6·02, 6·09; mean 6·09 grs. for two cells.

3. Chloride of strontium, 2 per cent.; density 1·01806. Diffused at 63°, in eight cells, 11·62, 11·71, 11·53, 11·79; mean 11·66 grs. for two cells.

4. Chloride of strontium, 4·014 per cent.; density 1·03537. Diffused at 63°, in four cells, 12·09, 11·75, 11·64, 11·79; mean 11·82 grs. for one cell; calculated for 4 per cent., 11·78 grs. at 63° for one cell.

5. Chloride of strontium, 8·028 per cent.; density 1·06959. Diffused at 63°, in four cells, 22·29, 22·34, 22·03, 22·57; mean 22·31 grs. for one cell; calculated for 8 per cent., 22·23 grs. at 63° for two cells.

Diffusion of Chloride of Strontium in 8·57 days at 63°; two cells.

| | Grs. | Ratio. |
|---|---|---|
| From 1 per cent. solution . . . | 6·09 | 1·045 |
| From 2 per cent. solution . . . | 11·66 | 2 |
| From 4 per cent. solution . . . | 23·56 | 4·041 |
| From 8 per cent. solution . . . | 44·46 | 7·626 |

The series of ratios in the preceding table will be found on comparison to correspond closely with the ratios of chloride of barium. It may be useful to compare further the amounts diffused from similar solutions of these two isomorphous compounds.

Diffusion in 8·57 days at 63°; two cells.

| | | |
|---|---|---|
| Chloride of barium, 1 per cent. . . | 6·32 | 100 |
| Chloride of strontium, 1 per cent. . | 6·09 | 96·36 |
| Chloride of barium, 2 per cent. . . | 12·07 | 100 |
| Chloride of strontium, 2 per cent. . | 11·66 | 96·90 |
| Chloride of barium, 4 per cent. . . | 23·96 | 100 |
| Chloride of strontium, 4 per cent. . | 23·56 | 99·16 |
| Chloride of barium, 8 per cent. . . | 45·92 | 100 |
| Chloride of strontium, 8 per cent. . | 44·46 | 96·83 |

The near coincidence of the 4 per cent. solutions probably arises from an accidental error of observation in the chloride of barium, for the latter departs here from the progression of its ratios. We appear then to have a small but constant difference of

about 3½ per cent. in the diffusion of these two isomorphous salts, the chloride of barium, which possesses the highest atomic weight, having the advantage.

The diffusion of the 1 per cent. solution of the same salts for the longer period of 11·43 days, gives 7·50 for chloride of barium at 50°·9, and 7°·52 for chloride of strontium at 51°, or nearly the same temperature. For the first time we have in the barytic salts a divergence between chlorides and nitrates, for the nitrates of the same bases have a number about 6·8 only at the same temperature. I am led however to believe that this discrepancy becomes much less at low temperatures by experiments which are at present in progress.

### 18. *Chloride of Calcium.*

Time of diffusion 11·43 days. The salt diffused was weighed as sulphate of lime.

1. Chloride of calcium, 1·065 per cent.; density 1·0091. Diffused at 50°·9, in eight cells, 6·95, 7·09, 6·78, 6·94; mean 6·94 grs. of chloride of calcium for two cells; calculated for 1 per cent., 6·51 grs. at 50°·9 for two cells.

2. Chloride of calcium, 1·03 per cent.; density 1·0089. Diffused at 63°·8, in eight cells, 8·08, 8·13, 8·28, 8·19; mean 8·17 grs. for two cells; calculated for 1 per cent., 7·92 grs. at 63°·8 for two cells.

3. Chloride of calcium, 2·06 per cent.; density 1·0171. Diffused at 63°·8, in eight cells, 15·70, 15·33, 16·48, 15·82; mean 15·83 grs. for two cells; calculated for 2 per cent., 15·35 grs. at 63°·8 for two cells.

4. Chloride of calcium, 4·12 per cent.; density 1·0334. Diffused at 63°·8, in four cells, 15·24, 16·20, 15·89, 16·20; mean 15·88 grs. for one cell; calculated for 4 per cent., 15·39 grs. at 63°·8 for one cell.

5. Chloride of calcium, 8·23 per cent.; density 1·0652. Diffused at 63°·8, in four cells, 32·97, 31·17, 30·64, 31·90; mean 31·67 grs. for one cell; calculated for 8 per cent., 30·78 grs. at 62°·8 for one cell.

The diffusion of the 1 per cent. solution of chloride of calcium is increased by a rise of temperature from 50°·9 to 63°·8, from 6·51 to 7·92, or from 100 to 121·6, which is an increase of 1·674 per cent. for 1°.

Diffusion of Chloride of Calcium in 11·43 days at 63°·8; two cells.

| | Grs. | Ratio. |
|---|---|---|
| From 1 per cent. solution . . . | 7·92 | 1·032 |
| From 2 per cent. solution . . . | 15·35 | 2 |
| From 4 per cent. solution . . . | 30·78 | 4·010 |
| From 8 per cent. solution . . . | 61·56 | 8·021 |

We may now observe how far the diffusion of the chloride of calcium is analogous to that of nitrate of lime. At the inferior temperatures, the results for the 1 per cent. solution of these two salts were as follows:—

| | | |
|---|---|---|
| Chloride of calcium at 50°·9 . . . | 6·51 | 100 |
| Nitrate of lime at 51°·5 . . . . . | 6·54 | 100·46 |

While at the higher temperatures, namely, 63°·8 for the chloride of calcium, and 64°·1 for the nitrate of lime, the results for the different proportions of salt are—

| | | |
|---|---|---|
| Chloride of calcium, 1 per cent. . . | 7·92 | 100 |
| Nitrate of lime, 1 per cent. . . . | 7·66 | 96·72 |
| Chloride of calcium, 2 per cent. . . | 15·35 | 100 |
| Nitrate of lime, 2 per cent. . . . | 15·01 | 97·79 |
| Chloride of calcium, 4 per cent. . . | 30·78 | 100 |
| Nitrate of lime, 4 per cent. . . . | 29·04 | 94·35 |
| Chloride of calcium, 8 per cent. . . | 61·56 | 100 |
| Nitrate of lime, 8 per cent. . . . | 55·10 | 89·51 |

The correspondence between the 1 and 2 per cent. solutions of chloride and nitrate is sufficiently close, but in the 4 and 8 per cent. the salts diverge, as happens also with hydrochloric and nitric acids themselves. The nitrate in both cases falls off, while the chloride sustains throughout the high diffusibility of the lower proportions.

19. *Chloride of Manganese.*

Time of diffusion 11·43 days. The salt diffused was estimated by means of nitrate of silver.

The 1 per cent. solution, of density 1·0085, gave at 50°·8, in eight cells, 6·67, 6·26, 6·79 and 6·81 grs.; mean 6·63 for two cells.

20. *Nitrate of Magnesia.*

Time of diffusion 11·43 days. The salt diffused was estimated as sulphate.

The 1 per cent. solution, of density 1·0073, gave at 50°·8, in eight cells, 6·29, 6·39, 6·52 and 6·76 grs.; mean 6·49 for two cells.

21. *Nitrate of Copper.*

Time of diffusion 11·43 days. The salt diffused was estimated from the oxide of copper obtained by ignition.

The 1 per cent. solution, of density 1·0075, in eight cells, at 50°·8, gave 6·52, 6·36, 6·18 and 6·70 grs.; mean 6·44 for two cells.

Comparing the preceding salts with chloride of calcium diffused at the same temperature, 50°·8, we have the following results:—

| | | |
|---|---|---|
| Chloride of calcium . . . . . | 6·51 | 100 |
| Chloride of manganese . . . . . | 6·63 | 101·85 |
| Nitrate of magnesia . . . . . | 6·49 | 99·69 |
| Nitrate of copper . . . . . | 6·44 | 98·92 |

This group of salts, belonging to the same isomorphous family of bases, the magnesian, again correspond closely in diffusibility.

The following additional magnesian chlorides were diffused, all 1 per cent. solu-

tions, either in six or in eight cells. The salt diffused was estimated by means of nitrate of silver.

22. *Chloride of Zinc* at 51°, solution of density 1·0091, gave 6·55, 6·20, 6·21 and 6·28 grs.; mean 6·29 for two cells.

23. *Chloride of Magnesium* at 50°·6, density 1·0077, gave 6·40, 5·84 and 6·29; mean 6·17 for two cells.

24. *Chloride of Copper* at 50°·6, solution of density 1·0093, gave 6·08, 6·08 and 6·02 grs.; mean 6·06 for two cells.

The results referred to chloride of calcium, at nearly the same temperature, 50°·8, are as follows:—

| | | |
|---|---|---|
| Chloride of calcium . . . . . | 6·51 | 100 |
| Chloride of zinc . . . . . | 6·29 | 96·61 |
| Chloride of magnesium . . . . . | 6·17 | 94·77 |
| Chloride of copper . . . . . | 6·06 | 93·08 |

These salts present a greater latitude in their diffusibility, if belonging to the same class, than is usual.

25. *Protochloride of Iron.*

A solution of this salt of 1·023 per cent. was diffused at 53°·5, a somewhat higher temperature than the corresponding chlorides. It gave 6·45, 6·48, 6·48 and 6·28 grs. in two cells; mean 6·44, or 6·30 for 1 per cent. in two cells. This salt appears therefore to belong to the last group.

26. *Sesquichloride of Iron.*

A full series of observations was made upon the diffusion of the different proportions of this salt from 1 to 8 per cent., but in all of them decomposition was determined by the diffusion, with turbidity also in the solution phial except in the 8 per cent. solution.

The mean diffusion from the 1 per cent. solution in 11·43 days, at 63°·3, was 4·13 grs. of sesquichloride of iron with 1·28 gr. of free hydrochloric acid, in two cells. This result indicates that one-half nearly of the sesquichloride of iron is decomposed in the diffusion.

The mean diffusion from the 8 per cent. solution, at 63°·3, was 55·88 grs. of sesquichloride of iron, with 6·66 grs. of free hydrochloric acid, in two cells. It appears from this experiment that perchloride of iron approaches the chloride of calcium in diffusibility. That the proto- and persalts of the magnesian metals should have a similar rate of diffusion, is not unlikely from other analogies which they exhibit.

27. *Sulphate of Magnesia.*

The time chosen for the diffusion of this salt, namely, 16·166 days, is a multiple by 2 of the time of sulphate of potash, and by 4 of the time of hydrate of potash. The diffusate was evaporated to dryness and weighed.

1. 1·012 per cent. of anhydrous sulphate of magnesia, density 1·0108, diffused at 65°·4, in eight cells, 7·34, 7·66, 7·43, 7·18; mean 7·40 grs. for two cells; calculated for 1 per cent., 7·31 grs. of sulphate of magnesia in two cells at 65°·4.

2. 2·024 per cent. of sulphate of magnesia, density 1·02089, diffused at 65°·4, in eight cells, 12·91, 13·13, 12·83, 12·93; mean 12·95 grs. for two cells; calculated for 2 per cent., 12·79 grs. of sulphate of magnesia in two cells at 65°·4.

3. 4·048 per cent. of sulphate of magnesia, density 1·04033, diffused at 65°·4, in four cells, 12·06, 12·56, 10·63, 12·24; mean 11·87 grs. for one cell; calculated for 4 per cent., 11·73 grs. of sulphate of magnesia in one cell at 65°·4.

4. 8·096 per cent. of sulphate of magnesia, density 1·07830, diffused at 65°·4, in four cells, 22·25, 20·56, 21·80, 22·06; mean 21·67 grs. for one cell; calculated for 8 per cent., 21·41 grs. of sulphate of magnesia in one cell at 65°·4.

5. 8·07 per cent. of sulphate of magnesia, density 1·07830, diffused at 62°·8, in four cells, 21·12, 21·20, 22·13, 21·77; mean 21·55 grs. for one cell; calculated for 8 per cent., 21·33 grs. of sulphate of magnesia in one cell at 62°·8.

6. 16·14 per cent. of sulphate of magnesia, density 1·15054, diffused at 62°·8, in four cells, 37·08, 38·39, 38·65, 37·50; mean 37·90 grs. for one cell; calculated for 16 per cent., 37·53 grs. of sulphate of magnesia in one cell at 62°·8.

7. 24·22 per cent. of sulphate of magnesia, density 1·21882, diffused at 62°·8, in four cells, 49·38, 50·40, 53·36, 53·00; mean 51·53 grs. for one cell; calculated for 24 per cent., 51·02 grs. of sulphate of magnesia in one cell at 62°·8.

Diffusion of Sulphate of Magnesia in 16·16 days at 65°·4; two cells.

| | Grs. | Ratio. |
|---|---|---|
| From 1 per cent. solution . . . . | 7·31 | 1·144 |
| From 2 per cent solution . . . . | 12·79 | 2 |
| From 4 per cent. solution . . . . | 23·46 | 3·671 |
| From 8 per cent. solution . . . . | 42·82 | 6·701 |
| From 8 per cent. solution at 62°·8 . | 42·66 | 1 |
| From 16 per cent. solution at 62°·8 . | 75·06 | 1·759 |
| From 24 per cent. solution at 62°·8 . | 102·04 | 2·340 |

### 28. *Sulphate of Zinc.*

Time of diffusion 16·166 days. The diffused salt was evaporated to dryness and weighed.

1. 1·001 per cent. of anhydrous sulphate of zinc, density 1·01093, diffused at 65°·4, in eight cells, 6·66, 6·76, 6·51, 6·80; mean 6·68 grs. for two cells; calculated for 1 per cent., 6·67 grs. of sulphate of zinc in two cells at 65°·4.

2. 2·002 per cent. sulphate of zinc, density 1·02120, diffused at 65°·4, in eight cells, 12·16, 12·19, 12·52, 12·05; mean 12·23 grs. for two cells; calculated for 2 per cent., 12·22 grs. of sulphate of zinc in two cells at 65°·4.

3. 4·005 per cent. of sulphate of zinc, density 1·04146, diffused at 65°·4, in four cells, 11·63, 11·70, 11·00, 11·95; mean 11·57 grs. for one cell; calculated for 4 per cent., 11·56 grs. of sulphate of zinc in one cell at 65°·4.

4. 8·01 per cent. of sulphate of zinc, density 1·08063, diffused at 65°·4, in four cells, 21·22, 20·52, 21·06, 21·84; mean 21·16 grs. for one cell; calculated for 8 per cent., 21·13 grs. of sulphate of zinc in one cell at 65°·4.

5. 8·04 per cent. of sulphate of zinc, density 1·08084, diffused at 62°·8, in four cells, 20·70, 18·57, 20·32, 20·36; mean 19·99 grs. for one cell; calculated for 8 per cent., 19·81 grs. of sulphate of zinc in one cell at 62°·8.

6. 16·08 per cent. of sulphate of zinc, density 1·15734, diffused at 62°·8, in four cells, 36·70, 37·15, 37·51, 38·21; mean 37·39 grs. for one cell; calculated for 16 per cent., 37·20 grs. of sulphate of zinc in one cell at 62°·8.

7. 24·11 per cent. of sulphate of zinc, density 1·23156, diffused at 62°·8, in three cells, 51·12, 50·14, 51·66; mean 50·97 grs. for one cell; calculated for 24 per cent., 50·71 grs. of sulphate of zinc in one cell at 62°·8.

Diffusion of Sulphate of Zinc in 16·16 days at 65°·4; two cells.

| | Grs. | Ratio. |
|---|---|---|
| From 1 per cent. solution . . . . . | 6·67 | 1·091 |
| From 2 per cent. solution . . . . . | 12·22 | 2 |
| From 4 per cent. solution . . . . . | 23·12 | 3·784 |
| From 8 per cent. solution . . . . . | 42·26 | 6·916 |
| From 8 per cent. solution at 62°·8 . | 39·62 | 1 |
| From 16 per cent. solution at 62°·8 . | 74·40 | 1·878 |
| From 24 per cent. solution at 62°·8 .. | 101·42 | 2·560 |

It will be remarked that the diffusion of these two isomorphous salts, sulphate of magnesia and sulphate of zinc, differs so much, in the 1 per cent. solution, as 7·31 to 6·67, that is, as 100 to 91·25; or 8·75 per cent. This I have no doubt, however, is an accidental error, the disturbances from changes of temperature and other causes of dispersion being in direct proportion to the duration of the experiment, and therefore much increased with these long times; while the 1 per cent. solution also appears to be generally the proportion most exposed to such errors. The sulphate of zinc appears to be the truest throughout, in its diffusion, of these two salts. The approach to equality becomes close in the 4 per cent. and larger proportions of salt, particularly with the unusually high proportions of 16 and 24 per cent., which were observed in these salts. The diffusion of both salts falls off remarkably in the higher proportions. The result of the comparison of these two magnesian sulphates is no doubt favourable to the similarity of diffusion of isomorphous salts.

### 29. *Sulphate of Alumina.*

The time of diffusion chosen was 16·166 days, or the same as that for sulphate of magnesia. The usual number of eight cells of the 1 and 2 per cent. solutions were diffused, and four cells of the 4 and 8 per cent. solutions. The whole diffusates of each proportion were then mixed together and the quantities of alumina and sulphuric acid, diffused for two cells, determined separately.

1. 1·045 per cent. of sulphate of alumina, density 1·01160, diffused at 65°·4, gave 1·80 gr. of alumina and 3·93 grs. of sulphuric acid, in all 5·73 grs. for two cells. Calculated for 1 per cent., 1·72 gr. alumina and 3·76 grs. sulphuric acid, in all 5·48 grs. of sulphate of alumina in two cells at 65°·4.

2. 2·091 per cent. of sulphate of alumina, density 1·02251, diffused at 65°·4, gave 3·32 grs. of alumina and 7·35 grs. of sulphuric acid, in all 10·67 grs. for two cells. Calculated for 2 per cent., 3·18 grs. of alumina and 7·03 grs. of sulphuric acid, in all 10·21 grs. of sulphate of alumina for two cells at 65°·4.

3. 4·182 per cent. of sulphate of alumina, density 1·0438, diffused at 65°·4, gave 3·17 grs. of alumina and 6·91 grs. of sulphuric acid, in all 10·08 grs. for one cell. Calculated for 4 per cent., 3·03 grs. of alumina and 6·61 grs. of sulphuric acid, in all 9·64 grs. of sulphate of alumina for one cell at 65°·4.

4. 8·364 per cent. of sulphate of alumina, density 1·08518, diffused at 65°·4, gave 5·37 grs. of alumina and 12·15 grs. of sulphuric acid, in all 17·52 grs. for one cell. Calculated for 8 per cent., 5·14 grs. of alumina and 11·62 grs. of sulphuric acid, in all 16·76 grs. of sulphate of alumina for one cell at 65°·4.

Diffusion of Sulphate of Alumina in 16·166 days at 65°·4; two cells.

| | Grs. | Ratio. |
|---|---|---|
| From 1 per cent. solution . . . | 5·48 | 1·074 |
| From 2 per cent. solution . . . | 10·21 | 2 |
| From 4 per cent. solution . . . | 19·28 | 3·780 |
| From 8 per cent. solution . . . | 33·52 | 6·572 |

The diffusion of sulphate of alumina, it will be observed, is very sensibly less than that of sulphate of zinc at the same temperature.

### 30. *Nitrate of Silver.*

Time of diffusion seven days. The quantity of salt diffused was ascertained by precipitation with hydrochloric acid, and weighing the chloride of silver formed.

1. Nitrate of silver, 0·996 per cent.; density 1·0089. Diffusion at 51°·4, in eight cells, 5·39, 5·39, 5·74, 5·50; mean 5·50 grs. for two cells; calculated for 1 per cent., 5·52 grs. at 51°·4 for two cells.

2. Nitrate of silver, 1·98 per cent.; density 1·0161. Diffusion at 53°, in eight cells, 11·27, 11·16, 11·05, 11·06; mean 11·13 grs. for two cells; calculated for 2 per cent., 11·24 grs. at 53° for two cells.

3. Nitrate of silver, 1·967 per cent.; density 1·01696. Diffusion at 63°·41, in eight cells, 13·85, 13·29, 13·70, 12·73; mean 13·39 grs. for two cells; calculated for 2 per cent., 13·61 grs. at 63°·4 for two cells.

4. Nitrate of silver, 3·93 per cent.; density 1·032. Diffusion at 63°·4, in four cells, 13·27, 12·70, 12·90, 12·90; mean 12·94 grs. for one cell; calculated for 4 per cent., 13·17 grs. at 63°·4 for one cell.

5. Nitrate of silver, 7·88 per cent.; density 1·066. Diffusion at 63°·4, in four cells, 26·45, 25·49, 24·57, 25·73; mean 25·56 grs. for one cell; calculated for 8 per cent., 25·94 grs. at 63°·4 for one cell.

A rise of 10°·4 of temperature, or from 53° to 63°·4, increases the diffusibility of this salt from 11·24 to 13·61, or from 100 to 121·2; which is an increase of 2·04 per cent. for 1°.

Diffusion of Nitrate of Silver for seven days at 63°·4; two cells.

| | Grs. | Ratio. |
|---|---|---|
| From 2 per cent. solution . . . . | 13·61 | 2 |
| From 4 per cent. solution . . . . | 26·34 | 3·87 |
| From 8 per cent. solution . . . . | 51·88 | 7·62 |

### 31. *Nitrate of Soda.*

Time of diffusion seven days. The quantity of salt diffused was ascertained by evaporation to dryness.

1. Nitrate of soda, 1·987 per cent.; density 1·0130. Diffusion at 53°, in eight cells, 11·37, 10·44, 10·76, 10·40; mean 10·74 grs. for two cells; calculated for 2 per cent., 10·81 grs. for two cells.

2. Nitrate of soda, 1·998 per cent. Diffusion at 63°·4, in eight cells, 12·53, 12·38, 12·39, 12·06; mean 12·34 grs. for two cells; calculated for 2 per cent., 12·35 grs. for two cells.

3. Nitrate of soda, 3·98 per cent.; density 1·027. Diffusion at 63°·4, in four cells, 12·21, 11·32, 12·10, 11·31; mean 11·73 grs. for one cell; calculated for 4 per cent., 11·78 grs. for one cell.

4. Nitrate of soda, 7·96 per cent.; density 1·053. Diffusion at 63°·4, in four cells, 24·96, 22·53, 23·16, 24·38; mean 23·76 grs. for one cell; calculated for 8 per cent., 23·87 grs. for one cell.

A rise of temperature from 53° to 63°·4 increases the diffusibility of nitrate of soda from 10·81 to 12·35, or from 100 to 114·3, which is an increase of 1·37 per cent. for 1°. The increase on the nitrate of silver for the same rise of temperature appeared to be considerably greater, namely, 2·04 per cent. for 1°.

Diffusion of Nitrate of Soda in seven days at 63°·4; two cells.

| | Grs. | Ratio. |
|---|---|---|
| From solution of 2 per cent. . . . | 12·35 | 2 |
| From solution of 4 per cent. . . . | 23·56 | 3·82 |
| From solution of 8 per cent. . . . | 47·74 | 7·73 |

The ratios of the last column of the preceding Table are sensibly the same as those already obtained for nitrate of silver. But the diffusibility of nitrate of soda appears to be increased less rapidly by temperature than nitrate of silver. Hence the diffusibility of these two salts appears more similar at low than high temperatures.

Diffusion from 2 per cent. solutions in seven days at 53°.

| | | |
|---|---|---|
| Nitrate of silver . . . . | 11·24 | 100 |
| Nitrate of soda . . . . | 10·81 | 96·17 |

Diffusion from 2 per cent. solutions in seven days at 63°·4.

| | | |
|---|---|---|
| Nitrate of silver . . . . | 13·61 | 100 |
| Nitrate of soda . . . . | 12·35 | 90·74 |

32. *Chloride of Sodium.*

Time of diffusion seven days. The salt diffused was treated with nitrate of silver, and the chloride of silver weighed.

1. Chloride of sodium, 1 per cent. Diffused at 50°·5, in eight cells, 5·96, 5·69, 5·54, 5·50; mean 5·70 grs. of chloride of sodium for two cells.

2. Chloride of sodium, 0·985 per cent. Diffused at 53°·4, in eight cells, 5·86, 5·86, 5·77, 5·76; mean 5·81 grs. for two cells; calculated for 1 per cent., 5·89 grs. at 53°·4 for two cells.

3. Chloride of sodium, 1 per cent.; density 1·00776. Diffused at 63°·4, in eight cells, 6·30, 6·18, 6·52, 6·30; mean 6·32 grs. for two cells.

4. Chloride of sodium, 2 per cent.; density 1·01483. Diffused at 63°·4, in eight cells, 12·37, 12·08, 12·45, 12·53; mean 12·37 grs. for two cells.

5. Chloride of sodium, 4 per cent.; density 1·02879. Diffused at 63°·4, in four cells, 12·56, 12·65, 12·55, 12·17; mean 12·48 grs. for one cell.

6. Chloride of sodium, 8 per cent.; density 1·0562. Diffused at 63°·4, in four cells, 25·11, 25·36, 22·82, 23·59; mean 24·22 grs. for one cell.

The rise of temperature from 50°·5 to 63°·4 increases the diffusion of the 1 per cent. solution of chloride of sodium from 5·70 to 6·32, or from 100 to 110·9, which is an increase of 0·843 per cent. for 1°.

Diffusion of Chloride of Sodium in seven days at 63°·4; two cells.

| | Grs. | Ratio. |
|---|---|---|
| From 1 per cent. solution . . . | 6·32 | 1·023 |
| From 2 per cent. solution . . . | 12·37 | 2 |
| From 4 per cent. solution . . . | 24·96 | 4·036 |
| From 8 per cent. solution . . . | 48·44 | 7·832 |

These numbers resemble closely those obtained in the diffusion of chloride of barium during the longer period of 8·57 days.

The chloride of sodium and nitrate of soda will be seen to exhibit the usual approach to parallelism between the chloride and nitrate of the same metal, by the following comparison:—

Diffusion of Chloride of Sodium and Nitrate of Soda, both at 63°·4.

| | | |
|---|---|---|
| Chloride of sodium, 2 per cent. . . | 12·37 | 100 |
| Nitrate of soda, 2 per cent. . . . | 12·35 | 99·83 |
| Chloride of sodium, 4 per cent. . . | 24·96 | 100 |
| Nitrate of soda, 4 per cent. . . . | 23·58 | 94·48 |
| Chloride of sodium, 8 per cent. . . | 48·44 | 100 |
| Nitrate of soda, 8 per cent. . . . | 47·74 | 98·55 |

As usual the chloride is slightly more rapid in its diffusion than the nitrate.

### 33. *Chloride of Potassium.*

Time of diffusion 5·71 days. The salt diffused was treated with nitrate of silver, and the chloride of silver weighed.

1. Chloride of potassium, 1 per cent.; density 1·00697. Diffused at 62°, in eight cells, 6·70, 6·75, 6·53, 6·77; mean 6·69 grs. of chloride of potassium for two cells.

2. Chloride of potassium, 2 per cent.; density 1·01333. Diffused at 62°, in eight cells, 13·36, 13·35, 13·60, 12·96; mean 13·32 grs. for two cells.

3. Chloride of potassium, 4 per cent.; density 1·0258. Diffused at 62°, in four cells, 12·51, 13·21, 13·46, 12·71; mean 12·97 grs. for one cell.

4. Chloride of potassium, 8 per cent.; density 1·0503. Diffused at 62°, in four cells, 26·88, 26·64, 26·15, 27·63; mean 26·82 grs. for one cell.

Diffusion of Chloride of Potassium in 5·71 days at 62°; two cells.

| | Grs. | Ratio. |
|---|---|---|
| From 1 per cent. solution . . . | 6·69 | 1·005 |
| From 2 per cent. solution . . . | 13·32 | 2 |
| From 4 per cent. solution . . . | 25·94 | 3·895 |
| From 8 per cent. solution . . . | 53·64 | 8·054 |

The ratios are in remarkably close accordance with the proportions of salt diffused.

The times 5·71 and seven days chosen for the chloride of potassium and sodium, it will be observed, are as the square roots of 2 and 3. A certain deviation from this ratio of the times of equal diffusion, appears on comparing the experimental results obtained at present for these salts.

Diffusion of Chloride of Potassium in 5·71 days at 62°, and of Chloride of Sodium in 7 days at 63°·4.

| | | |
|---|---|---|
| Chloride of potassium, 1 per cent. . | 6·69 | 100 |
| Chloride of sodium, 1 per cent. . . | 6·32 | 94·47 |
| Chloride of potassium, 2 per cent. . | 13·32 | 100 |
| Chloride of sodium, 2 per cent. . . | 12·37 | 92·86 |
| Chloride of potassium, 4 per cent. . | 25·94 | 100 |
| Chloride of sodium, 4 per cent. . . | 24·96 | 96·23 |
| Chloride of potassium, 8 per cent. . | 53·64 | 100 |
| Chloride of sodium, 8 per cent. . . | 48·44 | 90·30 |

The difference would be about 1 per cent. greater if the diffusion of both salts were reduced to the same temperature. The chloride of potassium deviates of course from the nitrate of soda in a similar manner. But chloride of potassium corresponds more closely with nitrate of silver than with chloride of sodium and nitrate of soda, at the temperature of the experiments.

Diffusion of Chloride of Potassium for 5·71 days at 62°, and of Nitrate of Silver for 7 days at 63°·4.

| | | |
|---|---|---|
| Chloride of potassium, 2 per cent. . | 13·32 | 100 |
| Nitrate of silver, 2 per cent. . . . | 13·61 | 102·18 |
| Chloride of potassium, 4 per cent. . | 25·94 | 100 |
| Nitrate of silver, 4 per cent. . . . | 26·34 | 101·54 |
| Chloride of potassium, 8 per cent. . | 53·64 | 100 |
| Nitrate of silver, 8 per cent. . . . | 51·88 | 96·71 |

The coincidence in rate would appear even closer in the 2 and 4 per cent. solutions, if the diffusion of the nitrate of silver was diminished about 1 per cent., on account of its higher temperature. It might thus be supposed that the nitrate of silver followed the sodium rate more accurately than the nitrate of soda and chloride of sodium themselves do.

A series of observations were made upon the diffusion of the 1 per cent. solution of chloride of potassium at a nearly constant temperature of 56°, but for different times, varying from five days to eight days, and eighteen hours, to discover the progression, which proved to be pretty similar to that of the 2 per cent. solution of hydrochloric acid. Six cells were diffused for each period, of which the mean result is given: the times advance by ten hours.

Diffusion of Chloride of Potassium, 1 per cent. solution; two cells.

| Time. | Temperature. | Diffusion in two cells. | Differences. |
|---|---|---|---|
| 5 days. | 55°·71 | 5·89 | |
| 5 days 10 hours. | 55·90 | 6·25 | 0·36 |
| 5 days 20 hours. | 55·79 | 6·55 | 0·30 |
| 6 days 6 hours. | 55·79 | 6·71 | 0·16 |
| 6 days 16 hours. | 55·90 | 6·95 | 0·24 |
| 7 days 2 hours. | 55·9 | 7·48 | 0·53 |
| 7 days 12 hours. | 55·9 | 7·58 | 0·10 |
| 7 days 22 hours. | 56·03 | 8·08 | 0·50 |
| 8 days 8 hours. | 56·28 | 8·34 | 0·26 |
| 8 days 18 hours. | 56·15 | 8·60 | 0·26 |

When the quantities of chloride of potassium are placed beside the same quantities of hydrochloric acid in the former Table, it is found that the times of diffusion of the salt and acid exhibit an approximately constant ratio. The squares of these times of equal diffusion are as 1 to 2·04 for the shortest period of the chloride of potassium, and as 1 to 2·10 for the longest period but one. The variation in the differences towards the middle of the Table is too great to be explained, except I fear by some error of observation, although no ordinary precaution was neglected in the execution of this laborious series of experiments.

### 34. *Iodides and Bromides of Potassium and Sodium.*

*Iodide of Potassium.*—Time of diffusion 5·716 days. The diffusate was estimated by means of nitrate of silver.

(1.) Iodide of potassium, 1·977 per cent.; density 1·0145. Diffused at 53°·5, in eight cells, 11·415, 11·506, 10·942 and 11·062 grs.; mean 11·24 for two cells, and 11·36 for two per cent.

Comparing this salt with the isomorphous chloride of potassium, we have—

Diffusion of 2 per cent. solutions in 5·716 days.

| | | |
|---|---|---|
| Chloride of potassium at 55° . . . | 11·48 | 100 |
| Iodide of potassium at 53°·5 . . . | 11·36 | 99·65 |

The diffusion of the iodide would slightly exceed that of the chloride, instead of falling below it as in the Table, if the temperatures were made equal.

(2.) Again, iodide of potassium 1·971 per cent., observed density 1·01486. Diffused at 59°·8, in eight cells, and the mean diffusate of the whole cells determined, it gave 12·33 grs. of iodide of potassium for two cells; or 12·51 grs. for a 2 per cent. solution.

*Bromide of Potassium.*—Time of diffusion and mode of estimating diffusate as above. The solution contained 1·975 per cent. of salt, and had a density of 1·014850. Diffused

at 59°·8, in eight cells, it gave a mean diffusate of 12·30 grs. for two cells; or 12·46 grs. for 2 per cent.

For comparison, a solution of *chloride of potassium*, containing exactly 2 per cent. of salt and having the density 1·0133, was diffused in the same circumstances of time and temperature as the two preceding salts. The mean diffusate of eight cells was 12·24 grs. for two cells.

Hence the following result of the diffusion of three isomorphous salts:—

Diffusion of 2 per cent. solutions in 5·716 days, at 59°·8.

| | Grs. | Ratio. |
|---|---|---|
| Chloride of potassium . . . . | 12·24 | 100 |
| Bromide of potassium . . . . | 12·46 | 101·80 |
| Iodide of potassium . . . . . | 12·51 | 102·21 |
| Mean . . . . | 12·40 | |

*Iodide of Sodium.*—Time of diffusion 7 days, temperature 59°·8. A solution of 2·011 per cent. and density 1·01618, diffused in eight cells, gave a mean diffusate of 12·24 grs. for two cells; that is, 12·18 grs. for 2 per cent. solution.

*Bromide of Sodium.*—Time of diffusion and temperature as above. A solution of 2·146 per cent., of density 1·01726, diffused in eight cells, gave a mean diffusate of 12·80 grs.; that is, 11·93 grs. for 2 per cent.

A comparative experiment was made with a solution of *chloride of sodium*, containing 1·917 per cent. of salt and of density 1·01376, in eight cells, at 60°. The diffusates for four pairs of cells were 11·65, 11·75, 11·63 and 11·47 grs.; mean 11·63 grs., which gives by proportion 12·14 grs. for a 2 per cent. solution. As the present salt differs only 0°·2 FAHR. in diffusion-temperature from the two preceding salts, which is inadequate to produce an assignable difference of diffusion, the three salts may be supposed to be diffused at the same temperature, without sensible error.

Diffusion of 2 per cent. solutions for 7 days.

| | Grs. | Ratio. |
|---|---|---|
| Chloride of sodium at 60° . . . . | 12·14 | 100 |
| Bromide of sodium at 59°·8 . . . | 11·93 | 98·27 |
| Iodide of sodium at 59°·8 . . . . | 12·18 | 100·33 |
| Mean . . . . | 12·08 | |

In both these isomorphous groups of salts of potassium and sodium, there is certainly a near approach to equality of diffusion. The times for the salts of the two bases being in the empirical proportion of the square roots of 2 and 3, the mean diffusates also approach pretty closely; namely, 12·40 grs. for the salts of potassium and 12·08 grs. for the salts of sodium, which are as 100 to 97·42. Here the members of each group are certainly very similar to each other in density and probably other physical pro-

perties, which was not the case with the equidiffusive group containing the hydrogen acids of the same salt-radicals (p. 807).

35. *Chloride of Ammonium.*

Time of diffusion 5·716 days. The salt diffused was estimated by means of nitrate of silver.

Solution 0·988 per cent.; density 1·0036. Diffused at 53°, in eight cells, 6·09, 6·07, 5·67, 5·87; mean 5·92 grs., and 5·99 for one per cent. in two cells. This is somewhat more than 5·68, one-half of the diffusate of the 2 per cent. solution of iodide of potassium, at nearly the same temperature. The diffusion, however, of the small proportions of salts of ammonium, such as the 1 per cent. solution, is apt to be given in excess, from their low density.

36. *Dichloride of Copper.*

Time of diffusion seven days, or that of chloride of sodium. The salt diffused was obtained by evaporation to dryness, in an air-bath, after treating the liquid with an excess of chlorine, in the form of chloride, from which the dichloride was calculated.

It was an object of interest to discover whether the dichloride of copper ($Cu_2Cl$), which should be isomorphous with the chloride of sodium, may separate from the protochloride of copper and other magnesian salts, and assume the high diffusibility of the salts of alkaline metals. But the salt in question is entirely insoluble in water. A solution, however, was obtained by dissolving an equivalent quantity of the red suboxide of copper recently precipitated, in hydrochloric acid, of density 1·033, so as to give one grain of dichloride in every hundred water-grain measures of the solution. This acid solution did not precipitate by dilution with water. The salt was diffused into pure water at a mean temperature of 53°·2.

1. Dichloride of copper diffused, 6·66, 6·57, 7·01 and 6·48 grs.; mean 6·68 grs. in two cells. Chloride of sodium at 53°·4, nearly the same temperature, gave 5·90 grs. in the same time. Reducing the result to the temperature of 51° by an approximative correction, we should have 6·48 grs. of dichloride of copper for that temperature, at which chloride of calcium gave 6·51 grs. in 11·43 days, and protochloride of copper (Cu Cl) 6·06 grs. at nearly the same temperature, also in 11·43 days.

So far as we can judge from an experiment at a single temperature, it would appear that the diffusion of dichloride of copper is more rapid than that of the chloride (Cu Cl), in a proportion which supposes the former compound to possess half the "solution-density" of the latter, the times of equal diffusion 7 and 11·43 days, being when squared as 1 to 2.

With the view of discovering whether the large proportion of hydrochloric acid, amounting to 7 per cent., present in the preceding solution of dichloride of copper, modified the diffusion of the salt, a portion of the same acid solution was treated with chlorine gas, to convert the copper salt into chloride, and diffused into water, after

the excess of chlorine was removed by agitation of the solution with air. The proportion of salt present was thus increased in weight from 1 to 1·36 per cent. The time of diffusion was 11·43 days, and the temperature 53°.

2. Chloride of copper diffused from a 1·36 per cent. solution of the salt in hydrochloric acid, 5·83, 5·66, and 5·30 grs. in two cells; mean 5·60 grs.

The corresponding diffusion from a 1 per cent. solution may be supposed to be less than 5·6 grs., in the proportion of 1·36 to 1, without any great error. The results thus become chloride of copper diffused, 3·98, 3·85 and 3·58 grs.; mean 3·80 grs. in two cells.

It hence appears that the diffusion of chloride of copper is much diminished by the presence of a great excess of hydrochloric acid in the same solution. Different causes suggest themselves for this result, such as the possibility of a combination existing of chloride of copper with chloride of hydrogen, in the acid solution; or the influence which must be admitted of the more soluble substance, in a mixture of two similar substances, in repressing the diffusion of the less soluble. The present result, however, is entirely opposed to the idea that the high diffusibility of the dichloride of copper, observed before, is due to the hydrochloric acid present.

3. The diffusion of chloride of sodium also appears to be repressed by contact with a large excess of hydrochloric acid. One per cent. of chloride of sodium raised the density of dilute hydrochloric acid from 1·035 to 1·0408. Diffused into pure water for seven days at 52°·9, in eight cells, the diffusates of chloride of sodium were 3·80, 3·87, 4·00 and 3·86 grs.; mean 3·88 for two cells. The diffusion of chloride of sodium is thus reduced in a corresponding measure with that of chloride of copper by association with seven times its weight of hydrochloric acid.

These results are interesting in a very different point of view. I have always watched for the appearance of some absorbent or imbibing power on the part of the acids, more analogous to an endosmotic attraction for water, as usually conceived. If such an attraction existed, it would complicate the phenomena of diffusion, for the volume of water absorbed by the acid would displace and project a portion of the latter into the reservoir, the phial not being extensible. The high diffusibility of hydrochloric and nitric acids would be thus explained. But by such a mechanical displacement the chloride of sodium would be thrown out in the preceding experiment, as well as the hydrochloric acid, which is not the case.

4. Even in hydrochloric acid of density 1·124 (25 per cent.), the diffusion of 1 per cent. of chloride of sodium for seven days, at 56°·6, was found to amount to 4·7 grs. only in two cells, and is less than from a solution in pure water.

5. In comparing the influence of nitric acid with that of hydrochloric acid upon the diffusion of chloride of sodium, it was found that in a 7 per cent. solution of nitric acid, the chloride of sodium (1 per cent.) was entirely decomposed in the diffusive process, at 56°·6, and gave hydrochloric acid in the full diffusive equivalent of that acid, together with nitrate of soda.

### 37. *Bicarbonate of Potash.*

Time of diffusion 8·083 days, or double that of hydrate of potash. The water of the jars was partially charged with carbonic acid gas, to prevent the decomposition of this and the other bicarbonates in the act of diffusion. The usual number of eight cells of the 1 and 2 per cent. solutions were diffused, and four cells of the 4 and 8 per cent. solutions. The whole diffusates of each proportion were then mixed together, and the quantity of bicarbonate of potash diffused for two cells, converted into the chloride of potassium, evaporated to dryness and weighed.

1. 1·059 per cent. of bicarbonate of potash ($HO . CO_2 + KO . CO_2$), density 1·00788, diffused at 68°·2, gave 7·66 grs. for two cells. Calculated for 1 per cent., 7·23 grs. of bicarbonate of potash in two cells.

2. 2·12 per cent. of bicarbonate of potash, density 1·01489, diffused at 62°·2, gave 14·88 grs. for two cells. Calculated for 2 per cent., 14·05 grs. of bicarbonate of potash in two cells.

3. 4·236 per cent. of bicarbonate of potash, density 1·0288, diffused at 68°·2, gave 14·15 grs. for 1 cell. Calculated for 4 per cent., 13·36 grs. of bicarbonate of potash in one cell.

4. 8·472 per cent. of bicarbonate of potash, density 1·05600, diffused at 68°·2, gave 27·55 grs. for one cell. Calculated for 8 per cent., 26·01 grs. of bicarbonate of potash in one cell.

Diffusion of Bicarbonate of Potash in 8·08 days at 68°·2; two cells.

| | Grs. | Ratio. |
|---|---|---|
| From 1 per cent. solution . . . | 7·23 | 1·029 |
| From 2 per cent. solution . . . | 14·05 | 2 |
| From 4 per cent. solution . . . | 26·72 | 3·806 |
| From 8 per cent. solution . . . | 52·01 | 7·408 |

### 38. *Bicarbonate of Ammonia.*

Time of diffusion 8·083 days. The usual number of eight cells of the 1 and 2 per cent. solutions of this substance were diffused, and four cells of the 4 and 8 per cent. solutions. The whole diffusates of each proportion were then mixed together, and the quantity of bicarbonate of ammonia, diffused for two cells, determined by an alkalimetrical experiment, which was always repeated twice.

1. 1·109 per cent. of bicarbonate of ammonia ($HO . CO_2 + NH_4O . CO_2$), density 1·00553, diffused at 68°·2, gave 7·66 grs. for two cells. Calculated for 1 per cent., 6·91 grs. of bicarbonate of ammonia in two cells.

2. 2·218 per cent. of bicarbonate of ammonia, density 1·01056, diffused at 68°·2, gave 15·14 grs. for two cells. Calculated for 2 per cent., 13·65 grs. of bicarbonate of ammonia in two cells.

3. 4·436 per cent. of bicarbonate of ammonia, density 1·02000, diffused at 68°·2,

gave 14·98 grs. for one cell. Calculated for 4 per cent., 13·50 grs. of bicarbonate of ammonia in one cell.

4. 8·872 per cent. of bicarbonate of ammonia, density 1·03856, diffused at 68°·2, gave 27·78 grs. for one cell. Calculated for 8 per cent., 25·05 grs. of bicarbonate of ammonia in one cell.

Diffusion of Bicarbonate of Ammonia in 8·08 days at 68°·2; two cells.

| | Grs. | Ratio. |
|---|---|---|
| From 1 per cent. solution . . . . . | 6·91 | 1·013 |
| From 2 per cent. solution . . . . . | 13·65 | 2 |
| From 4 per cent. solution . . . . . | 27·00 | 3·959 |
| From 8 per cent. solution . . . . . | 50·10 | 7·346 |

The amount and progression of the diffusion of this salt correspond well, for all the proportions diffused, with the preceding isomorphous bicarbonate of potash.

### 39. *Bicarbonate of Soda.*

Time of diffusion 9·875 days. The usual number of eight cells of the 1 and 2 per cent. solutions were diffused, and four cells of the 4 and 8 per cent. solutions. The whole diffusates of each proportion were then mixed together, and the quantity of bicarbonate of soda, diffused for two cells, converted into chloride of sodium, evaporated to dryness and weighed.

1. 1·135 per cent. of bicarbonate of soda, $HO.CO_2+NaO.CO_2$, density 1·00892, diffused at 68°·1, gave 8·30 grs. for two cells. Calculated for 1 per cent., 7·31 grs. of bicarbonate of soda in two cells.

2. 2·27 per cent. of bicarbonate of soda, density 1·01703, diffused at 68°·1, gave 15·68 grs. for two cells. Calculated for 2 per cent., 13·81 grs. of bicarbonate of soda in two cells.

3. 4·54 per cent. of bicarbonate of soda, density 1·03306, diffused at 68°·1, gave 15·16 grs. for one cell. Calculated for 4 per cent., 13·35 grs. of bicarbonate of soda in one cell.

4. 9·08 per cent. of bicarbonate of soda, density 1·06386, diffused at 68°·1, gave 29·73 grs. for one cell. Calculated for 8 per cent., 26·19 grs. of bicarbonate of soda in one cell.

Diffusion of Bicarbonate of Soda in 9·87 days at 68°·1; two cells.

| | Grs. | Ratio. |
|---|---|---|
| From 1 per cent. solution . . . . . | 7·31 | 1·059 |
| From 2 per cent. solution . . . . . | 13·81 | 2 |
| From 4 per cent. solution . . . . . | 26·70 | 3·869 |
| From 8 per cent. solution . . . . . | 52·38 | 7·590 |

A remarkable approach to equality in the diffusion of the bicarbonates of potash

and soda, in the times chosen, is observed equally in all the proportions of salt from 1 to 8 per cent.

The results for the three bicarbonates may be stated as follows, the diffusate of the 2 per cent. solution of bicarbonate of potash being made equal to 200, as a standard of comparison.

Diffusion of Bicarbonates of Potash and Ammonia in 8·08 days, at 68°·2, and of Bicarbonate of Soda in 9·875 days, at 68°·1:

| | Bicarbonate of potash. | Bicarbonate of ammonia. | Bicarbonate of soda. |
|---|---|---|---|
| From 1 per cent. solution | 102·9 | 98·3 | 104·0 |
| From 2 per cent. solution | 200·0 | 194·3 | 196·4 |
| From 4 per cent. solution | 380·6 | 384·3 | 380·0 |
| From 8 per cent. solution | 740·8 | 712·6 | 748·3 |

Or, making the diffusate from each proportion of the bicarbonate of potash equal to 100:—

| | Bicarbonate of potash. | Bicarbonate of ammonia. | Bicarbonate of soda. |
|---|---|---|---|
| From 1 per cent. solution | 100 | 95·53 | 101·07 |
| From 2 per cent. solution | 100 | 97·15 | 98·20 |
| From 4 per cent. solution | 100 | 100·97 | 99·84 |
| From 8 per cent. solution | 100 | 96·19 | 101·03 |

The bicarbonate of ammonia is slightly lower in general than the bicarbonate of potash, possibly from a small loss of the former salt by evaporation in the different operations. The times chosen for these two bicarbonates is to that of the bicarbonate of soda, as the square root of 2 to the square root of 3, and the remarkable agreement observed in the diffusion of these salts gives support therefore to that relation. In alluding to this relation, however, it is proper to add that the carbonates of potash and soda deviate from it in a sensible degree, and the hydrates of potash and soda very considerably. If the relation therefore has a real foundation, it must be masked in the salts last named by differences existing between them in certain properties, the discovery and investigation of which is of the last importance for the theory of liquid diffusion.

40. *Hydrochlorate of Morphine.*

Time of diffusion 11·43 days. The crystallized salt was assumed to be of the composition $C_{34}H_{18}NO_6 . HCl + 6HO$, with the equivalent 374·5. The quantity diffused was determined from the chlorine, which was precipitated as chloride of silver in an acid solution. Hydrochlorate of morphine, 1·88 per cent. of the salt supposed anhydrous, diffused at 64°·1, in six cells, 11·03, 10·72, 11·01; mean 10·92 grs. of the anhydrous salt for two cells. Calculated for 2 per cent., 11·60 grs. at 64°·1 for two cells.

41. *Hydrochlorate of Strychnine.*

Time of diffusion 11·43 days. The crystallized salt was assumed to be of the composition $C_{42}H_{22}N_2O_4.HCl+3HO$, with the equivalent 397·5. Hydrochlorate of strychnine, 2 per cent., density 1·0065, diffused at 64°·1, in six cells, 11·54, 11·62, 11·31; mean 11·49 grs. for two cells. The quantities refer to anhydrous salt, and were estimated from the chlorine, as with hydrochlorate of morphine.

These two analogous salts appear to approach very closely in diffusibility.

Diffusion from 2 per cent. solutions at 64°·1; two cells.

| | | |
|---|---|---|
| Hydrochlorate of morphine . . . . | 11·60 | 100 |
| Hydrochlorate of strychnine . . . . | 11·49 | 99·05 |

For a similar period of 11·43 days, but at a lower temperature, 53°·4, the 1 per cent. solution of hydrochlorate of morphine gave a mean result of 5·49 grs. from two cells, and the hydrochlorate of strychnine 5·77 grs. from two cells. But the weights of chloride of silver from which these numbers are deduced were too small to admit of much precision.

The diffusion of these salts of organic bases in 11·43 days, is exceeded by the diffusion of chloride of ammonium or potassium in 5·71 days, or half the former time. The vegeto-alkalies appear thus to be divided from ammonia and potash.

The new observations of the present paper are favourable to the existence of a relation amounting to close similarity or equality in diffusibility between certain classes of substances.

The chlorides and nitrates of the same metal generally exhibit this corespondence, as in the chloride of calcium and nitrate of lime, the chloride of sodium and nitrate of soda, and also in hydrochloric and nitric acids.

Isomorphous salts exhibit the same relation, as has been observed in the chlorides, bromides and iodides of potassium, sodium and hydrogen, in various salts of baryta, strontia and lead, in numerous magnesian salts, in the salts of silver, soda, and probably those of suboxide of copper, and in several additional salts of potash and ammonia.

Corresponding salts of two of the vegeto-alkalies are also found to be equidiffusive.

Before discussing the relations between the different groups of equidiffusive substances which are thus formed, it will be necessary to examine their diffusion at widely different temperatures, a subject attended with considerable difficulty.

# INDEX

TO THE

# PHILOSOPHICAL TRANSACTIONS

## FOR THE YEAR 1850.

---

### A.

*Aden*, Hourly readings of the Barometer at, 318; range of temperature at, 333.
*Albumen of Eggs*, on the freezing of, 221.
Algebraic expression of the number of partitions of which a given number is susceptible, 399.
*Alkaloids, artificial*, on the nitrogenated principles of vegetables as the sources of, 47.
*Ammonia*, salts of, diffusion of, 25.
*Amyl, Bromide of*, its action upon aniline, 115; upon amylaniline, 116; upon ethylaniline, 117.
*Aniline*, action of phenyl-alcohol upon, 97; action of bromide of ethyl upon, 98; action of bromide and iodide of methyl upon, 113; action of bromide of amyl upon, 115.
*Arctomys Empetra and pruinosa*, on the dental structures in, 538–539.
*Atmospheric temperature*, on the effect of its changes on the temperature of the human body, 442.
*Auditory nerve*, development of, 195.

### B.

Bakerian Lecture, the, 1.
Barometrical observations in India, 298–321.
*Bases derived from aniline and ammonia*, their relation with other groups of alkaloids, 124.
*Belemnite and Belemnoteuthis*, supplementary observations on the structure of, 393.
*Bombay*, range of Barometer at, 305. Temperature at, 324. Rain at, 353–367. Winds, 369.
Brodie (Benjamin C., Esq.). On the Condition of certain Elements at the moment of Chemical Change, 759.
*Bromaniline*, action of bromide of ethyl upon, 109.
Brooke (Charles, Esq., M.B.). On the Automatic Registration of Magnetometers and Meteorological Instruments, by Photography, No. III., 83.
Brougham (Lord). Experiments and Observations upon the Properties of Light, 235.

C.

*Calcutta*, range of barometer at, 305. Temperature at, 324–332. Winds, 370.
CARPENTER (WILLIAM B., M.D.). On the Mutual Relations of the Vital and Physical Forces, 727.
*Castor fiber*, on the dental structures in, 539.
*Chemical change*, on the condition of certain elements at the moment of, 759.
*Chloraniline*, action of bromide of ethyl upon, 108.
*Chloride of sodium*, diffusion of, 6.
*Cœlogenys Paca*, on the dental tissues of, 554.
*Cohesion*, strength of, in different woods, 684.
*Contraction*, on induced, 645.
*Copper*, ammoniated salts of, diffusion of, 12.
*Crocodilia*, on the communications between the cavity of the tympanum and the palate in the, 526.

D.

*Dasyprocta Aguti*, on the dental structures of, 553.
DAVY (Dr. JOHN). On the Temperature of Man within the Tropics, 437.
Decomposition of salts by diffusion, 19.
*Development of the Tadpole of the Triton and the Frog*, on the influence of physical agents on the, 431.
*Diamagnetic bodies*, on the polar or other condition of, 171.
*Diethylaniline*, a new basic compound, 103; Hydrobromate of, 104; Platinum salt of, 105; action of bromide of ethyl on, 106; action of iodide of methyl upon, 114.
*Diffusion of Liquids*, on the, 1. Characters of liquid diffusion, 6. Diffusion of chloride of sodium, 6; of various salts, 8; of ammoniated salts of copper, 12. Separation of salts of different bases by diffusion, 16. Decomposition of salts by diffusion, 19. Diffusion of double salts, 21. Diffusion of one salt into the solution of another salt, 22. Diffusion of salts of potash and ammonia, 25. Diffusion of salts of soda, 40. Diffusion of sulphate of magnesia, 43.
*Diffusion of Liquids*. Supplementary observations on, 805. Hydrochloric acid, 806. Hydroiodic acid, Hydrobromic acid and bromine, 807. Hydrocyanic acid, 809. Nitric acid, 809. Sulphuric acid, 811. Chromic acid, *ibid.* Acetic acid, 812. Ammonia, 813. Alcohol, 814. Nitrate of baryta, 815. Nitrate of strontia, *ibid.* Nitrate of lime, 816. Acetate of lead, *ibid.* Acetate of baryta, 817. Chloride of barium, *ibid.* Chloride of strontium, 818. Chloride of calcium, 819. Chloride of manganese, 820. Nitrate of magnesia, *ibid.* Nitrate of copper, *ibid.* Protochloride of iron, 821. Sesquichloride of iron, *ibid.* Sulphate of magnesia, *ibid.* Sulphate of zinc, 822. Sulphate of alumina, 824. Nitrate of silver, *ibid.* Nitrate of soda, 825. Chloride of sodium, 826. Chloride of potassium, 827. Iodides and bromides of potassium and sodium, 829. Chloride of ammonium, 831. Dichloride of copper, *ibid.* Bicarbonate of potash, 833. Bicarbonate of soda, 834. Hydrochlorate of morphine, 835. Hydrochlorate of strychnine, 836.
*Dodabetta*, Barometrical Observations at, 300–304, 308–313. Temperature at, 335. Observations on the wet-bulb at, 338. Winds, 372.
Dynamic stability of floating bodies, 609.

E.

*Electricity*, atmospheric, observations on, in India, 374.
*Electro-Physiological Researches*, 287. Conductibility of the Muscles in relation to that of the Nerve, 288. Difference of excitability produced in a nerve according to the direction of the electric current, 289. Excitability of the nerves in relation to the integrity of the nervous system, 290. Analogy between electricity and nervous force, 294.
———————. Induced contraction, 645.
*Epping*, on the mean monthly temperature at, 572.
*Equations*, linear, in finite differences, and linear differential equations, 261.
*Ethyl*, Bromide of, its action upon aniline, 98; upon ethylaniline, 103; upon diethylaniline, 106; upon chloraniline and upon ethylochloraniline, 108; upon bromaniline, 109; upon nitraniline, 110; upon amylaniline, 117.
*Ethylaniline*, a new basic compound, 100. Hydrobromate of, 101. Platinum-salt of, *ibid.* Action of bromide of ethyl upon, 103. Action of iodide of methyl upon, 114. Action of bromide of amyl upon, 117.
*Ethylochloraniline*, action of bromide of ethyl upon, 109.
*Exercise*, on the effect of, on the temperature of the body, 441.
Experiments and observations upon the properties of light, 235.

F.

Fairbairn (William, Esq.). An Experimental Inquiry into the Strength of Wrought-Iron Plates and their Riveted Joints as applied to Ship-building and Vessels exposed to severe strains, 677.
Faraday (Prof. M.). Experimental Researches in Electricity. Twenty-third Series. § 29. On the polar or other condition of diamagnetic bodies, 171.
*Fiber zibethicus*, on the dental structures of, 550.
*Floating bodies*, on the dynamic stability and on the oscillations of, 609.
*Fogs*, observations on, in India, 374.
*Forces*, on the mutual relations of the vital and physical, 727.
*Fucusamide*, 473.
*Fucusine*, 474. Nitrate of, 475. Muriate of, 477. Double platinum-salt of, *ibid.* Oxalate of, *ibid.*
*Fucusol*, 471.
*Furfuramide*. Furfurol, 467.
*Furfurine*, double chloride of, and platinum, 470. Nitrate of, 476. Opake crystals of, *ibid.*

G.

*Gerbillus Shawii*, on the dental structures of, 549.
Glaisher (James, Esq.). Sequel to a paper on the reduction of the Thermometrical Observations made at the Apartments of the Royal Society, 569.
Graham (Prof. Thomas). On the Diffusion of Liquids, 1.
———————. Supplementary Observations on the Diffusion of Liquids, 805.
Gray (Henry, Esq.). On the Development of the Retina and Optic Nerve, and of the Membranous Labyrinth and Auditory Nerve, 189.
*Greenwich*, on the thermometrical observations taken at the Royal Observatory, 569. Comparison of the temperature at, with that at Somerset House, 579.

H.

HARGREAVE (C. J., Esq.). General Methods in Analysis for the resolution of Linear Equations in Finite Differences and Linear Differential Equations, 261.

*Heat*, mechanical equivalent of, 61. Friction of water, 66. Friction of mercury, 70–75. Friction of cast iron, 77–80.

HERSCHEL (Sir J. F. W.). On the Algebraic Expression of the number of Partitions of which a given number is susceptible, 399.

HIGGINBOTTOM (JOHN, Esq.). On the Influence of Physical Agents on the development of the Tadpole of the Triton and the Frog, 431.

HOFMANN (Dr. A. W.). Researches regarding the Molecular Constitution of the Volatile Organic Bases, 93.

*Hylæosaurus*, on a dorsal dermal spine of, 391.

*Hystrix cristata*, on the dental structures of, 552.

I.

*India*, meteorological observations in, 297.

J.

*Jerboa Ægyptius*, on the dental structures in, 544.

JONES (HENRY BENCE, M.D.). Contributions to the Chemistry of the Urine. Paper IV. On the so-called Chylous Urine, 651.

JOULE (JAMES P., Esq.). On the Mechanical Equivalent of Heat, 61.

L.

*Ligamentum Rotundum Uteri*, on the structure and use of, 515.

*Light*, experiments and observations upon the properties of, 235.

*Linear Equations in Finite Differences and Linear Differential Equations*. General methods in analysis for the resolution of, 261. Linear equations in finite differences, *ibid.* Solution of differential equations in series, 270.

*Liquid diffusion*, characters of, 6.

*Liquids*, on the diffusion of, 1. Supplementary observations, 805.

*Lyndon*, on the mean monthly temperature at, 569.

M.

*Madras*, range of barometer at, 305. Temperature at, 324–331. Winds, 368.

*Magnesia*, sulphate of, diffusion of, 43.

*Magnetic Observatories* (British). On the means adopted therein for determining the absolute values, secular change, and annual variation of the magnetic force, 201. Sources of irregularity in the indications of the Bifilar, 202, 203. Portable Unifilar Magnetometer, 204. Instruments employed at Toronto, 205. Monthly results, 208. Total Force, its mean value and secular change, 210. Annual variation, 211.

*Magnetometers*, automatic registration of, 83.

*Magnets*, scale and temperature coefficients of, new method of determining, 85.

Mantell (Dr. G. A.). On a Dorsal dermal Spine of the Hylæosaurus, recently discovered in the Strata of Tilgate Forest, 391.

———————. Supplementary Observations on the Structure of the Belemnite and Belemnoteuthis, 393.

———————. On the Pelorosaurus; an undescribed gigantic terrestrial reptile whose remains are associated with those of the Iguanodon and other Saurians in the Strata of Tilgate Forest, in Sussex, 379.

Marshall (John, Esq.). On the development of the Great Anterior Veins in Man and Mammalia; including an account of certain remains of Fœtal Structure found in the Adult, a Comparative View of these Great Veins in the different Mammalia, and an Analysis of their occasional peculiarities in the Human Subject, 133.

Matteucci (Signor Carlo). Electro-Physiological Researches. Eighth Series, 287.

———————————————————— Ninth Series. On Induced Contraction, 645.

Mechanical equivalent of heat, 61.

*Membranous labyrinth and auditory nerve*, on the development of, 195.

*Meteorological Instruments*, automatic registration of, 83.

*Meteorological Observations taken in India*, discussion of, 297. Diurnal tides, 298. Table of daily oscillations of the barometer at Dodabetta, 300. Range of barometer at Dodabetta, 304–308. Dates of the maximum and minimum pressure at Madras, and range of barometer at Madras, Bombay, Calcutta, &c., 305. Horary oscillations, 308, 309, 314. Table of monthly means of daily atmospheric tides, 311. Table of movements of the atmosphere in twenty-four hours in each month at Dodabetta, 313. Table of means of the hourly readings of the barometer at Aden, 318. Pressure of the atmosphere, 321. Temperature, 323. Table of monthly mean temperatures at Madras, Bombay and Calcutta, &c., 324. Curves of temperature at high levels, 330. Range of temperature and hours of maxima and minima:—Madras, 331; Calcutta, 332; Aden, 333. Range of temperature at high levels, 333; at Sattara, 334; Mahabuleshwur, 335; Dodabetta, *ibid.* Aqueous vapour, 336. Observations by the wet-bulb at Dodabetta, 338; at Mahabuleshwur, 339. Rain, 352; at Bombay, 353; on the coast of Malabar and Coromandel, 357. Rain at different elevations, 363. Register of pluviometer at Bombay, 367. Winds at Madras, 368; at Bombay, 369; at Calcutta, 370; at Mahabuleshwur, 372; at Dodabetta, *ibid.* Fogs, 374. Electricity, 374.

*Methyl*, bromide and iodide of, their action upon aniline, 113; iodide of, its action upon ethylaniline, 114.

*Methylaniline*, 113. Methylethylaniline, 114.

Molecular constitution of the volatile organic bases, 93.

Moseley (The Rev. Henry). On the Dynamic Stability and on the Oscillations of Floating Bodies, 609.

*Moss*, Lichens and Ferns, oils produced from, 478.

*Muridæ*, on the dental structures in, 542.

*Mus decumanus*, on the dental structure of, 546.

*Muscular fibres of uterus*, changes in, during gestation, 518.

*Myopotamus Coypus*, on the dental tissues of, 555.

*Myoxus avellanarius*, on the dental structure in, 543.

N.

*Nebulæ*, observations on, 499. Account of the great telescope of the Earl of Rosse, *ibid.*

*Nerves*, experiments on the section of, and observations of the alterations produced thereby in the structure of their primitive fibres, 423.

*Nitraniline*, action of bromide of ethyl upon, 110.

*Nitrogenated principles of vegetables*, on the, as the sources of artificial alkaloids, 47. *Phaseolus communis*, 48. *Linum usitatissimum*, 53. Wheat, 54. Peat, *ibid.* Distillation of wood, 55. Formation of organic bases from the nitrogenated principles of vegetables and animals by means of alkaline lye, 56; by sulphuric acid, 57; by putrefaction, 57–59. Guano, 57. Bases from *Lycopodium*, 59. Bases from *Pteris aquilina*.

*Notation*, on a system of, for the teeth in Mammalia, 481.

O.

*Observatories*, British Magnetic, 201.

*Octodon Degus*, on the dental tissues of, 555.

*Oils*, on the, produced by the action of sulphuric acid upon various classes of vegetables, 467. Furfuramide, *ibid.* Furfurol, *ibid.* Double chloride of furfurine and platinum, 470. Nitrate of furfurine, *ibid.* Fucusol, 471. Fucusamide, 473. Thiofucusol, *ibid.* Pyrofucusol, 474. Fucusine, *ibid.* Nitrate of fucusine, 475. Nitrate of furfurine, 476. Muriate of fucusine, 477. Double platinum salt of, *ibid.* Oxalate of, *ibid.* Oil from Moss, Lichens and Ferns, 478. Opake crystals of nitrate of furfurine, 480.

*Optic nerve*, development of, 189.

Oscillations of floating bodies, 609.

Owen (Professor R.). On the Development and Homologies of the Molar Teeth of the Wart-Hogs (*Phacochœrus*), with Illustrations of a System of Notation for the Teeth in the Class Mammalia, 481.

———————. On the Communications between the Cavity of the Tympanum and the Palate in the Crocodilia, 521.

P.

Paget (Professor James). Observations on the Freezing of the Albumen of Eggs, 221.

*Pelorosaurus Conybearii*, a gigantic fossil reptile, description of its remains, 379. Indications of, in the Oolitic strata, 384.

*Phacochœrus*, or Wart-Hogs, on the development and homologies of the molar teeth of, 481.

*Phenyl-alcohol*, its action upon aniline, 97.

Photography as a means of automatic registration, 83.

*Physical and Vital Forces*, on the mutual relations of, 727.

*Plates, wrought-iron*, on the strength of, 677.

*Potash*, salts of, diffusion of, 25.

*Pyrofucusol*, 474.

R.

*Rain*, fall of, in India, 352–367.

Rainey (G. Esq.). On the Structure and Use of the Ligamentum Rotundum Uteri, with some observations upon the changes which take place in the Structure of the Uterus during Gestation, 515.

*Registration, automatic*, of magnetometers and meteorological instruments by photography, 83.
*Reptile, fossil* (Pelorosaurus), description of, 379.
*Retina and optic nerve*, on the development of, 189.
*Rodentia*, on the dental tissues of the Order, 529.
*Rolling of ships*, on the, 611.
Rosse (The Earl of). Observations on the Nebulæ, 499.
*Royal Society*, on the thermometrical observations taken at the Apartments of, 569. Comparison of the temperature at, with that of Greenwich, 579.

S.

Sabine (Lieut.-Col. R.A.). On the means adopted in the British Colonial Magnetic Observatories for determining the Absolute Values, Secular Change, and Annual Variation of the Magnetic Force, 201.
*Salts*, double, diffusion of, 21.
*Salts*, various, diffusion of, 8.
*Sciurus niger*, on the dental structures in, 535.
*Sea-sickness*, on its effect on the temperature of the body, 445.
Separation of salts by diffusion, 16.
*Ship-building*, conclusions applicable to, from experiments and considerations on the dynamical stability, and on the oscillations of floating bodies, 632.
*Ships*, on the rolling of, 611; on the dynamic stability of, 612.
*Soda*, salts of, diffusion of, 40.
*Spalax typhlus*, on the dental structures in, 541.
Stenhouse (Dr. John). On the Nitrogenated Principles of Vegetables as the Sources of Artificial Alkaloids, 47.
———————. On the Oils produced by the Action of Sulphuric Acid upon various Classes of Vegetables, 467.
*Sulphuric acid*, on the oils produced by the action of, upon various classes of vegetables, *ibid.*
Sykes (Lieut.-Col. W. H.). Discussion of Meteorological Observations taken in India, at various heights, embracing those at Dodabetta, on the Neelgherry Mountains, at 8640 feet above the level of the Sea, 297.

T.

*Tadpole of the Triton and the Frog*, on the influence of physical agents on the development of, 431; of the Triton, *ibid.*; of the Frog, 432. On the influence of atmospheric air, *ibid.*; of food, 433; of temperature, 434; of light, 435.
*Tamias Lysteri*, on the dental structures in, 538.
*Teeth*, a system of notation for, in the Class Mammalia, 481.
*Teeth, molar, in the Wart-Hogs* (*Phacochœrus*), on the development and homologies of, 481.
*Temperature of India*, observations on, 323–335.
*Temperature of Man within the Tropics*, on the, 437; variation of, during the twenty-four hours, *ibid.*; during different seasons of the year, 439; of the effect of active exercise and of rest after exercise, 440; of the effect of carriage exercise and of gentle walking exercise, 441; of the effect of change of temperature of the atmosphere, 442; of the effect of excited

and sustained attention, 443; of the effect of cool and heated rooms, 444; of the effect of sea-sickness, 445; of the effect of the temperature at sea, 446.

*Thames*, mean monthly temperature of the water of the, 576.

*Thermometer apparatus*, self-registering, 83.

*Thermometrical observations* (on the reduction of) *made at the Apartments of the Royal Society and at the Royal Observatory, Greenwich*, &c., 569.

*Thiofucusol*, 473.

*Tides*, researches on, 227.

Tomes (John, Esq.). On the Structure of the Dental Tissues in the Order Rodentia, 529.

*Toronto*, Magnetic Observatory at, 205.

*Triethylamine*, formation of, 121.

*Tropics*, on the temperature of man within the, 437.

*Tympanum and palate of the Crocodilia*, communications between them, 526.

U.

*Urine*, Contributions to the Chemistry of. On chylous urine, 551. On the influence of rest and motion in lessening or increasing the albumen in the urine previous to and after food was taken, 655.

*Uterus*, on the changes which take place in the structure of, during utero-gestation, 518.

V.

*Vegetables*, on the action of sulphuric acid upon, and the oils produced thereby, 467.

*Veins, Great Anterior, in Man and Mammalia*, on the development of, 133. Metamorphosis of the primitive lateral and symmetrical venous trunks, 137; development in the Sheep, 137; in Man, 141. Comparative view of those veins in Man and Mammalia, 148. Analysis of the varieties of these veins in Man, 153.

*Vital and Physical Forces*, on the mutual relations of, 727.

*Volatile organic bases*, on the molecular constitution of, 93.

W.

Waller (Dr. Aug.). Experiments on the Section of the Glossopharyngeal and Hypoglossal Nerves of the Frog, and observations of the alterations produced thereby in the Structure of their Primitive Fibres, 423.

*Wart-Hogs* (*Phacochœrus*), on the development and homologies of the molar teeth of, 481.

*Wet-bulb thermometer*, observations on, in India, 336 *et seq.*

Whewell (Rev. W., D.D.). Researches on the Tides.—Fourteenth Series, 227.

*Winds*, observations on, in India, 368–372.

*Woods, various*, on the strength of direct cohesion in, 684.

*Wrought-iron plates*, on the strength of, 677.

LONDON:
PRINTED BY RICHARD AND JOHN E. TAYLOR,
RED LION COURT, FLEET STREET.

# PRESENTS

RECEIVED BY

# THE ROYAL SOCIETY,

WITH THE

## NAMES OF THE DONORS.

---

### From November 1849 to June 1850.

| PRESENTS. | DONORS. |
|---|---|
| **ACADEMIES and SOCIETIES.** | |
| Abbeville :— | |
| Mémoires de la Société d'Émulation. 8vo. *Abbeville* 1849. | The Society. |
| Amsterdam :— | |
| Verhandelingen der eerste Klasse van het Koninklijk-Nederlandsche Instituut van Wetenschappen, Letterkunde en Schoone Kunsten te Amsterdam. Vol. II. Part 1. 1848. Derde Reeks. Eerste Deel. 4to. *Amsterdam* 1849. | The Institute. |
| Jaarboek van het Koninklijk-Nederlandsche Instituut voor 1847–9. 8vo. *Amsterdam* 1847–9. | ——— |
| Tijdschrift voor de Wis- en Natuurkundige Wetenschappen van het Koninklijk-Nederlandsche Instituut. Vol. II. Parts 3, 4. Vol. III. Parts 1, 2. 8vo. *Amsterdam* 1849. | ——— |
| Berlin :— | |
| Abhandlungen der Akademie der Wissenschaften zu Berlin für 1847. 4to. *Berlin* 1849. | The Academy. |
| Monatsbericht. Jan. to Dec. 1849. 8vo. | ——— |
| Bologna :— | |
| Novi Commentarii Academiæ Scientiarum Instituti Bononiensis. Tomus IX. 4to. *Bononiæ* 1849. | The Academy. |
| Bombay :— | |
| Transactions of the Bombay Geographical Society from October 1848 to May 1849. 8vo. *Bombay* 1849. | The Society. |
| Breslau :— | |
| Uebersicht der Arbeiten und Veränderungen der Schlesischen Gesellschaft für vaterländische Kultur im Jahre 1848. 4to. *Breslau* 1849. | The Society. |
| Brussels :— | |
| Mémoires de l'Académie Royale des Sciences de Belgique. Tome XXIII. 4to. *Bruxelles* 1849. | The Academy. |
| Bulletins. Tome XV. Part 2. Tome XVI. Part 1. 8vo. *Bruxelles* 1848–9. | ——— |

| Presents. | Donors. |
|---|---|
| **ACADEMIES and SOCIETIES (*continued*).** | |
| Brussels:— | |
| Annuaire de l'Académie Royale des Sciences de Belgique. 8vo. *Bruxelles* 1849. | The Academy. |
| Calcutta:— | |
| Journal of the Asiatic Society of Bengal. Nos. 203 to 207. 8vo. *Calcutta.* | The Society. |
| Cambridge:— | |
| Transactions of the Cambridge Philosophical Society. Vol. VIII. 4to. *Cambridge* 1849. | The Society. |
| Cambridge (United States):— | |
| Memoirs of the American Academy of Arts and Sciences. Vol. IV. Part 1. 4to. *Cambridge* 1849. | The Academy. |
| Connecticut:— | |
| Memoirs of the Connecticut Academy of Arts and Sciences. Vol. I. Parts 1 to 4. 8vo. *New Haven* 1810–16. | H. Stevens, Esq. |
| Cornwall:— | |
| Transactions of the Royal Geological Society of Cornwall. Vol. I. 8vo. *London* 1818. | The Society. |
| Annual Reports. 1845–46 and 1849. 8vo. *Penzance* 1845–46–49. | ——— |
| Dublin:— | |
| Transactions of the Royal Irish Academy. Vol. XXII. Parts 1 and 2. 4to. *Dublin* 1849–50. | The Academy. |
| Proceedings. Vol. IV. Part 2. 8vo. *Dublin* 1849. | ——— |
| Journal of the Geological Society of Dublin. Vol. IV. Parts 1 and 2. 8vo. | The Society. |
| Edinburgh:— | |
| Transactions of the Royal Society of Edinburgh. Vol. XVI. Part 5, and Vol. XIX. Part 1, being Observations in Magnetism and Meteorology made at Makerstoun in Scotland in 1845–46. Edited by J. A. Broun, Esq. 4to. *Edinburgh* 1849. | The Society. |
| Proceedings. Vol. II. Nos. 33 and 34. | ——— |
| Transactions of the Royal Scottish Society of Arts. Vol. III. Part 4. | The Society. |
| Geneva:— | |
| Mémoires de la Société de Physique et d'Histoire Naturelle de Genève. Tome XII. Part 1. 4to. *Genève* 1849. | The Society. |
| Glasgow:—Proceedings of the Philosophical Society. Vol. III. No. 1. | The Society. |
| Göttingen:—Nachrichten von der Georg-Augusts Universität und der K. Gesellschaft der Wissenschaften von 1849. Nos. 1 to 14. | The Society. |
| Hobarton:— | |
| Papers and Proceedings of the Royal Society of Van Diemen's Land. Vol. I. Part 1. | The Society. |
| Leeds:—Annual Reports of the Leeds Philosophical and Literary Society for 1847–48–49. 8vo. *Leeds* 1848–49. | The Society. |
| Liverpool:—Proceedings of the Literary and Philosophical Society of Liverpool. No. 5. 8vo. *London* 1849. | The Society. |
| London:— | |
| The Journal of the British Archæological Association. Nos. 16 to 20. | The Association. |
| British Association. Reports of the Eighteenth and Nineteenth Meetings. 8vo. *London* 1849–50. | The Association. |

| PRESENTS. | DONORS. |
|---|---|
| **ACADEMIES and SOCIETIES (*continued*).** | |
| London :— | |
| Chemical Society. Quarterly Journal. Nos. 6 to 9. 8vo. *London*. | The Society. |
| Geographical Society. Journal. Vol. XIX. 8vo. *London* 1849. | The Society. |
| Geological Society. Quarterly Journal. Nos. 19, 20, 21. 8vo. *London* 1849–50. | The Society. |
| Horticultural Society. Transactions. Second Series. 4to. Vol. III. Parts 2, 3. | The Society. |
| ——— Journal. Vol. III. Parts 2, 3. Vol. IV. Parts 1 to 4. Vol. V. Parts 1, 2. 8vo. *London* 1848–50. | ——— |
| Linnean Society. Charter and Bye-Laws. 8vo. *London* 1848. | The Society. |
| ——— List of Fellows. 1849. | ——— |
| Royal Agricultural Society. Journal. Vol. X. 8vo. *London* 1849. | The Society. |
| Royal Asiatic Society. Journal. Vol. XI. Part 1, and Vol. XII. 8vo. *London* 1849. | The Society. |
| Royal Astronomical Society. Memoirs. Vol. XVIII. 4to. *London* 1850. | The Society. |
| ——— Monthly Notices. Vol. IX. 8vo. *London* 1849. | ——— |
| Royal Medical and Chirurgical Society. Transactions. Second Series. Vol. XIV. 8vo. *London* 1849. | The Society. |
| Statistical Society. Journal. Vol. XII. 8vo. *London* 1850. | The Society. |
| Zoological Society. Reports of the Council and Auditors for 1849. | The Society. |
| Mauritius :—Transactions of the Royal Society of Arts and Sciences for 1847–48. 8vo. *Mauritius* 1849. | The Society. |
| Milan :— | |
| Effemeridi Astronomiche di Milano, per l'anni 1834–36, 1837–38, 1842–48, 1849–50, and Four Supplements. | The Institute. |
| Giornale dell Istituto Lombardo di Scienze. Parts 1 to 6. 4to. *Milano* 1847–48. | ——— |
| ——— 8vo. *Milano* 1846–47. | ——— |
| Memoria del F. Meguscher in risposta al quesito additare la migliore e più facile maniera per rimettere i Boschi nelle montagne diboschite dell' alta Lombardia. 8vo. *Milano* 1847. | ——— |
| Munich :— | |
| Abhandlungen der Philosophisch-Philologischen Classe der König. Bayerischen Akademie der Wissenschaften. Vol. V. Part 3. 4to. *München* 1849. | The Academy of Sciences at Munich. |
| Abhandlungen der Mathematisch-Physikalischen Classe. Vol. V. Part 3. 4to. *München* 1849. | ——— |
| Abhandlungen der Historischen Classe. Vol. V. Parts 2, 3. 4to. *München* 1849. | ——— |
| Almanach für 1849. | ——— |
| Gelehrte Anzeigen. Nos. 28–29. | ——— |
| Bulletin. Nos. 1 to 37. | ——— |
| Naples :— | |
| Escercitazioni Accademiche degli Aspiranti Naturalisti. 8vo. *Napoli* 1839. | The Academy. |
| Atlante della Statistica Fisica ed Economica dell' Isola di Capri. 4to. *Napoli* 1840. | ——— |
| Rendiconto della Reale Accademia delle Scienze. Nos. 39 to 45. 4to. *Napoli* 1849. | ——— |

| Presents. | Donors. |
|---|---|
| ACADEMIES and SOCIETIES (*continued*). | |
| New York:—Annals of the Lyceum of Natural History. Vol. IV. No. 12. Vol. V. No. 1. 8vo. *New York* 1849. | The Lyceum. |
| Paris:— | |
| Comptes Rendus de l'Académie des Sciences. Tome XXX. 1849. Nos. 1 to 21, 1850. 4to. *Paris.* | The Academy. |
| Bulletin de la Société de Géographie. Tomes X. XI. 8vo. *Paris* 1849. | The Society. |
| Mémoires de la Société Géologique de France. Vol. III. Part 2. 4to. *Paris* 1850. | The Society. |
| Bulletin. Vol. VII. Nos. 1 to 13. 8vo. | ——— |
| Journal de l'École Polytechnique. Vols. XVIII. XIX. 4to. *Paris* 1847–48. | The French Minister of War. |
| Philadelphia:— | |
| Journal of the Academy of Natural Sciences. New Series. Vol. I. Parts 3 and 4. 4to. *Philadelphia* 1849–50. | The Academy. |
| Proceedings. Vol. IV. Nos. 11 and 12, Vol. V. No. 1. 8vo. | ——— |
| Proceedings of the American Philosophical Society. Nos. 42 to 44. Vol. V. 8vo. | The Society. |
| Journal of the Franklin Institute. Vols. XV. XVI. XVII. 8vo. *Philadelphia* 1848–49. | The Institute. |
| Stockholm:— | |
| Årsberättelser om Botaniska Arbeten och Upptackter för åren 1843 och 1844, till Kongl. Vetenskaps-Akademien, af J. E. Wikström. Förra & sednare Delen. 8vo. *Stockholm* 1849. | Royal Academy of Sciences at Stockholm. |
| Årsberättelse om Technologiens Framsteg, till Kongl. Vetenskaps-Akademien, afgifven den 31 Mars 1842–44, 1846, af G. E. Pasch. 8vo. *Stockholm* 1849. | ——— |
| Öfversigt af Kongl. Vetenskaps-Akademiens Förhandlingar. Arg. 5. Nos. 7 to 10, 1848. | ——— |
| Kongl. Vetenskaps-Akademiens Handlingar för år 1847–48. 8vo. *Stockholm* 1849. | ——— |
| Några reflexioner i anledning af kemins studium och om denna vetenskaps ställning i staten. Tal: af L. F. Svanberg. 8vo. *Stockholm* 1849. | ——— |
| Årsberättelse om Framstegen i Kemi under år 1847 afgifven till Kongl. Vetenskaps-Akademien, af L. F. Svanberg. 8vo. *Stockholm* 1849. | ——— |
| Toulouse:—Mémoires de l'Académie de Toulouse. Tomes IV. V. VI. and Tome I. 3rd Series. 8vo. *Toulouse* 1837–39, 1843–44. | The Academy. |
| Turin:—Memorie della Reale Accademia delle Scienze di Torino. Tomo X. 4to. *Torino* 1849. | The Academy. |
| Utrecht:— | |
| Scheikundige Onderzoekingen Gedaan in het Laboratorium der Utrechtsche Hoogeschool. 5de Deel. 6 & 7de Stuk. 8vo. *Rotterdam* 1850. | The High School of Utrecht. |
| AIRY (G. B.) Astronomical Observations made at Greenwich in 1847. 4to. *London* 1849. | The Admiralty. |
| ——— Catalogue of 2156 Stars, formed from the Observations made during Twelve Years, from 1836 to 1847, at the Royal Observatory, Greenwich. 4to. *London* 1849. | ——— |
| ——— Magnetical and Meteorological Observations made at the Royal Observatory, Greenwich, in 1847. 4to. *London* 1849. | ——— |

| Presents. | Donors. |
|---|---|
| ANONYMOUS:— | |
| A Congratulatory Address to Mr. Robert Brown, from the Royal Botanical Society of Ratisbon, on that gentleman being elected President of the Linnean Society. | Dr. Wallich, F.R.S. |
| Anatomical Drawings selected from the Collection of Morbid Anatomy in the Army Medical Museum at Chatham. 5th Fasciculus. fol. *London* 1850. | Sir James MacGrigor, Bart. |
| A Natural Scale of Heights, constructed by Miss Colthurst. A sheet. | G.B.Greenough,Esq.,F.R.S. |
| Annales des Mines. Tomes XIII. to XVI. 8vo. *Paris* 1848–49. | Bureau des Mines, Paris. |
| Annales Hydrographiques, Années 1848–49. Tome I. 8vo. *Paris* 1849. | Bureau des Longitudes. |
| Annuaire des Marées des Côtes de France pour 1848–49. 12mo. *Paris* 1848–49. | ——— |
| Arctic Papers, published by the Admiralty. | The Admiralty. |
| Buildings and Monuments, edited by G. Godwin, F.R.S. Parts 3 to 6. fol. *London* 1849. | The Editor. |
| Catalogue of the Calcutta Public Library, and Report thereon. 8vo. *Calcutta* 1846. | The Library. |
| Die Fortschritte der Physik im Jahre 1847. Redigirt von Professor Karsten. 8vo. *Berlin* 1849. | Dr. Du Bois-Reymond. |
| Flora Batava. Nos. 150, 151, 159, 161, 162. 4to. | The King of the Netherlands. |
| Further Report on the proposed Great Exhibition of Industry, by the Executive Committee. fol. *London* 1849. | The Committee. |
| Index to the Additional Manuscripts in the British Museum. fol. *London* 1849. | The Trustees of the British Museum. |
| Letter to Lord John Russell on the Constitutional Defects of the University and Colleges of Oxford. By a Member of the Oxford Convocation. 8vo. *London* 1850. | The Author. |
| List of the Fellows and Members of the Royal College of Surgeons for 1849. 8vo. *London* 1849. | The College. |
| Magnetic and Meteorological Observations made under the direction of A.D. Bache, 1840–1845. 3 vols. and Atlas. 8vo. *Washington* 1847. | Dr. Forbes, F.R.S. |
| Observations Météorologiques faites à Nijne Taguilsk en 1846–47. 8vo. *Paris* 1846–47. | Prince Demidoff. |
| Quarterly Reports of the Registrar-General. Nos. 2 to 5. 8vo. *London* 1849–50. | The Registrar-General. |
| Report of the Commissioners appointed to inquire into the application of Iron to Railway Structures. fol. *London* 1849. | The Commissioners. |
| Plans accompanying the Report. | ——— |
| Report of the Commissioner of Patents for the United States. 8vo. *Washington* 1848. | The Commissioner. |
| Report of the Eleventh French Exposition of the Products of Industry. fol. *London* 1849. | D. Wyatt, Esq. |
| Report of the General Board of Health on the Supply of Water to the Metropolis. 8vo. *London* 1850. | The Commissioners of the General Board of Health. |
| Report on a General Scheme for Extramural Sepulture. 8vo. *London* 1850. | ——— |
| Report on the Nature and Import of certain Microscopic Bodies found in the Intestinal Discharges of Cholera. Presented to the Cholera Committee of the Royal College of Physicians of London, by their Sub-Committee, on Oct. 17, 1849. 8vo. *London* 1849. | The College of Physicians. |

| Presents. | Donors. |
|---|---|
| ANONYMOUS (*continued*). | |
| Tableau général des Phares et Fanaux des Côtes de Hollande et de Belgique. 8vo. *Paris* 1849. | Dépôt de la Marine. |
| The Helix considered as a Propeller of Steam Vessels. 8vo. *New York* 1849. | The Author. |
| The Sanitary Movement. 8vo. *Edinburgh* 1850. | The Author. |
| The Zoology of the Voyage of H.M.S. Samarang. Nos. 4, 5. 4to. *London* 1849. | The Editors. |
| Weekly and Quarterly Reports of the Registrar-General for 1849. | The Registrar-General. |
| ANSTED (D. T.) An Elementary Course of Geology, Mineralogy and Physical Geography. 8vo. *London* 1850. | The Author. |
| ART (Works of, &c.). | |
| A Wire which vibrates in a Parabolic Curve. | Mr. Perigal. |
| Original Drawing of Sir Isaac Newton, made for Roubilliac's Statue of that Philosopher at Cambridge. | Rev. C. Turnor, F.R.S. |
| ATKINS (Mrs.) The British Algæ. Parts 11 and 12. 4to. | The Author. |
| BARBIER (J. B. G.) Quelques Réflexions sur la Psychologie. 8vo. *Paris* 1849. | The Author. |
| BEAUTEMPS-BEAUPRÉ (C. F.) Rapports sur les Rades, Ports et Mouillages de la Côte Orientale du Golfe de Venise. 8vo. *Paris* 1849. | Bureau de la Marine. |
| BEKE (C. T.) On the Geographical Distribution of the Languages of Abessinia and the neighbouring Countries. 8vo. *Edinburgh* 1849. | The Author. |
| ———— On the Sources of the Nile. 8vo. *London* 1849. | ———— |
| ———— Ueber die geographische Verbreitung der Sprachen von Abessinien und der Nachbarländer. | ———— |
| BEROABLO (N. de.) L'Armonia Universale in sesta Rima. 4to. *Vienna* 1846. | The Author. |
| ———— Repulsione Centrale, Opera a complimento del Poema 'l'Armonia Universale.' 4to. *Vienna* 1849. | ———— |
| BIBO (H.) Erfindung und Bearbeitung einer neuen, durch die 2 gleichmässig ohne Brüche theilbaren Decimal-Rechnung, aus einem neuen Zahlensysteme hergeleitet. 8vo. *Berlin* 1850. | The Author. |
| BILLING (Dr.) Principles of Medicine. 5th edit. 8vo. *London* 1850. | The Author. |
| BIOT (J. B.) Une Anecdote relative à M. Laplace. 4to. | The Author. |
| BLAIR (Daniel.) Some Account of the last Yellow Fever Epidemic of British Guiana. 8vo. *London* 1850. | The Author. |
| BOURNE (John.) A Report on Indian River Navigation. 8vo. *London* 1849. | The Author. |
| ———— A Catechism of the Steam Engine. 8vo. *London* 1850. | ———— |
| BRODIE (Sir B. C.) Lectures on the Diseases of the Urinary Organs. 8vo. *London* 1849. | The Author. |
| ———— Pathological and Surgical Observations on the Diseases of the Joints. 8vo. *London* 1850. | ———— |
| BRYSON (Dr.) Statistical Reports of the Health of the Royal Navy. fol. *London* 1850. | Sir W. Burnett, M.D. |
| BUCHNER (L. A.) Ueber den Antheil der Pharmacie an der Entwicklung der Chemie. 4to. *München* 1849. | Acad. of Sciences, Munich. |
| BUSCH (A. L.) Verzeichniss sämmtlicher Werke, Abhandlungen, Aufsätze und Bemerkungen von F. W. Bessel. 4to. *Königsberg* 1849. | The Author. |
| ———— Astronomische Beobachtungen auf der Königlichen Universitäts-Sternwarte in Königsberg im 1843–8. fol. *Königsberg* 1848. | ———— |

| Presents. | Donors. |
|---|---|
| CARAMAN (Le Duc de.) Histoire des Révolutions de la Philosophie en France pendant le moyen âge, jusqu'au 16me siècle. Vol. III. 8vo. *Paris* 1848. | The Author. |
| COX (C. J.) On the Ravages committed by the *Scolitus Destructor* and Larva of the *Cossus Ligniperda*. 4to. *London* 1848. | The Author. |
| CURLING (T. B.) Article Testicle, from the Cyclopædia of Anatomy and Physiology. 8vo. | The Author. |
| DANA (J. D.) On the Isomorphism and Atomic Volume of some Minerals. | The Author. |
| DARONDEAU (B.) Mélanges Hydrographiques. Tomes I. II. III. 8vo. *Paris* 1846–7–8. | Bureau de la Marine. |
| DELESSE (A.) Recherches sur le Porphyre Quartzifère. | Bureau des Mines. |
| ——————— Recherches sur l'Euphotide. | ——— |
| ——————— Sur le Pouvoir Magnétique des Roches. | ——— |
| ——————— Sur la Constitution Minéralogique et Chimique des Roches des Vosges. | ——— |
| DEMIDOFF (Prince.) Voyage dans la Russie Méridionale et la Crimée. Livraisons 13 to the end. fol. | The Author. |
| DE MORGAN (A.) Method of Integrating Partial Differential Equations. 4to. *Cambridge* 1848. | Cambridge Phil. Society. |
| DIXON (R. V.) A Treatise on Heat. Part 1. 8vo. *Dublin* 1849. | The Author. |
| DOLLEN (W.) Neue Reduction der Königsberger Declinationen für 1820. 4to. *St. Petersburg* 1849. | The Author. |
| EENENS (M.) Mémoire sur la Fertilisation des Landes. 8vo. *Bruxelles* 1849. | The Author. |
| EMIL DU BOIS-REYMOND. Untersuchungen über Thierische Elektricitat. 2 vols. 8vo. *Berlin* 1848. | The Author. |
| ENCKE (J. F.) Astronomisches Jahrbuch für 1852. 8vo. *Berlin* 1849. | The Observatory of Berlin. |
| FALCONER (H.) and CAUTLEY (P. T.) Fauna Antiqua Sivalensis. Parts 1 to 9. fol. Text, Part 1. *London* 1845–9. | The Ordnance Survey. |
| FALLOWS (F.) Cape Observations, 1829–31. 4to. *London* 1850. | The Astronomer Royal. |
| FARREN (Edwin James.) Life Contingency Tables. Part 1. | The Author. |
| FELLOCKER (S.) Verzeichniss der von Bradley, Piazzi, Lalande und Bessel beobachteten Sterne in dem Theile des Himmels zwischen $6^h\ 56'$ bis $8^h\ 4'$ gerader Aufsteigung und 15° sudlicher bis 15° nordlicher Abweichung berechnet. With a sheet. fol. *Berlin* 1848. | The Author. |
| FOURCAULT (A.) Causes générales des Maladies chroniques. 8vo. *Paris* 1844. | The Author. |
| FROST (James.) Description of the Causes of the Explosion of Steam-Boilers. 8vo. *New York* 1848. | The Author. |
| FUSINIERI (Dr.) Memorie sopra la Luce, il Calorico, l' Elettricità, il Magnetismo, l' Elettro-Magnetismo ed altri Oggetti. 4to. *Padova* 1846. | The Author. |
| ——————— Memorie di Meteorologia. 4to. *Padova* 1847. | ——— |
| FUSS (P. H.) Ueber L. Euleri Commentationes Arithmeticæ Collectæ. 8vo. *Petrop.* 1848. | The Author. |
| GALTON (F.) The Telotype, a Printing Electric Telegraph. 8vo. *London* 1850. | The Author. |
| GARNER (R.) Natural History of the County of Stafford. 8vo. *London* 1844. | The Author. |
| GILBART (J. W.) Practical Treatise on Banking. 2 vols. 8vo. *London* 1849. | The Author. |
| ——————— A Lecture on the Philosophy of Language. 8vo. *London* 1850. | ——— |

| Presents. | Donors. |
|---|---|
| GILLISS (J. M.) The Longitude of Washington, computed from the Moon's Culminations, observed during the years 1839 to 1842, inclusive. 4to. *Philadelphia* 1849. | The Author. |
| GLYNN (Joseph.) Rudimentary Treatise on the Construction of Cranes. 8vo. *London* 1849. | The Author. |
| GUEST (Edwin.) On the Early English Settlements in South Britain. 8vo. *London* 1850. | The Author. |
| HALDAT (M.) Traité d'Optique Oculaire. 8vo. *Paris* 1849. | The Author. |
| ——————— Essai historique sur le Magnétisme. 8vo. *Nancy* 1849. | ——— |
| HAUGHTON (S.) On the Rotation of a Solid Body round a fixed point. 4to. *Dublin* 1849. | The Author. |
| ——————— On a Classification of Elastic Media, and the Laws of Plane Waves propagated through them. 4to. *Dublin* 1849. | ——— |
| HOGG (John.) Remarks and Additional Views on Dr. Lepsius' Proofs that Mount Serbal is the true Mount Sinai. Map to ditto. 8vo. *London* 1849. | The Author. |
| HOWARD (Luke.) Essay on the Modifications of Clouds. 8vo. *London* 1832. | The Author. |
| ——————— Papers on Meteorology. 4to. *London* 1850. | ——— |
| JACUBOWITSCH (N.) De Saliva. 8vo. *Dorpat* 1848. | The Author. |
| JAMES (C.) Voyage scientifique à Naples, avec M. Majendie en 1843. 8vo. *Paris* 1844. | The Author. |
| ——————— Études sur l'Hydrothérapie. 8vo. *Paris* 1846. | ——— |
| ——————— De l'Emploi de l'Électricité Galvanique dans le traitement de certaines Paralysies des Membres inférieures. 8vo. *Paris* 1849. | ——— |
| JELINCK (C.) Bahnbestimmung des von de Vico am 24 Jänner 1846 entdeckten Cometen. 4to. *Wien.* | The Author. |
| ——————— Meteorologische Beobachtungen an der Wiener Sternwarte im Jahre 1839. | The Observatory. |
| JELINCK (C.) und HORNSTEIN (C.) Cometen-Beobachtungen an der Wiener Sternwarte 1835–6 und 1843–6. 4to. *Wien.* | The Authors. |
| JOHNSON (M. J.) Astronomical Observations made at the Radcliffe Observatory, Oxford, in 1847. 8vo. *Oxford* 1849. | The Radcliffe Trustees. |
| Ditto in 1848. 8vo. 1850. | ——— |
| JOHNSTON (J. F. W.) Contributions to Scientific Agriculture. 8vo. *London* 1849. | The Author. |
| JOURNALS:— | |
| The American Journal of Science and Arts. Vol. IX. Nos. 25 to 27. 8vo. *Newhaven.* | Messrs. Silliman. |
| The Astronomical Journal. Nos. 1 to 4. 4to. *Washington* 1850. | The Editor. |
| The Athenæum. | The Editor. |
| The Builder. Vol. VIII. Parts 1 to 6. | The Editor. |
| The Journal of the Indian Archipelago and Eastern Asia. Nos. 1 and 4, Vol. IV. Nos. 3 to 9, Vol. III. 8vo. | The Editor. |
| The Literary Gazette. | The Editor. |
| The Philosophical Magazine, from Jan. 1846 to June 1850. | Richard Taylor, Esq. |
| KELLER (A. F.) Des Typhons de 1848. 8vo. *Paris* 1849. | Dépôt de la Marine. |
| KENNEDY (R. H.) De Clifford, a Romance of the Red Rose. A Poem, in 12 books. 8vo. *London* 1824. | The Author. |
| ——————— Narrative of the Campaign of the Army of the Indus in Sind and Kaubool in 1838–9. 2 vols. 8vo. *London* 1840. | ——— |

| Presents. | Donors. |
|---|---|
| KENNEDY (R. H.) Notes on the Epidemic Cholera. 8vo. *London* 1846. | The Author. |
| KERHALLET (C. P. de.) Description Nautique de la Côte Occidentale d'Afrique. 8vo. *Paris* 1849. | Dépôt de la Marine. |
| KOKSCHAROW (N. v.) Ueber Brookit-Krystalle vom Ural. 8vo. *St. Petersburg* 1849. | The Author. |
| KRECKE (F. W. C.) Description de l'Observatoire Météorologique et Magnétique à Utrecht. 8vo. *Utrecht* 1850. | The Author. |
| KREIL (K.) Magnetische und Geographische Ortsbestimmungen im Österreichischen Kaiserstaate für 1847 und 1848. 4to. *Prag* 1849–50. | The Author. |
| ———— Magnetische und Meteorologische Beobachtungen zu Prag 1848. 4to. *Prag* 1850. | ———— |
| ———— Ueber den Einfluss der Alpen auf die Aeusserungen der magnetischen Erdkraft. fol. *Wien* 1849. | ———— |
| KUPFFER (A.) Annuaire Magnétique et Météorologique du corps des Ingénieurs des Mines. Année 1846. 4to. *St. Pétersbourg* 1849. | The Author. |
| LAMONT (J.) Annalen der Königlichen Sternwarte bei München. 8vo. *München* 1849. | The Observatory. |
| LASSELL (W.) Description of a Machine for Polishing Specula. 4to. *London* 1849. | The Author. |
| LEE (Robert.) Memoirs on the Ganglia and Nerves of the Uterus. 4to. *London* 1849. | The Author. |
| LE VERRIER (U. J. J.) Rapport sur l'établissement de nouvelles Lignes de Télégraphie Électrique. | The Author. |
| LINDHAGEN (Dr.) Ueber die Genauigkeit der in Lalandes Catalog. 8vo. *St. Petersburg* 1849. | The Author. |
| LITTROW (C. L. von.) Annalen der Sternwarte in Wien. Tomes V.—IX. 4to. | The Observatory. |
| LOVELACE (Earl of.) On the Construction of a Collar Roof. 8vo. *London* 1849. | The Author. |
| LUBBOCK (Sir J. W., Bart.) On the Theory of the Moon. Part 8. 8vo. *London* 1849. | The Author. |
| LYELL (Sir Charles.) Address delivered at the Anniversary Meeting of the Geological Society of London, on the 15th February 1850. 8vo. *London* 1850. | The Author. |
| MANTELL (G. A.) Thoughts on a Pebble. 8vo. *London* 1849. | The Author. |
| MAPS, CHARTS, &c.:— | |
| The Charts and Sailing Directions published by the Admiralty during 1850. | The Admiralty. |
| Thirty-seven Maps and Charts from French Surveys. | Dépôt de la Marine. |
| Two Maps of Isothermal Lines. | H. W. Dove. |
| MARCET (F.) Cours de Physique Expérimentale. 8vo. *Paris* 1850. | The Author. |
| MARTIN (F.) Mémoire sur l'Étiologie du Pied-Bot, et Atlas. 8vo. *Paris* 1839. | The Author. |
| ———— Mémoire sur l'Amputation sus-Malléolaire. 4to. *Paris* 1842. | ———— |
| ———— Essai sur les Appareils Prothétiques. 8vo. *Paris* 1850. | ———— |
| MARTIN (J.) Outline of a Comprehensive Plan for diverting the Sewage of London and Westminster from the Thames, and applying it to Agricultural Purposes. 8vo. *London* 1850. | The Author. |
| MATTEUCCI (C.) Mémoire sur la Propagation de l'Électricité dans les Corps Solides Isolants. | The Author. |

| Presents. | Donors. |
|---|---|
| MATZKA (W.) Versuch einer richtigen Lehre von der Realitaet der vorgeblich imaginären Grössen der Algebra, oder einer Grundlehre von der Ablenkung algebraischer Grossenbeziehungen unternommen. 4to. *Prag* 1850. | The Author. |
| MAURY (Lieut.) Circular prepared by direction of the Hon. W. B. Preston, in relation to the Astronomical Expedition to Chile. 4to. *Washington* 1849. | Lieut. Gilliss. |
| MAYO (T.) Outlines of Medical Proof, revised and corrected. 8vo. *London* 1850. | The Author. |
| MIERS (John.) Illustrations of South American Plants. Parts 1—4. 4to. *London* 1846. | The Author. |
| MINERVINI (G.) Dell' Epilessia. 8vo. *Napoli* 1847. | The Author. |
| MINERVINI (R.) Soluzione di un Problema Geometrico Piano della Classe de' Problemi detta da' Geometri Greci *vevaeuv* delle Inclinazioni. 8vo. *Napoli* 1849. | The Author. |
| MISCELLANEOUS:— | |
| The original Model of the Safety Lamp made by Sir Humphry Davy's own hands, and given by him to James Prince Lee, D.D., Lord Bishop of Manchester. | Joseph Hodgson, Esq., F.R.S. |
| MOON (R.) The New Equation in Hydrodynamics. 8vo. *Cambridge* 1850. | The Author. |
| MORTON (S. G.) Catalogue of Skulls of Man and the Inferior Animals. 8vo. *Philadelphia* 1849. | The Author. |
| ——— Observations on the Size of the Brain in various races and families of Man. 8vo. *Philadelphia* 1849. | ——— |
| ——— Additional Observations on a new living species of Hippopotamus. 4to. *Philadelphia* 1849. | ——— |
| MÜLLER (Dr.) (Editor.) Rig-Veda-Sanhita. The Sacred Hymns of the Brahmans. Vol. I. 4to. *London* 1849. | The East India Company. |
| NICOL (James.) Manual of Mineralogy. 8vo. *Edinburgh* 1849. | The Author. |
| OHM (G. S.) Elemente der Analytischen-Geometrie im Raume am schiefwinkeligen Coordinatensysteme. 4to. *Nürnberg* 1849. | The Author. |
| ORLEBAR (A. B.) Observations made at the Magnetical and Meteorological Observatory at Bombay in 1846. 4to. *Bombay* 1849. | The Hon. Directors of the East India Company. |
| OVEREND (G.) Extraordinary New Steam-Engines. 8vo. | The Author. |
| PARAVEY (C. de.) Réfutation de l'Opinion émise par M. Jomard, que les Peuples de l'Amérique n'ont jamais eu aucun rapport avec ceux de l'Asie. 8vo. *Paris* 1848. | The Author. |
| ——— Mémoire sur la Découverte très-ancienne en Asie et dans l'Indo-Perse de la Poudre à Canon et des Armes à Feu. 8vo. *Paris* 1850. | ——— |
| PARKER (W.) The Physiological and Scientific Treatment of Cholera. 8vo. *London* 1849. | The Author. |
| PARLATORE (Filippo.) Viaggio alla Catena del Monte Bianco e al Gran San Bernardo. 8vo. *Firenze* 1850. | The Author. |
| ——— Flora Italiana. Fasc. 1. 8vo. *Firenze* 1848. | ——— |
| PERIGAL (H.) Notes on Revolution and Rotation with reference to the Motions of the Moon and of the Earth. 8vo. *London* 1846–9. | The Author. |
| ——— Contributions to Kinematics. | ——— |
| PETERS (C. A. F.) Über Professor Mädler's Untersuchungen über die Eigenen Bewegungen der Fixsterne. 4to. *St. Petersburg* 1848. | The Author. |

| Presents. | Donors. |
|---|---|
| PIROGOFF (N.) Anatomie Pathologique du Choléra Morbus. fol. *St. Pétersbourg* 1849. | The Author. |
| PLANTAMOUR (E.) Observations Astronomiques faites à l'Observatoire de Genève dans l'année 1847. 4to. *Genève* 1849. | The Author. |
| ——— Résumé Météorologique de l'année 1847–8 pour Genève et le Grand St. Bernard. 8vo. *Genève* 1848–9. | ——— |
| PLATEAU (J.) Note sur une nouvelle Application curieuse de la Persistance des Impressions de la Rétine. | The Author. |
| ——— Recherches sur les Figures d'Équilibre d'une Masse liquide sans pesanteur. 4to. *Bruxelles* 1849. | ——— |
| PORTA (L.) Delle Malattie e delle Operazioni della Ghiandola Tiroidea. 4to. *Milano* 1849. | The Author. |
| PORTER (G. R.) The Nature and Properties of the Sugar Cane. 8vo. *London* 1843. | The Author. |
| PORTRAITS:— | |
| Portrait in Lithograph of Sir J. P. Boileau, F.R.S. | George Ransome, Esq. |
| Prince Lucien Bonaparte. | ——— |
| J. S. Bowerbank, Esq., F.R.S. | ——— |
| Marquis of Bristol. | ——— |
| Edward Forster, Esq., F.R.S. | ——— |
| The Rev. Wm. Kirby, F.R.S. | ——— |
| Sir R. I. Murchison, F.R.S. | ——— |
| Robert Patterson, Esq. | ——— |
| Rev. Edwin Sidney. | ——— |
| William Spence, Esq., F.R.S. | ——— |
| William Thompson, Esq. | ——— |
| Portrait in Oil of John Hunter, F.R.S., by Edward Home. | Sir Everard Home, F.R.S. |
| J. Ramsden, F.R.S. | ——— |
| POWELL (B.) On Irradiation. | The Author. |
| QUETELET (A.) Rapport sur l'État et les Travaux de l'Observatoire Royal pendant l'année 1848. 8vo. *Bruxelles* 1848. | The Author. |
| ——— Annales de l'Observatoire Royal de Bruxelles. Tome VII. 4to. *Bruxelles* 1849. | The Observatory. |
| ——— Sur le Climat de la Belgique. Tome I. 4to. *Bruxelles* 1849. | The Author. |
| ——— Observations des Phénomènes Périodiques. 4to. *Bruxelles* 1849. | ——— |
| RATHKE (H.) Ueber die Entwickelung der Schildkröten. 4to. *Braunschweig* 1848. | The Author. |
| REEVE (Lovell.) Conchologia Iconica. Monographs of the Genus Achatina—Chama—Dolium—Cassis—Voluta—Eburna—Buccinum—Bulimus—Conus—Bullia—Chitonellus—Cassidaria—Chiton—Isocardia—Mitra—Ficula—Pectunculus—Oniscia—Fusus—Fasciolaria—Mangelia—Hemipecten—Monoceros—Eglisia—Mesalia—Haliotis—Purpura—Turbo—Ranella—Ricinula—Pyrula—Turbinella—Turritella—Paludomus. | The Author. |
| REGNAULT (V.) Cours Élémentaire de Chimie. 4 vols. 8vo. *Paris* 1849–50. | The Author. |

FRANKLIN INSTITUTE LIBRARY

| Presents. | Donors. |
|---|---|
| REGNAULT (V.) et REISET (J.) Recherches Chimiques sur la Respiration des Animaux des diverses Classes. 8vo. *Paris* 1849. | The Authors. |
| REID (Lieut.-Col.) The Progress of the Development of the Law of Storms. 8vo. *London* 1849. | The Author. |
| REMAK (R.) Neurologische Erläuterungen. 8vo. *Berlin.* | The Author. |
| RICHARDSON (James.) The Cruisers; being a Letter to the Marquis of Lansdowne, in defence of Armed Coercion for the Extinction of the Slave Trade. 8vo. *London* 1849. | The Author. |
| ROBERTS (Henry.) The Dwellings of the Labouring Classes; their Arrangement and Construction. 8vo. *London* 1850. | The Author. |
| ROYLE (J. F.) Report on the Progress of the Culture of the China Tea Plant in the Himalayas from 1835 to 1847. 8vo. *London* 1849. | The Author. |
| SABINE (Lieut.-Col.) Directions for the use of a small Apparatus to be employed with a Ship's Standard Compass. 8vo. *London* 1849. | The Author. |
| SCHMIDT (C.) Der Diagnostik Verdächtiger Flecke in Criminalfällen. 8vo. *Leipzig* 1848. | The Author. |
| SMEE (Alfred.) Principles of the Human Mind. 8vo. *London* 1849. | The Author. |
| ——— Instinct and Reason: deduced from Electro-Biology. 8vo. *London* 1850. | ——— |
| SMYTH (C. P.) Astronomical Observations made at the Royal Observatory, Edinburgh, by the late Thomas Henderson, Esq. Vol. VIII. 1842. 4to. *Edinburgh* 1849. | The Royal Observatory, Edinburgh. |
| SPINOLA (J. y) and CHALUZ DE VERNEVIL (F. T. A.) The Geneuphonic Grammar. 8vo. *London* 1850. | The Author. |
| STANNIUS (H.) Das peripherische Nervensystem der Fische. 4to. *Rostock* 1849. | The Author. |
| STAUNTON (Sir George, Bart.) Miscellaneous Notices relating to China. 8vo. *London* 1822–50. | The Author. |
| STEVENSON (W. F.) The Composition of Hydrogen and the Non-Decomposition of Water incontrovertibly established. Second Edition. 8vo. *Dublin* 1849. | The Author. |
| STRATFORD (Lieut.) The Nautical Almanac for 1853. 8vo. *London* 1850. | Lieut. Stratford, F.R.S. |
| STRUVE (W.) Rapport fait à l'Académie Impériale des Sciences, sur une Mission Scientifique en 1847. | The Author. |
| ——— Sur la Dilatation de la Glace. 4to. *St. Pétersbourg* 1848. | ——— |
| ——— Beschreibung der zur Ermittelung des Hohenunterscheides zwischen dem Schwarzen und dem Caspischen Meere. 4to. *St. Petersburg* 1849. | ——— |
| SYKES (Lieut.-Col.) Contributions to the Statistics of Sugar. | The Author. |
| SYMONDS (J. A.) Some Account of the Life, Writings and Character of the late J. C. Prichard, M.D., F.R.S. 8vo. *Bristol* 1849. | The Author. |
| TAYLOR (T. G.) Astronomical Observations made at the East India Company's Observatory, Madras, in 1843–7. | The East India Company. |
| TEMMINCK (C. J.) Coup-d'œil général sur les Possessions Néerlandaises dans l'Inde Archipélagique. Tome III. 8vo. *Leide* 1849. | J. E. Gray, Esq. |
| THURMANN (Jules.) Essai de Phytostatique appliqué à la Chaîne du Jura. 2 vols. 8vo. *Berne* 1849. | The Author. |

| Presents. | Donors. |
|---|---|
| TOYNBEE (J.) Pathological Researches into the Diseases of the Ear. 8vo. *London* 1849. | The Author. |
| TWINING (Elizabeth.) Illustrations of the Natural Orders of Plants, arranged in Groups, with Descriptions. Parts 1 to 6. fol. *London* 1849. | R. Twining, Esq., F.R.S. |
| WALKER (C. V.) Electric Telegraph Manipulation. 8vo. *London* 1850. | The Author. |
| WATERSTON (J. J.) An Account of a Mathematical Theory of Gases. | The Author. |
| WELD (Charles Richard.) Arctic Expeditions: a Lecture delivered at the London Institution, Feb. 6, 1850, with a Map. 8vo. *London* 1850. | The Author. |
| ——————— Auvergne, Piedmont, and Savoy: a Summer Ramble. 8vo. *London* 1850. | ——— |
| WHITE (Walter.) Arctic Explorations. 8vo. *Edinburgh* 1850. | The Author. |
| WILLICH (C. W.) Annual Supplement to Tithe Commutation Tables for 1850. | The Author. |
| ZANTEDESCHI (F.) Risposta ai Signori E. Knoblauch sulla Esistenza delle linee longitudinali nello Spettro Solare. 8vo. *Roma* 1849. | The Author. |
| ——————— Annali di Fisica. Part 4. | ——— |

*Mean Oscillations of the Barometer corrected for Temperature at Calcutta, Bo*




*N.B. These Barometric Curves represent 1st the mean daily oscillations of the barometer for each month of the year. — 2ndly The mean mon For example. At Bombay in 1845, the mean maximum daily pressure in Janr. was between 9 and 10 a.m. — The mean minimum daily mean maximum night pressure was between 10 and 11 p.m. and the mean minimum night pressure was between 3 and 4 a.m. — Th from 30.045 to 29.865. — Similarly in the monsoon months of June, July & August the horary oscillations or atmospheric tides con the mean range of the Barometer in June is from 29.683 to 29.607.*

*Bombay and Madras*

# 1845.

MAY. JUNE. JULY. AUGUST. SEPTE

+ A.M. HOURS P.M. + A.M. HOURS P.M. + A.M. HOURS P.M. + A.M. HOURS P.M. + A.M. HOU



*monthly pressure for each month in the year. — 3rdly The Annual curve of pressure.*
*daily pressure was between 3 and 4 p.m. The*
*The mean monthly range of the barometer was*
*continue at the same hours as in January but*

ture at Calcutta, Bombay and Madras.

# 1845.

APRIL. MAY. JUNE. JULY. AUGUST.




— 2ndly The mean monthly pressure for each month in the year. — 3rdly The Annual curve of pressure.
he mean minimum daily pressure was between 3 and 4 p.m. The
een 3 and 4 a.m. — The mean monthly range of the barometer was
or atmospheric tides continue at the same hours as in January, but


SEPTEMBER.
OCTOBER.
NOVEMBER.
DECEMBER.
+ A.M.
HOURS
P.M.
Calcutta
Madras
Bombay

*Mean hora*


JANUARY.
FEBRUARY.
MARCH.
APRIL.
A.M.
HOURS
P.M.
1845
1846
1848
1847

*rary oscillation of the Barometer at* **CALCUTTA** *for the years 1845, 1846, 1847 and 1848.*

MAY. JUNE. JULY. AUGUST. SEPTEMBE

+ A.M. HOURS P.M. + A.M. HOURS P.M. + A.M. HOURS P.M. + A.M. HOURS P.M. + A.M. HOURS



*Mean horary oscillation of the Barometer at* **CALCUTTA** *for the years 1845, 1846, 1847 and*



*nd 1848.*

SEPTEMBER. OCTOBER. NOVEMBER. DECEMBER.

+ A.M. HOURS P.M. + A.M. HOURS P.M. + A.M. HOURS P.M. + A.M. HOURS P.M.




*J. Basire, lith.*

*Mean horary*



*ry oscillation of the Barometer at* **BOMBAY**, *for the years 1843, 1844 & 1845.*



*Mean horary oscillation of the Barometer at* **BOMBAY**, *for the years 1843, 1844 & 18*



1845.


SEPTEMBER.
OCTOBER.
NOVEMBER.
DECEMBER.
+ A.M.
HOURS
P.M.
1843
1845
1844

*Mean he*



*horary oscillation of the Barometer at* **MADRAS**, *for the years 1843, 1844 and 1845.*

MAY. JUNE. JULY. AUGUST. SEPTEMB

.M. HOURS P.M. + A.M. HOURS P.M. + A.M. HOURS P.M. + A.M. HOURS P.M. + A.M. HOURS



*Mean horary oscillation of the Barometer at* **MADRAS**, *for the years 1843 1844 and 184*



1845.

SEPTEMBER. OCTOBER. NOVEMBER. DECEMBER.






Right Humerus of Pelorosaurus Conybearei.

(¼ linear the natural size.)

J. Vinkel del.

G. Scharf lith.

Printed by J. Basire.



Caudal Vertebræ of Pelorosaurus Conybearei.

From the Strata of Tilgate Forest.

(¼ linear the natural size.)

J. Dinkel del.

Printed by Leaf, Reigate.




*Saurian caudal Vertebræ, from the strata of Tilgate Forest.*

J. Basire sculp.

Printed by J. Basire




Caudal Vertebra of Pelorosaurus Conybearei.

(⅛ Natural Size.)

J. Dinkel del. G. Scharf lith.

Printed by J. Basire.




*Anterior view of a caudal vertebra of Pelorosaurus Conybearei*
*(¼ Natural Size)*

J. Dinkel, del. Printed by J. Basire G. Sidney, lith.




*Median caudal Vertebra of Pelorosaurus (?)*
*from the strata of Tilgate Forest, by Cap.n Lambart Brickenden.*
*(Natural Size.)*

J. Basire del.

G. Scharf, lith.

Printed by J. Basire.




*Dorsal dermal Spine of the Hylæosaurus*

(½ Nat. Size linear

J. Dinkel. del. et lith.




½ Natural Size.

1

2

*Upper portion of the Phragmocone of a Belemnite.*

*(in the British Museum)*

*½ Natural size)*

*Forrichter, lith.* *Mounsey, del.*




Belemnites and Belemnoteuthis.

J. Basire, lith.

Printed by J. Basire.

J. Mackrell, del.


e
h
f



*Belemnites Puzosianus, showing the upper part of the phragmocone with the pair of elongated processes, from the Oxford Clay, Wiltshire.*
*(In the possession of Dr Mantell.)*

J. Mawsey del. J. Erxleben, lith.

Printed by J. Basire.

Fig. 1.



Magnified 400 diam.ᵉᵗ

Fig. 2.




Magnified 400 diam.ᵉᵗ

Fig. 3.



Mag.ᵈ 400 diam.ᵉᵗ

M. M. Waller, ad. nat. del.

J. Basire, lith.


Mean Temp.re 60.° Fahr.
Mean Temp.re 56.° Fahr.
Mean Temp.re 53.° Fahr.
Mean Temp.re 51.° Fahr.
1848.
March 11.th
20.th
23.rd
25.th
27.th
28.th
31.st
April 4.th
6.th
10.th
May 22.nd
Aug.t 18.th
28.th
Oct.r 31.st
John Higginbottom, del.
J. Basire, lith.

Phil. Trans. MDCCCL. Plate XXXIII. page 407

Fig. 2




Fig. 3.




Fig. 1




Geo. Perkins del. et lith.

*Young Phacochœrus Æliani, (Nat. Size.)*




*Figs. 1, 7, 9, 10 & 12, Phacochœrus Æliani. Figs. 8 & 11 Ph. Pallasii.*

Phil. Trans. MDCCCL. Plate XXXIV. p. 497.

Fig. 1.

Fig. 2.



Fig. 3.



Fig. 4.



Fig. 5.

Fig. 6.

Fig. 7.

Fig. 8.

Fig. 9.

Fig. 10.

Fig. 11.

FRANKLIN INSTITUTE LIBRARY

Fig. 12.



Fig. 15

Fig. 13.

Fig. 16

Fig. 17

Fig. 14.

Fig. 1.

Fig. 2.

Fig. 3.



Fig. 4.



J. S. Bristowe del.

J. Basire, lith.

*Crocodilus acutus*




Fig 2



Fig 3




Fig 1

*Crocodilus acutus.*

*Crocodilus bipercatus.*

Jos Denkel del et lith.

Printed by J Basire

Fig. 5.




Fig. 6.




*Alligator lucius*

Fig. 7.




Fig. 4.




*Crocodilus acutus.*

*Crocodilus biporcatus*

Printed by J. Basire

Fig 8



*Crocodilus biporcatus.*

Fig 10.

Fig 9.



Joa Pinkal. del. et lith.

*Gairalis gangeticus*

Printed by J. Basire


3
A
D
B
4
C
B
A
2
B
A
8
7
D
E
D
E
9
D
E
5
6
D
E
F
10
C
D
13
11
D
E
12
F
E
D
14
F
E
C
15
D
E
F


18
D E
16
A D
17
E E D
21
D E
19
D E
20
D E
22
D E
23
E D
25
E D
34
E D
24
27
32
28
E D
29
E D
31
E D
30
D
33
1
2
3




W. Wing del. et lith.

Ford & Greig, Lithographers, Hatton Garden.


42
D
E

51


46
D
E


43
D
E


45
D
E


47
E
D


53


49
E
D


52
D
E


50
E
D


48
D
E

*Fig. 1.*




*Fig. 2.*



Fig. 4.




Fig. 3.




Fig. 5.




Fig. 6.




Fig. 7.




Fig. 9.

Belerophon.



Fig. 8.

Vanguard.



Fig. 10.

Canopus.



J. Basire Lith.




J. Basire, lith.

Fig. 1.




Fig. 3.







Fig. 2.

Fig. 4.




J. Basire, lith.

*The Variations of the Acidity of t*



the Urine when Tartrate of Ammonia was taken.


3rd DAY
of Tartrate of Ammonia
4th DAY
nearly 3 Drachms of Tartrate of Ammonia
5th DAY
no Tartrate of Ammonia was taken
Dinner Hour
Breakfast Hour
Dinner Hour
Breakfast Hour
Dinner Hour
Breakfast Hour
Thick Urates
Clear
Thick Urates
Clear
Thick Urates
Clear

*The Variations of the Acidity of th*



# the Urine when Carbonate of Ammonia was taken




J. Basire, Lith.

*The Variations of the Acidity of*


6TH DAY
no Carbonate of Ammonia
7TH DAY
Eighty grains of Carbonate of Ammonia
8TH D
no Carbonate of
Breakfast Hour
Dinner Hour
Breakfast Hour
Dinner Hour
Breakfast Hour
Dinner Hour
Acid
Neutral
Alkaline
30
20
10
10
20
30
Thick Urates 102.9
Thick Urates 102.6
Thick Urates 102.8
Thick Urates
Clear 102.6
Cloudy Urates
Cloudy from Phosphates
Thick Urates
Clear 102.6
Clear 102.8
Thick Urates 102.5
Clear 102.7
Clear 102.6
Clear 102.8
Clear 102.6
Clear 102.8
Clear 102.6
Clear 102.8

Phil. Trans. MDCCCL. Plate LIII. p. 674

*f the Urine when Carbonate of Ammonia was taken*




J. Basire, Lith.

Side View.




End View.




T.G. Horner del.

J. Basire sc.

YORKSHIRE PLATES.

TABLE I



Drawn in the direction of the fibre

Breaking weight
in tons pr sq. inch 25.77
do do do 22.76
Mean do do 24.27

TABLE II



Drawn across the fibre

Breaking weight
in tons pr sq. inch 27.40
do do do 26.03
Mean do do 26.76

DERBYSHIRE PLATES

TABLE III



Drawn in the direction of the fibre

Breaking weight
in tons pr sq. inch 21.66



Drawn across the fibre

Breaking weight
in tons pr sq. inch 18.66

Fig. 2.

SHROPSHIRE PLATES.

TABLE IV



Drawn in the direction of the fibre

Breaking weight
in tons pr sq. inch 22.82

Drawn across the fibre

Breaking weight
in tons pr sq. inch 22.00

STAFFORDSHIRE PLATES

TABLE V



Drawn in the direction of the fibre

Breaking weight
in tons pr sq. inch 21.56



Drawn across the fibre

Breaking weight
in tons pr sq. inch 20.01

J. Basire, Lith.

*Fig 3*

RIVETING MACHINE.

*Elevation.*




*Plan.*



J. Basire sc.

TABLE. VI.

Fig. 4.



TABLE VII.

Fig. 5.

Fig. 6.



TABLE. VIII.

Fig. 7.



Fig. 8.



TABLE. IX.

Fig. 9.



TABLE. X.



Fig. 10.

TABLE XI.

Fig. 11.



TABLE. XII.

Fig. 12.



Fig. 12a.



J. Basire. Lith.

TABLE XVI

Fig. 17.

Beam before the Experiment rib downwards
Weight of Beam. 84 lbs

Beam after the Experiment

Beam, showing the flange rib downwards



Beam before the Experiment rib upwards
Weight of Beam 88 lbs

Beam after the Experiment

Section

Plan of beam before the Experiment

Beam after the Experiment

TABLE XVII

Fig 18

Beam before the Experiment rib downwards
Weight of Beam. 82¼ lbs

Beam after the experiment



Beam with the flange downwards

Beam before the Experiment rib upwards
Weight of Beam 85 lbs



Beam after the Experiment



Section

Plan of beam before the Experiment



Beam after the Experiment

TABLE XX

Fig. 19.

Side view of Beam before the Experiment
Weight of Beam. 161¾ lbs

Section

Plan

TABLE XIII

Fig. 13.



Edge view of the fracture

Plan



½ inch thick

Fig. 14.



Edge view of the fracture

Plan



½ inch thick